

|          |       |            |     |     |                             |
|----------|-------|------------|-----|-----|-----------------------------|
| Job      | Truss | Truss Type | Qty | Ply | MUNGO HOMES-RUSSELL 2ND FLR |
| 72436981 | F200  | Truss      | 11  | 1   | Job Reference (optional)    |

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Joy Perry

Run: 8.81 S Sep 13 2024 Print: 8.810 S Sep 13 2024 MiTek Industries, Inc. Thu Feb 27 10:16:17

Page: 1

ID:Y?I0TELA5G72hK6FRQkx8OyE?ZL-rsQrmQdwLj6OstmZtUSYZBZVsf?AmgN3RwxGM4zh\_Cz




Plate Offsets (X, Y): [4:0-1-12,Edge], [6:0-3-0,Edge], [7:0-2-0,Edge], [9:0-2-8,Edge], [16:0-1-8,Edge], [17:0-1-8,Edge]

| Loading | (psf) | Spacing         | 2-0-0           | CSI       | DEFL | in       | (loc) | I/defl | L/d  | PLATES | GRIP           |                 |
|---------|-------|-----------------|-----------------|-----------|------|----------|-------|--------|------|--------|----------------|-----------------|
| TCLL    | 40.0  | Plate Grip DOL  | 1.00            | TC        | 0.28 | Vert(LL) | -0.31 | 16     | >737 | 480    | MT18HS         | 244/190         |
| TCDL    | 10.0  | Lumber DOL      | 1.00            | BC        | 0.65 | Vert(CT) | -0.44 | 16     | >506 | 360    | MT20           | 244/190         |
| BCLL    | 0.0   | Rep Stress Incr | NO              | WB        | 0.69 | Horz(CT) | 0.09  | 13     | n/a  | n/a    |                |                 |
| BCDL    | 5.0   | Code            | IRC2015/TPI2014 | Matrix-SH |      |          |       |        |      |        | Weight: 106 lb | FT = 20%F, 11%E |


| LUMBER    |                   | BRACING   |   |
|-----------|-------------------|-----------|---|
| TOP CHORD | 2x4 SP SS(flat)   | TOP CHORD | Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals. |
| BOT CHORD | 2x4 SP SS(flat)   | BOT CHORD | Rigid ceiling directly applied or 10-0-0 oc bracing.                                  |
| WEBS      | 2x4 SP No.3(flat) |           |   |
| OTHERS    | 2x4 SP No.3(flat) |           |   |

|           |   |  |
|-----------|---|--|
| REACTIONS | (lb/size)   | 13=1061/0-3-8, (min. 0-1-8), 20=1066/0-3-8, (min. 0-1-8) |
| FORCES    | (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  |  |
| TOP CHORD | 2-3=-3200/0, 3-4=-3202/0, 4-5=-5165/0, 5-6=-5165/0, 6-7=-5165/0, 7-8=-4548/0, 8-9=-4548/0, 9-10=-3182/0, 10-11=-3180/0  |  |
| BOT CHORD | 19-20=0/2362, 18-19=0/4042, 17-18=0/4042, 16-17=0/5165, 15-16=0/5035, 14-15=0/4024, 13-14=0/2346  |  |
| WEBS      | 5-17=-437/0, 6-16=-357/139, 2-20=-2533/0, 2-19=0/1092, 4-19=-1070/0, 4-17=0/1402, 11-13=-2517/0, 11-14=0/1086, 9-14=-1073/0, 9-15=0/665, 7-15=-619/0, 7-16=-267/675 |  |

- NOTES**
- Unbalanced floor live loads have been considered for this design.
  - All plates are MT20 plates unless otherwise indicated.
  - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Load case(s) 1 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.
  - Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
- LOAD CASE(S)** Standard
- 1) Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00
- Uniform Loads (lb/ft)
- Vert: 13-20=-10, 1-5=-100, 5-6=-136, 6-12=-100



|          |       |            |     |     |                             |
|----------|-------|------------|-----|-----|-----------------------------|
| Job      | Truss | Truss Type | Qty | Ply | MUNGO HOMES-RUSSELL 2ND FLR |
| 72436981 | F202  | Truss      | 1   | 1   | Job Reference (optional)    |



Scale = 1:37.9

|                       |                                   |
|-----------------------|-----------------------------------|
| Plate Offsets (X, Y): | [7'-0-2-0,Edge], [10'-0-2-0,Edge] |
|-----------------------|-----------------------------------|

| Loading | (psf) | Spacing         | 2'-0-0          | CSI       |      | DEFL     | in    | (loc) | l/defl | L/d | PLATES        | GRIP            |
|---------|-------|-----------------|-----------------|-----------|------|----------|-------|-------|--------|-----|---------------|-----------------|
| TCLL    | 40.0  | Plate Grip DOL  | 1.00            | TC        | 0.33 | Vert(LL) | -0.03 | 9-10  | >999   | 480 | MT20          | 244/190         |
| TCDL    | 10.0  | Lumber DOL      | 1.00            | BC        | 0.29 | Vert(CT) | -0.04 | 9-10  | >999   | 360 |               |                 |
| BCLL    | 0.0   | Rep Stress Incr | YES             | WB        | 0.18 | Horz(CT) | 0.01  | 7     | n/a    | n/a |               |                 |
| BCDL    | 5.0   | Code            | IRC2015/TPI2014 | Matrix-SH |      |          |       |       |        |     | Weight: 39 lb | FT = 20%F, 11%E |

| LUMBER    |                   | BRACING   |  |
|-----------|-------------------|-----------|--|
| TOP CHORD | 2x4 SP No.2(flat) | TOP CHORD | Structural wood sheathing directly applied or 6'-0-0 oc purlins, except end verticals. |
| BOT CHORD | 2x4 SP No.2(flat) | BOT CHORD | Rigid ceiling directly applied or 10'-0-0 oc bracing.                                  |
| WEBS      | 2x4 SP No.3(flat) |           |  |
| OTHERS    | 2x4 SP No.3(flat) |           |  |


|           |  |   |
|-----------|--|---|
| REACTIONS | (lb/size)  | 7=397/ Mechanical, (min. 0-1-8), 10=397/0-3-8, (min. 0-1-8) |
| FORCES    | (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown. |   |
| TOP CHORD | 2-3=-680/0, 3-4=-680/0, 4-5=-680/0   |   |
| BOT CHORD | 9-10=0/437, 8-9=0/680, 7-8=0/437   |   |
| WEBS      | 2-10=-544/0, 2-9=0/355, 5-7=-544/0, 5-8=0/375                                |   |

- NOTES**
- Unbalanced floor live loads have been considered for this design.
  - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Recommend 2x6 strongbacks, on edge, spaced at 10'-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.





UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Joy Perry Run: 8.81 S Sep 13 2024 Print: 8.810 S Sep 13 2024 MiTek Industries, Inc. Thu Feb 27 10:16:19 Page: 1  
ID:r1axiF0k135edFuBriZh64vE?S1-nEYbB6eBtKM66Bww vV0eceiStelEYWMuEQMRvzh Cx



| LUMBER    |                   | BRACING   |   |
|-----------|-------------------|-----------|---|
| TOP CHORD | 2x4 SP SS(flat)   | TOP CHORD | Structural wood sheathing directly applied or 5-7-1 oc purlins, except end verticals. |
| BOT CHORD | 2x4 SP SS(flat)   | BOT CHORD | Rigid ceiling directly applied or 10-0-0 oc bracing.                                  |
| WEBS      | 2x4 SP No.3(flat) |           |   |
| OTHERS    | 2x4 SP No.3(flat) |           |   |

**NOTES**

- 1) Unbalanced floor live loads have been considered for this design.
- 2) All plates are MT20 plates unless otherwise indicated.
- 3) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 4) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

A red circular professional engineer seal for John M. Presley, North Carolina. The seal contains the text "NORTH CAROLINA", "PROFESSIONAL", "SEAL", "025046", "2/27/25", "ENGINEER", and "JOHN M. PRESLEY". A blue ink signature "John M. Presley" is written over the seal.

This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFP<sup>®</sup> plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SRCA and Truss Plate Institute.

|          |       |            |     |     |                             |
|----------|-------|------------|-----|-----|-----------------------------|
| Job      | Truss | Truss Type | Qty | Ply | MUNGO HOMES-RUSSELL 2ND FLR |
| 72436981 | F205  | Truss      | 10  | 1   | Job Reference (optional)    |

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Joy Perry

Run: 8.81 S Sep 13 2024 Print: 8.810 S Sep 13 2024 MiTek Industries, Inc. Thu Feb 27 10:16:19

Page: 1

ID:z4viZKaDoV0\_zU\_D54TiW\_yE?RI-FR6\_PSPdeUzjLV8Yc0FBqBuPs\_Kz\_WV7u9wzOzh\_Cw




Plate Offsets (X, Y): [16:0-1-8,Edge], [17:0-1-8,Edge]

| Loading | (psf) | Spacing         | 2-0-0           | CSI       | DEFL | in       | (loc) | I/defl | L/d  | PLATES | GRIP           |                 |
|---------|-------|-----------------|-----------------|-----------|------|----------|-------|--------|------|--------|----------------|-----------------|
| TCLL    | 40.0  | Plate Grip DOL  | 1.00            | TC        | 0.78 | Vert(LL) | -0.27 | 17-18  | >741 | 480    | MT18HS         | 244/190         |
| TCDL    | 30.0  | Lumber DOL      | 1.00            | BC        | 0.81 | Vert(CT) | -0.49 | 17-18  | >405 | 360    | MT20           | 244/190         |
| BCLL    | 0.0   | Rep Stress Incr | NO              | WB        | 0.86 | Horz(CT) | 0.07  | 13     | n/a  | n/a    |                |                 |
| BCDL    | 5.0   | Code            | IRC2015/TPI2014 | Matrix-SH |      |          |       |        |      |        | Weight: 100 lb | FT = 20%F, 11%E |

| LUMBER    |                   | BRACING   |  |
|-----------|-------------------|-----------|--|
| TOP CHORD | 2x4 SP SS(flat)   | TOP CHORD | Structural wood sheathing directly applied or 5-6-15 oc purlins, except end verticals. |
| BOT CHORD | 2x4 SP SS(flat)   | BOT CHORD | Rigid ceiling directly applied or 10-0-0 oc bracing, Except:                           |
| WEBS      | 2x4 SP No.3(flat) |           | 6-0-0 oc bracing: 12-13.   |
| OTHERS    | 2x4 SP No.3(flat) |           |  |

| REACTIONS | (lb/size) | 13=2074/0-3-8, (min. 0-1-8), 19=1191/0-3-8, (min. 0-1-8) |
|-----------|-----------|--|
|           | Max Grav  | 13=2074 (LC 1), 19=1219 (LC 3)                           |

| FORCES    | (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.   |
|-----------|--|
| TOP CHORD | 2-3=-3470/0, 3-4=-4759/0, 4-5=-4759/0, 5-6=-4759/0, 6-23=-3174/0, 7-23=-3174/0, 7-8=0/998, 8-9=0/998, 9-10=0/992   |
| BOT CHORD | 18-19=0/2664, 17-18=0/4205, 16-17=0/4759, 15-16=0/4003, 14-15=0/4003, 13-14=0/2339, 12-13=-477/0   |
| WEBS      | 4-17=-278/0, 5-16=-435/0, 9-13=-324/0, 2-19=-2856/0, 2-18=0/1049, 3-18=-957/0, 3-17=0/895, 7-13=-3141/0, 7-14=0/1126, 6-14=-1129/0, 6-16=0/1224, 10-12=0/515, 10-13=-797/0 |

- NOTES**
- Unbalanced floor live loads have been considered for this design.
  - All plates are MT20 plates unless otherwise indicated.
  - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Load case(s) 1 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.
  - Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
  - CAUTION, Do not erect truss backwards.

| LOAD CASE(S)   | Standard |
|--|----------|
| 1) Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00 |          |
| Uniform Loads (lb/ft)  |          |
| Vert: 12-19=-10, 1-23=-140, 11-23=-176                                     |          |




|          |       |            |     |     |                             |
|----------|-------|------------|-----|-----|-----------------------------|
| Job      | Truss | Truss Type | Qty | Ply | MUNGO HOMES-RUSSELL 2ND FLR |
| 72436981 | F206  | Truss      | 7   | 1   | Job Reference (optional)    |

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Joy Perry

Run: 8.81 S Sep 13 2024 Print: 8.810 S Sep 13 2024 MiTek Industries, Inc. Thu Feb 27 10:16:19

Page: 1

ID:w?5J7e0oKZYtl0k8Ce68zayE?Qk-FR6\_PSfpdeUzjLV8Yc0FBqBvls\_\_z\_DV7u9wzOzh\_Cw



Scale = 1:40

Plate Offsets (X, Y): [4:0-3-0,Edge], [7:0-3-0,Edge], [8:0-2-12,Edge], [15:0-1-8,Edge], [16:0-1-8,Edge]

| Loading | (psf) | Spacing         | 2-0-0           | CSI       | DEFL | in       | (loc) | l/defl | L/d  | PLATES | GRIP          |                 |
|---------|-------|-----------------|-----------------|-----------|------|----------|-------|--------|------|--------|---------------|-----------------|
| TCLL    | 40.0  | Plate Grip DOL  | 1.00            | TC        | 0.72 | Vert(LL) | -0.22 | 16-17  | >934 | 480    | MT18HS        | 244/190         |
| TCDL    | 30.0  | Lumber DOL      | 1.00            | BC        | 0.77 | Vert(CT) | -0.46 | 16-17  | >435 | 360    | MT20          | 244/190         |
| BCLL    | 0.0   | Rep Stress Incr | NO              | WB        | 0.88 | Horz(CT) | 0.09  | 12     | n/a  | n/a    |               |                 |
| BCDL    | 5.0   | Code            | IRC2015/TPI2014 | Matrix-SH |      |          |       |        |      |        | Weight: 93 lb | FT = 20%F, 11%E |

| LUMBER    |                   | BRACING   |   |
|-----------|-------------------|-----------|---|
| TOP CHORD | 2x4 SP No.1(flat) | TOP CHORD | Structural wood sheathing directly applied or 5-8-5 oc purlins, except end verticals. |
| BOT CHORD | 2x4 SP SS(flat)   | BOT CHORD | Rigid ceiling directly applied or 10-0-0 oc bracing.                                  |
| WEBS      | 2x4 SP No.3(flat) |           |   |
| OTHERS    | 2x4 SP No.3(flat) |           |   |

|           |  |  |
|-----------|--|--|
| REACTIONS | (lb/size)  | 12=1330/0-3-8, (min. 0-1-8), 18=1360/0-3-8, (min. 0-1-8) |
| FORCES    | (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.   |  |
| TOP CHORD | 2-3=-4028/0, 3-4=-4035/0, 4-5=-5943/0, 5-6=-5943/0, 6-7=-5943/0, 7-8=-5943/0, 8-9=-3887/0, 9-10=-3884/0                                |  |
| BOT CHORD | 17-18=0/2993, 16-17=0/5068, 15-16=0/5943, 14-15=0/4871, 13-14=0/4871, 12-13=0/2923   |  |
| WEBS      | 6-16=-395/0, 7-15=-621/0, 2-18=-3210/0, 2-17=0/1347, 4-17=-1321/0, 4-16=0/1206, 10-12=-3135/0, 10-13=0/1251, 8-13=-1254/0, 8-15=0/1464 |  |

- NOTES**
- Unbalanced floor live loads have been considered for this design.
  - All plates are MT20 plates unless otherwise indicated.
  - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Load case(s) 1 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.
  - Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

|              |   |
|--------------|---|
| LOAD CASE(S) | Standard  |
| 1)           | Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00 |
|              | Uniform Loads (lb/ft)   |
|              | Vert: 12-18=-10, 1-3=-140, 3-7=-176, 7-11=-140                          |






|          |       |            |     |     |                             |
|----------|-------|------------|-----|-----|-----------------------------|
| Job      | Truss | Truss Type | Qty | Ply | MUNGO HOMES-RUSSELL 2ND FLR |
| 72436981 | F207  | Truss      | 3   | 1   | Job Reference (optional)    |

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Joy Perry

Run: 8.81 S Sep 13 2024 Print: 8.810 S Sep 13 2024 MiTek Industries, Inc. Thu Feb 27 10:16:19

Page: 1

ID:DdXO9rlsgxZTAiZlcgYnyeyE?QM-FR6\_PSPdeUzjLV8Yc0FBqBtps?7z\_PV7u9wzOzh\_Cw



Scale = 1:39.5

Plate Offsets (X, Y): [4:0-3-0,Edge], [7:0-3-0,Edge], [8:0-3-0,Edge], [15:0-1-8,Edge], [16:0-1-8,Edge]

| Loading | (psf) | Spacing         | 2-0-0           | CSI       |      | DEFL     | in    | (loc) | I/defl | L/d | PLATES        | GRIP            |
|---------|-------|-----------------|-----------------|-----------|------|----------|-------|-------|--------|-----|---------------|-----------------|
| TCLL    | 40.0  | Plate Grip DOL  | 1.00            | TC        | 0.88 | Vert(LL) | -0.21 | 16-17 | >946   | 480 | MT18HS        | 244/190         |
| TCDL    | 30.0  | Lumber DOL      | 1.00            | BC        | 0.76 | Vert(CT) | -0.45 | 16-17 | >437   | 360 | MT20          | 244/190         |
| BCLL    | 0.0   | Rep Stress Incr | NO              | WB        | 0.87 | Horz(CT) | 0.08  | 12    | n/a    | n/a |               |                 |
| BCDL    | 5.0   | Code            | IRC2015/TPI2014 | Matrix-SH |      |          |       |       |        |     | Weight: 90 lb | FT = 20%F, 11%E |

| LUMBER    |                   | BRACING   |  |
|-----------|-------------------|-----------|--|
| TOP CHORD | 2x4 SP No.1(flat) | TOP CHORD | Structural wood sheathing directly applied or 4-11-2 oc purlins, except end verticals. |
| BOT CHORD | 2x4 SP SS(flat)   | BOT CHORD | Rigid ceiling directly applied or 10-0-0 oc bracing.                                   |
| WEBS      | 2x4 SP No.3(flat) |           |  |
| OTHERS    | 2x4 SP No.3(flat) |           |  |

| REACTIONS | (lb/size)  | 12=1312/ Mechanical, (min. 0-1-8), 18=1342/0-3-8, (min. 0-1-8) |
|-----------|--|--|
| FORCES    | (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.   |  |
| TOP CHORD | 2-21=-3947/0, 3-21=-3947/0, 3-4=-3940/0, 4-5=-5760/0, 5-6=-5760/0, 6-7=-5760/0, 7-8=-5760/0, 8-9=-3778/0, 9-10=-3800/0                 |  |
| BOT CHORD | 17-18=0/2953, 16-17=0/4941, 15-16=0/5760, 14-15=0/4748, 13-14=0/4748, 12-13=0/2882   |  |
| WEBS      | 6-16=-374/0, 7-15=-697/0, 2-18=-3167/0, 2-17=0/1293, 4-17=-1263/0, 4-16=0/1134, 10-12=-3091/0, 10-13=0/1195, 8-13=-1204/0, 8-15=0/1432 |  |

- NOTES**
- Unbalanced floor live loads have been considered for this design.
  - All plates are MT20 plates unless otherwise indicated.
  - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Load case(s) 1 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.
  - Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

| LOAD CASE(S)   | Standard |
|--|----------|
| 1) Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00 |          |
| Uniform Loads (lb/ft)  |          |
| Vert: 12-18=-10, 1-21=-140, 7-21=-176, 7-11=-140                           |          |



|          |       |            |     |     |                             |
|----------|-------|------------|-----|-----|-----------------------------|
| Job      | Truss | Truss Type | Qty | Ply | MUNGO HOMES-RUSSELL 2ND FLR |
| 72436981 | FG1   | Truss      | 1   | 1   | Job Reference (optional)    |

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Joy Perry

Run: 8.81 S Sep 13 2024 Print: 8.810 S Sep 13 2024 MiTek Industries, Inc. Thu Feb 27 10:16:20

Page: 1

ID:jHq03Cnxq0m89H4Hdh6wJfYF?FQ-FR6\_PSPfdeUzjLV8Yc0FBqBtkS\_6z?EV7u9wzOzh\_Cw




Plate Offsets (X, Y): [4:0-3-0,Edge], [5:0-1-12,Edge], [13:Edge,0-3-0], [14:0-1-12,Edge], [15:0-2-0,Edge], [17:0-2-0,Edge], [19:0-2-0,Edge], [20:0-3-0,Edge], [21:0-1-8,Edge], [22:0-3-0,Edge]

| Loading | (psf) | Spacing         | 2-0-0           | CSI       |      | DEFL     | in    | (loc) | I/defl | L/d | PLATES         | GRIP            |
|---------|-------|-----------------|-----------------|-----------|------|----------|-------|-------|--------|-----|----------------|-----------------|
| TCLL    | 40.0  | Plate Grip DOL  | 1.00            | TC        | 0.88 | Vert(LL) | -0.44 | 19-20 | >530   | 480 | MT18HS         | 244/190         |
| TCDL    | 10.0  | Lumber DOL      | 1.00            | BC        | 0.82 | Vert(CT) | -0.61 | 19-20 | >386   | 360 | MT20           | 244/190         |
| BCLL    | 0.0   | Rep Stress Incr | NO              | WB        | 0.81 | Horz(CT) | 0.04  | 13    | n/a    | n/a |                |                 |
| BCDL    | 5.0   | Code            | IRC2015/TPI2014 | Matrix-SH |      |          |       |       |        |     | Weight: 141 lb | FT = 20%F, 11%E |

| LUMBER    |                   | BRACING   |   |
|-----------|-------------------|-----------|---|
| TOP CHORD | 2x4 SP SS(flat)   | TOP CHORD | Structural wood sheathing directly applied or 4-5-2 oc purlins, except end verticals. |
| BOT CHORD | 2x4 SP SS(flat)   | BOT CHORD | Rigid ceiling directly applied or 10-0-0 oc bracing.                                  |
| WEBS      | 2x4 SP No.3(flat) |           |   |
| OTHERS    | 2x4 SP No.3(flat) |           |   |

| REACTIONS | (lb/size) | 13=1163/ Mechanical, (min. 0-1-8), 22=1213/0-3-8, (min. 0-1-8) |
|-----------|-----------|--|
|           | Max Grav  | 13=1179 (LC 4), 22=1213 (LC 1)                                 |

| FORCES    | (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.   |
|-----------|--|
| TOP CHORD | 2-3=-4059/0, 3-4=-4059/0, 4-5=-4059/0, 5-25=-6740/0, 6-25=-6740/0, 6-7=-6111/0, 7-8=-6165/0, 8-9=-5275/0, 9-10=-3700/0, 10-11=-3700/0                          |
| BOT CHORD | 21-22=0/1861, 20-21=0/4059, 19-20=0/6618, 18-19=0/6585, 17-18=0/6585, 16-17=0/5835, 15-16=0/5835, 14-15=0/4654, 13-14=0/2845                                   |
| WEBS      | 3-21=-1260/0, 4-20=0/586, 2-22=-2150/0, 11-13=-2997/0, 11-14=0/1089, 9-14=-1213/0, 9-15=0/788, 8-15=-711/0, 8-17=0/420, 6-17=-520/0, 5-20=-2794/0, 2-21=0/2865 |


- NOTES**
- Unbalanced floor live loads have been considered for this design.
  - All plates are MT20 plates unless otherwise indicated.
  - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
  - Use Simpson Strong-Tie THA422 (6-16d Girder, 6-10d Truss) or equivalent at 7-8-12 from the left end to connect truss(es) to front face of top chord.
  - Fill all nail holes where hanger is in contact with lumber.
  - In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

| LOAD CASE(S) | Standard  |
|--------------|---|
| 1)           | Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00 |
|              | Uniform Loads (lb/ft)   |
|              | Vert: 13-22=-10, 1-12=-100  |
|              | Concentrated Loads (lb)   |
|              | Vert: 25=-216 (F)   |





UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Joy Perry Run: 8.81 S Sep 13 2024 Print: 8.810 S Sep 13 2024 MiTek Industries, Inc. Thu Feb 27 10:16:20 Page: 1  
ID:9wPDsvsVaW4cYkLCLVRSonyE\_LD-jdgMcngROxcqLV4K6KXUj1j18GLEiR0fMYvTvzrh\_C



|                  |  |  |  |
|------------------|--|--|--|
| <b>LUMBER</b>    |  | <b>BRACING</b>   |  |
| TOP CHORD        | 2x4 SP No.1(flat)  | TOP CHORD  | Structural wood sheathing directly applied or 4-10-5 oc purlins, except end verticals. |
| BOT CHORD        | 2x4 SP SS(flat)  | BOT CHORD  | Rigid ceiling directly applied or 10-0-0 oc bracing.                                   |
| WEBS             | 2x4 SP No.3(flat)  |  |  |
| OTHERS           | 2x4 SP No.3(flat)  |  |  |
| <b>REACTIONS</b> | (lb/size)  | 12=1299/0-3-8, (min. 0-1-8), 18=1310/0-3-8, (min. 0-1-8) |  |
| <b>FORCES</b>    | (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.   |  |  |
| TOP CHORD        | 2-3=-3825/0, 3-4=-3798/0, 4-5=-5674/0, 5-6=-5674/0, 6-7=-5674/0, 7-8=-3718/0, 8-9=-3749/0, 9-10=-3749/0                                |  |  |
| BOT CHORD        | 17-18=0/2873, 16-17=0/4772, 15-16=0/4772, 14-15=0/5674, 13-14=0/4681, 12-13=0/2851   |  |  |
| WEBS             | 5-15=-353/0, 6-14=-803/0, 10-12=-3058/0, 10-13=0/1169, 7-13=-1184/0, 7-14=0/1564, 2-18=-3081/0, 2-17=0/1239, 4-17=-1203/0, 4-15=0/1071 |  |  |

**NOTES**

- 1) Unbalanced floor live loads have been considered for this design.
- 2) All plates are MT20 plates unless otherwise indicated.
- 3) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 4) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
- 5) Use Simpson Strong-Tie THA422 (6-16d Girder, 6-10d Truss) or equivalent at 7-8-12 from the left end to connect truss(es) to back face of top chord.
- 6) Fill all nail holes where hanger is in contact with lumber.
- 7) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

| LOAD CASE(S) | Standard  |
|--------------|---|
| 1)           | Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00 |
|              | Uniform Loads (lb/ft)   |
|              | Vert: 12-18=-10, 1-11=-140  |
|              | Concentrated Loads (lb)   |
|              | Vert: 5=-176 (B)  |



This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.



|          |       |            |     |     |                             |
|----------|-------|------------|-----|-----|-----------------------------|
| Job      | Truss | Truss Type | Qty | Ply | MUNGO HOMES-RUSSELL 2ND FLR |
| 72436981 | FG3   | Truss      | 1   | 1   | Job Reference (optional)    |

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Joy Perry

Run: 8.81 S Sep 13 2024 Print: 8.810 S Sep 13 2024 MiTek Industries, Inc. Thu Feb 27 10:16:20

Page: 1

ID:2YMeRnnRhJzYswzaSXeE7TyE?I?-jdgMongROxcqLV4K6KXUj1jFRGT2idZfMYvTVrzh\_Cv




Plate Offsets (X, Y): [2:0-2-0,Edge], [3:0-3-0,Edge], [4:0-2-0,Edge], [5:0-2-0,Edge]

| Loading | (psf) | Spacing         | 2-0-0           | CSI      |      | DEFL     | in    | (loc) | I/defl | L/d | PLATES        | GRIP            |
|---------|-------|-----------------|-----------------|----------|------|----------|-------|-------|--------|-----|---------------|-----------------|
| TCLL    | 40.0  | Plate Grip DOL  | 1.00            | TC       | 0.05 | Vert(LL) | n/a   | -     | n/a    | 999 | MT20          | 244/190         |
| TCDL    | 10.0  | Lumber DOL      | 1.00            | BC       | 0.20 | Vert(CT) | -0.02 | 4-5   | >999   | 360 |               |                 |
| BCLL    | 0.0   | Rep Stress Incr | NO              | WB       | 0.10 | Horz(CT) | 0.00  | 4     | n/a    | n/a |               |                 |
| BCDL    | 5.0   | Code            | IRC2015/TPI2014 | Matrix-P |      |          |       |       |        |     | Weight: 24 lb | FT = 20%F, 11%E |

| LUMBER    |                   | BRACING   |   |
|-----------|-------------------|-----------|---|
| TOP CHORD | 2x4 SP No.2(flat) | TOP CHORD | Structural wood sheathing directly applied or 3-5-0 oc purlins, except end verticals. |
| BOT CHORD | 2x4 SP No.2(flat) | BOT CHORD | Rigid ceiling directly applied or 10-0-0 oc bracing.                                  |
| WEBS      | 2x4 SP No.3(flat) |           |   |
| OTHERS    | 2x4 SP No.3(flat) |           |   |

| REACTIONS | (lb/size)  | 4=316/ Mechanical, (min. 0-1-8), 5=316/ Mechanical, (min. 0-1-8) |
|-----------|--|--|
| FORCES    | (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown. |  |
| BOT CHORD | 4-5=0/376  |  |
| WEBS      | 2-4=-437/0, 2-5=-437/0   |  |


- NOTES**
- This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
  - Use Simpson Strong-Tie THA422 (6-16d Girder, 6-10d Truss) or equivalent at 1-10-4 from the left end to connect truss(es) to back face of top chord.
  - Fill all nail holes where hanger is in contact with lumber.
  - In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

| LOAD CASE(S)   | Standard |
|--|----------|
| 1) Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00 |          |
| Uniform Loads (lb/ft)  |          |
| Vert: 4-5=-10, 1-3=-100  |          |
| Concentrated Loads (lb)  |          |
| Vert: 2=-297 (B)   |          |





UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Joy Perry Run: 8.81 S Sep 13 2024 Print: 8.810 S Sep 13 2024 MiTek Industries, Inc. Thu Feb 27 10:16:20 Page: 1  
ID:5qSkFPUoDL8ZxMONo8?X\_yE?DD-jdgMcngROxcqLV4K6KXUj1j1GGKOiVxfMYvTVrz\_Cu




|                |       |                 |                 |            |      |             |       |       |        |     |               |                 |
|----------------|-------|-----------------|-----------------|------------|------|-------------|-------|-------|--------|-----|---------------|-----------------|
| <b>Loading</b> | (psf) | <b>Spacing</b>  | 2-0-0           | <b>CSI</b> |      | <b>DEFL</b> | in    | (loc) | I/defl | L/d | <b>PLATES</b> | <b>GRIP</b>     |
| TCLL           | 40.0  | Plate Grip DOL  | 1.00            | TC         | 0.90 | Vert(LL)    | n/a   | -     | n/a    | 999 | MT20          | 244/190         |
| TCDL           | 30.0  | Lumber DOL      | 1.00            | BC         | 0.82 | Vert(CT)    | -0.07 | 4-5   | >785   | 360 |               |                 |
| BCLL           | 0.0   | Rep Stress Incr | NO              | WB         | 0.59 | Horz(CT)    | 0.02  | 4     | n/a    | n/a |               |                 |
| BCDL           | 5.0   | Code            | IRC2015/TPI2014 | Matrix-P   |      |             |       |       |        |     | Weight: 32 lb | FT = 20%F, 11%E |

Vert: 8=-1172 (F), 9=-1173 (F)



UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Joy Perry Run: 8.81 S Sep 13 2024 Print: 8.810 S Sep 13 2024 MiTek Industries, Inc. Thu Feb 27 10:16:20 Page: 1  
ID:6kHpOvkk48bceYi?wZjoaTyE\_lo-ldgMcngROxcgLV4K6KXUj1jAvGUCia9fMYvTVrzrh\_Cv




|                  |   |
|------------------|---|
| <b>REACTIONS</b> | All bearings 9-9-8.   |
| (lb) - Max Grav  | All reactions 250 (lb) or less at joint(s) 12, 13, 14, 15, 17 except 10=274 (LC 1), 11=751 (LC 1), 16=1127 (LC 1) |
| <b>FORCES</b>    | (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.                                      |
| <b>WEBS</b>      | 2-16=1134/0, 7-11=723/0, 8-10=313/0   |

- 

This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.

|          |       |            |     |     |                             |
|----------|-------|------------|-----|-----|-----------------------------|
| Job      | Truss | Truss Type | Qty | Ply | MUNGO HOMES-RUSSELL 2ND FLR |
| 72436981 | K200  | Truss      | 1   | 1   | Job Reference (optional)    |



| Loading | (psf) | Spacing         | 2-0-0           | CSI      | DEFL | in        | (loc) | I/defl | L/d | PLATES | GRIP          |                 |
|---------|-------|-----------------|-----------------|----------|------|-----------|-------|--------|-----|--------|---------------|-----------------|
| TCLL    | 40.0  | Plate Grip DOL  | 1.00            | TC       | 0.09 | Vert(LL)  | n/a   | -      | n/a | 999    | MT20          | 244/190         |
| TCDL    | 10.0  | Lumber DOL      | 1.00            | BC       | 0.02 | Vert(TL)  | n/a   | -      | n/a | 999    |               |                 |
| BCLL    | 0.0   | Rep Stress Incr | YES             | WB       | 0.03 | Horiz(TL) | 0.00  | 18     | n/a | n/a    |               |                 |
| BCDL    | 5.0   | Code            | IRC2015/TPI2014 | Matrix-R |      |           |       |        |     |        | Weight: 80 lb | FT = 20%F, 11%E |

| LUMBER                      | BRACING   |
|-----------------------------|---|
| TOP CHORD 2x4 SP No.2(flat) | TOP CHORD Structural wood sheathing directly applied or 6'-0" 0 oc purlins, except end verticals. |
| BOT CHORD 2x4 SP No.2(flat) | BOT CHORD Rigid ceiling directly applied or 10'-0" 0 oc bracing.                                  |
| WEBS 2x4 SP No.3(flat)      |   |
| OTHERS 2x4 SP No.3(flat)    |   |

| REACTIONS       | All bearings 19'-0" 0.  |
|-----------------|---|
| (lb) - Max Grav | All reactions 250 (lb) or less at joint(s) 18, 19, 20, 21, 22, 23, 24, 26, 27, 28, 29, 30, 31, 32, 33 |

| FORCES | (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown. |
|--------|--|
|--------|--|

- NOTES**
- 1) All plates are 1.5x3 MT20 unless otherwise indicated.
  - 2) Gable requires continuous bottom chord bearing.
  - 3) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
  - 4) Gable studs spaced at 1'-4" 0 oc.
  - 5) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 6) Recommend 2x6 strongbacks, on edge, spaced at 10'-0" 0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.






|          |       |            |     |     |                             |
|----------|-------|------------|-----|-----|-----------------------------|
| Job      | Truss | Truss Type | Qty | Ply | MUNGO HOMES-RUSSELL 2ND FLR |
| 72436981 | K201  | Truss      | 1   | 1   | Job Reference (optional)    |

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Joy Perry

Run: 8.81 S Sep 13 2024 Print: 8.810 S Sep 13 2024 MiTek Industries, Inc. Thu Feb 27 10:16:21

Page: 1

ID:KdulQDGrBdiGp0wrtN5mDPyE?Y9-BpEkq7g39FkhzffXg12jGFGPsgslR5yoeCe12Hzh\_Cu



| Loading | (psf) | Spacing         | 2-0-0           | CSI      | DEFL | in        | (loc) | l/defl | L/d | PLATES | GRIP          |                 |
|---------|-------|-----------------|-----------------|----------|------|-----------|-------|--------|-----|--------|---------------|-----------------|
| TCLL    | 40.0  | Plate Grip DOL  | 1.00            | TC       | 0.08 | Vert(LL)  | n/a   | -      | n/a | 999    | MT20          | 244/190         |
| TCDL    | 10.0  | Lumber DOL      | 1.00            | BC       | 0.01 | Vert(TL)  | n/a   | -      | n/a | 999    |               |                 |
| BCLL    | 0.0   | Rep Stress Incr | YES             | WB       | 0.03 | Horiz(TL) | 0.00  | 18     | n/a | n/a    |               |                 |
| BCDL    | 5.0   | Code            | IRC2015/TPI2014 | Matrix-R |      |           |       |        |     |        | Weight: 83 lb | FT = 20%F, 11%E |

| LUMBER    | BRACING   |
|-----------|-----------|
| TOP CHORD | TOP CHORD |
| BOT CHORD | BOT CHORD |
| WEBS      |           |
| OTHERS    |           |

**REACTIONS** All bearings 20-0-0.

(lb) - Max Grav All reactions 250 (lb) or less at joint(s) 18, 19, 20, 21, 22, 23, 24, 25, 27, 28, 29, 30, 31, 32, 33, 34

**FORCES** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES**
- 1) All plates are 1.5x3 MT20 unless otherwise indicated.
  - 2) Gable requires continuous bottom chord bearing.
  - 3) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
  - 4) Gable studs spaced at 1-4-0 oc.
  - 5) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 6) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.




|          |       |            |     |     |                             |
|----------|-------|------------|-----|-----|-----------------------------|
| Job      | Truss | Truss Type | Qty | Ply | MUNGO HOMES-RUSSELL 2ND FLR |
| 72436981 | K202  | Truss      | 1   | 1   | Job Reference (optional)    |

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Joy Perry

Run: 8.81 S Sep 13 2024 Print: 8.810 S Sep 13 2024 MiTek Industries, Inc. Thu Feb 27 10:16:21

Page: 1

ID: \_C8iW8c2MXM9nTeQ4z6ZvXyE?Xi-BpEkq7g39FkhzffXg12jGFGPfgs?R5woaCe12Hzh\_Cu



| Loading | (psf) | Spacing         | 2-0-0           | CSI      | DEFL | in        | (loc) | l/defl | L/d | PLATES | GRIP          |                 |
|---------|-------|-----------------|-----------------|----------|------|-----------|-------|--------|-----|--------|---------------|-----------------|
| TCLL    | 40.0  | Plate Grip DOL  | 1.00            | TC       | 0.09 | Vert(LL)  | n/a   | -      | n/a | 999    | MT20          | 244/190         |
| TCDL    | 10.0  | Lumber DOL      | 1.00            | BC       | 0.03 | Vert(TL)  | n/a   | -      | n/a | 999    |               |                 |
| BCLL    | 0.0   | Rep Stress Incr | YES             | WB       | 0.03 | Horiz(TL) | 0.00  | 19     | n/a | n/a    |               |                 |
| BCDL    | 5.0   | Code            | IRC2015/TPI2014 | Matrix-R |      |           |       |        |     |        | Weight: 86 lb | FT = 20%F, 11%E |

| LUMBER                      | BRACING   |
|-----------------------------|---|
| TOP CHORD 2x4 SP No.2(flat) | TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals. |
| BOT CHORD 2x4 SP No.2(flat) | BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.                                  |
| WEBS 2x4 SP No.3(flat)      |   |
| OTHERS 2x4 SP No.3(flat)    |   |

**REACTIONS** All bearings 20-5-8.


(lb) - Max Grav All reactions 250 (lb) or less at joint(s) 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34

**FORCES** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES**
- 1) All plates are 1.5x3 MT20 unless otherwise indicated.
  - 2) Gable requires continuous bottom chord bearing.
  - 3) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
  - 4) Gable studs spaced at 1-4-0 oc.
  - 5) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 6) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.



|          |       |            |     |     |                             |
|----------|-------|------------|-----|-----|-----------------------------|
| Job      | Truss | Truss Type | Qty | Ply | MUNGO HOMES-RUSSELL 2ND FLR |
| 72436981 | K203  | Truss      | 1   | 1   | Job Reference (optional)    |



| Loading | (psf) | Spacing         | 2-0-0           | CSI      | DEFL | in        | (loc) | I/defl | L/d | PLATES | GRIP          |                 |
|---------|-------|-----------------|-----------------|----------|------|-----------|-------|--------|-----|--------|---------------|-----------------|
| TCLL    | 40.0  | Plate Grip DOL  | 1.00            | TC       | 0.08 | Vert(LL)  | n/a   | -      | n/a | 999    | MT20          | 244/190         |
| TCDL    | 10.0  | Lumber DOL      | 1.00            | BC       | 0.02 | Vert(TL)  | n/a   | -      | n/a | 999    |               |                 |
| BCLL    | 0.0   | Rep Stress Incr | YES             | WB       | 0.03 | Horiz(TL) | 0.00  | 14     | n/a | n/a    |               |                 |
| BCDL    | 5.0   | Code            | IRC2015/TPI2014 | Matrix-R |      |           |       |        |     |        | Weight: 66 lb | FT = 20%F, 11%E |

| LUMBER                      | BRACING   |
|-----------------------------|---|
| TOP CHORD 2x4 SP No.2(flat) | TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals. |
| BOT CHORD 2x4 SP No.2(flat) | BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.                                  |
| WEBS 2x4 SP No.3(flat)      |   |
| OTHERS 2x4 SP No.3(flat)    |   |

| REACTIONS       | All bearings 15-6-8.  |
|-----------------|---|
| (lb) - Max Grav | All reactions 250 (lb) or less at joint(s) 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26 |

| FORCES | (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown. |
|--------|--|
|--------|--|

- NOTES**
- 1) All plates are 1.5x3 MT20 unless otherwise indicated.
  - 2) Gable requires continuous bottom chord bearing.
  - 3) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
  - 4) Gable studs spaced at 1-4-0 oc.
  - 5) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 6) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

