



** TAPCON LDT 125 SCREWS (OR EQUIVALENT) REQ'D @ 6' O.C., 12" MAX FROM WALL CORNERS AND SOLE PLATE SPLICES IN LIEU OF WET SET ANCHOR BOLTS. MIN (2) SCREWS PER SOLE PLATE SEGMENT TYP @ CLOUDED WALLS. **

1ST FLOOR FRAMING PLAN
WALLS AND CEILING
N.T.S.

Engineering Tech
STRUCTURAL ENGINEERS
License No. C-3870
318 W Millbrook Rd. Unit 201
Raleigh, North Carolina 27609
Phone (919) 844-1661
ASSOCIATES, P.A.

ADAMS HOMES		REV #	REF PROJ #	DATE
SCOPE:	MISSING ANCHOR BOLTS			
LOC:	116 KIPLING CREEK			

ENG: CMC/WHF
DATE: 6/27/2025

PARENT
25-18-085

PROJECT NO.
25-75-667

SHEET NO.
SL1
1 of 1