

As directed by the North Carolina Board of Architecture and Registered Interior Designers, architectural seals are not required for - and should not be placed by NVR on - these plans and specifications. These plans and specifications are prepared solely by, and for the exclusive use of, NVR, Inc. and are solely for a family residence consisting of eight or fewer attached units with grade level exits and which is not part of or physically connected with any other buildings or residential units. NVR, Inc. does not provide any third party the opportunity to customize these plans. The respective drawings contained herein shall be used only as construction assembly drawings by NVR, Inc. and its subcontractors. Any unauthorized use of these plans with the written consent of NVR, Inc. is prohibited.

DOMINICA SPRING

DIV-COMM-LOT-UNIT		
<div style="text-align: center;"> <div style="border: 1px solid black; width: 100px; height: 100px; margin: 0 auto;"></div> </div>		
COMM-LOT		
<div style="text-align: center;"> <div style="border: 1px solid black; width: 100px; height: 100px; margin: 0 auto;"></div> </div>		
STREET ADDRESS		APT. NO.
<div style="text-align: center;"> <div style="border: 1px solid black; width: 100px; height: 100px; margin: 0 auto;"></div> </div>		<div style="text-align: center;"> <div style="border: 1px solid black; width: 100px; height: 100px; margin: 0 auto;"></div> </div>
CITY	STATE	ZIP
<div style="text-align: center;"> <div style="border: 1px solid black; width: 100px; height: 100px; margin: 0 auto;"></div> </div>	<div style="text-align: center;"> <div style="border: 1px solid black; width: 100px; height: 100px; margin: 0 auto;"></div> </div>	<div style="text-align: center;"> <div style="border: 1px solid black; width: 100px; height: 100px; margin: 0 auto;"></div> </div>

As directed by the North Carolina Board of Architecture and Registered Interior Designers, architectural seals are not required for – and should not be placed by NVR on – these plans and specifications.

James Bales
03/14/2025



NVR, Inc.
5285 Westview Drive,
Suite 100
Frederick, MD 21703

[illegible]

FIRST FLOOR SQUARE FOOTAGE	
DESCRIPTION	TOTAL SQ. FT.
1ST FLOOR CRAWL / SLAB FOUNDATION (BASE SF)	1644 SF
	1644 SF
GARAGE SQUARE FOOTAGE	
DESCRIPTION	TOTAL SQ. FT.
TWO CAR GARAGE CRAWL / SLAB FOUNDATION	442 SF
	442 SF
UNFINISHED SQUARE FOOTAGE	
DESCRIPTION	TOTAL SQ. FT.
REAR COVERED PORCH (ADD. SF)	140 SF
FRONT COVERED PORCH	24 SF
	164 SF
TOTAL FINISHED SQUARE FOOTAGE	
DESCRIPTION	TOTAL SQ. FT.
1ST FLOOR CRAWL / SLAB FOUNDATION (BASE SF)	1644 SF
	1644 SF

SET NO. - VERSION	SHEET NO.	PAGE NO.
DSP00 - 01	CS-1	1
RELEASE NO. ----		

STRUCTURAL DESIGN CRITERIA	
ALL LOCAL AND STATE CODES	
ROOF LIVE LOAD	20 psf
ULTIMATE WIND SPEED	130 mph
WIND EXPOSURE CATEGORY	B
SEISMIC DESIGN CATEGORY	A / B

\\As-Sold\2-Jobs\ASD\2025 1stHalf-Complete\RLH\DETACHED\DOMINICA SPRING_DSP00_01\ELK_R_VK_0015\1 CS-1 COVERSHEET.dwg 03/14/25 - 7:22 am

1. These plans and specifications are designed for the exclusive use by NVR, Inc. for the purpose of residential construction. As such, these products are offered for sale in NVR, Inc. communities only. NVR, Inc. is a production homebuilder and does not provide the opportunity to customize these plans. The respective drawings contained herein in shall only be used as construction assembly drawings by NVR, Inc. and their sub-contractors. Any unauthorized use of these plans without the written consent of NVR, Inc. is prohibited. All standard notes, section markers, elevation markers and title markers that reference "A-1" shall be considered "N-C-1" for sheet reference.
2. These plans are subjected to modification as necessary to meet code requirements or to facilitate mechanical/plumbing installations or to incorporate design improvements.
3. These plans are not to be scaled for construction purposes. Dimension lines and notes supersede all scale references.
4. Single Family Attached/Detached - Automatic residential fire sprinkler systems shall be installed in accordance with **MGRCB P2104** or **NFPA 13D** where required.
5. This note sheet only covers major code requirements. The plans are intended to conform to all current applicable codes or engineering design in accordance with Section 301.3.

1. This note sheet only covers major code requirements. The plans are intended to conform to all current applicable codes including, but not limited to:

NRCR 2018, NCMC 2018, NCPG 2018, NCF6C 2018, NEC 2020 w/ NC Amendments,
NCEC 2018, NCFPC 2018

2. Constr. Type: V-B

3. Max Stories: 3

1. Insulation requirements per 2018 NRCG Chapter 11, Energy Efficiency, or Chapter 4 of the 2018 North Carolina Energy Conservation Code (NCECC), or Chapter 4 of the 2015 International Energy Conservation Code (IECC), Residential Energy Efficiency by the prescriptive method. See NVR "Standard Energy Package" for field procedures and details.

R-values shown below are the minimum used.

CLIMATE ZONE	FENESTRATION U-FACTOR	GLAZED FENESTRATION SHGC	CEILING R-VALUE	FRAME WALL R-VALUE 2x4 / 2x6	FLOOR R-VALUE	BASEMENT WALL R-VALUE UNFIN. / FIN.	SLAB R-VALUE & DEPTH	GRAVL SPACE WALL R-VALUE
3	0.35	0.30	38	15 / 19	19	5 / 15	NA	5 / 15
4	0.35	0.30	38	15 / 19	19	10 / 15	10	10 / 15

2. All HVAC equipment is sized based on ACCA Manual J calculations. Ductwork is sized using ACCA Manual D. Minimum efficiencies of equipment are as listed below. Upgrades for improved energy performance may be installed.
 - Air conditioner - 14 SEER
 - Gas furnace - 92% / 96%
 - Heat Pump - 9.2 HSPF
3. Winter interior design temperatures shall be 70°F and summer interior design temperatures shall be 75°F. Exterior design temperatures vary based on geographic location and are listed on the Manual J calculations.
4. Roof ventilation calculations are based on the following specifications:

Ridge vent:	Minimum 18 sq. in. of vent per linear foot
Soffit vent:	Minimum 4.4 sq. in. of vent per linear foot
Roof Jack (box vent):	Minimum 45 sq. in. of vent per unit
5. See NVR "Standard Energy Package" for field procedures and details.

Table of Loads for House Structure, Per Table 301.5

Floor Living Areas	- 40# P.S.F. (Live)	
	- 10# P.S.F. (Dead)	unless noted otherwise by calculations
Floor Sleeping Areas	- 30# P.S.F. (Live)	unless noted otherwise by calculations
	- 10# P.S.F. (Dead)	unless noted otherwise by calculations
Garage Floors	- 50# P.S.F. (Live)	
	- 50# P.S.F. (Dead)	
Roof Areas	- Top Chord	
	- 20# P.S.F. (Live)	
	- 10# P.S.F. (Dead)	
	- Bottom Chord	
	- 10# P.S.F. (Live)	(Attics without storage)
	- 20# P.S.F. (Live)	(Attics with limited storage)
	- 10# P.S.F. (Dead)	
	- 30# P.S.F. (Live)	
Habitable Attics	- Areas up to 130 mph ultimate wind speed per	
Trusses	Table R301.2(4)	
	- Exposure category 'B'	
Walls	- Areas up to 130 mph ultimate wind speed per	
	Table R301.2(4)	

Vult	115 mph	130 mph
Vasd	84 mph	101 mph

Note: Linear interpolation between contour lines permitted.

Stairs	- 40# P.S.F. (Live)	
	- 10# P.S.F. (Dead)	

Allowable deflection of structural members per IRC Table R301.7

Design Codes:

1. National Design specification for Wood Construction by National Forest Products Association.
2. Specification for the Design Fabrication and Erection of Structural Steel for Buildings by American Institute of Steel Construction.

Materials:

Headers*	Southern Pine (KD-14), No. 1 Grade
Studs	Spruce-Pine-Fir, Stud Grade
Jacks	Spruce-Pine-Fir, Stud Grade
Beams**	Southern Pine (KD-14), No. 1 Grade
Joists	2x10 Hem-Fir (KD-14), No. 2 Grade or better (NCLIB & NWFA) 2x8 Southern Pine (KD-14), No. 1 Grade or better 2x10 Spruce-Pine-Fir (KD-14), No. 2 Grade or better (NLGA)
LVL	1.9E Minimum

- * Where required, Laminated Veneer Lumber may be used per Engineering
 ** Structural Steel - A.S.T.M. A36

5. All plan and reinforced concrete shall comply with ACI 318.
6. Concrete footings shall be poured a maximum 5' slump, 5 bag mix, and 2,500 psi minimum strength per **Table R402.2**. Concrete walls shall be poured a maximum 5' slump, 5 1/2-bag mix, and 3,000 psi minimum strength per **Foundation Wall Design Table** below. Special soil and/or wall backfill conditions may require a higher psi mix.
7. Walls and footings designed as unreinforced unless otherwise specified on foundation plans or details. Special soil and/or site conditions may require the addition of reinforcing.
8. Footing frost depth to be no less than 12" per **R403.1.4** and **Table R301.2(1)**.
9. Minimum Soil Bearing Capacity shall be 2,000 PSF per **Table R401.4.1**.
10. Slab requirements:

Interior slabs on grade (excluding garage slabs) to be minimum 3'-1/2" concrete (may be represented on plans as nominal 4") over 4" sub-base, with vapor barrier (6-mil polyethylene) as required per **Section S06** and a minimum 2,500 PSI per **Table R402.2**.

Non-structural garage slabs shall be nominal 3'-1/2" thick and shall be installed on compacted / undisturbed soil per **Table R402.2.2**. Slabs shall be 3,500 PSI air-entrained concrete.

Structural garage slabs utilizing grade beams shall be nominal 4" thick. Slabs shall be 3,500 PSI air-entrained concrete.

Porch slab and exterior concrete work shall be nominal 4" minimum 3,500 PSI air-entrained concrete with #6x16 N4xPL4 mesh or equivalent fiber mesh reinforcement.
11. Unconditioned crawl spaces shall have a minimum net area of ventilation not less than 1 square foot for each 150 square feet of area, unless the ground surface is covered by a Class I vapor retarder, in which case the minimum net area of ventilation shall not be less than 1 square foot for each 150 square feet of area. One such ventilating opening shall be within 3 feet (914 mm) of each corner of the building, per **R408.1.2**.
12. Foundation drains shall be located per local codes and according to local site conditions. Drain discharge by gravity or mechanical means to conform with approved site plan and installed per **Section R405.1**.
13. The top course of block of foundation walls shall be semi-solid block or open cores of hollow block shall be filled with mortar.
14. Block piers to be solid block or mortar-filled hollow block.
15. A poured concrete foundation wall designed to withstand an equivalent fluid weight of 30# per cubic ft. may be substituted where masonry units (block) are shown on plans.
16. Concrete and masonry foundation walls shall be dampproofed with min. 3/8" portland cement parging from footing to top of finished grade. The parging shall be covered with a coat of approved bituminous material applied at the recommended rate per **R406.1**.
17. Where required, concrete and masonry foundation walls shall be waterproofed with an approved membrane extending from footing to top of finished grade. The joints in the membrane shall be lapped and sealed with an adhesive compatible with the waterproofing membrane. Waterproofing to be in accordance with **R406.2**.
18. Reserved for future use.
19. Foundation framing anchors shall be 1/2"x18" anchor bolts with 7" minimum embedment or Simpson Strong-Tie MASA / USP FA3 (6 gauge steel, galvanized) or equivalent set in concrete or grouted cell, 1'-0" maximum from corners and spaced at a maximum of 6' o.c. and in the middle third of the width of the plate. For walls connecting offset braced wall panels, those 24" in length or shorter shall have min. (1) anchor strap and those 12" or shorter can be installed without a strap and secured with an approved tie category "C" shall require a .224" x 3" x 3/4" plate washer per **R403.1.6.1** and maximum anchor bolt spacing for buildings over two stories shall be 4'.
20. Steel columns and bases shall be given a shop coating of rust-inhibitive paint or equivalent to provide corrosion resistance per **R407.2**.
21. For masonry veneers:

Per **R703.8.4.1** - Corrugated sheet metal veneer ties shall be a minimum of No. 22 U.S. gauge by 7/8 inch. Each tie shall be spaced not more than 32" o.c. horizontally and 24" o.c. vertically and shall support not more than 2.67 square feet of wall area. For townhouses in Seismic Design Category C and in wind areas of more than 30 pounds per square foot pressure, each tie shall support not more than 2 square feet of wall area.

Additional metal ties shall be provided around all wall openings greater than 16 inches (406 mm) in either dimension. Metal ties around the perimeter of openings shall be spaced not more than 3 feet (914 mm) on center and placed within 12 inches (305 mm) of the wall opening.

Per R703.2 - One layer of No. 15 asphalt felt or other approved water-resistive barrier shall be provided behind brick.

Per Table R703.8.4 - Provide minimum 1-inch air space between brick veneer and sheathing.

Per R703.8.6 - Provide minimum 3/16" diameter weep holes at 33" on center maximum, located immediately above the flashing.

Per R703.8.5 - When veneer of brick, clay tile, concrete, or natural or artificial stone are used, 6 mil plastic flashing shall be attached to the sheathing wherever necessary to prevent moisture penetration behind the veneer. See NVR Flashing Details.

19. Foundation wall strip footing thickness to be 8" (or 6" with a single story) unless otherwise noted as specified by engineering. Strip footing projections beyond the face of the foundation wall shall not to exceed the footing thickness. Bump out footings, pier pads, and any other footing identified as being greater than 8" in thickness shall not be reduced.

20. Block foundation walls may be substituted for poured foundation walls shown on foundation plans provided all requirements of **Section R404** are met.
21. Termite treatment provided below slabs or to framing members per **R318.1**

FOUNDATION WALL DESIGN^(c)
NCRBC PRESCRIPTIVE CODE OR ENGINEERED DESIGN PER ACI 332

WALL HEIGHT	WALL THICKNESS	LATERAL SOIL LOAD (a)	UNBALANCED FILL	VERTICAL REINFORCING (b)	HORIZONTAL REINFORCING (b)
8'-0"	8"	45	6'-0"	NOT REQUIRED	2- #4 BARS (f)
			7'-0"	NOT REQUIRED (d)	3- #4 BARS (de)
		60	6'-0"	NOT REQUIRED (d)	3- #4 BARS (de)
			7'-0"	#4 @ 22" O.C. (d)	3- #4 BARS (de)
	10"	45	6'-0"	NOT REQUIRED	2- #4 BARS (f)
			7'-0"	NOT REQUIRED	2- #4 BARS (f)
		60	6'-0"	NOT REQUIRED	2- #4 BARS (f)
			7'-0"	NOT REQUIRED	2- #4 BARS (f)
4'-0"	8"	45	7'-0"	NOT REQUIRED (d)	4- #4 BARS (de)
			8'-0"	#4 @ 19" O.C. (d)	4- #4 BARS (de)
		60	7'-0"	#4 @ 14" O.C. (d)	4- #4 BARS (de)
			8'-0"	#4 @ 15" O.C. (d)	4- #4 BARS (de)
	10"	45	7'-0"	NOT REQUIRED	3- #4 BARS (g)
			8'-0"	NOT REQUIRED (d)	4- #4 BARS (de)
		60	7'-0"	NOT REQUIRED (d)	4- #4 BARS (de)
			8'-0"	#4 @ 19" O.C. (d)	4- #4 BARS (de)

NOTE: BACKFILLING OF THE FOUNDATION SHALL NOT TAKE PLACE BEFORE THE BASEMENT SLAB IS IN PLACE AND THE FLOOR FRAMING IS ERECTED OR UNLESS WALLS ARE ADEQUATELY BRACED.

- a. SOIL CLASSES GM, GC, SM, SM-SC AND ML - 45 PSF
- b. SOIL CLASSES SC, MH, ML-CL AND CL - 60 PSF
- b. SPACING SHOWN IS BASED UPON FY = 60,000 PSI
STEEL FOR FY = 40,000 PSI STEEL, REDUCE SPACING BY 0.67
- c. CONCRETE SHALL HAVE A COMPRESSIVE STRENGTH OF NOT LESS THAN 3000 PSI
- d. ENGINEERED DESIGN PER ACI 332-14, REQUIREMENTS FOR RESIDENTIAL
CONCRETE CONSTRUCTION
- e. FOR ALL WALL HEIGHTS, ONE HORIZONTAL BAR SHALL BE LOCATED WITHIN THE
TOP 24", ONE IN THE BOTTOM 24" WITH THE REMAINING BARS EQUALLY SPACED.
MAINTAIN 2" OF CONCRETE COVER BETWEEN INSIDE FACE OF WALL AND FACE OF
HORIZONTAL BARS.
- f. ONE BAR WITHIN 12" OF TOP AND AT MID-HEIGHT OF WALL PER TABLE R404.1(2)(1).
- g. ONE BAR WITHIN 12" OF TOP AND ONE EACH AT THIRD POINT OF WALL HEIGHT
PER TABLE R404.1(2)(1).

1. Habitable attics and sleeping rooms shall have a window or door as a second means of egress that shall be minimum 5.7 sq. ft. openable area (5.0 sq. ft. if at grade level) with maximum sill height 44" above finish floor (min. hgt. 24", min. width 20") per **R310.1**.
2. All emergency escape and rescue openings shall have a minimum net clear openable area of 4 sq. ft. The minimum net clear opening height shall be 20" and a minimum net clear opening width of 20". Emergency escape and rescue openings must have a minimum total glazing area of not less than 5 sq. ft. in the case of a ground window and not less than 5.7 sq. ft. in the case of an upper story window per **R310.2.1**. Window wells where required, shall be installed per **R310.2.3** with a minimum of 9 sq. ft. and a minimum horizontal projection and width of 36". Wells with a greater depth of 44" shall have permanently affixed ladder or steps per **R310.2.3.1**.
3. Clear opening heights for exterior doors to be 6'-6" minimum per **R311.2**. All exterior doors providing egress and rescue openings must have nominal minimum dimensions of 2'-6" by 6'-8" per **R311.6.1**. Habitable rooms with double doors less than 5'-0" in total width (less than 2'-6" per door slab) shall have a total opening width of at least 2'-6" with no side bolts or locking devices installed on either door.
4. Sliding glass drs/patio drs/skds must be safety glazed per **R308.4**.
5. Interior stairways shall have minimum head room of 6'-8" per **R311.7.1** and minimum tread depth of 4" and maximum riser height of 8 1/4". Handrails are required for stairs with four or more risers and shall have minimum height of 34" and maximum height of 38" above treads and landings. Handrail to have maximum 4 1/2" projection into width of stair per **Section R311.7**. Enclosed accessible space under stairs shall have walls on stair surface and any soffits protected on the enclosed side with 1/2" gypsum board per **R302.1**.
6. Guard rails to have minimum height of 36" and shall not have openings from the walking surface to the required guard height which allow passage of a sphere 4 inches in diameter per **R312**.
7. The triangular openings at the open side of stair, formed by the riser, tread and bottom rail of a guard, shall not allow passage of a sphere 6 inches (153 mm) in diameter per **R312.1.3**.
8. Where exterior landings or floors serving the required egress door are not at grade, they shall be provided with access to grade by means of a stairway in accordance with **Section R311.7** (see item #5 above) or a ramp in accordance with **Section R311.8**.
9. Handrails shall be installed on exterior stairs having (4) or more risers per **R311.7.8**. Guards shall be installed at exterior porches / decks that are located more than 30 inches (762 mm) measured vertically to the floor or grade below at any point within 36 inches (914 mm) horizontally to the edge of the open side. Insect screening shall not be considered as a guard.
10. All flashing used (including at windows, doors, and with stone or masonry veneer) shall be corrosion-resistant per **R103.4**. See NVR Flashing Details.
11. Wood framed bearing walls shall 2 x 6 at 24" o.c. maximum or 2 x 4 at 16" o.c. maximum per **Table R602.3(3)** and **Table R602.3(5)** unless otherwise noted on plans.
12. All exterior sheathing to be structural sheathing designed in accordance with **R602.10**.
13. An approved water-resistant barrier shall be applied over sheathing of exterior walls per **Section R103.2**.
14. Interior sheathing shall be 1/2" gypsum wall board unless otherwise noted. Exceptions may include, but are not limited to, special requirements for wall bracing and fire separation.
15. Scaffolding is typical for gypsum installation and nailing will only be permitted at the perimeter of the board.
 - All screws shall be corrosion-resistant Type W1 1-1/4" drywall screws.

SCREW FASTENING SCHEDULE				
Framing Spacing		WITH ADHESIVE		
		Ceilings	Load-brg. walls	Non-load-brg. walls
16		16	24	24
24		16	16	24
Framing Spacing		WITHOUT ADHESIVE		
		Ceilings	Load-brg. walls	Non-load-brg. walls
16		12	16	16
24		12	12	12


- For 1/2" wallboard, nails shall be 1-1/4" long, 1/4" head and .048 diameter shanks with annular ring or acceptable equivalent and comply with ASTM C544.
- For 5/8" wallboard, nails shall be 1-3/8" long, 1/4" head and .048 diameter shanks.
- Garages shall be completely separated from the residence and attic area by not less than 1/2" gypsum board applied to the garage side. Garages beneath habitable rooms shall be separated from all habitable rooms above by not less than 5/8" type X gyp. board. Where a structure is supporting a fire assembly, the structure supporting the garage, the structure shall also be protected by not less than 1/2" gypsum board per **Section R302.6**. Openings and penetrations through the separation shall be protected by sealing the area around the penetration per **Section R302.5**. The garage door shall be a 20-minute fire-rated door and be equipped with a self-closing device installed per **Section R302.5.1**.
- Asphalt shingles shall be installed per **Section R05.2**. For roof slopes of 2:12 through 4:12, in lieu of two layers of underlayment, a self-adhering polymer-modified bitumen underlayment shall be used per **R301.5.1** Exception #1.
- Attic spaces shall be ventilated w/ ridge and soffit vents unless otherwise noted. Venting provided per **R06.2**.
- Fireblocking shall be installed between ceiling and floor openings per **R302.11**. Draftstopping to be installed in accordance with **R302.12**.
- Water closet, lavatory or bidet shall not be set closer than 15 inches from its center to any side wall or any side wall opening of the window shall be a minimum of 30 inches center-to-center. Between adjacent fixtures, there shall be a clearance of not less than 2 inches in front of the water closet, lavatory or bidet to any wall, fixture or door per **P2105.1**.
- Heating and cooling equipment installation shall be in accordance with **IRC Chapter 14** and the **International Mechanical Code**.
- Mechanical fireplaces shall be installed per **Section R100.4** and **100.5**.
- Single family attached structures to have 2-hour dwelling unit separation wall continuous to roof deck. Roofing material to be minimum class "C" over approved fire retardant wood decking extending 4" each side of dwelling unit separation wall per **R302.2** and **R302.3**.
- Untreated wood shall be minimum 8" above finish grade per **R311.1** Item #2.
- Bottom plates on sills and any wood in contact w/ concrete or masonry to be pressure treated material per **Section R317**.
- Exterior egress swing doors shall open onto a landing not more than 8 1/4" below the top of the threshold when door swings in and 1 1/2" below the top of the threshold when the door swings out. The landing shall contain a minimum of 36" in the direction of travel and be at least the width of the doorway served per **R315.3**.
- Air exhaust and intake openings that terminate outdoors shall be protected with corrosion-resistant screens, louvers, or grills having a min. opening size of 1/4" and maximum of 1/2" in any dimension per **R30.6**.
- Fasteners and connectors for pressure preservative-treated wood shall be hot-dipped galvanized steel.
- Windows that have an operable opening more than 12" above finished grade or surface below, the lowest part of clear opening of the window shall be a minimum of 24" above the finished floor of the room in which the window is located. Glazing between the floor and 24" shall be fixed or have openings through which a 4" dia. sphere cannot pass per **Section R312.2**.
- The final grade shall fall a minimum of 6 inches within the first 10 feet of the foundation per **R401.3**.
- One- and two-family dwelling construction (R302.11):**
Vinyl or aluminum soffit material shall be securely attached to framing members and use an underlayment material of either fire retardant treated wood, 3/4-inch wood sheathing or 5/8-inch gypsum board. Venting requirements shall apply to both soffit and underlayment and shall be per **Section R06**. Where the property line is 10 feet or more from the building face, the provisions of this code section shall not apply.
Townhouse construction (R302.2.5):
Projections extending into the fire-separation distance shall have not less than 1-hour fire-resistive construction on the underside. Vinyl or aluminum soffit material shall be securely attached to framing members and use an underlayment material of either fire retardant treated wood, 3/4-inch wood sheathing or 5/8-inch gypsum board. Venting requirements shall apply to both soffits and underlayment. Soffits shall be nominal 2-inch continuous or equivalent intermittent and shall not exceed the minimum net free air requirements of **Section R06.2** by more than 50%. Vents in soffits are not allowed within 4 feet of fire walls or property lines per **R302.2.5** and **R302.2.6**.
- 1-hour fire-rated construction required on projections within 2' to 3' of lot line per **R302.1**. No projections allowed within 2' of property line.
- Note: Single Family Detached product will NOT be built within 3' of the property line.
- Wall bracing is designed in compliance with **Section R602.10**. When wall bracing is beyond the criteria for a prescriptive approach, the structure is analyzed utilizing engineering in compliance with the North Carolina Building Code (NCBC). Refer to house-specific wall bracing detail sheets and wall bracing standard details. Adhesive attachment of wall sheathing, including Method GB, shall not be permitted in Seismic Design Category C.
- Minimum floor sheathing shall be 5/8" tongue & groove decking underlayment grade plugged and sanded, exterior glue, glued and nailed on joists to meet "American Plywood Association" approved glued floor system, unless otherwise specified.

1. Ground-fault and arc-fault circuit interrupter protection is provided per NFPA 70 (National Electric Code).
2. Electric panel box installation to be in accordance with NFPA 70, Article 408 Section III. Location may vary by design.
3. Approved smoke detectors shall be installed in each sleeping room; outside each separate sleeping area. In the immediate vicinity of the bedrooms; and on each additional story of the dwelling, including basements and habitable attics but not including crawl spaces and uninhabitable attics. Where more than one smoke detector is required, the detectors shall be installed in such a manner that the activation of one alarm will activate all of the alarms in the individual unit. All smoke detectors shall receive their primary power from the building wiring and be equipped with a battery backup.
4. Unless listed for installation in such locations, smoke detectors shall be installed at least 10 feet from a cooking appliance, at least 3 feet from the door to a bathroom containing a tub or shower, at least 3 feet from an airc or supply registers, and at least 3 feet from the tip of a ceiling fan blade. In sleeping rooms, smoke detectors should be located in the vicinity of the room entrance. They shall be installed at the highest position of the ceiling (including tray or coffered ceilings) or within 12 inches vertically from the highest point in rooms with sloped ceilings.
5. Interior stairs shall be provided with an artificial light source in the vicinity of each landing or directly over each stair section, limiting light source to the level of each landing to a level not less than 1fc measured at the center of the tread or landing per R303.7.
6. Outlets within 6' of a sink must be GFI protected.
7. An approved carbon monoxide alarm shall be installed outside of each separate sleeping area in the immediate vicinity of the bedrooms. Where a fuel-burning appliance is located within a bedroom or its attached bathroom, a carbon monoxide alarm shall be installed within the bedroom. R315.3.
8. Outlets installed in laundry areas must be GFI protected.

As directed by the North Carolina Board of Architecture and Registered Interior Designers, architectural seals are not required for – and should not be placed by NVR on – these plans and specifications.

REV.	NO.	DATE	REMARKS
	1	1/8/14	MBT - CODE UPDATES FOR 2010 NCEBC
	2	3/1/14	MBT - UPDATED ENRGY NOTES
	3	12/16/22	MBT - REVISE NOTE FOR 2X4 OR 2X6 EXTERIOR WALLS.

03/14/2025



NVR, Inc.
Firm license #: D-047

©NVR, Inc., The owner, expressly reserves its copyright and other property rights in these plans. These plans are not to be reproduced, changed, or copied in any form or manner whatsoever, nor are they to be assigned to any third party, without first obtaining the expressed written consent of NVR, Inc.

NVR
NVR, Inc.
5285 Westview Drive, Suite 100
Frederick, MD 21703

SET NO.	
VERSION	
DRAWN BY	
DATE:	
OPTION	

SHEET NO.	SS-1	MODEL NCRC 2018 SPEC SHEET
		DRAWING TITLE SINGLE FAMILY ATTACHED SINGLE FAMILY DETACHED
		OPTION DESCRIPTION NC State Building Code - Residential Code 2018



ROOF VENTILATION CALCULATIONS

HOUSE NAME
HOUSE VERSION

DOMINICA SPRING			
DSPO0_01			
SOFFIT:	3.0 sq in of vent per ft		
RIDGE:	1.8 sq in of vent per ft		
BOX / GABLE VENT:	45 sq in of vent per unit		

USER GUIDE

(any)	(any)	VENT OK	No action req'd.
(any)	(any)	VENT OK	No action req'd.
(any)	(any)	FAIL	Increase ridge
(any)	(any)	FAIL	Decrease ridge
(any)	(any)	FAIL	Increase total vent

ELEVATION "K" OR "L"													
Location / Options	Area (A) (sq in)	Required: A/150 (sq in)	Required: A/300 (sq in)	Soffit (sq)	Soffit Vent (sq in)	Ridge (sq)	Ridge Vent (sq in)	Upper Box / Gable Vent (sq in)	Lower Box Vent (sq in)	TOTAL (sq in)	OK A/150	OK A/300	A/300 40%-50% OK?
MAIN - NO REAR PORCH	311043	2079.62	1039.81	150	1387.50	25	450.00			3732.00	YES	YES	43.05%
MAIN - W/ REAR PORCH	311203	2238.02	1119.01	150	1485.00	25	468.00			3953.00	YES	YES	42.39%
		0.00	0.00		0.00		0.00			0.00	NO	NO	
		0.00	0.00		0.00		0.00			0.00	NO	NO	
		0.00	0.00		0.00		0.00			0.00	NO	NO	
		0.00	0.00		0.00		0.00			0.00	NO	NO	

CUSTOM ELEVATION													
Location / Options	Area (A) (sq in)	Required: A/150 (sq in)	Required: A/300 (sq in)	Soffit (sq)	Soffit Vent (sq in)	Ridge (sq)	Ridge Vent (sq in)	Upper Box / Gable Vent (sq in)	Lower Box Vent (sq in)	TOTAL (sq in)	OK A/150	OK A/300	A/300 40%-50% OK?
MAIN - NO REAR PORCH	311043	2079.62	1039.81	142	1405.80	25	450.00			3655.40	YES	YES	43.40%
MAIN - W/ REAR PORCH	311203	2238.02	1119.01	142	1463.80	25	468.00			3913.80	YES	YES	42.39%
		0.00	0.00		0.00		0.00			0.00	NO	NO	
		0.00	0.00		0.00		0.00			0.00	NO	NO	
		0.00	0.00		0.00		0.00			0.00	NO	NO	
		0.00	0.00		0.00		0.00			0.00	NO	NO	



HOUSE VOLUME CALCULATIONS

HOUSE NAME DOMINICA SPRING
HOUSE VERSION DSPO0 / 01
PRODUCT LINE RYANHOMES

Note: The volume of the structure has been computed in accordance with "Title 5. of the Community Affairs, Chapter 23. Uniform Construction Code, Subchapter 2. Administration and enforcement: Process." (5.23-2.28. Volume computation)

ELEVATION "K", "L"			
Location / Area of house	Floor Area (sq. ft.)	Mean height (ft.)	Total volume (cu. Ft.)
Main section of the house	1680.00	13.27	22295
Gable at front of the house	56.00	9.82	550
Garage bump out from main house	400.00	10.55	4219
Porch on front of house	24.00	8.66	208
		Total House Volume	27064

Additional areas of volume to be added to total house volume as needed			
Location / Area of house / option	Floor Area (sq. ft.)	Mean height (ft.)	Total volume (cu. Ft.)
Covered Porch "EPE"	140.00	10.02	1403
Full Basement "FBA"	1744.67	8.63	15048
Crawl space "FCA"	1744.67	0.80	1396


As directed by the North Carolina Board of Architecture and Registered Interior Designers, architectural seals are not required for these plans and should not be placed by NVR on these plans and specifications.

DIV - COMM - LOT - UNIT
COMM - LOT
STREET ADDRESS
CITY
STATE
ZIP




The owner, expressly reserves its right to make changes in these plans. These plans are not to be reproduced, changed, or altered in any way without the express written consent of NVR, Inc.

NVR logo
NVR, Inc.
5285 Westview Drive, Suite 100
Frederick, MD 21702

SHEET NO. 2
MODEL DOMINICA SPRING
DRAWING TITLE ROOF VENT AND VOLUME CALCULATIONS
VOLUME CALCULATIONS
OPTION DESCRIPTION
SET NO. DSPO0
VERSION 01
RELEASE NO. ----
DRAWN BY
DATE
OPTION



1 FRONT ELEVATION "K"
A-1 SCALE: 1/4" = 1'-0"



As directed by the North Carolina Board of Architecture and Registered Interior Designers, architectural seals are not required for – and should not be placed by NVR on – these plans and specifications.

DIV-COMM-LOT-UNIT	---
COMM-LOT	---
STREET ADDRESS	---
CITY	---
STATE	---
ZIP	---

NVR, Inc., expressly reserves its copyright and other property rights in these plans. These plans are not to be reproduced, copied, or otherwise used in any form or manner whatsoever, nor are they to be used for any purpose other than that first obtaining the express written consent of NVR, Inc.



SHEET NO.	MODEL	SET NO.	VERSION	RELEASE NO.	DRAWN BY	DATE	OPTION	DESCRIPTION
NC-1	DOMINICA SPRING	01	01	----	SKED	03/14/2025	FSM	SLAB FOUNDATION MONOLITHIC POUR
4								

PAD FOOTING SCHEDULE					
IDENTIFIER	LENGTH	WIDTH	HEIGHT	OPTIONS	ENS. NUM.
FOOT	2'-0"	2'-0"	1'-0"		50001
FOOB	2'-0"	2'-0"	1'-0"		50001


FOUNDATION DIAGONALS			
A		B	
A	0"	A	43'-1"
B	43'-1"	B	0"
C	25'-7 3/8"	C	20'-0"
D	14'-0"	D	30'-6 3/8"
E	46'-0"	E	73'-1 3/8"
F	60'-11 1/2"	F	62'-0"

FOUNDATION NOTES - SLAB

- SEE STANDARD DETAIL CATEGORY "FD" SHEET(S).
- CONCRETE SLAB ON VAPOR BARRIER OVER SUB-BASE (SEE SPEC SHEET FOR SLAB NOTES).
- FOUNDATION UNDER GARAGE:
 - UNEXCAVATED WITH CONCRETE SLAB OVER SUB-BASE (SEE SPEC SHEET FOR SLAB NOTES) OR
 - STRUCTURAL CONCRETE SLAB OVER SUB-BASE (SEE SPEC SHEET FOR SLAB NOTES).
- SEE FOUNDATION HOLD DOWN SHEET FOR CONNECTION INFORMATION.
- SLAB LEDGE LOCATIONS VARY W/ GRADE BEAM(S) ORIENTATION. SEE GB-1 FOR DETAILS.
- THE DIRECTION OF THE ARROW IS THE DIRECTION OF REBAR, AS REQUIRED.
- ALL FOOTINGS ARE PLAIN, NON-REINFORCED CONCRETE UNLESS NOTES OTHERWISE.
- SEE WG- DETAILS FOR FOOTER SLEEVE INFORMATION.
- THICKEND SLAB DEPTHS MEASURE 4" BELOW TOP OF SLAB. PAD FOOTING DEPTHS MEASURE 4" BELOW TOP OF SLAB.

LEGEND


- BEARING WALL
- NON BEARING WALL
- MASONRY WALL
- INDICATES BEARING FROM POINT-LOAD ABOVE
- JACKS
- BEAM/HEADER
- FOOTING/THICKEND SLAB
- STEEL COLUMN
- TRUSS TIE DOWN
- PORTAL FRAME
- JOIST/TRUSS
- LVL
- ENGINEERING PAGE NUMBER
- WINDOW/DOOR TAG
- PRECAST LINTEL TAG
- SEE FA DETAILS FOR FIRE ASSEMBLIES
- SEE FC DETAILS FOR FRAMING CONNECTORS AND MATERIAL USAGE




1 FOUNDATION PLAN
SCALE: 1/4" = 1'-0"

As directed by the North Carolina Board of Architecture and Registered Interior Designers, architectural seals are not required for – and should not be placed by NVR on – these plans and specifications.

DIV - COMM - LOT - UNIT		COMM - LOT		STREET ADDRESS		CITY		STATE		ZIP	
---		---		---		---		---		---	



NVR, Inc. expressly reserves its copyright and other property rights in these plans. These plans are not to be reproduced, stored in a retrieval system, or copied in any form or manner whatsoever, nor are they to be used for any purpose other than that first obtaining the expressed written consent of NVR, Inc.



SET NO. D5FOO	VERSION 01	RELEASE NO. ---	DRAWN BY SGA	DATE: ---	OPTION FSA
---------------	------------	-----------------	--------------	-----------	------------

SHEET NO. NC-2	MODEL DOMINICA SPRING FOUNDATION	DRAWING TITLE FOUNDATION	OPTION DESCRIPTION SLAB FOUNDATION	7



Architectural floor plan showing the layout of a building. The plan includes a **COVERED PORCH** at the top right, a large **SLAB FOUNDATION** area in the center, and a **TWO CAR GARAGE** at the bottom left. The garage area is shaded with diagonal lines. A central circular feature is labeled **NH**.

Dimensions are provided for various areas:

- Top left corner: $4'-0\frac{5}{16}"$ and $4'-5\frac{1}{2}"$.
- Bottom left corner: $18'-1\frac{1}{2}"$, $18'-4\frac{5}{16}"$, $19'-4\frac{1}{16}"$, and $19'-7\frac{1}{2}"$.
- Bottom right corner: $11'-6"$, $13'-4\frac{1}{2}"$, $2'-6"$, and $7\frac{1}{2}"$.
- Right side: $4\frac{1}{2}"$, $7\frac{5}{16}"$, $1'-7\frac{11}{16}"$, and $1'-0\frac{1}{2}"$.

1
NC-3

FOUNDATION HOLD DOWN DETAIL

SCALE: 1/4" = 1'-0"

As directed by the North Carolina Board of Architecture and Registered Interior Designers, architectural seals are not required for – and should not be placed by NVR on – these plans and specifications.


DIV-COMM-LOT-UNIT		-----	
COMM-LOT		-----	
STREET ADDRESS		APT. NO.	
-----		-----	
CITY	STATE	ZIP	
-----	-----	-----	

03/14/2025

NORTH CAROLINA
PROFESSIONAL
SEAL
44932
ENGINEER
JONATHAN EDWARD ABERTS

NVR, Inc.
Firm license #: D-04

© NVR, Inc., expressly reserves its copyright and other property rights in these plans. These plans are not to be reproduced, changed, or copied in any form or manner whatsoever, nor are they to be assigned to any third party, without first obtaining the expressed written consent of NVR, Inc.



SHEET NO.	NC-3	MODEL DOMINICA SPRING DRAWING TITLE FOUNDATION HOLD DOWN	SET NO. D5600 VERSION 01 RELEASE NO. ---- DRAWN BY CEL DATE:
		OPTION DESCRIPTION	OPTION
	9		

**RADON REMEDIATION
RADON LOOP:**

- (4") PERFORATED HDPE "LOOP"
- MUST BE PLACED IN STONE BED SLIGHTLY HIGHER THAN ANY INTERIOR DRAINTILE
- LOOP TO BE SEPARATE FROM ANY DRAINTILE ELEMENTS
- TO BE CORRUGATED HDPE PIPE
- SCREWS TO BE INSTALLED THROUGH LOOP AT TEE UP INTO STACK

STACK REQUIREMENTS:

- 3" PVC STACK (4") IF BASEMENT IS GREATER THAN 2200 SQFT.)
- NO PART OF STACK IS TO BE HORIZONTAL (45° ELBOWS PERMITTED AS REQUIRED)
- PIPE TO BE PHYSICALLY LABELED IN THE FIELD AS "RADON VENT" OR OTHER
JURISDICTIONALLY REQUIRED LANGUAGE (ON EVERY LEVEL OF HOUSE)
- ROOF TERMINATION TO BE IN TOP 1/3 OF ROOF
- SCREEN OR VENT CAP INSTALLED TO KEEP PESTS OUT OF RADON VENT AT ROOF TERMINATION.

DIVISION

SLAB FOUNDATION

TWO CAR GARAGE

TEE UP FOR WATER SLEEVE HOLD TIGHT TO FTG.

SHOWER DRAIN

HOLD TIGHT TO FOOTING

WASHER

TANKED WATER HEATER

CONDENSATE LINE

TUB DRAIN

SINK

CONDENSATE LINE

TEE UP FOR WATER SLEEVE

END CAP

PVC CONDUIT FOR ELECTRICAL AT KITCHEN ISLAND (TEE UP THROUGH SLAB AT EACH END)

TEE UP FOR WATER SLEEVE HOLD TIGHT TO FTG.

Dimensions and Notes:

- 12'-1"
- 14'-0 1/2"
- 15'-2 1/2"
- 19'-4"
- 21'-2 1/2"
- 30'-6"
- 11'-7"
- 20'-5 1/2"
- 20'-7 1/2"
- 21'-10"
- 14'-11 1/2"
- 14'-0"
- 26'-6 5/8"
- 24'-10 3/4"
- 26'-0"
- 24'-9"
- 32'-6"
- 30'-6"
- 24'-0 3/4"
- 17'-6"
- 16'-8"
- 15'-8"
- 1'-6"
- 6'-9"
- 6'-7"
- 18'-6 1/2"

PLUMBING PLAN

s directed by the North Carolina Board of Architecture and Registered Interior Designers, architectural plans are not required for – and should not be replaced by NVR on – these plans and specifications.

		COMM-LOT	
		STREET ADDRESS	
		APT. NO.	
CITY		STATE	ZIP

the owner, expressly reserves its copyright and other property rights in these plans. These plans are not to be reproduced, changed, or copied in any form or manner whatsoever, nor are they to be assigned to any third party, without first obtaining the expressed written consent of NVR, Inc.

NVR
NVR, Inc.
5285 Westview Drive, Suite 100
Redwood City, CA 94063
James Bales
03/14/2025

NC-4	DRAWING TITLE PLUMBING	DOMINICA SPRING	VERSION 01
	OPTION DESCRIPTION		RELEASE NO. ----- DRAWN BY SGA DATE: OPTION
10			

V:\As-Sold\2-Jobs\ASD\2025 1stHalf-Complete\RLH\DETACHED\DOMINICA SPRING_DSP00_01\ELK_R_VK_0015\10 NC-4 PLMG_LS.dwg 03/14/25 - 7:22 am

FIRST FLOOR JACK SCHEDULE				
IDENTIFIER	DESCRIPTION	OPTIONS	ENG. NUM.	REMARKS
J101	JACK - (2) 2X4 SPF STUD GRADE		1004	
J102	JACK - (2) 2X4 SPF STUD GRADE		1004	
J103	JACK - (2) 2X4 SPF STUD GRADE		1006	
J104	JACK - (2) 2X4 SPF STUD GRADE		1006	
J105	JACK - (3) 2X4 SPF STUD GRADE		1008	
J106	JACK - (3) 2X4 SPF STUD GRADE		1008	
J107	JACK - (2) 2X4 SPF STUD GRADE		1010	
J108	JACK - (2) 2X4 SPF STUD GRADE		1010	

FLOOR PLAN NOTES:

- ALL HEADERS ARE (2) 2x6 w/ 2x4 WALLS OR (3) 2x6 w/ 2x6 WALLS, UNLESS OTHERWISE NOTED.
- ALL HEADERS TO HAVE (1) 2x4 OR 2x6 JACK AND KING STUD EACH END, UNLESS OTHERWISE NOTED. MULTI-OPENING HEADERS TO HAVE (2) JACKS AT INTERMEDIATE BEARING, UNLESS OTHERWISE NOTED. NO ADDITIONAL FLOOR SYSTEM BLOCKING OR CONTINUOUS LOAD PATH JACKS ARE REQUIRED UNLESS OTHERWISE NOTED.
- ALL EXTERIOR WALLS TO BE 4" OR 6" AND ALL INTERIOR WALLS TO BE 3 1/2", UNLESS OTHERWISE NOTED. HATCHED AREAS INDICATE DROPPED CEILINGS. ALL DROPPED CEILINGS ARE 12" UNLESS OTHERWISE NOTED. SEE ARCHITECTURAL DETAIL 8/11-B FOR 3/4" FIRE STOPPING AT BULKHEAD / CEILING PANELS.
- SEE "BRACED WALL PANEL DETAIL SHEET" FOR SPECIAL WALL FRAMING LOCATIONS AND HEADER SIZES, IF APPLICABLE.
- SEE STANDARD DETAIL CATEGORY "11" SHEET(S) FOR INTERIOR TRIM DETAILS.
- SEE DETAIL SHEET "AD" FOR HOUSE SPECIFIC INTERIOR TRIM OPTION TABLE.
- ALL HEADERS IN NON-BEARING WALLS SHALL BE A SINGLE FLAT 2X4 OR 2X6 ATTACHED TO CRIPPLES ABOVE, UNLESS OTHERWISE NOTED.
- TANKED WATER HEATER SHOWN AS BASE CONDITION. OPTIONAL TANKLESS WATER HEATER IS AVAILABLE IN LIEU OF TANKED WATER HEATER.
- INTERIOR HEADER HEIGHT FOR 8' CEILING WILL BE 6'-11", 9' CEILING WILL BE 7'-11", 10' CEILING WILL BE 8'-3", UNLESS OTHERWISE NOTED.
- BASEMENT FINISH DIMENSIONS ASSUME A 1/2" GAP BETWEEN FRAME WALL AND CONCRETE WALL.
- ALL INTERIOR BEARING WALLS SHALL HAVE GYPSUM APPLIED TO AT LEAST ONE SIDE OR HAVE MID-HEIGHT BLOCKING INSTALLED.
- NON-BEARING WALLS OVER CONCRETE TO BE HELD 1/2" SHORT OF FRAMING ABOVE.

GYPSUM NOTES:

AT GARAGE:

GYPSUM BOARD AT COMMON WALLS, CEILINGS, BEAM WRAPS AND SUPPORTS PER STANDARD DETAIL FA-1(2) FIRE ASSEMBLIES OR AS REQUIRED BY LOCAL CODE.


AT STAIRS:

1/2" GYPSUM BOARD AT UNDERSIDE OF STAIRS AND WALLS IN CLOSET

LEGEND

- BEARING WALL
- NON BEARING WALL
- MASONRY WALL
- INDICATES BEARING FROM POINT-LOAD ABOVE
- JACKS
- BEAM/HEADER
- FOOTING/THICKENED SLAB
- STEEL COLUMN
- TRUSS TIE DOWN
- PORTAL FRAME
- JOIST/TRUSS
- LVL
- ENGINEERING PAGE NUMBER
- WINDOW/DOOR TAG
- PRECAST LINTEL TAG
- SEE FA DETAILS FOR FIRE ASSEMBLIES
- SEE FC DETAILS FOR FRAMING CONNECTORS AND MATERIAL USAGE

ALL WINDOWS HAVE 7'-0 1/2" HEADER HEIGHT UNLESS OTHERWISE NOTED



FIRST FLOOR PLAN
SCALE: 1/4" = 1'-0"

As directed by the North Carolina Board of Architecture and Registered Interior Designers, architectural seals are not required for – and should not be placed by NVR on – these plans and specifications.

DIV-COMM-LOT-UNIT	COM-LOT	STREET ADDRESS	CITY	STATE	ZIP
---	---	---	---	---	---

03/14/2025

NORTH CAROLINA PROFESSIONAL SEAL 44932

DOMINICA EDWARD ABERTS

ENGINEER

NVR, Inc. License # D-0477


© NVR, Inc., expressly reserves its copyright and other property rights in these plans. These plans are not to be reproduced, stored in a retrieval system, or copied in any form or manner whatsoever, nor are they to be used for any project without the express written consent of NVR, Inc.

NVR

NVR, Inc., Suite 100
5285 Westwick
Frederick, MD 21703

SET NO. D5F00	VERSION 01	RELEASE NO. ---	DRAWN BY SKB
DRAWING TITLE		DATE:	OPTION
DOMINICA SPRING			
FIRST FLOOR PLAN			

SHEET NO.	NC-6	12
MODEL	DOMINICA SPRING	
DRAWING TITLE	FIRST FLOOR PLAN	
OPTION DESCRIPTION		



BUILDING SECTION - FOYER
SCALE: 1/4" = 1'-0"

As directed by the North Carolina Board of Architecture and Registered Interior Designers, architectural seals are not required for – and should not be placed by NVR on – these plans and specifications.


DIV-COMM-LOT-UNIT		-----	
COMM-LOT		-----	
STREET ADDRESS		APT. NO. -----	
CITY		STATE	ZIP
-----		-----	-----

© NVR, Inc., expressly reserves its copyright and other property rights in these plans. These plans are not to be reproduced, stored in a retrieval system, or copied in any form or manner whatsoever, nor are they to be used for any purpose without the first obtaining the expressed written consent of NVR, Inc.

NVR
NVR, Inc.
5285 Westview Drive
Raleigh, NC 27617
James Gales
03/14/2025

SHEET NO. NC-7	MODEL	SET NO. D5P00
	DOMINICA SPRING	VERSION 01
	DRAWING TITLE	RELEASE NO. ----
	BUILDING SECTION	DRAWN BY SKD
13	OPTION DESCRIPTION	DATE: _____
		OPTION _____

VA-As-Sold-2-Jobs\ASD\2025 1stHalf-Complete RH DETACHED DOMINICA SPRING_DSP00_01.EIK R_VK_001513 NC-7 SECT_FOYER_LS.dwg 03/14/25 - 7:22 am




BUILDING SECTION - GARAGE
SCALE: 1/4" = 1'-0"


As directed by the North Carolina Board of Architecture and Registered Interior Designers, architectural seals are not required for – and should not be placed by NVR on – these plans and specifications.

DIV-COMM-LOT-UNIT	
COMM-LOT	-----
STREET ADDRESS	
CITY	STATE
ZIP	APT. NO.

©NVR, Inc., expressly reserves its copyright and other property rights in these plans. These plans are not to be reproduced, stored in a retrieval system, or copied in any form or manner whatsoever, nor are they to be used for any purpose without the first obtaining the expressed written consent of NVR, Inc.





SHEET NO. NC-8	MODEL	SET NO. D5F00
	DOMINICA SPRING	VERSION 01
	DRAWING TITLE	RELEASE NO. ----
	BUILDING SECTION	DRAWN BY SKED
	OPTION DESCRIPTION	DATE:
14		OPTION



FIELD INSTALLED ROOF FRAMING BEAM/HEADER SCHEDULE				
IDENTIFIER	DESCRIPTION	LENGTH	ENG. NUM.	REMARKS
B101	BEAM BUILT 2XB - 2 PLY RFF	6'-0"	1006	
L201-2	LVL 1.75 - 04-04	10'-0"	1008	A.1


1. REFER TO THE STANDARD DETAILS FOR THE FOLLOWING:
 - 1.1. TRUSS TIE STAND (2/RF-I)
 - 1.2. PIGGYBACK TRUSS ATTACHMENT (2/RF-I)
 - 1.3. VALLEY GABLE TRUSS BRACING (3/RF-I)
 - 1.4. GABLE BRACING (1/RF-Ic)
 - 1.5. TURN GABLE BRACING (1/RF-I)
 - 1.6. TRUSS LATERAL BRACING (2/RF-Ic)
 - 1.7. LIFELINE ATTACHMENT (5/RF-I)
 - 1.8. FALL PROTECTION ON PLATFORM TRUSS (11/RF-I)
2. IF TRUSS DOES NOT APPEAR ON THE TRUSS BRACING SHEET, THE ADDITIONAL LATERAL BRACING REQUIRED:
 - ALL FINISHED ROOF OVERHANGS ARE TO BE 12" FROM FRAMED WALL UNLESS OTHERWISE NOTED.



3
S-2

PORCH ROOF FRAMING PLAN

SCALE: 1/4" = 1'-0"




2 PORCH BEAM FRAMING PLAN

S-2 SCALE: 1/4" = 1'-0"

1
S-2

ROOF FRAMING

SCALE: 1/4" = 1'-0"




1
S-3
TRUSS BRACING DETAILS
SCALE: 1/8" = 1'-0"

ROOF FRAMING NOTES:


- REFER TO THE STANDARD DETAILS FOR THE FOLLOWING:
 - TRUSS TIE-DOWNS (1/RF-1)
 - PIGGYBACK TRUSS ATTACHMENT (2/RF-1)
 - VALLEY GABLE TRUSS BRACING (3/RF-1)
 - GABLE BRACING (1/RF-1G)
 - TURN GABLE BRACING (1/RF-1)
 - TRUSS LATERAL BRACING (2/RF-1G)
 - LIFELINE ATTACHMENT (5/RF-1)
 - FALL PROTECTION ON PLATFORM TRUSS (1/RF-1)
- IF TRUSS DOES NOT APPEAR ON THE TRUSS BRACING SHEET, NO ADDITIONAL LATERAL BRACING REQUIRED
- ALL FINISHED ROOF OVERHANGS ARE TO BE 12" FROM FRAMED WALL UNLESS OTHERWISE NOTED.

As directed by the North Carolina Board of Architecture and Registered Interior Designers, architectural seals are not required for – and should not be placed by NVR on – these plans and specifications.

DIV-COMM-LOT-UNIT -----	
COMM-LOT -----	
STREET ADDRESS -----	
CITY -----	STATE -----
APT. NO. -----	
ZIP -----	




© NVR, Inc., expressly reserves its copyright and other property rights in these plans. These plans are not to be reproduced, stored in a retrieval system, or transmitted in any form or manner whatsoever, nor are they to be used for any purpose other than that first obtaining the expressed written consent of NVR, Inc.



SHEET NO. S-3	MODEL DOMINICA SPRING	SET NO. DSP00 VERSION 01 RELEASE NO. ---- DRAWN BY SGA DATE: OPTION
22	DRAWING TITLE TRUSS BRACING DETAILS OPTION DESCRIPTION	

BRACED WALL LINE SCHEDULE				
WIND SPEED (ULT)	IDENTIFIER	REQUIRED (FT)	ACTUAL (FT)	METHOD
130 MPH	BWL 100.00	8.60'	9.00'	CONTINUOUS (WITH GNB)
130 MPH	BWL 101.00	8.72	40.00'	WSP (WITH GNB)
130 MPH	BWL 102.00	12.54'	16.75'	CONTINUOUS (WITH GNB)
130 MPH	BWL 103.00	8.90'	54.06'	WSP (WITH GNB)
130 MPH	BWL 104.00			ENGINEERED
130 MPH	BWL 105.00	4.71'	17.00'	WSP (WITH GNB)


BRACING LEGEND		FASTENING SCHEDULE			
BWL XXX.XX	BRACED WALL LINE I.D.	SHEATHING	FASTENER	SPACING	
				EDGES	FIELD
---	BRACED WALL LINE	PRESCRIPTIVE 7/16" WOOD STRUCTURAL PANELS OR EQUIVALENT (W/ METHOD WSP, CS-WSP, CS-G)	8d COMMON NAILS	6" O.C.	6" O.C.
---	HOUSE WALL		ALTERNATIVE FASTENER 1-3/4" 16-GAUGE CORROSION RESISTANT STAPLES	3" O.C.	6" O.C.
////	BRACED WALL PANEL	ENGINEERED 7/16" WOOD STRUCTURAL PANELS (W/ METHOD ENG-WSP-A, ENG-WSP-B, ENG-WSP-C)	A - 8d COMMON NAILS	4" O.C.	6" O.C.
(X)	ENGINEERING PAGE NUMBER		A - 1-3/4" 16-GAUGE CORROSION RESISTANT STAPLES	3" O.C.	6" O.C.
WSP	WOOD STRUCTURAL PANEL		B - 8d COMMON NAILS*	3" O.C.	6" O.C.
GB	GYPSUM BOARD (1) SIDED OR (2) SIDED		B - 1-3/4" 16-GAUGE CORROSION RESISTANT STAPLES	N/A	6" O.C.
GB-BW	GYPSUM BOARD BLOCKED WALL CONSTRUCTION (1) SIDED OR (2) SIDED (SEE STANDARD DETAIL 6 /WB-2)		C - 8d COMMON NAILS*	3" O.C.	6" O.C.
LIB	LET-IN BRACING (SEE STANDARD DETAIL F /WB-2)		C - 1-3/4" 16-GAUGE CORROSION RESISTANT STAPLES	N/A	6" O.C.
CS-WSP	CONTINUOUS SHEATHING - WOOD STRUCTURAL PANEL	1/2" GYPSUM WALLBOARD (W/ METHOD GB-I, GB-2, ENG-GBI-A)	1-1/4" LONG, 1/4" HEAD, .048" DIA. ANNULAR-RINGED NAILS	7" O.C.	7" O.C.
CS-PF	CONTINUOUS SHEATHING - PORTAL FRAME, SEE FLOOR PLANS FOR PORTAL FRAME HEADER INFORMATION (SEE STANDARD DETAIL A, C/ WB-2)		CORROSION RESISTANT TYPE W 1-1/4" DRYWALL SCREWS	7" O.C.	7" O.C.
CS-G	CONTINUOUS SHEATHING - WOOD STRUCTURAL PANEL ADJACENT TO GARAGE OPENINGS	1/2" GYPSUM WALL BOARD BLOCKED AT THE EDGES (W/ METHOD GB-BW-1, GB-BW-2, ENG-BW)	BLOCKING REQUIRED AT ALL GYPSUM EDGES. USE CORROSION RESISTANT TYPE W 1-1/4" DRYWALL SCREWS	4" O.C.	12" O.C.
ENG-WSP-A	ENGINEERED DESIGN W/ WALL STRUCTURAL PANEL SHEATHING TYPE 'A' FASTENING REQUIREMENTS (NO HOLD DOWNS REQUIRED UNLESS NOTED)				
ENG-WSP-B	ENGINEERED DESIGN W/ WALL STRUCTURAL PANEL SHEATHING TYPE 'B' FASTENING REQUIREMENTS (NO HOLD DOWNS REQUIRED UNLESS NOTED)				
ENG-WSP-C	ENGINEERED DESIGN W/ WALL STRUCTURAL PANEL SHEATHING ON BOTH SIDES OF THE WALL TYPE 'C' FASTENING REQUIREMENTS (NO HOLD DOWNS REQUIRED UNLESS NOTED)				
ENG-PF	ENGINEERED DESIGN W/ PORTAL FRAME, SEE FLOOR PLANS FOR PORTAL FRAME HEADER INFORMATION (SEE STANDARD DETAIL PAGE WB-1)				
ENG-GBI-A	ENGINEERED DESIGN W/ (1) SIDED GYPSUM BOARD TYPE 'A' FASTENING REQUIREMENTS				
ENG-GBI-B	ENGINEERED DESIGN W/ (1) SIDED GYPSUM BOARD TYPE 'B' FASTENING REQUIREMENTS				
ENG-BW	ENGINEERED DESIGN W/ (1) SIDED GYPSUM BOARD W/ BLOCK WALL CONSTRUCTION (SEE STANDARD DETAIL IT/WB-1)				
HO	HOLD-DOWN: 1. SEE SHEET WB-2 FOR "P." INDICATOR SCHEDULE AND DETAILS 2. SEE SHEET WB-1 FOR "H." INDICATOR SCHEDULE AND DETAILS 3. ARROW INDICATES LOCATION.				
NOTES: HOUSE HAS BEEN ANALYZED UTILIZING A PRESCRIPTIVE METHOD IN COMPLIANCE WITH INTERNATIONAL RESIDENTIAL CODES (IRC) UNLESS OTHERWISE NOTED. ENGINEERED WALL LINES ARE IN COMPLIANCE WITH INTERNATIONAL BUILDING CODES (IBC).		NOTES: 1. MINIMUM 7/16" CROWN WIDTH FOR STAPLES IN WOOD STRUCTURAL PANEL. 2. SPECIFIED GYPSUM FASTENING REQUIRED ONLY WHERE METHOD GB IS IDENTIFIED. SEE PHASE SPECS FOR TYPICAL GYPSUM FASTENER SPACING. 3. USE OF STAPLES IN WOOD STRUCTURAL PANEL AS FASTENING METHOD ON WALLS PER ENGINEERED ALTERNATIVE. 4. STAPLE ALTERNATIVE FOR USE IN FIELD ONLY. WALL PANELS NOT IDENTIFIED AS BRACED WALL PANELS SHALL BE FASTENED IN ACCORDANCE WITH THE WSP/ENG-WSP-A METHOD.			




1
S-4 FIRST FLOOR WALL BRACING DETAIL
SCALE: 1/4" = 1'-0"

As directed by the North Carolina Board of Architecture and Registered Interior Designers, architectural seals are not required for – and should not be placed by NVR on – these plans and specifications.

DIV-COMM-LOT-UNIT	COMM-LOT	STREET ADDRESS	CITY	STATE	ZIP
----	----	----	----	----	----






© NVR, Inc., expressly reserves its copyright and other property rights in these plans. These plans are not to be reproduced, stored in a retrieval system, or transmitted in any form or manner whatsoever, nor are they to be used for any purpose other than the first obtaining the express written consent of NVR, Inc.





SET NO. D5F00	VERSION 01	RELEASE NO. ----	DRAWN BY BRK	DATE: ----	OPTION
---------------	------------	------------------	--------------	------------	--------

MODEL DOMINICA SPRING	DRAWING TITLE FIRST FLOOR BRACED WALL	OPTION DESCRIPTION
--------------------------	--	--------------------






**PORTAL FRAME:
SHEATHING
APPLICATION DETAIL**




ALTERNATE PORTAL
FRAME: SHEATHING
APPLICATION DETAIL



SCALE 3/8" = 1'-0"

SCALE 3/8" = 1'-0"

B-2 SCALE: 3/4" = 1'-0"



ALTERNATE EXTERIOR WALL BRACING PANEL W/ CANTILEVER ALTERNATIVE

NOTE: STD EMBEDDED HOL D DOWN FOR USE WITH POURED FOUNDATION WALLS ONLY

OPT. INTERIOR SHEATHING FOR STRAP ALIGNMENT

STRUCTURAL SHEATHING

2x STUD WALL

(2) 2x STUDS MIN. FOR ATTACHMENT

MIN. 2x4 P.T. BOTTOM PLATE

EQ.

FASTEN BOTTOM PLATE TO FOUNDATION WALL WITH 1/2" x 3" SIMPSON TITEN HD ANCHOR BOLT (MIN. (2) BOLTS PER PORTAL FRAME LEG)

ALTERNATE

1/2" x 3" SIMPSON TITEN HD ANCHOR BOLT OR EQUIVALENT

1" MINIMUM EMBEDMENT

FOUNDATION WALL

WALL LENGTH VARIES PER HOUSE DESIGN

(2) 2x STUDS MIN. FOR ATTACHMENT

MIN. 670 LB. FRAMING ANCHORS (LTM4 TYP. - ANY ORIENTATION PERMITTED). INSTALL (2) PER PANEL AS SHOWN

NAIL SILL PLATE TO JOIST PER IRC TABLE R602.3(1)

FLOOR FRAMING

MUDSILL

FOUNDATION WALL (CONCRETE OR

A cross-sectional diagram of a wall assembly. At the bottom is a stippled area representing the foundation wall, labeled 'FOUNDATION WALL (CONCRETE OR BLOCK)'. Above this is a horizontal line representing the 'MUDSILL'. Above the mudsill is a horizontal line representing the 'FLOOR FRAMING'. Above the floor framing is a vertical line representing the 'LSTA15' insulation. The diagram shows the wall assembly from the foundation up to the floor framing.

(2) 2x... STUDS MIN. FOR ATTACHMENT

ALTERNATE: STRIP/4 EMBEDDED HOLDDOWN.

FASTEN WITH (3) 1/4" SINKERS

HTTA SIMPSON STRONG-TIE HOLD DOWN w/ 5/8" Ø ALL-THREAD RODS & SIMPSON ACRYLIC- TIE ADHESIVE.

MINIMUM EMBEDMENT:

PRE-POURED - 7"

POST-POURED - 12"

ALTERNATE:















1/2" X 6" SIMPSON TITEN HD ANCHOR BOLT OR EQUIVALENT

#4 REBAR REQUIRED WITH STRAP

INSTALL 3'-5" BELOW TOP OF SLAB OR COLD JOINT

RETURN REBAR AT CORNERS OF THE HOUSE

FOUNDATION WALL (CONCRETE OR

ID	BOTTOM CONNECTOR	QTY.	DETAIL	TOP CONNECTOR	QTY.	DETAIL
P1	3"x3"x1/4" PLATE WASHER 1/2" THREADED ROD	1		NONE	N/A	N/A
P2	3"x3"x1/4" PLATE WASHER 1/2" THREADED ROD	1		LSTA24	1	
P3	3"x3"x1/4" PLATE WASHER 1/2" THREADED ROD	1		MST48	1	
P4	LTP4	1		NONE	N/A	N/A
P5	LTP4	1		LSTA24	1	
P6	LTP4	1		MST48	1	
P7	LSTA15	1		NONE	N/A	N/A
P8	HTT4 5/8" A24 THR. ROD	1		NONE	N/A	N/A
P9	NONE	N/A	N/A	LSTA24	1	
P10	NONE	N/A	N/A	MST48	1	

NOTES: THREADED ROD PART INCLUDES (2) NUTS AND (2) WASHERS

CONTINUOUSLY SHEATHED
PORTAL: TYP. HEADER /
PANEL CONNECTION

ALTERNATE PORTAL FRAME:
HEADER / PANEL CONNECTION

HOLD-DOWN DETAIL: FOUNDATION

HOLD-DOWN DETAIL: FRAMED FLOOR


**HOLD-DOWN DETAIL:
FRAMED FLOOR**

HOLD-DOWN DETAIL:
FOUNDATION

As directed by the North Carolina Board of Architecture and Registered Interior Designers, architectural seals are not required for – and should not be placed by NVR on – these plans and specifications.

REV.	NO.	DATE	REMARKS
37		1/11/24	ARS - GC40503 DETAIL B REVISED S/WAVE SIZE FROM 1 1/4" TO 3/4"
38		1/23/24	DLR - GC40764 - REVISED DETAIL E/W-B-2 CORNER DETAIL
39		4/24/20	CEL - GC46694 - PLATE WASHERS CHANGED TO 3"x3" WITH 1/2" THREADED ROD
30		10/5/20	CEL - REVISED HWB-2 TO INCLUDE FLOOR TRUSSES
32		10/13/20	CEL - ADDED NOTES DETAILING WHEN TO USE K/WB-2
33		4/7/21	ARS - REV. DTL C PONT WALL NOTES
34		6/3/21	CEL - GC41929 - REVISED HWB-2 TO REMOVE USE OF FLAT BLOCKING
35		12/13/22	DLR - GC40426 - REVISED PERP. WALL BRACING DTL AND ALT. FISHING TO HWB-2
36		4/11/23	DLR - GC46628 - REVISED CONNECTOR CHART, REMOVED PART NUMBERS

03/14/2025



© NVR, Inc.
The owner, expressly reserves its copyright and other property rights in these plans. These plans are not to be reproduced, changed, or copied in any form or manner whatsoever, nor are they to be assigned to any third party, without first obtaining the expressed written consent of NVR, Inc.



SET NO.	
VERSION	
DRAWN BY	ELH
DATE:	4/8/14
OPTION	

SHEET NO.	MODEL	WALL BRACING DETAILS
WB-2	DRAWING TITLE	PREScriptive WALL BRACING DESIGN
	OPTION DESCRIPTION	