

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC. ~~X~~ Can change D-Box
PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: Elyse Meadow

INITIAL SYSTEM: ^{Pump} APPROVED 25% REDUCTION

DISTRIBUTION: D-Box

BENCHMARK: 100.0

NO. BEDROOMS: 4

LOT 4

REPAIR ^{Pump} Approved 25% Reduction

DISTRIBUTION D-Box

LOCATION T&S BC 4/5

LTAR 0.5 gpd/ft²

LINE	FLAG COLOR	ELEVATION	LENGTH	
I { 1	P	96.93	90	(60)
2	L	96.91	90	
3	P	95.50	90	
4	L	94.93	90	
				360 AVAIL 240
R { 5	P	94.50	90	(60)
6	L	93.93	90	
7	P	93.41	90	
8	L	93.17	90	
				360 AVAIL 240

BY B.C. RAYNOR

TYPICAL PROFILE

0-33 LS VFR GR

33-36 LSCL Fi SBK

GR ≥ 36"

DATE 03/10/2024

THERE SHALL BE NO GRADING,

CUTTING, LOGGING OR OTHER SOIL

DISTURBANCE IN SEPTIC AREA

HEALTH DEPARTMENT USE ONLY.

DESIGNS DO NOT GUARANTEE FUNCTIONALITY

Southeastern Soil and Environmental Associates LLC
PO Box 9321 Fayetteville, NC 28311
Mike@southeasternsoil.com
(910) 822-4540

Elyse Meadow Preliminary Septic Evaluation

