

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: Elyse Meadow

LOT 7

INITIAL SYSTEM: GRAV
APPROVED 25% REDUCTION

REPAIR GRAV
Approved 25% Reduction

DISTRIBUTION: SERIAL

DISTRIBUTION SERIAL

BENCHMARK: 100.0

LOCATION BL TO S 6/7

NO. BEDROOMS: 4

LTAR 0.35 gpd/ft²

LINE	FLAG COLOR	ELEVATION	LENGTH
1	0	100.00	50
2	L	99.50	65
3	0	99.17	75
4	L	98.93	90
5A	0	98.50	70
			350
5b	0	98.50	30
6	L	98.25	110
7	0	97.41	125
8	L	96.91	110
			375

BY B.C. RAYNOR

DATE 03/06/2024

TYPICAL PROFILE

THERE SHALL BE NO GRADING,

0-18 LS VFR GR

CUTTING, LOGGING OR OTHER SOIL

18-36 SCL F/SBK

DISTURBANCE IN SEPTIC AREA

CR2 ≥ 27"

HEALTH DEPARTMENT USE ONLY.

DESIGNS DO NOT GUARANTEE FUNCTIONALITY

Southeastern Soil and Environmental Associates LLC
PO Box 9321 Fayetteville, NC 28311
Mike@southeasternsoil.com
(910) 822-4540

Elyse Meadow
Preliminary Septic Evaluation

