

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: FLYSE MEADOWS

INITIAL SYSTEM: ^{pump to} Approved 25% Reduction

DISTRIBUTION: D-Box

BENCHMARK: 100.0

NO. BEDROOMS: 4

SEPTIC TANK SIZE 1000

LOT 57

REPAIR: ^{pump to} Approved 25% Reduction

DISTRIBUTION D-Box

LOCATION TOP STAKE 399

LTAR 0.4 GPD/FT²

PUMP TANK SIZE 1000

LINE	FLAG COLOR	ELEVATION	LENGTH
1	G	97.60	75'
2	O	97.30	75'
3	G	97.00	75'
4	O	96.70	75'
			<u>300'</u>
5	G	96.50	75'
6	O	96.10	75'
7	G	95.90	75'
8	O	95.60	75'
			<u>300'</u>

Initial system

BY M. EAKER

DATE 03/2024

TYPICAL PROFILE

0-10 LS (VF, w-1)
10-36 + sec (F; shcl)
CR 2 ? 34"

THERE SHALL BE NO GRADING,

CUTTING, LOGGING OR OTHER SOIL

DISTURBANCE IN SEPTIC AREA

HEALTH DEPARTMENT USE ONLY.

DESIGNS DO NOT GUARANTEE FUNCTIONALITY

Southeastern Soil & Environmental Associates LLC
PO Box 9321 Fayetteville, NC 28311
Mike@southeasternsoil.com
(910) 822-4540

Elyse Meadow Preliminary Septic Evaluation

