

Mark Morris, P.E.

#126, 1317-M, Summerville, SC 29483
843 209-5784, Fax (866)-213-4614

The truss drawing(s) listed below have been prepared by **Atlantic Building Components** under my direct supervision based on the parameters provided by the truss designers.

AST #: 57986
JOB: 25-2569-F01
JOB NAME: LOT 0.0040 HONEYCUTT HILLS
Wind Code: N/A
Wind Speed: Vult= N/A
Exposure Category: N/A
Mean Roof Height (feet): N/A
These truss designs comply with IRC 2015 as well as IRC 2018.
20 Truss Design(s)

Trusses:

F1-01, F1-02, F1-03, F1-04, F1-05, F1-06, F1-07, F1-08, F1-10, F1-11, F1-12, F1-12A, F1-13, F1-14, F1-16, F1-17, F1-17A, F1-19, F1-21, F1-22



3/27/2025

Mark Morris


My license renewal date for the state of North Carolina is 12/31/2025

Warning !—Verify design parameters and read notes before use.

This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

8.630 s Jul 12 2024 MiTek Industries, Inc. Fri Mar 28 16:18:51 2025 Page 1
ID:fcZ0KwZoZQmeXTiMivGJ CysCYm-f1reCvjNVis9WqXwc2cAh8dnHjiJG7hyJpV3HzWMnl


Scale = 1:21.7



LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.1(flat)	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.1(flat)	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3(flat)		
OTHERS	2x4 SP No.3(flat)		

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

LOAD CASE(S) Standard



Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 Guide to *Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D’Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0040 HONEYCUTT HILLS 208 SHELBY MEADOW LANE ANGIER, NC
25-2569-F01	F1-02	Floor	5	1	
Job Reference (optional)					# 57986

8.630 s Jul 12 2024 MiTek Industries, Inc. Fri Mar 28 16:18:52 2025 Page 1
ID:fcZ0KwZoZQmeXTIMivGJ_CysCYm-7EP0Plj?G0_08z66Am7PDMAum7?Y2h2rBzZ3bjzWMnH




Plate Offsets (X,Y)-- [2:0-1-8,Edge], [3:0-1-8,Edge], [5:Edge,0-1-8], [10:Edge,0-1-8]					
LOADING (psf)	SPACING-	1-7-3	CSL	DEFL.	in (loc) l/defl L/d
TCLL 40.0	Plate Grip DOL	1.00	TC 0.27	Vert(LL)	-0.03 7 >999 480
TCDL 10.0	Lumber DOL	1.00	BC 0.24	Vert(CT)	-0.03 7 >999 360
BCLL 0.0	Rep Stress Incr	YES	WB 0.18	Horz(CT)	0.00 5 n/a n/a
BCDL 5.0	Code IRC2021/TPI2014		Matrix-SH		
				PLATES	GRIP
				MT20	244/190
				Weight: 40 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (lb/size) 10=322/0-7-14 (min. 0-1-8), 5=327/0-5-4 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 10-11=-317/0, 1-11=-317/0, 4-5=-322/0, 1-2=-301/0, 2-3=-580/0, 3-4=-302/0
BOT CHORD 8-9=0/580, 7-8=0/580, 6-7=0/580
WEBS 2-9=-355/0, 1-9=0/365, 3-6=-355/0, 4-6=0/381

NOTES- (4-7)
1) Unbalanced floor live loads have been considered for this design.
2) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
3) CAUTION. Do not erect truss backwards.
4) Graphical bracing representation does not depict the size, type or the orientation of the brace on the member. Symbol only indicates that the member must be braced.
5) Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.
6) Web bracing shown is for lateral support of individual web members only. Refer to BCSI - Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses for additional bracing guidelines, including diagonal bracing.
7) SEE BCSI-B3 SUMMARY SHEET- PERMANENT RESTRAINING/BRACING OF CHORDS & WEB MEMBERS FOR RECOMMENDED MINIMUM BRACING REQUIREMENTS OF TOP CHORD, BOTTOM CHORD, AND WEB PLANES. IN ADDITION TO THESE MINIMUM GUIDELINES, ALWAYS CONSULT THE PROJECT ARCHITECT OR ENGINEER FOR ADDITIONAL BRACING CONSIDERATIONS.

LOAD CASE(S) Standard



3/27/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0040 HONEYCUTT HILLS 208 SHELBY MEADOW LANE ANGIER, NC
25-2569-F01	F1-03	GABLE	1	1	
Job Reference (optional)					# 57986

8.630 s Jul 12 2024 MiTek Industries, Inc. Fri Mar 28 16:18:52 2025 Page 1
ID:fcZ0KwZoZQmeXTIMivGJ_CysCYm-7EP0Plj?G0_08z66Am7PDMaY37292jMrBzZ3bjzWMnH

0-1-8

Scale = 1:15.1




Plate Offsets (X,Y)-- [4:0-1-8,Edge], [11:0-1-8,Edge], [15:Edge,0-1-8]		1-4-0		2-8-0		4-0-0		5-4-0		6-8-0		8-0-0		8-4-8	
LOADING (psf)		SPACING-		2-0-0		CSI.		DEFL.		in (loc)		l/defl		L/d	
TCLL 40.0		Plate Grip DOL		1.00		TC 0.06		Vert(LL)		n/a		-		n/a	
TCDL 10.0		Lumber DOL		1.00		BC 0.01		Vert(CT)		n/a		-		n/a	
BCLL 0.0		Rep Stress Incr		YES		WB 0.03		Horz(CT)		0.00		9		n/a	
BCDL 5.0		Code IRC2021/TPI2014				Matrix-P									
														Weight: 40 lb	
														FT = 20%F, 11%E	


LUMBER-		BRACING-	
TOP CHORD 2x4 SP No.1(flat)		TOP CHORD	
BOT CHORD 2x4 SP No.1(flat)			
WEBS 2x4 SP No.3(flat)		BOT CHORD	
OTHERS 2x4 SP No.3(flat)			
		Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.	
		Rigid ceiling directly applied or 10-0-0 oc bracing.	

REACTIONS. All bearings 8-4-8.
(lb) - Max Grav All reactions 250 lb or less at joint(s) 15, 9, 14, 13, 12, 11, 10

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES- (6)
1) Gable requires continuous bottom chord bearing.
2) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
3) Gable studs spaced at 1-4-0 oc.
4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
5) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard




3/27/2025


Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0040 HONEYCUTT HILLS 208 SHELBY MEADOW LANE ANGIER, NC
25-2569-F01	F1-04	Floor	2	1	
Job Reference (optional)					# 57986

8.630 s Jul 12 2024 MiTek Industries, Inc. Fri Mar 28 16:18:53 2025 Page 1
ID:fcZ0KwZoZQmeXTIMivGJ_CysCYm-cQzOdek1J6tm7hJkTeemZjxDX9Mn_s_Pdlc79zWMnG



Scale = 1:28.3



2-0-10	8-7-14	9-7-14	10-7-14	17-5-2
2-0-10	6-7-4	1-0-0	1-0-0	6-9-4
Plate Offsets (X,Y)-- [1:Edge,0-1-8], [6:0-1-8,Edge], [7:0-1-8,Edge], [21:Edge,0-1-8]				

LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 40.0	1-4-0	TC 0.80	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.00	BC 0.91	Vert(LL) -0.19 16-17 >999 480		
BCLL 0.0	Lumber DOL 1.00	WB 0.79	Vert(CT) -0.42 16-17 >494 360		
BCDL 5.0	Rep Stress Incr NO	Matrix-SH	Horz(CT) 0.06 11 n/a n/a		
	Code IRC2021/TPI2014			Weight: 90 lb	FT = 20%F, 11%E


LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 5-10-6 oc purlins, except end verticals.
BOT CHORD 2x4 SP SS(flat) *Except* B2: 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (lb/size) 21=1518/0-5-4 (min. 0-1-8), 11=742/0-4-8 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-21=-1516/0, 1-2=-772/0, 2-3=-2678/0, 3-4=-3371/0, 4-5=-3371/0, 5-6=-3564/0, 6-7=-3362/0, 7-8=-2750/0, 8-9=-1679/0
BOT CHORD 19-20=0/2678, 18-19=0/3129, 17-18=0/3603, 16-17=0/3362, 15-16=0/3362, 14-15=0/3362, 13-14=0/2293, 12-13=0/2293, 11-12=0/1027
WEBS 2-19=0/325, 6-16=-298/0, 7-15=0/320, 7-14=-887/0, 8-14=0/621, 8-12=-799/0, 9-12=0/849, 9-11=-1245/0, 2-20=-2391/0, 1-20=0/1649, 6-17=0/459, 5-18=-302/0, 3-18=0/315, 3-19=-552/0

- NOTES-** (5-8)
- Unbalanced floor live loads have been considered for this design.
 - Load case(s) 1, 2, 3, 4, 5, 6 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - CAUTION, Do not erect truss backwards.
 - Graphical bracing representation does not depict the size, type or the orientation of the brace on the member. Symbol only indicates that the member must be braced.
 - Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.
 - Web bracing shown is for lateral support of individual web members only. Refer to BCSI - Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses for additional bracing guidelines, including diagonal bracing.
 - SEE BCSI-B3 SUMMARY SHEET- PERMANENT RESTRAING/BRACING OF CHORDS & WEB MEMBERS FOR RECOMMENDED MINIMUM BRACING REQUIREMENTS OF TOP CHORD, BOTTOM CHORD, AND WEB PLANES. IN ADDITION TO THESE MINIMUM GUIDELINES, ALWAYS CONSULT THE PROJECT ARCHITECT OR ENGINEER FOR ADDITIONAL BRACING CONSIDERATIONS.

- LOAD CASE(S)** Standard
- Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (plf)
Vert: 11-21=-7, 1-10=-67
Concentrated Loads (lb)
Vert: 2=-1000
 - Dead: Lumber Increase=1.00, Plate Increase=1.00



3/27/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0040 HONEYCUTT HILLS 208 SHELBY MEADOW LANE ANGIER, NC
25-2569-F01	F1-04	Floor	2	1	Job Reference (optional) # 57986

8.630 s Jul 12 2024 MiTek Industries, Inc. Fri Mar 28 16:18:53 2025 Page 2
ID:fcZ0KwZoZQmeXTIMivGJ_CysCYm-cQzOdek1J6tm7hJkTeemZjxDX9Mn_s_Pdlc79zWMnG

- LOAD CASE(S)** Standard
- Uniform Loads (plf)
 - Vert: 11-21=-7, 1-10=-67
 - Concentrated Loads (lb)
 - Vert: 2=-1000
- 3) 1st chase Dead + Floor Live (unbalanced): Lumber Increase=1.00, Plate Increase=1.00
- Uniform Loads (plf)
 - Vert: 11-21=-7, 1-7=-67, 7-10=-13
 - Concentrated Loads (lb)
 - Vert: 2=-1000
- 4) 2nd chase Dead + Floor Live (unbalanced): Lumber Increase=1.00, Plate Increase=1.00
- Uniform Loads (plf)
 - Vert: 11-21=-7, 1-6=-13, 6-10=-67
 - Concentrated Loads (lb)
 - Vert: 2=-1000
- 5) 3rd chase Dead: Lumber Increase=1.00, Plate Increase=1.00
- Uniform Loads (plf)
 - Vert: 11-21=-7, 1-7=-67, 7-10=-13
 - Concentrated Loads (lb)
 - Vert: 2=-1000
- 6) 4th chase Dead: Lumber Increase=1.00, Plate Increase=1.00
- Uniform Loads (plf)
 - Vert: 11-21=-7, 1-6=-13, 6-10=-67
 - Concentrated Loads (lb)
 - Vert: 2=-1000



3/27/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0040 HONEYCUTT HILLS 208 SHELBY MEADOW LANE ANGIER, NC
25-2569-F01	F1-05	GABLE	1	1	
					Job Reference (optional) # 57986

8.630 s Jul 12 2024 MiTek Industries, Inc. Fri Mar 28 16:18:53 2025 Page 1
ID:fcZ0KwZoZQmeXTIMivGJ_CysCYm-cQzOdek1J6tm7hJkTeemZj7rXNTnAe_Pdlc79zWMnG

0-1-8

Scale = 1:27.0




Plate Offsets (X,Y)-- [8:0-1-8,Edge], [23:0-1-8,Edge], [30:Edge,0-1-8]															
LOADING (psf)															
TCLL	40.0	SPACING-				2-0-0	CSI.				DEFL.	in	(loc)	l/defl	L/d
TCDL	10.0	Plate Grip DOL				1.00	TC				Vert(LL)	n/a	-	n/a	999
BCLL	0.0	Lumber DOL				1.00	BC				Vert(CT)	n/a	-	n/a	999
BCDL	5.0	Rep Stress Incr				YES	WB				Horz(CT)	0.00	16	n/a	n/a
				Code IRC2021/TPI2014				Matrix-SH				PLATES			
												GRIP			
												MT20			
												244/190			
												Weight: 73 lb			
												FT = 20%F, 11%E			


LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.1(flat)	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.1(flat)	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3(flat)		
OTHERS	2x4 SP No.3(flat)		

REACTIONS. All bearings 16-6-8.
(lb) - Max Uplift All uplift 100 lb or less at joint(s) 16
Max Grav All reactions 250 lb or less at joint(s) 30, 16, 29, 28, 27, 26, 25, 24, 23, 22, 21, 19, 18, 17

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-** (7)
- Gable requires continuous bottom chord bearing.
 - Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - Gable studs spaced at 1-4-0 oc.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 16.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard



3/27/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

8.630 s Jul 12 2024 MiTek Industries, Inc. Fri Mar 28 16:18:54 2025 Page 1
ID:fcZ0KwZoZQmeXTIMivGJ CysCYm-4Cxmg IFodEkNHGVIBatInFHRxjhWdr7eH29fczWMmF


LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.1(flat)	TOP CHORD	Structural wood sheathing directly applied or 10-0-0 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.1(flat)	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3(flat)		
OTHERS	2x4 SP No.3(flat)		

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES- (5)

- 1) Gable requires continuous bottom chord bearing.
- 2) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
- 3) Gable studs spaced at 1-4-0 oc.
- 4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard





3/27/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 Guide to *Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D’Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0040 HONEYCUTT HILLS 208 SHELBY MEADOW LANE ANGIER, NC
25-2569-F01	F1-07	Floor	13	1	
					Job Reference (optional) # 57986

8.630 s Jul 12 2024 MiTek Industries, Inc. Fri Mar 28 16:18:54 2025 Page 1
ID:fcZ0KwZoZQmeXTIMivGJ_CysCYm-4cXmq_lFodEkNHGVIBAtInFDRxZTWW87eH29fczWMnF



1-6-0	4-0-0	6-6-0	7-11-6	8-11-6	9-11-6	11-3-14	13-9-14	16-3-14	17-10-12
1-6-0	2-6-0	2-6-0	1-5-6	1-0-0	1-0-0	1-4-8	2-6-0	2-6-0	1-6-14
Plate Offsets (X,Y)-- [5:0-1-8,Edge], [6:0-1-8,Edge], [20:Edge,0-1-8]									

LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 40.0	1-4-0	TC 0.32	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.00	BC 0.66	Vert(LL) -0.19 15-16 >999 480		
BCLL 0.0	Lumber DOL 1.00	WB 0.46	Vert(CT) -0.26 15-16 >806 360		
BCDL 5.0	Rep Stress Incr YES	Matrix-SH	Horz(CT) -0.05 20 n/a n/a		
	Code IRC2021/TPI2014			Weight: 89 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (lb/size) 20=647/0-5-4 (min. 0-1-8), 10=647/0-5-4 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-20=-642/0, 9-10=-642/0, 1-2=-753/0, 2-3=-1861/0, 3-4=-1861/0, 4-5=-2496/0, 5-6=-2718/0, 6-7=-2510/0, 7-8=-1887/0, 8-9=-790/0

BOT CHORD 18-19=0/1422, 17-18=0/2280, 16-17=0/2718, 15-16=0/2718, 14-15=0/2718, 13-14=0/2296, 12-13=0/1456, 11-12=0/1456

WEBS 1-19=0/945, 2-19=-871/0, 2-18=0/572, 4-18=-544/0, 4-17=0/345, 5-17=-444/0, 6-14=-436/3, 7-14=0/345, 7-13=-533/0, 8-13=0/561, 8-11=-867/0, 9-11=0/973

NOTES- (3)

1) Unbalanced floor live loads have been considered for this design.

2) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard



3/27/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0040 HONEYCUTT HILLS 208 SHELBY MEADOW LANE ANGIER, NC
25-2569-F01	F1-08	Floor	1	1	Job Reference (optional) # 57986

8.630 s Jul 12 2024 MiTek Industries, Inc. Fri Mar 28 16:18:55 2025 Page 1
ID:fcZ0KwZoZQmeXTIMivGJ_CysCYm-Yo582JmtZxMb?Rrhruh6r_oQML?MF24HtnjC2zWMnE




Plate Offsets (X,Y)-- [2:0-1-8,Edge], [3:0-1-8,Edge], [9:Edge,0-1-8]									
LOADING (psf)		SPACING-		CSI.		DEFL.		PLATES	
TCLL	40.0	1-4-0	Plate Grip DOL	1.00	TC	0.25	in (loc)	L/defl	L/d
TCDL	10.0	1-6-0	Lumber DOL	1.00	BC	0.30	Vert(LL)	-0.03	7 >999 480
BCLL	0.0	1-3-11	Rep Stress Incr	YES	WB	0.10	Vert(CT)	-0.04	7 >999 360
BCDL	5.0	2-9-11	Code IRC2021/TPI2014		Matrix-SH		Horz(CT)	0.00	5 n/a n/a
					Weight: 32 lb FT = 20%F, 11%E				


LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.1(flat)	TOP CHORD	Structural wood sheathing directly applied or 5-9-14 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.1(flat)	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3(flat)		

REACTIONS. (lb/size) 9=204/0-7-8 (min. 0-1-8), 5=204/0-5-4 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 3-5=-387/0

NOTES- (3)
1) Unbalanced floor live loads have been considered for this design.
2) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard



3/27/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D’Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0040 HONEYCUTT HILLS 208 SHELBY MEADOW LANE ANGIER, NC
25-2569-F01	F1-10	GABLE	1	1	
Job Reference (optional)					# 57986

8.630 s Jul 12 2024 MiTek Industries, Inc. Fri Mar 28 16:18:55 2025 Page 1
ID:fcZ0KwZoZQmeXTIMivGJ_CysCYm-Yo582JmtZxMb?Rrhruh6r_oTJL3rF36HtnjC2zWMnE

0-1-8

Scale = 1:12.9




Plate Offsets (X,Y)-- [3:0-1-8,Edge], [10:0-1-8,Edge], [13:Edge,0-1-8]		1-4-0		2-8-0		4-0-0		5-4-0		6-8-0		7-1-8	
		1-4-0		1-4-0		1-4-0		1-4-0		1-4-0		0-5-8	
LOADING (psf)		SPACING-		CSI.		DEFL.				PLATES		GRIP	
TCLL 40.0		2-0-0		TC 0.06		in (loc)		l/defl		L/d		MT20	
TCDL 10.0		Plate Grip DOL 1.00		BC 0.01		Vert(LL) n/a		-		n/a		244/190	
BCLL 0.0		Lumber DOL 1.00		WB 0.03		Vert(CT) n/a		-		n/a			
BCDL 5.0		Rep Stress Incr YES		Matrix-P		Horz(CT) 0.00		8		n/a			
		Code IRC2021/TPI2014										Weight: 35 lb	
												FT = 20%F, 11%E	

LUMBER-		BRACING-	
TOP CHORD 2x4 SP No.1(flat)		TOP CHORD	
BOT CHORD 2x4 SP No.1(flat)		Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.	
WEBS 2x4 SP No.3(flat)		BOT CHORD	
OTHERS 2x4 SP No.3(flat)		Rigid ceiling directly applied or 10-0-0 oc bracing.	

REACTIONS. All bearings 7-1-8.
(lb) - Max Grav All reactions 250 lb or less at joint(s) 13, 8, 12, 11, 10, 9

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES- (6)
1) Gable requires continuous bottom chord bearing.
2) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
3) Gable studs spaced at 1-4-0 oc.
4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
5) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard



3/27/2025


Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0040 HONEYCUTT HILLS 208 SHELBY MEADOW LANE ANGIER, NC
25-2569-F01	F1-11	GABLE	1	1	Job Reference (optional) # 57986

8.630 s Jul 12 2024 MiTek Industries, Inc. Fri Mar 28 16:18:56 2025 Page 1
ID:fcZ0KwZoZQmeXTIMivGJ_CysCYm-0?fXFnWKEUSdbQuPcCLOCLe2kPA_WMq6bXGkUzWMnD

0-1-8

Scale = 1:27.9



Job	Truss	Truss Type	Qty	Ply	LOT 0.0040 HONEYCUTT HILLS 208 SHELBY MEADOW LANE ANGIER, NC
25-2569-F01	F1-12	Floor	7	1	
Job Reference (optional)					# 57986

8.630 s Jul 12 2024 MiTek Industries, Inc. Fri Mar 28 16:18:56 2025 Page 1
ID:fcZ0KwZoZQmeXTIMivGJ_CysCYm-0?fXFfnWKEUSdbQuPcCLOCLZDkDw_RAQ6bXGkUzWMnD



Scale = 1:28.6




Plate Offsets (X,Y)-- [1:Edge,0-1-8], [7:0-1-8,Edge], [8:0-1-8,Edge]					
LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 40.0	1-4-0	TC 0.37	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.00	BC 0.79	Vert(LL) -0.20 17-18 >999 480	Weight: 89 lb FT = 20%F, 11%E	
BCLL 0.0	Lumber DOL 1.00	WB 0.36	Vert(CT) -0.28 17-18 >745 360		
BCDL 5.0	Rep Stress Incr YES	Matrix-SH	Horz(CT) 0.04 12 n/a n/a		
Code IRC2021/TPI2014					

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (lb/size) 21=634/0-5-4 (min. 0-1-8), 12=629/0-3-8 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1067/0, 3-4=-2040/0, 4-5=-2040/0, 5-6=-2040/0, 6-7=-2516/0, 7-8=-2578/0, 8-9=-2226/0, 9-10=-1436/0
BOT CHORD 20-21=0/478, 19-20=0/1635, 18-19=0/2392, 17-18=0/2578, 16-17=0/2578, 15-16=0/2578, 14-15=0/1926, 13-14=0/1926, 12-13=0/916
WEBS 7-18=-306/127, 6-18=0/266, 6-19=-450/0, 3-19=0/517, 3-20=-739/0, 2-20=0/766, 8-15=-558/0, 9-15=0/421, 9-13=-639/0, 10-13=0/677, 10-12=-1085/0, 2-21=-797/0

NOTES- (4)
1) Unbalanced floor live loads have been considered for this design.
2) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
3) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard



3/27/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0040 HONEYCUTT HILLS 208 SHELBY MEADOW LANE ANGIER, NC
25-2569-F01	F1-12A	Floor	5	1	
Job Reference (optional)					# 57986

8.630 s Jul 12 2024 MiTek Industries, Inc. Fri Mar 28 16:18:57 2025 Page 1
ID:fcZ0KwZoZQmeXTiMivGJ_CysCYm-UBDvT?n85YcJEI?4zJjawPtky8Z6juSaKFGpGwzWMnC





Plate Offsets (X,Y)-- [1:Edge,0-1-8], [7:0-1-8,Edge], [8:0-1-8,Edge]					
LOADING (psf)	SPACING-	1-4-0	CSI.	DEFL.	in (loc) l/defl L/d
TCLL 40.0	Plate Grip DOL	1.00	TC 0.37	Vert(LL)	-0.20 17-18 >999 480
TCDL 10.0	Lumber DOL	1.00	BC 0.79	Vert(CT)	-0.28 17-18 >749 360
BCLL 0.0	Rep Stress Incr	YES	WB 0.36	Horz(CT)	0.04 12 n/a n/a
BCDL 5.0	Code IRC2021/TPI2014		Matrix-SH		
				PLATES	GRIP
				MT20	244/190
				Weight: 89 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (lb/size) 21=630/0-5-4 (min. 0-1-8), 12=630/0-6-4 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1060/0, 3-4=-2023/0, 4-5=-2023/0, 5-6=-2023/0, 6-7=-2490/0, 7-8=-2543/0, 8-9=-2183/0, 9-10=-1383/0
BOT CHORD 20-21=0/475, 19-20=0/1623, 18-19=0/2371, 17-18=0/2543, 16-17=0/2543, 15-16=0/2543, 14-15=0/1878, 13-14=0/1878, 12-13=0/859
WEBS 7-18=-297/133, 6-18=0/260, 6-19=-445/0, 3-19=0/511, 3-20=-733/0, 2-20=0/761, 2-21=-792/0, 8-15=-564/0, 9-15=0/425, 9-13=-644/0, 10-13=0/682, 10-12=-1041/0

- NOTES- (3-6)
- Unbalanced floor live loads have been considered for this design.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - Graphical bracing representation does not depict the size, type or the orientation of the brace on the member. Symbol only indicates that the member must be braced.
 - Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.
 - Web bracing shown is for lateral support of individual web members only. Refer to BCSI - Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses for additional bracing guidelines, including diagonal bracing.
 - SEE BCSI-B3 SUMMARY SHEET- PERMANENT RESTRAING/BRACING OF CHORDS & WEB MEMBERS FOR RECOMMENDED MINIMUM BRACING REQUIREMENTS OF TOP CHORD, BOTTOM CHORD, AND WEB PLANES. IN ADDITION TO THESE MINIMUM GUIDELINES, ALWAYS CONSULT THE PROJECT ARCHITECT OR ENGINEER FOR ADDITIONAL BRACING CONSIDERATIONS.

LOAD CASE(S) Standard



3/27/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0040 HONEYCUTT HILLS 208 SHELBY MEADOW LANE ANGIER, NC
25-2569-F01	F1-13	Floor Supported Gable	2	1	
Job Reference (optional)					# 57986

8.630 s Jul 12 2024 MiTek Industries, Inc. Fri Mar 28 16:18:57 2025 Page 1
ID:fcZ0KwZoZQmeXTIMivGJ_CysCYm-UBDvT?n85YcJEI?4zJjawPtp08IQzjaKFGpGwzWMnC

0-1-8 0-1-8
Scale = 1:17.8




Plate Offsets (X,Y)-- [4:0-1-8,Edge], [10:Edge,0-1-8], [14:0-1-8,Edge], [18:Edge,0-1-8]									
LOADING (psf)	SPACING-	1-7-3	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES
TCLL 40.0	Plate Grip DOL	1.00	TC 0.05	Vert(LL)	n/a	-	n/a	999	MT20
TCDL 10.0	Lumber DOL	1.00	BC 0.01	Vert(CT)	n/a	-	n/a	999	GRIP
BCLL 0.0	Rep Stress Incr	YES	WB 0.03	Horz(CT)	0.00	10	n/a	n/a	244/190
BCDL 5.0	Code IRC2021/TPI2014		Matrix-SH						Weight: 46 lb FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	
OTHERS 2x4 SP No.3(flat)	

REACTIONS. All bearings 9-11-14.
(lb) - Max Grav All reactions 250 lb or less at joint(s) 18, 10, 17, 16, 15, 14, 13, 12, 11

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES- (5-8)
- Gable requires continuous bottom chord bearing.
 - Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - Gable studs spaced at 1-4-0 oc.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - Graphical bracing representation does not depict the size, type or the orientation of the brace on the member. Symbol only indicates that the member must be braced.
 - Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.
 - Web bracing shown is for lateral support of individual web members only. Refer to BCSI - Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses for additional bracing guidelines, including diagonal bracing.
 - SEE BCSI-B3 SUMMARY SHEET - PERMANENT RESTRAINING/BRACING OF CHORDS & WEB MEMBERS FOR RECOMMENDED MINIMUM BRACING REQUIREMENTS OF TOP CHORD, BOTTOM CHORD, AND WEB PLANES. IN ADDITION TO THESE MINIMUM GUIDELINES, ALWAYS CONSULT THE PROJECT ARCHITECT OR ENGINEER FOR ADDITIONAL BRACING CONSIDERATIONS.

LOAD CASE(S) Standard



3/27/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0040 HONEYCUTT HILLS 208 SHELBY MEADOW LANE ANGIER, NC
25-2569-F01	F1-14	Floor	7	1	
Job Reference (optional)					# 57986

8.630 s Jul 12 2024 MiTek Industries, Inc. Fri Mar 28 16:18:57 2025 Page 1
ID:fcZ0KwZoZQmeXTIMivGJ_CysCYm-UBDvT?n85YcJEI?4zJjawPtmP8i0jvpaKFGpGwzWMnC




Plate Offsets (X,Y)-- [12:Edge,0-1-8]											
LOADING (psf)		SPACING- 1-7-3		CSI.		DEFL. in (loc) l/defl L/d			PLATES GRIP		
TCLL	40.0	Plate Grip DOL	1.00	TC	0.21	Vert(LL)	-0.03	9-10	>999	480	MT20 244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.22	Vert(CT)	-0.04	9-10	>999	360	
BCLL	0.0	Rep Stress Incr	YES	WB	0.28	Horz(CT)	0.01	6	n/a	n/a	
BCDL	5.0	Code IRC2021/TPI2014		Matrix-SH							Weight: 56 lb FT = 20%F, 11%E


LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (lb/size) 12=446/0-7-14 (min. 0-1-8), 6=451/0-4-8 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 12-13=-442/0, 1-13=-442/0, 5-6=-446/0, 1-2=-479/0, 2-3=-1026/0, 3-4=-1024/0, 4-5=-441/0
BOT CHORD 10-11=0/891, 9-10=0/1137, 8-9=0/883, 7-8=0/883
WEBS 1-11=0/578, 2-11=-536/0, 4-7=-565/0, 5-7=0/572

- NOTES- (3-6)
- 1) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 2) CAUTION, Do not erect truss backwards.
 - 3) Graphical bracing representation does not depict the size, type or the orientation of the brace on the member. Symbol only indicates that the member must be braced.
 - 4) Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.
 - 5) Web bracing shown is for lateral support of individual web members only. Refer to BCSI - Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses for additional bracing guidelines, including diagonal bracing.
 - 6) SEE BCSI-B3 SUMMARY SHEET - PERMANENT RESTRAING/BRACING OF CHORDS & WEB MEMBERS FOR RECOMMENDED MINIMUM BRACING REQUIREMENTS OF TOP CHORD, BOTTOM CHORD, AND WEB PLANES. IN ADDITION TO THESE MINIMUM GUIDELINES, ALWAYS CONSULT THE PROJECT ARCHITECT OR ENGINEER FOR ADDITIONAL BRACING CONSIDERATIONS.

LOAD CASE(S) Standard



3/27/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.


Job	Truss	Truss Type	Qty	Ply	LOT 0.0040 HONEYCUTT HILLS 208 SHELBY MEADOW LANE ANGIER, NC
25-2569-F01	F1-16	Floor Supported Gable	1	1	Job Reference (optional) # 57986

8.630 s Jul 12 2024 MiTek Industries, Inc. Fri Mar 28 16:18:58 2025 Page 1
ID:fcZ0KwZoZQmeXTIMivGJ_CysCYm-yNnHgLomssk9suZGX0EpTdQ_bY5eSQtiZv0NoNzWMnB

0-1-8

0-1-8

Scale = 1:25.9



LOADING (psf) TCLL 40.0 TCDL 10.0 BCLL 0.0 BCDL 5.0	SPACING- Plate Grip DOL 1.00 Lumber DOL 1.00 Rep Stress Incr YES Code IRC2021/TPI2014	CSI. TC 0.06 BC 0.01 WB 0.03 Matrix-SH	DEFL. Vert(LL) n/a Vert(CT) n/a Horz(CT) 0.00	in (loc) - - 14	l/defl n/a n/a n/a	L/d 999 999 n/a	PLATES MT20 Weight: 69 lb	GRIP 244/190 FT = 20%F, 11%E
--	--	---	---	---------------------------------	------------------------------------	---------------------------------	--	---


LUMBER- TOP CHORD 2x4 SP No.1(flat) BOT CHORD 2x4 SP No.1(flat) WEBS 2x4 SP No.3(flat) OTHERS 2x4 SP No.3(flat)	BRACING- TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals. BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
--	--

REACTIONS. All bearings 15-9-0.
(lb) - Max Grav All reactions 250 lb or less at joint(s) 26, 14, 25, 24, 23, 22, 21, 20, 19, 18, 17, 16, 15

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES- (5)
1) Gable requires continuous bottom chord bearing.
2) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
3) Gable studs spaced at 1-4-0 oc.
4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard




3/27/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0040 HONEYCUTT HILLS 208 SHELBY MEADOW LANE ANGIER, NC
25-2569-F01	F1-17	Floor	4	1	
Job Reference (optional)					# 57986

8.630 s Jul 12 2024 MiTek Industries, Inc. Fri Mar 28 16:18:58 2025 Page 1
ID:fcZ0KwZoZQmeXTIMivGJ_CysCYm-yNnHgLomssk9suZGX0EpTdQwqYxbSLzjZv0NoNzWMnB



Scale = 1:25.7




Plate Offsets (X,Y)-- [1:Edge,0-1-8], [4:0-1-8,Edge], [5:0-1-8,Edge], [8:0-1-8,Edge]					
LOADING (psf)	SPACING-	1-7-3	CSI.	DEFL.	in (loc) l/defl L/d
TCLL 40.0	Plate Grip DOL	1.00	TC 0.30	Vert(LL)	-0.14 13-14 >999 480
TCDL 10.0	Lumber DOL	1.00	BC 0.65	Vert(CT)	-0.19 13-14 >973 360
BCLL 0.0	Rep Stress Incr	YES	WB 0.35	Horz(CT)	0.04 9 n/a n/a
BCDL 5.0	Code IRC2021/TPI2014		Matrix-SH		
			PLATES		GRIP
			MT20		244/190
			Weight: 79 lb		FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except
BOT CHORD 2x4 SP No.1(flat)	end verticals.
WEBS 2x4 SP No.3(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (lb/size) 9=676/0-7-14 (min. 0-1-8), 17=681/0-5-4 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 9-18=-675/0, 8-18=-674/0, 2-3=-1484/0, 3-4=-2250/0, 4-5=-2504/0, 5-6=-2266/0, 6-7=-1517/0, 7-8=-399/0
BOT CHORD 16-17=0/945, 15-16=0/1993, 14-15=0/2504, 13-14=0/2504, 12-13=0/2504, 11-12=0/2019, 10-11=0/991
WEBS 4-15=-479/0, 3-15=0/385, 3-16=-663/0, 2-16=0/701, 2-17=-1134/0, 5-12=-464/0, 6-12=0/378, 6-11=-653/0, 7-11=0/684, 7-10=-855/0, 8-10=0/725

- NOTES- (4-7)
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 3) CAUTION, Do not erect truss backwards.
 - 4) Graphical bracing representation does not depict the size, type or the orientation of the brace on the member. Symbol only indicates that the member must be braced.
 - 5) Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.
 - 6) Web bracing shown is for lateral support of individual web members only. Refer to BCSI - Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses for additional bracing guidelines, including diagonal bracing.
 - 7) SEE BCSI-B3 SUMMARY SHEET- PERMANENT RESTRAINING/BRACING OF CHORDS & WEB MEMBERS FOR RECOMMENDED MINIMUM BRACING REQUIREMENTS OF TOP CHORD, BOTTOM CHORD, AND WEB PLANES. IN ADDITION TO THESE MINIMUM GUIDELINES, ALWAYS CONSULT THE PROJECT ARCHITECT OR ENGINEER FOR ADDITIONAL BRACING CONSIDERATIONS.

LOAD CASE(S) Standard




3/27/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0040 HONEYCUTT HILLS 208 SHELBY MEADOW LANE ANGIER, NC
25-2569-F01	F1-17A	Floor	2	1	
Job Reference (optional)					# 57986

8.630 s Jul 12 2024 MiTek Industries, Inc. Fri Mar 28 16:18:59 2025 Page 1
ID:fcZ0KwZoZQmeXTIMivGJ_CysCYm-QaKfhpOd9t0U28S4kl2?qz5fyH0BoQtoZlwLpzWMnA



Scale = 1:25.3




Plate Offsets (X,Y)-- [1:Edge,0-1-8], [4:0-1-8,Edge], [5:0-1-8,Edge]					
LOADING (psf)		SPACING-	CSI.	DEFL.	PLATES
TCLL 40.0		1-7-3	TC 0.29	in (loc) l/defl L/d	GRIP
TCDL 10.0		Plate Grip DOL 1.00	BC 0.64	Vert(LL) -0.13 13-14 >999 480	MT20 244/190
BCLL 0.0		Lumber DOL 1.00	WB 0.33	Vert(CT) -0.19 12-13 >993 360	
BCDL 5.0		Rep Stress Incr YES	Matrix-SH	Horz(CT) 0.04 9 n/a n/a	
		Code IRC2021/TPI2014			Weight: 78 lb FT = 20%F, 11%E


LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (lb/size) 16=675/0-5-4 (min. 0-1-8), 9=675/0-6-4 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1468/0, 3-4=-2219/0, 4-5=-2460/0, 5-6=-2209/0, 6-7=-1446/0
BOT CHORD 15-16=0/936, 14-15=0/1971, 13-14=0/2460, 12-13=0/2460, 11-12=0/2460, 10-11=0/1955, 9-10=0/909
WEBS 4-14=-464/0, 3-14=0/376, 3-15=-655/0, 2-15=0/692, 2-16=-1123/0, 5-11=-473/0, 6-11=0/382, 6-10=-662/0, 7-10=0/699, 7-9=-1102/0

- NOTES-** (3-6)
- Unbalanced floor live loads have been considered for this design.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - Graphical bracing representation does not depict the size, type or the orientation of the brace on the member. Symbol only indicates that the member must be braced.
 - Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.
 - Web bracing shown is for lateral support of individual web members only. Refer to BCSI - Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses for additional bracing guidelines, including diagonal bracing.
 - SEE BCSI-B3 SUMMARY SHEET- PERMANENT RESTRAINING/BRACING OF CHORDS & WEB MEMBERS FOR RECOMMENDED MINIMUM BRACING REQUIREMENTS OF TOP CHORD, BOTTOM CHORD, AND WEB PLANES. IN ADDITION TO THESE MINIMUM GUIDELINES, ALWAYS CONSULT THE PROJECT ARCHITECT OR ENGINEER FOR ADDITIONAL BRACING CONSIDERATIONS.

LOAD CASE(S) Standard




3/27/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0040 HONEYCUTT HILLS 208 SHELBY MEADOW LANE ANGIER, NC
25-2569-F01	F1-19	Floor	7	1	
Job Reference (optional)					# 57986

8.630 s Jul 12 2024 MiTek Industries, Inc. Fri Mar 28 16:18:59 2025 Page 1
ID:fcZ0KwZoZQmeXTIMivGJ_CysCYm-QaKfhpOd9t0U28S4kl2?qz5dyGtBoBtoZlWlpzWMnA



LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 40.0	1-7-3	TC 0.30	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.00	BC 0.65	Vert(LL) -0.14 13-14 >999 480		
BCLL 0.0	Lumber DOL 1.00	WB 0.35	Vert(CT) -0.19 13-14 >966 360		
BCDL 5.0	Rep Stress Incr YES	Matrix-SH	Horz(CT) 0.04 9 n/a n/a		
	Code IRC2021/TPI2014			Weight: 80 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (lb/size) 18=679/0-7-14 (min. 0-1-8), 9=679/0-7-14 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 18-19=-678/0, 1-19=-677/0, 9-20=-678/0, 8-20=-677/0, 1-2=-402/0, 2-3=-1527/0, 3-4=-2285/0, 4-5=-2531/0, 5-6=-2285/0, 6-7=-1527/0, 7-8=-402/0

BOT CHORD 16-17=0/997, 15-16=0/2033, 14-15=0/2531, 13-14=0/2531, 12-13=0/2531, 11-12=0/2033, 10-11=0/997

WEBS 4-15=-473/0, 3-15=0/383, 3-16=-658/0, 2-16=0/690, 2-17=-860/0, 1-17=0/729, 5-12=-473/0, 6-12=0/383, 6-11=-658/0, 7-11=0/690, 7-10=-860/0, 8-10=0/729

- NOTES-** (3-6)
- Unbalanced floor live loads have been considered for this design.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - Graphical bracing representation does not depict the size, type or the orientation of the brace on the member. Symbol only indicates that the member must be braced.
 - Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.
 - Web bracing shown is for lateral support of individual web members only. Refer to BCSI - Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses for additional bracing guidelines, including diagonal bracing.
 - SEE BCSI-B3 SUMMARY SHEET- PERMANENT RESTRAINING/BRACING OF CHORDS & WEB MEMBERS FOR RECOMMENDED MINIMUM BRACING REQUIREMENTS OF TOP CHORD, BOTTOM CHORD, AND WEB PLANES. IN ADDITION TO THESE MINIMUM GUIDELINES, ALWAYS CONSULT THE PROJECT ARCHITECT OR ENGINEER FOR ADDITIONAL BRACING CONSIDERATIONS.

LOAD CASE(S) Standard




3/27/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

8.630 s Jul 12 2024 MiTek Industries, Inc. Fri Mar 28 16:18:59 2025 Page 1
ID:fcZ0KwZoZQmeXTiMivGJ CysCYm-QaKfthpOd9t0U28S4kl2?gz6JyJABoUtoZlwlPzWMnA

0-3-11
Scale = 1:21.8




REACTIONS. (lb/size) 16=573/0-7-14 (min. 0-1-8), 9=578/0-5-4 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-804/0, 3-4=-1560/0, 4-5=-1802/0, 5-6=-1554/0, 6-7=-791/0
 BOT CHORD 15-16=0/277, 14-15=0/1309, 13-14=0/1802, 12-13=0/1802, 11-12=0/1802, 10-11=0/1299, 9-10=0/261
 WEBS 4-14=-417/0, 3-14=0/348, 3-15=-657/0, 2-15=0/686, 2-16=-690/0, 5-11=-422/0, 6-11=0/352, 6-10=-661/0, 7-10=0/690,
 7-9=-682/0

NOTES- (4-7)

- 1) Unbalanced floor live loads have been considered for this design.
- 2) Recommend 2x6 strongbacks, on edge, spaced at 10'-0" o.c. and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
- 3) CAUTION, Do not erect truss backwards.
- 4) Graphical bracing representation does not depict the size, type or the orientation of the brace on the member. Symbol only indicates that the member must be braced.
- 5) Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.
- 6) Web bracing shown is for lateral support of individual web members only. Refer to BCSI - Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses for additional bracing guidelines, including diagonal bracing.
- 7) SEE BCSI-B3 SUMMARY SHEET- PERMANENT RESTRAINING/BRACING OF CHORDS & WEB MEMBERS FOR RECOMMENDED MINIMUM BRACING REQUIREMENTS OF TOP CHORD, BOTTOM CHORD, AND WEB PLANES. IN ADDITION TO THESE MINIMUM GUIDELINES, ALWAYS CONSULT THE PROJECT ARCHITECT OR ENGINEER FOR ADDITIONAL BRACING CONSIDERATIONS.

LOAD CASE(S) Standard



3/27/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D’Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0040 HONEYCUTT HILLS 208 SHELBY MEADOW LANE ANGIER, NC
25-2569-F01	F1-22	Floor	4	1	
Job Reference (optional)					# 57986

8.630 s Jul 12 2024 MiTek Industries, Inc. Fri Mar 28 16:19:00 2025 Page 1
ID:fcZ0KwZoZQmeXTIMivGJ_CysCYm-umu151q00T?t6CjfeRGHY2VJ7MI1wJw00CVUifzWMn9




Plate Offsets (X,Y)-- [3:0-1-8,Edge], [7:0-1-8,Edge], [8:Edge,0-1-8]									
LOADING (psf)		SPACING-		CSI.		DEFL.		PLATES	
TCLL	40.0	Plate Grip DOL	1-7-3	TC	0.12	in	(loc)	MT20	GRIP
TCDL	10.0	Lumber DOL	1.00	BC	0.08	Vert(LL)	-0.01		244/190
BCLL	0.0	Rep Stress Incr	YES	WB	0.12	Vert(CT)	-0.01		
BCDL	5.0	Code IRC2021/TPI2014		Matrix-SH		Horz(CT)	0.00		
								Weight: 27 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 4-11-12 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (lb/size) 8=203/0-7-14 (min. 0-1-8), 5=208/0-5-4 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 1-7=0/262, 3-5=-275/0

- NOTES-** (4-7)
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 3) CAUTION, Do not erect truss backwards.
 - 4) Graphical bracing representation does not depict the size, type or the orientation of the brace on the member. Symbol only indicates that the member must be braced.
 - 5) Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.
 - 6) Web bracing shown is for lateral support of individual web members only. Refer to BCSI - Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses for additional bracing guidelines, including diagonal bracing.
 - 7) SEE BCSI-B3 SUMMARY SHEET- PERMANENT RESTRAINING/BRACING OF CHORDS & WEB MEMBERS FOR RECOMMENDED MINIMUM BRACING REQUIREMENTS OF TOP CHORD, BOTTOM CHORD, AND WEB PLANES. IN ADDITION TO THESE MINIMUM GUIDELINES, ALWAYS CONSULT THE PROJECT ARCHITECT OR ENGINEER FOR ADDITIONAL BRACING CONSIDERATIONS.

LOAD CASE(S) Standard



3/27/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.