

Mark Morris, P.E.

#126, 1317-M, Summerville, SC 29483
843 209-5784, Fax (866)-213-4614

The truss drawing(s) listed below have been prepared by **Atlantic Building Components** under my direct supervision based on the parameters provided by the truss designers.

AST #: 57987
JOB: 25-2569-F02
JOB NAME: LOT 0.0040 HONEYCUTT HILLS
Wind Code: N/A
Wind Speed: Vult= N/A
Exposure Category: N/A
Mean Roof Height (feet): N/A
These truss designs comply with IRC 2015 as well as IRC 2018.
17 Truss Design(s)

Trusses:

F201, F202, F202A, F203, F205A, F206, F207, F208, F209, F210, F211, F212, F213, F214, F215, F216, F217



3/27/2025

Mark Morris

My license renewal date for the state of North Carolina is 12/31/2025

Warning !—Verify design parameters and read notes before use.

This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0040 HONEYCUTT HILLS 208 SHELBY MEADOW LANE ANGIER, NC
25-2569-F02	F201	Floor Supported Gable	1	1	Job Reference (optional) # 57987

8.630 s Jul 12 2024 MiTek Industries, Inc. Fri Mar 28 16:21:51 2025 Page 1
ID:Wl8rkg6BK5SaRYCYGf9_0xywFJ5-Ofkh_VuH6?Xc6UIW9srN_65XkH76VgfBLJQ1NrZWmKu

0-1-8

Scale = 1:28.5




Plate Offsets (X,Y)-- [8:0-1-8,Edge], [25:0-1-8,Edge], [30:Edge,0-1-8]									
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES
TCLL 40.0	Plate Grip DOL	1.00	TC 0.07	Vert(LL)	n/a	-	n/a	999	MT20
TCDL 10.0	Lumber DOL	1.00	BC 0.01	Vert(CT)	n/a	-	n/a	999	GRIP
BCLL 0.0	Rep Stress Incr	YES	WB 0.03	Horz(CT)	0.00	16	n/a	n/a	244/190
BCDL 5.0	Code IRC2021/TPI2014		Matrix-SH						Weight: 76 lb FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	
OTHERS 2x4 SP No.3(flat)	

REACTIONS. All bearings 17-5-12.
(lb) - Max Grav All reactions 250 lb or less at joint(s) 30, 16, 29, 28, 27, 26, 25, 24, 23, 21, 20, 19, 18, 17

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES- (6)
1) Gable requires continuous bottom chord bearing.
2) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
3) Gable studs spaced at 1-4-0 oc.
4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
5) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard




3/27/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

8.630 s Jul 12 2024 MiTek Industries, Inc. Fri Mar 28 16:21:52 2025 Page 1
ID:Wl8rkg6BK5SaRYCYGf9_0xywFJ5-ssH3BrvtJfTketijZmCWJdaehH8E?5Kaz9avHzWMkT

0-9-11
Scale = 1:28.6



REACTIONS. (lb/size) 21=942/0-3-6 (min. 0-1-8), 12=948/0-3-8 (min. 0-1-8)

TOP CHORD	2-3=-2028/0, 3-4=-2028/0, 4-5=-3259/0, 5-6=-3830/0, 6-7=-3780/0, 7-8=-3111/0, 8-9=-3111/0, 9-10=-1700/0
BOT CHORD	20-21=0/1226, 19-20=0/2785, 18-19=0/3830, 17-18=0/3830, 16-17=0/3830, 15-16=0/3619, 14-15=0/3619, 13-14=0/2529, 12-13=0/837
WEBS	5-18=-65/292, 6-17=-260/97, 5-19=-879/0, 4-19=0/650, 4-20=-986/0, 2-20=0/1044, 2-21=-1514/0, 6-16=-424/231, 7-16=0/374, 7-14=-648/0, 9-14=0/744, 9-13=-1079/0, 10-13=0/1122, 10-12=-1256/0

- 1) Unbalanced floor live loads have been considered for this design.
- 2) All plates are MT20 plates unless otherwise indicated.
- 3) Recommend 2x6 strongbacks, on edge, spaced at 10'-0" oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
- 4) CAUTION, Do not erect truss backwards.

A circular professional engineer seal for the State of North Carolina. The outer ring contains the text "NORTH CAROLINA" at the top and "ENGINEER" at the bottom. Inside this ring, the word "PROFESSIONAL" is at the top and "SEAL" is at the bottom. The center of the seal features the license number "28147" and the name "MARK K. MORRIS" in a stylized, slanted font. A red ink signature is written across the seal, overlapping the "PROFESSIONAL" and "SEAL" text.

3/27/2025


Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 Guide to *Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0040 HONEYCUTT HILLS 208 SHELBY MEADOW LANE ANGIER, NC
25-2569-F02	F202A	Floor	1	1	
Job Reference (optional)					# 57987

8.630 s Jul 12 2024 MiTek Industries, Inc. Fri Mar 28 16:21:53 2025 Page 1
ID:pMqJz?gO_6c5LWiSfGO4QyyWIk-K2rRPBwXedoKMoSvHHtr3XAIM5dFzSWUodv8RkzWMkS



Scale = 1:27.9



6-4-13	7-4-13	8-4-13	17-2-8
6-4-13	1-0-0	1-0-0	8-9-11

Plate Offsets (X,Y)-- [1:Edge,0-1-8], [5:0-1-8,Edge], [6:0-1-8,Edge]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.64	Vert(LL)	-0.29 16-17	>713	480	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.80	Vert(CT)	-0.39 16-17	>519	360	MT20HS	187/143
BCLL 0.0	Rep Stress Incr	YES	WB 0.52	Horz(CT)	0.06 12	n/a	n/a		
BCDL 5.0	Code IRC2021/TPI2014		Matrix-SH						
									Weight: 88 lb FT = 20%F, 11%E


LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 5-9-15 oc purlins, except end verticals.
BOT CHORD 2x4 SP SS(flat) *Except* B2: 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (lb/size) 21=933/Mechanical, 12=933/0-3-8 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1813/0, 3-4=-1813/0, 4-5=-3081/0, 5-6=-3687/0, 6-7=-3673/0, 7-8=-3039/0, 8-9=-3039/0, 9-10=-1668/0
BOT CHORD 20-21=0/995, 19-20=0/2587, 18-19=0/3687, 17-18=0/3687, 16-17=0/3687, 15-16=0/3533, 14-15=0/2478, 13-14=0/2478, 12-13=0/824
WEBS 5-18=-51/302, 6-17=-270/83, 5-19=-904/0, 4-19=0/666, 4-20=-1007/0, 2-20=0/1065, 2-21=-1342/0, 6-16=-387/257, 7-16=0/351, 7-15=-630/0, 9-15=0/716, 9-13=-1055/0, 10-13=0/1099, 10-12=-1235/0

NOTES- (5)
1) Unbalanced floor live loads have been considered for this design.
2) All plates are MT20 plates unless otherwise indicated.
3) Refer to girder(s) for truss to truss connections.
4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard





3/27/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0040 HONEYCUTT HILLS 208 SHELBY MEADOW LANE ANGIER, NC
25-2569-F02	F203	Floor	7	1	
Job Reference (optional)					# 57987

8.630 s Jul 12 2024 MiTek Industries, Inc. Fri Mar 28 16:21:53 2025 Page 1
ID:pMqJz?gO_6c5LWfSGO4QyyWlk-K2rRPBwXedoKMoSvHHtr3XApQ5dQzU3Uodv8RkzWMkS



6-4-13	7-4-13	8-4-13	15-1-0
6-4-13	1-0-0	1-0-0	6-8-3

LOADING (psf)				SPACING-				CSI.				DEFL.				PLATES		GRIP	
TCLL	40.0			Plate Grip DOL	1.00			TC	0.38			Vert(LL)	-0.16	11-12	>999	480	MT20		244/190
TCDL	10.0			Lumber DOL	1.00			BC	0.79			Vert(CT)	-0.21	11-12	>833	360			
BCLL	0.0			Rep Stress Incr	YES			WB	0.42			Horz(CT)	0.04	9	n/a	n/a			
BCDL	5.0			Code IRC2021/TPI2014				Matrix-SH											
Weight: 76 lb FT = 20%F, 11%E																			

LUMBER-				BRACING-			
TOP CHORD	2x4 SP No.1(flat)			TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.		
BOT CHORD	2x4 SP No.1(flat)			BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.		
WEBS	2x4 SP No.3(flat)						

REACTIONS. (lb/size) 16=816/Mechanical, 9=816/Mechanical

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1545/0, 3-4=-2532/0, 4-5=-2874/0, 5-6=-2601/0, 6-7=-1691/0
BOT CHORD 15-16=0/861, 14-15=0/2196, 13-14=0/2874, 12-13=0/2874, 11-12=0/2874, 10-11=0/2308, 9-10=0/1040
WEBS 4-14=-602/0, 3-14=0/485, 3-15=-847/0, 2-15=0/892, 2-16=-1161/0, 5-11=-542/0, 6-11=0/446, 6-10=-803/0, 7-10=0/847, 7-9=-1286/0

NOTES- (4)
1) Unbalanced floor live loads have been considered for this design.
2) Refer to girder(s) for truss to truss connections.
3) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard



3/27/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0040 HONEYCUTT HILLS 208 SHELBY MEADOW LANE ANGIER, NC
25-2569-F02	F205A	Floor	1	1	
Job Reference (optional)					# 57987

8.630 s Jul 12 2024 MiTek Industries, Inc. Fri Mar 28 16:21:54 2025 Page 1
ID:pMqJz?gO_6c5LWfSiGO4QyyWlk-oEPpcXw9PwwB_x15q_O4bkj?wV16izPd1Heh_AzWMkr





Plate Offsets (X,Y)-- [1:Edge,0-1-8], [4:0-1-8,Edge], [5:0-1-8,Edge]					
LOADING (psf)		SPACING-		CSI.	
TCLL 40.0		1-4-0		TC 0.27	
TCDL 10.0		Plate Grip DOL 1.00		BC 0.56	
BCLL 0.0		Lumber DOL 1.00		WB 0.29	
BCDL 5.0		Rep Stress Incr YES		Matrix-SH	
		Code IRC2021/TPI2014			
				DEFL. in (loc) l/defl L/d	
				Vert(LL) -0.12 12-13 >999 480	
				Vert(CT) -0.16 12-13 >999 360	
				Horz(CT) 0.03 9 n/a n/a	
				PLATES MT20	
				GRIP 244/190	
				Weight: 78 lb FT = 20%F, 11%E	

LUMBER-		BRACING-	
TOP CHORD 2x4 SP No.1(flat)		TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.	
BOT CHORD 2x4 SP No.1(flat)		BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.	
WEBS 2x4 SP No.3(flat)			

REACTIONS. (lb/size) 9=555/0-3-8 (min. 0-1-8), 17=555/Mechanical

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 8-9=-556/0, 2-3=-1055/0, 3-4=-1738/0, 4-5=-1990/0, 5-6=-1832/0, 6-7=-1252/0
BOT CHORD 16-17=0/586, 15-16=0/1500, 14-15=0/1990, 13-14=0/1990, 12-13=0/1990, 11-12=0/1651, 10-11=0/834
WEBS 4-15=-428/0, 3-15=0/340, 3-16=-579/0, 2-16=0/610, 2-17=-790/0, 5-12=-346/0, 6-12=0/289, 6-11=-519/0, 7-11=0/544, 7-10=-781/0, 8-10=0/565

NOTES- (4)
1) Unbalanced floor live loads have been considered for this design.
2) Refer to girder(s) for truss to truss connections.
3) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard




3/27/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D’Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0040 HONEYCUTT HILLS 208 SHELBY MEADOW LANE ANGIER, NC
25-2569-F02	F206	Floor	11	1	
Job Reference (optional)					# 57987

8.630 s Jul 12 2024 MiTek Industries, Inc. Fri Mar 28 16:21:54 2025 Page 1
ID:pMqJz?gO_6c5LWiSfiGO4QyyWlk-oEPpcXw9PwwB_x15q_O4bkjzhVvyvixld1Heh_AzWMkr



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.41	Vert(LL)	-0.18	12-13	>999	480	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.83	Vert(CT)	-0.24	12-13	>772	360		
BCLL 0.0	Rep Stress Incr	YES	WB 0.43	Horz(CT)	0.05	9	n/a	n/a		
BCDL 5.0	Code IRC2021/TPI2014		Matrix-SH						Weight: 79 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (lb/size) 9=847/0-3-8 (min. 0-1-8), 17=841/0-3-6 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 8-9=-849/0, 2-3=-1771/0, 3-4=-2758/0, 4-5=-3101/0, 5-6=-2829/0, 6-7=-1921/0, 7-8=-358/0

BOT CHORD 16-17=0/1084, 15-16=0/2422, 14-15=0/3101, 13-14=0/3101, 12-13=0/3101, 11-12=0/2536, 10-11=0/1277

WEBS 4-15=-620/0, 3-15=0/496, 3-16=-847/0, 2-16=0/894, 2-17=-1337/0, 5-12=-556/0, 6-12=0/457, 6-11=-800/0, 7-11=0/839, 7-10=-1197/0, 8-10=0/864

NOTES- (4)

1) Unbalanced floor live loads have been considered for this design.

2) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

3) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard



3/27/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D’Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0040 HONEYCUTT HILLS 208 SHELBY MEADOW LANE ANGIER, NC
25-2569-F02	F207	Floor Supported Gable	1	1	Job Reference (optional) # 57987

8.630 s Jul 12 2024 MiTek Industries, Inc. Fri Mar 28 16:21:54 2025 Page 1
ID:pMqJz?gO_6c5LWISfiGO4QyyWlk-oEPpcXw9PwwB_x15q_O4bkj3AV9qi1Sd1Heh_AzWMkR

0-1-8

Scale = 1:25.5




Plate Offsets (X,Y)-- [7:0-1-8,Edge], [21:0-1-8,Edge], [26:Edge,0-1-8]											
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d			PLATES GRIP		
TCLL	40.0	Plate Grip DOL	1.00	TC	0.06	Vert(LL)	n/a	-	n/a	999	MT20 244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.01	Vert(CT)	n/a	-	n/a	999	
BCLL	0.0	Rep Stress Incr	YES	WB	0.03	Horz(CT)	0.00	14	n/a	n/a	
BCDL	5.0	Code IRC2021/TPI2014		Matrix-SH							Weight: 69 lb FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	
OTHERS 2x4 SP No.3(flat)	

REACTIONS. All bearings 15-7-12.
(lb) - Max Grav All reactions 250 lb or less at joint(s) 26, 14, 25, 24, 23, 22, 21, 20, 19, 18, 17, 16, 15

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES- (6)
1) Gable requires continuous bottom chord bearing.
2) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
3) Gable studs spaced at 1-4-0 oc.
4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
5) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard



3/27/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0040 HONEYCUTT HILLS 208 SHELBY MEADOW LANE ANGIER, NC
25-2569-F02	F208	Floor Supported Gable	1	1	Job Reference (optional) # 57987

8.630 s Jul 12 2024 MiTek Industries, Inc. Fri Mar 28 16:21:55 2025 Page 1
ID:pMqJz?gO_6c5LWiSfIGO4QyyWlk-HRzBqtxoAE22b5bHOivJ8yFEWuV2RUhmGxOEWczWMkQ

0-1-8

0-1-8

Scale = 1:21.2




Plate Offsets (X,Y)-- [6:0-1-8,Edge], [18:0-1-8,Edge], [22:Edge,0-1-8]									
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES
TCLL 40.0	Plate Grip DOL	1.00	TC 0.06	Vert(LL)	n/a	-	n/a	999	MT20
TCDL 10.0	Lumber DOL	1.00	BC 0.01	Vert(CT)	n/a	-	n/a	999	GRIP
BCLL 0.0	Rep Stress Incr	YES	WB 0.03	Horz(CT)	0.00	12	n/a	n/a	244/190
BCDL 5.0	Code IRC2021/TPI2014		Matrix-SH						Weight: 58 lb FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	
OTHERS 2x4 SP No.3(flat)	

REACTIONS. All bearings 12-11-12.
(lb) - Max Grav All reactions 250 lb or less at joint(s) 22, 12, 21, 20, 19, 18, 17, 16, 15, 14, 13

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES- (5)
1) Gable requires continuous bottom chord bearing.
2) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
3) Gable studs spaced at 1-4-0 oc.
4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard




3/27/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0040 HONEYCUTT HILLS 208 SHELBY MEADOW LANE ANGIER, NC
25-2569-F02	F209	Floor	2	1	
Job Reference (optional)					# 57987

8.630 s Jul 12 2024 MiTek Industries, Inc. Fri Mar 28 16:21:56 2025 Page 1
ID:pMqJz?gO_6c5LWsfGO4QyyWlkldXa1CyQxYAvDFAUyPQYh9oKWlIFaq6wVb7o22zWMkP



LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 40.0	2-0-0	TC 0.32	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.00	BC 0.58	Vert(LL) -0.10 11-12 >999 480		
BCLL 0.0	Lumber DOL 1.00	WB 0.47	Vert(CT) -0.13 9-10 >999 360		
BCDL 5.0	Rep Stress Incr YES	Matrix-SH	Horz(CT) 0.03 7 n/a n/a		
	Code IRC2021/TPI2014			Weight: 65 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (lb/size) 14=694/0-3-6 (min. 0-1-8), 7=694/0-3-6 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 14-15=-688/0, 1-15=-687/0, 7-16=-688/0, 6-16=-687/0, 1-2=-836/0, 2-3=-1812/0, 3-4=-2109/0, 4-5=-1812/0, 5-6=-836/0

BOT CHORD 12-13=0/1506, 11-12=0/2109, 10-11=0/2109, 9-10=0/2109, 8-9=0/1506


WEBS 3-12=-507/0, 2-12=0/427, 2-13=-872/0, 1-13=0/984, 4-9=-507/0, 5-9=0/427, 5-8=-872/0, 6-8=0/984

NOTES- (3)

1) Unbalanced floor live loads have been considered for this design.

2) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard



3/27/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0040 HONEYCUTT HILLS 208 SHELBY MEADOW LANE ANGIER, NC
25-2569-F02	F210	Floor	3	1	
Job Reference (optional)					# 57987

8.630 s Jul 12 2024 MiTek Industries, Inc. Fri Mar 28 16:21:56 2025 Page 1
ID:pMqJz?gO_6c5LWISfiGO4QyyWlk-ldXa1CyQxYAvDFAUyPQYh9oCZleiAsSwVb7o22zWMkP




Plate Offsets (X,Y)-- [7:0-1-8,Edge], [8:0-1-8,Edge], [13:Edge,0-3-0], [24:Edge,0-3-0]		8-5-15		9-5-15	10-5-15	11-8-1	12-8-10	19-3-4
		8-5-15		1-0-0	1-0-0	0-1-8	1-0-9	6-5-2
LOADING (psf)		SPACING-		CSI.		DEFL.		PLATES
TCLL 40.0		2-0-0		TC 0.83		in (loc) l/defl L/d		GRIP
TCDL 10.0		Plate Grip DOL 1.00		BC 0.88		Vert(LL) -0.25 20-21 >612 480		MT20
BCLL 0.0		Lumber DOL 1.00		WB 0.38		Vert(CT) -0.34 20-21 >451 360		244/190
BCDL 5.0		Rep Stress Incr YES		Matrix-SH		Horz(CT) 0.03 13 n/a n/a		
		Code IRC2021/TPI2014						Weight: 100 lb FT = 20%F, 11%E


LUMBER-		BRACING-	
TOP CHORD 2x4 SP No.1(flat)		TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.	
BOT CHORD 2x4 SP SS(flat) *Except*		BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except:	
B2: 2x4 SP No.1(flat)		6-0-0 oc bracing: 17-18,16-17.	
WEBS 2x4 SP No.3(flat)			

REACTIONS. (lb/size) 24=697/0-3-6 (min. 0-1-8), 17=1035/0-3-8 (min. 0-1-8), 13=348/0-3-6 (min. 0-1-8)
Max Grav 24=703(LC 3), 17=1035(LC 1), 13=376(LC 7)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1058/0, 3-4=-1954/0, 4-5=-1954/0, 5-6=-1954/0, 6-7=-2133/0, 7-8=-1724/0,
8-9=-668/0, 9-10=-476/0, 10-11=-559/0
BOT CHORD 23-24=0/442, 22-23=0/1639, 21-22=0/2254, 20-21=0/1724, 19-20=0/1724, 18-19=0/1724,
15-16=0/698, 14-15=0/698, 13-14=0/384
WEBS 7-20=-399/0, 8-19=0/456, 9-17=-914/0, 7-21=0/562, 6-22=-383/0, 3-22=0/402,
3-23=-756/0, 2-23=0/803, 2-24=-870/0, 8-18=-1360/0, 9-18=0/775, 9-16=0/408,
10-16=-376/0, 11-13=-511/0

NOTES- (4)
1) Unbalanced floor live loads have been considered for this design.
2) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
3) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard




3/27/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0040 HONEYCUTT HILLS 208 SHELBY MEADOW LANE ANGIER, NC
25-2569-F02	F211	Floor	5	1	
Job Reference (optional)					# 57987

8.630 s Jul 12 2024 MiTek Industries, Inc. Fri Mar 28 16:21:57 2025 Page 1
ID:pMqJz?gO_6c5LW5fiGO4QyyWlk-Dp5yEYz2irlmrPlgW6ynDNKT6izlvHp3JfLaVzWMkO



LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 40.0	1-7-3	TC 0.46	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.00	BC 0.92	Vert(LL) -0.31 19-20 >747 480		
BCLL 0.0	Lumber DOL 1.00	WB 0.50	Vert(CT) -0.42 19-20 >542 360		
BCDL 5.0	Rep Stress Incr YES	Matrix-SH	Horz(CT) 0.07 14 n/a n/a		
	Code IRC2021/TPI2014			Weight: 98 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except:
WEBS 2x4 SP No.3(flat)	2-2-0 oc bracing: 19-20.

REACTIONS. (lb/size) 24=831/0-3-6 (min. 0-1-8), 14=831/0-3-6 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-1325/0, 3-4=-2720/0, 4-5=-2720/0, 5-6=-2720/0, 6-7=-3509/0, 7-8=-3788/0, 8-9=-3565/0, 9-10=-2835/0, 10-11=-2835/0, 11-12=-1502/0

BOT CHORD 23-24=0/513, 22-23=0/2114, 21-22=0/3233, 20-21=0/3788, 19-20=0/3788, 18-19=0/3788, 17-18=0/3324, 16-17=0/2263, 15-16=0/2263, 14-15=0/717


WEBS 7-21=-579/9, 6-21=0/454, 6-22=-656/0, 3-22=0/773, 3-23=-1028/0, 2-23=0/1057, 2-24=-1008/0, 8-18=-531/57, 9-18=0/423, 9-17=-624/0, 11-17=0/730, 11-15=-990/0, 12-15=0/1022, 12-14=-1096/0

NOTES- (3)

1) Unbalanced floor live loads have been considered for this design.

2) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard




3/27/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0040 HONEYCUTT HILLS 208 SHELBY MEADOW LANE ANGIER, NC
25-2569-F02	F212	Floor	5	1	
Job Reference (optional)					# 57987

8.630 s Jul 12 2024 MiTek Industries, Inc. Fri Mar 28 16:21:57 2025 Page 1
ID:pMqJz?gO_6c5LWsfGO4QyyWlk-Dp5yEYz2IrlmrPlgW6ynDNKT5izGvHp3jFlLaVzWMkO



LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 40.0	1-7-3	TC 0.46	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.00	BC 0.92	Vert(LL) -0.31 19-20 >745 480		
BCLL 0.0	Lumber DOL 1.00	WB 0.50	Vert(CT) -0.42 19-20 >541 360		
BCDL 5.0	Rep Stress Incr YES	Matrix-SH	Horz(CT) 0.07 14 n/a n/a		
	Code IRC2021/TPI2014			Weight: 99 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 2-2-0 oc bracing: 19-20.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (lb/size) 24=832/0-3-6 (min. 0-1-8), 14=837/0-3-8 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-1326/0, 3-4=-2722/0, 4-5=-2722/0, 5-6=-2722/0, 6-7=-3512/0, 7-8=-3792/0, 8-9=-3570/0, 9-10=-2841/0, 10-11=-2841/0, 11-12=-1510/0

BOT CHORD 23-24=0/513, 22-23=0/2116, 21-22=0/3236, 20-21=0/3792, 19-20=0/3792, 18-19=0/3792, 17-18=0/3330, 16-17=0/2270, 15-16=0/2270, 14-15=0/725

WEBS 7-21=-581/9, 6-21=0/455, 6-22=-656/0, 3-22=0/774, 3-23=-1028/0, 2-23=0/1058, 2-24=-1008/0, 8-18=-531/59, 9-18=0/423, 9-17=-624/0, 11-17=0/730, 11-15=-989/0, 12-15=0/1022, 12-14=-1101/0


NOTES- (4)

1) Unbalanced floor live loads have been considered for this design.

2) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

3) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard




3/27/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0040 HONEYCUTT HILLS 208 SHELBY MEADOW LANE ANGIER, NC
25-2569-F02	F213	Floor	3	1	
Job Reference (optional)					# 57987

8.630 s Jul 12 2024 MiTek Industries, Inc. Fri Mar 28 16:21:58 2025 Page 1
ID:pMqJz?gO_6c5LWiSfGO4QyyWlk-h0fKSu_gT9QdSZKs3qT0matf16JlejCDyvcu7xzWMkN



LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.43	Vert(LL)	-0.29 19-20	>785	480	MT20	244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.87	Vert(CT)	-0.40 19-20	>569	360		
BCLL 0.0	Rep Stress Incr YES	WB 0.49	Horz(CT)	0.07 14	n/a	n/a		
BCDL 5.0	Code IRC2021/TPI2014	Matrix-SH					Weight: 98 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (lb/size) 24=819/0-3-6 (min. 0-1-8), 14=824/Mechanical

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-1303/0, 3-4=-2667/0, 4-5=-2667/0, 5-6=-2667/0, 6-7=-3426/0, 7-8=-3678/0, 8-9=-3426/0, 9-10=-2667/0, 10-11=-2667/0, 11-12=-1303/0

BOT CHORD 23-24=0/505, 22-23=0/2077, 21-22=0/3168, 20-21=0/3678, 19-20=0/3678, 18-19=0/3678, 17-18=0/3168, 16-17=0/2077, 15-16=0/2077, 14-15=0/506

WEBS 7-21=-549/27, 6-21=0/434, 6-22=-640/0, 3-22=0/753, 3-23=-1008/0, 2-23=0/1038, 2-24=-994/0, 8-18=-549/27, 9-18=0/434, 9-17=-640/0, 11-17=0/752, 11-15=-1008/0, 12-15=0/1038, 12-14=-989/0

NOTES- (5)


1) Unbalanced floor live loads have been considered for this design.

2) Refer to girder(s) for truss to truss connections.

3) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

4) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard



3/27/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0040 HONEYCUTT HILLS 208 SHELBY MEADOW LANE ANGIER, NC
25-2569-F02	F214	FLOOR	1	1	
Job Reference (optional)					# 57987

8.630 s Jul 12 2024 MiTek Industries, Inc. Fri Mar 28 16:21:58 2025 Page 1
ID:pMqJz?gO_6c5LWsfGO4QyyWlk-h0fKSu_gT9QdSZKs3qT0mathi6V1eoADyvcu7xzWMkN




Plate Offsets (X,Y)-- [8:Edge,0-1-8]									
LOADING (psf)		SPACING-		CSI.		DEFL.		PLATES	
TCLL	40.0	2-0-0	Plate Grip DOL	1.00	TC	0.28	in (loc)	L/defl	L/d
TCDL	10.0	1.00	Lumber DOL	1.00	BC	0.12	Vert(LL)	-0.01	6 >999 480
BCLL	0.0	YES	Rep Stress Incr	YES	WB	0.18	Vert(CT)	-0.01	6-7 >999 360
BCDL	5.0	Code IRC2021/TPI2014	Code IRC2021/TPI2014		Matrix-P		Horz(CT)	0.00	5 n/a n/a
								Weight: 35 lb	FT = 20%F, 11%E

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.1(flat)	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.1(flat)	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3(flat)		

REACTIONS. (lb/size) 8=332/0-3-8 (min. 0-1-8), 5=332/Mechanical

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-8=-327/0, 1-2=-295/0, 2-3=-422/0

BOT CHORD 6-7=0/538, 5-6=0/275


WEBS 1-7=0/370, 2-7=-317/0, 3-5=-416/0

NOTES- (3)

1) Refer to girder(s) for truss to truss connections.

2) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard




3/27/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0040 HONEYCUTT HILLS 208 SHELBY MEADOW LANE ANGIER, NC
25-2569-F02	F215	FLOOR	6	1	
Job Reference (optional)					# 57987

8.630 s Jul 12 2024 MiTek Industries, Inc. Fri Mar 28 16:21:58 2025 Page 1
ID:pMqJz?gO_6c5LWsfGO4QyyWik-h0fKSu_gT9QdSZKs3qT0matc86HHejHDyvcu7xzWMkN



LOADING (psf)	SPACING-	1-6-0	CSI.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.64	Vert(LL)	-0.43	22	>575	480	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 1.00	Vert(CT)	-0.60	22	>418	360	MT20HS	187/143
BCLL 0.0	Rep Stress Incr	YES	WB 0.49	Horz(CT)	0.08	13	n/a	n/a		
BCDL 5.0	Code IRC2021/TPI2014		Matrix-SH							
										Weight: 113 lb FT = 20%F, 11%E

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.1(flat)	TOP CHORD	Structural wood sheathing directly applied or 5-7-1 oc purlins, except end verticals. Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 2-2-0 oc bracing: 18-20.
BOT CHORD	2x4 SP No.1(flat)	BOT CHORD	
WEBS	2x4 SP No.3(flat)		

REACTIONS. (lb/size) 26=856/0-3-8 (min. 0-1-8), 13=851/0-3-6 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 13-27=-853/0, 12-27=-851/0, 2-3=-1815/0, 3-4=-3107/0, 4-5=-3107/0, 5-6=-3947/0, 6-7=-3947/0, 7-8=-4218/0, 8-9=-4008/0, 9-10=-3550/0, 10-11=-2316/0, 11-12=-615/0

BOT CHORD 25-26=0/1025, 24-25=0/2580, 23-24=0/3613, 22-23=0/4175, 21-22=0/4253, 20-21=0/4253, 19-20=0/3550, 18-19=0/3522, 17-18=0/3550, 16-17=0/3550, 15-16=0/1537, 14-15=0/1538

WEBS 9-18=-545/0, 10-17=0/736, 9-20=-24/716, 8-20=-363/31, 7-23=-292/0, 5-23=0/426, 5-24=-659/0, 3-24=0/685, 3-25=-996/0, 2-25=0/1028, 2-26=-1311/0, 10-16=-1540/0, 11-16=0/987, 11-14=-1202/0, 12-14=0/969

- NOTES- (5)
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) All plates are MT20 plates unless otherwise indicated.
 - 3) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 4) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard



3/27/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

8.630 s Jul 12 2024 MiTek Industries, Inc. Fri Mar 28 16:21:59 2025 Page 1
ID:pMqJz?gO_6c5LWiSfiGO4QyyWlk-9CCiFe_IETyU4jv3dX_FloQrpWpKNDOMBZMSfnzWmKkM

1-3-0

Scale = 1:16.8

1 3x6 =

2 3x4 =

3 1.5x3 ||

4 3x4 =

5 3x4 =

6 3x4 ||

7

8 3x4 =

9 3x8 =

10 3x4 =

T1

B1

W1

1-2-0

9-4-8

9-4-8

Plate Offsets (X,Y)-- [11:Edge,0-1-8]

LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.32	Vert(LL) -0.02 9 >999 480	MT20	244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.24	Vert(CT) -0.03 8-9 >999 360		
BCLL 0.0	Rep Stress Incr NO	WB 0.31	Horz(CT) 0.01 7 n/a n/a		
BCDL 5.0	Code IRC2021/TPI2014	Matrix-SH		Weight: 51 lb	FT = 20%F, 11%E

LUMBER-

TOP CHORD 2x4 SP No.1(flat)
BOT CHORD 2x4 SP No.1(flat)
WEBS 2x4 SP No.3(flat)

BRACING-

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 10-11.

REACTIONS. (lb/size) 11=502/0-3-8 (min. 0-1-8), 7=502/0-3-8 (min. 0-1-8)

Max Uplift11=-56(LC 6), 7=-56(LC 7)
Max Grav 11=528(LC 3), 7=528(LC 2)


FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-11=-523/60, 1-2=-562/78, 2-3=-1072/0, 3-4=-1072/0, 4-5=-870/6
BOT CHORD 9-10=-14/954, 8-9=0/1109, 7-8=-75/627
WEBS 1-10=-121/723, 2-10=-648/149, 2-9=-206/315, 4-9=-253/254, 4-8=-434/199, 5-8=-153/479, 5-7=-804/118

NOTES- (5)

- 1) Unbalanced floor live loads have been considered for this design.
- 2) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 56 lb uplift at joint 11 and 56 lb uplift at joint 7.
- 3) This truss has been designed for a total drag load of 150 plf. Lumber DOL=(1.33) Plate grip DOL=(1.33) Connect truss to resist drag loads along bottom chord from 0-0-0 to 9-4-8 for 150.0 plf.
- 4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard





3/27/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 Guide to *Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D’Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0040 HONEYCUTT HILLS 208 SHELBY MEADOW LANE ANGIER, NC
25-2569-F02	F217	Floor	4	1	
Job Reference (optional)					# 57987

8.630 s Jul 12 2024 MiTek Industries, Inc. Fri Mar 28 16:21:59 2025 Page 1
ID:pMqJz?gO_6c5LWISfGO4QyyWlk-9CCifE_IETYU4jv3dX_FloQsIWIKNC1MBZMSfNzWMkM



4-9-11	5-9-11	6-9-11	11-7-6
4-9-11	1-0-0	1-0-0	4-9-11

Plate Offsets (X,Y)-- [3:0-1-8,Edge], [4:0-1-8,Edge], [6:0-1-8,Edge], [14:Edge,0-1-8]					
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc) l/defl L/d
TCLL 40.0	Plate Grip DOL	1.00	TC 0.26	Vert(LL)	-0.08 9-10 >999 480
TCDL 10.0	Lumber DOL	1.00	BC 0.50	Vert(CT)	-0.09 9-10 >999 360
BCLL 0.0	Rep Stress Incr	YES	WB 0.33	Horz(CT)	0.02 7 n/a n/a
BCDL 5.0	Code IRC2021/TPI2014		Matrix-SH		
				PLATES	GRIP
				MT20	244/190
				Weight: 60 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (lb/size) 14=625/0-3-8 (min. 0-1-8), 7=619/0-3-6 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-14=-624/0, 7-15=-619/0, 6-15=-618/0, 1-2=-424/0, 2-3=-1373/0, 3-4=-1681/0, 4-5=-1373/0, 5-6=-426/0
BOT CHORD 12-13=0/1056, 11-12=0/1681, 10-11=0/1681, 9-10=0/1681, 8-9=0/1055
WEBS 3-12=-476/0, 2-12=0/413, 2-13=-822/0, 1-13=0/693, 4-9=-476/0, 5-9=0/414, 5-8=-818/0, 6-8=0/669

NOTES- (4)
1) Unbalanced floor live loads have been considered for this design.
2) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
3) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard



3/27/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.