


Project: Address: 4/15/2025

Input by: Curtis Quick Job Name: Plan 1 Beams Page 1 of 9

Project #:

1.750" X 11.875" 2-Ply - PASSED **Kerto-S LVL GDH**

Level: Level



Member Infor	mation		Rea	Reactions UNPATTERNED lb (Uplift)							
Type:	Girder	Application:	Floor	Brg	Direction	Live	[Dead	Snow	Wind	Const
Plies:	2	Design Method:	ASD	1	Vertical	0		2182	0	0	0
Moisture Condition	n: Dry	Building Code:	IBC/IRC 2015	2	Vertical	0		2182	0	0	0
Deflection LL:	480	Load Sharing:	No								
Deflection TL:	360	Deck:	Not Checked								
Importance:	Normal - II										
Temperature:	Temp <= 100°F			_							
				Bea	rings						
				Bea	aring Length	Dir.	Cap. F	React D/L lb	Total	Ld. Case	Ld. Comb.
				1 -	SPF 3.500"	Vert	42%	2182 / 0	2182	Uniform	D
		ļ		2 -	SPF 3.500"	Vert	42%	2182 / 0	2182	Uniform	D

Analysis Results

Analysis	Actual	Location	Allowed	Capacity	Comb.	Case
Moment	8689 ft-lb	8'5"	17919 ft-lb	0.485 (48%)	D	Uniform
Unbraced	8689 ft-lb	8'5"	8702 ft-lb	0.998 (100%)	D	Uniform
Shear	1859 lb	15'6 5/8"	7980 lb	0.233 (23%)	D	Uniform
LL Defl inch	0.000 (L/999)	0	999.000 (L/0)	0.000 (0%)		
TL Defl inch	0.453 (L/433)	8'5 1/16"	0.546 (L/360)	0.831 (83%)	D	Uniform

Design Notes

- 1 Provide support to prevent lateral movement and rotation at the end bearings. Lateral support may also be required at the interior bearings by the building code.
- 2 Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c. Maximum end distance not to exceed 6".
- 3 Refer to last page of calculations for fasteners required for specified loads.
- 4 Girders are designed to be supported on the bottom edge only.
- 5 Top loads must be supported equally by all plies.
- 6 Top must be laterally braced at a maximum of 10'8 15/16" o.c.
- 7 Bottom must be laterally braced at end bearings.
- 8 Lateral slenderness ratio based on single ply width.

ID	Load Type	Location	Trib Width	Side	Dead 0.9	Live 1	Snow 1.15	Wind 1.6	Const. 1.25	Comments
1	Uniform			Тор	250 PLF	0 PLF	0 PLF	0 PLF	0 PLF	
	Self Weight				9 PLF					

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

- Dry service conditions, unless noted otherwise
 LVL not to be treated with fire retardant or corrosive
- Handling & Installation
- LVL beams must not be cut or drilled
 Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals

 2 Damaged Beams must not be used
- Design assumes top edge is laterally restrained
 Provide lateral support at bearing points to avoid
 lateral displacement and rotation
- 6. For flat roofs provide proper drainage to prevent ponding

 Manufacturer Info

This design is valid until 6/28/2026

,	Metsä Wood 301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851 (800) 622-5850 www.metsawood.com/us

Client: Wellco Contractors


Project: Address: 4/15/2025

Input by: Curtis Quick Job Name: Plan 1 Beams Page 2 of 9

Project #:

1.750" X 11.875" 2-Ply - PASSED **GDH Kerto-S LVL**

Level: Level



Multi-Ply Analysis

Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c.. Maximum end distance not to exceed 6".

·		
Capacity	0.0 %	
Load	0.0 PLF	
Yield Limit per Foot	163.7 PLF	
Yield Limit per Fastener	81.9 lb.	
См	1	
Yield Mode	IV	
Edge Distance	1 1/2"	
Min. End Distance	3"	
Load Combination		
Duration Factor	1 00	

Notes

NOtes
Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

Dry service conditions, unless noted otherwise
 LVL not to be treated with fire retardant or corrosive

Handling & Installation

- Handling & Installation

 1. UVI beams must not be cut or drilled

 2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals

 3. Damaged Beams must not be used

 4. Design assumes top edge is laterally restrained

 5. Provide lateral support at bearing points to avoid lateral displacement and rotation
- For flat roofs provide proper drainage to prevent ponding

This design is valid until 6/28/2026

Metsä Wood 301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851 (800) 622-5850 www.metsawood.com/us

Manufacturer Info




Project: Address: Date: 4/15/2025 Input by: Curtis Quick


Project #:

1.750" X 9.250" 2-Ply - PASSED Kerto-S LVL BM1

Level: Level

Job Name: Plan 1 Beams





Page 3 of 9

Member Information

Type: Plies: 2 Moisture Condition: Dry Deflection LL: 480 Deflection TL: 360 Importance: Normal - II Temp <= 100°F Temperature:

Application: Design Method: ASD **Building Code: IBC/IRC 2015** Load Sharing: No Deck: Not Checked

Reactions UNPATTERNED Ib (Uplift) Live Wind Brg Direction Dead Snow Const 0 1828 1804 0 Vertical 0 2 Vertical 0 1828 1804 0 0

Bearings

Bearing Length Dir. Cap. React D/L lb Total Ld. Case Ld. Comb. D+S 1 - SPF 3.500" Vert 1828 / 1804 3631 L 2 - SPF 3.500" Vert 70% 1828 / 1804 3631 L D+S

Analysis Results

Analysis	Actual	Location	Allowed	Capacity	Comb.	Case
Moment	5173 ft-lb	3'3 1/2"	14423 ft-lb	0.359 (36%)	D+S	L
Unbraced	5173 ft-lb	3'3 1/2"	10451 ft-lb	0.495 (50%)	D+S	L
Shear	2465 lb	1' 3/4"	7943 lb	0.310 (31%)	D+S	L
LL Defl inch	0.047 (L/1573)	3'3 1/2"	0.153 (L/480)	0.305 (31%)	S	L
TL Defl inch	0.094 (L/781)	3'3 1/2"	0.204 (L/360)	0.461 (46%)	D+S	L

Design Notes

- 1 Provide support to prevent lateral movement and rotation at the end bearings. Lateral support may also be required at the interior bearings by the building code.
- 2 Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c. Maximum end distance not to exceed 6".
- 3 Refer to last page of calculations for fasteners required for specified loads.
- 4 Girders are designed to be supported on the bottom edge only.
- 5 Top loads must be supported equally by all plies.
- 6 Top must be laterally braced at end bearings.
- 7 Bottom must be laterally braced at end bearings.
- 8 Lateral slenderness ratio based on single ply width.

ID	Load Type	Location	Trib Width	Side	Dead 0.9	Live 1	Snow 1.15	Wind 1.6	Const. 1.25	Comments
1	Uniform			Тор	548 PLF	0 PLF	548 PLF	0 PLF	0 PLF	A1
	Self Weight				7 PLF					

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

- Dry service conditions, unless noted otherwise
 LVL not to be treated with fire retardant or corrosive
- Handling & Installation
- LVL beams must not be cut or drilled
 Refer to manufacturer's product information
 regarding installation requirements, multi-ply
 fastening details, beam strength values, and code
 approvals
- Damaged Beams must not be used
- Design assumes top edge is laterally restrained
 Provide lateral support at bearing points to avoid
 lateral displacement and rotation
- 6. For flat roofs provide proper drainage to prevent ponding

This design is valid until 6/28/2026

Jarsian 22 40 70E	Dowarad	h. C+r. c+TM	Datacati	24051401	1520
Version 23.40.705	Powered	by istruct	Dataset.	24031401.	1323

Client: Wellco Contractors

Project: Address: Date: 4/15/2025

Input by: Curtis Quick Job Name: Plan 1 Beams


Project #:


Kerto-S LVL BM1

1.750" X 9.250"

2-Ply - PASSED

Level: Level





Page 4 of 9

Multi-Ply Analysis

Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c.. Maximum end distance not to exceed 6".

Capacity	0.0 %	
Load	0.0 PLF	
Yield Limit per Foot	163.7 PLF	
Yield Limit per Fastener	81.9 lb.	
См	1	
Yield Mode	IV	
Edge Distance	1 1/2"	
Min. End Distance	3"	
Load Combination		
Duration Factor	1.00	

Notes

NOtes
Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

- Dry service conditions, unless noted otherwise
 LVL not to be treated with fire retardant or corrosive

Handling & Installation

- Handling & Installation

 1. UVI beams must not be cut or drilled

 2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals

 3. Damaged Beams must not be used

 4. Design assumes top edge is laterally restrained

 5. Provide lateral support at bearing points to avoid lateral displacement and rotation

6. For flat roofs provide proper drainage to prevent ponding

This design is valid until 6/28/2026

Manufacturer Info

Metsä Wood 301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851

(800) 622-5850 www.metsawood.com/us



Project: Address: Date: 4/15/2025 Input by: Curtis Quick

Job Name: Plan 1 Beams

Project #:

Kerto-S LVL BM₂


1.750" X 9.250"


2-Ply - PASSED

2

Vertical

Level: Level





0

0

0

Page 5 of 9

Member Information

Type: Plies: 2 Moisture Condition: Dry Deflection LL: 480 Deflection TL: 360 Importance: Normal - II Temperature: Temp <= 100°F

Application: Design Method: ASD **Building Code: IBC/IRC 2015** Load Sharing: No Deck: Not Checked

Reactions UNPATTERNED Ib (Uplift) Live Wind Brg Direction Dead Snow Const 0 1621 1598 0 Vertical

2000

1976

0

Bearings Bearing Length Dir. Cap. React D/L lb Total Ld. Case Ld. Comb. D+S 1 - SPF 3.500" Vert 62% 1621 / 1598 3219 L 2 - SPF 3.500" Vert 76% 2000 / 1976 3976 L D+S

Analysis Results

Analysis	Actual	Location	Allowed	Capacity	Comb.	Case
Moment	7321 ft-lb	2'6 1/8"	14423 ft-lb	0.508 (51%)	D+S	L
Unbraced	7321 ft-lb	2'6 1/8"	10451 ft-lb	0.701 (70%)	D+S	L
Shear	3386 lb	5'6 1/4"	7943 lb	0.426 (43%)	D+S	L
LL Defl inch	0.062 (L/1192)	3'2 1/16"	0.153 (L/480)	0.403 (40%)	S	L
TL Defl inch	0.124 (L/593)	3'2 1/16"	0.204 (L/360)	0.607 (61%)	D+S	L

Design Notes

- 1 Provide support to prevent lateral movement and rotation at the end bearings. Lateral support may also be required at the interior bearings by the building code.
- 2 Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c. Maximum end distance not to exceed 6".
- 3 Refer to last page of calculations for fasteners required for specified loads.
- 4 Girders are designed to be supported on the bottom edge only.
- 5 Top loads must be supported equally by all plies.
- 6 Top must be laterally braced at end bearings.
- 7 Bottom must be laterally braced at end bearings.
- 8 Lateral slenderness ratio based on single ply width.

	-	, , ,							
II	D Load Type	Location Trib Widtl	n Side	Dead 0.9	Live 1	Snow 1.15	Wind 1.6	Const. 1.25	Comments
1	l Point	2-6-2	Тор	1834 lb	0 lb	1834 lb	0 lb	0 lb	C2
	Bearing Length	0-3-8							
2	Point	3-9-6	Тор	870 lb	0 lb	870 lb	0 lb	0 lb	C1
	Bearing Length	0-3-8							
3	Point	5-9-6	Тор	870 lb	0 lb	870 lb	0 lb	0 lb	C1

Continued on page 2...

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.


- Dry service conditions, unless noted otherwise
 LVL not to be treated with fire retardant or corrosive
- Handling & Installation
- andling & Instantation.

 LVL beams must not be cut or drilled

 Refer to manufacturer's product information regarding installation requirements, multi-ply
- 6. For flat roofs provide proper drainage to prevent ponding

	iastering details, bearn strength val
	approvals
3.	Damaged Beams must not be used
4	Design assumes ton adap is leterally

- Design assumes top edge is laterally restrained
 Provide lateral support at bearing points to avoid lateral displacement and rotation
 - This design is valid until 6/28/2026



Client: Wellco Contractors

Project: Address: Date: 4/15/2025

Input by: Curtis Quick Job Name: Plan 1 Beams


Project #:


Kerto-S LVL BM2

1.750" X 9.250"

2-Ply - PASSED

Level: Level





Page 7 of 9

Multi-Ply Analysis

Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c.. Maximum end distance not to exceed 6".

Capacity	0.0 %
Load	0.0 PLF
Yield Limit per Foot	163.7 PLF
Yield Limit per Fastener	81.9 lb.
См	1
Yield Mode	IV
Edge Distance	1 1/2"
Min. End Distance	3"
Load Combination	
Duration Factor	1 00

Notes

NOtes
Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

- Dry service conditions, unless noted otherwise
 LVL not to be treated with fire retardant or corrosive

Handling & Installation

- Handling & Installation

 1. UVI beams must not be cut or drilled

 2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals

 3. Damaged Beams must not be used

 4. Design assumes top edge is laterally restrained

 5. Provide lateral support at bearing points to avoid lateral displacement and rotation
- 6. For flat roofs provide proper drainage to prevent ponding

This design is valid until 6/28/2026



Project: Address: Date: 4/15/2025 Input by: Curtis Quick


Job Name: Plan 1 Beams


Project #:

1.750" X 9.250" 2-Ply - PASSED **Kerto-S LVL** BM₃

Level: Level

Reactions UNPATTERNED Ib (Uplift)





Page 8 of 9

Member Information

Type:	Girder
Plies:	2
Moisture Condition:	Dry
Deflection LL:	480
Deflection TL:	360
Importance:	Normal - II
Temperature:	Temp <= 100°F

Application: Design Method: ASD **Building Code: IBC/IRC 2015** Load Sharing: No Deck: Not Checked

Direction Live Snow Wind Brg Dead Const 0 1439 0 Vertical 1415 0 2 Vertical 0 1439 1415 0 0

Bearings

Bearing	Length	Dir.	Cap. I	React D/L lb	Total	Ld. Case	Ld. Comb
1 - SPF	3.500"	Vert	55%	1439 / 1415	2855	L	D+S
2 - SPF	3 500"	Vert	55%	1439 / 1415	2855	1	D+S

Analysis Results

Analysis	Actual	Location	Allowed	Capacity	Comb.	Case
Moment	4067 ft-lb	3'3 1/2"	14423 ft-lb	0.282 (28%)	D+S	L
Unbraced	4067 ft-lb	3'3 1/2"	10451 ft-lb	0.389 (39%)	D+S	L
Shear	1939 lb	5'6 1/4"	7943 lb	0.244 (24%)	D+S	L
LL Defl inch	0.037 (L/2004)	3'3 1/2"	0.153 (L/480)	0.239 (24%)	S	L
TL Defl inch	0.074 (L/994)	3'3 1/2"	0.204 (L/360)	0.362 (36%)	D+S	L

Design Notes

- 1 Provide support to prevent lateral movement and rotation at the end bearings. Lateral support may also be required at the interior bearings by the building code.
- 2 Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c. Maximum end distance not to exceed 6".
- 3 Refer to last page of calculations for fasteners required for specified loads.
- 4 Girders are designed to be supported on the bottom edge only.
- 5 Top loads must be supported equally by all plies.
- 6 Top must be laterally braced at end bearings.
- 7 Bottom must be laterally braced at end bearings.
- 8 Lateral slenderness ratio based on single ply width.

ID	Load Type	Location	Trib Width	Side	Dead 0.9	Live 1	Snow 1.15	Wind 1.6	Const. 1.25	Comments
1	Uniform			Тор	430 PLF	0 PLF	430 PLF	0 PLF	0 PLF	B1
	Self Weight				7 PLF					

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

- Dry service conditions, unless noted otherwise
 LVL not to be treated with fire retardant or corrosive
- Handling & Installation
- LVL beams must not be cut or drilled
 Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals

 2 Damaged Beams must not be used

- Design assumes top edge is laterally restrained
 Provide lateral support at bearing points to avoid
 lateral displacement and rotation
- 6. For flat roofs provide proper drainage to prevent

This design is valid until 6/28/2026

n			ponding		
t or	drilled				
's	product	information			

Client: Wellco Contractors

Project: Address: Date: 4/15/2025

Input by: Curtis Quick Job Name: Plan 1 Beams


Project #:


Kerto-S LVL BM3

1.750" X 9.250"

2-Ply - PASSED

Level: Level





Page 9 of 9

Multi-Ply Analysis

Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c.. Maximum end distance not to exceed 6".

Capacity	0.0 %
Load	0.0 PLF
Yield Limit per Foot	163.7 PLF
Yield Limit per Fastener	81.9 lb.
CM	1
Yield Mode	IV
Edge Distance	1 1/2"
Min. End Distance	3"
Load Combination	
Duration Factor	1.00

Notes

NOtes
Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

- Dry service conditions, unless noted otherwise
 LVL not to be treated with fire retardant or corrosive

Handling & Installation

- Handling & Installation

 1. UVI beams must not be cut or drilled

 2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals

 3. Damaged Beams must not be used

 4. Design assumes top edge is laterally restrained

 5. Provide lateral support at bearing points to avoid lateral displacement and rotation
- For flat roofs provide proper drainage to prevent ponding

This design is valid until 6/28/2026

Metsä Wood 301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851 (800) 622-5850 www.metsawood.com/us

Manufacturer Info