



Pinnacle Engineering & Inspections, PLLC

GEOTECHNICAL & ENVIRONMENTAL ENGINEERS

P.O. Box 477, Graham, NC 27253 (336) 516-7205

Partnered with ET Engineering

Firm No. 2839

PROJECT: Atherstone
LOCATION: Angier, NC

REPORT DATE: 11/25/25
COMMENTS:

CONTRACTOR: LGI

STREET ADDRESS: 46 Foxton Place

LOT NO: 202

PERMIT NO.: SFD2504-0061

COMPONENT: 3rd Party Mono Slab
Inspection

Summaries of Engineering Services performed, including Field Test Data.

Location(s), Elevation(s), and Depth(s) noted are estimated.

SUMMARY:

Arrived on site as requested by the contractor to perform a third party check on a turn down slab at the above referenced site. The design bearing capacity is 2000 psf. The turned down slab area was probed and found to be capable of supporting an allowable soil bearing capacity of 2000 psf. Footings are free of loose dirt and cleared of any organic material. Footings measured 16" wide x 20" deep minimum with 2 - #4 rebar continuous throughout. All footing depths are well below the 12" frost line depth. Slab has been filled with suitable soil and compacted. Slab measured 4" thick, minimum. Contractor has installed a 6 mil. vapor barrier over slab. Contractor has installed a 2"- R-10 insulation board around the perimeter. This work was performed in accordance with accepted engineering practices as required by the 2018 North Carolina Residential Building Code. This area was approved for the placement of 3000 psi concrete.



APPENDIX G
Design Professional Inspection Form

RECORD OF THE INSPECTION OF A COMPONENT OR ELEMENT BY A NC LICENSED ARCHITECT OR ENGINEER

Project Information:

Residential Single Family Project:	<input checked="" type="checkbox"/> Y	<input type="checkbox"/> N	Commercial Project:	<input type="checkbox"/> Y	<input checked="" type="checkbox"/> x	N
Code Enforcement Project No:			Permit #:	SFD2504-0061		
Project Name:	Atherstone		Owner:	-		
Project Address:	46 Foxton Place		Suite No:	-		
Date Inspected:	11/25/25		Contractor Name:	LGI		
Component Inspected:	3rd Party Mono Slab Inspection					

Responsible Licensed NC Architect or NC Engineer

Name:	Brandon M. Holt, P.E.		
Firm Name:	Pinnacle Engineering & Inspections, PLLC - Firm No. P-2839		
Phone Numbers:	Office: (743) 205-3905	Mobile: (336) 516-7205	
Email Address:	Bmholt75@outlook.com		

APPLICABLE CODE: **2018 NCRC**

2018 NCBC = 2018 NC building Code: 2018 NCRC = 2018 NC Residential Code


Describe Element/Component/Type of Inspection: * [**See Report for Description**](#)

*(subgrade form/letter may also be required)

Attestation/Signature:

By signing below, I certify that the component and/or element of the building as identified on this form has been inspected by me or someone under my direct supervision per G.S. 160D-11-6 and is in compliance with the Code or other proposal of the architect or engineer for the project. This inspection is in compliance with all of the requirements of the above referenced Code. Attach any additional documents if needed.

Licensed Architect or Engineer



Inspection Department Disclaimer:

Upon the receipt of a signed written document as required by G.S. 160D-11-6, Code Enforcement shall be discharged and released from any liabilities, duties and responsibilities imposed by this article or in the common law from any claim arising out of or attributed to the component or element in the construction of the building for which the signed written document was submitted. Be aware that this inspection will be noted in all inspection records including the Certificate of Occupancy or Certificate of Compliance. This inspection does not address any local ordinances or zoning requirements.