




Carter Sanford Component Plant
298 Harvey Faulk Rd
Sanford, NC 27332

Phone #:919-775-1450

Builder: Pro Build
Model: OverHills



THE PLACEMENT PLAN NOTES:

1. The Placement Plan is a diagram for truss installation. It is not an engineered drawing and has not been reviewed by an engineer. The Owner/Building Designer is responsible for obtaining an engineer's review if one is required by the local jurisdiction.
2. The responsibilities of the Owner, Contractor, Building Designer, Component Designer and Component Manufacturer shall be as set forth in ANSI/TPI 1. Capitalized terms shall be as defined in ANSI/TP 1 unless otherwise indicated.
3. Each Component is designed as an individual component utilizing information provided by others. The Owner/Building Designer is responsible for reviewing all Component Submittal Packages and individual Component Design Drawings for compliance with the Construction Documents and compatibility with the overall Building design.
4. Contractor will not proceed with component installation until the Owner/Building Designer has reviewed the Component Submittal Package. Questions on the suitability of any Component will be resolved by the Building Designer.
5. The Building Designer and Contractor are responsible for all temporary and permanent bracing.
6. The Placement Plan assumes the building is dimensionally correct, structurally sound, and in a suitable condition to support each Component during installation and thereafter, including but not limited to installation of all bearing points. Proper design and construction of all structural components, including foundations, headers, beams, walls and columns are the responsibility of the Owner, Building Designer and Contractor.
7. Do not cut, drill, or modify any Component without first consulting the Component Manufacturer or Building Designer. Damaged Components shall not be installed unless directed by the Building Designer or approved by the Component Manufacturer.
8. Components must be handled and installed following all applicable safety standards and best practices, including but not limited to BCSI, OSHA, TPI and local codes. Failure to properly handle, brace or otherwise install Component can result in serious injury or death.

Apprvd by: _____

Date: _____

General Notes:

General Notes: ** CUTTING OR DRILLING OF COMPONENTS SHOULD NOT BE DONE WITHOUT CONTACTING COMPONENT SUPPLIER FIRST. CUSTOMER TAKES FULL RESPONSIBILITY FOR COMPONENTS IF CUT BEFORE AUTHORIZATION.

ALL BEARING POINTS MUST BE INSTALLED PRIOR TO SETTING ANY COMPONENTS.

Revisions	
00/00/00	Name
00/00/00	Name
00/00/00	Name
00/00/00	Name
00/00/00	Name

THIS IS A TRUSS PLACEMENT DIAGRAM ONLY. These trusses are designed as individual components to be incorporated into the building design at the specification of the building designer. See individual design sheets for each truss design identified on the placement drawing. The building designer is responsible for temporary and permanent bracing of the roof and floor systems and for the overall structure. The design of the russ support structure including headers, beams, walls, and columns is the responsibility of the building designer. For general guidance regarding the bracing, consult "Bracing of Wood Trusses" available from the Truss Plate Institute, 583 D'Onofrio Drive, Marlston, WI 53179.



Probuild

Overhills

ROOF PLACEMENT PLAN

Scale:

NTS

Date: _____

6/3/2025



Designer

Project Number:

25040114


Sheet Number

3/3



Truss Drawing Left
End Indicator

PRELIMINARY - NOT FOR CONSTRUCTION



Floor Hanger List	
THA422	7
HU410	45
HGUS28-2	2
HGUS210-3	2

ProdID	Length	Product	SPlen	Net Qty	Fab Type
BM01	35-00-00	2.1 Rigidum SP LVL, 1.34 x 0.94 x 1.0	2	2	FF
BM05	12-00-00	2.1 Rigidum SP LVL, 1.34 x 0.94 x 1.0	2	2	FF
BM12	12-00-00	2.1 Rigidum SP LVL, 1.34 x 0.94 x 1.0	2	2	FF
BM15	10-00-00	2.1 Rigidum SP LVL, 1.34 x 0.94 x 1.0	2	2	FF
BM17	10-00-00	2.1 Rigidum SP LVL, 1.34 x 0.94 x 1.0	2	2	FF
BM18	10-00-00	2.1 Rigidum SP LVL, 1.34 x 0.94 x 1.0	2	2	FF
BM10	6-00-00	2.1 Rigidum SP LVL, 1.34 x 0.94 x 1.0	2	2	FF
BM11	6-00-00	2.1 Rigidum SP LVL, 1.34 x 0.94 x 1.0	2	2	FF
BM9	4-00-00	2.1 Rigidum SP LVL, 1.34 x 0.94 x 1.0	2	2	FF
BM8	14-00-00	2.1 Rigidum SP LVL, 1.34 x 1.17 x 1.0	2	2	FF
BM16	16-00-00	2.1 Rigidum SP LVL, 1.34 x 1.17 x 1.0	2	2	FF
BM3	16-00-00	2.1 Rigidum SP LVL, 1.34 x 1.18	3	3	FF
BM20	30-00-00	2.1 Rigidum SP LVL, 1.34 x 2.4	3	3	FF

Roof Hanger List	
LUS26	33
HTU26	23
HGUS26-2	2
HTU26-2	1

TRIANGULAR SYMBOL NEAR END OF TRUSS INDICATES LEFT END OF TRUSS AS SHOWN ON INDIVIDUAL TRUSS DRAWINGS.

PLUMBING DROPS NOTED ARE IN THE APPROXIMATE LOCATIONS PER PLAN. BUILDER TO VERIFY LOCATIONS BEFORE SETTING TRUSSES.

REFER TO FINAL TRUSS ENGINEERING SHEETS FOR PLY TO PLY CONNECTIONS.

Trenco
818 Soundside Rd
Edenton, NC 27932

Re: 25040114-01
Overhills-Roof-CL-20-020

The truss drawing(s) referenced below have been prepared by Truss Engineering Co. under my direct supervision based on the parameters provided by Carter Components (Sanford, NC)).

Pages or sheets covered by this seal: I74009654 thru I74009725

My license renewal date for the state of North Carolina is December 31, 2025.

North Carolina COA: C-0844



June 6, 2025

Tony Miller

IMPORTANT NOTE: The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to MiTek or TRENCO. Any project specific information included is for MiTek's or TRENCO's customers file reference purpose only, and was not taken into account in the preparation of these designs. MiTek or TRENCO has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.


Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:04 Page: 1

ID:qGlZsS4tG4Lt3bYtXUG69ezPdT4-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:04

Page: 1

ID:qGlZsS4tG4Lt3bYtXUG69ezPdT4-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



LUMBER		BOT CHORD	40-41=202/201, 39-40=-174/379, 37-39=-499/143, 36-37=-27/534, 33-36=0/1061, 31-33=0/1220, 28-31=0/884, 26-28=0/884, 23-26=0/884, 21-23=-148/321, 18-21=-21/527, 17-18=-53/98, 34-35=-2/16, 32-34=-474/0, 30-32=-861/0, 27-30=-861/0, 25-27=-349/365, 24-25=-18/1073, 22-24=-18/1073, 20-22=-7/273, 19-20=-14/20		3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=18.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10, Lu=50-0-0
TOP CHORD	2x6 SP No.2		16-18=0/682, 35-36=-213/189, 7-35=-198/327, 18-19=-250/81, 15-19=-237/171, 8-44=-567/263, 42-44=-358/1479, 42-43=-568/1438, 14-43=-1028/489, 34-36=-616/0, 20-21=-318/0, 33-34=-3/207, 21-22=-22/468, 32-33=-320/28, 22-23=-636/0, 31-32=-17/191, 23-24=-8/37, 30-31=-322/0, 27-31=0/736, 27-28=-281/0, 25-26=0/319, 11-42=-466/70, 12-43=-250/124, 10-44=-208/83, 9-44=-146/1746, 10-42=-42/303, 12-42=-159/388, 13-43=-247/1785, 18-20=-17/359, 23-25=-1315/0, 5-39=-1772/0, 6-37=-1112/0, 6-36=-35/599, 5-37=0/1436, 3-39=-564/63, 3-40=0/154, 2-40=-243/276		4) Unbalanced snow loads have been considered for this design.
BOT CHORD	2x4 SP No.2				5) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 13.9 psf on overhangs non-concurrent with other live loads.
WEBS	2x4 SP No.3 *Except* 41-2:2x6 SP No.2, 7-36,15-18,8-14:2x4 SP No.2	WEBS			6) Provide adequate drainage to prevent water ponding.
BRACING					7) All plates are 2x4 MT20 unless otherwise indicated.
TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (4-5-2 max.): 9-13.				8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
BOT CHORD	Rigid ceiling directly applied or 5-5-11 oc bracing.				9) Ceiling dead load (5.0 psf) on member(s). 6-7, 7-8, 14-15, 8-44, 42-44, 42-43, 14-43; Wall dead load (5.0psf) on member(s). 7-35, 15-19
WEBS	1 Row at midpt 7-35, 15-19, 5-39, 6-37				10) Bottom chord live load (40.0 psf) and additional bottom chord dead load (0.0 psf) applied only to room. 34-35, 32-34, 30-32, 27-30, 25-27, 24-25, 22-24, 20-22, 19-20
JOINTS	1 Brace at Jt(s): 34, 20, 24, 30, 42, 43, 44				11) All bearings are assumed to be SP No. 2.
REACTIONS	(size) 17=0-3-8, 23=0-5-8, 39=0-3-8, 41=0-3-0 Max Horiz 41=267 (LC 14) Max Uplift 41=-156 (LC 11) Max Grav 17=1162 (LC 47), 23=1109 (LC 63), 39=2064 (LC 70), 41=490 (LC 2)				
FORCES	(lb) - Maximum Compression/Maximum Tension				
TOP CHORD	1-2=0/54, 2-3=-445/282, 3-5=-217/604, 5-6=-617/232, 6-7=-1114/252, 7-8=-992/216, 8-9=-785/101, 9-10=-2136/225, 10-11=-2423/229, 11-12=-2423/229, 12-13=-2095/242, 13-14=-743/157, 14-15=-1017/215, 15-16=-1140/88, 2-41=-436/276, 16-17=-1161/54	NOTES			
		1) Unbalanced roof live loads have been considered for this design.			
		2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCFL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C			

June 6, 2025

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)


ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020
25040114-01	A2	Attic	2	1	174009654
Job Reference (optional)					

- 12) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 156 lb uplift at joint 41.
- 13) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- 14) Attic room checked for L/360 deflection.

LOAD CASE(S) Standard




June 6,2025

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009655
25040114-01	A1	Attic Structural Gable	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:03

Page: 1



Scale = 1:91.9

Plate Offsets (X, Y): [13:0-2-8,0-2-4], [16:0-5-14,0-3-0], [20:0-5-14,0-3-0], [21:0-1-6,0-2-0], [23:0-3-4,0-1-8], [4-12

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.63	Vert(LL)	-0.07	34-37	>999	240	244/190
Snow (Pf/Pg)	18.9/20.0	Lumber DOL	1.15	BC	0.74	Vert(CT)	-0.08	24-25	>999	180	
TCDL	10.0	Rep Stress Incr	YES	WB	0.74	Horz(CT)	0.01	24	n/a	n/a	
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH		Attic	-0.06	26-42	>999	360	
BCDL	10.0										
Weight: 379 lb FT = 20%											

LUMBER		TOP CHORD		1-2=0/54, 2-3=300/607, 3-4=236/523, 4-5=223/537, 5-6=204/537, 6-8=186/548, 8-9=175/562, 9-10=148/532, 10-13=135/545, 11-12=1352/0, 12-13=1330/0, 13-14=1189/240, 14-15=1008/212, 15-16=799/108, 16-17=2158/231, 17-18=2444/230, 18-19=2444/230, 19-20=2117/236, 20-21=757/135, 21-22=1033/209, 22-23=1181/78, 2-52=212/368, 23-24=1196/54	WEBS		23-25=0/707, 15-55=571/249, 53-55=357/1486, 53-54=549/1445, 21-54=1013/454, 42-43=161/223, 14-42=145/360, 25-26=232/78, 22-26=219/169, 41-43=635/0, 27-28=286/0, 40-41=2/219, 28-29=33/425, 39-40=344/13, 29-30=599/10, 38-39=4/212, 30-31=14/33, 37-38=315/0, 34-38=0/689, 34-35=267/0, 32-33=0/306, 18-53=467/70, 19-54=249/118, 17-55=206/82, 16-55=140/1744, 17-53=42/303, 19-53=150/389, 20-54=245/1783, 25-27=21/329, 30-32=1271/0, 13-44=456/0, 13-43=25/553, 11-44=0/1008, 10-12=60/15, 8-47=113/50, 6-48=109/46, 5-49=168/13, 4-50=167/26, 3-51=313/127, 11-46=1768/0, 9-11=291/46
BRACING		BOT CHORD		51-52=465/114, 50-51=465/114, 49-50=465/114, 48-49=465/114, 47-48=465/114, 46-47=465/114, 44-46=464/115, 43-44=35/561, 40-43=0/1101, 38-40=0/1282, 35-38=23/1006, 33-35=23/1006, 30-33=23/1006, 28-30=141/435, 25-28=31/596, 24-25=54/100, 41-42=4/17, 39-41=491/0, 37-39=911/0, 34-37=911/0, 32-34=434/317, 31-32=36/963, 29-31=36/963, 27-29=7/250, 26-27=15/25	NOTES		1) Unbalanced roof live loads have been considered for this design.
REACTIONS		JOINTS		24=0-3-8, 30=0-5-8, 46=11-7-4, 47=11-7-4, 48=11-7-4, 49=11-7-4, 50=11-7-4, 51=11-7-4, 52=11-7-4			
		Max Horiz		52=267 (LC 14)			
		Max Uplift		47=18 (LC 11), 48=13 (LC 15), 51=152 (LC 12), 52=401 (LC 60)			
		Max Grav		24=1180 (LC 47), 30=1078 (LC 63), 46=1870 (LC 70), 47=228 (LC 35), 48=250 (LC 70), 49=306 (LC 70), 50=293 (LC 35), 51=542 (LC 60), 52=259 (LC 12)			
FORCES		REMARKS		(lb) - Maximum Compression/Maximum Tension			

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020
25040114-01	A1	Attic Structural Gable	1	1	174009655
					Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:03
ID:yKPecdlP9myEMOyv3pNRj6zPfzE-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrcDoi7J4zJC?i

Page: 2

- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust)
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat.
II; Exp B; Enclosed; MWFRS (envelope) and C-C
Exterior(2E) -1-7-9 to 2-4-0, Interior (1) 2-4-0 to 19-6-8,
Exterior(2R) 19-6-8 to 23-6-1, Interior (1) 23-6-1 to
31-7-8, Exterior(2R) 31-7-8 to 35-7-1, Interior (1) 35-7-1
to 39-5-12 zone; cantilever left and right exposed ; end
vertical left and right exposed;C-C for members and
forces & MWFRS for reactions shown; Lumber
DOL=1.60 plate grip DOL=1.33
- 3) Truss designed for wind loads in the plane of the truss
only. For studs exposed to wind (normal to the face),
see Standard Industry Gable End Details as applicable,
or consult qualified building designer as per ANSI/TPI 1.
- 4) TCELL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15
Plate DOL=1.15); Pg=20.0 psf; Pf=18.9 psf (Lum
DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully
Exp.; Ce=0.9; Cs=1.00; Ct=1.10, Lu=50-0-0
- 5) Unbalanced snow loads have been considered for this
design.
- 6) This truss has been designed for greater of min roof live
load of 12.0 psf or 2.00 times flat roof load of 13.9 psf on
overhangs non-concurrent with other live loads.
- 7) Provide adequate drainage to prevent water ponding.
- 8) All plates are 2x4 MT20 unless otherwise indicated.
- 9) Truss to be fully sheathed from one face or securely
braced against lateral movement (i.e. diagonal web).
- 10) Gable studs spaced at 2-0-0 oc.
- 11) * This truss has been designed for a live load of 20.0psf
on the bottom chord in all areas where a rectangle
3-06-00 tall by 2-00-00 wide will fit between the bottom
chord and any other members.
- 12) Ceiling dead load (5.0 psf) on member(s). 2-3, 3-4, 4-5,
13-14, 14-15, 21-22, 15-55, 53-55, 53-54, 21-54; Wall
dead load (5.0psf) on member(s).14-42, 22-26, 5-49,
4-50, 3-51, 11-46, 9-11
- 13) Bottom chord live load (40.0 psf) and additional bottom
chord dead load (0.0 psf) applied only to room. 51-52,
50-51, 49-50, 48-49, 47-48, 46-47, 41-42, 39-41, 37-39,
34-37, 32-34, 31-32, 29-31, 27-29, 26-27
- 14) All bearings are assumed to be SP No.2 .
- 15) Provide mechanical connection (by others) of truss to
bearing plate capable of withstanding 401 lb uplift at joint
52, 18 lb uplift at joint 47, 13 lb uplift at joint 48 and 152
lb uplift at joint 51.
- 16) Graphical purlin representation does not depict the size
or the orientation of the purlin along the top and/or
bottom chord.
- 17) Attic room checked for L/360 deflection.

LOAD CASE(S) Standard



June 6,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009656
25040114-01	A7	Piggyback Base	6	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:06
ID:11h65Xut_4SxwY1bMH9dEazPfzQ-RfC?PsB70Hq3NSgPqnL8w3uITXbGKwRCDoi7J4zJC?f

Page: 1



Scale = 1:75.1

Plate Offsets (X, Y): [8:0-2-11,Edge], [11:0-4-8,0-1-8], [14:0-2-12,0-2-0], [19:0-1-4,0-1-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.57	Vert(LL)	0.03	11-12	>999	240	MT20	244/190
Snow (Pf/Pg)	18.9/20.0	Lumber DOL	1.15	BC	0.27	Vert(CT)	-0.05	17-18	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.60	Horz(CT)	0.09	19	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 231 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3 *Except* 10-19:2x4 SP No.2,
18-2:2x6 SP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or
6-0-0 oc purlins, except end verticals, and
2-0-0 oc purlins (6-0-0 max.): 8-10.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc
bracing.
WEBS 1 Row at midpt 10-19, 8-13, 9-11, 9-12,
8-12

REACTIONS

(size) 16=0-3-8, 18=0-3-0, 19=
Mechanical
Max Horiz 18=329 (LC 14)
Max Uplift 16=6 (LC 15), 18=38 (LC 11),
19=58 (LC 12)
Max Grav 16=1474 (LC 3), 18=454 (LC 2),
19=836 (LC 50)


FORCES

(lb) - Maximum Compression/Maximum
Tension
TOP CHORD 1-2=0/60, 2-3=-366/44, 3-5=-284/538,
5-6=-141/198, 6-7=-129/220, 7-8=-570/189,
8-9=-437/173, 9-10=-139/149,
11-19=-959/147, 10-11=-201/60,
2-18=-435/169
BOT CHORD 17-18=-562/496, 16-17=-303/401,
15-16=-26/1, 14-15=-34/0, 6-14=-92/13,
13-14=-279/369, 12-13=-258/462,
11-12=-204/483
WEBS 7-14=-725/54, 7-13=0/227, 8-13=-45/118,
9-11=-776/146, 3-17=0/238, 3-16=-682/125,
5-16=-984/310, 14-16=-555/200,
5-14=-183/640, 2-17=-140/262,
9-12=-15/270, 8-12=-69/134

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust)
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Exterior(2E) -1-10-2 to 1-1-14, Interior (1) 1-1-14 to 18-7-11, Exterior(2R) 18-7-11 to 21-7-11, Interior (1) 21-7-11 to 28-0-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=18.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10, Lu=50-0-0
- Unbalanced snow loads have been considered for this design.
- This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 13.9 psf on overhangs non-concurrent with other live loads.
- Provide adequate drainage to prevent water ponding.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Bearings are assumed to be: Joint 18 SP No.2, Joint 16 SP No.2.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 38 lb uplift at joint 18, 6 lb uplift at joint 16 and 58 lb uplift at joint 19.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard



June 6, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009657
25040114-01	A6	Piggyback Base	2	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:05
ID:Mv5mF4HShLoDshUlxw8LlZPfzB-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:69.3

Plate Offsets (X, Y): [7:0-2-11,Edge], [9:Edge,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.80	Vert(LL)	-0.08	12-14	>999	240	MT20	244/190
Snow (Pf/Pg)	18.9/20.0	Lumber DOL	1.15	BC	0.40	Vert(CT)	-0.12	12-14	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.51	Horz(CT)	0.01	10	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 226 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3 *Except*
9-10,12-7,10-8,11-8,11-7:2x4 SP No.2,
16-2:2x6 SP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or
6-0-0 oc purlins, except end verticals, and
2-0-0 oc purlins (6-0-0 max.): 7-9.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc
bracing.
WEBS 1 Row at midpt 9-10, 7-12, 8-10, 6-14,
7-11

REACTIONS

(size) 10= Mechanical, 14=0-3-8,
16=0-3-0
Max Horiz 16=326 (LC 12)
Max Uplift 10=66 (LC 12), 14=18 (LC 15),
16=23 (LC 11)
Max Grav 10=883 (LC 50), 14=1442 (LC 3),
16=494 (LC 2)

FORCES


(lb) - Maximum Compression/Maximum
Tension
TOP CHORD 1-2=0/60, 2-3=-414/15, 3-5=-227/391,
5-6=-158/343, 6-7=-601/218, 7-8=-427/195,
8-9=-171/184, 9-10=-211/76, 2-16=-460/154
BOT CHORD 15-16=-561/501, 14-15=-350/498,
12-14=-254/378, 11-12=-236/450,
10-11=-184/439
WEBS 6-12=0/218, 7-12=-34/184, 8-10=-827/175,
3-14=-639/122, 3-15=0/211, 5-14=-345/119,
6-14=-848/66, 2-15=-86/213, 8-11=-26/308,
7-11=-133/130

NOTES

1) Unbalanced roof live loads have been considered for
this design.

- Wind: ASCE 7-16; Vult=130mph (3-second gust)
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat.
II; Exp B; Enclosed; MWFRS (envelope) and C-C
Exterior(2E) -1-10-2 to 1-1-14, Interior (1) 1-1-14 to
18-7-11, Exterior(2R) 18-7-11 to 21-7-11, Interior (1)
21-7-11 to 28-0-8 zone; cantilever left and right
exposed ; end vertical left and right exposed;C-C for
members and forces & MWFRS for reactions shown;
Lumber DOL=1.60 plate grip DOL=1.33
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15
Plate DOL=1.15); Pg=20.0 psf; Pf=18.9 psf (Lum
DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully
Exp.; Ce=0.9; Cs=1.00; Ct=1.10, Lu=50-0-0
- Unbalanced snow loads have been considered for this
design.
- This truss has been designed for greater of min roof live
load of 12.0 psf or 2.00 times flat roof load of 13.9 psf on
overhangs non-concurrent with other live loads.
- Provide adequate drainage to prevent water ponding.
- * This truss has been designed for a live load of 20.0psf
on the bottom chord in all areas where a rectangle
3-06-00 tall by 2-00-00 wide will fit between the bottom
chord and any other members, with BCDL = 10.0psf.
- Bearings are assumed to be: Joint 16 SP No.2 , Joint 14
SP No.2 .
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to
bearing plate capable of withstanding 66 lb uplift at joint
10, 23 lb uplift at joint 16 and 18 lb uplift at joint 14.
- Graphical purlin representation does not depict the size
or the orientation of the purlin along the top and/or
bottom chord.

LOAD CASE(S) Standard



June 6,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932


Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009658
25040114-01	B6	Attic	2	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:08

Page: 1

ID:DhFqqqWJoPJntOvI0_ZUPzPczX-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrcDoi7J4zJC?f



Scale = 1:91.6

Plate Offsets (X, Y): [3:0-4-12,0-1-8], [4:0-1-8,0-3-12], [8:0-5-14,0-3-0], [10:0-3-0,0-2-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.66	Vert(LL)	-0.26	23-24	>999	240	MT20	244/190
Snow (Pf/Pg)	18.9/20.0	Lumber DOL	1.15	BC	0.81	Vert(CT)	-0.41	23-24	>804	180	MT18HS	244/190
TCDL	10.0	Rep Stress Incr	YES	WB	0.63	Horz(CT)	0.07	12	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH		Attic	-0.19	14-33	>999	360		
BCDL	10.0										Weight: 291 lb	FT = 20%

LUMBER	
TOP CHORD	2x6 SP No.2
BOT CHORD	2x4 SP No.1 *Except* 33-26,26-14:2x4 SP No.2
WEBS	2x4 SP No.3 *Except* 2-34,10-13,3-9:2x4 SP No.2
OTHERS	2x4 SP No.3
BRACING	
TOP CHORD	Structural wood sheathing directly applied or 4-4-9 oc purlins, except 2-0-0 oc purlins (6-0-0 max.): 4-8.
BOT CHORD	Rigid ceiling directly applied or 3-0-14 oc bracing.
JOINTS	1 Brace at Jt(s): 15, 32, 19, 29, 23, 24, 36, 37, 38
REACTIONS (size) 12=0-3-8, 35=0-3-8 Max Horiz 35=-182 (LC 11) Max Grav 12=1726 (LC 3), 35=1856 (LC 3)	
FORCES (lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=-1870/0, 2-3=-1450/96, 3-4=-282/881, 4-5=-883/819, 5-6=-1220/453, 6-7=-1220/453, 7-8=-1020/264, 8-9=-383/114, 9-10=-1188/140, 10-11=-1896/0
BOT CHORD	34-35=-182/182, 31-34=0/1924, 28-31=0/2579, 25-28=0/3670, 22-25=0/3955, 18-22=0/3694, 16-18=0/2632, 13-16=0/1888, 12-13=0/0, 32-33=-105/193, 30-32=-903/102, 29-30=-2375/0, 27-29=-2375/0, 24-27=-3073/0, 23-24=-3073/0, 21-23=-3073/0, 19-21=-2413/0, 17-19=-2413/0, 15-17=-952/0, 14-15=-75/80



June 6,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 E Mar 19 2025 Print: 8.730 E Mar 19 2025 MiTek Industries, Inc. Fri Jun 06 10:38:53 Page: 1

ID:fXXrHsMLo3MP5YW58_MnJpzPfyp-djlPhE6ymQtC_V16WnSnApuOuGaJU0ND537O3rz9Bmo

Run: 8.73 E Mar 19 2025 Print: 8.730 E Mar 19 2025 MiTek Industries, Inc. Fri Jun 06 10:38:53
ID:fXXrHsMLo3MP5YW58_MnJpzPfyp-djlphE6ymQtC_V16WnSnApuOuGaJU0ND537O3rz9Bmo

Page: 1



Scale = 1:95.5

PLY-TO-PLY CONNECTION REQUIRES THAT AN APPROVED FACE MOUNT HANGER (SPECIFIED BY OTHERS) IS REQUIRED AT JOINT 34 FOR LOAD REPORTED IN NOTES. FACE MOUNT HANGER SHALL BE ATTACHED WITH A MINIMUM OF 0.25"x 6" SCREWS OR OTHER FASTENERS THAT PENETRATES ALL PLIES, PER HANGER MANUFACTURER SPECIFICATIONS.

Plate Offsets (X, Y): [3:0-5-12,0-9-12], [4:0-5-0,0-1-12], [5:0-0-12,0-3-12], [9:0-5-14,0-3-0], [11:0-5-0,0-4-4], [13:0-4-12,0-1-12], [14:8-0-2-8,Edge], [36:0-4-4,0-2-4], [37:0-3-12,0-3-0]

Weight: 1408 lb FT = 20%

BOT CHORD

BOT CHORD 38-39=-1029/2210, 36-38=-1839/1968,
34-36=0/15901, 34-44=0/15901,
31-44=0/15901, 31-45=0/18969,
45-46=0/18969, 28-46=0/18969,
28-47=0/18581, 25-47=0/18581,
25-48=0/15257, 23-48=0/15257,
21-23=0/15257, 21-49=0/7542,
17-49=0/7542, 16-17=-2984/0,
16-50=-2798/0, 50-51=-2798/0,
15-51=-2798/0, 35-37=-4807/0,
33-35=-4807/0, 33-54=-12714/0,
32-54=-12714/0, 32-55=-12714/0,
30-55=-12714/0, 29-30=-12616/0,
29-56=-12616/0, 27-56=-12616/0,
27-57=-12616/0, 26-57=-12616/0,
26-58=-12616/0, 24-58=-12616/0,
24-59=-5996/0, 22-59=-5996/0,
22-60=-5996/0, 20-60=-5996/0,
19-20=0/3810, 18-19=0/3810

WEBS

WEBS

37-38=0/1739, 3-37=0/11157, 16-18=0/2215,
11-18=0/7320, 4-41=-13963/0,
41-42=-11461/0, 42-43=-8118/0,
10-43=-6303/0, 36-37=0/13215,
17-19=-266/0, 20-21=0/5675,
31-33=-65/4167, 21-24=-4265/0,
30-31=-411/1667, 24-25=0/4488,
28-30=-2326/0, 25-26=-597/0, 27-28=0/461,
12-15=-4119/0, 6-41=-1486/0, 7-42=0/770,
6-42=0/3294, 8-43=-737/0, 9-43=-1833/454,
13-15=0/5516, 15-18=0/7510, 12-18=0/1987,
5-41=0/2824, 17-18=0/7020, 17-20=-5819/0,
33-34=0/5295, 33-36=-10040/0,
1-40=-9991/0, 2-39=8150/0, 37-39=0/6052,
2-37=-92/1730, 1-39=0/6514

- 2) 4-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc, 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2x6 - 3 rows staggered at 0-4-0 oc, 2x4 - 1 row at 0-9-0 oc.
Web connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc, 2x4 - 1 row at 0-9-0 oc.
- Attach BC w/ 1/2" diam. bolts (ASTM A-307) in the center of the member w/washers at 4-0-0 oc.
- 3) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- 4) Unbalanced roof live loads have been considered for this design.
- 5) Wind: ASCE 7-16; Vult=130mph (3-second gust)
Vasd=103mph; TCdL=6.0psf; BCdL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope); cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate arip DOL=1.33

NOTES

(lb) or less except when shown.

TOP CHORD 1-2=-6890/0, 2-3=-12288/0, 3-4=-4435/0,
4-5=0/4659, 5-6=0/5449, 6-7=-406/2337,
7-8=-406/2337, 8-9=-256/2121,
9-10=-145/615, 10-11=-3853/0,
11-12=-9576/0, 12-13=-7398/0,
13-14=-8691/0

1) N/A

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinet.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

June 6.2025

ENGINEERING BY
TRENCO
A MI Tek Affiliate

818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009659
25040114-01	B7	Attic Girder	1	4	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 E Mar 19 2025 Print: 8.730 E Mar 19 2025 MiTek Industries, Inc. Fri Jun 06 10:38:53
ID:fXXrHsMLo3MP5YW58_MnJpzPfyp-djlphE6ymQtC_V16WnSnApuOuGajU0ND537O3rz9Bmo

Page: 2

- 6) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=18.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10, Lu=50-0-0; Min. flat roof snow load governs. Rain surcharge applied to all exposed surfaces with slopes less than 0.500/12 in accordance with IBC 1608.3.4.
- 7) Provide adequate drainage to prevent water ponding.
- 8) All plates are MT20 plates unless otherwise indicated.
- 9) All plates are 2x4 MT20 unless otherwise indicated.
- 10) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- 11) Ceiling dead load (5.0 psf) on member(s). 3-4, 10-11, 4-41, 41-42, 42-43, 10-43; Wall dead load (5.0psf) on member(s).3-37, 11-18
- 12) Bottom chord live load (40.0 psf) and additional bottom chord dead load (0.0 psf) applied only to room. 35-37, 33-35, 32-33, 30-32, 27-30, 26-27, 24-26, 22-24, 20-22, 19-20, 18-19
- 13) Load case(s) 1, 2 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.
- 14) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- 15) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 7199 lb down at 7-1-4, 691 lb down at 8-2-0, 691 lb down at 9-9-3, 691 lb down at 11-4-6, 691 lb down at 12-11-9, 691 lb down at 14-6-12, 691 lb down at 16-1-15, 691 lb down at 17-9-2, 691 lb down at 19-4-5, 691 lb down at 20-10-8, 691 lb down at 22-6-11, 691 lb down at 24-1-14, and 691 lb down at 25-9-1, and 693 lb down at 27-4-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 16) Attic room checked for L/360 deflection.

LOAD CASE(S) Standard

- 1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-3=-48, 3-4=-58, 4-5=-48, 5-7=-58, 7-9=-98, 9-10=-88, 10-11=-98, 11-13=-168, 14-40=-20, 18-37=-20, 4-41=-10, 41-42=-10, 42-43=-10, 10-43=-10
Drag: 3-37=-10, 11-18=-10
Concentrated Loads (lb)
Vert: 23=-177 (F), 16=-177 (F), 17=-177 (F), 34=-5015 (F), 44=-177 (F), 45=-177 (F), 46=-177 (F), 47=-177 (F), 48=-177 (F), 49=-177 (F), 50=-177 (F), 51=-177 (F), 52=-177 (F), 53=-179 (F)
- 2) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-3=-60, 3-4=-70, 4-5=-60, 5-7=-60, 7-9=-100, 9-10=-100, 10-11=-110, 11-13=-180, 14-40=-20, 18-37=-20, 4-41=-10, 41-42=-10, 42-43=-10, 10-43=-10
Drag: 3-37=-10, 11-18=-10
Concentrated Loads (lb)
Vert: 23=-177 (F), 16=-177 (F), 17=-177 (F), 34=-5165 (F), 44=-177 (F), 45=-177 (F), 46=-177 (F), 47=-177 (F), 48=-177 (F), 49=-177 (F), 50=-177 (F), 51=-177 (F), 52=-177 (F), 53=-179 (F)



June 6, 2025


WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932

Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:08 Page: 1



WERB 0.05 1500/310 00.05 310/100 7.0 3.11 1.50 0.0 1.0 0.0 0.10

BRACING 16-17=-836/0, 27-28=-836/0, 17-18=0/667, 27-29, 25-27, 23-25, 21-23, 19-21, 17-19, 15-17, 14-15

REACTIONS (size) 12=0-3-8. 32=0-3-8 1) Unbalanced roof live loads have been considered for

FORCES (lb) - Maximum Compression/Maximum Tension
 Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Ex. P; Enclosed; MWFRS (asymptotic) and C.C.


b) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust)
 Vasd=103mph; TCDFL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Exterior(2E) 0-1-12 to 3-1-12, Interior (1) 3-1-12 to 8-0-0, Exterior(2R) 8-0-0 to 12-2-15, Interior (1) 12-2-15 to 20-1-0, Exterior(2R) 20-1-0 to 24-3-15, Interior (1) 24-3-15 to 27-11-4 zone; cantilever left and right exposed ; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
- 3) TCELL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=18.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10, Lu=50-0-0
- 4) Provide adequate drainage to prevent water ponding.
- 5) All plates are 3x5 MT20 unless otherwise indicated.
- 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.

- LOAD CASE(S) Standard




Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:07 Page: 1
ID:a6e9S24vD Tf0FgleRNuvzPfzA-RfC?PsB70Ha3NSqPqnL8w3uITXbGKWRcDoi7J4zJC?f



LUMBER		WEBS			
TOP CHORD	2x6 SP No.2		3-6=-1497/337, 34-36=-604/437,		7) * This truss has been designed for a live load of 20.0psf
BOT CHORD	2x4 SP No.2		34-35=-607/458, 9-35=-1506/316,		on the bottom chord in all areas where a rectangle
WEBS	2x4 SP No.3 *Except* 3-9,2-32,10-14:2x4 SP No.2		1-32=0/1098, 11-14=0/1080, 31-32=0/567,		3-06-00 tall by 2-00-00 wide will fit between the bottom
			2-31=0/722, 14-15=0/571, 10-15=0/726,		chord and any other members.
BRACING			30-32=-1032/0, 16-17=0/462, 29-30=0/465,		8) Ceiling dead load (5.0 psf) on member(s). 2-3, 9-10,
TOP CHORD	Structural wood sheathing directly applied or 4-7-11 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 4-8.		17-18=-838/0, 28-29=-834/0, 18-19=0/668,		3-36, 34-36, 34-35, 9-35; Wall dead load (5.0psf) on
BOT CHORD	Rigid ceiling directly applied or 2-2-0 oc bracing.		27-28=0/665, 19-20=-152/0, 26-27=-153/3,		member(s).2-31, 10-15
JOINTS	1 Brace at Jt(s): 30, 16, 20, 26, 34, 35, 36		19-22=-355/32, 24-27=-349/40,		9) Bottom chord live load (40.0 psf) and additional bottom
			24-25=-10/52, 22-23=-8/52, 6-34=-226/69,		chord dead load (0.0 psf) applied only to room. 30-31,
			7-35=-321/94, 5-36=-324/100,		28-30, 26-28, 24-26, 22-24, 20-22, 18-20, 16-18, 15-16
			4-36=-260/1094, 5-34=-126/401,		10) All bearings are assumed to be SP No.2 .
			7-34=-121/406, 8-35=-253/1108,		11) Graphical purlin representation does not depict the size
			14-16=-1026/0		or the orientation of the purlin along the top and/or
					bottom chord.
REACTIONS	(size) 13=0-3-8, 33=0-3-8	NOTES			12) Attic room checked for L/360 deflection.
Max Horiz	33=-273 (LC 9)	1) Unbalanced roof live loads have been considered for this design.			
Max Grav	13=1788 (LC 3), 33=1690 (LC 3)	2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Exterior(2E) 0-1-12 to 3-1-12, Interior (1) 3-1-12 to 8-0-0, Exterior(2R) 8-0-0 to 12-2-15, Interior (1) 12-2-15 to 20-1-0, Exterior(2R) 20-1-0 to 24-3-15, Interior (1) 24-3-15 to 29-9-6 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33			LOAD CASE(S) Standard
FORCES	(lb) - Maximum Compression/Maximum Tension				
TOP CHORD	1-2=-1907/0, 2-3=-1246/117, 3-4=-449/192, 4-5=-1161/289, 5-6=-1353/184, 6-7=-1353/184, 7-8=-1176/309, 8-9=-455/208, 9-10=-1247/114, 10-11=-1911/0, 11-12=0/106, 1-33=-1920/0, 11-13=-2053/0				
BOT CHORD	32-33=-267/327, 29-32=0/1809, 27-29=0/2292, 25-27=0/3039, 23-25=0/3039, 19-23=0/3039, 17-19=0/2262, 14-17=0/1702, 13-14=-40/83, 30-31=-90/110, 28-30=-771/44, 26-28=-1905/0, 24-26=-1905/0, 22-24=-2172/0, 20-22=-1900/0, 18-20=-1900/0, 16-18=-761/57, 15-16=-91/120				



Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:05 Page: 1



LUMBER		<p>4-22=2317/0, 5-39=2637/0, 37-38=3359/0, 10-38=3972/0, 33-34=0/4866, 3-33=0/3593, 16-18=0/670, 11-18=0/2498, 31-33=320/0, 17-19=323/0, 31-32=11/63, 17-20=2280/0, 30-31=0/1180, 20-21=0/2241, 29-30=1455/0, 21-22=24/47, 28-29=298/0, 26-29=0/3346, 26-27=1788/0, 24-25=0/1819, 7-37=159/212, 8-38=673/0, 6-39=344/0, 5-39=527/812, 6-37=0/397, 8-37=0/903, 9-38=0/1451, 17-18=0/2387, 21-24=4033/0, 2-35=123/255, 33-35=6415/0, 2-33=581/0, 1-35=0/3775, 12-15=3203/0, 13-15=0/2090, 15-18=0/6550, 12-18=0/1948</p>
TOP CHORD	2x6 SP No.2	
BOT CHORD	2x6 SP No.2 *Except* 33-18:2x4 SP No.2, 23-36:2x6 SP 2400F 2.0E	
WEBS	2x4 SP No.3 *Except* 4-10,3-34,11-16,35-33,15-18:2x4 SP No.2	
BRACING		
TOP CHORD	Structural wood sheathing directly applied or 4-2-2 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 5-9.	
BOT CHORD	Rigid ceiling directly applied or 4-11-13 oc bracing.	
JOINTS	1 Brace at Jt(s): 19, 32, 22, 28, 37, 38, 39	
REACTIONS	(size) 14=0-3-8, 21=0-5-8, 36=0-3-8	
	Max Horiz 36=244 (LC 5)	
	Max Uplift 21=157 (LC 35)	
	Max Grav 14=3663 (LC 21), 21=392 (LC 22), 36=5776 (LC 21)	
FORCES	(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	4-5=-4838/0, 2-3=-4763/0, 3-4=-2155/0, 4-5=-571/10, 5-6=-1266/257, 6-7=-1641/209, 7-8=-1641/209, 8-9=-1090/615, 9-10=-262/533, 10-11=-2418/0, 11-12=-4506/0, 12-13=-2979/0, 1-36=-5789/0, 13-14=-3564/0	
BOT CHORD	35-36=-224/239, 34-35=0/9281, 31-34=0/8711, 29-31=0/7743, 27-29=0/3907, 25-27=0/3907, 21-25=0/3907, 17-21=-1095/0, 16-17=-4728/0, 15-16=-4557/0, 14-15=0/73, 32-33=-5747/0, 30-32=-5747/0, 28-30=-3722/0, 26-28=-3722/0, 24-26=-1019/0, 22-24=0/2265, 20-22=0/2265, 19-20=0/5758, 18-19=0/5758	
WEBS		
NOTES		<p>1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows: Top chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc, 2x4 - 1 row at 0-9-0 oc. Bottom chords connected as follows: 2x6 - 3 rows staggered at 0-2-0 oc, 2x4 - 1 row at 0-9-0 oc. Web connected as follows: 2x4 - 1 row at 0-9-0 oc.</p> <p>2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.</p> <p>3) Unbalanced roof live loads have been considered for this design.</p> <p>4) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCdL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope); cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.33</p>

June 6, 2025

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MITEK® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinet.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbccomponents.com)



818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	I74009662
25040114-01	A3	Attic Girder	1	2	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,


Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:05
ID:MBcCpTHySvUOmTUIE0k8XKzPtyw-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrcDoi7J4zJC?f

Page: 2

- 12) Load case(s) 1, 2 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.
- 13) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- 14) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 5747 lb down at 7-2-8 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 15) Attic room checked for L/360 deflection.

LOAD CASE(S) Standard

- 1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-3=-48, 3-4=-58, 4-5=-48, 5-7=-58, 7-9=-98, 9-10=-88, 10-11=-98, 11-13=-168, 14-36=-20, 18-33=-20, 4-39=-10, 37-39=-10, 37-38=-10, 10-38=-10
Drag: 3-33=-10, 11-18=-10
Concentrated Loads (lb)
Vert: 34=-3421 (B)
- 2) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-3=-60, 3-4=-70, 4-5=-60, 5-7=-60, 7-9=-100, 9-10=-100, 10-11=-110, 11-13=-180, 14-36=-20, 18-33=-20, 4-39=-10, 37-39=-10, 37-38=-10, 10-38=-10
Drag: 3-33=-10, 11-18=-10
Concentrated Loads (lb)
Vert: 34=-3393 (B)



June 6, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932


Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009663
25040114-01	B3	Attic	2	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:07

Page: 1

ID:q6e9S?4vD_Tfr0fgleRNuyzPfzA-RfC?PsB70Hg3NSgPqnL8w3uTXbGKwRCdoi7J4zJC?i



Scale = 1:95

Plate Offsets (X, Y): [2:0-3-0,0-1-4], [5:0-5-14,0-3-0], [9:0-5-14,0-3-0], [11:0-3-0,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.73	Vert(LL)	-0.20	32	>972	240	MT20	244/190
Snow (Pf/Pg)	18.9/20.0	Lumber DOL	1.15	BC	0.82	Vert(CT)	-0.31	32-33	>645	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.47	Horz(CT)	0.04	13	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MSH		Attic	-0.18	15-31	>928	360		
BCDL	10.0										Weight: 285 lb	FT = 20%

LUMBER
TOP CHORD 2x6 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3 *Except* 4-10,3-32,11-14:2x4 SP No.2

BRACING
TOP CHORD Structural wood sheathing directly applied or 5-0-1 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 5-9.
BOT CHORD Rigid ceiling directly applied or 4-8-11 oc bracing.
WEBS 1 Row at midpt 11-15
JOINTS 1 Brace at Jt(s): 30, 16, 20, 26, 34, 35, 36

REACTIONS (size) 13=0-3-8, 19=0-5-8, 33=0-3-8
Max Horiz 33=273 (LC 12)
Max Uplift 19=189 (LC 9)
Max Grav 13=1400 (LC 30), 19=894 (LC 31), 33=1592 (LC 30)


FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/106, 2-3=-1608/0, 3-4=-1068/140, 4-5=-480/81, 5-6=-1205/155, 6-7=-1375/186, 7-8=-1375/186, 8-9=-1121/276, 9-10=-367/166, 10-11=-1128/138, 11-12=-1506/57, 2-33=-1747/0, 12-13=-1533/0
BOT CHORD 32-33=-275/318, 29-32=-182/1582, 27-29=-202/1915, 25-27=-478/2025, 23-25=-478/2025, 19-23=-478/2025, 17-19=-516/1290, 14-17=-237/1018, 13-14=-51/78, 30-31=-83/41, 28-30=-689/112, 26-28=-1288/154, 24-26=-1288/154, 22-24=-1155/408, 20-22=-743/813, 18-20=-743/813, 16-18=-134/213, 15-16=-57/137

WEBS
4-36=-958/380, 34-36=-318/653, 34-35=-532/582, 10-35=-1506/344, 2-32=0/802, 12-14=-91/925, 31-32=0/394, 3-31=0/549, 14-15=-210/256, 11-15=-197/379, 30-32=-788/90, 16-17=-218/148, 29-30=-80/341, 17-18=-410/379, 28-29=-473/25, 18-19=-431/402, 27-28=-30/343, 19-20=-59/37, 26-27=-274/0, 24-27=-152/539, 24-25=-223/47, 22-23=-14/261, 7-34=-249/76, 8-35=-341/96, 6-36=-228/106, 5-36=-230/1028, 6-34=-100/222, 8-34=-73/506, 9-35=-153/1274, 14-16=-343/309, 19-22=-1075/28

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Exterior(2E) -1-8-6 to 1-3-10, Interior (1) 1-3-10 to 8-0-0, Exterior(2R) 8-0-0 to 12-2-15, Interior (1) 12-2-15 to 20-1-0, Exterior(2R) 20-1-0 to 24-3-15, Interior (1) 24-3-15 to 27-11-4 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=18.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10, Lu=50-0-0
4) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 13.9 psf on overhangs non-concurrent with other live loads.
5) Provide adequate drainage to prevent water ponding.
6) All plates are 3x5 MT20 unless otherwise indicated.

- 7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) Ceiling dead load (5.0 psf) on member(s). 3-4, 10-11, 4-36, 34-36, 34-35, 10-35; Wall dead load (5.0psf) on member(s). 3-31, 11-15
9) Bottom chord live load (40.0 psf) and additional bottom chord dead load (0.0 psf) applied only to room. 30-31, 28-30, 26-28, 24-26, 22-24, 20-22, 18-20, 16-18, 15-16
10) All bearings are assumed to be SP No.2.
11) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 189 lb uplift at joint 19.
12) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
13) Attic room checked for L/360 deflection.

LOAD CASE(S) Standard



June 6,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932


Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009664
25040114-01	B2	Attic	3	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:07

Page: 1

ID:q6e9S74vD_Tfr0FgleRNuyzPfzA-RfC?PsB70Hg3NSgPqnL8w3uTXbGKWrcDoi7J4zJC?f



Scale = 1:92.2

Plate Offsets (X, Y): [2:0-3-4,0-1-12], [5:0-5-14,0-3-0], [9:0-5-14,0-3-0], [11:0-3-0,0-2-8], [12:0-3-4,0-1-12], [14:0-3-4,0-1-12], [15:0-3-4,0-1-12], [16:0-3-4,0-1-12], [17:0-3-4,0-1-12], [18:0-3-4,0-1-12], [19:0-3-4,0-1-12], [20:0-3-4,0-1-12], [21:0-3-4,0-1-12], [22:0-3-4,0-1-12], [23:0-3-4,0-1-12], [24:0-3-4,0-1-12], [25:0-3-4,0-1-12], [26:0-3-4,0-1-12], [27:0-3-4,0-1-12], [28:0-3-4,0-1-12], [29:0-3-4,0-1-12], [30:0-3-4,0-1-12], [31:0-3-4,0-1-12], [32:0-3-4,0-1-12], [33:0-3-4,0-1-12], [34:0-3-4,0-1-12]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.62	Vert(LL)	0.27	33-34	>999	240	MT20	244/190
Snow (Pf/Pg)	18.9/20.0	Lumber DOL	1.15	BC	0.92	Vert(CT)	-0.31	33-34	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.46	Horz(CT)	0.06	14	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MSH		Attic	-0.16	16-32	>999	360		
BCDL	10.0											
											Weight: 291 lb	FT = 20%

LUMBER
TOP CHORD 2x6 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3 *Except* 3-33,11-15,4-10:2x4 SP No.2

BRACING
TOP CHORD Structural wood sheathing directly applied or 4-10-2 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 5-9.
BOT CHORD Rigid ceiling directly applied or 2-2-0 oc bracing.
JOINTS 1 Brace at Jt(s): 17, 31, 21, 27, 35, 36, 37

REACTIONS (size) 14=0-3-8, 34=0-3-8
Max Horiz 34=288 (LC 11)
Max Grav 14=1785 (LC 3), 34=1785 (LC 3)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/106, 2-3=-1906/0, 3-4=-1242/116, 4-5=-462/202, 5-6=-1184/303, 6-7=-1358/181, 7-8=-1358/181, 8-9=-1183/304, 9-10=-459/204, 10-11=-1242/116, 11-12=-1906/0, 12-13=0/106, 2-34=-2048/0, 12-14=-2048/0
BOT CHORD 33-34=-296/348, 30-33=0/1790, 28-30=0/2277, 26-28=0/3037, 24-26=0/3037, 20-24=0/3037, 18-20=0/2263, 15-18=0/1708, 14-15=-40/84, 31-32=-88/111, 29-31=-767/44, 27-29=-1903/0, 25-27=-1903/0, 23-25=-2172/0, 21-23=-1902/0, 19-21=-1902/0, 17-19=-766/54, 16-17=-91/114

WEBS
32-33=0/570, 3-32=0/725, 15-16=0/570, 11-16=0/725, 4-37=-1457/309, 35-37=-593/468, 35-36=-594/467, 10-36=-1476/313, 15-17=-1029/0, 31-33=-1029/0, 17-18=0/464, 30-31=0/464, 18-19=-836/0, 29-30=-836/0, 19-20=0/667, 28-29=0/666, 20-21=-152/0, 27-28=-152/3, 20-23=-349/32, 25-28=-354/39, 25-26=-9/52, 23-24=-8/51, 2-33=0/1069, 12-15=0/1071, 7-35=-227/68, 8-36=-316/94, 6-37=-318/94, 5-37=-258/1096, 6-35=-124/395, 8-35=-125/398, 9-36=-257/1104

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Exterior(2E) -1-8-6 to 1-3-10, Interior (1) 1-3-10 to 8-0-0, Exterior(2R) 8-0-0 to 12-2-15, Interior (1) 12-2-15 to 20-1-0, Exterior(2R) 20-1-0 to 24-3-15, Interior (1) 24-3-15 to 29-9-6 zone; cantilever left and right exposed ; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
3) TALL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=18.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10, Lu=50-0-0
4) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 13.9 psf on overhangs non-concurrent with other live loads.
5) Provide adequate drainage to prevent water ponding.
6) All plates are 3x5 MT20 unless otherwise indicated.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.

8) Ceiling dead load (5.0 psf) on member(s). 3-4, 10-11, 4-37, 35-37, 35-36, 10-36; Wall dead load (5.0psf) on member(s).3-32, 11-16
9) Bottom chord live load (40.0 psf) and additional bottom chord dead load (0.0 psf) applied only to room. 31-32, 29-31, 27-29, 25-27, 23-25, 21-23, 19-21, 17-19, 16-17
10) All bearings are assumed to be SP No.2.
11) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
12) Attic room checked for L/360 deflection.
LOAD CASE(S) Standard



June 6,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932



Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009665
25040114-01	B1	Attic Supported Gable	2	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:06

Page: 1

ID:Mv5mF4HShLoDshUlw8LlzPzB-RfC?PsB70Hq3NSgPqnL8w3uTXbGKWrcDoi7J4zJC?f



Scale = 1:93.2

Plate Offsets (X, Y): [8:0-5-14,0-3-0], [12:0-5-14,0-3-0], [13:0-3-0,0-1-8], [20:Edge,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.53	Vert(LL)	n/a	-	n/a	999	244/190
Snow (Pf/Pg)	18.9/20.0	Lumber DOL	1.15	BC	0.24	Vert(CT)	n/a	-	n/a	999	
TCDL	10.0	Rep Stress Incr	YES	WB	0.48	Horz(CT)	-0.01	20	n/a	n/a	
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH							
BCDL	10.0										
Weight: 320 lb FT = 20%											

LUMBER	
TOP CHORD	2x6 SP No.2
BOT CHORD	2x4 SP No.2
WEBS	2x4 SP No.3 *Except* 6-42,14-24,7-13:2x4 SP No.2
OTHERS	2x4 SP No.3
BRACING	
TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (5-5-1 max.): 8-12.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 38-40,26-28.
WEBS	1 Row at midpt 6-41, 14-25
JOINTS	1 Brace at Jt(s): 47, 48, 49, 40, 26, 30, 36
REACTIONS (size)	
	20=28-1-0, 21=28-1-0, 22=28-1-0, 23=28-1-0, 24=28-1-0, 27=28-1-0, 29=28-1-0, 33=28-1-0, 35=28-1-0, 37=28-1-0, 39=28-1-0, 42=28-1-0, 43=28-1-0, 44=28-1-0, 45=28-1-0, 46=28-1-0
Max Horiz	46=-288 (LC 11)
Max Uplift	20=-458 (LC 10), 21=-361 (LC 11), 22=-74 (LC 14), 23=-82 (LC 14), 43=-81 (LC 13), 44=-74 (LC 13), 45=-378 (LC 12), 46=-478 (LC 9)
Max Grav	20=599 (LC 30), 21=421 (LC 12), 22=172 (LC 31), 23=129 (LC 12), 24=761 (LC 2), 27=122 (LC 11), 29=102 (LC 12), 33=73 (LC 12), 35=94 (LC 11), 37=103 (LC 12), 39=128 (LC 11), 42=759 (LC 2), 43=129 (LC 11), 44=172 (LC 30), 45=438 (LC 11), 46=617 (LC 31)

FORCES	
(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	2-46=-419/304, 1-2=0/106, 2-3=-321/312, 3-4=-173/183, 4-5=-232/282, 5-6=-269/386, 6-7=-554/254, 7-8=-581/49, 8-9=-1569/135, 9-10=-1748/208, 10-11=-1748/208, 11-12=-1568/135, 12-13=-582/48, 13-14=-554/254, 14-15=-269/387, 15-16=-234/284, 16-17=-166/176, 17-18=-310/299, 18-19=0/106, 18-20=-408/292
BOT CHORD	45-46=-148/143, 44-45=-146/141, 43-44=-146/140, 42-43=-146/140, 39-42=-98/96, 37-39=-74/95, 35-37=-50/56, 33-35=-50/56, 29-33=-74/72, 27-29=-74/93, 24-27=-87/85, 23-24=-143/137, 22-23=-142/137, 21-22=-142/137, 20-21=-140/135, 40-41=-13/14, 38-40=-47/42, 36-38=-62/68, 34-36=-62/68, 32-34=-71/66, 30-32=-52/61, 28-30=-52/61, 26-28=-57/53, 25-26=-14/14
WEBS	10-47=-357/37, 11-48=-105/90, 9-49=-105/91, 9-47=-78/190, 11-47=-78/191, 41-42=-734/0, 6-41=-724/0, 24-25=-735/0, 14-25=-725/0, 7-49=-81/319, 47-49=-21/1394, 47-48=-16/1394, 13-48=-80/323, 40-42=-76/69, 26-27=-68/6, 39-40=-81/17, 27-28=-17/0, 38-39=-32/6, 28-29=-25/0, 37-38=-33/0, 29-30=-31/0, 36-37=-31/0, 29-32=-24/9, 34-37=-41/22, 34-35=-59/4, 32-33=-43/0, 8-49=-131/1303, 12-48=-134/1299, 24-26=-56/49, 33-34=-27/19, 5-43=-90/109, 4-44=-203/127, 3-45=-196/182, 15-23=-90/110, 16-22=-203/126, 17-21=-189/175

NOTES
1) Unbalanced roof live loads have been considered for this design.

- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Exterior(2E) -1-8-6 to 1-3-10, Interior (1) 1-3-10 to 8-0-0, Exterior(2R) 8-0-0 to 12-2-15, Interior (1) 12-2-15 to 20-1-0, Exterior(2R) 20-1-0 to 24-3-15, Interior (1) 24-3-15 to 29-9-6 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
- 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 4) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=18.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10, Lu=50-0-0
- 5) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 13.9 psf on overhangs non-concurrent with other live loads.
- 6) Provide adequate drainage to prevent water ponding.

June 6,2025

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020
25040114-01	B1	Attic Supported Gable	2	1	174009665
					Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:06
ID:Mv5mF4HShLoDshUlxw8LizPfbB-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrcDoi7J4zJC?f

Page: 2

- 7) All plates are 2x4 MT20 unless otherwise indicated.
- 8) Gable requires continuous bottom chord bearing.
- 9) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
- 10) Gable studs spaced at 2-0-0 oc.
- 11) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- 12) ~~Ceiling dead load (5.0psf) on member(s) 6-13-14, 7-48, 47-48, 47-48, 13-48; Wall dead load (5.0psf) on member(s) 6-41, 14-25~~
- 13) All bearings are assumed to be SP No.2 .
- 14) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 458 lb uplift at joint 20, 478 lb uplift at joint 46, 81 lb uplift at joint 43, 74 lb uplift at joint 44, 378 lb uplift at joint 45, 82 lb uplift at joint 23, 74 lb uplift at joint 22 and 361 lb uplift at joint 21.
- 15) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- 16) Attic room checked for L/360 deflection.

LOAD CASE(S) Standard



June 6, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009666
25040114-01	A9	Piggyback Base Girder	1	2	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:06
ID:fG0QJ29goqDpZxjqfvYo7DzPfz4-RfC?PsB70Hq3NSgPqnL8w3uITxbGKWrcDoi7J4zJC?f

Page: 1



Scale = 1:65.6

Plate Offsets (X, Y): [2:0-2-8,0-0-8], [3:0-2-11,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.94	Vert(LL)	-0.03	7-9	>999	240	MT20	244/190
Snow (Pf/Pg)	18.9/20.0	Lumber DOL	1.15	BC	0.16	Vert(CT)	-0.04	7-9	>999	180		
TCDL	10.0	Rep Stress Incr	NO	WB	0.44	Horz(CT)	0.00	6	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 348 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2 *Except* 3-5:2x4 SP No.1
BOT CHORD 2x6 SP No.2
WEBS 2x4 SP No.2 *Except* 9-1,9-2,10-1:2x4 SP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 3-5.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 1 Row at midpt 5-6

REACTIONS

(size) 6=0-3-0, 10=0-3-8
Max Horiz 10=299 (LC 8)
Max Grav 6=1434 (LC 43), 10=1171 (LC 27)

FORCES

(lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-688/0, 2-3=-876/2, 3-4=-612/0, 4-5=-612/0, 5-6=-1341/0, 1-10=-1123/0, 9-10=-280/174, 7-9=-70/614, 6-7=-119/86
BOT CHORD 1-9=0/977, 2-9=-527/89, 3-9=-214/124, 3-7=-139/117, 4-7=-1047/0, 5-7=0/1407
WEBS


NOTES

- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-5-0 oc.
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Unbalanced roof live loads have been considered for this design.

- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope); cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.33
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=18.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10, Lu=50-0-0
- Unbalanced snow loads have been considered for this design.
- Provide adequate drainage to prevent water ponding.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- All bearings are assumed to be SP No.2.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 986 lb down at 20-10-6 on top chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard

- Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-2=-48, 2-3=-48, 3-5=-58, 6-10=-20
Concentrated Loads (lb)
Vert: 12=-759 (F)



June 6,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009667
25040114-01	C6	Piggyback Base	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:10
ID:UP7oICzPjBkA1vLrFVPdQzPdF0-RfC?PsB70Hq3NSgPqnL8w3uITxbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:67.2

Plate Offsets (X, Y): [1:0-2-8,0-1-8], [2:0-2-11,Edge], [4:0-2-11,Edge], [5:0-2-8,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.88	Vert(LL)	-0.05	11-12	>999	240	MT20	244/190
Snow (Pf/Pg)	18.9/20.0	Lumber DOL	1.15	BC	0.38	Vert(CT)	-0.10	11-12	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.41	Horz(CT)	0.01	6	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 203 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3 *Except* 7-3,2-10,10-3:2x4 SP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 2-4.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 1 Row at midpt 4-7, 2-10, 3-10

REACTIONS

(size) 6=0-3-8, 10=0-3-8, 12=0-3-8
Max Horiz 12=219 (LC 12)
Max Grav 6=678 (LC 3), 10=1021 (LC 3), 12=462 (LC 29)

FORCES

(lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-419/111, 2-3=-170/165, 3-4=-461/187, 4-5=-714/136, 1-12=-466/91, 5-6=-744/89
BOT CHORD 11-12=-218/250, 10-11=-101/205, 9-10=-62/231, 7-9=-62/231, 6-7=-79/134
WEBS 2-11=0/224, 3-9=0/246, 4-7=-62/125, 1-11=-110/176, 5-7=-25/264, 3-7=-28/217, 2-10=-452/59, 3-10=-814/54

NOTES

1) Unbalanced roof live loads have been considered for this design.

- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Exterior(2E) 0-1-12 to 3-1-12, Interior (1) 3-1-12 to 6-8-13, Exterior(2R) 6-8-13 to 10-11-11, Interior (1) 10-11-11 to 18-2-3, Exterior(2R) 18-2-3 to 22-5-2, Interior (1) 22-5-2 to 24-9-4 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=18.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10, Lu=50-0-0
- Provide adequate drainage to prevent water ponding.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- All bearings are assumed to be SP No.2.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard



June 6, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009668
25040114-01	C5	Piggyback Base	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:09
ID:jtufIM7QGdZ5JdZRXUWK2ozPfz6-RfC?PsB70Hq3NSgPqnL8w3uITxbGKWrcDoi7J4zJC7f

Page: 1



Scale = 1:67.2

Plate Offsets (X, Y): [2:Edge,0-1-5], [3:0-2-11,Edge], [5:0-2-11,Edge], [6:0-3-8,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.87	Vert(LL)	-0.05	12-13	>999	240	MT20	244/190
Snow (Pf/Pg)	18.9/20.0	Lumber DOL	1.15	BC	0.38	Vert(CT)	-0.10	12-13	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.42	Horz(CT)	0.01	7	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 207 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3 *Except*
8-4,13-2-7-6,3-11,11-4:2x4 SP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 3-5.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 12-13.
WEBS 1 Row at midpt 5-8, 3-11, 4-11

REACTIONS

(size) 7=0-3-8, 11=0-3-8, 13=0-3-8
Max Horiz 13=247 (LC 10)
Max Grav 7=676 (LC 38), 11=1019 (LC 3), 13=550 (LC 3)

FORCES


(lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/112, 2-3=-432/130, 3-4=-170/169, 4-5=-460/189, 5-6=-712/139, 2-13=-602/120, 6-7=-742/92
BOT CHORD 12-13=-252/272, 11-12=-105/197, 10-11=-65/229, 8-10=-65/229, 7-8=-79/135
WEBS 3-12=-8/225, 4-10=0/246, 4-8=-26/220, 5-8=-64/125, 2-12=-129/240, 6-8=-27/261, 3-11=-436/56, 4-11=-824/52

NOTES

1) Unbalanced roof live loads have been considered for this design.

- Wind: ASCE 7-16; Vult=130mph (3-second gust)
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Exterior(2E) -1-9-11 to 1-2-5, Interior (1) 1-2-5 to 6-8-13, Exterior(2R) 6-8-13 to 10-11-11, Interior (1) 10-11-11 to 18-2-3, Exterior(2R) 18-2-3 to 22-5-2, Interior (1) 22-5-2 to 24-9-4 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=18.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10, Lu=50-0-0
- This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 13.9 psf on overhangs non-concurrent with other live loads.
- Provide adequate drainage to prevent water ponding.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- All bearings are assumed to be SP No.2.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard



June 6,2025


WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932

Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:09 Page: 1
ID:FhKH407oWvrEIT F n?4VbzPzf7-RfC?PsB70Hg3NSaPqnL8w3uLTxbGKWCrDoi7J4zJC?f

[illegible]

- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust)
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; H=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Exterior(2E) 1-9-11 to 1-2-5, Interior (1) 1-2-5 to 6-8-13, Exterior(2R) 6-8-13 to 10-11-11, Interior (1) 10-11-11 to 18-2-3, Exterior(2R) 18-2-3 to 22-5-2, Interior (1) 22-5-2 to 24-9-4 zone; cantilever left and right exposed ; end vertical left and right exposed ;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
- 3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=18.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10, Lu=50-0-0
- 4) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 13.9 psf on overhangs non-concurrent with other live loads.
- 5) Provide adequate drainage to prevent water ponding.
- 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 7) All bearings are assumed to be SP No.2 .
- 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 42 lb uplift at joint 11.
- 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

1) Unbalanced roof live loads have been considered for this design.




Design valid for use only with MiTeK® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinet.org) and **BCSI Building Component Safety Information** available from the Structural Building Components Association (www.sbcacomponents.com)

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009670
25040114-01	C3	Piggyback Base	3	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:09
ID:nUmvgt6AlcjN4JP3Q3UrzNzPfz8-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?i

Page: 1



Scale = 1:66.3

Plate Offsets (X, Y): [2:Edge,0-1-5], [3:0-2-11,Edge], [5:0-2-11,Edge], [6:0-2-8,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.86	Vert(LL)	-0.04	10-11	>999	240	244/190
Snow (Pf/Pg)	18.9/20.0	Lumber DOL	1.15	BC	0.46	Vert(CT)	-0.09	11-12	>999	180	
TCDL	10.0	Rep Stress Incr	YES	WB	0.25	Horz(CT)	0.01	7	n/a	n/a	
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH							
BCDL	10.0										
Weight: 194 lb FT = 20%											

LUMBER

TOP CHORD 2x4 SP No.2 *Except* 5-6:2x4 SP No.1
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3 *Except* 11-4,8-4,12-2,7-6:2x4 SP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 3-5.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 11-12.
WEBS 1 Row at midpt 4-11, 4-8

REACTIONS

(size) 7=0-3-8, 12=0-3-8
Max Horiz 12=247 (LC 10)
Max Grav 7=1096 (LC 3), 12=1202 (LC 3)

FORCES


(lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/112, 2-3=-1219/173, 3-4=-771/202, 4-5=-779/201, 5-6=-1214/158, 2-12=-1394/150, 6-7=-1255/124
BOT CHORD 11-12=-253/272, 10-11=-58/855, 8-10=-58/855, 7-8=-78/134
WEBS 3-11=0/417, 4-11=-407/87, 4-10=0/328, 4-8=-393/91, 5-8=0/399, 2-11=-18/560, 6-8=-24/567

NOTES

1) Unbalanced roof live loads have been considered for this design.

- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Exterior(2E) -1-9-11 to 1-2-5, Interior (1) 1-2-5 to 6-8-13, Exterior(2R) 6-8-13 to 10-11-11, Interior (1) 10-11-11 to 18-2-3, Exterior(2R) 18-2-3 to 22-5-2, Interior (1) 22-5-2 to 24-9-4 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=18.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10, Lu=50-0-0
- This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 13.9 psf on overhangs non-concurrent with other live loads.
- Provide adequate drainage to prevent water ponding.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- All bearings are assumed to be SP No.2.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard



June 6,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009671
25040114-01	C2	Piggyback Base	12	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:09
ID:IIICXfL5X_lbWS9qssMycQAzPfz9-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWRcDoi7J4zJC?f

Page: 1



Scale = 1:66.3

Plate Offsets (X, Y): [2:Edge,0-1-5], [3:0-2-11,Edge], [5:0-2-11,Edge], [6:Edge,0-1-5]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.85	Vert(LL)	-0.04	11-12	>999	240	MT20	244/190
Snow (Pf/Pg)	18.9/20.0	Lumber DOL	1.15	BC	0.46	Vert(CT)	-0.09	8-9	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.25	Horz(CT)	0.01	8	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 198 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3 *Except* 12-4,9-4,13-2,8-6:2x4 SP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 3-5.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 1 Row at midpt 4-12, 4-9

REACTIONS

(size) 8=0-3-8, 13=0-3-8
Max Horiz 13=264 (LC 11)
Max Grav 8=1198 (LC 3), 13=1198 (LC 3)

FORCES


(lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/112, 2-3=-1215/176, 3-4=-769/203, 4-5=-769/203, 5-6=-1215/176, 6-7=0/112, 2-13=-1389/152, 6-8=-1389/152
BOT CHORD 12-13=-234/300, 11-12=-37/813, 9-11=-37/813, 8-9=-80/136
WEBS 3-12=0/415, 4-12=-403/90, 4-11=0/328, 4-9=-403/89, 5-9=0/414, 2-12=-19/557, 6-9=-20/557

NOTES

1) Unbalanced roof live loads have been considered for this design.

- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Exterior(2E) -1-9-11 to 1-2-5, Interior (1) 1-2-5 to 6-8-13, Exterior(2R) 6-8-13 to 10-11-11, Interior (1) 10-11-11 to 18-2-3, Exterior(2R) 18-2-3 to 22-5-2, Interior (1) 22-5-2 to 26-8-11 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=18.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10, Lu=50-0-0
- This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 13.9 psf on overhangs non-concurrent with other live loads.
- Provide adequate drainage to prevent water ponding.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- All bearings are assumed to be SP No.2.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard



June 6,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009672
25040114-01	C1	Piggyback Base Supported Gable	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:09
ID:JZkyE9lCzWk6?ne8MQmcizPtyu-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:65

Plate Offsets (X, Y): [7:0-2-5,Edge], [13:0-2-5,Edge]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.38	Vert(LL)	n/a	-	n/a	999	244/190
Snow (Pf/Pg)	18.9/20.0	Lumber DOL	1.15	BC	0.17	Vert(CT)	n/a	-	n/a	999	
TCDL	10.0	Rep Stress Incr	YES	WB	0.24	Horz(CT)	-0.01	20	n/a	n/a	
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MR							
BCDL	10.0										
Weight: 247 lb FT = 20%											

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
WEBS	2x4 SP No.3
OTHERS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (10-0-0 max.): 7-13.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS	1 Row at midpt 10-27, 9-28, 8-29, 6-30, 11-26, 12-24, 14-23

REACTIONS (size)

20=24-11-0, 21=24-11-0, 22=24-11-0, 23=24-11-0, 24=24-11-0, 26=24-11-0, 27=24-11-0, 28=24-11-0, 29=24-11-0, 30=24-11-0, 31=24-11-0, 32=24-11-0, 33=24-11-0	
Max Horiz	33=264 (LC 11)
Max Uplift	20=197 (LC 10), 21=206 (LC 9), 22=74 (LC 14), 26=8 (LC 9), 27=2 (LC 10), 28=8 (LC 10), 31=74 (LC 13), 32=213 (LC 10), 33=207 (LC 9)
Max Grav	20=311 (LC 29), 21=325 (LC 12), 22=167 (LC 36), 23=207 (LC 31), 24=166 (LC 35), 26=159 (LC 35), 27=160 (LC 2), 28=159 (LC 36), 29=166 (LC 36), 30=208 (LC 32), 31=167 (LC 35), 32=333 (LC 11), 33=320 (LC 30)

FORCES

(lb) - Maximum Compression/Maximum Tension

TOP CHORD

2-33=-505/479, 1-2=0/112, 2-3=-309/392, 3-4=-194/221, 4-5=-181/263, 5-6=-285/403, 6-7=-185/225, 7-8=-211/295, 8-9=-211/295, 9-10=-211/295, 10-11=-211/295, 11-12=-211/295, 12-13=-211/295, 13-14=-184/226, 14-15=-294/407, 15-16=-188/274, 16-17=-184/212, 17-18=-302/378, 18-19=0/112, 18-20=-496/457


BOT CHORD

32-33=-142/135, 31-32=-142/135, 30-31=-142/135, 29-30=-142/135, 28-29=-142/135, 27-28=-142/135, 26-27=-142/135, 24-26=-142/135, 23-24=-142/135, 22-23=-142/135, 21-22=-142/135, 20-21=-142/135, 10-27=-140/37, 9-28=-151/59, 8-29=-126/11, 6-30=-216/78, 5-31=-223/170, 4-32=-231/193, 3-33=-530/545, 11-26=-151/60, 12-24=-126/12, 14-23=-225/89, 15-22=-224/170, 16-21=-226/182, 17-20=-509/523

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Corner (3E) -1-9-11 to 1-2-5, Exterior(2N) 1-2-5 to 6-8-13, Corner(3R) 6-8-13 to 9-8-13, Exterior(2N) 9-8-13 to 18-2-3, Corner(3R) 18-2-3 to 21-2-3, Exterior(2N) 21-2-3 to 26-8-11 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.

- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=18.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10, Lu=50-0-0
- This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 13.9 psf on overhangs non-concurrent with other live loads.
- Provide adequate drainage to prevent water ponding.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
- Gable studs spaced at 2-0-0 oc.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- All bearings are assumed to be SP No.2.



June 6, 2025

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)


ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020
25040114-01	C1	Piggyback Base Supported Gable	1	1	174009672
Job Reference (optional)					

- 13) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 197 lb uplift at joint 20, 207 lb uplift at joint 33, 2 lb uplift at joint 27, 8 lb uplift at joint 28, 74 lb uplift at joint 31, 213 lb uplift at joint 32, 8 lb uplift at joint 26, 74 lb uplift at joint 22 and 206 lb uplift at joint 21.
- 14) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard



June 6,2025


Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009673
25040114-01	L3	Roof Special Girder	1	2	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:13

Page: 1

ID:j8Q5sAL4GR6hsEMj1ZJJEzPfyR-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:100.5

Plate Offsets (X, Y): [1:0-4-8,0-1-5], [2:0-2-4,0-1-8], [5:Edge,0-2-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.38	Vert(LL)	-0.05	8-9	>999	240	MT20	244/190
Snow (Pf/Pg)	13.9/20.0	Lumber DOL	1.15	BC	0.56	Vert(CT)	-0.09	8-9	>999	180		
TCDL	10.0	Rep Stress Incr	NO	WB	0.96	Horz(CT)	0.08	7	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 319 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2
 BOT CHORD 2x6 SP No.2
 WEBS 2x4 SP No.3 *Except* 8-5,7-6,7-5:2x4 SP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 5-0-14 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except:
 6-0-0 oc bracing: 9-10.

WEBS 1 Row at midpt 6-7, 5-7

REACTIONS (size) 7=0-3-8, 10=0-3-8

Max Horiz 10=413 (LC 6)

Max Grav 7=1765 (LC 20), 10=5235 (LC 21)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=-6061/0, 2-4=-1834/0, 4-5=-1840/0, 5-6=-268/213, 1-10=-5102/0, 6-7=-249/178

BOT CHORD 9-10=-544/395, 1-9=0/3867, 8-9=0/4124, 7-8=-80/299

WEBS 2-9=0/5057, 2-8=-3513/0, 4-8=-359/249, 5-8=0/2869, 5-7=-1652/25


NOTES

- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
 Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
 Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-3-0 oc.
 Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust)
 Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope); cantilever left and right exposed; end vertical left and right exposed;
 Lumber DOL=1.60 plate grip DOL=1.33
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- All bearings are assumed to be SP No.2.
- Bearing at joint(s) 10 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 4799 lb down at 2-9-6 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard

- Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
 Uniform Loads (lb/ft)
 Vert: 1-5=-48, 5-6=-48, 9-10=-20, 7-9=-20
 Concentrated Loads (lb)
 Vert: 9=-3852 (B), 12=-810 (B)



June 6,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
 A MiTek Affiliate


818 Soundside Road
 Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009674
25040114-01	E3	Piggyback Base Girder	1	2	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:11
ID:t1TvoBKSZl9w_UjyPCvCduzPuRt-RfC?PsB70Hq3NSgPqnL8w3uITXbGKwRCDoi7J4zJC?f

Page: 1




Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009675
25040114-01	VL1	Valley	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:16

Page: 1

ID: ?_iz004HWrvvyGcwgH0HHTzPuSc-RfC?PsB70Hq3NSgPqnL8w3uITxbGKWrCDoi7J4zJC?r



Scale = 1:50.7

Plate Offsets (X, Y): [3:0-2-5,Edge], [7:0-2-5,Edge]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.19	Vert(LL)	n/a	-	n/a	999	MT20
Snow (Pf/Pg)	18.9/20.0	Lumber DOL	1.15	BC	0.19	Vert(TL)	n/a	-	n/a	999	244/190
TCDL	10.0	Rep Stress Incr	YES	WB	0.28	Horiz(TL)	0.01	9	n/a	n/a	
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH							
BCDL	10.0										
Weight: 122 lb FT = 20%											

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except 2-0-0 oc purlins (6-0-0 max.): 3-7.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 1=24-0-0, 9=24-0-0, 10=24-0-0, 11=24-0-0, 13=24-0-0, 14=24-0-0, 15=24-0-0
Max Horiz 1=-141 (LC 9)
Max Uplift 10=-117 (LC 14), 13=-14 (LC 9), 14=-5 (LC 10), 15=-122 (LC 13)
Max Grav 1=181 (LC 30), 9=176 (LC 31), 10=487 (LC 29), 11=379 (LC 37), 13=410 (LC 36), 14=379 (LC 36), 15=495 (LC 28)

FORCES

(lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-204/145, 2-3=-140/52, 3-4=-65/62, 4-5=-65/62, 5-6=-65/62, 6-7=-65/62, 7-8=-140/52, 8-9=-201/145
BOT CHORD 1-15=-138/175, 14-15=-138/175, 13-14=-138/175, 11-13=-138/175, 10-11=-138/175, 9-10=-138/175
WEBS 5-13=-297/94, 4-14=-243/58, 2-15=-364/211, 6-11=-243/58, 8-10=-364/211

NOTES

1) Unbalanced roof live loads have been considered for this design.

- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Corner (3E) 0-0-0 to 3-0-0, Exterior(2N) 3-0-0 to 6-3-5, Corner (3R) 6-3-5 to 9-3-5, Exterior(2N) 9-3-5 to 17-8-11, Corner(3R) 17-8-11 to 20-8-11, Exterior(2N) 20-8-11 to 24-0-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=18.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10, Lu=50-0-0
- Provide adequate drainage to prevent water ponding.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- All bearings are assumed to be SP No.2.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 14 lb uplift at joint 13, 5 lb uplift at joint 14, 122 lb uplift at joint 15 and 117 lb uplift at joint 10.
- Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 1, 9.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard



June 6, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020
25040114-01	L1	Roof Special	2	1	Job Reference (optional)


I74009676

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:13

Page: 1

ID: BowcxuxO2lyMPALNb7EZPQzPfzMRfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:98.1

Plate Offsets (X, Y): [5:Edge,0-2-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.32	Vert(LL)	-0.15	7-8	>999	240	MT20	244/190
Snow (Pf/Pg)	13.9/20.0	Lumber DOL	1.15	BC	0.61	Vert(CT)	-0.23	7-8	>724	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.66	Horz(CT)	0.03	7	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 147 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3 *Except* 7-6,8-5,7-5:2x4 SP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 5-8-12 oc purlins.
BOT CHORD Rigid ceiling directly applied or 8-2-11 oc bracing.
WEBS 1 Row at midpt 6-7, 4-8, 5-8, 5-7

REACTIONS

(size) 7=0-3-8, 10=0-3-8
Max Horiz 10=310 (LC 13)
Max Uplift 7=-184 (LC 13)
Max Grav 7=794 (LC 28), 10=652 (LC 29)

FORCES

(lb) - Maximum Compression/Maximum Tension

TOP CHORD 5-6=-52/77, 1-2=-999/280, 2-4=-620/32, 4-5=-844/329
BOT CHORD 9-10=-523/485, 8-9=-494/852, 7-8=-40/115
WEBS 2-9=-320/368, 1-10=-825/223, 1-9=-139/614, 6-7=-81/52, 2-8=-461/367, 4-8=-521/335, 5-8=-482/1141, 5-7=-762/265

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Exterior(2E) 0-1-12 to 3-1-12, Interior (1) 3-1-12 to 11-11-15, Exterior(2E) 11-11-15 to 14-3-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33

- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- All bearings are assumed to be SP No.2.
- Bearing at joint(s) 10 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 184 lb uplift at joint 7.

LOAD CASE(S) Standard



June 6,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009677
25040114-01	L2	Roof Special	5	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:13
ID:f_U78Ey0pc4D0JwZ9ri0xezPfzL-RfC?PsB70Hq3NSgPqnL8w3uITxbGKWrcDoi7J4zJC?f

Page: 1



Scale = 1:81.2

Plate Offsets (X, Y): [3:0-2-8,0-0-4], [5:Edge,0-2-8]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.80	Vert(LL)	-0.14	7-8	>999	240	244/190
Snow (Pf/Pg)	13.9/20.0	Lumber DOL	1.15	BC	0.56	Vert(CT)	-0.22	7-8	>787	180	
TCDL	10.0	Rep Stress Incr	YES	WB	0.74	Horz(CT)	0.01	7	n/a	n/a	
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH							
BCDL	10.0										
										Weight: 157 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3 *Except* 7-6:2x4 SP No.1,
7-5,8-5:2x4 SP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or
5-11-5 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc
bracing.
WEBS 1 Row at midpt 6-7, 5-7, 5-8, 4-8

REACTIONS (size) 7=0-3-8, 10=0-3-8
Max Horiz 10=396 (LC 12)
Max Uplift 7=91 (LC 10)
Max Grav 7=777 (LC 29), 10=799 (LC 30)

FORCES


(lb) - Maximum Compression/Maximum
Tension
TOP CHORD 1-2=0/95, 2-3=-678/104, 3-4=-777/237,
4-5=-853/452, 5-6=-386/427, 2-10=-806/177,
6-7=-352/367
BOT CHORD 9-10=-650/549, 8-9=-304/529, 7-8=-197/252
WEBS 3-9=-363/162, 2-9=-19/446, 5-7=-854/508,
5-8=-378/938, 4-8=-589/433, 4-9=-205/336

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust)
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat.
II; Exp B; Enclosed; MWFRS (envelope) and C-C
Exterior(2E) -1-9-14 to 1-2-2, Interior (1) 1-2-2 to
11-11-15, Exterior(2E) 11-11-15 to 14-3-8 zone;
cantilever left and right exposed; end vertical left and
right exposed; C-C for members and forces & MWFRS
for reactions shown; Lumber DOL=1.60 plate grip
DOL=1.33

- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15
Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum
DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully
Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- This truss has been designed for greater of min roof live
load of 12.0 psf or 2.00 times flat roof load of 13.9 psf on
overhangs non-concurrent with other live loads.
- * This truss has been designed for a live load of 20.0psf
on the bottom chord in all areas where a rectangle
3-06-00 tall by 2-00-00 wide will fit between the bottom
chord and any other members, with BCDL = 10.0psf.
- All bearings are assumed to be SP No.2 .
- Provide mechanical connection (by others) of truss to
bearing plate capable of withstanding 91 lb uplift at joint
7.

LOAD CASE(S) Standard



June 6, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009678
25040114-01	E5	Piggyback Base Girder	1	2	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:11
ID:nmIKRUJqkqsZdCKv8Hr9zzPfyf-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:82

Plate Offsets (X, Y): [3:0-2-11,Edge], [5:0-2-11,Edge], [11:0-4-0,0-3-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.39	Vert(LL)	-0.06	10-11	>999	240	MT20	244/190
Snow (Pf/Pg)	18.9/20.0	Lumber DOL	1.15	BC	0.64	Vert(CT)	-0.11	10-11	>999	180		
TCDL	10.0	Rep Stress Incr	NO	WB	0.42	Horz(CT)	0.04	7	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 369 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x6 SP No.2
WEBS 2x4 SP No.3 *Except* 10-4-8-4:2x4 SP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 3-5.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 7= Mechanical, 12=0-3-8
Max Horiz 12=252 (LC 6)
Max Grav 7=1020 (LC 20), 12=1674 (LC 21)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-12=-1935/0, 1-2=-3184/0, 2-3=-1142/0, 3-4=-670/63, 4-5=-454/72, 5-6=-793/36, 6-7=-930/0

BOT CHORD 11-12=-263/333, 10-11=-182/2181, 8-10=-42/605, 7-8=-36/31

WEBS 1-11=0/2304, 2-11=0/1529, 2-10=-1483/159, 3-10=0/506, 4-10=-30/372, 4-8=-425/69, 5-8=0/335, 6-8=-11/528


NOTES

- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust)
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope); cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.33
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=18.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10, Lu=50-0-0
- Provide adequate drainage to prevent water ponding.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Bearings are assumed to be: Joint 12 SP No.2 .
- Refer to girder(s) for truss to truss connections.
- Bearing at joint(s) 12 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 879 lb down at 2-7-10 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard

- Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-3=-48, 3-5=-58, 5-6=-48, 11-12=-20, 7-11=-20
Concentrated Loads (lb)
Vert: 13=-710 (B)



June 6,2025


WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932

Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:10 Page: 1
ID:tlxTEN7oa40KRTwhv75DRJzPuS8-RfC?PsB70Hq3NSqPqnL8w3ulTXbGKWRcDoi7J4zJC?f

[illegible]

June 6, 2025

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Components Association (www.sbcacomponents.com)


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009680
25040114-01	E1	Piggyback Base	5	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:10
ID:2K2nPWmM_76bBLfG3oBq0SzPuSV-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrcD0i7J4zJC?f

Page: 1



Scale = 1:84.8

Plate Offsets (X, Y): [4:0-2-11,Edge], [6:0-2-11,Edge], [9:0-3-12,0-2-8], [17:0-3-12,0-2-8], [18:0-5-4,0-2-8]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.82	Vert(LL)	-0.09	10-15	>999	240	244/190
Snow (Pf/Pg)	18.9/20.0	Lumber DOL	1.15	BC	0.79	Vert(CT)	-0.18	10-15	>999	180	
TCDL	10.0	Rep Stress Incr	NO	WB	0.42	Horz(CT)	0.08	8	n/a	n/a	
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH							
BCDL	10.0										
Weight: 193 lb FT = 20%											

LUMBER

TOP CHORD 2x4 SP No.2 *Except* 6-7:2x4 SP No.1
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3 *Except* 5-17,5-9:2x4 SP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 3-6-9 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 4-6.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except:
6-0-0 oc bracing: 14-16
5-0-6 oc bracing: 12-14.
WEBS 1 Row at midpt 5-17, 5-9

REACTIONS

(size) 8= Mechanical, 19=0-3-8
Max Horiz 19=215 (LC 10)
Max Grav 8=1259 (LC 3), 19=1161 (LC 3)

FORCES


(lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-19=-1466/79, 1-2=-2029/93,
2-3=-2082/220, 3-4=-1533/71, 4-5=-888/112,
5-6=-694/115, 6-7=-1096/3
BOT CHORD 18-19=-300/296, 17-18=-21/1059,
15-17=0/1626, 10-15=0/1626, 9-10=0/1626,
8-9=0/0, 14-16=-27/21, 12-14=-1115/0,
11-12=-6/98
WEBS 1-18=-11/1261, 2-18=-139/126, 7-8=-1440/0,
16-17=-26/205, 5-16=-26/213, 5-11=-327/87,
9-11=-301/76, 4-17=0/831, 6-9=0/454,
7-9=0/768, 14-15=0/219, 10-12=0/253,
3-17=-412/229, 3-18=-259/571,
14-17=-1205/0, 9-12=-1279/0

NOTES

1) Unbalanced roof live loads have been considered for this design.

- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust)
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Exterior(2E) 0-1-12 to 3-1-12, Interior (1) 3-1-12 to 8-11-3, Exterior(2R) 8-11-3 to 13-2-1, Interior (1) 13-2-1 to 15-4-15, Exterior(2R) 15-4-15 to 19-7-14, Interior (1) 19-7-14 to 21-0-4 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
- 3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=18.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10, Lu=50-0-0
- 4) 200.0lb AC unit load placed on the bottom chord, 12-2-1 from left end, supported at two points, 5-0-0 apart.
- 5) Provide adequate drainage to prevent water ponding.
- 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 7) Bearings are assumed to be: Joint 19 SP No.2 .
- 8) Refer to girder(s) for truss to truss connections.
- 9) Bearing at joint(s) 19 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard



June 6,2025


WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)


ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932

Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:05 Page: 1
ID:ujXO1J3fhNCybi6lBEPvoXzPlzC-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrcDoI7J4zJC?i

LOAD CASE(S) Standard

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust)
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; H=25ft; Cat.
II; Exp B; Enclosed; MWFRS (envelope) and C-C
Exterior(2E) -1-10-2 to 1-1-14, Interior (1) 1-1-14 to
20-9-14 zone; cantilever left and right exposed ; end
vertical left and right exposed; C-C for members and
forces & MWFRS for reactions shown; Lumber
DOL=1.60 plate grip DOL=1.33
- 2) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15
Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum
DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully
Exp.; Ce=0.9; Cs=1.00; Ct=1.0



Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009682
25040114-01	VL2	Valley	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:16
ID:Wo8aAg3fiXN2L61k7aV2kFzPuSD-RfC?PsB70Hq3NSgPqnL8w3uITxbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:68.2

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.25	n/a	-	n/a	999	MT20	244/190
Snow (Pf/Pg)	13.9/20.0	Lumber DOL	1.15	BC	0.17	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.36	Horiz(TL)	0.01	7	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH							
BCDL	10.0										
										Weight: 115 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
OTHERS	2x4 SP No.3 *Except* 11-4:2x4 SP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.

BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

WEBS 1 Row at midpt 4-11

REACTIONS	(size)
	1=20-0-0, 7=20-0-0, 8=20-0-0, 9=20-0-0, 11=20-0-0, 12=20-0-0, 13=20-0-0
Max Horiz	1=224 (LC 10)
Max Uplift	1=-110 (LC 11), 7=-71 (LC 12), 8=-80 (LC 14), 9=-167 (LC 14), 12=-166 (LC 13), 13=-87 (LC 13)
Max Grav	1=184 (LC 10), 7=154 (LC 14), 8=353 (LC 29), 9=523 (LC 29), 11=355 (LC 31), 12=522 (LC 28), 13=364 (LC 28)

FORCES (lb) - Maximum Compression/Maximum Tension


TOP CHORD	1-2=-278/226, 2-3=-216/152, 3-4=-258/204, 4-5=-258/204, 5-6=-180/104, 6-7=-278/226
BOT CHORD	1-13=-141/193, 12-13=-141/193, 11-12=-141/193, 9-11=-141/193, 8-9=-141/193, 7-8=-141/193
WEBS	4-11=-204/106, 3-12=-440/304, 2-13=-329/219, 5-9=-440/305, 6-8=-328/218

NOTES

- Unbalanced roof live loads have been considered for this design.

- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Corner (3E) 0-0-0 to 3-0-0, Exterior(2N) 3-0-0 to 10-0-0, Corner (3R) 10-0-0 to 13-0-0, Exterior(2N) 13-0-0 to 19-8-3 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- All bearings are assumed to be SP No.2.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 110 lb uplift at joint 1, 71 lb uplift at joint 7, 166 lb uplift at joint 12, 87 lb uplift at joint 13, 167 lb uplift at joint 9 and 80 lb uplift at joint 8.
- Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 1, 7.

LOAD CASE(S) Standard



June 6, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009683
25040114-01	E4	Piggyback Base	2	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:11
ID:EPosWCv7Whif9sB_UiB5J?zPfzO-RfC?PsB70Hq3NSgPqnL8w3uITxbGKWrCDoi7J4zJC?i

Page: 1



Scale = 1:63.4

Plate Offsets (X, Y): [1:0-1-8,0-1-8], [2:0-2-11,Edge], [3:0-2-11,Edge], [4:0-1-12,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.75	Vert(LL)	-0.08	7-8	>999	240	MT20	244/190
Snow (Pf/Pg)	18.9/20.0	Lumber DOL	1.15	BC	0.44	Vert(CT)	-0.11	7-8	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.15	Horz(CT)	0.01	5	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0											
Weight: 140 lb											FT = 20%	

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3 *Except* 7-2:2x4 SP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 2-3.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

WEBS 1 Row at midpt 2-8, 2-7, 3-7
REACTIONS (size) 5= Mechanical, 9= Mechanical
Max Horiz 9=229 (LC 10)
Max Grav 5=797 (LC 3), 9=805 (LC 3)

FORCES

(lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-827/143, 2-3=-519/191, 3-4=-794/157,
1-9=-931/116, 4-5=-934/117
BOT CHORD 8-9=-216/224, 7-8=-91/467, 5-7=-68/89
WEBS 2-8=-6/212, 2-7=-113/101, 3-7=-61/168,
1-8=-31/390, 4-7=-31/420

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Exterior(2E) 0-8-4 to 3-8-4, Interior (1) 3-8-4 to 6-8-9, Exterior(2R) 6-8-9 to 10-11-8, Interior (1) 10-11-8 to 13-2-6, Exterior(2R) 13-2-6 to 17-5-4, Interior (1) 17-5-4 to 18-9-10 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33

- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=18.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10, Lu=50-0-0
- Provide adequate drainage to prevent water ponding.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Refer to girder(s) for truss to truss connections.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard



June 6, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009684
25040114-01	A8	Roof Special	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:06
ID:u_2qc7GJhbMX8JvZglDv?7zPfyx-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:71.4

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.75	Vert(LL)	-0.10	7-8	>805	240	MT20	244/190
Snow (Pf/Pg)	13.9/20.0	Lumber DOL	1.15	BC	0.46	Vert(CT)	-0.15	7-8	>519	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.53	Horz(CT)	-0.01	7	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0											
Weight: 129 lb FT = 20%												

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
WEBS	2x4 SP No.3 *Except* 6-7:2x4 SP No.2, 11-1:2x6 SP No.2

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.

WEBS 1 Row at midpt 6-7, 5-8

REACTIONS	(size) 7= Mechanical, 8=0-3-8, 11=0-3-0
	Max Horiz 11=301 (LC 12)
	Max Uplift 7=-108 (LC 12), 8=-29 (LC 15)
	Max Grav 7=222 (LC 32), 8=1007 (LC 3), 11=420 (LC 33)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD	1-2=-515/36, 2-4=-256/302, 4-5=-173/259, 5-6=-223/189, 6-7=-147/171, 1-11=-374/72
BOT CHORD	10-11=-582/473, 8-10=-374/579, 7-8=-151/143
WEBS	5-7=-50/125, 4-8=-335/160, 2-10=0/196, 2-8=-653/192, 1-10=-24/259, 5-8=-300/27

NOTES

- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Exterior(2E) 0-2-12 to 3-2-12, Interior (1) 3-2-12 to 18-3-12 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10

- Unbalanced snow loads have been considered for this design.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - Bearings are assumed to be: Joint 11 SP No.2, Joint 8 SP No.2.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 108 lb uplift at joint 7 and 29 lb uplift at joint 8.
- LOAD CASE(S)** Standard



June 6, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932


Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009685
25040114-01	A4	Roof Special	6	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:05

Page: 1

ID:ujXO1J3fhNCybi6iBEPvoXzPfc-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKwRCDoi7J4zJC?i



Scale = 1:75.9

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.75	Vert(LL)	-0.10	8-9	>805	240	MT20	244/190
Snow (Pf/Pg)	13.9/20.0	Lumber DOL	1.15	BC	0.46	Vert(CT)	-0.15	8-9	>519	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.51	Horz(CT)	-0.01	8	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 132 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
WEBS	2x4 SP No.3 *Except* 7-8:2x4 SP No.2, 12-2:2x6 SP No.2

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS	1 Row at midpt 7-8, 6-9

REACTIONS

(size)	8= Mechanical, 9=0-3-8, 12=0-3-0
Max Horiz	12=313 (LC 12)
Max Uplift	8=-109 (LC 12), 9=-27 (LC 15), 12=-16 (LC 11)
Max Grav	8=222 (LC 33), 9=997 (LC 3), 12=520 (LC 2)

FORCES

(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=0/60, 2-3=-496/18, 3-5=-255/300, 5-6=-171/255, 6-7=-223/190, 7-8=-147/171, 2-12=-503/175
BOT CHORD	11-12=-582/485, 9-11=-369/560, 8-9=-150/144
WEBS	6-8=-50/126, 3-9=-628/184, 3-11=0/195, 5-9=-341/165, 6-9=-295/27, 2-11=-59/273

NOTES

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Exterior(2E) -1-10-2 to 1-1-14, Interior (1) 1-1-14 to 18-3-12 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33

- 2) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- 3) Unbalanced snow loads have been considered for this design.
- 4) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 13.9 psf on overhangs non-concurrent with other live loads.
- 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 6) Bearings are assumed to be: Joint 12 SP No.2 , Joint 9 SP No.2 .
- 7) Refer to girder(s) for truss to truss connections.
- 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 109 lb uplift at joint 8, 16 lb uplift at joint 12 and 27 lb uplift at joint 9.

LOAD CASE(S)

Standard




June 6,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932




818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009687
25040114-01	G1	Piggyback Base Structural Gable	2	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:11
ID:6DSSYe0nSc?TUel9RSyL6dzPuSG-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:72.6

Plate Offsets (X, Y): [7:0-2-5,Edge], [9:0-2-5,Edge]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.36	Vert(LL)	n/a	-	n/a	999	MT20
Snow (Pf/Pg)	18.9/20.0	Lumber DOL	1.15	BC	0.17	Vert(CT)	n/a	-	n/a	999	244/190
TCDL	10.0	Rep Stress Incr	YES	WB	0.27	Horz(CT)	-0.01	16	n/a	n/a	
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MR							
BCDL	10.0										
Weight: 143 lb FT = 20%											

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
WEBS	2x4 SP No.3
OTHERS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (10-0-0 max.): 7-9.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS

(size)	16=16-11-0, 17=16-11-0, 18=16-11-0, 19=16-11-0, 20=16-11-0, 21=16-11-0, 22=16-11-0, 23=16-11-0, 24=16-11-0, 25=16-11-0, 26=16-11-0
Max Horiz	26=266 (LC 14)
Max Uplift	16=-119 (LC 15), 17=-19 (LC 11), 18=-73 (LC 16), 19=-82 (LC 16), 23=-82 (LC 15), 24=-75 (LC 15), 25=-307 (LC 14), 26=-357 (LC 11)
Max Grav	16=317 (LC 44), 17=57 (LC 12), 18=210 (LC 44), 19=260 (LC 44), 20=224 (LC 60), 21=263 (LC 43), 22=224 (LC 62), 23=260 (LC 44), 24=220 (LC 56), 25=337 (LC 13), 26=525 (LC 58)

FORCES

(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	2-26=-570/442, 1-2=0/116, 2-3=-343/364, 3-4=-202/230, 4-5=-201/267, 5-6=-320/403, 6-7=-218/246, 7-8=-234/295, 8-9=-234/295, 9-10=-218/246, 10-11=-319/399, 11-12=-202/270, 12-13=-192/221, 13-14=-333/359, 14-15=0/116, 14-16=-558/434


BOT CHORD	25-26=-263/230, 24-25=-143/126, 23-24=-143/126, 22-23=-143/126, 21-22=-143/126, 20-21=-143/126, 19-20=-143/126, 18-19=-143/126, 17-18=-143/126, 16-17=-197/169
WEBS	8-21=-223/24, 6-22=-195/82, 5-23=-304/175, 4-24=-303/192, 3-26=-577/595, 10-20=-192/81, 11-19=-304/174, 12-18=-302/186, 13-16=-552/570

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Exterior(2E) -1-9-11 to 1-2-5, Interior (1) 1-2-5 to 6-9-7, Exterior(2E) 6-9-7 to 10-1-9, Exterior(2R) 10-1-9 to 14-5-8, Interior (1) 14-5-8 to 18-8-11 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=18.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10, Lu=50-0-0
- Unbalanced snow loads have been considered for this design.
- This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 13.9 psf on overhangs non-concurrent with other live loads.
- Provide adequate drainage to prevent water ponding.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.

- Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
- Gable studs spaced at 2-0-0 oc.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- All bearings are assumed to be SP No.2 .
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 357 lb uplift at joint 26, 307 lb uplift at joint 25, 19 lb uplift at joint 17, 119 lb uplift at joint 16, 82 lb uplift at joint 23, 75 lb uplift at joint 24, 82 lb uplift at joint 19 and 73 lb uplift at joint 18.
- Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 25, 17, 21, 22, 23, 24, 20, 19, 18.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard



June 6,2025


WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932

Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:12 Page: 1
ID:PqvXarJqo 13MK8mrUNz5qzPuRu-RfC?PsB70Hq3NSqPqnL8w3ulTXbGKWrcDoi7J4zJC?f



LUMBER		2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.	14) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 909 lb down at 2-0-0, 909 lb down at 4-0-0, 909 lb down at 6-0-0, 909 lb down at 8-0-0, 909 lb down at 10-0-0, 909 lb down at 12-0-0, and 909 lb down at 14-0-0, and 915 lb down at 16-0-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
TOP CHORD	2x4 SP No.2		
BOT CHORD	2x6 SP No.2		
WEBS	2x4 SP No.3		
BRACING		3) Unbalanced roof live loads have been considered for this design.	
TOP CHORD	Structural wood sheathing directly applied or 5-7-9 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 4-5, 6-7.	4) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope); cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.33	LOAD CASE(S) Standard
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 13-14.	5) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=18.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10, Lu=50-0-0	1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
REACTIONS (size) 8= Mechanical, 14=0-3-8 Max Horiz 14=246 (LC 60) Max Grav 8=4529 (LC 3), 14=3992 (LC 3)		6) Unbalanced snow loads have been considered for this design.	Uniform Loads (lb/ft) Vert: 1-2=-48, 2-4=-48, 4-5=-58, 5-6=-48, 6-7=-58, 13-14=-20, 8-13=-20
FORCES (lb) - Maximum Compression/Maximum Tension		7) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 13.9 psf on overhangs non-concurrent with other live loads.	Concentrated Loads (lb) Vert: 10=-737 (F), 9=-737 (F), 19=-737 (F), 21=-737 (F), 22=-737 (F), 23=-737 (F), 24=-737 (F), 25=-743 (F)
TOP CHORD	2-14=-3879/0, 1-2=0/116, 2-3=-5008/0, 3-4=-3574/0, 4-5=-2197/0, 5-6=-3572/0, 6-7=-63/12, 7-8=-148/12	8) Provide adequate drainage to prevent water ponding.	
BOT CHORD	13-14=-365/763, 2-13=0/3256, 12-13=0/3349, 10-12=0/2215, 9-10=0/3055, 8-9=0/2982	9) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members	
WEBS	3-13=0/1635, 3-12=-1306/0, 4-12=0/2505, 4-10=-114/102, 5-10=0/2515, 6-10=-1040/0, 6-9=0/1474, 6-8=-4712/0		

14) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 909 lb down at 2-0-0, 909 lb down at 4-0-0, 909 lb down at 6-0-0, 909 lb down at 8-0-0, 909 lb down at 10-0-0, 909 lb down at 12-0-0, and 909 lb down at 14-0-0, and 915 lb down at 16-0-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard

1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (lb/ft)

Vert: 1-2=-48, 2-4=-48, 4-5=-58, 5-6=-48, 6-7=-58, 13-14=-20, 8-13=-20

Concentrated Loads (lb)

Vert: 10=-737 (F), 9=-737 (F), 19=-737 (F), 21=-737 (F), 22=-737 (F), 23=-737 (F), 24=-737 (F), 25=-743 (F)




Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009690
25040114-01	G3	Piggyback Base	2	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:11

Page: 1

ID:AqKh7y?Ww?lIEl9mK1wt1CzPuSi-RfC?PsB70Hq3NSgPqnL8w3uITxbGKWrCDoi7J4zJC?f



Scale = 1:70.1

Plate Offsets (X, Y): [4:0-2-11,Edge], [5:0-2-11,Edge], [6:0-4-4,0-2-0]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.81	Vert(LL)	-0.02	10-11	>999	240	244/190
Snow (Pf/Pg)	18.9/20.0	Lumber DOL	1.15	BC	0.30	Vert(CT)	-0.06	8-9	>999	180	
TCDL	10.0	Rep Stress Incr	YES	WB	0.28	Horz(CT)	0.04	8	n/a	n/a	
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH							
BCDL	10.0										
Weight: 129 lb FT = 20%											

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 3-1-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 4-5, 6-7.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except:
6-0-0 oc bracing: 11-12.
WEBS 1 Row at midpt 4-9

REACTIONS

(size) 8= Mechanical, 12=0-3-8
Max Horiz 12=233 (LC 12)
Max Grav 8=810 (LC 46), 12=1045 (LC 46)

FORCES

(lb) - Maximum Compression/Maximum Tension
TOP CHORD 2-12=-1048/269, 1-2=0/116, 2-3=-1171/300, 3-4=-911/196, 4-5=-542/182, 5-6=-914/146, 6-7=-46/0, 7-8=-126/219
BOT CHORD 11-12=-317/293, 10-11=-230/785, 9-10=-68/417, 8-9=-161/734
WEBS 2-11=-65/753, 3-11=-191/266, 3-10=-433/247, 4-10=-92/308, 4-9=-103/127, 5-9=-28/205, 6-9=-346/204, 6-8=-1258/308

NOTES

1) Unbalanced roof live loads have been considered for this design.

- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Exterior(2E) -1-9-11 to 1-2-5, Interior (1) 1-2-5 to 6-9-7, Exterior(2R) 6-9-7 to 9-9-7, Interior (1) 9-9-7 to 10-1-9, Exterior(2R) 10-1-9 to 13-1-9, Interior (1) 13-1-9 to 16-5-12 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=18.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10, Lu=50-0-0
- Unbalanced snow loads have been considered for this design.
- This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 13.9 psf on overhangs non-concurrent with other live loads.
- Provide adequate drainage to prevent water ponding.
- The Fabrication Tolerance at joint 6 = 8%
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Bearings are assumed to be: Joint 12 SP No.2 .
- Refer to girder(s) for truss to truss connections.
- Bearing at joint(s) 12 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard



June 6,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009691
25040114-01	VL3	Valley	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:16
ID:Wo8aAg3fiXN2L61k7aV2kFzPuSD-RfC?PsB70Hq3NSgPqnL8w3uITxbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:57.7

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.27	n/a	-	n/a	999	MT20	244/190
Snow (Pf/Pg)	13.9/20.0	Lumber DOL	1.15	BC	0.16	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.16	Horiz(TL)	0.00	5	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH							
BCDL	10.0									Weight: 84 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
OTHERS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 10-0-0 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.

WEBS	1 Row at midpt	3-7
------	----------------	-----

REACTIONS	(size)	1=16-0-0, 5=16-0-0, 6=16-0-0, 7=16-0-0, 8=16-0-0
	Max Horiz	1=178 (LC 10)
	Max Uplift	1=-42 (LC 11), 5=-13 (LC 12), 6=-157 (LC 14), 8=-160 (LC 13)
	Max Grav	1=160 (LC 29), 5=122 (LC 31), 6=521 (LC 29), 7=437 (LC 28), 8=527 (LC 28)

FORCES	(lb) - Maximum Compression/Maximum Tension
--------	--

TOP CHORD	1-2=-173/222, 2-3=-115/135, 3-4=-115/126, 4-5=-174/221
-----------	--

BOT CHORD	1-8=-161/175, 7-8=-161/175, 6-7=-161/175, 5-6=-161/175
-----------	--


WEBS	3-7=-244/0, 2-8=-444/306, 4-6=-443/306
------	--

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Corner (3E) 0-0-0 to 3-0-0, Exterior(2N) 3-0-0 to 8-0-0, Corner (3R) 8-0-0 to 11-0-0, Exterior(2N) 11-0-0 to 15-8-3 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33

- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- All bearings are assumed to be SP No.2 .
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 42 lb uplift at joint 1, 13 lb uplift at joint 5, 160 lb uplift at joint 8 and 157 lb uplift at joint 6.
- Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 1, 5.

LOAD CASE(S) Standard



June 6,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	
25040114-01	C7	Piggyback Base Girder	1	2	Job Reference (optional)	I74009692

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:10
ID:ZBEST0bSmm96Vbb5pa3hzPdCw-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrcD0i7J4zJC?f

Page: 1



Scale = 1:66.9

Plate Offsets (X, Y): [3:0-4-4,0-1-0]

Loading	(psf)	Spacing	1-11-4	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.48	Vert(LL)	-0.02	8-9	>999	240	MT20	244/190
Snow (Pf/Pg)	18.9/20.0	Lumber DOL	1.15	BC	0.22	Vert(CT)	-0.03	8-9	>999	180		
TCDL	10.0	Rep Stress Incr	NO	WB	0.16	Horz(CT)	0.00	6	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0											
Weight: 333 lb											FT = 20%	

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x6 SP No.2
WEBS 2x4 SP No.3 *Except* 9-1,9-3:2x4 SP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 1-3.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 1 Row at midpt 1-10

REACTIONS

(size) 6=0-3-8, 10=0-3-8
Max Horiz 10=-280 (LC 7)
Max Uplift 6=-214 (LC 10), 10=-333 (LC 5)
Max Grav 6=1979 (LC 22), 10=1921 (LC 21)

FORCES

(lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-10=-1630/301, 1-2=-691/155, 2-3=-691/155, 3-4=-1280/243, 4-5=-1418/180, 5-6=-1710/186
BOT CHORD 9-10=-167/225, 8-9=-140/806, 7-8=-123/899, 6-7=-18/36
WEBS 1-9=-315/1697, 2-9=-283/87, 3-9=-332/132, 3-8=-218/1069, 4-8=-303/155, 4-7=-67/226, 5-7=-133/1055

NOTES

- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc.

- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope); cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.33
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=18.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10, Lu=50-0-0
- Provide adequate drainage to prevent water ponding.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- All bearings are assumed to be SP No.2.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 333 lb uplift at joint 10 and 214 lb uplift at joint 6.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- Use Simpson Strong-Tie LUS26 (4-10d Girder, 3-10d Truss, Single Ply Girder) or equivalent spaced at 2-0-0 oc max. starting at 1-10-8 from the left end to 13-10-8 to connect truss(es) to back face of bottom chord.
- Fill all nail holes where hanger is in contact with lumber.

LOAD CASE(S) Standard

- Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-3=-56, 3-5=-46, 6-10=-19
Concentrated Loads (lb)

Vert: 7=-205 (B), 11=-211 (B), 13=-205 (B), 14=-205 (B), 15=-205 (B), 16=-205 (B), 17=-205 (B)



June 6, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932


Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020
25040114-01	Q1	Roof Special Supported Gable	2	1	Job Reference (optional)

I74009693

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:16
ID:?VuV?cyHgefnu8FOVA3XIYZPa?A-RfC?PsB70Hq3NSgPqnL8w3uTXbGKwRCDoi7J4zJC?f

Page: 1



Scale = 1:82.4

Plate Offsets (X, Y): [9:Edge,0-1-8]

Loading	(psf)	Spacing	1-11-4	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.22	Vert(LL)	n/a	-	n/a	999	MT20
Snow (Pf/Pg)	13.9/20.0	Lumber DOL	1.15	BC	0.11	Vert(TL)	n/a	-	n/a	999	244/190
TCDL	10.0	Rep Stress Incr	YES	WB	0.47	Horiz(TL)	-0.01	9	n/a	n/a	
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH							
BCDL	10.0										
Weight: 140 lb FT = 20%											

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3
OTHERS 2x4 SP No.3 *Except* 13-5,12-6:2x4 SP No.2

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

WEBS 1 Row at midpt 5-13, 4-15, 6-12

REACTIONS (size) 9=14-0-8, 10=14-0-8, 11=14-0-8, 12=14-0-8, 13=14-0-8, 14=14-0-8, 15=14-0-8, 16=14-0-8, 17=14-0-8, 18=14-0-8
Max Horiz 18=244 (LC 10)
Max Uplift 9=-365 (LC 10), 10=-113 (LC 13), 11=-59 (LC 14), 12=-247 (LC 11), 13=-92 (LC 13), 14=-282 (LC 11), 15=-77 (LC 13), 16=-69 (LC 13), 17=-107 (LC 13), 18=-6 (LC 11)
Max Grav 9=358 (LC 11), 10=180 (LC 28), 11=204 (LC 29), 12=472 (LC 13), 13=217 (LC 28), 14=295 (LC 10), 15=180 (LC 28), 16=181 (LC 28), 17=183 (LC 28), 18=67 (LC 13)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-18=-87/98, 1-2=-101/132, 2-3=-177/220, 3-4=-285/352, 4-5=-400/494, 5-6=-485/599, 6-7=-487/601, 7-8=-399/495, 8-9=-291/347
BOT CHORD 17-18=-221/193, 16-17=-221/193, 15-16=-221/193, 14-15=-221/193, 13-14=-383/359, 12-13=-350/312, 11-12=-350/311, 10-11=-356/315, 9-10=-297/250

WEBS 5-13=-192/123, 4-15=-209/167, 3-16=-208/153, 2-17=-188/162, 6-12=-828/605, 7-11=-200/127, 8-10=-208/197

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Corner (3E) 0-1-12 to 3-0-4, Exterior(2N) 3-0-4 to 8-11-15, Corner(3R) 8-11-15 to 11-11-15, Exterior(2N) 11-11-15 to 14-0-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 2-0-0 oc.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- All bearings are assumed to be SP No.2.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 6 lb uplift at joint 18, 282 lb uplift at joint 14, 365 lb uplift at joint 9, 92 lb uplift at joint 13, 77 lb uplift at joint 15, 69 lb uplift at joint 16, 107 lb uplift at joint 17, 247 lb uplift at joint 12, 59 lb uplift at joint 11 and 113 lb uplift at joint 10.

11) Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 9, 13, 12, 11, 10.

LOAD CASE(S) Standard

June 6, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009694
25040114-01	PB7	Piggyback	1	4	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:15
ID:0i0WQ4UNSS_7TGkYEZJYjdzPZxv-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:50.1

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.06	n/a	-	n/a	999	MT20	244/190
Snow (Pf/Pg)	13.9/20.0	Lumber DOL	1.15	BC	0.04	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.03	Horiz(TL)	0.00	7	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH							
BCDL	10.0									Weight: 233 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
OTHERS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(size)	1=12-1-0, 2=12-1-0, 6=12-1-0, 7=12-1-0, 8=12-1-0, 9=12-1-0, 10=12-1-0
Max Horiz	1=-134 (LC 11)
Max Uplift	1=-102 (LC 9), 2=-22 (LC 24), 7=-26 (LC 12), 8=-124 (LC 14), 10=-149 (LC 13)
Max Grav	1=150 (LC 30), 2=89 (LC 14), 7=92 (LC 29), 8=397 (LC 30), 9=327 (LC 29), 10=415 (LC 29)

FORCES

(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=-194/172, 2-3=-166/141, 3-4=-208/126, 4-5=-207/126, 5-6=-157/121, 6-7=-73/37
BOT CHORD	2-10=-69/114, 9-10=-69/114, 8-9=-69/114, 6-8=-79/126
WEBS	4-9=-126/0, 3-10=-411/322, 5-8=-402/308

NOTES

- 4-ply truss to be connected together as follows:
Top chords connected with 10d (0.131"x3") nails as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected with 10d (0.131"x3") nails as follows: 2x4 - 1 row at 0-9-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Corner (3E) 0-2-7 to 3-2-7, Exterior(2N) 3-2-7 to 6-0-8, Corner (3R) 6-0-8 to 9-0-8, Exterior(2N) 9-0-8 to 11-10-9 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- All bearings are assumed to be SP No.2.
- Bearing at joint(s) 2, 6, 1, 7, 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 22 lb uplift at joint 2, 102 lb uplift at joint 1, 26 lb uplift at joint 7, 149 lb uplift at joint 10, 124 lb uplift at joint 8 and 22 lb uplift at joint 2.
- See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

LOAD CASE(S) Standard



June 6, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009695
25040114-01	PB6	Piggyback	1	2	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:15
ID:mGvYCTeUNZ0iu4wFTFCM7hzPa7J-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?fi

Page: 1



Scale = 1:50.1

Plate Offsets (X, Y): [2:0-3-10,0-1-8], [6:0-3-10,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.11	Vert(LL)	n/a	-	999	MT20	244/190
Snow (Pf/Pg)	13.9/20.0	Lumber DOL	1.15	BC	0.08	Vert(CT)	n/a	-	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.05	Horz(CT)	0.00	14	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH							
BCDL	10.0										
										Weight: 116 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 2=11-0-9, 6=11-0-9, 8=11-0-9, 9=11-0-9, 10=11-0-9
Max Horiz 2=-134 (LC 11)
Max Uplift 2=-74 (LC 11), 6=-54 (LC 12), 8=-148 (LC 14), 10=-149 (LC 13)
Max Grav 2=129 (LC 10), 6=109 (LC 9), 8=396 (LC 30), 9=329 (LC 29), 10=397 (LC 29)

FORCES


(lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/18, 2-3=-180/142, 3-4=-195/112, 4-5=-195/112, 5-6=-180/143, 6-7=0/18
BOT CHORD 2-10=-75/121, 9-10=-75/121, 8-9=-75/121, 6-8=-75/121
WEBS 4-9=-129/0, 3-10=-405/321, 5-8=-405/321

NOTES

- 2-ply truss to be connected together as follows:
Top chords connected with 10d (0.131"x3") nails as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected with 10d (0.131"x3") nails as follows: 2x4 - 1 row at 0-9-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Unbalanced roof live loads have been considered for this design.

- Wind: ASCE 7-16; Vult=130mph (3-second gust)
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Corner (3E) 0-2-7 to 3-2-7, Exterior(2N) 3-2-7 to 6-0-8, Corner (3R) 6-0-8 to 9-0-8, Exterior(2N) 9-0-8 to 11-10-9 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 13.9 psf on overhangs non-concurrent with other live loads.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- All bearings are assumed to be SP No.2.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 74 lb uplift at joint 2, 54 lb uplift at joint 6, 149 lb uplift at joint 10, 148 lb uplift at joint 8, 74 lb uplift at joint 2 and 54 lb uplift at joint 6.
- See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

LOAD CASE(S) Standard



June 6,2025


WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932

Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:15 Page: 1
ID:WJrSRwVbGh7xbs3Wke0wHzPevV-RfC?PsB70Hg3NSgPqnL8w3uITxbGKWkrCDoi7J4zJC?f



- 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 4) T.C.L.L: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- 5) Gable requires continuous bottom chord bearing.
- 6) Gable studs spaced at 4'-0" oc.
- 7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3'-06" tall by 2'-00" wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 8) All bearings are assumed to be SP No.2 .
- 9) Bearing at joint(s) 2, 6, 1, 7, 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 29 lb uplift at joint 2, 101 lb uplift at joint 1, 27 lb uplift at joint 7, 151 lb uplift at joint 10, 124 lb uplift at joint 8 and 29 lb uplift at joint 2.
- 11) See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MITEK® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI 1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbccomponents.com)

ENGINEERING BY
TRENCO
A MI Tek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009697
25040114-01	PB4	Piggyback	2	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:14
ID:Q2qS9Mh_6egX2qXqLfMCz_zPdho-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:47.2

Plate Offsets (X, Y): [2'-0"-3'-10", 0'-1'-8"], [8'-0"-3'-10", 0'-1'-8"]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.06	Vert(LL)	n/a	-	999	MT20	244/190
Snow (Pf/Pg)	13.9/20.0	Lumber DOL	1.15	BC	0.04	Vert(CT)	n/a	-	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.09	Horz(CT)	0.00	8	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH							
BCDL	10.0										
										Weight: 70 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 6'-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10'-0-0 oc bracing.

REACTIONS (size) 2=11'-0-9, 8=11'-0-9, 10=11'-0-9, 11=11'-0-9, 12=11'-0-9, 13=11'-0-9, 14=11'-0-9
Max Horiz 2=-134 (LC 11)
Max Uplift 2=-42 (LC 11), 8=-22 (LC 12), 10=-80 (LC 14), 11=-74 (LC 14), 13=-74 (LC 13), 14=-80 (LC 13)
Max Grav 2=127 (LC 30), 8=115 (LC 32), 10=179 (LC 30), 11=194 (LC 30), 12=118 (LC 32), 13=195 (LC 29), 14=179 (LC 29)

FORCES (lb) - Maximum Compression/Maximum Tension


TOP CHORD 1-2=0/18, 2-3=-145/129, 3-4=-112/73, 4-5=-142/108, 5-6=-142/108, 6-7=-93/48, 7-8=-145/130, 8-9=0/18
BOT CHORD 2-14=-107/131, 13-14=-107/131, 12-13=-107/131, 11-12=-107/131, 10-11=-107/131, 8-10=-107/131
WEBS 5-12=-108/68, 4-13=-222/142, 3-14=-195/129, 6-11=-222/142, 7-10=-195/129

NOTES

1) Unbalanced roof live loads have been considered for this design.

- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Exterior(2E) 0-2-7 to 3-2-7, Interior (1) 3-2-7 to 6-0-8, Exterior(2R) 6-0-8 to 9-0-8, Interior (1) 9-0-8 to 11-10-9 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 13.9 psf on overhangs non-concurrent with other live loads.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 2'-0-0 oc.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3'-06-00 tall by 2'-00-00 wide will fit between the bottom chord and any other members.
- All bearings are assumed to be SP No.2.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 42 lb uplift at joint 2, 22 lb uplift at joint 8, 74 lb uplift at joint 13, 80 lb uplift at joint 14, 74 lb uplift at joint 11, 80 lb uplift at joint 10, 42 lb uplift at joint 2 and 22 lb uplift at joint 8.
- See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

LOAD CASE(S) Standard



June 6, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009698
25040114-01	VL4	Valley	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:17
ID:Wo8aAg3fIXN2L61k7aV2kFzPuSD-RfC?PsB70Hq3NSgPqnL8w3uITxbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:47.6

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.23	Vert(LL)	n/a	-	n/a	999	MT20
Snow (Pf/Pg)	13.9/20.0	Lumber DOL	1.15	BC	0.17	Vert(TL)	n/a	-	n/a	999	244/190
TCDL	10.0	Rep Stress Incr	YES	WB	0.25	Horiz(TL)	0.00	5	n/a	n/a	
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH							
BCDL	10.0										
Weight: 59 lb FT = 20%											

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
OTHERS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 10-0-0 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS

(size)	1=12-0-0, 5=12-0-0, 6=12-0-0, 7=12-0-0, 8=12-0-0
Max Horiz	1=133 (LC 10)
Max Uplift	1=-118 (LC 11), 5=-1 (LC 28), 6=-115 (LC 14), 8=-130 (LC 13)
Max Grav	1=128 (LC 10), 6=401 (LC 29), 7=504 (LC 28), 8=389 (LC 28)

FORCES


(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=-178/230, 2-3=-184/241, 3-4=-184/240, 4-5=-34/118
BOT CHORD	1-8=-44/33, 7-8=-44/33, 6-7=-44/33, 5-6=-44/33
WEBS	3-7=-303/33, 2-8=-397/305, 4-6=-398/297

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Corner (3E) 0-0-0 to 3-0-0, Exterior(2N) 3-0-0 to 6-0-0, Corner (3R) 6-0-0 to 9-0-0, Exterior(2N) 9-0-0 to 12-0-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33

- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- All bearings are assumed to be SP No.2.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 118 lb uplift at joint 1, 1 lb uplift at joint 5, 130 lb uplift at joint 8, 115 lb uplift at joint 6 and 1 lb uplift at joint 5.
- Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 1, 5, 13.

LOAD CASE(S) Standard



June 6,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009699
25040114-01	PB2	Piggyback	19	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:14
ID:caiZZ4aio3?h_754UmO1PtzPdKh-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWRCDoi7J4zJC?f

Page: 1



Scale = 1:48.5

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.23	Vert(LL)	n/a	-	n/a	999	MT20
Snow (Pf/Pg)	13.9/20.0	Lumber DOL	1.15	BC	0.09	Vert(TL)	n/a	-	n/a	999	244/190
TCDL	10.0	Rep Stress Incr	YES	WB	0.11	Horiz(TL)	0.00	7	n/a	n/a	
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH							
BCDL	10.0										
										Weight: 54 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
OTHERS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(size)	1=11-5-7, 2=11-5-7, 6=11-5-7, 7=11-5-7, 8=11-5-7, 9=11-5-7, 10=11-5-7
Max Horiz	1=-126 (LC 11)
Max Uplift	1=-90 (LC 9), 2=-62 (LC 35), 7=-42 (LC 12), 8=-123 (LC 14), 10=-158 (LC 13)
Max Grav	1=143 (LC 30), 2=102 (LC 13), 7=87 (LC 14), 8=337 (LC 30), 9=207 (LC 2), 10=368 (LC 29)

FORCES

(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=-187/158, 2-3=-195/156, 3-4=-206/118, 4-5=-205/118, 5-6=-182/143, 6-7=-82/56, 2-10=-62/107, 9-10=-62/107, 8-9=-62/107, 6-8=-77/107
BOT CHORD	
WEBS	4-9=-120/0, 3-10=-445/353, 5-8=-430/335

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Corner (3E) 0-2-7 to 3-2-7, Exterior(2N) 3-2-7 to 5-8-11, Corner (3R) 5-8-11 to 8-8-11, Exterior(2N) 8-8-11 to 11-3-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33

- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- All bearings are assumed to be SP No.2 .
- Bearing at joint(s) 2, 6, 1, 7, 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 62 lb uplift at joint 2, 90 lb uplift at joint 1, 42 lb uplift at joint 7, 158 lb uplift at joint 10, 123 lb uplift at joint 8 and 62 lb uplift at joint 2.
- See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

LOAD CASE(S) Standard



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009700
25040114-01	PB1	Piggyback	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:14
ID:1hRZKk1w5RgPwQB92ZjPgZPdK6-RfC?PsB70Hq3NSgPqnL8w3uITxbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:45.5

Plate Offsets (X, Y): [2:0-3-10,0-1-8], [8:0-3-10,0-1-8]												
Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.06	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf/Pg)	13.9/20.0	Lumber DOL	1.15	BC	0.03	Vert(CT)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.07	Horz(CT)	0.00	8	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 65 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 6'-0" oc purlins.
BOT CHORD Rigid ceiling directly applied or 10'-0" oc bracing.

REACTIONS (size) 2=10-5-0, 8=10-5-0, 10=10-5-0, 11=10-5-0, 12=10-5-0, 13=10-5-0, 14=10-5-0
Max Horiz 2=-126 (LC 11)
Max Uplift 2=-50 (LC 11), 8=-30 (LC 12), 10=-74 (LC 14), 11=-76 (LC 14), 13=-76 (LC 13), 14=-75 (LC 13)
Max Grav 2=114 (LC 30), 8=104 (LC 32), 10=163 (LC 30), 11=197 (LC 30), 12=115 (LC 32), 13=198 (LC 29), 14=164 (LC 29)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/18, 2-3=-146/132, 3-4=-110/74, 4-5=-136/102, 5-6=-136/102, 6-7=-92/50, 7-8=-147/133, 8-9=0/18
BOT CHORD 2-14=-101/125, 13-14=-101/125, 12-13=-101/125, 11-12=-101/125, 10-11=-101/125, 8-10=-101/125
WEBS 5-12=-98/58, 4-13=-225/145, 3-14=-183/123, 6-11=-225/145, 7-10=-183/123

NOTES
1) Unbalanced roof live loads have been considered for this design.

- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Exterior(2E) 0-2-7 to 3-2-7, Interior (1) 3-2-7 to 5-8-11, Exterior(2R) 5-8-11 to 8-8-11, Interior (1) 8-8-11 to 11-3-0 zone; cantilever left and right exposed ; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 13.9 psf on overhangs non-concurrent with other live loads.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 2'-0" oc.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3'-0"-0" tall by 2'-0"-0" wide will fit between the bottom chord and any other members.
- All bearings are assumed to be SP No.2 .
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 50 lb uplift at joint 2, 30 lb uplift at joint 8, 76 lb uplift at joint 13, 75 lb uplift at joint 14, 76 lb uplift at joint 11, 74 lb uplift at joint 10, 50 lb uplift at joint 2 and 30 lb uplift at joint 8.
- See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

LOAD CASE(S) Standard



June 6,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009701
25040114-01	HJ1	Roof Special Girder	2	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:12
ID:E7aB2VeRA?DX82VhyheZfVzOdh9-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWCrCDoi7J4zJC?f

Page: 1



Scale = 1:38

Loading	(psf)	Spacing	1-11-4	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.99	Vert(LL)	-0.03	5-6	>999	240	244/190
Snow (Pf/Pg)	13.9/20.0	Lumber DOL	1.15	BC	0.57	Vert(CT)	-0.09	5-6	>999	180	
TCDL	10.0	Rep Stress Incr	NO	WB	0.51	Horz(CT)	0.01	8	n/a	n/a	
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH							
BCDL	10.0										
										Weight: 66 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
WEBS	2x4 SP No.3 *Except* 7-2:2x6 SP No.2
OTHERS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 2-4-4 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS	(size) 7=0-4-4, 8=0-1-8
	Max Horiz 7=79 (LC 7)
	Max Uplift 7=78 (LC 7), 8=27 (LC 11)
	Max Grav 7=695 (LC 29), 8=633 (LC 18)

FORCES	(lb) - Maximum Compression/Maximum Tension
--------	--

TOP CHORD	1-2=0/48, 2-3=-937/0, 3-4=-177/13, 4-5=0/391, 2-7=-652/104
-----------	--

BOT CHORD	6-7=-245/48, 5-6=-41/881
WEBS	2-6=-60/981, 3-6=0/130, 3-5=-831/38, 4-8=-636/27

NOTES

- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope); cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.33
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 13.9 psf on overhangs non-concurrent with other live loads.

- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Bearings are assumed to be: Joint 7 SP No.2, Joint 8 SP No.3.
- Bearing at joint(s) 8 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Provide mechanical connection (by others) of truss to bearing plate at joint(s) 8.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 78 lb uplift at joint 7 and 27 lb uplift at joint 8.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 13 lb down and 11 lb up at 3-1-6, 13 lb down and 11 lb up at 3-1-6, 66 lb down and 35 lb up at 5-11-5, 66 lb down and 35 lb up at 5-11-5, and 142 lb down and 43 lb up at 8-9-4, and 142 lb down and 43 lb up at 8-9-4 on top chord, and 14 lb down and 20 lb up at 3-1-6, 14 lb down and 20 lb up at 3-1-6, 21 lb down and 9 lb up at 5-11-5, 21 lb down and 9 lb up at 5-11-5, and 41 lb down at 8-9-4, and 41 lb down at 8-9-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-2=-46, 2-4=-46, 5-7=-19
Concentrated Loads (lb)
Vert: 11=-78 (F=-39, B=-39), 12=-231 (F=-116, B=-115), 13=7 (F=3, B=3), 14=-11 (F=-6, B=-6), 15=-82 (F=-41, B=-41)



June 6, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009702
25040114-01	M2	Monopitch	8	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:13
ID:JmpSuosNzbDwA4CbAa4O0hzPcU5-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:36.4

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.38	Vert(LL)	-0.01	6	>999	240	MT20	244/190
Snow (Pf/Pg)	13.9/20.0	Lumber DOL	1.15	BC	0.21	Vert(CT)	-0.03	5-6	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.36	Horz(CT)	0.01	5	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 61 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
WEBS	2x4 SP No.3 *Except* 7-2:2x6 SP No.2

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS	(size) 5= Mechanical, 7=0-3-0
	Max Horiz 7=135 (LC 12)
	Max Uplift 5=-16 (LC 15), 7=-59 (LC 11)
	Max Grav 5=437 (LC 22), 7=551 (LC 2)

FORCES	(lb) - Maximum Compression/Maximum Tension
--------	--

TOP CHORD	1-2=0/50, 2-3=-602/139, 3-4=-109/74, 4-5=-160/112, 2-7=-536/267
BOT CHORD	6-7=-280/294, 5-6=-260/586
WEBS	3-6=0/96, 3-5=-584/224, 2-6=-119/474

NOTES

- Wind: ASCE 7-16; Vult=130mph (3-second gust)
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Exterior(2E) -1-10-3 to 1-1-13, Interior (1) 1-1-13 to 10-6-12 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 13.9 psf on overhangs non-concurrent with other live loads.

- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Bearings are assumed to be: Joint 7 SP No.2 .
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 59 lb uplift at joint 7 and 16 lb uplift at joint 5.

LOAD CASE(S) Standard



June 6, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009703
25040114-01	PB9	Piggyback	1	2	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:15
ID:sgUBXIX0Q7oYrY_w3bl5BHzOZTT-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrcDoi7J4zJC?f

Page: 1



Scale = 1:67.1

Plate Offsets (X, Y): [2:0-2-10,0-1-0]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.39	Vert(LL)	n/a	-	999	MT20	244/190
Snow (Pf/Pg)	13.9/20.0	Lumber DOL	1.15	BC	0.29	Vert(CT)	n/a	-	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.08	Horz(CT)	-0.01	9	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH							
BCDL	10.0										
										Weight: 122 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
WEBS	2x4 SP No.2
OTHERS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	1 Row at midpt 5-9

REACTIONS

(size)	2=9-0-6, 6=9-0-6, 7=9-0-6, 8=9-0-6, 9=9-0-6
Max Horiz	2=312 (LC 12)
Max Uplift	2=-219 (LC 11), 6=-114 (LC 12), 7=-180 (LC 13), 8=-131 (LC 13)
Max Grav	2=314 (LC 10), 6=222 (LC 29), 7=501 (LC 29), 8=358 (LC 29)

FORCES

(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=0/18, 2-3=-867/792, 3-4=-627/607, 4-5=-273/300, 6-9=0/0, 5-6=-281/228
BOT CHORD	2-8=-229/254, 7-8=-182/234, 6-7=-182/234
WEBS	4-7=-510/418, 3-8=-412/370

NOTES

- 2-ply truss to be connected together as follows:
Top chords connected with 10d (0.131"x3") nails as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected with 10d (0.131"x3") nails as follows: 2x4 - 1 row at 0-9-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.

- Wind: ASCE 7-16; Vult=130mph (3-second gust)
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Corner (3E) 0-2-7 to 3-2-7, Exterior(2N) 3-2-7 to 9-4-13 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 13.9 psf on overhangs non-concurrent with other live loads.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- All bearings are assumed to be SP No.2.
- Bearing at joint(s) 9, 6 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 219 lb uplift at joint 2, 114 lb uplift at joint 6, 180 lb uplift at joint 7, 131 lb uplift at joint 8 and 219 lb uplift at joint 2.
- See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

LOAD CASE(S) Standard




June 6,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932

Page: 1


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009705
25040114-01	PB16	Piggyback	8	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:16
ID:oxAWL48lhMvFzAkA3SueKzPcR9-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWRCDoi7J4zJC?i

Page: 1



Scale = 1:37

Plate Offsets (X, Y): [2:0-5-0,0-0-6], [4:0-5-0,0-0-6]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.26	Vert(LL)	n/a	-	n/a	999	MT20
Snow (Pf/Pg)	13.9/20.0	Lumber DOL	1.15	BC	0.26	Vert(CT)	n/a	-	n/a	999	244/190
TCDL	10.0	Rep Stress Incr	YES	WB	0.03	Horz(CT)	0.00	2	n/a	n/a	
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP							
BCDL	10.0										
Weight: 38 lb FT = 20%											

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(size) 2=7-9-0, 4=7-9-0, 6=7-9-0
Max Horiz 2=-96 (LC 11)
Max Uplift 2=-21 (LC 14), 4=-17 (LC 14)
Max Grav 2=238 (LC 2), 4=238 (LC 2), 6=181 (LC 2)

FORCES

(lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/18, 2-3=-254/109, 3-4=-254/109, 4-5=0/18

BOT CHORD 2-6=-67/140, 4-6=-68/143


WEBS 3-6=-75/69

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Exterior(2E) 0-2-7 to 3-2-7, Interior (1) 3-2-7 to 4-4-11, Exterior(2R) 4-4-11 to 7-4-11, Interior (1) 7-4-11 to 8-7-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.

- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 13.9 psf on overhangs non-concurrent with other live loads.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- All bearings are assumed to be SP No.2.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 21 lb uplift at joint 2, 17 lb uplift at joint 4, 21 lb uplift at joint 2 and 17 lb uplift at joint 4.
- See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

LOAD CASE(S) Standard



June 6,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009706
25040114-01	PB17	Piggyback	1	2	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:16
ID:5H69pTDh1WnF32c45147QpzPcR2-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrcD0i7J4zJC?f

Page: 1



Scale = 1:37

Plate Offsets (X, Y): [2:0-2-10,0-1-0], [4:0-2-10,0-1-0]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.13	Vert(LL)	n/a	-	n/a	999	MT20
Snow (Pf/Pg)	13.9/20.0	Lumber DOL	1.15	BC	0.13	Vert(CT)	n/a	-	n/a	999	244/190
TCDL	10.0	Rep Stress Incr	YES	WB	0.01	Horz(CT)	0.00	2	n/a	n/a	
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP							
BCDL	10.0										
										Weight: 76 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(size) 2=7-9-0, 4=7-9-0, 6=7-9-0
Max Horiz 2=-96 (LC 11)
Max Uplift 2=-22 (LC 14), 4=-18 (LC 14)
Max Grav 2=239 (LC 2), 4=239 (LC 2), 6=181 (LC 2)

FORCES

(lb) - Maximum Compression/Maximum Tension


TOP CHORD 1-2=0/18, 2-3=-254/110, 3-4=-254/110, 4-5=0/18
BOT CHORD 2-6=-77/163, 4-6=-78/167
WEBS 3-6=-76/70

NOTES

- 2-ply truss to be connected together as follows:
Top chords connected with 10d (0.131"x3") nails as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected with 10d (0.131"x3") nails as follows: 2x4 - 1 row at 0-9-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Unbalanced roof live loads have been considered for this design.

- Wind: ASCE 7-16; Vult=130mph (3-second gust)
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Exterior(2E) 0-2-7 to 3-2-7, Interior (1) 3-2-7 to 4-4-11, Exterior(2R) 4-4-11 to 7-4-11, Interior (1) 7-4-11 to 8-7-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 13.9 psf on overhangs non-concurrent with other live loads.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- All bearings are assumed to be SP No.2.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 22 lb uplift at joint 2, 18 lb uplift at joint 4, 22 lb uplift at joint 2 and 18 lb uplift at joint 4.
- See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

LOAD CASE(S) Standard



June 6, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009707
25040114-01	PB3	Piggyback	1	2	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:14
ID:LR_IeUlrS2vTsCpX1?KGdzPdA8-RfC?PsB70Hq3NSgPqnL8w3uITxbGKWrcDoi7J4zJC?f

Page: 1



Scale = 1:49.5

Plate Offsets (X, Y): [4:0-2-10,0-1-0]

Loading	(psf)	Spacing	1-11-4	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.15	Vert(LL)	n/a	-	n/a	999	MT20
Snow (Pf/Pg)	13.9/20.0	Lumber DOL	1.15	BC	0.03	Vert(CT)	n/a	-	n/a	999	244/190
TCDL	10.0	Rep Stress Incr	YES	WB	0.06	Horz(CT)	0.00	4	n/a	n/a	
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP							
BCDL	10.0										
Weight: 94 lb FT = 20%											

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
WEBS	2x4 SP No.3
OTHERS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6'-0-0 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 10'-0-0 oc bracing.

REACTIONS	(size)	4=8-0-8, 6=8-0-8, 7=8-0-8, 8=8-0-8, 9=8-0-8
	Max Horiz	9=154 (LC 11)
	Max Uplift	4=172 (LC 12), 6=166 (LC 14), 7=64 (LC 9), 8=68 (LC 10)
	Max Grav	4=192 (LC 9), 6=372 (LC 30), 7=307 (LC 30), 8=151 (LC 29)

FORCES

	(lb) - Maximum Compression/Maximum Tension
TOP CHORD	8-9=0/0, 1-8=187/197, 1-2=171/216, 2-3=200/197, 3-4=348/352, 4-5=0/18
BOT CHORD	7-8=155/191, 6-7=155/191, 4-6=155/191
WEBS	2-7=257/126, 3-6=496/416

NOTES

- 2-ply truss to be connected together as follows:
Top chords connected with 10d (0.131"x3") nails as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected with 10d (0.131"x3") nails as follows: 2x4 - 1 row at 0-9-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Unbalanced roof live loads have been considered for this design.

- Wind: ASCE 7-16; Vult=130mph (3-second gust)
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Corner (3E) 0-1-12 to 2-10-0, Corner(3R) 2-10-0 to 5-10-0, Exterior(2N) 5-10-0 to 8-4-5 zone; cantilever left and right exposed; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 13.9 psf on overhangs non-concurrent with other live loads.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4'-0-0 oc.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3'-06-00 tall by 2'-00-00 wide will fit between the bottom chord and any other members.
- All bearings are assumed to be SP No.2 .
- Bearing at joint(s) 9, 8 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 68 lb uplift at joint 8, 172 lb uplift at joint 4, 64 lb uplift at joint 7, 166 lb uplift at joint 6 and 172 lb uplift at joint 4.
- See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

LOAD CASE(S) Standard



June 6,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009708
25040114-01	M1	Monopitch	18	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:13
ID:joSjNCUwG4JKyJKerZ17G9zPcUa-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWRCDoi7J4zJC?f

Page: 1



Scale = 1:38.9

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.38	Vert(LL)	-0.01	6	>999	240	MT20	244/190
Snow (Pf/Pg)	13.9/20.0	Lumber DOL	1.15	BC	0.14	Vert(CT)	-0.01	5-6	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.15	Horz(CT)	0.00	8	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	10.0											
											Weight: 51 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
WEBS	2x4 SP No.3 *Except* 7-2:2x6 SP No.2
OTHERS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS	(size) 7=0-3-0, 8=0-1-8
	Max Horiz 7=90 (LC 11)
	Max Uplift 7=48 (LC 11), 8=21 (LC 15)
	Max Grav 7=451 (LC 2), 8=315 (LC 22)


FORCES	(lb) - Maximum Compression/Maximum Tension
TOP CHORD	1-2=0/50, 2-3=-406/96, 3-4=-72/5, 4-5=-85/220
BOT CHORD	6-7=-205/66, 5-6=-197/369
WEBS	3-5=-395/211, 3-6=0/68, 2-7=-440/261, 2-6=-2/360, 4-8=-316/169

NOTES

- Wind: ASCE 7-16; Vult=130mph (3-second gust)
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Exterior(2E) -1-10-3 to 1-1-13, Interior (1) 1-1-13 to 7-9-0 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.

- This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 13.9 psf on overhangs non-concurrent with other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Bearings are assumed to be: Joint 7 SP No.2 , Joint 8 SP No.3 .
- Bearing at joint(s) 8 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Provide mechanical connection (by others) of truss to bearing plate at joint(s) 8.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 48 lb uplift at joint 7 and 21 lb uplift at joint 8.

LOAD CASE(S) Standard



June 6,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009709
25040114-01	M4	Monopitch	2	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:13
ID:B3S2Vi821X5yn8e5C1Zb0zPfz5-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrcDoi7J4zJC?f

Page: 1



Scale = 1:39.2

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.22	Vert(LL)	-0.01	5	>999	240	MT20	244/190
Snow (Pf/Pg)	13.9/20.0	Lumber DOL	1.15	BC	0.15	Vert(CT)	-0.01	4-5	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.17	Horz(CT)	0.00	7	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	10.0											
											Weight: 48 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
WEBS	2x4 SP No.3 *Except* 6-1:2x6 SP No.2
OTHERS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(size)	6=0-3-0, 7=0-1-8
Max Horiz	6=64 (LC 11)
Max Uplift	7=22 (LC 11)
Max Grav	6=315 (LC 22), 7=328 (LC 22)

FORCES


(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=-429/119, 2-3=-75/1, 3-4=-103/236
BOT CHORD	5-6=-155/55, 4-5=-230/399
WEBS	2-4=-429/247, 2-5=0/74, 1-6=-293/122, 1-5=-76/399, 3-7=-329/180

NOTES

- Wind: ASCE 7-16; Vult=130mph (3-second gust)
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Exterior(2E) 0-2-12 to 3-2-12, Interior (1) 3-2-12 to 7-9-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.

- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Bearings are assumed to be: Joint 6 SP No.2, Joint 7 SP No.3.
- Bearing at joint(s) 7 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Provide mechanical connection (by others) of truss to bearing plate at joint(s) 7.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 22 lb uplift at joint 7.

LOAD CASE(S) Standard



June 6, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009710
25040114-01	M3	Monopitch	4	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:13
ID:B3S2Vi821X5yn8e5C1Zb0zPfz5-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrcDoi7J4zJC?f

Page: 1



Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.38	Vert(LL)	-0.01	6	>999	240	MT20	244/190
Snow (Pf/Pg)	13.9/20.0	Lumber DOL	1.15	BC	0.14	Vert(CT)	-0.01	5-6	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.15	Horz(CT)	0.00	8	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	10.0										Weight: 51 lb	FT = 20%

LUMBER	
TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
WEBS	2x4 SP No.3 *Except* 7-2:2x6 SP No.2
OTHERS	2x4 SP No.3
BRACING	
TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
REACTIONS	(size) 7=0-3-0, 8=0-1-8 Max Horiz 7=90 (LC 11) Max Uplift 7=48 (LC 11), 8=21 (LC 15) Max Grav 7=451 (LC 2), 8=315 (LC 22)
FORCES	(lb) - Maximum Compression/Maximum Tension
TOP CHORD	1-2=0/50, 2-3=-406/96, 3-4=-72/5, 4-5=-85/220
BOT CHORD	6-7=-205/66, 5-6=-197/369
WEBS	3-5=-395/211, 3-6=0/68, 2-7=-440/261, 2-6=-2/360, 4-8=-316/169

NOTES

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust)
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Exterior(2E) -1-10-3 to 1-1-13, Interior (1) 1-1-13 to 7-9-0 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
- 2) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- 3) Unbalanced snow loads have been considered for this design.

- 4) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 13.9 psf on overhangs non-concurrent with other live loads.
- 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- 6) Bearings are assumed to be: Joint 7 SP No.2 , Joint 8 SP No.3 .
- 7) Bearing at joint(s) 8 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 8) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 8.
- 9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 48 lb uplift at joint 7 and 21 lb uplift at joint 8.

LOAD CASE(S) Standard



June 6,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009711
25040114-01	VL7	Valley	2	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:17
ID:WXc9css?IJESoVETdVi3YgzPuSU-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:35.7

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.25	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf/Pg)	13.9/20.0	Lumber DOL	1.15	BC	0.24	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.19	Horiz(TL)	0.00	3	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	10.0											
											Weight: 35 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
OTHERS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 7-11-9 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS

(size)	1=8-0-0, 3=8-0-0, 4=8-0-0
Max Horiz	1=87 (LC 12)
Max Uplift	1=-13 (LC 35), 3=-13 (LC 34), 4=-65 (LC 13)
Max Grav	1=67 (LC 34), 3=67 (LC 35), 4=566 (LC 2)

FORCES


(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=-151/262, 2-3=-151/262
BOT CHORD	1-4=-215/191, 3-4=-215/191
WEBS	2-4=-553/254

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Corner (3E) 0-0-0 to 3-0-0, Exterior(2N) 3-0-0 to 4-0-0, Corner (3R) 4-0-0 to 7-0-0, Exterior(2N) 7-0-0 to 8-0-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.

- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- All bearings are assumed to be SP No.2.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 13 lb uplift at joint 1, 13 lb uplift at joint 3 and 65 lb uplift at joint 4.
- Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 1, 3.

LOAD CASE(S) Standard



June 6,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009712
25040114-01	VL5	Valley	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:17
ID:WXc9css?IJESoVETdVi3YgzPuSU-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:35.7

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.25	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf/Pg)	13.9/20.0	Lumber DOL	1.15	BC	0.24	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.19	Horiz(TL)	0.00	3	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	10.0										Weight: 35 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
OTHERS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 7-11-9 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS

(size)	1=8-0-0, 3=8-0-0, 4=8-0-0
Max Horiz	1=87 (LC 12)
Max Uplift	1=-13 (LC 35), 3=-13 (LC 34), 4=-65 (LC 13)
Max Grav	1=67 (LC 34), 3=67 (LC 35), 4=566 (LC 2)

FORCES

(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=-151/262, 2-3=-151/262
BOT CHORD	1-4=-215/191, 3-4=-215/191
WEBS	2-4=-553/254

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Corner (3E) 0-0-0 to 3-0-0, Exterior(2N) 3-0-0 to 4-0-0, Corner (3R) 4-0-0 to 7-0-0, Exterior(2N) 7-0-0 to 8-0-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.

- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- All bearings are assumed to be SP No.2.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 13 lb uplift at joint 1, 13 lb uplift at joint 3 and 65 lb uplift at joint 4.
- Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 1, 3.

LOAD CASE(S) Standard



June 6, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009713
25040114-01	N2	Monopitch	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:14
ID: Pb0WkMkGkE8xruIEl6v0q5zPenR-RfC?PsB70Hq3NSgPqnL8w3uITxBgKWrcDoi7J4zJC?f

Page: 1



Scale = 1:55.8

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.68	Vert(LL)	-0.07	3-4	>999	240	MT20	244/190
Snow (Pf/Pg)	13.9/20.0	Lumber DOL	1.15	BC	0.79	Vert(CT)	-0.20	3-4	>389	180		
TCDL	10.0	Rep Stress Incr	NO	WB	0.43	Horz(CT)	0.00	3	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	10.0											
											Weight: 55 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP 2400F 2.0E
BOT CHORD	2x4 SP No.2
WEBS	2x4 SP No.3 *Except* 2-3:2x4 SP 2400F 2.0E

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-11-0 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 7-6-6 oc bracing.
WEBS	1 Row at midpt 2-3

REACTIONS

(size)	3= Mechanical, 4= Mechanical
Max Horiz	4=291 (LC 12)
Max Uplift	3=-176 (LC 10), 4=-54 (LC 9)
Max Grav	3=459 (LC 28), 4=402 (LC 29)

FORCES

(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=-407/429, 2-3=-473/372, 1-4=-372/276
BOT CHORD	3-4=-545/549
WEBS	1-3=-454/466

NOTES

- Wind: ASCE 7-16; Vult=130mph (3-second gust)
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Exterior(2E) 0-1-12 to 3-1-12, Interior (1) 3-1-12 to 6-9-4 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss to truss connections.

- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 54 lb uplift at joint 4 and 176 lb uplift at joint 3.
- Load case(s) 1, 3 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.

LOAD CASE(S) Standard

- Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-2=-48, 4-5=-20, 3-5=-35
- Dead + 0.75 Roof Live (balanced) + 0.75 Attic Floor:
Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-2=-50, 4-5=-20, 3-5=-65



June 6, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009714
25040114-01	N1	Monopitch	6	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:13
ID:Pb0WkMkGkE8xruIEl6v0q5zPenR-RfC?PsB70Hq3NSgPqnL8w3uITxbGKWrcDoi7J4zJC?f

Page: 1



Scale = 1:55.8

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.59	n/a	-	n/a	999	MT20	244/190
Snow (Pf/Pg)	13.9/20.0	Lumber DOL	1.15	BC	0.40	Vert(CT)	-0.12	3-4	>688	180	
TCDL	10.0	Rep Stress Incr	YES	WB	0.43	Horz(CT)	0.00	3	n/a	n/a	
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP							
BCDL	10.0										
										Weight: 55 lb	FT = 20%


LUMBER
TOP CHORD 2x4 SP 2400F 2.0E
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3 *Except* 2-3:2x4 SP 2400F 2.0E

5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 60 lb uplift at joint 4 and 205 lb uplift at joint 3.

LOAD CASE(S) Standard

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-11-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 7-8-2 oc bracing.
WEBS 1 Row at midpt 2-3
REACTIONS (size) 3= Mechanical, 4= Mechanical
Max Horiz 4=291 (LC 12)
Max Uplift 3=-205 (LC 10), 4=-60 (LC 9)
Max Grav 3=372 (LC 28), 4=383 (LC 29)
FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-407/429, 2-3=-473/372, 1-4=-372/276
BOT CHORD 3-4=-545/549
WEBS 1-3=-454/466

NOTES
1) Wind: ASCE 7-16; Vult=130mph (3-second gust)
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Exterior(2E) 0-1-12 to 3-1-12, Interior (1) 3-1-12 to 6-9-4 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
3) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
4) Refer to girder(s) for truss to truss connections.



June 6,2025


WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932

Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:15 Page: 1
ID:5H69pTDh1WnF32c45147QpzPcR2-RfC?PsB70Hq3NSqPanL8w3uITXbGKwKRCdoi7J4zJC?fi



LUMBER	
TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
OTHERS	2x4 SP No.3
BRACING	
TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.
REACTIONS (size)	
	1=6-5-13, 2=6-5-13, 4=6-5-13, 5=6-5-13, 6=6-5-13
Max Horiz	1=70 (LC 9)
Max Uplift	1=204 (LC 29), 2=111 (LC 13), 6=5 (LC 14)
Max Grav	1=121 (LC 10), 2=327 (LC 29), 5=96 (LC 2), 6=276 (LC 2)
FORCES (lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=137/208, 2-3=153/159, 3-4=82/77, 4-5=75/12
BOT CHORD	2-6=93/106, 4-6=93/106
WEBS	3-6=203/69

- ## NOTES

- 1) 2-ply truss to be connected together as follows:
Top chords connected with 10d (0.131"x3") nails as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected with 10d (0.131"x3") nails as follows: 2x4 - 1 row at 0-9-0 oc.
- 2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- 3) Unbalanced roof live loads have been considered for this design.

- 4) Wind: ASCE 7-16; Vult=130mph (3-second gust)
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Corner (3E) zone; cantilever left and right exposed ; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
- 5) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 6) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- 7) Gable requires continuous bottom chord bearing.
- 8) Gable studs spaced at 4'-0" oc.
- 9) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3'-0" tall by 2'-0" wide will fit between the bottom chord and any other members.
- 10) All bearings are assumed to be SP No.2 .
- 11) Bearing at joint(s) 2, 4, 1, 5, 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 12) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 111 lb uplift at joint 2, 204 lb uplift at joint 1, 5 lb uplift at joint 6 and 111 lb uplift at joint 2.
- 13) See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

LOAD CASE(S) Standard



Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Components Association (www.sbcacomponents.com)




818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009716
25040114-01	PB11	Piggyback	7	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:15
ID:oxAWL48lhMvFjzakA3SueKzPcR9-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWRCDoi7J4zJC?i

Page: 1



Scale = 1:31.6

Plate Offsets (X, Y): [2:0-2-10,0-1-0], [4:0-2-10,0-1-0]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.12	Vert(LL)	n/a	-	n/a	999	MT20
Snow (Pf/Pg)	13.9/20.0	Lumber DOL	1.15	BC	0.13	Vert(CT)	n/a	-	n/a	999	244/190
TCDL	10.0	Rep Stress Incr	YES	WB	0.01	Horz(CT)	0.00	4	n/a	n/a	
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP							
BCDL	10.0										
										Weight: 27 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(size) 2=5-5-6, 4=5-5-6, 6=5-5-6
Max Horiz 2=-70 (LC 11)
Max Uplift 2=-10 (LC 14), 4=-8 (LC 14)
Max Grav 2=164 (LC 2), 4=164 (LC 2), 6=146 (LC 2)

FORCES

(lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/18, 2-3=-157/85, 3-4=-157/85, 4-5=0/18

BOT CHORD 2-6=-37/74, 4-6=-37/78


WEBS 3-6=-44/22

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Corner (3E) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.

- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 13.9 psf on overhangs non-concurrent with other live loads.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- All bearings are assumed to be SP No.2.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 10 lb uplift at joint 2, 8 lb uplift at joint 4, 10 lb uplift at joint 2 and 8 lb uplift at joint 4.
- See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

LOAD CASE(S) Standard



June 6, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932


Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009717
25040114-01	CJ3	Jack-Open	4	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:10

Page: 1

ID:jtuflM7QGDz5JdZRXUWK2ozPfz6-RfC?PsB70Hq3NSgPqnL8w3uITxbGKWrCDoi7J4zJC?f



Scale = 1:27.2

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.62	Vert(LL)	0.06	4-5	>999	240	MT20	244/190
Snow (Pf/Pg)	13.9/20.0	Lumber DOL	1.15	BC	0.33	Vert(CT)	-0.10	4-5	>706	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.05	3	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MR								
BCDL	10.0											
											Weight: 23 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
WEBS	2x6 SP No.2

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS	(size)	3= Mechanical, 4= Mechanical,
		5=0-3-0
	Max Horiz	5=67 (LC 11)
	Max Uplift	3=-40 (LC 15), 5=-51 (LC 11)
	Max Grav	3=181 (LC 22), 4=69 (LC 22),
		5=384 (LC 22)

FORCES	(lb) - Maximum Compression/Maximum Tension
--------	--


TOP CHORD	2-5=-357/243, 1-2=0/50, 2-3=-77/49
BOT CHORD	4-5=0/0

NOTES

- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Exterior(2E) -1-10-3 to 1-1-13, Interior (1) 1-1-13 to 6-0-15 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 13.9 psf on overhangs non-concurrent with other live loads.

- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Bearings are assumed to be: , Joint 5 SP No.2 .
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 51 lb uplift at joint 5 and 40 lb uplift at joint 3.

LOAD CASE(S) Standard



June 6,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932


Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009718
25040114-01	CJ2	Jack-Open	4	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:10

Page: 1

ID:jtufIM7QGDz5JdZRXUWK2ozPfz6-RfC?PsB70Hq3NSgPqnL8w3uITxbGKWrCDoi7J4zJC?f



Scale = 1:25.7

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.38	Vert(LL)	0.01	4-5	>999	240	MT20	244/190
Snow (Pf/Pg)	13.9/20.0	Lumber DOL	1.15	BC	0.18	Vert(CT)	-0.02	4-5	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.01	3	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MR								
BCDL	10.0										Weight: 17 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
WEBS	2x6 SP No.2

BRACING

TOP CHORD	Structural wood sheathing directly applied or 4-1-11 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS	(size)	3= Mechanical, 4= Mechanical,
		5=0-3-0
	Max Horiz	5=50 (LC 11)
	Max Uplift	3=-26 (LC 15), 5=-57 (LC 11)
	Max Grav	3=104 (LC 22), 4=34 (LC 20),
		5=364 (LC 22)

FORCES	(lb) - Maximum Compression/Maximum Tension
--------	--

TOP CHORD	2-5=-319/215, 1-2=0/50, 2-3=-54/31
BOT CHORD	4-5=0/0

NOTES

- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Exterior(2E) -1-10-3 to 1-1-13, Interior (1) 1-1-13 to 4-0-15 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 13.9 psf on overhangs non-concurrent with other live loads.

- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Bearings are assumed to be: , Joint 5 SP No.2 .
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 57 lb uplift at joint 5 and 26 lb uplift at joint 3.

LOAD CASE(S) Standard



June 6,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	
25040114-01	K1	Flat Girder	1	2	Job Reference (optional)	I74009719

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:12
ID:xf2Rz1cEZbaL2Co8usBBGUzOZmj-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:25

Loading	(psf)	Spacing	1-11-4	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.15	Vert(LL)	-0.02	3-4	>999	240	244/190
Snow (Pf/Pg)	18.9/20.0	Lumber DOL	1.15	BC	0.53	Vert(CT)	-0.03	3-4	>999	180	
TCDL	10.0	Rep Stress Incr	NO	WB	0.01	Horz(CT)	0.00	3	n/a	n/a	
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP							
BCDL	10.0										
										Weight: 57 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x6 SP No.2
WEBS 2x4 SP No.3

BRACING

TOP CHORD 2-0-0 oc purlins: 1-2, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 3= Mechanical, 4= Mechanical
Max Horiz 4=-70 (LC 7)
Max Grav 3=967 (LC 3), 4=861 (LC 3)

FORCES

(lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-4=-109/49, 1-2=-28/21, 2-3=-109/25
BOT CHORD 3-4=-62/55
WEBS 1-3=-43/43

NOTES

- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Wind: ASCE 7-16; Vult=130mph (3-second gust)
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope); cantilever left and right exposed; end vertical left and right exposed;
Lumber DOL=1.60 plate grip DOL=1.33
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=18.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10, Lu=50-0-0

- Unbalanced snow loads have been considered for this design.
- Provide adequate drainage to prevent water ponding.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss to truss connections.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 786 lb down at 1-1-12, and 788 lb down at 3-1-12 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard

- Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-2=-56, 3-4=-19
Concentrated Loads (lb)
Vert: 5=-626 (F), 6=-628 (F)



June 6, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009720
25040114-01	VL8	Valley	2	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:17
ID:WXc9css?IJESoVETdV3YgzPuSU-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:27.2

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.04	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf/Pg)	13.9/20.0	Lumber DOL	1.15	BC	0.06	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.03	Horiz(TL)	0.00	3	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	10.0										Weight: 16 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
OTHERS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 3-11-9 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS

(size)	1=4-0-0, 3=4-0-0, 4=4-0-0
Max Horiz	1=-41 (LC 9)
Max Uplift	4=-9 (LC 13)
Max Grav	1=57 (LC 34), 3=57 (LC 35), 4=219 (LC 2)

FORCES

(lb) - Maximum Compression/Maximum Tension


TOP CHORD	1-2=-47/58, 2-3=-47/53
BOT CHORD	1-4=-65/69, 3-4=-65/69
WEBS	2-4=-149/51

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Corner (3E) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Gable requires continuous bottom chord bearing.

- Gable studs spaced at 4-0-0 oc.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- All bearings are assumed to be SP No.2 .
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 9 lb uplift at joint 4.
- Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 1, 3.

LOAD CASE(S) Standard



June 6, 2025


WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932

Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:17 Page: 1
ID:Wxc9css?JUESoVETdV3YazPuSU-RfC?PsB70Hq3NSqPanL8w3uITxbGKWrCDoi7J4zJC?f



- 7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- 8) All bearings are assumed to be SP No.2 .
- 9) Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 1, 3.

LOAD CASE(S) Standard

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTeK® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinstr.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbccomponents.com).

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932


Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009722
25040114-01	PB14	Piggyback	2	2	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:16

Page: 1

ID: _Jt6DfUs5zQH4Hj6pxy2nEzPcQj-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f



Scale = 1:30.4

Plate Offsets (X, Y): [2:0-2-10,0-1-0], [3:Edge,0-2-7], [4:0-2-10,0-1-0]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.01	Vert(LL)	n/a	-	n/a	999	MT20
Snow (Pf/Pg)	13.9/20.0	Lumber DOL	1.15	BC	0.01	Vert(CT)	n/a	-	n/a	999	244/190
TCDL	10.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.00	2	n/a	n/a	
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP							
BCDL	10.0										
										Weight: 22 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 3-4-2 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 2=2-3-11, 4=2-3-11
Max Horiz 2=-34 (LC 11)
Max Grav 2=111 (LC 2), 4=111 (LC 2)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/18, 2-3=-66/25, 3-4=-66/25, 4-5=0/18
BOT CHORD 2-4=-14/38

NOTES

- 2-ply truss to be connected together as follows:
Top chords connected with 10d (0.131"x3") nails as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected with 10d (0.131"x3") nails as follows: 2x4 - 1 row at 0-9-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust)
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Corner (3E) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33

- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 13.9 psf on overhangs non-concurrent with other live loads.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- All bearings are assumed to be SP No.2 .
- See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

LOAD CASE(S) Standard



June 6,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932


Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009723
25040114-01	PB13	Piggyback	4	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:16

Page: 1

ID:DnO4XwNr_VQP726aLFpASyZpCqR-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f



Scale = 1:30.2

Plate Offsets (X, Y): [3:Edge,0-2-7]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.06	Vert(LL)	n/a	-	n/a	999	MT20
Snow (Pf/Pg)	13.9/20.0	Lumber DOL	1.15	BC	0.04	Vert(TL)	n/a	-	n/a	999	244/190
TCDL	10.0	Rep Stress Incr	YES	WB	0.00	Horiz(TL)	0.00	5	n/a	n/a	
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP							
BCDL	10.0										
										Weight: 11 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 3-4-2 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 1=3-4-2, 2=3-4-2, 4=3-4-2, 5=3-4-2
Max Horiz 1=-34 (LC 9)
Max Uplift 1=-78 (LC 29), 2=-11 (LC 13)
Max Grav 1=24 (LC 10), 2=215 (LC 29), 5=100 (LC 2)

FORCES (lb) - Maximum Compression/Maximum Tension


TOP CHORD 1-2=-40/95, 2-3=-75/27, 3-4=-76/22, 4-5=-87/24
BOT CHORD 2-4=-32/48

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Corner (3E) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Gable requires continuous bottom chord bearing.

- Gable studs spaced at 4-0-0 oc.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- All bearings are assumed to be SP No.2 .
- Bearing at joint(s) 2, 4, 1, 5, 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 11 lb uplift at joint 2, 78 lb uplift at joint 1 and 11 lb uplift at joint 2.
- See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

LOAD CASE(S) Standard



June 6,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009724
25040114-01	PB12	Piggyback	2	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:15
ID:wRTR3XISdMXPNz3ERHBXg4zPcQy-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrcDoi7J4zJC?i

Page: 1



Scale = 1:32.4

Plate Offsets (X, Y): [2:0-2-10,0-1-0], [4:0-2-10,0-1-0]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.02	Vert(LL)	n/a	-	n/a	999	244/190
Snow (Pf/Pg)	13.9/20.0	Lumber DOL	1.15	BC	0.02	Vert(CT)	n/a	-	n/a	999	
TCDL	10.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.00	4	n/a	n/a	
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP							
BCDL	10.0										
										Weight: 13 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 3-4-2 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 2=2-3-11, 4=2-3-11, 6=2-3-11
Max Horiz 2=-34 (LC 11)
Max Uplift 2=-1 (LC 14), 4=-1 (LC 14)
Max Grav 2=76 (LC 2), 4=76 (LC 2), 6=70 (LC 2)

FORCES (lb) - Maximum Compression/Maximum Tension


TOP CHORD 1-2=0/18, 2-3=-49/22, 3-4=-50/23, 4-5=0/18
BOT CHORD 2-6=-21/35, 4-6=-21/35
WEBS 3-6=-24/0

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Exterior(2E) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10

- This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 13.9 psf on overhangs non-concurrent with other live loads.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 2-0-0 oc.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- All bearings are assumed to be SP No.2 .
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 1 lb uplift at joint 2, 1 lb uplift at joint 4, 1 lb uplift at joint 2 and 1 lb uplift at joint 4.
- See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

LOAD CASE(S) Standard



June 6,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Overhills-Roof-CL-20-020	174009725
25040114-01	CJ1	Jack-Open	4	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Thu Jun 05 13:53:10
ID:jtuflIM7QGDz5JdZRXUWK2ozPfz6-RfC?PsB70Hq3NSgPqnL8w3uITxbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:24.3

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.38	Vert(LL)	0.00	4-5	>999	240	MT20	244/190
Snow (Pf/Pg)	13.9/20.0	Lumber DOL	1.15	BC	0.17	Vert(CT)	0.00	4-5	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	-0.01	3	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MR								
BCDL	10.0											
											Weight: 11 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
WEBS	2x6 SP No.2

BRACING

TOP CHORD	Structural wood sheathing directly applied or 2-1-11 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS	(size)	3= Mechanical, 4= Mechanical,
		5=0-3-0
	Max Horiz	5=34 (LC 12)
	Max Uplift	3=-31 (LC 21), 4=-21 (LC 21), 5=-72 (LC 11)
	Max Grav	3=14 (LC 22), 4=16 (LC 11), 5=305 (LC 22)

FORCES

(lb) - Maximum Compression/Maximum Tension

TOP CHORD	2-5=-256/197, 1-2=0/50, 2-3=-36/14
BOT CHORD	4-5=0/0

NOTES

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) and C-C Exterior(2E) -1-10-3 to 1-1-13, Interior (1) 1-1-13 to 2-0-15 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.33
- 2) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=13.9 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- 3) Unbalanced snow loads have been considered for this design.
- 4) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 13.9 psf on overhangs non-concurrent with other live loads.

- 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- 6) Bearings are assumed to be: , Joint 5 SP No.2 .
- 7) Refer to girder(s) for truss to truss connections.
- 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 72 lb uplift at joint 5, 31 lb uplift at joint 3 and 21 lb uplift at joint 4.

LOAD CASE(S) Standard



June 6,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.




Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932

Symbols

PLATE LOCATION AND ORIENTATION



* Plate location details available in MITek software or upon request.

PLATE SIZE

4 X 4


The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T or I bracing if indicated.


BEARING



Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number/letter where bearings occur. Min size shown is for crushing only.

Industry Standards:
ANSI/TP1: National Design Specification for Metal Plate Connected Wood Truss Construction.
DSB-22: Building Component Safety Information, Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses.

Numbering System



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

Product Code Approvals

ICC-ES Reports:
ESR-1988, ESR-2362, ESR-2685, ESR-3282
ESR-4722, ESL-1388

Design General Notes

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.
Lumber design values are in accordance with ANSI/TP1 section 6.3. These truss designs rely on lumber values established by others.

© 2023 MITek® All Rights Reserved

General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor I bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TP1 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TP1 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TP1 1 Quality Criteria.
21. The design does not take into account any dynamic or other loads other than those expressly stated.

MITek®

ENGINEERING BY
TRENCO
A MITek Affiliate

MITek Engineering Reference Sheet: MII-7473 rev. 1/2/2023