


THIS IS A TRUSS PLACEMENT DIAGRAM (TPD) ONLY, NOT AN ENGINEERED DOCUMENT. Trusses are designed as individual building components to be incorporated into the building design at the specification of the building designer. See individual truss design drawings (TDD's) for each truss design identified on the TPD. The Contractor is responsible for the temporary bracing of the roof and floor system, and the building designer is responsible for the permanent bracing of the roof and floor system and the overall structure. The design of the support structure including but not limited to headers, beams, walls, and columns is also the responsibility of the building designer. For general guidance regarding installation and bracing, consult "Building Component Safety Information" (BCSI) available from the SBC Association (www.sbcassociation.com). It is the responsibility of the General Contractor to verify that the provided component layout matches the final intended construction plans, loading conditions, and use. If they do not, it is the responsibility of the General Contractor to notify UFP and provide plans containing the latest specifications and designs. UFP will not be responsible for plan changes by others after final approval of shop drawings, or for errors or modifications made on-site during construction. DO NOT CUT, NOTCH, DRILL, OR OTHERWISE "REPAIR" MANUFACTURED TRUSSES IN ANY WAY WITHOUT PRIOR WRITTEN AUTHORIZATION BY A LICENSED PROFESSIONAL DESIGNATED BY UFP. The Framing is responsible to verify all dimensions, including adjusting member spacing within tolerances to allow for the drop and rise of plumbing/HVAC, unless noted otherwise. Truss-to-wall connections, if shown, are for uplift only and do not consider lateral loads. All connectors on this project are to be installed per the connector manufacturer's specifications. All connectors shown that are not truss-to-truss are suggestions only and are to be verified by the Building Designer or Engineer of Record for suitability to this particular project. UFP accepts no responsibility for the specific application or suitability of any connector that is not truss-to-truss as they apply to this specific structure.

PLACEMENT PLAN

14	FACE MOUNT HANGER	HUS26	A
5	FACE MOUNT HANGER	LUS26	B



△ INDICATES LEFT END OF TRUSS SCALE: N.T.S

REVISIONS		DSN
DATE	DESCRIPTION	
-	-	-
-	-	-
-	-	-
-	-	-
-	-	-
-	-	-
-	-	-
-	-	-
-	-	-

DESIGNER	DBM
LAYOUT DATE	1/6/24
ARCH DATE	-
STRUC DATE	-

JOB #: 23061397

HANOVER PLAN W/CAFE

PBS RALEIGH-NEW HOME

TRADITIONAL OR LOW COUNTRY

-

This drawing is property of UFP Site Built, LLC. Any unauthorized use of this document without written permission is prohibited. UFP relinquishes ownership of delivered product upon delivery. Owner of product must obtain UFP's authorization prior to any alteration or modification of product. UFP will not be held responsible for any unauthorized modifications done or costs incurred without prior written authorization from UFP.

TRUSS TRAX

UFP CONSTRUCTION

TrustTraxUFP.com

UFP SITE BUILT

A UFP INDUSTRIES COMPANY

Burlington, NC

Chesapeake, VA

Clinton, NC

Conway, SC

Jefferson, GA

Locust, NC

Liberty, NC

Ooltewah, TN

Pearisburg, VA

Stanfield, NC

Customer Service (800) 476-9356

Job	Truss	Truss Type	Qty	Ply	PBS\HANOVER TRADITIONAL W/CAFE
72500235	A	Truss	5	1	Job Reference (optional)

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Micah Clayton

Run: 8.81 S Sep 13 2024 Print: 8.810 S Sep 13 2024 MiTek Industries, Inc. Mon Jan 06 14:54:40

Page: 1

ID:wIPFXjKqcg6XXvXIPvPLdKz3TNI-LRa7VX5dDpsGoTAr8ngkiHCOUAnswVJukjYx8Ozy3?z




Plate Offsets (X, Y): [2:0-2-4,0-3-0], [7:0-3-0,0-3-0], [20:0-6-8,0-1-4]												
Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.85	Vert(LL)	-0.30	18-19	>829	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.99	Vert(CT)	-0.65	18-19	>382	180	MT18HS	244/190
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.95	Horz(CT)	0.28	9	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MR							Weight: 258 lb	FT = 20%

LUMBER		BRACING	
TOP CHORD	2x4 SP No.2 *Except* T4:2x4 SP SS	TOP CHORD	Structural wood sheathing directly applied, except end verticals.
BOT CHORD	2x4 SP No.2 *Except* B1,B5:2x4 SP No.1	BOT CHORD	Rigid ceiling directly applied or 2-2-0 oc bracing.
WEBS	2x4 SP No.3 *Except* W1:2x4 SP No.2	WEBS	1 Row at midpt 4-18, 2-20, 3-18
SLIDER	Right 2x6 SP No.2 -- 1-11-0		
REACTIONS			
(lb/size)	9=1550/0-3-8, (min. 0-1-13), 14=460/0-3-8, (min. 0-1-8), 20=1493/ Mechanical, (min. 0-1-8)		
Max Horiz	20=-192 (LC 15)		
Max Uplift	9=-244 (LC 11), 20=-208 (LC 10)		
Max Grav	9=1550 (LC 1), 14=742 (LC 16), 20=1493 (LC 1)		
FORCES			
(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.			
TOP CHORD	1-2=-744/271, 2-3=-3754/997, 3-4=-1845/640, 4-5=-1813/742, 5-6=-1948/738, 6-7=-2237/720, 7-8=-2377/670, 8-9=-250/245, 1-20=-509/219		
BOT CHORD	19-20=-768/3342, 18-19=-488/2423, 18-25=-95/1246, 14-25=-95/1246, 14-26=-95/1246, 13-26=-95/1246, 13-27=-363/1847, 12-27=-363/1847, 12-28=-363/1847, 11-28=-363/1847, 9-11=-455/2019		
WEBS	4-18=-284/180, 6-11=-79/299, 2-20=-3150/739, 3-19=-347/1755, 3-18=-1178/377, 17-18=-280/796, 5-17=-234/755, 5-15=-220/720, 13-15=-268/713, 6-13=-601/343, 14-16=-378/0		

- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCCL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - All plates are MT20 plates unless otherwise indicated.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 244 lb uplift at joint 9 and 208 lb uplift at joint 20.
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Micah Clayton Run: 8.81 S Sep 13 2024 Print: 8.810 S Sep 13 2024 MiTek Industries, Inc. Mon Jan 06 14:54:40 Page: 1



LUMBER		BRACING	
TOP CHORD	2x4 SP No.2 *Except* T4,T3:2x4 SP SS	TOP CHORD	Structural wood sheathing directly applied or 2-2-0 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.1 *Except* B3,B2:2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 2-2-0 oc bracing.
WEBS	2x4 SP No.3 *Except* W1:2x4 SP No.2	WEBS	1 Row at midpt 5-19, 4-19
SLIDER	Right 2x6 SP No.2 -- 1-11-0		

FORCES	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	2-3=-693/284, 3-4=-3880/1053, 4-5=-1881/659, 5-6=-1872/778, 6-7=-1977/756, 7-8=-2249/728, 8-9=-2392/680, 9-10=-255/260, 2-21=-561/297
BOT CHORD	20-21=-828/3485, 19-20=-515/2481, 19-26=-91/1242, 15-26=-91/1242, 15-27=-91/1242, 14-27=-91/1242, 14-28=-379/1872, 13-28=-379/1872, 13-29=-379/1872, 12-29=-379/1872, 10-12=-463/2029
WEBS	5-19=-304/204, 7-12=-71/291, 3-21=-3342/784, 4-20=-386/1850, 4-19=-1213/387, 18-19=-324/841, 6-18=-275/796, 6-16=-239/738, 14-16=-290/739, 7-14=-624/360, 15-17=-379/0

NOTES

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; cantilever left and right exposed ; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) All plates are MT20 plates unless otherwise indicated.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 6) Bearing at joint(s) 21 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 247 lb uplift at joint 10 and 240 lb uplift at joint 21.
- 8) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SRCA and Truss Plate Institute.



Job	Truss	Truss Type	Qty	Ply	PBS\HANOVER TRADITIONAL W/CAFE
72500235	A2	Truss	4	1	Job Reference (optional)




Plate Offsets (X, Y): [2:0-3-0,Edge], [8:0-3-0,0-3-0], [16:0-6-8,0-1-4]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.84	Vert(LL)	-0.58	13-14	>828	240	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.78	Vert(CT)	-1.07	13-14	>454	180	
BCLL	0.0*	Rep Stress Incr	YES	WB	0.98	Horz(CT)	0.27	10	n/a	n/a	
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH							
										Weight: 250 lb	FT = 20%

LUMBER		BRACING		
TOP CHORD	2x4 SP No.2 *Except* T3:2x4 SP SS	TOP CHORD	Structural wood sheathing directly applied, except end verticals.	
BOT CHORD	2x4 SP No.1 *Except* B3:2x4 SP No.2, B2:2x4 SP SS	BOT CHORD	Rigid ceiling directly applied or 6-5-15 oc bracing.	
WEBS	2x4 SP No.3 *Except* W1:2x4 SP No.2	WEBS	1 Row at midpt 5-14, 4-14, 8-10	
REACTIONS	(lb/size)	10=1612/ Mechanical, (min. 0-1-8), 16=1683/0-3-8, (min. 0-1-8)	WEBS	2 Rows at 1/3 pts 3-16
	Max Horiz	16=174 (LC 7)		
	Max Uplift	10=-216 (LC 11), 16=-245 (LC 10)		
FORCES				
	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.			
TOP CHORD	9-10=-317/169, 2-3=-728/289, 3-4=-4214/1112, 4-5=-2117/687, 5-6=-2109/807, 6-7=-2249/773, 7-8=-2428/750, 8-9=-374/179, 2-16=-579/300			
BOT CHORD	15-16=-898/3766, 14-15=-570/2724, 14-17=-171/1492, 17-18=-171/1492, 13-18=-171/1492, 13-19=-408/2064, 12-19=-408/2064, 12-20=-408/2064, 11-20=-408/2064, 10-11=-492/2130			
WEBS	5-14=-306/205, 3-16=-3633/837, 4-15=-418/1949, 4-14=-1264/402, 6-14=-299/902, 6-13=-237/909, 7-13=-540/348, 8-10=-2229/527			

- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCCL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; cantilever left and right exposed ; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - Bearing at joint(s) 16 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 216 lb uplift at joint 10 and 245 lb uplift at joint 16.
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

Job	Truss	Truss Type	Qty	Ply	PBS\HANOVER TRADITIONAL W/CAFE
72500235	A3	Truss	5	1	Job Reference (optional)

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Micah Clayton

Run: 8.810 S Sep 13 2024 Print: 8.810 S Sep 13 2024 MiTek Industries, Inc. Mon Jan 06 14:54:42

Page: 1

ID:fHvQ8KY3BFVwqeHDR3fVtCz3TJc-HpitwD7ulQ6_1mKEFCjCoilk6zVZOOHBC111DGzy3?x




Plate Offsets (X, Y): [7:0-3-0,0-3-0], [15:0-6-8,0-1-4]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.84	Vert(LL)	-0.58	12-13	>828	240	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.78	Vert(CT)	-1.07	12-13	>454	180	
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.98	Horz(CT)	0.27	9	n/a	n/a	
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH							
										Weight: 248 lb	FT = 20%

LUMBER		BRACING	
TOP CHORD	2x4 SP No.2 *Except* T3:2x4 SP SS	TOP CHORD	Structural wood sheathing directly applied, except end verticals.
BOT CHORD	2x4 SP No.1 *Except* B3:2x4 SP No.2, B2:2x4 SP SS	BOT CHORD	Rigid ceiling directly applied or 6-5-3 oc bracing.
WEBS	2x4 SP No.3 *Except* W1,W2:2x4 SP No.2	WEBS	1 Row at midpt 4-13, 2-15, 3-13, 7-9

REACTIONS	(lb/size)	9=1613/ Mechanical, (min. 0-1-8), 15=1613/ Mechanical, (min. 0-1-8)
	Max Horiz	15=163 (LC 7)
	Max Uplift	9=-216 (LC 11), 15=-219 (LC 10)

FORCES	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	8-9=-317/169, 1-2=-563/209, 2-3=-4242/1125, 3-4=-2120/688, 4-5=-2113/809, 5-6=-2250/773, 6-7=-2430/751, 7-8=-374/179, 1-15=-413/184
BOT CHORD	14-15=-915/3801, 13-14=-572/2728, 13-16=-171/1493, 16-17=-171/1493, 12-17=-171/1493, 12-18=-409/2066, 11-18=-409/2066, 11-19=-409/2066, 10-19=-409/2066, 9-10=-493/2131
WEBS	4-13=-309/207, 2-15=-3832/934, 3-14=-432/1978, 3-13=-1265/403, 5-13=-301/906, 5-12=-237/909, 6-12=-540/348, 7-9=-2231/528

- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 216 lb uplift at joint 9 and 219 lb uplift at joint 15.
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/ TPI 1.

Job	Truss	Truss Type	Qty	Ply	PBS\HANOVER TRADITIONAL W/CAFE
72500235	A3G	Truss	1	1	Job Reference (optional)

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Micah Clayton

Run: 8.81 S Sep 13 2024 Print: 8.810 S Sep 13 2024 MiTek Industries, Inc. Mon Jan 06 14:54:42

Page: 1

ID:ukQPTbS24oU3tPghzNWdYWz3TJk-HpitwD7ulQ6_1mKEFCjCoilu3zgwOcbBC111DGzy3?x





Plate Offsets (X, Y): [13:0-3-0,Edge]												
Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.21	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.12	Vert(TL)	n/a	-	n/a	999		
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.13	Horiz(TL)	0.01	26	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MR							Weight: 289 lb	FT = 20%

LUMBER		BRACING	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing, Except:
WEBS	2x4 SP No.3		6-0-0 oc bracing: 45-46.
OTHERS	2x4 SP No.3	WEBS	1 Row at midpt 12-38, 14-37, 11-39, 10-41, 15-36, 16-35
REACTIONS			
	All bearings 40-7-8.		
(lb) - Max Horiz	50=163 (LC 7)		
Max Uplift	All uplift 100 (lb) or less at joint(s) 26, 28, 29, 30, 31, 32, 34, 35, 36, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 50 except 27=205 (LC 11), 49=187 (LC 10)		
Max Grav	All reactions 250 (lb) or less at joint(s) 26, 27, 28, 29, 30, 31, 32, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 49, 50		
FORCES			
	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.		
TOP CHORD	9-10=106/252, 10-11=123/300, 11-12=147/367, 12-13=128/317, 13-14=128/317, 14-15=147/367, 15-16=123/300, 16-17=106/252		

- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; cantilever left and right exposed ; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Truss designed for wind loads in the plane of the truss only.
 - All plates are 2x3 MT20 unless otherwise indicated.
 - Gable requires continuous bottom chord bearing.
 - Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - Gable studs spaced at 2-0-0 oc.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
 - Bearing at joint(s) 50 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 50, 26, 45, 40, 39, 41, 42, 43, 44, 46, 47, 48, 36, 35, 34, 32, 31, 30, 29, 28 except (jt=lb) 49=186, 27=204.
 - Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 45, 41, 42, 43, 44, 46, 47, 48, 49.
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Micah Clayton Run: 8.81 S Sep 13 2024 Print: 8.810 S Sep 13 2024 MiTek Industries, Inc. Mon Jan 06 14:54:42 Page: 1
ID:r7Y9uHTlcPln6jq34oY5dxz3TJi-HpitwD7uIQ6 1mKEFCjCollu5zg2OcbBC111DGzy37x



LUMBER		BRACING	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing, Except:
WEBS	2x4 SP No.3		6-0-0 oc bracing: 46-47.
OTHERS	2x4 SP No.3	WEBS	1 Row at midpt 12-39, 14-38, 11-40, 10-42, 15-37, 16-36
REACTIONS			
	All bearings 40-8-8.		
	(lb) - Max Horiz 51=-174 (LC 11)		
	Max Uplift All uplift 100 (lb) or less at joint(s) 27, 29, 30, 31, 32, 33, 35, 36, 37, 40, 41, 42, 43, 44, 45, 46, 47, 48, 49 except 28=-157 (LC 11), 50=-215 (LC 10), 51=-101 (LC 8)		
	Max Grav All reactions 250 (lb) or less at joint(s) 27, 28, 29, 30, 31, 32, 33, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 49, 50, 51		
FORCES			
	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.		
TOP CHORD	10-11=-115/297, 11-12=-139/364, 12-13=-122/315, 13-14=-122/315, 14-15=-139/364, 15-16=-115/297		

This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.



Job	Truss	Truss Type	Qty	Ply	PBS\HANOVER TRADITIONAL W/CAFE
72500235	B	Truss	1	1	Job Reference (optional)

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Micah Clayton

Run: 8.81 S Sep 13 2024 Print: 8.810 S Sep 13 2024 MiTek Industries, Inc. Mon Jan 06 14:54:43

Page: 1

ID:JJ6X5dUwNjteksPGeV3KA9z3TJh-I?GF8Z7WWkFrFwvQpwERKwq1VN_R7ziLQhmbIjzy3?w




Plate Offsets (X, Y): [2:0-1-0,0-1-12], [5:0-0-0,0-0-0], [6:0-1-0,0-1-12], [10:0-4-0,0-3-0]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.36	Vert(LL)	-0.02	8-9	>999	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.23	Vert(CT)	-0.03	8-9	>999	180		
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.46	Horz(CT)	0.01	8	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH							Weight: 150 lb	FT = 20%

LUMBER			BRACING		
TOP CHORD	2x4 SP No.2		TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.	
BOT CHORD	2x4 SP No.2		BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.	
WEBS	2x4 SP No.3				
REACTIONS					
	(lb/size)	8=675/0-3-8, (min. 0-1-8), 11=727/0-3-8, (min. 0-1-8), 12=312/0-3-8, (min. 0-1-8)			
	Max Horiz	12=332 (LC 9)			
	Max Uplift	8=-66 (LC 11), 11=-166 (LC 10), 12=-14 (LC 11)			
	Max Grav	8=675 (LC 1), 11=727 (LC 1), 12=314 (LC 21)			
FORCES					
	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.				
TOP CHORD		3-4=-408/231, 4-5=-408/231, 5-6=-592/140, 2-12=-271/68, 6-8=-629/167			
BOT CHORD		11-12=-308/361, 9-10=0/362			
WEBS		6-9=0/316, 3-11=-619/214, 3-10=-14/254, 4-10=-185/297, 5-10=-371/245			

- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 14 lb uplift at joint 12, 166 lb uplift at joint 11 and 66 lb uplift at joint 8.
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

Job	Truss	Truss Type	Qty	Ply	PBS\HANOVER TRADITIONAL W/CAFE
72500235	BG	Truss	1	1	Job Reference (optional)

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Micah Clayton

Run: 8.81 S Sep 13 2024 Print: 8.810 S Sep 13 2024 MiTek Industries, Inc. Mon Jan 06 14:54:43

Page: 1

ID:nVgwJzVY80?VL0_SCDbZiMz3TJg-I?GF8Z7WWkFrwvQpwERKwqyWNIv7vLLQhmbIjzy3?w




Plate Offsets (X, Y): [8:Edge,0-1-8], [11:0-2-0,0-1-8], [20:0-1-8,0-0-12]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.67	Vert(LL)	0.17	18-19	>361	240	
TCDL	10.0	Lumber DOL	1.15	BC	0.68	Vert(CT)	-0.15	18-19	>394	180	
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.74	Horz(CT)	0.01	13	n/a	n/a	
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH							
										Weight: 156 lb	FT = 20%

LUMBER		BRACING	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3 *Except* W5:2x6 SP No.2	JOINTS	1 Brace at Jt(s): 22, 23, 24
OTHERS	2x4 SP No.3		
REACTIONS			
	(lb/size)	13=743/0-3-8, (min. 0-1-8), 16=457/0-3-8, (min. 0-1-8), 20=513/0-3-8, (min. 0-1-8)	
	Max Horiz	20=334 (LC 9)	
	Max Uplift	13=-47 (LC 11), 16=-194 (LC 10)	
	Max Grav	13=743 (LC 1), 16=540 (LC 17), 20=513 (LC 1)	
FORCES			
	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.		
TOP CHORD		2-3=-377/0, 3-4=-297/32, 4-5=-278/0, 5-6=-296/122, 6-7=-252/172, 9-10=-368/256, 10-11=-662/115, 2-20=-439/0, 11-13=-669/157	
BOT CHORD		19-20=-196/320, 18-19=-196/320, 17-18=-196/320, 16-17=0/425, 16-25=0/425, 15-25=0/425, 14-15=0/425, 13-14=-219/364	
WEBS		17-21=-489/226, 21-22=-418/156, 22-23=-413/150, 23-24=-405/154, 10-24=-474/227, 10-14=0/279, 11-14=-212/399	

- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Truss designed for wind loads in the plane of the truss only.
 - All plates are 1.5x3 MT20 unless otherwise indicated.
 - Gable studs spaced at 2'-0" oc.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3'-0" tall by 2'-0" wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 47 lb uplift at joint 13 and 194 lb uplift at joint 16.
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

Job	Truss	Truss Type	Qty	Ply	PBS\HANOVER TRADITIONAL W/CAFE
72500235	BL	Truss	1	3	Job Reference (optional)

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Micah Clayton

Run: 8.81 S Sep 13 2024 Print: 8.810 S Sep 13 2024 MiTek Industries, Inc. Mon Jan 06 14:54:43

Page: 1

ID:rO4aS5gycduMeKdLatM4pXz3TJR-I?GF8Z7WWkFrFwvQpwERKwq2aNq07zGLQhmbIjzy3?w





Plate Offsets (X, Y): [1:0-2-0,0-1-8], [5:0-2-0,0-1-8], [8:0-4-0,0-4-8]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.29	Vert(LL)	-0.04	7-8	>999	240	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.83	Vert(CT)	-0.09	7-8	>999	180	
BCLL	0.0 *	Rep Stress Incr	NO	WB	0.48	Horz(CT)	0.01	6	n/a	n/a	
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH							
										Weight: 491 lb	FT = 20%

LUMBER			BRACING		
TOP CHORD	2x4 SP No.2		TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.	
BOT CHORD	2x6 SP No.2		BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 8-9.	
WEBS	2x4 SP No.3 *Except* W1:2x6 SP No.2				
REACTIONS	(lb/size)	6=5599/0-3-8, (min. 0-2-3), 9=9184/0-3-8, (req. 0-3-10), 10=1117/0-3-8, (min. 0-1-8) Max Horiz 10=300 (LC 5) Max Uplift 6=755 (LC 8), 9=1383 (LC 8), 10=121 (LC 4)			
FORCES	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.				
TOP CHORD	2-3=-2753/539, 3-4=-2749/522, 4-5=-5099/739, 5-6=-4403/617				
BOT CHORD	10-11=-360/705, 11-12=-360/705, 9-12=-360/705, 9-13=-235/254, 13-14=-235/254, 8-14=-235/254, 8-15=-438/3534, 15-16=-438/3534, 7-16=-438/3534, 7-17=-140/686, 17-18=-140/686, 6-18=-140/686				
WEBS	3-8=-619/3462, 4-8=-2704/594, 4-7=-469/3512, 2-8=-436/3084, 2-9=-4627/763, 1-9=-621/257, 5-7=-373/2939				

- NOTES**
- 3-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc, 2x6 - 2 rows staggered at 0-9-0 oc.
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-5-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
 - All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
 - Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
 - WARNING: Required bearing size at joint(s) 9 greater than input bearing size.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 121 lb uplift at joint 10, 1383 lb uplift at joint 9 and 755 lb uplift at joint 6.
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - Use Simpson Strong-Tie HUS26 (14-16d Girder, 4-16d Truss) or equivalent spaced at 2-0-0 oc max. starting at 1-11-4 from the left end to 17-11-4 to connect truss(es) to back face of bottom chord.
 - Fill all nail holes where hanger is in contact with lumber.
- LOAD CASE(S)** Standard
- Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-3=-60, 3-5=-60, 6-10=-20
Concentrated Loads (lb)
Vert: 8=-1593 (B), 11=-1592 (B), 12=-1592 (B), 13=-1592 (B), 14=-1592 (B), 15=-1593 (B), 16=-1593 (B), 17=-1593 (B), 18=-1593 (B)


UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Micah Clayton Run: 8.81 S Sep 13 2024 Print: 8.810 S Sep 13 2024 MiTek Industries, Inc. Mon Jan 06 14:54:44 Page: 1
ID:nVgwJzVY80?VL0_SCDbZiMz3TJg-I?GF8Z7WWWkFrwvQpwERKwq3MN04725LQhmblijzy3?w



LUMBER		BRACING	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals. Rigid ceiling directly applied or 10-0-0 oc bracing.
BOT CHORD	2x4 SP No.2		
WEBS	2x4 SP No.3	BOT CHORD	
OTHERS	2x4 SP No.3		
REACTIONS			
	All bearings 15-0-0.		
	(lb) - Max Horiz 21=267 (LC 9)		
	Max Uplift All uplift 100 (lb) or less at joint(s) 14 except 15=237 (LC 11), 16=-127 (LC 11), 19=-125 (LC 10), 20=-240 (LC 10), 21=-111 (LC 6)		
	Max Grav All reactions 250 (lb) or less at joint(s) 14, 16, 17, 18, 19 except 15=273 (LC 18), 20=280 (LC 17), 21=255 (LC 18)		
FORCES			
	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.		
TOP CHORD	2-21=-219/319, 5-6=-227/274, 8-9=-227/274, 12-14=-212/319		
WEBS	3-21=-342/279, 11-14=-321/257		

- This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.

Job	Truss	Truss Type	Qty	Ply	PBS\HANOVER TRADITIONAL W/CAFE
72500235	D	Truss	5	1	Job Reference (optional)



Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.57	Vert(LL)	-0.02	7-8	>999	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.21	Vert(CT)	-0.04	7-8	>999	180		
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.08	Horz(CT)	0.00	6	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MR							Weight: 46 lb	FT = 20%

LUMBER		BRACING	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 6'-0" oc purlins, except end verticals.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 10'-0" oc bracing.
WEBS	2x4 SP No.3		

REACTIONS	(lb/size)	6=477/0-3-8, (min. 0-1-8), 8=477/0-5-8, (min. 0-1-8)
	Max Horiz	8=-142 (LC 8)
	Max Uplift	6=-74 (LC 11), 8=-74 (LC 10)

FORCES	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	2-3=-397/117, 3-4=-397/117, 2-8=-415/183, 4-6=-415/183
BOT CHORD	7-8=0/270, 6-7=0/270

- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3'-0" tall by 2'-0" wide will fit between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 74 lb uplift at joint 8 and 74 lb uplift at joint 6.
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

Job	Truss	Truss Type	Qty	Ply	PBS/HANOVER TRADITIONAL W/CAFE
72500235	DG	Truss	1	1	Job Reference (optional)




Plate Offsets (X, Y):	[5:0-3-0,Edge]
-----------------------	----------------

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.13	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.06	Vert(CT)	n/a	-	n/a	999		
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.04	Horz(CT)	0.00	10	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MR							Weight: 57 lb	FT = 20%

LUMBER		BRACING	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3		
OTHERS	2x4 SP No.3		

REACTIONS	All bearings 10-6-0.
(lb) - Max Horiz	15=-142 (LC 8)
Max Uplift	All uplift 100 (lb) or less at joint(s) 10, 15 except 11=-122 (LC 11), 14=-123 (LC 10)
Max Grav	All reactions 250 (lb) or less at joint(s) 10, 11, 12, 13, 14, 15
FORCES	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Truss designed for wind loads in the plane of the truss only.
 - All plates are 1.5x3 MT20 unless otherwise indicated.
 - Gable requires continuous bottom chord bearing.
 - Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - Gable studs spaced at 2-0-0 oc.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 10, 15 except (jt=lb) 14=122, 11=121.
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.




Job	Truss	Truss Type	Qty	Ply	PBS\HANOVER TRADITIONAL W/CAFE
72500235	DL	Truss	1	2	Job Reference (optional)

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Micah Clayton

Run: 8.81 S Sep 13 2024 Print: 8.810 S Sep 13 2024 MiTek Industries, Inc. Mon Jan 06 14:54:44

Page: 1

ID:rO4aS5gycdUeKdLatM4pXz3TJR-ECqeLu88H2NIH4UcNdlgt7NCHnBrsL0UfLW8H9zy3?v




Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.35	Vert(LL)	-0.04	6-9	>999	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.80	Vert(CT)	-0.08	6-9	>999	180		
BCLL	0.0 *	Rep Stress Incr	NO	WB	0.77	Horz(CT)	0.01	5	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH							Weight: 117 lb	FT = 20%

LUMBER	BRACING
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 6'-0" oc purlins.
BOT CHORD 2x6 SP No.1	BOT CHORD Rigid ceiling directly applied or 10'-0" oc bracing.
WEBS 2x4 SP No.3	
SLIDER Left 2x6 SP No.2 -- 1'-11"-0, Right 2x6 SP No.2 -- 1'-11"-0	
REACTIONS (lb/size)	
1=3591/0-3-8, (min. 0-2-2), 5=4619/0-3-8, (min. 0-2-12)	
Max Horiz 1=90 (LC 23)	
Max Uplift 1=523 (LC 8), 5=674 (LC 9)	
FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.	
TOP CHORD 1-2=-2758/470, 2-3=-3599/576, 3-4=-3598/575, 4-5=-2432/400	
BOT CHORD 1-15=-418/2923, 15-16=-418/2923, 6-16=-418/2923, 6-17=-418/2923, 17-18=-418/2923, 5-18=-418/2923	
WEBS 3-6=-527/3724	

- NOTES**
- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9'-0 oc.
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-7'-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9'-0 oc.
 - All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
 - Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3'-0"-0 tall by 2'-0"-0 wide will fit between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 523 lb uplift at joint 1 and 674 lb uplift at joint 5.
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - Use Simpson Strong-Tie HUS26 (14-16d Girder, 4-16d Truss) or equivalent spaced at 2'-3'-0 oc max. starting at 1'-11'-4 from the left end to 9'-11'-4 to connect truss(es) to front face of bottom chord.
 - Fill all nail holes where hanger is in contact with lumber.

LOAD CASE(S)	Standard
1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15	
Uniform Loads (lb/ft)	
Vert: 1-3=-60, 3-5=-60, 7-11=-20	
Concentrated Loads (lb)	
Vert: 13=-1478 (F), 15=-1473 (F), 16=-1473 (F), 17=-1473 (F), 18=-1473 (F)	

Job	Truss	Truss Type	Qty	Ply	PBS\HANOVER TRADITIONAL W/CAFE
72500235	E	Truss	5	1	Job Reference (optional)



Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.52	Vert(LL)	-0.03	7-8	>999	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.25	Vert(CT)	-0.06	7-8	>999	180		
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.09	Horz(CT)	0.01	6	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MR							Weight: 54 lb	FT = 20%

LUMBER		BRACING	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x6 SP No.2 *Except* W2:2x4 SP No.3		

REACTIONS	(lb/size)	6=535/0-3-8, (min. 0-1-8), 8=535/0-3-8, (min. 0-1-8)
	Max Horiz	8=-157 (LC 8)
	Max Uplift	6=-82 (LC 11), 8=-82 (LC 10)

FORCES	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	2-3=-460/129, 3-4=-460/129, 2-8=-471/199, 4-6=-471/199
BOT CHORD	7-8=0/312, 6-7=0/312

- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 82 lb uplift at joint 8 and 82 lb uplift at joint 6.
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

Job	Truss	Truss Type	Qty	Ply	PBS/HANOVER TRADITIONAL W/CAFE
72500235	EG	Truss	1	1	Job Reference (optional)




Plate Offsets (X, Y): [6:0-3-0,Edge]


Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.13	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.06	Vert(CT)	n/a	-	n/a	999		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.04	Horz(CT)	0.00	12	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MR							Weight: 68 lb	FT = 20%

LUMBER		BRACING	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS	2x4 SP No.3		
OTHERS	2x4 SP No.3		

REACTIONS	All bearings 12-0-0.
(lb) - Max Horiz	19=-155 (LC 8)
Max Uplift	All uplift 100 (lb) or less at joint(s) 12, 14, 17, 19 except 13=-118 (LC 11), 18=-122 (LC 10)
Max Grav	All reactions 250 (lb) or less at joint(s) 12, 13, 14, 15, 16, 17, 18, 19
FORCES	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Truss designed for wind loads in the plane of the truss only.
 - All plates are 1.5x3 MT20 unless otherwise indicated.
 - Gable requires continuous bottom chord bearing.
 - Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - Gable studs spaced at 2-0-0 oc.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 19, 12, 17, 14 except (jt=lb) 18=122, 13=117.
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Micah Clayton Run: 8.81 S Sep 13 2024 Print: 8.810 S Sep 13 2024 MiTek Industries, Inc. Mon Jan 06 14:54:45 Page: 1
ID: VZlh8eUly0h2sWYlUt3Lyez3R0V-iOO0ZE9m2LVZuE3oxKGvPLwNYBVUbgzue?Fiqbzy3U



NOTES

- 1) 3-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-5-0 oc.
Web connected as follows: 2x4 - 2 rows staggered at 0-9-0 oc.
- 2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- 3) Unbalanced roof live loads have been considered for this design.
- 4) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDF=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 638 lb uplift at joint 1 and 628 lb uplift at joint 5.
- 8) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 9) Use Simpson Strong-Tie HUS26 (14-16d Girder, 4-16d Truss) or equivalent spaced at 2-0-0 oc max. starting at 1-11-4 from the left end to 9-11-4 to connect truss(es) to front face of bottom chord.
- 10) Fill all nail holes where hanger is in contact with lumber.

This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.



Job	Truss	Truss Type	Qty	Ply	PBS\HANOVER TRADITIONAL W/CAFE
72500235	V1	Truss	1	1	Job Reference (optional)

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Micah Clayton

Run: 8.81 S Sep 13 2024 Print: 8.810 S Sep 13 2024 MiTek Industries, Inc. Mon Jan 06 14:54:45

Page: 1

ID:FiEIWJVAvK7MzAZemw6oFaz3TJf-I000ZE9m2LVZuE3oxKGvPLwPOBhabyZeu?Figbzy3?u




Plate Offsets (X, Y): [10:0-3-0,0-3-0]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.20	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.19	Vert(TL)	n/a	-	n/a	999		
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.18	Horiz(TL)	0.01	7	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH							Weight: 97 lb	FT = 20%

LUMBER		BRACING	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
OTHERS	2x4 SP No.3	WEBS	1 Row at midpt 4-10
REACTIONS	All bearings 18-10-0.		
(lb) - Max Horiz	1=-239 (LC 6)		
Max Uplift	All uplift 100 (lb) or less at joint(s) 7 except 1=-126 (LC 8), 8=-127 (LC 11), 9=-258 (LC 11), 11=-257 (LC 10), 12=-138 (LC 10)		
Max Grav	All reactions 250 (lb) or less at joint(s) 1, 7 except 8=274 (LC 18), 9=462 (LC 18), 10=394 (LC 20), 11=461 (LC 17), 12=287 (LC 17)		
FORCES	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.		
TOP CHORD	1-2=-338/213, 6-7=-296/196		
WEBS	3-11=-362/303, 2-12=-287/236, 5-9=-362/303, 6-8=-287/232		

- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - All plates are 1.5x3 MT20 unless otherwise indicated.
 - Gable requires continuous bottom chord bearing.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 7 except (jt=lb) 1=125, 11=257, 12=138, 9=257, 8=126.
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.


Job	Truss	Truss Type	Qty	Ply	PBS\HANOVER TRADITIONAL W/CAFE
72500235	V2	Truss	1	1	Job Reference (optional)

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Micah Clayton

Run: 8.81 S Sep 13 2024 Print: 8.810 S Sep 13 2024 MiTek Industries, Inc. Mon Jan 06 14:54:45

Page: 1

ID:FiEIWJVAvK7MzAZemw6oFaz3TJf-iOO0ZE9m2LVZuE3oxKGvPLwORBhobvceu?Figbzy3?u



Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.26	Vert(LL)	n/a	-	n/a	999	MT20
TCDL	10.0	Lumber DOL	1.15	BC	0.17	Vert(TL)	n/a	-	n/a	999	244/190
BCLL	0.0*	Rep Stress Incr	YES	WB	0.37	Horiz(TL)	0.00	5	n/a	n/a	
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH							Weight: 82 lb
											FT = 20%

LUMBER	BRACING
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 10-0-0 oc purlins.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
OTHERS 2x4 SP No.3	

REACTIONS	All bearings 16-10-0.
(lb) - Max Horiz	1=213 (LC 7)
Max Uplift	All uplift 100 (lb) or less at joint(s) 1 except 6=-269 (LC 11), 9=-274 (LC 10)
Max Grav	All reactions 250 (lb) or less at joint(s) 1, 5 except 6=510 (LC 18), 7=469 (LC 17), 9=515 (LC 17)

FORCES	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS	3-7=-292/0, 2-9=-376/302, 4-6=-376/300

- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCCL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Gable requires continuous bottom chord bearing.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1 except (jt=lb) 9=273, 6=268.
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.


Job	Truss	Truss Type	Qty	Ply	PBS\HANOVER TRADITIONAL W/CAFE
72500235	V3	Truss	1	1	Job Reference (optional)

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Micah Clayton

Run: 8.81 S Sep 13 2024 Print: 8.810 S Sep 13 2024 MiTek Industries, Inc. Mon Jan 06 14:54:45

Page: 1

ID:FiEIWJVAvK7MzAZemw6oFaz3TJf-iOO0ZE9m2LVZuE3oxKGvPLwPKBhmbx7eu?Figbzy3?u



Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.21	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.18	Vert(TL)	n/a	-	n/a	999		
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.20	Horiz(TL)	0.00	5	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH							Weight: 71 lb	FT = 20%

LUMBER	BRACING
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
OTHERS 2x4 SP No.3	

REACTIONS	All bearings 14-10-0.
(lb) - Max Horiz	1=-187 (LC 6)
Max Uplift	All uplift 100 (lb) or less at joint(s) 1, 5 except 6=-233 (LC 11), 8=-238 (LC 10)
Max Grav	All reactions 250 (lb) or less at joint(s) 1, 5 except 6=431 (LC 18), 7=403 (LC 17), 8=437 (LC 17)

FORCES	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS	2-8=-339/273, 4-6=-339/271

- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Gable requires continuous bottom chord bearing.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 5 except (jt=lb) 8=237, 6=233.
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.


Job	Truss	Truss Type	Qty	Ply	PBS\HANOVER TRADITIONAL W/CAFE
72500235	V4	Truss	1	1	Job Reference (optional)

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Micah Clayton

Run: 8.81 S Sep 13 2024 Print: 8.810 S Sep 13 2024 MiTek Industries, Inc. Mon Jan 06 14:54:45

Page: 1

ID:juogjlfWogeFCbK8rJed1onz3TJe-iOO0ZE9m2LVZuE3oxKGvPLwPRBh9bzbheu?Fiqbzy3?u



Loading	(psf)	Spacing	2'-0"-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.20	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.15	Vert(TL)	n/a	-	n/a	999		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.11	Horiz(TL)	0.00	5	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH							Weight: 59 lb	FT = 20%

LUMBER		BRACING	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
OTHERS	2x4 SP No.3		
REACTIONS			
	All bearings 12-10-0.		
(lb) - Max Horiz	1=-161 (LC 6)		
Max Uplift	All uplift 100 (lb) or less at joint(s) 1, 5 except 6=-206 (LC 11), 8=-211 (LC 10)		
Max Grav	All reactions 250 (lb) or less at joint(s) 1, 5 except 6=368 (LC 18), 7=340 (LC 17), 8=373 (LC 17)		
FORCES			
	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.		
WEBS	2-8=-320/261, 4-6=-320/259		
NOTES			
1)	Unbalanced roof live loads have been considered for this design.		
2)	Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCCL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60		
3)	Gable requires continuous bottom chord bearing.		
4)	This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.		
5)	* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.		
6)	Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 5 except (jt=lb) 8=210, 6=205.		
7)	This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.		


Job	Truss	Truss Type	Qty	Ply	PBS\HANOVER TRADITIONAL W/CAFE
72500235	V5	Truss	1	1	Job Reference (optional)

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Micah Clayton

Run: 8.81 S Sep 13 2024 Print: 8.810 S Sep 13 2024 MiTek Industries, Inc. Mon Jan 06 14:54:46

Page: 1

ID:juogjFWogeFCbK8rJed1onz3TJe-iOO0ZE9m2LVZuE3oxKGvPLwQbBibbzueu?Figbzy3?u



Loading	(psf)	Spacing	2'-0\"/>
TCLL (roof)	20.0	Plate Grip DOL	1.15
TCDL	10.0	Lumber DOL	1.15
BCLL	0.0 *	Rep Stress Incr	YES
BCDL	10.0	Code	IRC2015/TPI2014
			Matrix-MSH
			0.09
			Horiz(TL)
			0.00
			5
			n/a
			n/a
			999
			999
			n/a
			n/a
			Weight: 47 lb
			FT = 20%

LUMBER		BRACING	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 6'-0\"/>
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 10'-0\"/>
OTHERS	2x4 SP No.3		
REACTIONS	All bearings 10'-10\"/>		
	(lb) - Max Horiz		1=-135 (LC 6)
	Max Uplift		All uplift 100 (lb) or less at joint(s) 1, 5 except 6=-196 (LC 11), 8=-203 (LC 10)
	Max Grav		All reactions 250 (lb) or less at joint(s) 1, 5, 7 except 6=341 (LC 18), 8=348 (LC 17)
FORCES	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.		
WEBS	2-8=-364/307, 4-6=-364/305		
NOTES			
1)	Unbalanced roof live loads have been considered for this design.		
2)	Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60		
3)	Gable requires continuous bottom chord bearing.		
4)	This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.		
5)	* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3'-0\"/>		
6)	Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 5 except (jt=lb) 8=202, 6=196.		
7)	This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.		


Job	Truss	Truss Type	Qty	Ply	PBS\HANOVER TRADITIONAL W/CAFE
72500235	V6	Truss	1	1	Job Reference (optional)

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Micah Clayton

Run: 8.81 S Sep 13 2024 Print: 8.810 S Sep 13 2024 MiTek Industries, Inc. Mon Jan 06 14:54:46

Page: 1

ID:juogjFWogeFCbK8rJed1onz3TJe-AayOmaAOpfdQWOe?U2n8yYSara0MKP3n7f?FM2zy3?t



Loading	(psf)	Spacing	2'-0"-0	CSI	DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.22	Vert(LL)	n/a	-	n/a	999	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.22	Vert(TL)	n/a	-	n/a	999	
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.16	Horiz(TL)	0.00	3	n/a	n/a	
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH						Weight: 36 lb	FT = 20%

LUMBER			BRACING		
TOP CHORD	2x4 SP No.2		TOP CHORD	Structural wood sheathing directly applied or 8'-10'-0 oc purlins.	
BOT CHORD	2x4 SP No.2		BOT CHORD	Rigid ceiling directly applied or 6'-0'-0 oc bracing.	
OTHERS	2x4 SP No.3				
REACTIONS	(lb/size)	1=45/8'-10'-0, (min. 0'-1'-8), 3=45/8'-10'-0, (min. 0'-1'-8), 4=617/8'-10'-0, (min. 0'-1'-8)			
	Max Horiz	1=-109 (LC 6)			
	Max Uplift	1=-12 (LC 22), 3=-12 (LC 21), 4=-152 (LC 10)			
	Max Grav	1=77 (LC 21), 3=77 (LC 22), 4=617 (LC 1)			
FORCES	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.				
WEBS	2'-4"=474/226				

- NOTES**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 3) Gable requires continuous bottom chord bearing.
 - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3'-0"-0 wide by 2'-0"-0 wide will fit between the bottom chord and any other members.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 12 lb uplift at joint 1, 12 lb uplift at joint 3 and 152 lb uplift at joint 4.
 - 7) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/ TPI 1.


Job	Truss	Truss Type	Qty	Ply	PBS\HANOVER TRADITIONAL W/CAFE
72500235	V7	Truss	1	1	Job Reference (optional)

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Micah Clayton

Run: 8.81 S Sep 13 2024 Print: 8.810 S Sep 13 2024 MiTek Industries, Inc. Mon Jan 06 14:54:46

Page: 1

ID:juogjlfWogeFCbK8rJed1onz3TJe-AayOmaAOpfdQWOe?U2n8yYScQa1eKQOn7f?FM2zy3?t



Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.12	Vert(LL)	n/a	-	n/a	999	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.14	Vert(TL)	n/a	-	n/a	999	
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.08	Horiz(TL)	0.00	3	n/a	n/a	
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH							
										Weight: 27 lb	FT = 20%


LUMBER		BRACING	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 6-10-0 oc purlins.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.
OTHERS	2x4 SP No.3		

REACTIONS	(lb/size)	1=58/6-10-0, (min. 0-1-8), 3=58/6-10-0, (min. 0-1-8), 4=430/6-10-0, (min. 0-1-8)
	Max Horiz	1=-84 (LC 6)
	Max Uplift	4=-93 (LC 10)
	Max Grav	1=77 (LC 21), 3=77 (LC 22), 4=430 (LC 1)

FORCES	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS	2-4=-300/140

- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Gable requires continuous bottom chord bearing.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 93 lb uplift at joint 4.
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/ TPI 1.

Job	Truss	Truss Type	Qty	Ply	PBS\HANOVER TRADITIONAL W/CAFE
72500235	V8	Truss	1	1	Job Reference (optional)



Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.06	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.08	Vert(TL)	n/a	-	n/a	999		
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.04	Horiz(TL)	0.00	3	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MP							Weight: 19 lb	FT = 20%

LUMBER	BRACING
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 4-10-0 oc purlins.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
OTHERS 2x4 SP No.3	

REACTIONS	(lb/size)	1=52/4-10-0, (min. 0-1-8), 3=52/4-10-0, (min. 0-1-8), 4=283/4-10-0, (min. 0-1-8)
Max Horiz	1=-58 (LC 6)	
Max Uplift	3=-2 (LC 11), 4=-57 (LC 10)	
Max Grav	1=63 (LC 21), 3=63 (LC 22), 4=283 (LC 1)	

FORCES	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
--------	--

- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Gable requires continuous bottom chord bearing.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 2 lb uplift at joint 3 and 57 lb uplift at joint 4.
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/ TPI 1.

Job	Truss	Truss Type	Qty	Ply	PBS\HANOVER TRADITIONAL W/CAFE
72500235	V9	Truss	1	1	Job Reference (optional)




Plate Offsets (X, Y):	[2:0-2-0,Edge]
-----------------------	----------------

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.06	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.05	Vert(TL)	n/a	-	n/a	999		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.00	Horiz(TL)	0.00	3	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MP							Weight: 9 lb	FT = 20%

LUMBER		BRACING	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 2-10-0 oc purlins.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
REACTIONS	(lb/size)		
	1=113/2-10-0, (min. 0-1-8), 3=113/2-10-0, (min. 0-1-8)		
	Max Horiz	1=-32 (LC 8)	
	Max Uplift	1=-12 (LC 10), 3=-12 (LC 11)	

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Gable requires continuous bottom chord bearing.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 12 lb uplift at joint 1 and 12 lb uplift at joint 3.
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/ TPI 1.


Job	Truss	Truss Type	Qty	Ply	PBS\HANOVER TRADITIONAL W/CAFE
72500235	V10	Truss	2	1	Job Reference (optional)

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Micah Clayton

Run: 8.81 S Sep 13 2024 Print: 8.810 S Sep 13 2024 MiTek Industries, Inc. Mon Jan 06 14:54:46

Page: 1

ID:K3V5SJlv43LnXs3bqY5hCz3TOV-AayOmaAOpfdQWOe?U2n8yYSZDa04KPNn7f?FM2zy3?t



Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.26	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.24	Vert(TL)	n/a	-	n/a	999		
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.14	Horiz(TL)	0.00	3	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH							Weight: 32 lb	FT = 20%

LUMBER		BRACING	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 9-3-0 oc purlins.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.
OTHERS	2x4 SP No.3		
REACTIONS	All bearings 9-3-12.		
	(lb) - Max Horiz 1=76 (LC 7), 7=76 (LC 7)		
	Max Uplift All uplift 100 (lb) or less at joint(s) 1, 3, 4, 7		
	Max Grav All reactions 250 (lb) or less at joint(s) 1, 3, 7 except 4=745 (LC 1)		
FORCES	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.		
TOP CHORD	1-2=-145/401, 2-3=-68/386		
BOT CHORD	1-4=-312/132, 3-4=-287/116		
WEBS	2-4=-595/174		

- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCCL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Gable requires continuous bottom chord bearing.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 3, 4, 1.
 - Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 1, 3, 7.
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/ TPI 1.


Job	Truss	Truss Type	Qty	Ply	PBS\HANOVER TRADITIONAL W/CAFE
72500235	V11	Truss	2	1	Job Reference (optional)

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Micah Clayton

Run: 8.81 S Sep 13 2024 Print: 8.810 S Sep 13 2024 MiTek Industries, Inc. Mon Jan 06 14:54:46

Page: 1

ID:FiEIWJVAvK7MzAZemw6oFaz3TJf-AayOmaAOpfdQWOe?U2n8yYScTa28KQIn7?FM2zy3?I



Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.12	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.10	Vert(TL)	n/a	-	n/a	999		
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.08	Horiz(TL)	0.00	3	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH							Weight: 21 lb	FT = 20%

LUMBER		BRACING	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 6-3-0 oc purlins.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.
OTHERS	2x4 SP No.3		

REACTIONS	All bearings 6-3-12.
(lb) - Max Horiz	1=-50 (LC 6), 7=-50 (LC 6)
Max Uplift	All uplift 100 (lb) or less at joint(s) 1, 3, 4, 7
Max Grav	All reactions 250 (lb) or less at joint(s) 1, 3, 7 except 4=505 (LC 1)

FORCES	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	1-2=-92/278, 2-3=-50/266
WEBS	2-4=-399/123

- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Gable requires continuous bottom chord bearing.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3, 4.
 - Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 1, 3, 7.
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/ TPI 1.

Job	Truss	Truss Type	Qty	Ply	PBS\HANOVER TRADITIONAL W/CAFE
72500235	V12	Truss	2	1	Job Reference (optional)




Plate Offsets (X, Y): [2:0-2-0,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.08	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.08	Vert(TL)	n/a	-	n/a	999		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.00	Horiz(TL)	0.00	3	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MP							Weight: 9 lb	FT = 20%

LUMBER			BRACING	
TOP CHORD	2x4 SP No.2		TOP CHORD	Structural wood sheathing directly applied or 3-3-0 oc purlins. Rigid ceiling directly applied or 10-0-0 oc bracing.
BOT CHORD	2x4 SP No.2		BOT CHORD	
REACTIONS	(lb/size)	1=133/3-3-12, (min. 0-1-8), 3=133/3-3-12, (min. 0-1-8)		
	Max Horiz	1=-24 (LC 8)		
	Max Uplift	1=-18 (LC 10), 3=-18 (LC 11)		

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Gable requires continuous bottom chord bearing.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 18 lb uplift at joint 1 and 18 lb uplift at joint 3.
 - Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 1, 3.
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/ TPI 1.