


Job	Truss	Truss Type	Qty	Ply	PBS\CLAYTON FRENCH COUNTRY LH RF
72509877REP2	A7	Truss	1	1	Job Reference (optional)

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, clm

Run: 8.83 S Mar 20 2025 Print: 8.830 S Apr 11 2025 MiTek Industries, Inc. Mon Jul 28 09:36:35

Page: 1

ID:kiUWkr3qE6VC0lws3qT2j7yRXv0-dPvoh4buCF6yljfw5wKMarobloWEI56zzeMXrtyb2S




Repair to replace web 4-18 and 5-18

Cut and fit tight new 2x4 SP or SPF No.2 members as shown  
attach 3/4in. Plywood or OSB (23/32in. APA Rated Sheathing 48/24 Exposure 1) gusset  
to both sides of truss as shown with two rows of 10d (.131" x 3") nails spaced 4" oc  
in all members from each face, driven through both sheets of plywood.

Plate Offsets (X, Y): [4:0-4-0,0-4-8], [12:Edge,0-3-8], [15:0-4-0,0-4-8]												
Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.99	Vert(LL)	-0.28	16-18	>999	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.96	Vert(CT)	-0.51	16-18	>999	180	M18AHS	186/179
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.96	Horz(CT)	0.12	12	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH							Weight: 416 lb	FT = 20%

LUMBER			BRACING		
TOP CHORD	2x6 SP No.2		TOP CHORD	Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (4-2-2 max.): 6-10.	
BOT CHORD	2x6 SP No.2		BOT CHORD	Rigid ceiling directly applied or 2-2-0 oc bracing.	
WEBS	2x4 SP No.3 "Except" W6,W5;2x4 SP No.2		WEBS	1 Row at midpt	11-12, 7-15, 5-16, 9-13, 7-16
SLIDER	Left 2x4 SP No.3 ~ 1-11-0				
REACTIONS					
	(lb/size)	2=2100/0-3-8, (min. 0-2-8), 12=2047/0-3-8, (min. 0-2-10)			
	Max Horiz	2=346 (LC 10)			
	Max Uplift	2=252 (LC 10), 12=175 (LC 6)			
	Max Grav	2=2104 (LC 2), 12=2200 (LC 2)			
FORCES					
	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.				
TOP CHORD	2-3=-1448/114, 3-4=-3629/857, 4-5=-3470/915, 5-6=-2840/771, 6-7=-2493/739, 7-8=-2399/672, 8-9=-2399/672, 9-10=-1436/468, 10-11=-1665/439, 11-12=-2063/540				
BOT CHORD	2-18=-923/3135, 18-23=-759/2840, 17-23=-759/2840, 17-24=-759/2840, 16-24=-759/2840, 16-25=-582/2548, 25-26=-582/2548, 15-26=-582/2548, 15-27=-452/2058, 27-28=-452/2058, 14-28=-452/2058, 13-14=-452/2058				
WEBS	4-18=-276/268, 5-18=-133/493, 7-15=-476/230, 11-13=-359/1822, 9-15=-88/856, 5-16=-663/340, 9-13=-1381/363, 10-13=-25/478, 6-16=-193/1010, 7-16=-338/229				


- NOTES (10)
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; end vertical left exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - Provide adequate drainage to prevent water ponding.
  - All plates are MT20 plates unless otherwise indicated.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 175 lb uplift at joint 12 and 252 lb uplift at joint 2.
  - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
  - This repair has been prepared based on information and use conditions supplied by client. Designer has made a good faith effort to outline damage and repair conditions as reported by client. When actual field conditions do not approximate those indicated on this drawing, client shall immediately inform the engineer and refrain from applying the repair.



This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.



Job	Truss	Truss Type	Qty	Ply	PBS\CLAYTON FRENCH COUNTRY LH RF
72509877REP2	A7	Truss	1	1	Job Reference (optional)



Repair to replace web 4-18 as shown.

Cut and fit tight new 2x4 SP or SPF No.2 member as shown  
attach 3/4in. Plywood or OSB (23/32in. APA Rated Sheathing 48/24 Exposure 1) gusset  
to both sides of truss as shown with two rows of 10d (.131" x 3") nails spaced 4" oc  
in all members from each face, driven through both sheets of plywood.

Plate Offsets (X, Y): [4:0-4-0,0-4-8], [12:Edge,0-3-8], [15:0-4-0,0-4-8]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	Vert(LL)	-0.28	16-18	>999	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	Vert(CT)	-0.51	16-18	>999	180	M18AHS	186/179
BCLL	0.0 *	Rep Stress Incr	YES	WB	Horz(CT)	0.12	12	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MSH						Weight: 416 lb	FT = 20%

LUMBER			BRACING		
TOP CHORD	2x6 SP No.2		TOP CHORD	Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (4-2-2 max.): 6-10.	
BOT CHORD	2x6 SP No.2		BOT CHORD	Rigid ceiling directly applied or 2-2-0 oc bracing.	
WEBS	2x4 SP No.3 "Except" W6,W5;2x4 SP No.2		WEBS	1 Row at midpt	11-12, 7-15, 5-16, 9-13, 7-16
SLIDER	Left 2x4 SP No.3 - 1-11-0				
REACTIONS					
	(lb/size)	2=2100/0-3-8, (min. 0-2-8), 12=2047/0-3-8, (min. 0-2-10)			
	Max Horiz	2=346 (LC 10)			
	Max Uplift	2=-252 (LC 10), 12=-175 (LC 6)			
	Max Grav	2=2104 (LC 2), 12=2200 (LC 2)			
FORCES					
	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.				
TOP CHORD	2-3=-1448/114, 3-4=-3629/857, 4-5=-3470/915, 5-6=-2840/771, 6-7=-2493/739, 7-8=-2399/672, 8-9=-2399/672, 9-10=-1436/468, 10-11=-1665/439, 11-12=-2063/540				
BOT CHORD	2-18=-923/3135, 18-23=-759/2840, 17-23=-759/2840, 17-24=-759/2840, 16-24=-759/2840, 16-25=-582/2548, 25-26=-582/2548, 15-26=-582/2548, 15-27=-452/2058, 27-28=-452/2058, 14-28=-452/2058, 13-14=-452/2058				
WEBS	4-18=-276/268, 5-18=-133/493, 7-15=-476/230, 11-13=-359/1822, 9-15=-88/856, 5-16=-663/340, 9-13=-1381/363, 10-13=-25/478, 6-16=-193/1010, 7-16=-338/229				

- NOTES (10)**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior (2) zone; end vertical left exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
  - Provide adequate drainage to prevent water ponding.
  - All plates are MT20 plates unless otherwise indicated.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 175 lb uplift at joint 12 and 252 lb uplift at joint 2.
  - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
  - This repair has been prepared based on information and use conditions supplied by client. Designer has made a good faith effort to outline damage and repair conditions as reported by client. When actual field conditions do not approximate those indicated on this drawing, client shall immediately inform the engineer and refrain from applying the repair.

