LAWSON

BRIARWOOD BLUFF LOT 0017

PLAN ID 110122



110 VILLAGE TRAIL SUITE 215 WOODSTOCK, GA. 30188

| DF | RAWING INDEX |
|---|--|
| A0.0 A1.1 A2.1 A3.1 A5.1 A5.2 A6.1 A7.2-A7.3 | COVER SHEET FRONT ELEVATIONS SIDE & REAR ELEVATIONS SLAB FOUNDATION FIRST FLOOR PLANS & DETAILS SECOND FLOOR PLANS & DETAILS ROOF PLANS ELECTRICAL PLANS TRIM LOCATION LAYOUTS |
| 7.012 | |

| AREA TABULATION | | |
|-----------------------|------|--|
| FIRST FLOOR | 704 | |
| SECOND FLOOR | 946 | |
| TOTAL | 1650 | |
| GARAGE | 402 | |
| FRONT PORCH (COVERED) | 91 | |
| REAR PATIO | 120 | |

| DATE | BY | REVISION | PAGE # |
|-----------|----|---|--|
| 5/30/2023 | AW | Prototype walk revisions - see revision sheet | A3.1, A5.1, A5.2, A7.2, A7.3, A8.1 |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

PLAN REVISIONS

GOVERNMENTAL CODES & STANDARDS

HOME TO BE BUILT TO CONFORM TO ALL APPLICABLE LOCAL CODES, PRACTICES AND STANDARDS


BUILDING CODE ANALYSIS / DESIGN CRITERIA

HOME TO BE BUILT TO MEET OR EXCEED ALL LOCAL CODES AND DESIGN CRITERIA

ALL NON-MASONRY RETURNS TO BE HORIZONTAL SIDING


SEE SHEET D3 OF SDH TYPICAL DETAILS FOR SOFFIT DETAILS PER SOFFIT MATERIAL

BRIARWOOD BLUFF LOT 0017



FRONT ELEVATION "A"

SCALE: 3/16"=1'-0"




SMITH DOUGLAS HOMES

ELEVATIONS FRONT ELEVATION LAWSON


SMITH DOUGLAS HOMES
110 VILLAGE TRAIL
SUITE 115
WOODSTOCK, GA 30188
www.smithdouglas.com


SMITH DOUGLAS HOMES expressly reserves it's property rights in these plans and drawings. These plans and related drawings are not to be reproduced without written consent from SMITH DOUGLAS HOMES.





BRIARWOOD BLUFF LOT 0017







SMITH DOUGLAS HOMES QUALITY I INTEGRITY I VALUE

ELEVATIONS
SIDES AND REAR
LAWSON

SMITH DOUGLAS HOMES 110 VILLAGE TRAIL SUITE 115 WOODSTOCK, GA 30188 www.smithdouglas.com

SMITH DOUGLAS HOMES expressly reserves it's property rights in these plans and drawings. These plans and related drawings are not to be reproduced without writte consent from SMITH DOUGLAS HOMES.





*RADON VENT PROVIDED PER LOCAL CODE


REFER TO DETAIL 3/D1
FOR BRICK LEDGE
DETAIL WHEN BRICK
VENEER IS CHOSEN


SMITH DOUGLAS HOMES

FOUNDATION PLAN SLAB PLAN LAWSON


SMITH DOUGLAS HOMES 110 VILLAGE TRAIL SUITE 115 WOODSTOCK, GA 30188 www.smithdouglas.com

SMITH DOUGLAS HOMES expressly reserves it's property rights in these plans and drawings. These plans and relatedrawings are not to be reproduced without writte consent from SMITH DOUGLAS HOMES.





SECTION AT STAIRS






FLOOR PLAN
FIRST FLOOR
LAWSON

SMITH DOUGLAS HOMES
110 VILLAGE TRAIL
SUITE 115
WOODSTOCK, GA 30188
www.smithdouglas.com

SMITH DOUGLAS HOMES
expressly reserves it's
property rights in these
plans and drawings.
These plans and relate
drawings are not to be

*RADON VENT PROVIDED PER LOCAL CODE





*RADON VENT PROVIDED
PER LOCAL CODE


REFER TO MANUFACTURER'S SPECS. FOR DRAIN LOCATIONS ON DETAIL SHEETS D12, D12.1, & D12.2


SMITH DOUGLAS HOMES


FLOOR PLAN
SECOND FLOOR
LAWSON

SMITH DOUGLAS HOMES 110 VILLAGE TRAIL SUITE 115 WOODSTOCK, GA 30188 www.smithdouglas.com

SMITH DOUGLAS HOMES expressly reserves it's property rights in these plans and drawings. These plans are not related drawings are not to be reproduced without writte consent from SMITH DOUGLAS HOMES.










ROOF PLAN
ROOF PLAN
LAWSON

SMITH DOUGLAS HOMES 110 VILLAGE TRAIL SUITE 115 WOODSTOCK, GA 30188 www.smithdouglas.com

SMITH DOUGLAS HOMES expressly reserves it's property rights in these plans and drawings. These plans are not related drawings are not to be reproduced without writte consent from SMITH DOUGLAS HOMES.



10'X12' PATIO **FAMILY** ROOM PROVIDED AS NEEDED PWDR GARAGE FOYER COVERED PORCH


FIRST FLOOR ELECTRICAL PLAN

SCALE : 1/8" = 1'-0"

BRIARWOOD BLUFF LOT 0017

| ELECTRICAL LEGEND | | | |
|--|-------------------------------------|-----------------------|-----------------------------|
| \$ | SWITCH | TV. | TV |
| \$3 | 3 WAY SWITCH | φ | 120V RECEPTACLE |
| \$4 | 4 WAY SWITCH | P | 120V SWITCHED RECEPTACLE |
| Ø | CEILING FIXTURE | Φ | 220V RECEPTACLE |
| -\$ _K | KEYLESS | P _{GFCI} | GFCI OUTLET |
| ΗØ | WALL MOUNT FIXTURE | PAFCI | ARCH FAULT CIRCUIT |
| 0 | CEILING FIXTURE | † _{GL} | GAS LINE |
| • | FLEX CONDUIT | † _{wL} | WATER LINE |
| СН | CHIMES | ¥ | HOSE BIBB |
| ₽H | TELEPHONE | 8 | FLOOD LIGHT |
| SD/Cc ₩ | SMOKE DETECTOR & CARBON MONOXIDE | | 1x4 LUMINOUS FIXTURE |
| SO | SECURITY OUTLET | | OFILING FAN |
| | GARAGE DOOR OPENER | | CEILING FAN |
| | EXHAUST FAN | | ELECTRICAL WIRING |
| <u></u> | FAN/LIGHT | | CEILING FIXTURE |
| ELECTRICAL PLANS TO FOLLOW ALL LOCAL CODES | | | |
| APPROX. FIXTURE HGTS (MEASURED FROM BOTTOM OF FIXTURE) | | | |
| BREAKFAST/DINING ROOM 63" ABO | | 63" ABO | VE FINISHED FLOOR |
| KITCHEN PENDANT LIGHTS | | 33" ABOVE COUNTER TOP | |
| TWO STORY FOYER FIXTURE 96" ABOVE FINISHED FLOOR | | VE FINISHED FLOOR | |
| CEILING FAN 96" ABOVE FINISHED | | VE FINISHED FLOOR | |
| FLOOD LIGHT | | 10' MAX. | . ABOVE FIN. FLOOR |
| | | | |

NOTE: FINAL PLACEMENT OF PHONE/CABLE T.B.D. ON SITE BY THE BUILDER



SMITH DOUGLAS HOMES

ELECTRICAL PLAN
ELECTRICAL PLAN
FINANCIA STATEMENT STATE

SMITH DOUGLAS HOMES expressly reserves it's property rights in these plans and drawings. These plans and related drawings are not to be eproduced without writter consent from SMITH.



W.I.C. OWNER'S SUITE BEDROOM 2 BEDROOM 3 BEDROOM 3 BEDROOM 3


SECOND FLOOR ELECTRICAL PLAN

SCALE : 1/8" = 1'-0"

BRIARWOOD BLUFF LOT 0017

| ELECTRICAL LEGEND | | | |
|--|-------------------------------------|-------------------|-----------------------------|
| \$ | SWITCH | | TV |
| \$3 | 3 WAY SWITCH | φ | 120V RECEPTACLE |
| \$4 | 4 WAY SWITCH | • | 120V SWITCHED RECEPTACLE |
| Ø | CEILING FIXTURE | • | 220V RECEPTACLE |
| -\$ _K | KEYLESS | P _{GFCI} | GFCI OUTLET |
| ₩X | WALL MOUNT FIXTURE | PAFCI | ARCH FAULT CIRCUIT |
| 0 | CEILING FIXTURE | T _{GL} | GAS LINE |
| • | FLEX CONDUIT | T _{WL} | WATER LINE |
| СН | CHIMES | ¥ | HOSE BIBB |
| PH | TELEPHONE | B | FLOOD LIGHT |
| SD/Cd ₩ | SMOKE DETECTOR & CARBON MONOXIDE | | 1x4 LUMINOUS FIXTURE |
| SO | SECURITY OUTLET | | |
| | GARAGE DOOR OPENER | | CEILING FAN |
| ≡ | EXHAUST FAN | | ELECTRICAL WIRING |
| 0 | FAN/LIGHT | | CEILING FIXTURE |
| ELECTRICAL PLANS TO FOLLOW ALL LOCAL CODES | | | |
| APPROX. FIXTURE HGTS (MEASURED FROM BOTTOM OF FIXTURE) | | | |
| BREAKFAST/DINING ROOM 63" ABOVE FINISHED FLOOR | | VE FINISHED FLOOR | |
| KITCHEN PENDANT LIGHTS | | 33" ABO | VE COUNTER TOP |
| TWO STORY FOYER FIXTURE 96" ABOVE FINISHED FLOOR | | VE FINISHED FLOOR | |
| CEILING FAN 96" ABOVE FINISHED FLOOI | | VE FINISHED FLOOR | |
| FLOOD LIGHT | | 10' MAX | . ABOVE FIN. FLOOR |
| | | | |

NOTE: FINAL PLACEMENT OF PHONE/CABLE T.B.D. ON SITE BY THE BUILDER




SMITH DOUGLAS HOMES

ELECTRICAL PLAN
SECOND FLOOR
LAWSON

SMITH DOUGLAS HOMES 110 VILLAGE TRAIL SUITE 115 WOODSTOCK, GA 30188 www.smithdouglas.com

SMITH DOUGLAS HOMES expressly reserves it's property rights in these plans and drawings. These plans and related drawings are not to be reproduced without written consent from SMITH DOUGLAS HOMES.






FOYER TRIM - CHAIR/SHADOW ----

TRIM LAYOUT FIRST FLOOR PLAN


SCALE : 1/8" = 1'-0"






SMITH DOUGLAS HOMES
110 VILLAGE TRAIL
SUITE 115
WOODSTOCK, GA 30188
www.smithdouglas.com

SMITH DOUGLAS HOMES expressly reserves it's property rights in these plans and drawings. These plans and related drawings are not to be exproduced without writte





 DATE
 REVISION
 BY

SMITH DOUGLAS HOMES QUALITY | INTEGRITY | VALUE

INTERIOR TRIM
DETAILS

SMITH DOUGLAS HOMES 110 VILLAGE TRAIL SUITE 215 WOODSTOCK, GA 30188 www.smithdouglas.com

SMITH DOUGLAS HOMES expressly reserves it's property rights in these plans and drawings. These plans and related drawings are not to be reproduced without written consent from SMITH DOUGLAS HOMES.

DATE: 6/13/23

FACADE OPT:

PLAN ID:

FND: ELLEV:

PAGE NO: D 1.1

CONNECTION SPECIFICATIONS (TYP. U.N.O.)

| DESCRIPTION OF BLDG. ELEMENT | 3"x0.131" NAIL5 | 3"x0.120" NAILS | |
|---|--|---|--|
| JOIST TO SOLE PLATE | (3) TOENAILS | (3) TOENAILS* | |
| SOLE PL. TO JOIST/RIM OR BLK'G | NAILS @ 4" o.c. | NAILS @ 4" o.c. | |
| STUD TO PLATE | (4) TOENAILS/ (3)END NAILS | (4) TOENAILS/ (4)END NAILS* | |
| RIM TO TOP PLATE | TOENAILS @ 6" o.c. | TOENAILS @ 4" o.c.* | |
| BLK'G. BTWN. JOISTS TO TOP PL. | (3) TOENAILS EA. END | (3) TOENAILS EA. END* | |
| DOUBLE STUD | NAILS @ 16" o.c. | NAILS @ 16" O.C. | |
| DOUBLE TOP PLATE | NAILS ⊘ 12" o.c. | NAILS @ 8" o.c. | |
| DOUBLE TOP PLATE LAP SPLICE | (I2) NAILS IN LAPPED AREA (24" MIN.) | (15) NAILS IN LAPPED AREA (24" MIN.) | |
| TOP PLATE LAP @ CORNERS & INTERSECTING WALLS | (3) NAILS | (3) NAILS | |
| RAFTER/TRUSS TO TOP PLATE | (4) TOENAILS + (I) SIMPSON H2.5T | (4) TOENAILS + (I) SIMPSON H2.5T | |
| GAB. END TRUSS TO DBL. TOP PL. | TOENAILS @ 8" o.c. | TOENAILS @ 6" o.c. | |
| R.T. w/ HEEL HT. 91/4" TO 12" | 2xIO BLK EVERY 3RD BAY FASTENED TO DBL. TOP PLATE W/ TOENAILS @ 6" O.C. | 2xIO BLK EVERY 3RD BAY FASTENED TO DBL. TOP PLATE W/ TOENAILS @ 4" O.C. | |
| R.T. w/ HEEL HT. 12" TO 16" | 2xI2 BLK EVERY 3RD BAY FASTENED TO DBL. TOP PLATE w/ TOENAILS @ 6" O.C. | 2xI2 BLK EVERY 3RD BAY FASTENED TO DBL. TOP PLATE w/ TOENAILS @ 4" O.C. | |
| R.T. w/ HEEL HT. UP TO 24" | LAP WALL SHTG. W/ DBL. TOP PL. \$ INSTALL ON TRUSS VERT FASTEN W/ NAILS @ 6" O.C. | LAP WALL SHTG. W/ DBL. TOP PL. & INSTALL ON TRUSS VERT FASTEN W/ NAILS @ 6" O.C.* | |
| R.T. w/ HEEL HT. 24" TO 48" | LAP WALL SHTG, W DBL. TOP PL. & INSTALL ON TRUSS VERT FASTEN W NAILS @ 6" O.C. PROVIDE 2x BLK @ EA. BAY AT TOP OF HEEL | LAP WALL SHTG, W/ DBL, TOP PL. 4 INSTALL ON TRUSS VERT FASTEN W/ NAILS @ 6" O.C. PROVIDE 2x BLK @ EA. BAY AT TOP OF HEEL* | |
| WALL TO FOUNDATION | WALL SHTG. LAP W/ SILL PL. & FASTENED PER SHEAR WALL FASTENING SPEC. | | |
| * OVER OUR IC AN ACCEPTABLE ALTERNATIVE TO A REGION CANE CRACING OR NIMPER OF MALIC | | | |

2½"x0.113 IS AN ACCEPTABLE ALTERNATIVE TO A 3"x0.120", SAME SPACING OR NUMBER OF NAILS. ONLY ACCEPTABLE WHERE * ARE SHOWN)

ADDITIONAL NOTES FOR TRUSS & I-JOIST MANUFACTURER

ROOF TRUSS AND ENGINEERED JOISTS SHALL BE DESIGNED TO MEET THE DEFLECTION CRITERIA BELOW, UNLESS NOTED OTHERWISE ON PLAN. MULHERN & KULP CANNOT BE HELD RESPONSIBLE FOR ANY STRUCTURAL ISSUES RELATED TO ANY BUILDING COMPONENT IF COMPONENT SHOP DRAWINGS ARE NOT SUBMITTED TO M&K FOR REVIEW PRIOR TO FABRICATION, DELIVERY, OR INSTALL ATION

TRUSSES/ MISTS SHALL BE DESIGNED SO THAT DIFFERENTIAL DEFLECTION BETWEEN ADJACENT PARALLEL TRUSSES/JOISTS OR GIRDER TRUSSES/FLUS BEAMS DO NOT EXCEED THE FOLLOWING:

- A. ROOF TRUSSES: I/4" DEAD LOAD
- B. ATTIC TRUSSES, & I-JOISTS:
- 1/8" DEAD LOAD

ABSOLUTE DEAD LOAD DEFECTION OF ATTIC TRUSSES WHEN AD IACENT TO ELOOP ERAMING BY OTHERS SHALL BE LIMITED TO 3/16". (NOT DIFFERENTIAL DEFLECTION)

VENEER LINTEL SCHEDULE

| SPAN (MAX) | HEIGHT OF VENEER ABOVE LINTEL | STEEL ANGLE SIZE |
|---------------|----------------------------------|------------------|
| 3'-0" | 20 FT, MAX | L3"x3"x¼;" |
| | 3 FT. MAX | L3"x3"x/4;" |
| 6'-0" | I2 FT. MAX | L4"x3"x¼" |
| | 20 FT. MAX | L5"x3½"x¾" |
| 8'-0" | 3 FT. MAX | L4"x4"x¼" * |
| | I2 FT. MAX | L5"x3½"x¾" |
| | I6 FT. MAX | L6"x3½"x¾" |
| 9'-6" | I2 FT. MAX | L6"x3½"x¾6" |

L LINICLES: SHALL SUPPORT 2 3%' - 3 ½' VENEER W 40 pef MAXIM. 16' SHALL HAVE 4" MIN. BEARING 16' SHALL HAVE 8" MIN. BEARING 16' SHALL NOT BE FASTENED BACK TO HEADER.

(4) SHALL NOT BE FASTIBED BACK TO HEADER IN WALL \$48\times_{10} \times_{10} \times_{10}

GENERAL STRUCTURAL NOTES

FOUNDATION

- DESIGN IS BASED ON 2018 NCSBC-RESIDENTIAL CODE & 2018 IRC WITH SOUTH CAROLINA AMENDMENTS
- FOOTING DESIGN 2,000 PSF NET ALLOWABLE SOIL BEARING PRESSURE IS ASSUMED, BUILDER/CONTRACTOR MUST VERIFY.
- FASTEN 2×4/6 SILL PLATES TO CONC FND WITH A MINIMUM OF 2 ANCHORS PER PLATE, 12" MAX. FROM PLATE ENDS - UTILIZING I/2" DIA ANCHOR BOLTS @ 6'-0" O.C.7" MIN. EMBEDMENT.
- FA4 ANCHOR STRAPS @ 6'-0" O.C
- FASTEN 2xIO SILL PLATES TO PRECAST BOMT WALLS WITH A MINIMUN OF 2 ANCHORS PER PLATE, 12" MAX. FROM PLATE ENDS - UTILIZING: • I/2" DIA. BOLTS @ 2'-0" O.C
- ALL LUMBER EXPOSED TO WEATHER OR IN CONTACT W/ PERIMETER FOUNDATION SHALL BE PRESERVATIVE TREATED SOUTHERN PINE #2.
- BUILDER TO VERIFY CORROSION-RESISTANCE COMPATIBILITY OF HARDWARE & FASTENERS IN CONTACT W/ PRESERVATIVE-TREATED WOOD, CONTACT LUMBER & HARDWARE SUPPLIERS TO COORD.
- FOUNDATION WALLS & FOOTINGS SHALL BE PLAIN CONCRETE, U.N.O.
- CONCRETE DESIGN BASED ON ACI 318. CONCRETE SHALL ATTAIN THE FOLLOWING MIN. COMPRESSIVE STRENGTHS IN 28 DAYS, U.N.O.: f'c = 4,000 psi: FOUNDATION WALLS
 - 3,000 psi: FOOTINGS & INTERIOR SLABS ON GRADE 3,500 psi: GARAGE & EXTERIOR SLABS ON GRADE = 60,000 psi
- BASEMENT FOUNDATION WALL DESIGN BASED ON:
 - . 8' OR 9' HEIGHT (AS NOTED ON PLANS) TALLER WALLS MUST BE ENGINEERED.
- BASEMENT WALL DESIGN IS BASED ON 30 OR 45 PCF BACKFILL SOIL TYPE CLASSIFICATIONS:
 - 30 PCF TYPE (GW, GP, SW, SP) 45 PCF TYPE (GM, GC, SM, SM-SC, ML)
- IMPORTANT IF 60 PCF SOIL TYPE (SC, ML-CL, OR CL) IS UTILIZED FOR BACKELL CONTACT MULHERN & KULP FOR FURTHER EVALUATION OF FOUNDATION DESIGN
- BASEMENT WALLS SHALL BE BRACED, PRIOR TO BACKFILLING, BY ADEQUATE TEMPORARY BRACING OR INSTALL Ist FLOOR DECK.
- ALL CONCRETE EXPOSED TO THE WEATHER SHALL NOT HAVE LESS THAN 5% OR MORE THAN 7% AIR ENTRAINMENT.
- ALL FOOTINGS SHALL BEAR BELOW FROST LINE (TYP.) OR 12" MIN IN REGIONS WHERE CODE FROST DEPTH IS NOT APPLICABLE. CONSULT SOILS REPORT OR BUILDING DEPT. FOR MINIMUM DEPTH BELOW
- FOOTINGS AND SLABS ON GRADE SHALL BEAR ON VIRGIN SOIL OR 95% COMPACTED FILL.
- PROVIDE CONTROL JOINTS AT ALL INSIDE CORNERS OF SLAB EDGES, AND OTHER LOCATIONS WHERE SLAB CRACKS ARE LIKELY TO DEVELOP. JOINTS SHALL BE LOCATED @ 10'-0" O.C. (RECOMMENDED) OR
- 15'-0" O.C. (MAXIMUM)
- JOINT GRID PATTERN SHALL BE AS CLOSE TO SQUARES AS POSSIBLE (I:I RATIO), WITH A MAXIMUM OF I:I.5 RATIO
- · CONTROL JOINTS SHALL NOT BE INSTALLED IN STRUCTURAL
- TYPICAL REINFORGEMENT DETAILS: PROVIDE 3" MIN CLEAR COVER WHERE CAST AGAINST EARTH, I 1/2" MIN, CLEAR COVER AGAINST FORMS. LAP ALL REBAR 48 BAR DIAMETERS MIN. (24" FOR #4 BARS) & BEND BARS AND LAP AT CORNERS. PROVIDE 61 HOOK INTO SUPPORTING FOOTINGS WHEN FOOTINGS INTERSECT
- DIMENSIONS BY OTHERS BUILDER TO VERIEY.

LEGEND

R.T. NDICATES ROOF TRUSSES @ 24" O.C. PER ROOF. MANUF. (TYP. U.N.O.)

INDICATES TRUSS OVERFRAMING @ 24" O.C. (TYP. U.N.O.)

INDICATES 14" DEEP FLOOR I-JOISTS @ 24" O.C. MAX. JOIST SERIES AND SPACING SHALL BE THE RESPONSIBILITY OF THE MANUFACTURER NOTE: 14" FLOOR TRUSSES @ 24" O.C. MAX. IS AN ACCEPTABLE ALTERNATE FLOOR SYSTEM

INDICATES LOCATIONS OF POTENTIAL TILE FLOOR JOIST MANUFACTURER SHALL DESIGN FLOOR SYSTEM FOR ADD'L 10 PSF DEAD LOAD AT THESE

- INTERIOR BEARING WALL
- □□□□□ BFARING WALL ABOVE (B.W.A.)
- --- BEAM/HEADER
- JL METAL HANGER
- INDICATES POST ABOVE (P.A.) PROVIDE SOLID BLOCKING UNDER POST OR JAMB ABOVE.

.ATERAL/WALL BRACING & WALL SHEATHING SPECIFICATIONS

THIS MODEL HAS BEEN DESIGNED TO RESIST LATERAL FORCES RESULTING FROM: MPH WIND IN 2018 NGSBC:RO

& 120MPH WIND IN 2018 IRC (120 MPH WIND SPEED IN ASCE 7

WIND MAP PER IRC R30(211) EXP. B. RISK CAT. 2 & SEISMIC CAT. A/B.

HE DESIGN WAS COMPLETED PER 2015 \$ 2018 IBC SECTION 1609) & ASCE 7 AS PERMITTED BY R3011: OF THE 2018 NOSBO:RC & 2018 IRC. ACCORDINGLY THIS MODEL, AS DOCUMENTED AND DETAILED HEREWITHIN, IS ADEQUATE TO RESIST THE CODE REQUIRED LATERAL FORCES

DESIGN WIND UPLIFT LOADS HAVE BEEN CALCULATED UTILIZING ASCE 7 (ACCEPTED) ENGINEERING PRACTICE) AS ALLOWED PER 2018 NCSBC:RC & 2018 IRC SECTION R802.II.I.I. THIS MODEL HAS BEEN DETAILED WHERE REQUIRED & ENGINEERED TO RESIST THE WIND UPLIFT LOAD PATH PER SECTIONS R602.3.54 R802.II.

EXT. WALL SHEATHING SPECIFICATION

- 1/16" OSB OR 15/32" PLYWOOD: FASTEN SHEATHING W/ 2 3 "XO.II3 NAIL5 @ 6" O.C. AT EDGES & @ 12" O.C. IN THE PANEL FIELD. (TYP, U.N.O.)
- ALL SHEATHING PANELS SHALL BE ORIENTED VERTICALLY (LONG DIRECTION PARALLEL TO STUDS) AND INSTALLED FULL HEIGHT OF SHEAR WALL - OR 2x HORIZONTAL BLOCKING SHALL BE PROVIDED TO SUPPORT ALL UNSUPPORTED PANEL EDGES & EDGE
- ALL EXT. WALLS SHALL BE CONTINUOUSLY SHEATHED AND ARE CONSIDERED SHEAR WALLS.
- ALT STAPLE CONNECTION SPEC: 1 3/4 16 GA STAPLES (1/6" CROWN) @ 3" O.C. AT EDGES & @ 6" O.C IN FIELD.

3" O.C. EDGE NAILING

AT DESIGNATED AREAS - FASTEN PANEL EDGES OF WOOD STRUCTURAL WALL SHEATHING TO FRAMING W/ 2 3" x 0.113" NAILS @ 3" O.C. AND 12" O.C. IN THE . FIELD<u>NO STAPLE ALTERNATIVE AVAILABLE</u> AT THIS SPEC. ALL SHEATHING PANELS SHALL BE ORIENTED VERTICALLY (LONG DIRECTION PARALLEI TO STUD) AND INSTALLED FULL HEIGHT OF SHEAR - OR - 2x HORIZONTAL BLOCKING SHALL BE PROVIDED TO SUPPORT UNSUPPORTED PANEL EDGES AND 3" O.C. EDGE FASTENING.

- SEE CONNECTION SPECIFICATIONS CHART FOR STANDARD SHEAR TRANSFER DETAILING, IF ADDITIONAL CAPACITY IS REQUIRED BY DESIGN. IT WILL BE SPECIFICALLY NOTED ON PLAN.
- DESIGN ASSUMES 16" O.C MAX, STUD SPACING, U.N.O.
- ALL STRUCTURAL PANELS ARE TO BE DIRECTLY APPLIED TO STUD FRAMING.
- PRE-MANUFACTURED PANELIZED WALLS: EASTEN TOGETHER END STUDS OF WALL PANELS SHEATHED W/ OSB OR PLYWOOD W/ 3" x 0.120" NAILS @ 4" O.C. (THRU ONE SIDE ONLY)

INDICATES EXTENT OF INT. OSB SHEARWALL, AND/OR 3" O.C. EDGE NAILING

INDICATES HOLDOWN

NON-BEARING HEADER SCHEDULE

| SPAN | 2x4 NON-BEARING PARTITION WALL | 2x6 NON-BEARING PARTITION WALL |
|-------------|-----------------------------------|-----------------------------------|
| UP TO 3'-0" | (I)2x4 FLAT | (I)2x6 FLAT |
| UP TO 6'-0" | (2)2x4 | (3)2×4 |
| UP TO 8'-0" | (2)2×6 | (3)2x6 |
| | | |

NOTES

• ALL NON-BEARING INTERIOR STUD WALLS SHALL BE CONSTRUCTED WITH 2x 'STUD' GRADE MEMBERS SPACED @ 24" O.C. (MAX.)

FLOOR FRAMING

- I-JOISTS SHALL BE DESIGNED BY MANUF, TO MEET OR EXCEED L/480 LIVE LOAD DEFLECTION CRITERIA. (EXCLUDES STONE/MARBLE OR WET BED CONSTRUCTED FLOORS - CONTACT M&K FOR EXCLUDED FLOOR DESIGNS)
- PER THE GUIDELINES OF THE TILE COUNCIL OF NORTH AMERICA (TCNA HANDBOOK), IT SHALL BE THE FLOOR FINISH INSTALLER'S RESPONSIBILITY TO VERIEY THAT THE FINISHES TO BE INSTALLED MATCH THE DESIGN CRITERIA NOTED ABOVE (UNDER "DESIGN
- FLOOR SYSTEMS & SHEATHING HAVE BEEN DESIGNED TO SUPPORT ADDITIONAL DEAD LOAD FROM CERAMIC TILE (EXCLUDING MARBLE OR STONE). HOWEVER, IT SHALL BE THE FLOOR FINISH INSTALLER'S RESPONSIBILITY TO PROVIDE PROPER UNDERLAYMENT, UNGOUPLING MEMBRANE AND MORTAR/GROUT PER THE ASSEMBLY DESIGNATION IN THE TONA HANDBOOK (TILE COUNCIL OF NORTH AMERICA).
- AT I-JOIST FLOORS, PROVIDE I" MIN. OSB RIM BOARD.
- METAL HANGERS SHALL BE SPECIFIED BY MANUFACTURER, U.N.O. I-JOIST SHOP DWGS. SHALL BE SUBMITTED TO ARCH. & ENG. FOR REVIEW AND APPROVAL PRIOR TO FABRICATION OR DELIVERY.
- FLOOR SHEATHING SHALL BE 23/32" A.P.A. RATED 'STURD-I-FLOOR 24" O.C, EXPOSURE I (OR APPROVED EQUAL) WITH TONGUE AND GROOVE EDGES. FASTEN TO FRAMING MEMBERS W GLUE AND
- 2 f" x 0.131" NAILS @ 6"o.c. @ PANEL EDGES & @ 12"o.c. FIELD - 2 🖥 × 0.120" NAILS @ 4" O.C. @ PANEL EDGES \$ @ 8" O.C. FIELD.
- 2 3 × 0.113 NAILS @ 3 O.C. @ PANEL EDGES & @ 6 O.C. IN FIELD

ROOF FRAMING

- ROOF SHEATHING SHALL BE 1/16" A.P.A. RATED SHEATHING 24/16 EXPOSURE I (OR APPROVED EQUAL). FASTEN TO FRAMING MEMBERS - W/ 2 3" × 0.131" NAILS @ 6"o.c. @ PANEL EDGES \$ @ 12" O.C. FIELD.
- W/ 2 🖁 × 0.120" NAILS @ 4"O.C. @ PANEL EDGES & @ 8" O.C. FIELD. - W/ 2 📲 x 0.113" NAILS @ 3"O.C. @ PANEL EDGES € @ 6" O.C. FIELD.
- WITHIN 48" OF ALL ROOF EDGES, RIDGES, & HIPS FASTEN ROOF SHEATHING FIELDS PER EDGE NAILING SPEC
- FASTEN EACH ROOF TRUSS TO TOP PLATE W USP RTTA CLIP (OR APPROVED EQUAL) @ ALL BEARING POINTS. PROVIDE (2) RTTA CLIPS AT 2-PLY GIRDER TRUSSES, (3) RT7A CLIPS AT 3-PLY GIRDER TRUSSES & ROOF BEAMS - AT ALL BEARING POINTS.
- METAL HANGERS SHALL BE SPECIFIED BY THE MANUFACTURER, U.N.O

OF METAL PLATE CONNECTED WOOD TRUSSES."

- ROOF TRUSS SHOP DWGS. SHALL BE SUBMITTED TO ARCH & ENG. FOR REVIEW AND APPROVAL PRIOR TO FABRICATION OR DELIVERY ERECT AND INSTALL ROOF TRUSSES PER WTCA & TPI'S BCSI I "GUIDE TO GOOD PRACTICE FOR HANDLING, INSTALLING & BRACING
- SUPPORT SHORT SPAN ROOF TRUSSES W/2x4 LEDGER FASTENED TO FRAMING w/(2) 3" x 0.120" NAILS @ 16" O.C. (UP TO 7' SPAN)

MEANS & METHODS NOTES

THE STRUCTURE IS DESIGNED TO BE SELF SUPPORTING AND STABLE AFTER THE BUILDING IS FINISHED AND ALL PLAN, DETAIL, AND NOTE SPECIFICATIONS HAVE BEEN COMPLETED. IT IS THE CONTRACTOR'S SOLE RESPONSIBILITY TO DETERMINE THE ERECTION PROCEDURES AND SEQUENCE TO INSURE THE SAFETY OF THE BUILDING AND ITS COMPONENTS DURING CONSTRUCTION. THIS INCLUDES, BUT IS NOT LIMITED TO, THE ADDITION OF NECESSARY SHORING, SHEETING, TEMPORARY BRACING, GUYS, AND TIE-DOWNS. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL SHORING AND BRACING REQUIRED TO STABILIZE AND PROTECT EXISTING AND ADJACENT STRUCTURES AND SYSTEMS DURING COURSE OF DEMOLITION AND CONSTRUCTION OF

STRUCTURAL DESIGN AND SPECIFICATIONS ASSUME THAT ALL SUPPORTING AND NON-SUPPORTING ELEMENTS IN CONTACT WITH FLOOR FRAMING ARE LEVEL, INCLUDING, BUT NOT LIMITED TO; FOUNDATIONS SLABS ON GRADE BEAMS WALLS AND NON-BEARING ELEMENTS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY LEVELNESS AND MAKE ADJUSTMENTS AS NECESSARY, INCLUDING MAY BE WITHIN CONTRACTUAL INDUSTRY OR WARRANTY TO FRANCES

GENERAL STRUCTURAL NOTES

- DESIGN IS BASED ON 2018 NCSBC-RESIDENTIAL CODE & 2018 IRC WITH SOUTH CAROLINA AMENDMENTS
- WOOD FRAME ENGINEERING IS BASED ON NDS, "NATIONAL DESIGN SPECIFICATION FOR WOOD CONSTRUCTION" - LATEST EDITION.

• DESIGN LOADS: LIVE = 20 PSF DEAD = 7 PSF T.C., 10 PSF B.C. ROOF

LOAD DURATION FACTOR = 1.25

FLOOR LIVE = 40 PSF (30 PSF @ SLEEPING AREAS) DEAD = 10 PSF (1-JOISTS)

ADD'L IO PSF @ CERAMIC TILE IN BATHS & LAUND.

2,000 PSF ASSUMED ALLOWABLE BEARING PRESSURE (TO BE VERIFIED BY BUILDER)

GENERAL FRAMING

- ALL TYP, NAIL FASTENER REQUIREMENTS ARE NOTED IN STANDARD CONNECTIONS TABLE (IRC. TABLE R602 3(1)) OR ON PLANS ALL NAILS SPECIFIED ARE MIN DIAMETER AND LENGTH REQUIRED FOR CONNECTION. ALL HANGER NAILS SHALL BE INSTALLED PER MANUFACTURER'S REQUIREMENTS FOR MAX CHARTED CAPACITY. NOTE: HANGERS USE COMMON NAIL DIAMETERS NOT TYPICAL FRAMING GUN NAILS.
- EXT. & INT. BEARING WALLS SHALL BE 2x4 OR 2x6 (AS SHOWN ON PLANS) @ 16" O.C. SPF/SP "STUD" GRADE LUMBER, OR BETTER, U.N.O.. MALLS OVER 12' TALL SHALL BE PER PLAN.
- ALL INTERIOR BEARING WALLS ARE ASSUMED TO BE SHEATHED W. GYP WALL BOARD (ONE SIDE MIN.) OR PROVIDE MID HT. BLOCKING.
- ALL HEADERS, BEAMS & OTHER STRUCTURAL MEMBERS SHALL BE SPRUCE-PINE-FIR #2 (SPF) OR SOUTHERN PINE #2 (SP) LUMBER, OR BETTER. SUPPORT ALL HEADERS/ BEAMS W (1)2x JACK STUD & (1)2x KING STUD, MINIMUM,
- THE NUMBER OF STUDS SPECIFIED AT A SUPPORT INDICATES THE NUMBER OF JACK STUDS REQUIRED, U.N.O.. ALL NON-BEARING INTERIOR STUD WALLS SHALL BE CONSTRUCTED
- WITH 2x 'STUD' GRADE MEMBERS SPACED @ 24" O.C. (MAX., U.N.O.) . HEADERS IN NON-LOAD BEARING WALLS SHALL BE: (1)2x4/6 FLAT @ OPENINGS UP TO 4', (2)2x4/6 FLAT UP TO 8'.
- ALL FRAMING LUMBER SHALL BE DRIED TO 15% MC (KD-15). PENGINEERED LUMBER BEAMS TO MEET OR EXCEED THE FOLLOWING
- 'LVL' Fb=2600 psi; Fv=285 psi; E=2.0x10^6 psi • ENGINEERED LUMBER POSTS TO MEET OR EXCEED THE FOLLOWING:
- 'LVL' Fb=2400 psi; FcII=2500 psi; E=I.8xI0^6 psi FOR 2 & 3 PLY BEAMS OF FOUAL 13/11 MAX WIDTH FASTEN PLIES TOGETHER WITH 3 ROWS OF 3"X0.120" NAILS @ 8" O/C OR 2 ROWS LISP WS35 SCREWS (OR 3/4" TRUSSI OK SCREWS) @ 16" O/C, LISE A APPLY FASTENING AT BOTH FACES FOR 3-PLY CONDITION. LOCATE TOP & BOTTOM NAILS/SCREWS 2" FROM EDGE. SOLID 3 ½" OR 5 ¼" BEAMS ARE ACCEPTABLE USE 2 ROWS OF NAILS FOR 2x6 & 2x8
- FOR 4 PLY BEAMS OF FOUAL 13/4" MAX WIDTH FASTEN PLIES TOGETHER WITH 3 ROWS OF USP WS6 SCREWS (OR 6 3/4" TRUSSLOK SCREWS) @ 16" O/C. USE A MINIMUM OF 4 ROWS FOR BEAM DEPTHS OF 14" OR GREATER, APPLY FASTENING AT BOTH FACES (ONE SIDE ONLY FOR TRUSSLOK SCREWS). LOCATE TOP AND BOTTOM SCREWS 2" FROM EDGE. A SOLID 7" BEAM IS ACCEPTABLE.
- PROVIDE SOLID BLOCKING IN FLOOR SYSTEM UNDER ALL POSTS CONTINUOUS TO END /BEARING. BLOCKING TO MATCH POST ABOVE.
- ALL EXTERIOR 4x4 WOOD POSTS SHALL HAVE USP BCS22-4 CAP & PA44E BASE, U.N.O.
- · CORROSION NOTES
- BUILDER RESPONSIBLE TO DETERMINE CORROSION-RESISTANCE REQUIREMENTS AND COMPATIBILITY OF HARDWARE FASTENERS AND CONNECTORS FOR ENVIRONMENTAL EXPOSURE AND IN CONTACT W/ PRESERVATIVE-TREATED WOOD OF ACTUAL FINAL CONDITIONS AND SOURCED MATERIALS. CONTACT LUMBER & HARDWARE SUPPLIERS TO GOORD.
- ALL FASTENERS AND CONNECTORS EXPOSED TO SALT WATER (WITHIN 300' OF SALT WATER SHORELINE, INCLUDING VENTED SPACES) SHALL BE STAINLESS STEEL.

Briarwood _OT 17

MULHERN+KUL RESIDENTIAL STRUCTURAL ENGINEERIN

C-3825

Julhern+Kulp project numbe 256-22017


SMK roject maj MRG ssue date: 12-09-22


REVISIONS initial:

SMITH DOUGL HOMES

STRUCTURAL NOTES MOD SON GENERAL \geq

I WIND ZONE CAROLINA 120 MPH ON NORTH C







MULHERN+KULP

RESIDENTIAL STRUCTURAL ENGINEERING

SES ENGINEERING, Sup. 165 - Aphron. 8A. 3022

\$776-777-474 - Ambronispecer

NC License # C-3825



Mulhern+Kulp project number: 256-22017

SMK MRG issue date: 12-09-22

REVISIONS:


initial:

SMITH DOUGLAS HOMES

Mono-SLAB FOUNDATION

LAWSON MODEL


120 MPH WIND ZONE NORTH CAROLINA



MONO-SLAB FOUNDATION PLAN

ALL ELEVS. SIM.

SCALE: 1/4"=1'-0" ON 22x34 1/8"=1'-0" ON 11x17



Briarwood LOT 17

REFER TO SO.0 FOR TYPICAL STRUCTURAL NOTES & SCHEDULES

LEGEND

R.T. INDICATES ROOF TRUSSES @ 24" O.C. PER ROOF. MANUF. (TYP. U.N.O.)

O.F. INDICATES TRUSS OVERFRAMING (
24" O.C. (TYP. U.N.O.)

INDICATES 14" DEEP FLOOR I-JOISTS © 24" O.C.
MAX. JOIST SERIES AND SPACING SHALL BE THE
RESPONSIBILITY OF THE MANUFACTURER NOTE: I4" FLOOR TRUSSES @ 24" O.C. MAX. IS AN ACCEPTABLE ALTERNATE FLOOR SYSTEM

INDICATES LOCATIONS OF POTENTIAL TILE FLOOR - JOIST MANUFACTURER SHALL DESIGN FLOOR - SYSTEM FOR ADD'L 10 PSF DEAD LOAD AT THESE


INTERIOR BEARING WALL


• ==== BEARING WALL ABOVE (B.W.A.)

• --- BEAM/HEADER


• JL METAL HANGER

• * INDICATES POST ABOVE (P.A.) PROVIDE SOLID BLOCKING UNDER POST OR JAMB ABOVE.









9/15/23

MULHERN + KULP

RESIDENTIAL STRUCTURAL ENGINERING

SESTIMATION STATEMENTS SANSE

\$770-77-401 v. mathemisticon

NC License # C-3825



Mulhern+Kulp project number:

256-22017 SMK

drawn by: MRG issue date: 12-09-22

REVISIONS:

initial:

SMITH DOUGLAS HOMES

REFER TO SO.0 FOR TYPICAL STRUCTURAL NOTES & SCHEDULES

THIS LEVEL HAS BEEN DESIGNED FOR 9'-1" PLATE HEIGHT

Briarwood LOT 17

F.J. INDICATES I4" DEEP FLOOR I-JOISTS @ 24" O.C.
MAX. JOIST SERIES AND SPACING SHALL BE THE
RESPONSIBILITY OF THE MANUFACTURER
NOTE: I4" FLOOR TRUSESS @ 24" O.C. MAX. IS AN
ACCEPTABLE ALTERNATE FLOOR SYSTEM

INDICATES LOCATIONS OF POTENTIAL TILE FLOOR.

JOIST MANUFACTURER SHALL DESIGN FLOOR

SYSTEM FOR ADD'L 10 PSF DEAD LOAD AT THESE LOCATIONS.

INTERIOR BEARING WALL

• ETTT BEARING WALL ABOVE (B.W.A.)

• — BEAM/HEADER

• JL METAL HANGER

** INDICATES POST ABOVE (P.A.) PROVIDE SOLID BLOCKING UNDER POST OR JAMB ABOVE.

LEGEND

RT. INDICATES ROOF TRUSSES © 24" O.C. PER ROOF. MANUF. (TYP. U.N.O.)


OF INDICATES TRUSS OVERFRAMING (24" O.C. (TYP. U.N.O.)

S3.0

LAWSON MODEL


120 MPH WIND ZONE NORTH CAROLINA

ROOF FRAMING PLAN




TYPICAL SLAB ON GRADE


PERIMETER FOOTING



TYPICAL SLAB ON GRADE


2 PERIMETER FOOTING







TYPICAL SLAB ON GRADE GARAGE 3 PERIMETER FOOTING

TYPICAL SLAB ON GRADE GARAGE











w/ BRICK VENEER

TYPICAL SLAB ON GRADE GARAGE 6 ENTRY @ PERIMETER FOOTING




TYPICAL MONOLITHIC INTERIOR GARAGE FOOTING





OPT. BRICK (SEE ARCH FOR LOCATIONS)

TYPICAL SLAB ON GRADE PERIMETER FOOTING @ PORCH/PATIO



TYPICAL THICKENED SLAB @ 9 INTERIOR BEARING WALL





1/19/24

MULHERN+KULP
RESIDENTIAL STRUCTURAL ENGINEERINS SECSION CONTROL OF STATE OF ST

Mulhern+Kulp project number:


256-22017 SMK MRG issue date: 12-09-22 REVISIONS: initial:

SMITH DOUGLAS HOMES


MODEL FOUNDATION DETAILS AWSON

120 MPH WIND ZONE NORTH CAROLINA


SD1.0



BOTH SIDES OF GARAGE DOOR 120 MPH WIND SPEED (ULT) SCALE: N.T.S.



COVERED PORCH CONNECTION DETAIL



DETAIL @ PENT ROOF

1/19/24

MULHERN+KULP
RESIDENTIAL STRUCTURAL ENSINEERINS

265 Brockside Perkvey, Suite 265 • Agina 2-78-77-4804 • menhanicapasan NC License # C-3825



Mulhern+Kulp project number: 256-22017

SMK drawn by: MRG issue date: 12-09-22

REVISIONS:


initial:


SMITH DOUGLAS HOMES

MODE 120 MPH WIND ZONE NORTH CAROLINA AWSON

FRAMING DETAILS **SD2.0**

Briarwood LOT 17






BRACE GABLE END TRUSSES PER ABOVE DETAIL WHEN GABLE HEIGHT IS LESS THAN 9"-O". "L" BRACES REQUIRED WHERE NOTED BY TRUSS MANUFACTURER.

TYPICAL GABLE END BRACING DETAIL SCALE: NONE READ & GABLE END TRUSS


LETTERED DETAILS ARE TYPICAL FOR THIS HOME & SHALL BE IMPLEMENTED IN ALL APPLICABLE AREAS. THESE DETAILS ARE NOT "CUT" ON THE PLANS.


NUMBERED DETAILS ARE PLAN SPECIFIC AND ARE ONLY REQUIRED WHERE SPECIFICALLY INDICATED ("CUT") ON THE PLANS.



TYPICAL GABLE END BRACING DETAIL SCALE: NONE REQUES 6ABLE END TRUSS REQ'D @ GABLE END TRUSS HEIGHT BETW'N 9'-0" TO 14'-0"

BRACE GABLE END TRUSSES PER ABOVE DETAIL WHEN GABLE HEIGHT EXCEEDS 9'-0'. 'L' BRACES NOT REQUIRED.





TYPICAL SHEAR TRANSFER DETAIL @ EXTERIOR SHEARWALL

Briarwood LOT 17

1/19/24

MULHERN+KULP
RESIDENTIAL STRUCTURAL ENGINEERINS 265 Streeteist Parkvey, Suite 255 - Agina 2-778-777-4874 - methemicalesem NC License # C-3825

Mulhern+Kulp project number: 256-22017

SMK MRG issue date: 12-09-22

REVISIONS:


initial:

SMITH DOUGLAS HOMES

MODE 120 MPH WIND ZONE NORTH CAROLINA FRAMING DETAILS AWSON

SD2.1

72508396 17 BRIARWOOD



BUILT SITE A UFP INDUSTRIES C UFP 0 H LINES: VALLEY Ŧ 67 50. LINE RIDGE sqft AREA: DESIGNER JNN LAYOUT DATE 7/8/24 ROOF ARCH DATE

JOB #: MASTER