

# Mark Morris, P.E.

#126, 1317-M, Summerville, SC 29483

843 209-5784, Fax (866)-213-4614

The truss drawing(s) listed below have been prepared by **Atlantic Building Components** under my direct supervision based on the parameters provided by the truss designers.

AST #: 58496

JOB: 25-3337-F02

JOB NAME: LOT 0.0020 HONEYCUTT HILLS

Wind Code: N/A

Wind Speed: Vult= N/A

Exposure Category: N/A

Mean Roof Height (feet): N/A

These truss designs comply with IRC 2015 as well as IRC 2018.

*21 Truss Design(s)*

Trusses:

F201, F202, F203, F204, F205, F205A, F206, F208, F209, F210, F211, F212, F213, F214, F215, F216, F217, F218, F219, F220, F221



**4/14/2025**

**Mark Morris**

*My license renewal date for the state of North Carolina is 12/31/2025*

***Warning !—Verify design parameters and read notes before use.***

This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI

Job	Truss	Truss Type	Qty	Ply	LOT 0.0020 HONEYCUTT HILLS   380 SHELBY MEADOW LANE ANGIER, NC
25-3337-F02	F201	Floor Supported Gable	1	1	

Job Reference (optional) # 58496

8.630 s Jul 12 2024 MiTek Industries, Inc. Wed Apr 16 09:11:25 2025 Page 1  
ID:gUCksxzC6J7HT2yGkHFINYyiOvf-525wWh?b3d168JgM9GuMEAZq3bUy3gL\_?sEIF7zQCG0

0-1-8

Scale: 3/8"=1'





Plate Offsets (X,Y)-- [8:0-1-8,Edge], [25:0-1-8,Edge], [34:Edge,0-1-8]									
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d		PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.06	Vert(LL)	n/a - n/a	999	MT20 244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.01	Vert(CT)	n/a - n/a	999	
BCLL	0.0	Rep Stress Incr	YES	WB	0.03	Horz(CT)	0.00 18 n/a	n/a	
BCDL	5.0	Code IRC2021/TPI2014		Matrix-SH					Weight: 85 lb FT = 20%F, 11%E

8.630 s Jul 12 2024 MiTek Industries, Inc. Wed Apr 16 09:11:26 2025 Page 1  
ID:gUCksxzC6J7HT2yGkHFINYyiOvf-ZEflk10Dqx9zmTFYjzPbmO5ol?gqo2R7EWzFnazQCG?

1-1-4  
Scale = 1:32.5



<b>LOADING</b> (psf)	<b>SPACING-</b> 1-7-3	<b>CSI.</b>	<b>DEFL.</b> in (loc) l/defl L/d	<b>PLATES</b>	<b>GRIP</b>
TCLL 40.0	Plate Grip DOL 1.00	TC 0.90	Vert(LL) -0.22 19-20 >653 480	MT20	244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.67	Vert(CT) -0.31 19-20 >474 360		
BCLL 0.0	Rep Stress Incr YES	WB 0.36	Horz(CT) 0.02 12 n/a n/a		
BCDL 5.0	Code IRC2021/TPI2014	Matrix-SH		Weight: 102 lb	FT = 20%F, 11%E

<b>BRACING-</b>	
<b>TOP CHORD</b>	Structural wood sheathing directly applied or 2-2-0 oc purlins, except end verticals.
<b>BOT CHORD</b>	Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 16-17.


**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

**TOP CHORD** 23-24=-556/0, 1-24=-555/0, 11-12=-368/0, 1-2=-630/0, 2-3=-1431/0, 3-4=-1431/0, 4-5=-1744/0, 5-6=-1209/0, 6-7=-1209/0, 7-8=-292/27, 8-9=-551/0, 9-10=-729/0, 10-11=-340/0

**BOT CHORD** 21-22=0/1169, 20-21=0/1696, 19-20=0/1661, 18-19=0/1209, 17-18=0/1209, 16-17=-27/292, 15-16=0/774, 14-15=0/774, 13-14=0/664

**WEBS** 7-18=0/345, 8-17=-335/54, 1-22=0/761, 2-22=-702/0, 2-21=0/340, 4-21=-345/0, 5-19=-632/0, 7-17=-1213/0, 8-16=0/411, 9-16=-346/0, 10-13=-422/0, 11-13=0/445


LOAD CASE(S) Standard



**Warning !—Verify design parameters and read notes before use.** This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 Guide to *Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D’Onofrio Drive, Madison, WI 53719.

8.630 s Jul 12 2024 MiTek Industries, Inc. Wed Apr 16 09:11:26 2025 Page 1  
ID:gUCksxzC6J7HT2yGkHFINYyiOvf-ZEflk10DqxzmTFYjzPbmO5op?gso2Q7EWzFnazQCG?

0-9-12  
Scale: 3/8"=1'



LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.1(flat)	TOP CHORD	Structural wood sheathing directly applied or 2-2-0 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.1(flat) *Except*	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing, Except:
	B1: 2x4 SP SS(flat)		6-0-0 oc bracing: 16-17.
WEBS	2x4 SP No.3(flat)		

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD	23-24=-557/0, 1-24=-556/0, 11-12=-362/0, 1-2=-631/0, 2-3=-1433/0, 3-4=-1433/0, 4-5=-1748/0, 5-6=-1216/0, 6-7=-1216/0, 7-8=-301/9, 8-9=-550/0, 9-10=-684/0, 10-11=-263/0
BOT CHORD	21-22=0/1171, 20-21=0/1700, 19-20=0/1666, 18-19=0/1216, 17-18=0/1216, 16-17=-9/301, 15-16=0/754, 14-15=0/754, 13-14=0/593
WEBS	7-18=0/343, 8-17=-320/60, 1-22=0/762, 2-22=-704/0, 2-21=0/342, 4-21=-347/0, 5-19=-627/0, 7-17=-1211/0, 8-16=0/388, 9-16=-323/0, 10-13=-430/0, 11-13=0/393

**NOTES-** (6-7)

- 1) Unbalanced floor live loads have been considered for this design.
- 2) All plates are 3x4 MT20 unless otherwise indicated.
- 3) Refer to girder(s) for truss to truss connections.
- 4) Recommend 2x6 strongbacks, on edge, spaced at 10'-0" o.c. and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
- 5) CAUTION, Do not erect truss backwards.
- 6) Graphical web bracing representation does not depict the size, type or the orientation of the brace on the web. Symbol only indicates that the member must be braced.
- 7) Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.

4/14/2025

**Warning !—Verify design parameters and read notes before use.** This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 Guide to *Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D’Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0020 HONEYCUTT HILLS   380 SHELBY MEADOW LANE ANGIER, NC
25-3337-F02	F204	Floor Supported Gable	1	1	
Job Reference (optional)					# 58496

8.630 s Jul 12 2024 MiTek Industries, Inc. Wed Apr 16 09:11:27 2025 Page 1  
ID:gUCksxzC6J7HT2yGkHFINYjiOvf-1RCgxN1rbEHqNdpkHhxqJbeAmP9RXaxHTAjoJ0zQCG\_




Plate Offsets (X,Y)-- [5:0-1-8,Edge], [6:Edge,0-1-8]									
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d		PLATES GRIP	
TCLL	40.0	Plate Grip DOL	1.00	TC	0.05	Vert(LL)	n/a - n/a	999	MT20 244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.01	Vert(CT)	n/a - n/a	999	
BCLL	0.0	Rep Stress Incr	YES	WB	0.03	Horz(CT)	0.00 4 n/a	n/a	
BCDL	5.0	Code IRC2021/TPI2014		Matrix-P					Weight: 14 lb FT = 20%F, 11%E


LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 1-11-14 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	
OTHERS 2x4 SP No.3(flat)	

REACTIONS. (lb/size) 6=50/1-11-14 (min. 0-1-8), 4=5/1-11-14 (min. 0-1-8), 5=130/1-11-14 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES- (6-7)
- 1) Gable requires continuous bottom chord bearing.
  - 2) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
  - 3) Gable studs spaced at 1-4-0 oc.
  - 4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
  - 5) CAUTION, Do not erect truss backwards.
  - 6) Graphical web bracing representation does not depict the size, type or the orientation of the brace on the web. Symbol only indicates that the member must be braced.
  - 7) Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.

LOAD CASE(S) Standard



4/14/2025

**Warning !—Verify design parameters and read notes before use.** This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

8.630 s Jul 12 2024 MiTek Industries, Inc. Wed Apr 16 09:11:27 2025 Page 1  
ID:gUCksxzC6J7HT2vGkHFINYiOvf-1RCqxN1rbEHqNdpkHhxqJbe QPzUXU4HTAjoJ0zQCG

H | 1-3-0

0-5-15      2-0-0      1-0-3

A horizontal timeline representing the 1990s, from 1990 to 1999. The timeline is marked with vertical lines for each year. Above the timeline, the years are listed in a stylized font: 1-6-0, 4-0-0, 9-1-8, 10-10-7, 10-11-15, 12-11-15, 13-7-9, 14-3-2, 15-7-10, 18-1-10, 20-7-10, 21-8-6. Below the timeline, the years are listed in a stylized font: 1-6-0, 2-6-0, 5-1-8, 1-8-15, 0-1-81-0-0, 1-0-00-1-8, 0-6-2, 0-1-8, 1-4-8, 2-6-0, 2-6-0, 1-0-12.

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.1(flat) *Except* T1: 2x4 SP SS(flat)	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.1(flat) *Except* B2: 2x4 SP SS(flat)	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 17-18.
WEBS	2x4 SP No.3(flat)		


**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

**TOP CHORD**  
26-27=-607/0, 1-27=-806/0, 13-14=-301/0, 1-2=-696/0, 2-3=-1638/0, 3-4=-2047/0,  
4-5=-2047/0, 5-6=-1920/0, 6-7=-1042/0, 7-8=-1042/0, 11-12=-483/0

**BOT CHORD**  
24-25=0/1308, 23-24=0/1934, 22-23=0/1934, 21-22=0/2078, 20-21=0/1565, 19-20=0/1042,  
18-19=0/1042, 16-17=0/482, 15-16=0/465

**WEBS**  
7-20=0/691, 8-19=0/423, 9-18=-324/59, 1-25=0/843, 2-25=-796/0, 2-24=0/429,  
3-24=-386/0, 6-21=0/481, 6-20=-1135/0, 8-18=-1558/0, 9-17=0/485, 11-17=-370/0,  
12-15=-335/0, 13-15=0/312

LOAD CASE(S) Standard




4/14/2025

**Warning !—Verify design parameters and read notes before use.** This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.



Job	Truss	Truss Type	Qty	Ply	LOT 0.0020 HONEYCUTT HILLS   380 SHELBY MEADOW LANE ANGIER, NC
25-3337-F02	F205A	Floor	1	1	
Job Reference (optional)					# 58496

8.630 s Jul 12 2024 MiTek Industries, Inc. Wed Apr 16 09:11:27 2025 Page 1  
ID:gUCksxzC6J7HT2yGkHFINYyiOvf-1RCgxN1rbEHqNdpkHhxqJbe2wPxyXVaHTAjoJ0zQCG\_



1-6-0	4-0-0	6-6-0	7-10-3	8-10-3	9-10-3	11-2-11	13-8-11	14-3-2	15-7-10	18-1-10	20-7-10	21-8-6
1-6-0	2-6-0	2-6-0	1-4-3	1-0-0	1-0-0	1-4-8	2-6-0	0-6-7	1-4-8	2-6-0	2-6-0	1-0-12

Plate Offsets (X,Y)-- [4:0-1-8,Edge], [5:0-1-8,Edge], [25:Edge,0-1-8]															
LOADING (psf)		SPACING- 1-7-3		CSI.		DEFL. in (loc)		l/defl		L/d		PLATES		GRIP	
TCLL	40.0	Plate Grip DOL	1.00	TC	0.55	Vert(LL)	-0.18 20-21	>951	480	MT20	244/190				
TCDL	10.0	Lumber DOL	1.00	BC	0.93	Vert(CT)	-0.24 20-21	>701	360						
BCLL	0.0	Rep Stress Incr	YES	WB	0.37	Horz(CT)	0.02 16	n/a	n/a						
BCDL	5.0	Code IRC2021/TPI2014		Matrix-SH								Weight: 111 lb		FT = 20%F, 11%E	


<b>LUMBER-</b>		<b>BRACING-</b>	
TOP CHORD	2x4 SP No.1(flat)	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.1(flat)	BOT CHORD	Rigid ceiling directly applied or 2-2-0 oc bracing.
WEBS	2x4 SP No.3(flat)		

**REACTIONS.** (lb/size) 25=563/0-3-6 (min. 0-1-8), 12=218/Mechanical, 16=1100/0-3-8 (min. 0-1-8)  
Max Uplift12=-1(LC 3)  
Max Grav25=571(LC 3), 12=279(LC 4), 16=1100(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 25-26=-568/0, 1-26=-567/0, 11-12=-277/2, 1-2=-642/0, 2-3=-1492/0, 3-4=-1768/0,  
4-5=-1589/0, 5-6=-910/0, 6-7=0/500, 7-8=-73/410, 8-9=-73/410, 9-10=-405/139  
BOT CHORD 23-24=0/1195, 22-23=0/1780, 21-22=0/1780, 20-21=0/1589, 19-20=0/1589, 18-19=0/1589,  
17-18=-21/387, 16-17=-741/0, 15-16=-724/0, 14-15=-254/365, 13-14=-50/420  
WEBS 5-19=0/271, 7-16=-1083/0, 1-24=0/776, 2-24=-721/0, 2-23=0/386, 3-23=-375/0,  
4-21=-9/308, 5-18=-891/0, 6-18=0/699, 6-17=-880/0, 7-17=0/672, 7-15=0/517,  
9-15=-482/0, 10-13=-302/48, 11-13=-20/281

- NOTES-** (7-8)
- 1) Unbalanced floor live loads have been considered for this design.
  - 2) All plates are 3x4 MT20 unless otherwise indicated.
  - 3) Refer to girder(s) for truss to truss connections.
  - 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 1 lb uplift at joint 12.
  - 5) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
  - 6) CAUTION, Do not erect truss backwards.
  - 7) Graphical web bracing representation does not depict the size, type or the orientation of the brace on the web. Symbol only indicates that the member must be braced.
  - 8) Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.

**LOAD CASE(S)** Standard




4/14/2025

**Warning !—Verify design parameters and read notes before use.** This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

8.630 s Jul 12 2024 MiTek Industries, Inc. Wed Apr 16 09:11:28 2025 Page 1  
ID:gUCksxzC6J7HT2yGkHFINYyiOvf-Vdm29j2TMYPh?nOxrOS3rpBB1pGGGyHQhgSMrSzQCFz

0-7-40-1-8  
Scale = 1:36.3



<b>LOADING</b> (psf)	<b>SPACING-</b> 1-7-3	<b>CSI.</b>	<b>DEFL.</b> in (loc)	<b>l/defl</b>	<b>L/d</b>	<b>PLATES</b>	<b>GRIP</b>
TCLL 40.0	Plate Grip DOL 1.00	TC 0.65	Vert(LL) -0.19 22-23	>768	480	MT20	244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.99	Vert(CT) -0.25 22-23	>566	360		
BCLL 0.0	Rep Stress Incr YES	WB 0.34	Horz(CT) 0.03 13	n/a	n/a		
BCDL 5.0	Code IRC2021/TPI2014	Matrix-SH				Weight: 112 lb	FT = 20%F, 11%E

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 2-2-0 oc bracing.

**NOTES-** (5-6)

- 1) Unbalanced floor live loads have been considered for this design.
- 2) All plates are 3x4 MT20 unless otherwise indicated.
- 3) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
- 4) CAUTION, Do not erect truss backwards.
- 5) Graphical web bracing representation does not depict the size, type or the orientation of the brace on the web. Symbol only indicates that the member must be braced.
- 6) Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.


4/14/2025

**Warning !—Verify design parameters and read notes before use.** This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.



8.630 s Jul 12 2024 MiTek Industries, Inc. Wed Apr 16 09:11:28 2025 Page 1  
ID:gUCksxzC6J7HT2yGkHFINYyiOvf-Vdm29j2TMYPh?nOxrOS3rpBlvpScGzYQhgSMrSzQCFz

0-7-8  
Scale: 3/4"=1'



<b>BRACING-</b>	
<b>TOP CHORD</b>	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
<b>BOT CHORD</b>	Rigid ceiling directly applied or 10-0-0 oc bracing.

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 12-13=-420/0, 1-13=-419/0, 6-7=-429/0, 1-2=-451/0, 2-3=-940/0, 3-4=-902/0, 4-5=-902/0, 5-6=-261/0  
 BOT CHORD 10-11=0/837, 9-10=0/1019, 8-9=0/677  
 WEBS 1-11=0/544, 2-11=-502/0, 5-9=0/287, 5-8=-541/0, 6-8=0/447

**NOTES-** (4-5)

- 1) All plates are 3x4 MT20 unless otherwise indicated.
- 2) Recommend 2x6 strongbacks, on edge, spaced at 10-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
- 3) CAUTION, Do not erect truss backwards.
- 4) Graphical web bracing representation does not depict the size, type or the orientation of the brace on the web. Symbol only indicates that the member must be braced.
- 5) Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.

LOAD CASE(S) Standard




4/14/2025

**Warning !—Verify design parameters and read notes before use.** This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D’Onofrio Drive, Madison, WI 53719.

8.630 s Jul 12 2024 MiTek Industries, Inc. Wed Apr 16 09:11:29 2025 Page 1  
ID:gUCksxzC6J7HT2yGkHFINYyiOvf-zpKQM3257sXYdwz7O6zIO0jNGDd2?PRZwUCvNvzQCFy

0-8-4 0-1-8  
Scale = 1:29.9



**LUMBER-**

TOP CHORD 2x4 SP No.1(flat)  
BOT CHORD 2x4 SP No.1(flat)  
WEBS 2x4 SP No.3(flat)

## BRACING-

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 2-2-0 oc bracing: 17-18 6-0-0 oc bracing: 15-16, 14-15.

**REACTIONS.** (lb/size) 22=535/0-3-6 (min. 0-1-8), 15=752/0-3-8 (min. 0-1-8), 11=281/0-3-8 (min. 0-1-8)  
Max Grav 22=539(LC 3), 15=752(LC 1), 11=304(LC 7)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD	22-23=-537/0, 1-23=-536/0, 1-2=-600/0, 2-3=-1375/0, 3-4=-1375/0, 4-5=-1575/0, 5-6=-1328/0, 6-7=-585/0, 7-8=-437/0, 8-9=-416/0
BOT CHORD	20-21=0/1115, 19-20=0/1630, 18-19=0/1328, 17-18=0/1328, 16-17=0/1328, 15-16=-109/284, 14-15=-102/289, 13-14=0/569, 12-13=0/569
WEBS	5-18=-267/0, 6-17=0/307, 7-15=-667/0, 1-21=0/725, 2-21=-671/0, 2-20=0/338, 4-20=-331/0, 5-19=0/345, 6-16=-979/0, 7-16=0/559, 7-14=0/289, 8-14=-262/0, 9-11=-383/0

**NOTES- (5-6)**

- 1) Unbalanced floor live loads have been considered for this design.
- 2) All plates are 3x4 MT20 unless otherwise indicated.
- 3) Recommend 2x6 strongbacks, on edge, spaced at 10-0" o.c. and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
- 4) CAUTION, Do not erect truss backwards.
- 5) Graphical web bracing representation does not depict the size, type or the orientation of the brace on the web. Symbol only indicates that the member must be braced.
- 6) Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.

LOAD CASE(S) Standard




4/14/2025

**Warning !—Verify design parameters and read notes before use.** This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

8.630 s Jul 12 2024 MiTek Industries, Inc. Wed Apr 16 09:11:29 2025 Page 1  
ID:gUCksxzC6J7HT2yGkHFINYyiOvf-zpKQM3257sXYdwz7O6zIO0iV Dru?UNZwUCvNvzQCFy

Scale = 1:19.8



<b>BRACING-</b>	
<b>TOP CHORD</b>	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
<b>BOT CHORD</b>	Rigid ceiling directly applied or 10-0-0 oc bracing.

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

LOAD CASE(S) Standard



4/14/2025

**Warning !—Verify design parameters and read notes before use.** This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0020 HONEYCUTT HILLS   380 SHELBY MEADOW LANE ANGIER, NC
25-3337-F02	F211	FLOOR GIRDER	1	1	

Job Reference (optional) # 58496

8.630 s Jul 12 2024 MiTek Industries, Inc. Wed Apr 16 09:11:30 2025 Page 1

ID:gUCksxzC6J7HT2yGkHFJNYyiOvf-R?uoZP3ju9gPE4YJypUxxEGWnc8MksTj98xSvLzQCFx




Plate Offsets (X,Y)-- [6:Edge,0-1-8]

LOADING (psf)	SPACING-	1-7-3	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.77	Vert(LL)	-0.00	5	>999	480	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.25	Vert(CT)	-0.01	4-5	>999	360		
BCLL 0.0	Rep Stress Incr	NO	WB 0.36	Horz(CT)	0.00	4	n/a	n/a		
BCDL 5.0	Code IRC2021/TPI2014		Matrix-P							
									Weight: 28 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 3-10-13 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (lb/size) 6=1059/Mechanical, 4=803/1-4-13 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


TOP CHORD	1-6=-1053/0, 3-4=0/283, 1-7=-599/0, 7-8=-599/0, 2-8=-599/0
BOT CHORD	4-5=0/1127
WEBS	1-5=0/735, 2-5=-671/0, 2-4=-1558/0

NOTES- (6-7)

- 1) Refer to girder(s) for truss to truss connections.
- 2) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
- 3) Use Simpson Strong-Tie THA422 (6-16d Girder, 6-10d Truss) or equivalent spaced at 1-7-3 oc max. starting at 0-10-3 from the left end to 2-5-6 to connect truss(es) F216 (1 ply 2x4 SP) to back face of top chord.
- 4) Fill all nail holes where hanger is in contact with lumber.
- 5) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).
- 6) Graphical web bracing representation does not depict the size, type or the orientation of the brace on the web. Symbol only indicates that the member must be braced.
- 7) Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.

LOAD CASE(S) Standard

- 1) Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00
- Uniform Loads (plf)
- Vert: 4-6=-8, 1-3=-80
- Concentrated Loads (lb)
- Vert: 7=-772(B) 8=-769(B)



4/14/2025

**Warning !—Verify design parameters and read notes before use.** This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0020 HONEYCUTT HILLS   380 SHELBY MEADOW LANE ANGIER, NC
25-3337-F02	F212	Floor Supported Gable	1	1	Job Reference (optional) # 58496

8.630 s Jul 12 2024 MiTek Industries, Inc. Wed Apr 16 09:11:30 2025 Page 1  
ID:gUCksxzC6J7HT2yGkHFINYiOvf-R?uoZP3ju9gPE4YJypUXxEGhqcB7kxbj98xSvLzQCFx

0-1-8

Scale = 1:37.9




Plate Offsets (X,Y)-- [11:0-1-8,Edge], [32:0-1-8,Edge], [40:Edge,0-1-8]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.06	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.01	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0	Rep Stress Incr	YES	WB 0.03	Horz(CT)	0.00	21	n/a	n/a		
BCDL 5.0	Code IRC2021/TPI2014		Matrix-SH							
									Weight: 100 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	
OTHERS 2x4 SP No.3(flat)	

**REACTIONS.** All bearings 23-3-4.  
(lb) - Max Grav All reactions 250 lb or less at joint(s) 40, 21, 39, 38, 37, 36, 35, 34, 33, 32, 31, 30, 28, 27, 26, 25, 24, 23, 22

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-** (7-8)
- 1) All plates are 1.5x3 MT20 unless otherwise indicated.
  - 2) Gable requires continuous bottom chord bearing.
  - 3) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
  - 4) Gable studs spaced at 1-4-0 oc.
  - 5) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
  - 6) CAUTION, Do not erect truss backwards.
  - 7) Graphical web bracing representation does not depict the size, type or the orientation of the brace on the web. Symbol only indicates that the member must be braced.
  - 8) Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.

**LOAD CASE(S)** Standard



4/14/2025

**Warning !—Verify design parameters and read notes before use.** This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0020 HONEYCUTT HILLS   380 SHELBY MEADOW LANE ANGIER, NC
25-3337-F02	F213	FLOOR	3	1	
Job Reference (optional)					# 58496

8.630 s Jul 12 2024 MiTek Industries, Inc. Wed Apr 16 09:11:31 2025 Page 1  
ID:gUCksxzC6J7HT2yGkHFINYjiOvf-vCSBnl4MfToGsE7WWX?mTRop900fTCNsOoh0RnzQCFW




Plate Offsets (X,Y)-- [1:0-1-8,0-0-8], [14:0-3-0,Edge], [21:0-3-0,0-0-0]					
<b>LOADING</b> (psf)	<b>SPACING-</b>	<b>CSI.</b>	<b>DEFL.</b>	<b>PLATES</b>	<b>GRIP</b>
TCLL 40.0	1-7-3	TC 0.21	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.00	BC 0.63	Vert(LL) -0.42 21-22 >653 480	MT20HS	187/143
BCLL 0.0	Lumber DOL 1.00	WB 0.83	Vert(CT) -0.58 21-22 >475 360		
BCDL 5.0	Rep Stress Incr YES	Matrix-SH	Horz(CT) 0.07 15 n/a n/a		
	Code IRC2021/TPI2014			Weight: 180 lb	FT = 20%F, 11%E

<b>LUMBER-</b>	<b>BRACING-</b>
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

**REACTIONS.** (lb/size) 28=1013/0-3-6 (min. 0-1-8), 15=1013/0-3-8 (min. 0-1-8)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-28=-996/0, 14-15=-997/0, 1-2=-1501/0, 2-3=-3651/0, 3-4=-3651/0, 4-5=-5118/0, 5-6=-5118/0, 6-7=-5975/0, 7-8=-6248/0, 8-9=-5975/0, 9-10=-5118/0, 10-11=-5118/0, 11-12=-3651/0, 12-13=-3651/0, 13-14=-1485/0

BOT CHORD 26-27=0/2697, 25-26=0/4521, 24-25=0/5691, 23-24=0/5691, 22-23=0/6248, 21-22=0/6248, 20-21=0/6248, 19-20=0/5691, 18-19=0/5691, 17-18=0/4521, 16-17=0/2697

WEBS 7-23=-678/135, 6-23=0/527, 6-25=-711/0, 4-25=0/740, 4-26=-1061/0, 2-26=0/1163, 2-27=-1485/0, 1-27=0/1743, 8-20=-678/135, 9-20=0/527, 9-18=-711/0, 11-18=0/740, 11-17=-1061/0, 13-17=0/1163, 13-16=-1503/0, 14-16=0/1735

- NOTES-** (6-7)
- 1) Unbalanced floor live loads have been considered for this design.
  - 2) All plates are MT20 plates unless otherwise indicated.
  - 3) All plates are 3x6 MT20 unless otherwise indicated.
  - 4) Required 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
  - 5) CAUTION, Do not erect truss backwards.
  - 6) Graphical web bracing representation does not depict the size, type or the orientation of the brace on the web. Symbol only indicates that the member must be braced.
  - 7) Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.

**LOAD CASE(S)** Standard



4/14/2025

**Warning !—Verify design parameters and read notes before use.** This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.



Job	Truss	Truss Type	Qty	Ply	LOT 0.0020 HONEYCUTT HILLS   380 SHELBY MEADOW LANE ANGIER, NC
25-3337-F02	F214	FLOOR	8	1	
Job Reference (optional)					# 58496

8.630 s Jul 12 2024 MiTek Industries, Inc. Wed Apr 16 09:11:31 2025 Page 1  
ID:gUCksxzC6J7HT2yGkHFINYyiOvf-vCSBn4MfToGsE7WWX?mTRohZ0RCTDWsOoh0RnzQCFw




Plate Offsets (X,Y)-- [1:Edge,0-1-8], [7:0-1-8,Edge], [8:0-1-8,Edge], [20:0-3-0,0-0-0]					
<b>LOADING</b> (psf)		<b>SPACING-</b>		<b>CSI.</b>	
TCLL 40.0		1-7-3		TC 0.76	
TCDL 10.0		Plate Grip DOL 1.00		BC 0.40	
BCLL 0.0		Lumber DOL 1.00		WB 0.76	
BCDL 5.0		Rep Stress Incr YES		Matrix-SH	
		Code IRC2021/TPI2014			
				<b>DEFL.</b>	
				in (loc) l/defl L/d	
				Vert(LL) -0.50 20-21 >548 480	
				Vert(CT) -0.68 20-21 >399 360	
				Horz(CT) 0.05 14 n/a n/a	
				<b>PLATES</b>	
				<b>GRIP</b>	
				MT20 244/190	
				MT20HS 187/143	
				Weight: 147 lb FT = 20%F, 11%E	

<b>LUMBER-</b>		<b>BRACING-</b>	
TOP CHORD 2x4 SP No.1(flat)		TOP CHORD Structural wood sheathing directly applied or 4-5-11 oc purlins, except end verticals.	
BOT CHORD 2x4 SP SS(flat)		BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.	
WEBS 2x4 SP No.3(flat)			

**REACTIONS.** (lb/size) 27=995/0-3-6 (min. 0-1-8), 14=1000/Mechanical

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


**TOP CHORD** 27-28=-978/0, 1-28=-977/0, 13-14=-984/0, 1-2=-1379/0, 2-3=-3366/0, 3-4=-3366/0, 4-5=-4723/0, 5-6=-4723/0, 6-7=-5476/0, 7-8=-5728/0, 8-9=-5411/0, 9-10=-4584/0, 10-11=-4584/0, 11-12=-3122/0, 12-13=-1131/0

**BOT CHORD** 25-26=0/2500, 24-25=0/4178, 23-24=0/5235, 22-23=0/5235, 21-22=0/5728, 20-21=0/5728, 19-20=0/5728, 18-19=0/5131, 17-18=0/5131, 16-17=0/3948, 15-16=0/2272

**WEBS** 7-21=-259/279, 8-20=-234/305, 7-22=-675/158, 6-22=0/437, 6-24=-651/0, 4-24=0/691, 4-25=-1013/0, 2-25=0/1081, 2-26=-1423/0, 1-26=0/1588, 8-19=-727/102, 9-19=0/468, 9-17=-682/0, 11-17=0/794, 11-16=-1049/0, 12-16=0/1079, 12-15=-1450/0, 13-15=0/1448

- NOTES-** (7-8)
- 1) Unbalanced floor live loads have been considered for this design.
  - 2) All plates are MT20 plates unless otherwise indicated.
  - 3) All plates are 3x6 MT20 unless otherwise indicated.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) Required 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
  - 6) CAUTION, Do not erect truss backwards.
  - 7) Graphical web bracing representation does not depict the size, type or the orientation of the brace on the web. Symbol only indicates that the member must be braced.
  - 8) Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.

**LOAD CASE(S)** Standard




4/14/2025

**Warning !—Verify design parameters and read notes before use.** This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0020 HONEYCUTT HILLS   380 SHELBY MEADOW LANE ANGIER, NC
25-3337-F02	F215	FLOOR GIRDER	1	2	
Job Reference (optional)					# 58496

8.630 s Jul 12 2024 MiTek Industries, Inc. Wed Apr 16 09:11:31 2025 Page 1  
ID:gUCksxzC6J7HT2yGkHFINYyiOvf-vCSbnI4MfToGsE7WWX?mTRojp0MeTFusOoh0RnzQCFw



LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.62	Vert(LL) -0.45	20	>614	480	MT20	244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.76	Vert(CT) -0.62	19-20	>444	360	MT20HS	187/143
BCLL 0.0	Rep Stress Incr NO	WB 0.60	Horz(CT) 0.08	14	n/a	n/a		
BCDL 5.0	Code IRC2021/TPI2014	Matrix-SH						
							Weight: 236 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP SS(flat) *Except*	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
B2: 2x4 SP No.1(flat)	
WEBS 2x4 SP No.3(flat)	

REACTIONS. (lb/size) 26=1173/0-3-6 (min. 0-1-8), 14=1843/0-3-8 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 26-27=-1167/0, 1-27=-1165/0, 1-2=-1569/0, 2-3=-3885/0, 3-4=-3885/0, 4-5=-5599/0, 5-6=-5599/0, 6-7=-6755/0, 7-8=-7372/0, 8-9=-7494/0, 9-10=-7137/0, 10-11=-6133/0, 11-12=-4018/0

BOT CHORD 24-25=0/2839, 23-24=0/4880, 22-23=0/6279, 21-22=0/7372, 20-21=0/7372, 19-20=0/7372, 18-19=0/7471, 17-18=0/7471, 16-17=0/6785, 15-16=0/6133, 14-15=0/2068

WEBS 11-16=0/438, 7-21=0/406, 8-20=-378/2, 7-22=-1118/0, 6-22=0/778, 6-23=-885/0, 4-23=0/936, 4-24=-1270/0, 2-24=0/1335, 2-25=-1652/0, 1-25=0/1845, 8-19=-150/601, 9-17=-434/0, 10-17=0/458, 10-16=-782/0, 11-15=-2654/0, 12-15=0/2537, 12-14=-2751/0

- NOTES- (10-11)
- 1) Fasten trusses together to act as a single unit as per standard industry detail, or loads are to be evenly applied to all plies.
  - 2) Unbalanced floor live loads have been considered for this design.
  - 3) All plates are MT20 plates unless otherwise indicated.
  - 4) All plates are 3x4 MT20 unless otherwise indicated.
  - 5) Required 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
  - 6) CAUTION, Do not erect truss backwards.
  - 7) Use Simpson Strong-Tie THA422 (Single Chord Girder) or equivalent at 19-4-2 from the left end to connect truss(es) F211 (1 ply 2x4 SP) to back face of top chord.
  - 8) Fill all nail holes where hanger is in contact with lumber.
  - 9) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).
  - 10) Graphical web bracing representation does not depict the size, type or the orientation of the brace on the web. Symbol only indicates that the member must be braced.
  - 11) Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.

LOAD CASE(S) Standard

1) Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00

Uniform Loads (plf)

Vert: 14-26=-8, 1-13=-80

Concentrated Loads (lb)

Vert: 11=-996(B)




4/14/2025

**Warning !—Verify design parameters and read notes before use.** This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0020 HONEYCUTT HILLS   380 SHELBY MEADOW LANE ANGIER, NC
25-3337-F02	F216	Floor	2	1	
Job Reference (optional)					# 58496

8.630 s Jul 12 2024 MiTek Industries, Inc. Wed Apr 16 09:11:32 2025 Page 1  
ID:gUCksxzC6J7HT2yGkHFINYiOvf-OO0Z\_55\_Qnw6U0ii4EW?0flqWQfDCKp0cSQZ\_DzQCFv



LOADING (psf)	SPACING-	1-7-3	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.88	Vert(LL)	-0.40 18-19	>575	480	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.93	Vert(CT)	-0.54 18-19	>418	360	MT20HS	187/143
BCLL 0.0	Rep Stress Incr	YES	WB 0.50	Horz(CT)	0.06 13	n/a	n/a		
BCDL 5.0	Code IRC2021/TPI2014		Matrix-SH						
									Weight: 97 lb FT = 20%F, 11%E

<b>LUMBER-</b>		<b>BRACING-</b>	
TOP CHORD	2x4 SP No.1(flat)	TOP CHORD	Structural wood sheathing directly applied or 2-2-0 oc purlins, except end verticals.
BOT CHORD	2x4 SP SS(flat) *Except*	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing, Except:
	B2: 2x4 SP No.1(flat)		2-2-0 oc bracing: 19-20.
WEBS	2x4 SP No.3(flat)		

**REACTIONS.** (lb/size) 23=828/0-3-6 (min. 0-1-8), 13=833/Mechanical

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


TOP CHORD 2-3=-1336/0, 3-4=-2669/0, 4-5=-3450/0, 5-6=-3738/0, 6-7=-3556/0, 7-8=-3556/0, 8-9=-2838/0, 9-10=-2838/0, 10-11=-1514/0

BOT CHORD 22-23=0/534, 21-22=0/2092, 20-21=0/3450, 19-20=0/3450, 18-19=0/3450, 17-18=0/3812, 16-17=0/3812, 15-16=0/3296, 14-15=0/2268, 13-14=0/736

WEBS 4-20=0/378, 5-19=-352/0, 4-21=-1051/0, 3-21=0/751, 3-22=-984/0, 2-22=0/1044, 2-23=-1025/0, 5-18=-125/535, 6-16=-333/0, 8-16=0/339, 8-15=-584/0, 10-15=0/728, 10-14=-982/0, 11-14=0/1012, 11-13=-1104/0

- NOTES-** (7-8)
- 1) Unbalanced floor live loads have been considered for this design.
  - 2) All plates are MT20 plates unless otherwise indicated.
  - 3) All plates are 3x4 MT20 unless otherwise indicated.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
  - 6) CAUTION, Do not erect truss backwards.
  - 7) Graphical web bracing representation does not depict the size, type or the orientation of the brace on the web. Symbol only indicates that the member must be braced.
  - 8) Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.

**LOAD CASE(S)** Standard



4/14/2025

**Warning !—Verify design parameters and read notes before use.** This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0020 HONEYCUTT HILLS   380 SHELBY MEADOW LANE ANGIER, NC
25-3337-F02	F217	Floor	4	1	
Job Reference (optional)					# 58496

8.630 s Jul 12 2024 MiTek Industries, Inc. Wed Apr 16 09:11:32 2025 Page 1  
ID:gUCksxzC6J7HT2yGkHFINYjiOvf-OO0Z\_55\_Qnw6U0ii4EW?0fLpIQfCkg0cSQZ\_DzQCfV




Plate Offsets (X,Y)-- [4:0-1-8,Edge], [5:0-1-8,Edge], [23:Edge,0-3-0]										
LOADING (psf)		SPACING- 1-7-3		CSI.		DEFL. in (loc) l/defl L/d		PLATES GRIP		
TCLL	40.0	Plate Grip DOL	1.00	TC	0.93	Vert(LL)	-0.42 18-19 >550	480	MT20	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.96	Vert(CT)	-0.58 18-19 >400	360	MT20HS	187/143
BCLL	0.0	Rep Stress Incr	YES	WB	0.51	Horz(CT)	0.07 13 n/a	n/a		
BCDL	5.0	Code IRC2021/TPI2014		Matrix-SH					Weight: 98 lb	FT = 20%F, 11%E


LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP SS(flat) *Except* B2: 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 2-2-0 oc bracing: 19-20.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (lb/size) 23=841/0-3-6 (min. 0-1-8), 13=846/0-3-8 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-1359/0, 3-4=-2723/0, 4-5=-3533/0, 5-6=-3850/0, 6-7=-3699/0, 7-8=-3699/0, 8-9=-3013/0, 9-10=-3013/0, 10-11=-1720/0  
BOT CHORD 22-23=0/543, 21-22=0/2129, 20-21=0/3533, 19-20=0/3533, 18-19=0/3533, 17-18=0/3941, 16-17=0/3941, 15-16=0/3453, 14-15=0/2459, 13-14=0/956  
WEBS 4-20=0/393, 5-19=-366/0, 4-21=-1085/0, 3-21=0/773, 3-22=-1001/0, 2-22=0/1063, 2-23=-1042/0, 5-18=-111/569, 6-16=-315/0, 8-16=0/320, 8-15=-563/0, 10-15=0/707, 10-14=-962/0, 11-14=0/995, 11-13=-1255/0

- NOTES- (6-7)
- 1) Unbalanced floor live loads have been considered for this design.
  - 2) All plates are MT20 plates unless otherwise indicated.
  - 3) All plates are 3x4 MT20 unless otherwise indicated.
  - 4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
  - 5) CAUTION, Do not erect truss backwards.
  - 6) Graphical web bracing representation does not depict the size, type or the orientation of the brace on the web. Symbol only indicates that the member must be braced.
  - 7) Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.

LOAD CASE(S) Standard




4/14/2025

**Warning !—Verify design parameters and read notes before use.** This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0020 HONEYCUTT HILLS   380 SHELBY MEADOW LANE ANGIER, NC
25-3337-F02	F218	Floor	13	1	
Job Reference (optional)					# 58496

8.630 s Jul 12 2024 MiTek Industries, Inc. Wed Apr 16 09:11:32 2025 Page 1  
ID:gUCksxzC6J7HT2yGkHFINYyiOvf-000Z\_55\_Qnw6UOIi4EW?0fLzEQlbCmS0cSQZ\_DzQCFv



LOADING (psf)	SPACING-	1-7-3	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.26	Vert(LL)	-0.09 11-12	>999	480	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.52	Vert(CT)	-0.12 11-12	>999	360		
BCLL 0.0	Rep Stress Incr	YES	WB 0.33	Horz(CT)	0.03 9	n/a	n/a		
BCDL 5.0	Code IRC2021/TPI2014		Matrix-SH						
									Weight: 70 lb FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (lb/size) 16=590/0-3-6 (min. 0-1-8), 9=595/0-3-8 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


TOP CHORD 2-3=-906/0, 3-4=-1665/0, 4-5=-1910/0, 5-6=-1665/0, 6-7=-906/0

BOT CHORD 15-16=0/376, 14-15=0/1413, 13-14=0/1910, 12-13=0/1910, 11-12=0/1910, 10-11=0/1413, 9-10=0/376

WEBS 4-14=-428/0, 3-14=0/355, 3-15=-660/0, 2-15=0/690, 2-16=-720/0, 5-11=-428/0, 6-11=0/355, 6-10=-660/0, 7-10=0/690, 7-9=-717/0

- NOTES- (5-6)
- 1) Unbalanced floor live loads have been considered for this design.
  - 2) All plates are 3x4 MT20 unless otherwise indicated.
  - 3) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
  - 4) CAUTION. Do not erect truss backwards.
  - 5) Graphical web bracing representation does not depict the size, type or the orientation of the brace on the web. Symbol only indicates that the member must be braced.
  - 6) Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.

LOAD CASE(S) Standard



4/14/2025

**Warning !—Verify design parameters and read notes before use.** This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0020 HONEYCUTT HILLS   380 SHELBY MEADOW LANE ANGIER, NC
25-3337-F02	F219	Floor Supported Gable	1	1	Job Reference (optional) # 58496

8.630 s Jul 12 2024 MiTek Industries, Inc. Wed Apr 16 09:11:33 2025 Page 1  
ID:gUCksxzC6J7HT2yGkHFINYyiOvf-saaxCQ5cB42z5YHudy2EYsuC2qCkxIL9r6A7WgzQCfU

0-1-8

Scale = 1:22.3




Plate Offsets (X,Y)-- [7:0-1-8,Edge], [18:0-1-8,Edge], [23:Edge,0-1-8]									
<b>LOADING</b> (psf)		<b>SPACING-</b>		<b>CSI.</b>		<b>DEFL.</b>		<b>PLATES</b>	
TCLL	40.0	2-0-0	Plate Grip DOL	1.00	TC	0.06	in (loc)	l/defl	L/d
TCDL	10.0	Lumber DOL	1.00	BC	0.01	Vert(LL)	n/a	-	n/a
BCLL	0.0	Rep Stress Incr	YES	WB	0.03	Vert(CT)	n/a	-	n/a
BCDL	5.0	Code IRC2021/TPI2014		Matrix-SH		Horz(CT)	0.00	13	n/a
								Weight: 62 lb	FT = 20%F, 11%E

<b>LUMBER-</b>		<b>BRACING-</b>	
TOP CHORD	2x4 SP No.1(flat)	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.1(flat)	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3(flat)		
OTHERS	2x4 SP No.3(flat)		

**REACTIONS.** All bearings 13-9-6.  
(lb) - Max Grav All reactions 250 lb or less at joint(s) 23, 13, 22, 21, 20, 19, 18, 17, 16, 15, 14

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-** (7-8)
- 1) All plates are 1.5x3 MT20 unless otherwise indicated.
  - 2) Gable requires continuous bottom chord bearing.
  - 3) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
  - 4) Gable studs spaced at 1-4-0 oc.
  - 5) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
  - 6) CAUTION, Do not erect truss backwards.
  - 7) Graphical web bracing representation does not depict the size, type or the orientation of the brace on the web. Symbol only indicates that the member must be braced.
  - 8) Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.

**LOAD CASE(S)** Standard



4/14/2025


**Warning !—Verify design parameters and read notes before use.** This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.



8.630 s Jul 12 2024 MiTek Industries, Inc. Wed Apr 16 09:11:33 2025 Page 1  
ID:gUCksxzc6J7HT2yGkHFINYyiOvf-saaxCQ5cB42z5YHudy2EYsu6Tq?pxB79r6A7WgzQCFu

0-3-10

Scale = 1:29.8



**LUMBER-**

TOP CHORD 2x4 SP No.1(flat)  
BOT CHORD 2x4 SP No.1(flat)  
WEBS 2x4 SP No.3(flat)

**BRACING-**

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (lb/size) 24=807/0-3-8 (min. 0-1-8), 14=807/Mechanical

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD	2-3=-1153/0, 3-4=-2517/0, 4-5=-2517/0, 5-6=-3276/0, 6-7=-3528/0, 7-8=-3276/0, 8-9=-2517/0, 9-10=-2517/0, 10-11=-2517/0, 11-12=-1153/0
BOT CHORD	23-24=0/357, 22-23=0/1927, 21-22=0/3018, 20-21=0/3018, 19-20=0/3528, 18-19=0/3528, 17-18=0/3528, 16-17=0/3018, 15-16=0/1927, 14-15=0/357
WEBS	6-20=-540/18, 5-20=0/429, 5-22=-640/0, 3-22=0/753, 3-23=-1007/0, 2-23=0/1036, 2-24=-942/0, 7-17=-540/18, 8-17=0/429, 8-16=-640/0, 11-16=0/753, 11-15=-1007/0, 12-15=0/1036, 12-14=-942/0

**NOTES- (6-7)**

- 1) Unbalanced floor live loads have been considered for this design.
- 2) All plates are MT20 plates unless otherwise indicated.
- 3) All plates are 3x4 MT20 unless otherwise indicated.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Recommend 2x6 strongbacks, on edge, spaced at 10'-0" o.c. and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
- 6) Graphical web bracing representation does not depict the size, type or the orientation of the brace on the web. Symbol only indicates that the member must be braced.
- 7) Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.

## LOAD CASE(S) Standard



4/14/2025

**Warning !—Verify design parameters and read notes before use.** This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 Guide to *Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D’Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0020 HONEYCUTT HILLS   380 SHELBY MEADOW LANE ANGIER, NC
25-3337-F02	F221	Floor Supported Gable	1	1	
Job Reference (optional)					# 58496

8.630 s Jul 12 2024 MiTek Industries, Inc. Wed Apr 16 09:11:33 2025 Page 1  
ID:gUCksxzC6J7HT2yGkHFINYyiOvf-saaxCQ5cB42z5YHudy2EYsuC1qCqxIK9r6A7WgzQCFu

Scale = 1:29.7




Plate Offsets (X,Y)-- [1:Edge,0-1-8], [8:0-1-8,Edge], [25:0-1-8,Edge], [32:Edge,0-1-8]									
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES
TCLL 40.0	Plate Grip DOL	1.00	TC 0.06	Vert(LL)	n/a	-	n/a	999	MT20
TCDL 10.0	Lumber DOL	1.00	BC 0.01	Vert(CT)	n/a	-	n/a	999	GRIP
BCLL 0.0	Rep Stress Incr	YES	WB 0.03	Horz(CT)	-0.00	25	n/a	n/a	244/190
BCDL 5.0	Code IRC2021/TPI2014		Matrix-SH						Weight: 80 lb FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 10-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	
OTHERS 2x4 SP No.3(flat)	

**REACTIONS.** All bearings 18-3-10.  
(lb) - Max Grav All reactions 250 lb or less at joint(s) 32, 17, 31, 30, 29, 28, 26, 25, 24, 23, 22, 21, 20, 19, 18

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

**NOTES-** (6-7)  
1) All plates are 1.5x3 MT20 unless otherwise indicated.  
2) Gable requires continuous bottom chord bearing.  
3) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).  
4) Gable studs spaced at 1-4-0 oc.  
5) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.  
6) Graphical web bracing representation does not depict the size, type or the orientation of the brace on the web. Symbol only indicates that the member must be braced.  
7) Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.

**LOAD CASE(S)** Standard



4/14/2025

**Warning !—Verify design parameters and read notes before use.** This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.