



HARNETT COUNTY ENVIRONMENTAL HEALTH

File/Permit #: SFD2505-0015

CDP #:

IMPROVEMENT PERMIT (IP)

Owner: ☒ New ☐ Expansion ☐ Repair ☐ System Relocation ☐ Change of Use
Applicant: DRB GROUP NORTH CAROLINA LLC
Property Location: 380 SHELBY MEADOW LN ANGIER, NC 27501
PIN/Lot Identifier: 0663-51-9591.000 Lot 20
Subdivision: HONEYCUTT HILLS
Lot #: 20 Block: Section:
Facility Type: SFD 63.4' x 50' Number of bedrooms: 4 Number of Occupants: 8 Other:
Design Daily Flow: 480 GPD LTAR (Initial): .275 gpd/ft² LTAR (Repair): .3 gpd/ft²
Wastewater System Type: 25% Reduction System (Initial)
Pump Required: ☐ Yes ☐ No ☒ May be required Usable Depth to Limiting Condition (Initial): 31"
Wastewater System Type: 25% Reduction System (Repair)
Pump Required: ☒ Yes ☐ No ☐ May be required Usable Depth to Limiting Condition (Repair): 38"
Effluent Standard: ☒ DSE ☐ HSE ☐ Other: Type of Water Supply: ☐ Private well ☒ Municipal Supply ☐ Other:

Permit conditions:

No Foundation or Gutter Drains to be Directed Towards Septic System.
No Cutting or Grading of Soil in Septic or Septic Repair Area.

The issuance of this permit in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This permit is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of 15A NCAC 18E and to the conditions of this permit.

Authorized Agent's Printed Name: Ren Levocz

Date: 05/16/2025

Authorized Agent's Signature: *Ren Levocz*

Expiration Date: 05/16/2030

CONSTRUCTION AUTHORIZATION (CA)

Owner: ☒ New ☐ Expansion ☐ Repair ☐ System Relocation ☐ Change of Use
Applicant: DRB GROUP NORTH CAROLINA LLC
Property Location: 380 SHELBY MEADOW LN ANGIER, NC 27501
PIN/Lot Identifier: 0663-51-9591.000 Lot 20
Subdivision: HONEYCUTT HILLS
Lot #: 20 Block: Section:
Facility Type: SFD 63.4' x 50' Number of bedrooms: 4 Number of Occupants: 8 Other:
Design Daily Flow: 480 GPD LTAR: .275 gpd/ft²
Effluent Standard: ☒ DSE ☐ HSE ☐ Other: Type of Water Supply: ☐ Private well ☒ Municipal Supply ☐ Other:

Installation Requirements/Conditions

Wastewater System Type: 25% Reduction System Pump Required: ☐ Yes ☐ No ☐ May be required
Septic Tank Size: 1,000 gallons Total Trench Length: 437' feet Trench Spacing: 9' feet on center
Pump Tank Size: 1,000 gallons Maximum Trench Depth: 18" inches Soil Cover: 6" inches
Trench Width: 36" inches Distribution Method: ☒ Serial ☐ D-Box or Parallel ☐ Pressure Manifold ☐ Other:
Artificial Drainage Required: Yes ☐ No ☒ If yes, please specify details:
Management Entity Required: ☐ Yes ☒ No Minimum O&M Requirements:

Permit conditions:

No Foundation or Gutter Drains to be Directed Towards Septic System.
No Cutting or Grading of Soil in Septic or Septic Repair Area.

The requirements of 15A NCAC 18E are incorporated by reference into this permit and shall be met. Systems shall be installed in accordance with the attached site sketch. This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be affected by a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of 15A NCAC 18E, or 15A NCAC 18A .1900, as applicable, and to the conditions of this permit.

Authorized Agent's Printed Name: Ren Levocz

Date: 05/16/25

Authorized Agent's Signature: *Ren Levocz*

Expiration Date: 05/16/2030

Owner/Legal Representative Signature:

Date:

*See attached site sketch

Harnett County Environmental Health

SITE SKETCH

PIN 0663-51-9591.000

Permit Number SFD2505-0015

DRB GROUP NORTH CAROLINA LLC

HONEYCUTT HILLS Lot 20

Applicant's Name

Subdivision/Section/Lot Number

Ren Levocz

05/16/2025

Authorized State Agent

Date _____

System components represent approximate contours only. The contractor must flag the system prior to beginning the installation to ensure that the proper grade is maintained.

* More line is Flagged Than Needed, Need a total of 437

Scale = NTS