ENGINEERING BY TRENCO
A MiTek Affiliate

RE: 25030124-01
919 Serenity-Roof-B330 E BNS CP TMB GRH

Trenco
818 Soundside Rd
Edenton, NC 27932

Site Information:

Customer: David Weekley Homes Project Name: 25030124-01
Lot/Block: 919 Model:
Address: 1126 Serenity Walk Parkway Subdivision: Serenity
City: Fuquay-Varina State: NC

General Truss Engineering Criteria & Design Loads (Individual Truss Design Drawings Show Special Loading Conditions):

Design Code: IRC2021/TPI2014 Design Program: MiTek 20/20 8.7
Wind Code: ASCE 7-16 Wind Speed: 130 mph
Roof Load: 40.0 psf Floor Load: N/A psf

This package includes 43 individual, dated Truss Design Drawings and 0 Additional Drawings.

No.	Seal#	Truss Name	Date	No.	Seal#	Truss Name	Date
1	I72215035	A	3/25/2025	21	I72215055	H1	3/25/2025
2	I72215036	AGE	3/25/2025	22	I72215056	H2	3/25/2025
3	I72215037	B	3/25/2025	23	I72215057	I1	3/25/2025
4	I72215038	B1	3/25/2025	24	I72215058	J1	3/25/2025
5	I72215039	B1GE	3/25/2025	25	I72215059	J1T	3/25/2025
6	I72215040	B1T	3/25/2025	26	I72215060	J02	3/25/2025
7	I72215041	BGR	3/25/2025	27	I72215061	J02A	3/25/2025
8	I72215042	C	3/25/2025	28	I72215062	K1	3/25/2025
9	I72215043	CGE	3/25/2025	29	I72215063	L01	3/25/2025
10	I72215044	CGR	3/25/2025	30	I72215064	L02	3/25/2025
11	I72215045	D	3/25/2025	31	I72215065	M01	3/25/2025
12	I72215046	DGE	3/25/2025	32	I72215066	PB1	3/25/2025
13	I72215047	E	3/25/2025	33	I72215067	PB1GR	3/25/2025
14	I72215048	E2	3/25/2025	34	I72215068	PB2	3/25/2025
15	I72215049	EGE	3/25/2025	35	I72215069	PB3	3/25/2025
16	I72215050	F	3/25/2025	36	I72215070	V03	3/25/2025
17	I72215051	F1GE	3/25/2025	37	I72215071	V06	3/25/2025
18	I72215052	FGE	3/25/2025	38	I72215072	V07	3/25/2025
19	I72215053	G	3/25/2025	39	I72215073	V09	3/25/2025
20	I72215054	GSE	3/25/2025	40	I72215074	V10	3/25/2025

The truss drawing(s) referenced above have been prepared by Truss Engineering Co. under my direct supervision based on the parameters provided by Carter Components (Sanford, NC)).

Truss Design Engineer's Name: Johnson, Andrew

My license renewal date for the state of North Carolina is December 31, 2025.

North Carolina COA: C-0844



IMPORTANT NOTE: The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to TRENCO. Any project specific information included is for TRENCO customers file reference purpose only, and was not taken into account in the preparation of these designs. TRENCO has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.

March 25, 2025

Johnson, Andrew

ENGINEERING BY TRENCO
A MiTek Affiliate

Trenco
818 Soundside Rd
Edenton, NC 27932

RE: 25030124-01 - 919 Serenity-Roof-B330 E BNS CP TMB GRH

Site Information:

Project Customer: David Weekley Homes Project Name: 25030124-01
Lot/Block: 919 Subdivision: Serenity
Address: 1126 Serenity Walk Parkway
City, County: Fuquay-Varina State: NC

No.	Seal#	Truss Name	Date
41	I72215075	V13	3/25/2025
42	I72215076	V17	3/25/2025
43	I72215077	V20	3/25/2025

Job	Truss	Truss Type	Qty	Ply	919 Serenity-Roof-B330 E BNS CP TMB GRH
25030124-01	A	Common	4	1	I72215035 Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 13:31:57 Page: 1
ID:CttcSzQgwNcSj9X9hY?FsHzF_uO-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:73.1

Plate Offsets (X, Y): [2:0-4-1,Edge], [5:0-4-0,0-3-0], [7:0-4-0,0-3-0], [10:0-4-1,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.87	Vert(LL)	-0.37	14-16	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	1.00	Vert(CT)	-0.64	14-16	>754	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.41	Horz(CT)	0.15	10	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 213 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.1
BOT CHORD	2x4 SP No.1
WEBS	2x4 SP No.3 *Except* 14-6:2x4 SP No.2
SLIDER	Left 2x4 SP No.3 -- 1-6-0, Right 2x4 SP No.3 -- 1-6-0

BRACING

TOP CHORD	Structural wood sheathing directly applied or 2-2-0 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 2-2-0 oc bracing.
WEBS	1 Row at midpt 7-14, 5-14

REACTIONS (size) 2=0-5-8, 10=0-5-8
Max Horiz 2=-165 (LC 15)
Max Uplift 2=-170 (LC 14), 10=-170 (LC 15)
Max Grav 2=1809 (LC 3), 10=1809 (LC 3)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD	1-2=0/23, 2-4=-3431/321, 4-6=-3226/333, 6-8=-3226/333, 8-10=-3431/321, 10-11=0/23
BOT CHORD	2-16=-330/2978, 14-16=-191/2524, 12-14=-109/2524, 10-12=-185/2978
WEBS	6-14=-114/1658, 7-14=-853/247, 7-12=-25/626, 8-12=-301/191, 5-14=-853/247, 5-16=-25/626, 4-16=-301/191

NOTES

1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-10-8 to 3-1-8, Interior (1) 3-1-8 to 16-0-0, Exterior(2R) 16-0-0 to 24-0-0, Interior (1) 24-0-0 to 36-10-8, Exterior(2E) 36-10-8 to 40-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
4) Unbalanced snow loads have been considered for this design.
5) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
8) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 2 and 10. This connection is for uplift only and does not consider lateral forces.

LOAD CASE(S) Standard

March 25,2025

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	919 Serenity-Roof-B330 E BNS CP TMB GRH
25030124-01	AGE	Common Supported Gable	1	1	I72215036 Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 13:31:58 Page: 1
ID:94aeZ53wRfHxaJ4LIBSgWSzF_tZ-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:73.1

Plate Offsets (X, Y): [2:0-2-8,0-0-5], [26:0-3-1,0-0-5], [35:0-3-0,0-3-0], [39:0-3-0,0-3-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.08	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.05	Vert(CT)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.15	Horz(CT)	0.01	26	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 286 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3 *Except* 37-14:2x4 SP No.2
SLIDER Left 2x4 SP No.3 -- 1-6-0, Right 2x4 SP No.3 -- 1-6-0

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 1 Row at midpt 14-37, 13-38, 12-39, 15-36, 16-35

REACTIONS (size) 2=40-0-0, 26=40-0-0, 28=40-0-0, 29=40-0-0, 30=40-0-0, 31=40-0-0, 32=40-0-0, 33=40-0-0, 34=40-0-0, 35=40-0-0, 36=40-0-0, 37=40-0-0, 38=40-0-0, 39=40-0-0, 40=40-0-0, 41=40-0-0, 42=40-0-0, 43=40-0-0, 44=40-0-0, 45=40-0-0, 46=40-0-0
Max Horiz 2=165 (LC 14)
Max Uplift 2=-21 (LC 10), 28=-80 (LC 15), 29=-36 (LC 15), 30=-46 (LC 15), 31=-43 (LC 15), 32=-44 (LC 15), 33=-44 (LC 15), 34=-44 (LC 15), 35=-48 (LC 15), 36=-35 (LC 15), 38=-39 (LC 14), 39=-47 (LC 14), 40=-44 (LC 14), 41=-43 (LC 14), 42=-44 (LC 14), 43=-43 (LC 14), 44=-46 (LC 14), 45=-33 (LC 14), 46=-96 (LC 14)
Max Grav 2=162 (LC 27), 26=139 (LC 1), 28=161 (LC 37), 29=160 (LC 1), 30=160 (LC 37), 31=160 (LC 1), 32=161 (LC 22), 33=160 (LC 37), 34=179 (LC 22), 35=233 (LC 22), 36=247 (LC 22), 37=200 (LC 28), 38=247 (LC 21), 39=233 (LC 21), 40=179 (LC 21), 41=160 (LC 36), 42=161 (LC 21), 43=160 (LC 1), 44=160 (LC 36), 45=160 (LC 1), 46=161 (LC 36)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/23, 2-4=-216/79, 4-5=-167/82, 5-6=-129/94, 6-7=-96/108, 7-8=-74/131, 8-9=-62/154, 9-11=-72/178, 11-12=-85/222, 12-13=-104/271, 13-14=-121/311, 14-15=-121/311, 15-16=-104/271, 16-17=-85/222, 17-19=-72/177, 19-20=-60/132, 20-21=-48/86, 21-22=-44/41, 22-23=-66/27, 23-24=-99/35, 24-26=-144/59, 26-27=0/23
BOT CHORD 2-46=-44/167, 45-46=-44/167, 44-45=-44/167, 43-44=-44/167, 42-43=-44/167, 41-42=-44/167, 40-41=-44/167, 38-40=-44/167, 37-38=-44/166, 36-37=-44/166, 34-36=-44/167, 33-34=-44/167, 32-33=-44/167, 31-32=-44/167, 30-31=-44/167, 29-30=-44/167, 28-29=-44/167, 26-28=-44/167
WEBS 14-37=-205/45, 13-38=-205/66, 12-39=-193/83, 11-40=-140/76, 9-41=-126/77, 8-42=-126/77, 7-43=-126/77, 6-44=-127/77, 5-45=-126/80, 4-46=-131/135, 15-36=-205/66, 16-35=-193/83, 17-34=-140/76, 19-33=-126/77, 20-32=-126/77, 21-31=-126/77, 22-30=-127/77, 23-29=-126/80, 24-28=-131/135

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Corner(3E) -0-10-8 to 3-1-8, Exterior(2N) 3-1-8 to 16-0-0, Corner(3R) 16-0-0 to 24-0-0, Exterior(2N) 24-0-0 to 36-10-8, Corner(3E) 36-10-8 to 40-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60



March 25,2025

Continued on page 2

ENGINEERING BY TRENCO A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
4) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
5) Unbalanced snow loads have been considered for this design.
6) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
7) All plates are 2x4 MT20 unless otherwise indicated.
8) Gable requires continuous bottom chord bearing.
9) Gable studs spaced at 2-0-0 oc.
10) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
11) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
12) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 21 lb uplift at joint 2, 39 lb uplift at joint 38, 47 lb uplift at joint 39, 44 lb uplift at joint 40, 43 lb uplift at joint 41, 44 lb uplift at joint 42, 43 lb uplift at joint 43, 46 lb uplift at joint 44, 33 lb uplift at joint 45, 96 lb uplift at joint 46, 35 lb uplift at joint 36, 48 lb uplift at joint 35, 44 lb uplift at joint 34, 44 lb uplift at joint 33, 44 lb uplift at joint 32, 43 lb uplift at joint 31, 46 lb uplift at joint 30, 36 lb uplift at joint 29, 80 lb uplift at joint 28 and 21 lb uplift at joint 2.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	919 Serenity-Roof-B330 E BNS CP TMB GRH
25030124-01	B	Attic	3	1	I72215037 Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 13:31:58 Page: 1

ID:6tPM5lr?FJUMxDStPvqO5SzF_Wb-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:86.7

Plate Offsets (X, Y): [2:0-2-14,0-2-0], [4:0-4-0,0-2-0], [5:0-5-4,0-2-12], [7:0-5-4,0-2-12], [8:0-0-2,0-2-4], [9:0-2-3,0-2-4], [12:Edge,0-1-8], [13:0-3-8,0-1-8], [17:0-2-8,0-2-8], [27:0-2-4,Edge], [31:0-3-8,0-1-8], [34:0-4-0,0-2-4]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.57	Vert(LL)	-0.33	16-19	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.90	Vert(CT)	-0.54	19-21	>748	180	MT20HS	187/143
TCDL	10.0	Rep Stress Incr	YES	WB	0.97	Horz(CT)	0.08	12	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH		Attic	-0.25	15-29	>725	360		
BCDL	10.0										Weight: 340 lb	FT = 20%

LUMBER

TOP CHORD 2x6 SP No.2 *Except* 7-11:2x6 SP 2400F 2.0E

BOT CHORD 2x4 SP No.1 *Except* 29-15:2x4 SP No.2, 27-18:2x4 SP 2400F 2.0E

WEBS 2x4 SP No.3 *Except* 4-30,9-14,4-8,8-9:2x6 SP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 4-8-9 oc purlins, except end verticals, and 2-0-0 oc purlins (5-5-7 max.): 5-7.

BOT CHORD Rigid ceiling directly applied or 2-9-3 oc bracing.

WEBS 1 Row at midpt 8-34

JOINTS 1 Brace at Jt(s): 19, 26, 34

REACTIONS (size) 12= Mechanical, 32=0-5-8
Max Horiz 32=-279 (LC 12)
Max Grav 12=2109 (LC 48), 32=2084 (LC 48)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/30, 2-3=-2274/0, 3-4=-2494/0, 4-5=-1152/208, 5-6=-1573/557, 6-7=-1573/557, 7-8=-992/421, 8-9=-2025/21, 9-10=-2789/0, 10-11=-2599/0, 2-32=-2190/0, 11-12=-2237/0

BOT CHORD 31-32=-242/278, 30-31=0/1755, 25-30=-135/3865, 23-25=0/4682, 20-23=0/4682, 17-20=0/4162, 14-17=-24/1903, 13-14=0/2071, 12-13=-5/74, 28-29=-1034/53, 26-28=-1034/53, 24-26=-3102/0, 22-24=-3102/0, 21-22=-3229/0, 19-21=-3229/0, 16-19=-1586/13, 15-16=-1586/13

WEBS 3-31=-641/0, 3-30=-111/484, 29-30=-81/178, 4-29=0/934, 14-15=-47/272, 9-15=0/1067, 4-33=-1691/53, 33-34=-1621/46, 34-35=-2164/0, 8-35=-2186/0, 2-31=0/1784, 10-14=-276/250, 10-13=-560/0, 11-13=0/2096, 15-17=0/1848, 27-29=0/1797, 16-17=-242/0, 27-28=-283/0, 17-19=-1179/0, 26-27=-1389/0, 19-20=0/809, 25-26=0/1061, 20-21=-272/0, 24-25=-426/0, 20-22=-129/353, 22-23=-163/14, 5-33=-36/469, 6-34=-460/112, 7-35=0/336, 7-34=-387/865, 5-34=-740/686

NOTES

1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-8-4 to 2-8-10, Interior (1) 2-8-10 to 6-6-3, Exterior(2R) 6-6-3 to 16-1-13, Interior (1) 16-1-13 to 16-10-13, Exterior(2R) 16-10-13 to 26-6-8, Interior (1) 26-6-8 to 30-6-6, Exterior(2E) 30-6-6 to 33-11-4 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
4) Unbalanced snow loads have been considered for this design.
5) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
6) Provide adequate drainage to prevent water ponding.
7) All plates are MT20 plates unless otherwise indicated.
8) All plates are 3x5 MT20 unless otherwise indicated.
9) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
10) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
11) Ceiling dead load (5.0 psf) on member(s). 8-9, 4-33, 33-34, 34-35, 8-35; Wall dead load (5.0psf) on member (s).4-29, 9-15
12) Bottom chord live load (40.0 psf) and additional bottom chord dead load (5.0 psf) applied only to room. 28-29, 26-28, 24-26, 22-24, 21-22, 19-21, 16-19, 15-16
13) Refer to girder(s) for truss to truss connections.
14) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
15) Attic room checked for L/360 deflection.

LOAD CASE(S) Standard



March 25,2025

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	919 Serenity-Roof-B330 E BNS CP TMB GRH
25030124-01	B1	Piggyback Base	1	1	I72215038 Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 13:31:59 ID:LKC_EscL4trfY8AISnB7qGypZv8-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:69.1

Plate Offsets (X, Y): [4:0-3-12,0-1-12], [6:0-3-12,0-1-12]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.89	Vert(LL)	-0.20	12-14	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.97	Vert(CT)	-0.33	12-14	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.67	Horz(CT)	0.07	9	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 242 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2 *Except* 6-8:2x4 SP No.1
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3 *Except* 14-4,12-4,12-5,12-6,10-6:2x4 SP No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (4-5-4 max.): 4-6.
BOT CHORD Rigid ceiling directly applied or 2-2-0 oc bracing, Except:
10-0-0 oc bracing: 14-15.
WEBS 1 Row at midpt 3-15, 7-9, 5-12

REACTIONS (size) 9= Mechanical, 15=0-5-8
Max Horiz 15=-283 (LC 12)
Max Uplift 9=-127 (LC 15), 15=-139 (LC 14)
Max Grav 9=1617 (LC 47), 15=1680 (LC 47)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/37, 2-3=-228/123, 3-4=-1911/287, 4-5=-1537/266, 5-6=-1537/266, 6-7=-2064/283, 7-8=-261/100, 2-15=-290/136, 8-9=-248/86
BOT CHORD 14-15=-175/1361, 12-14=-121/1232, 10-12=-28/1288, 9-10=-92/1543
WEBS 3-15=-1919/111, 7-9=-2016/118, 4-14=-118/464, 3-14=-106/339, 4-12=-121/554, 5-12=-562/154, 6-12=-132/450, 6-10=-108/600, 7-10=-221/245

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-10-8 to 2-6-6, Interior (1) 2-6-6 to 6-6-3, Exterior(2R) 6-6-3 to 16-1-13, Interior (1) 16-1-13 to 16-10-13, Exterior(2R) 16-10-13 to 26-6-8, Interior (1) 26-6-8 to 30-6-6, Exterior(2E) 30-6-6 to 33-11-4 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
4) Unbalanced snow loads have been considered for this design.
5) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
6) Provide adequate drainage to prevent water ponding.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
9) Refer to girder(s) for truss to truss connections.
10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 127 lb uplift at joint 9.
11) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 15. This connection is for uplift only and does not consider lateral forces.
12) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

March 25,2025

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	919 Serenity-Roof-B330 E BNS CP TMB GRH
25030124-01	B1GE	Piggyback Base Supported Gable	1	1	I72215039 Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 13:31:59 Page: 1
ID:va6oJ_bKLZdwDLTYr9P9wpzF_UL-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:67.7

Plate Offsets (X, Y): [9:0-2-8,0-0-5], [15:0-2-8,0-0-5]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.36	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.22	Vert(CT)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.19	Horz(CT)	-0.01	23	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MR								
BCDL	10.0										Weight: 304 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3
OTHERS 2x4 SP No.3 *Except*
33-12,32-13,31-14,34-11,35-10:2x4 SP No.2

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 9-15.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 1 Row at midpt 12-33, 13-32, 14-31, 16-29, 17-28, 11-34, 10-35, 8-37, 7-38

REACTIONS (size) 23=34-1-0, 24=34-1-0, 25=34-1-0, 26=34-1-0, 27=34-1-0, 28=34-1-0, 29=34-1-0, 31=34-1-0, 32=34-1-0, 33=34-1-0, 34=34-1-0, 35=34-1-0, 37=34-1-0, 38=34-1-0, 39=34-1-0, 40=34-1-0, 41=34-1-0, 42=34-1-0
Max Horiz 42=-283 (LC 12)
Max Uplift 23=-262 (LC 11), 24=-239 (LC 10), 25=-46 (LC 15), 26=-72 (LC 15), 27=-62 (LC 15), 28=-92 (LC 15), 31=-4 (LC 10), 32=-36 (LC 11), 33=-24 (LC 10), 34=-34 (LC 11), 38=-92 (LC 14), 39=-69 (LC 14), 40=-36 (LC 14), 41=-187 (LC 11), 42=-138 (LC 10)
Max Grav 23=309 (LC 12), 24=332 (LC 13), 25=164 (LC 1), 26=203 (LC 53), 27=233 (LC 41), 28=234 (LC 41), 29=212 (LC 55), 31=221 (LC 40), 32=231 (LC 40), 33=229 (LC 40), 34=231 (LC 40), 35=221 (LC 40), 37=205 (LC 57), 38=234 (LC 41), 39=234 (LC 51), 40=192 (LC 41), 41=310 (LC 25), 42=253 (LC 53)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 2-42=-345/308, 1-2=0/37, 2-3=-186/179, 3-4=-155/154, 4-5=-94/145, 5-6=-131/191, 6-7=-160/254, 7-8=-206/335, 8-9=-186/294, 9-10=-176/299, 10-11=-176/299, 11-12=-176/299, 12-13=-176/299, 13-14=-176/299, 14-15=-176/299, 15-16=-186/294, 16-17=-206/335, 17-18=-160/254, 18-19=-135/212, 19-20=-148/173, 20-21=-158/155, 21-22=-230/215, 22-23=-196/170
BOT CHORD 41-42=-165/165, 40-41=-165/165, 39-40=-165/165, 38-39=-165/165, 37-38=-165/165, 35-37=-165/165, 34-35=-165/165, 33-34=-165/165, 32-33=-165/165, 31-32=-165/165, 29-31=-165/165, 28-29=-165/165, 27-28=-165/165, 26-27=-165/165, 25-26=-165/165, 24-25=-165/165, 23-24=-165/165
WEBS 12-33=-189/48, 13-32=-194/70, 14-31=-181/29, 16-29=-172/20, 17-28=-215/116, 18-27=-199/87, 19-26=-173/93, 20-25=-151/83, 21-24=-193/147, 11-34=-194/70, 10-35=-181/25, 8-37=-165/0, 7-38=-215/117, 6-39=-201/92, 5-40=-164/84, 4-41=-226/176, 3-42=-434/410

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Corner(3E) -0-10-8 to 2-6-5, Exterior(2N) 2-6-5 to 7-11-2, Corner(3R) 7-11-2 to 14-6-5, Exterior(2N) 14-6-5 to 18-3-12, Corner(3R) 18-3-12 to 25-1-9, Exterior(2N) 25-1-9 to 30-6-5, Corner(3E) 30-6-5 to 33-11-4 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
4) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10



March 25,2025

Continued on page 2

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

5) Unbalanced snow loads have been considered for this design.
6) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
7) Provide adequate drainage to prevent water ponding.
8) All plates are 2x4 MT20 unless otherwise indicated.
9) Gable requires continuous bottom chord bearing.
10) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
11) Gable studs spaced at 2-0-0 oc.
12) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
13) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
14) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 138 lb uplift at joint 42, 262 lb uplift at joint 23, 24 lb uplift at joint 33, 36 lb uplift at joint 32, 4 lb uplift at joint 31, 92 lb uplift at joint 28, 62 lb uplift at joint 27, 72 lb uplift at joint 26, 46 lb uplift at joint 25, 239 lb uplift at joint 24, 34 lb uplift at joint 34, 92 lb uplift at joint 38, 69 lb uplift at joint 39, 36 lb uplift at joint 40 and 187 lb uplift at joint 41.
15) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	919 Serenity-Roof-B330 E BNS CP TMB GRH
25030124-01	B1T	Piggyback Base	4	1	I72215040 Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 13:31:59 Page: 1

ID:jCQDRPFmxy5us2K9CGvbovzF_Un-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Plate Offsets (X, Y): [5:0-3-12,0-1-12], [7:0-3-12,0-1-12], [10:Edge,0-1-8], [12:0-2-12,0-3-0], [14:0-2-12,0-2-0], [16:0-2-12,0-2-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.76	Vert(LL)	-0.12	14-15	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.76	Vert(CT)	-0.21	14-15	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.54	Horz(CT)	0.08	10	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 266 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2 *Except* 17-3:2x4 SP No.3
WEBS 2x4 SP No.3 *Except* 14-5,14-7,12-7:2x4 SP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 3-3-12 oc purlins, except end verticals, and 2-0-0 oc purlins (3-6-8 max.): 5-7.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except:
6-0-0 oc bracing: 17-18.
1 Row at midpt 6-14
WEBS 1 Row at midpt 8-12

REACTIONS (size) 10= Mechanical, 18=0-5-8
Max Horiz 18=-283 (LC 12)
Max Uplift 10=-127 (LC 15), 18=-139 (LC 14)
Max Grav 10=1551 (LC 47), 18=1628 (LC 47)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/37, 2-3=-1615/161, 3-4=-1724/293, 4-5=-2006/293, 5-6=-1594/266, 6-7=-1593/267, 7-8=-1797/263, 8-9=-1963/181, 2-18=-1780/185, 9-10=-1629/159
BOT CHORD 17-18=-28/19, 16-17=0/41, 3-16=-250/162, 15-16=-182/1540, 14-15=-130/1313, 13-14=0/121, 6-14=-582/157, 11-13=-63/1519, 10-11=-39/127
WEBS 4-16=-464/151, 5-14=-145/531, 12-14=-29/1225, 7-14=-162/530, 7-12=-74/404, 8-12=-423/191, 8-11=-171/81, 9-11=-30/1442, 5-15=-131/653, 4-15=-318/229, 16-18=-265/275, 2-16=-113/1434

NOTES

1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-10-8 to 2-6-6, Interior (1) 2-6-6 to 6-6-3, Exterior(2R) 6-6-3 to 16-1-13, Interior (1) 16-1-13 to 16-10-13, Exterior(2R) 16-10-13 to 26-6-8, Interior (1) 26-6-8 to 30-6-6, Exterior(2E) 30-6-6 to 33-11-4 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
4) Unbalanced snow loads have been considered for this design.
5) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
6) Provide adequate drainage to prevent water ponding.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
9) Refer to girder(s) for truss to truss connections.
10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 127 lb uplift at joint 10.
11) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 18. This connection is for uplift only and does not consider lateral forces.
12) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

March 25,2025

ENGINEERING BY TRENCO A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	919 Serenity-Roof-B330 E BNS CP TMB GRH
25030124-01	BGR	Attic Girder	1	2	I72215041 Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 13:32:00 Page: 1

ID:HiLQkPKHOQTU5G6uHHvM5iy8nJN-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:83

Plate Offsets (X, Y): [4:0-4-0,0-2-0], [5:0-5-4,0-2-12], [7:0-5-4,0-2-12], [27:0-2-4,0-3-0], [35:0-4-0,0-2-4]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.48	Vert(LL)	-0.21	16-19	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.80	Vert(CT)	-0.35	19-21	>999	180		
TCDL	10.0	Rep Stress Incr	NO	WB	0.62	Horz(CT)	0.06	12	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH		Attic	-0.15	15-29	>999	360		
BCDL	10.0										Weight: 681 lb	FT = 20%

LUMBER

TOP CHORD 2x6 SP No.2 *Except* 7-11:2x6 SP 2400F 2.0E
BOT CHORD 2x4 SP No.2 *Except* 27-18:2x4 SP No.1
WEBS 2x4 SP No.3 *Except* 4-30,9-14,4-8,8-9:2x6 SP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 5-7.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
JOINTS 1 Brace at Jt(s): 19, 26, 35

REACTIONS (size) 12= Mechanical, 32=0-5-8
Max Horiz 32=-279 (LC 10)
Max Grav 12=2889 (LC 48), 32=2829 (LC 46)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/30, 2-3=-2887/0, 3-4=-3224/0, 4-5=-1195/215, 5-6=-1341/811, 6-7=-1341/811, 7-8=-861/421, 8-9=-2468/36, 9-10=-3633/0, 10-11=-3347/0, 2-32=-2765/0, 11-12=-2840/0

BOT CHORD 31-32=-243/282, 30-31=-19/2394, 25-30=-208/4442, 23-25=0/5284, 20-23=0/5284, 17-20=0/4765, 14-17=-118/2629, 13-14=0/2654, 12-13=-5/67, 28-29=-902/132, 26-28=-902/132, 24-26=-3001/0, 22-24=-3001/0, 21-22=-3216/0, 19-21=-3216/0, 16-19=-1613/24, 15-16=-1613/24

WEBS 3-31=-846/7, 3-30=-131/716, 29-30=-144/846, 4-29=0/1613, 14-15=-124/1027, 9-15=0/1794, 10-14=-261/248, 10-13=-755/5, 4-33=-2463/124, 33-35=-2370/116, 34-35=-3398/37, 8-34=-3429/36, 2-31=0/2321, 11-13=0/2714, 15-17=0/1856, 27-29=0/1840, 16-17=-267/0, 27-28=-309/0, 17-19=-1103/0, 26-27=-1355/0, 19-20=0/845, 25-26=0/1140, 20-21=-324/0, 24-25=-489/0, 20-22=-129/420, 22-23=-153/14, 5-33=-50/576, 7-34=-7/404, 6-35=-477/115, 7-35=-385/824, 5-35=-1259/409

NOTES

1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc, 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc, 2x6 - 2 rows staggered at 0-9-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) Unbalanced roof live loads have been considered for this design.
4) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
5) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
6) Unbalanced snow loads have been considered for this design.
7) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
8) Provide adequate drainage to prevent water ponding.
9) All plates are 3x5 MT20 unless otherwise indicated.
10) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
11) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
12) Ceiling dead load (5.0 psf) on member(s). 8-9, 4-33, 33-35, 34-35, 8-34; Wall dead load (5.0psf) on member (s).4-29, 9-15

March 25,2025

Continued on page 2

ENGINEERING BY TRENCO A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

13) Bottom chord live load (40.0 psf) and additional bottom chord dead load (5.0 psf) applied only to room. 28-29, 26-28, 24-26, 22-24, 21-22, 19-21, 16-19, 15-16
14) Refer to girder(s) for truss to truss connections.
15) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
16) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 839 lb down and 71 lb up at 10-4-12, and 839 lb down and 71 lb up at 25-3-4 on bottom chord. The design/ selection of such connection device(s) is the responsibility of others.
17) Attic room checked for L/360 deflection.

LOAD CASE(S) Standard

1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
   Uniform Loads (lb/ft)
   Vert: 1-2=-60, 2-5=-60, 5-7=-60, 7-8=-60, 8-9=-70, 9-11=-60, 12-32=-20, 15-29=-30, 4-33=-10, 33-35=-10, 34-35=-10, 8-34=-10
   Drag: 4-29=-10, 9-15=-10
   Concentrated Loads (lb)
   Vert: 30=-450 (F), 14=-450 (F)

Job	Truss	Truss Type	Qty	Ply	919 Serenity-Roof-B330 E BNS CP TMB GRH
25030124-01	C	Attic	7	1	I72215042 Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 13:32:00 Page: 1

ID:VP5mnZE7ejtTka?ri?H4b3zEzov-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Plate Offsets (X, Y): [2:0-2-12,0-2-0], [6:0-5-4,0-2-12], [8:0-5-4,0-2-12], [9:0-1-6,0-2-4], [14:Edge,0-1-3], [17:0-3-8,0-2-8], [19:0-4-4,0-3-4], [28:0-2-4,Edge], [31:0-5-0,0-3-0], [37:0-3-8,0-2-8], [39:Edge,0-3-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.78	Vert(LL)	-0.28	23-25	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.92	Vert(CT)	-0.51	23	>827	180	MT20HS	187/143
TCDL	10.0	Rep Stress Incr	YES	WB	1.00	Horz(CT)	0.11	14	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH		Attic	-0.20	17-30	>912	360		
BCDL	10.0										Weight: 369 lb	FT = 20%

LUMBER

TOP CHORD 2x6 SP No.2 *Except* 8-11:2x6 SP 2400F 2.0E

BOT CHORD 2x4 SP No.1 *Except* 30-17,37-30:2x4 SP No.2, 28-19:2x4 SP 2400F 2.0E

WEBS 2x4 SP No.3 *Except* 10-16,5-9,5-31,9-10,4-3:2x6 SP No.2, 37-2:2x4 SP No.2

SLIDER Right 2x4 SP No.3 -- 1-6-0

BRACING

TOP CHORD Structural wood sheathing directly applied or 2-9-14 oc purlins, except end verticals, and 2-0-0 oc purlins (5-9-13 max.): 6-8.

BOT CHORD Rigid ceiling directly applied or 2-2-0 oc bracing.

WEBS 1 Row at midpt 9-42

JOINTS 1 Brace at Jt(s): 20, 34, 27, 42

REACTIONS (size) 14= Mechanical, 39=0-5-8
Max Horiz 39=-277 (LC 12)
Max Grav 14=2265 (LC 48), 39=2848 (LC 48)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/30, 2-3=-3050/0, 3-4=-3381/0, 4-5=-2887/0, 5-6=-1321/116, 6-7=-1398/672, 7-8=-1398/672, 8-9=-811/513, 9-10=-2534/0, 10-12=-3347/0, 12-14=-3520/0, 2-39=-3152/0

BOT CHORD 38-39=-897/483, 35-38=-976/485, 33-35=-354/1274, 31-33=-665/1075, 26-31=-971/3622, 24-26=0/4470, 21-24=0/4470, 16-21=0/3986, 15-16=0/2691, 14-15=0/2691, 29-30=-769/1531, 27-29=-769/1531, 25-27=-2354/28, 23-25=-2354/28, 22-23=-2584/0, 20-22=-2584/0, 18-20=-902/0, 17-18=-902/0, 36-37=-153/2061, 34-36=-153/2061, 32-34=-353/1815, 30-32=-353/1815

WEBS 37-38=0/96, 3-37=-704/139, 16-17=-8/435, 10-17=0/1132, 12-16=-384/242, 12-15=-43/127, 5-40=-1888/67, 40-42=-1811/59, 41-42=-3224/0, 9-41=-3260/0, 30-31=0/122, 30-43=0/1491, 5-43=0/1562, 17-19=0/1629, 18-19=-261/0, 19-20=-1140/0, 20-21=0/815, 21-22=-293/0, 21-23=-221/729, 23-24=-220/32, 25-26=-510/0, 35-37=0/1226, 35-36=-284/0, 34-35=-523/0, 33-34=0/357, 28-30=0/2069, 28-29=-253/0, 27-28=-1413/0, 26-27=0/1233, 32-33=-293/0, 30-33=0/739, 6-40=-44/477, 8-41=0/447, 7-42=-472/108, 8-42=-253/973, 6-42=-1322/377, 37-39=-246/811, 2-37=0/2859, 4-43=-404/49

NOTES

1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-8-4 to 2-10-2, Interior (1) 2-10-2 to 6-4-1, Exterior(2R) 6-4-1 to 26-8-10, Interior (1) 26-8-10 to 31-8-14, Exterior(2E) 31-8-14 to 35-3-4 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
4) Unbalanced snow loads have been considered for this design.
5) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
6) Provide adequate drainage to prevent water ponding.
7) All plates are MT20 plates unless otherwise indicated.

March 25,2025

Continued on page 2

ENGINEERING BY TRENCO A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

8) All plates are 2x4 MT20 unless otherwise indicated.
9) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
10) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
11) Ceiling dead load (5.0 psf) on member(s). 3-4, 9-10, 5-40, 40-42, 41-42, 9-41, 4-43; Wall dead load (5.0psf) on member(s).3-37, 10-17, 30-43, 5-43
12) Bottom chord live load (40.0 psf) and additional bottom chord dead load (5.0 psf) applied only to room. 29-30, 27-29, 25-27, 23-25, 22-23, 20-22, 18-20, 17-18, 36-37, 34-36, 32-34, 30-32
13) Refer to girder(s) for truss to truss connections.
14) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
15) Attic room checked for L/360 deflection.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	919 Serenity-Roof-B330 E BNS CP TMB GRH
25030124-01	CGE	Attic Structural Gable	1	1	I72215043 Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 13:32:01 Page: 1
ID:HSVLvMXIBUOh6Uln9Dc1gjzEzgn-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:85.8

Plate Offsets (X, Y): [2:0-2-8,0-2-8], [4:0-4-0,0-2-0], [5:0-3-4,0-2-12], [11:0-3-0,0-2-12], [12:0-0-2,0-2-4], [20:Edge,0-1-3]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.38	Vert(LL)	0.00	13	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.15	Vert(CT)	-0.01	13	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.43	Horz(CT)	0.02	20	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 331 lb	FT = 20%

LUMBER
TOP CHORD 2x6 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3 *Except* 13-26,4-12,45-4,12-13:2x6 SP No.2
OTHERS 2x4 SP No.3
WEDGE Right: 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 5-6-2 oc purlins, except end verticals, and 2-0-0 oc purlins (5-8-1 max.): 5-11.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 1 Row at midpt 4-44
JOINTS 1 Brace at Jt(s): 56, 57, 58, 59, 60, 62

REACTIONS (size) 20=35-4-0, 21=35-4-0, 22=35-4-0, 23=35-4-0, 24=35-4-0, 25=35-4-0, 26=35-4-0, 29=35-4-0, 32=35-4-0, 34=35-4-0, 36=35-4-0, 38=35-4-0, 40=35-4-0, 42=35-4-0, 45=35-4-0, 47=35-4-0, 49=35-4-0, 51=35-4-0, 53=35-4-0, 54=35-4-0
Max Horiz 54=-278 (LC 12)
Max Uplift 20=-53 (LC 11), 21=-90 (LC 15), 22=-58 (LC 15), 23=-6 (LC 11), 24=-63 (LC 15), 25=-164 (LC 41), 26=-44 (LC 10), 45=-42 (LC 14), 53=-370 (LC 14), 54=-277 (LC 10)
Max Grav 20=332 (LC 41), 21=104 (LC 13), 22=188 (LC 23), 23=382 (LC 23), 24=189 (LC 54), 25=59 (LC 11), 26=572 (LC 46), 29=216 (LC 21), 32=268 (LC 21), 34=258 (LC 21), 36=260 (LC 21), 38=262 (LC 21), 40=253 (LC 21), 42=285 (LC 21), 45=731 (LC 38), 47=265 (LC 21), 49=247 (LC 21), 51=304 (LC 21), 53=588 (LC 52), 54=846 (LC 41)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/30, 2-3=-575/215, 3-4=-720/230, 4-5=-1539/285, 5-6=-1329/273, 6-7=-1329/273, 7-8=-1329/273, 8-9=-1329/273, 9-10=-1329/273, 10-11=-1329/273, 11-12=-1474/292, 12-13=-775/221, 13-14=-452/157, 14-16=-589/130, 16-17=-590/105, 17-18=-366/72, 18-19=-349/59, 19-20=-366/63, 2-54=-761/259
BOT CHORD 53-54=-231/243, 51-53=-90/426, 49-51=-90/426, 47-49=-90/426, 45-47=-90/426, 42-45=-81/394, 40-42=-81/394, 38-40=-81/394, 36-38=-81/394, 34-36=-81/394, 32-34=-81/394, 29-32=-81/394, 26-29=-81/394, 25-26=-45/269, 24-25=-45/269, 23-24=-45/269, 22-23=-45/269, 21-22=-45/269, 20-21=-45/269, 41-44=-12/78, 39-41=-12/78, 37-39=-12/78, 35-37=-12/78, 33-35=-12/78, 31-33=-12/78, 28-31=-12/78, 27-28=-12/78, 50-52=-7/59, 48-50=-7/59, 46-48=-7/59, 44-46=-7/59
WEBS 52-53=-654/259, 3-52=-577/301, 26-27=-675/23, 13-27=-679/87, 26-61=-57/242, 61-62=-58/244, 17-62=-59/247, 4-63=-121/705, 56-63=-139/856, 56-57=-139/856, 57-58=-139/856, 58-59=-139/856, 59-60=-139/856, 60-64=-139/856, 12-64=-126/789, 2-55=-206/610, 53-55=-221/647, 54-55=-64/26, 50-51=-263/0, 48-49=-207/0, 46-47=-227/0, 6-56=-302/77, 41-42=-243/0, 7-57=-58/28, 39-40=-214/0, 8-58=-94/33, 37-38=-222/0, 9-59=-69/31, 35-36=-220/0, 10-60=-193/60, 33-34=-218/0, 31-32=-227/0, 28-29=-183/0, 14-61=-36/196, 25-61=-37/200, 16-62=-155/86, 24-62=-151/87, 17-23=-343/30, 18-22=-154/84, 19-21=-68/82, 44-45=-705/66, 4-44=-626/178, 5-63=-185/789, 11-64=-113/564

NOTES

March 25,2025

Continued on page 2

ENGINEERING BY TRENCO A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-8-4 to 2-10-2, Interior (1) 2-10-2 to 6-4-1, Exterior(2R) 6-4-1 to 26-6-4, Interior (1) 26-6-4 to 31-9-10, Exterior(2E) 31-9-10 to 35-4-0 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
4) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
5) Unbalanced snow loads have been considered for this design.
6) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
7) Provide adequate drainage to prevent water ponding.
8) All plates are 2x4 MT20 unless otherwise indicated.
9) Gable studs spaced at 2-0-0 oc.
10) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
11) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
12) Ceiling dead load (5.0 psf) on member(s). 12-13, 4-63, 56-63, 56-57, 57-58, 58-59, 59-60, 60-64, 12-64; Wall dead load (5.0psf) on member(s).3-52, 13-27, 4-44
13) Bottom chord live load (40.0 psf) and additional bottom chord dead load (5.0 psf) applied only to room. 41-44, 39-41, 37-39, 35-37, 33-35, 31-33, 28-31, 27-28, 50-52, 48-50, 46-48, 44-46
14) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 54, 53, 26, 20, 25, 24, 23, 22, 21, and 45. This connection is for uplift only and does not consider lateral forces.
15) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
16) Attic room checked for L/360 deflection.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	919 Serenity-Roof-B330 E BNS CP TMB GRH
25030124-01	CGR	Attic Girder	2	**2**	I72215044 Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 13:32:01 Page: 1

ID:VP5mnZE7ejtTka?ri?H4b3zEzov-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:82.3

Plate Offsets (X, Y): [2:0-2-8,0-2-8], [6:0-5-4,0-2-12], [8:0-5-4,0-2-12], [9:0-0-10,0-2-4], [13:Edge,0-1-3], [19:0-2-4,0-3-0], [28:0-2-4,0-3-4], [37:0-2-4,0-2-8], [42:0-4-0,0-2-4]

Loading	(psf)	**Spacing**	3-0-0	**CSI**		**DEFL**	in	(loc)	l/defl	L/d	**PLATES**	**GRIP**
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.67	Vert(LL)	-0.24	23-25	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.99	Vert(CT)	-0.42	23-25	>999	180		
TCDL	10.0	Rep Stress Incr	NO	WB	0.86	Horz(CT)	0.09	13	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH		Attic	-0.18	17-30	>999	360		
BCDL	10.0										Weight: 727 lb	FT = 20%

LUMBER

TOP CHORD 2x6 SP No.2 *Except* 8-11:2x6 SP 2400F 2.0E

BOT CHORD 2x4 SP No.1 *Except* 30-17,37-30:2x4 SP No.2

WEBS 2x4 SP No.3 *Except* 10-16:2x4 SP No.2, 5-9,31-5,9-10,4-3:2x6 SP No.2

WEDGE Right: 2x4 SP No.3

BRACING

TOP CHORD 2-0-0 oc purlins (6-0-0 max.), except end verticals
(Switched from sheeted: Spacing > 2-8-0).

BOT CHORD Rigid ceiling directly applied or 5-6-2 oc bracing.

JOINTS 1 Brace at Jt(s): 6, 8, 2, 20, 34, 27, 40, 41, 42, 43

REACTIONS (size) 13=0-5-8, 39=0-5-8
Max Horiz 39=-428 (LC 10)
Max Grav 13=3443 (LC 44), 39=4279 (LC 44)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/45, 2-3=-4302/0, 3-4=-4729/0, 4-5=-4052/0, 5-6=-1866/175, 6-7=-2124/937, 7-8=-2124/937, 8-9=-1234/747, 9-10=-3465/0, 10-12=-4657/0, 12-13=-4923/0, 13-14=0/37, 2-39=-4471/0

BOT CHORD 38-39=-1322/778, 35-38=-1442/783, 33-35=-559/2027, 31-33=-1122/1781, 26-31=-1609/5680, 24-26=0/6972, 21-24=0/6972, 16-21=0/6253, 15-16=0/3787, 13-15=0/3787, 29-30=-1343/2480, 27-29=-1343/2480, 25-27=-3832/249, 23-25=-3832/249, 22-23=-4249/0, 20-22=-4249/0, 18-20=-1617/0, 17-18=-1617/0, 36-37=-300/3072, 34-36=-300/3072, 32-34=-628/2833, 30-32=-628/2833

WEBS 37-38=0/142, 3-37=-984/207, 16-17=0/694, 10-17=0/1670, 12-16=-612/396, 12-15=-94/182, 5-40=-2736/180, 40-42=-2637/163, 41-42=-4734/0, 9-41=-4781/0, 17-19=0/2161, 18-19=-403/0, 19-20=-1661/0, 20-21=0/1262, 21-22=-487/0, 21-23=-288/1091, 23-24=-296/38, 35-37=0/1856, 35-36=-424/0, 34-35=-805/0, 33-34=0/553, 32-33=-436/0, 25-26=-828/0, 30-31=0/182, 30-43=0/2248, 5-43=0/2355, 27-28=-2079/0, 30-33=0/1111, 28-29=-398/0, 28-30=0/3140, 26-27=0/1902, 37-39=-411/1178, 2-37=0/4083, 6-40=-86/616, 8-41=0/623, 7-42=-706/161, 8-42=-396/1454, 6-42=-2003/565, 4-43=-656/85

NOTES

1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc, 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc, 2x6 - 2 rows staggered at 0-9-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) Unbalanced roof live loads have been considered for this design.
4) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
5) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
6) Unbalanced snow loads have been considered for this design.
7) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.



March 25,2025

Continued on page 2

ENGINEERING BY TRENCO A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

8) Provide adequate drainage to prevent water ponding.
9) All plates are 2x4 MT20 unless otherwise indicated.
10) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
11) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
12) Ceiling dead load (5.0 psf) on member(s). 3-4, 9-10, 5-40, 40-42, 41-42, 9-41, 4-43; Wall dead load (5.0psf) on member(s).3-37, 10-17, 30-43, 5-43
13) Bottom chord live load (40.0 psf) and additional bottom chord dead load (5.0 psf) applied only to room. 29-30, 27-29, 25-27, 23-25, 22-23, 20-22, 18-20, 17-18, 36-37, 34-36, 32-34, 30-32
14) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
15) Attic room checked for L/360 deflection.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	919 Serenity-Roof-B330 E BNS CP TMB GRH
25030124-01	D	Common	4	1	I72215045 Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 13:32:02
ID:nqLL14Jf5JAmMe82YAnlwAzF_pM-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:34.2

Plate Offsets (X, Y): [2:Edge,0-0-14], [2:0-2-5,Edge], [4:Edge,0-0-14], [4:0-2-5,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.72	Vert(LL)	-0.09	6-11	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.56	Vert(CT)	-0.13	6-11	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.10	Horz(CT)	0.02	4	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 51 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3
WEDGE Left: 2x4 SP No.3
Right: 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 4-1-1 oc purlins.
BOT CHORD Rigid ceiling directly applied or 8-6-15 oc bracing.

REACTIONS (size) 2=0-3-0, 4=0-3-0
Max Horiz 2=41 (LC 14)
Max Uplift 2=-221 (LC 10), 4=-221 (LC 11)
Max Grav 2=708 (LC 21), 4=708 (LC 22)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/17, 2-3=-901/594, 3-4=-901/594, 4-5=0/17
BOT CHORD 2-6=-458/775, 4-6=-458/775
WEBS 3-6=-116/268

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior (1) 2-1-8 to 3-11-8, Exterior(2R) 3-11-8 to 9-11-8, Interior (1) 9-11-8 to 11-9-8, Exterior(2E) 11-9-8 to 14-9-8 zone; cantilever left and right exposed ; end vertical left and right exposed; porch left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
4) Unbalanced snow loads have been considered for this design.
5) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 2 and 4. This connection is for uplift only and does not consider lateral forces.

LOAD CASE(S) Standard

March 25,2025

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	919 Serenity-Roof-B330 E BNS CP TMB GRH
25030124-01	DGE	Common Supported Gable	1	1	I72215046 Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 13:32:02 Page: 1
ID:UUQhZhEGk9Im0a6ieC968izF_pT-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:33.5

Plate Offsets (X, Y): [2:Edge,0-0-14], [2:0-2-5,Edge], [8:Edge,0-0-14], [8:0-2-5,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.29	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.19	Vert(CT)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.08	Horz(CT)	-0.01	8	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 59 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3
WEDGE Left: 2x4 SP No.3
Right: 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 10-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS (size) 2=13-3-0, 8=13-3-0, 10=13-3-0, 11=13-3-0, 12=13-3-0, 13=13-3-0, 14=13-3-0
Max Horiz 2=41 (LC 14)
Max Uplift 2=-1 (LC 21), 8=-71 (LC 36), 10=-44 (LC 15), 11=-35 (LC 11), 12=-47 (LC 10), 13=-23 (LC 14), 14=-75 (LC 10)
Max Grav 2=0 (LC 10), 8=128 (LC 22), 10=302 (LC 22), 11=205 (LC 22), 12=420 (LC 21), 13=123 (LC 21), 14=437 (LC 21)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/17, 2-3=-220/432, 3-4=-165/401, 4-5=-123/411, 5-6=-122/395, 6-7=-170/392, 7-8=-217/405, 8-9=0/17
BOT CHORD 2-14=-365/260, 13-14=-365/260, 12-13=-365/260, 11-12=-365/260, 10-11=-365/260, 8-10=-365/260
WEBS 5-12=-360/181, 4-13=-146/110, 3-14=-275/153, 6-11=-183/128, 7-10=-212/127

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Corner(3E) -0-10-8 to 2-1-8, Exterior(2N) 2-1-8 to 3-11-8, Corner(3R) 3-11-8 to 9-11-8, Exterior(2N) 9-11-8 to 11-9-8, Corner(3E) 11-9-8 to 14-9-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
4) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
5) Unbalanced snow loads have been considered for this design.
6) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
7) All plates are 2x4 MT20 unless otherwise indicated.
8) Gable studs spaced at 2-0-0 oc.
9) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
10) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.

LOAD CASE(S) Standard

March 25,2025

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	919 Serenity-Roof-B330 E BNS CP TMB GRH
25030124-01	E	Common	3	1	I72215047 Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 13:32:02 Page: 1
ID:wb1oEU3ot9zDodjcIXhweSzF_Yu-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:46.6

Plate Offsets (X, Y): [2:0-0-12,0-2-0], [4:0-0-12,0-2-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.80	Vert(LL)	-0.03	7-8	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.36	Vert(CT)	-0.06	7-8	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.13	Horz(CT)	0.01	6	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 77 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3 *Except* 8-2,6-4:2x6 SP No.2

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 6=0-5-8, 8=0-5-8
Max Horiz 8=168 (LC 13)
Max Uplift 6=-54 (LC 15), 8=-54 (LC 14)
Max Grav 6=648 (LC 22), 8=648 (LC 21)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/40, 2-3=-593/129, 3-4=-593/129, 4-5=0/40, 2-8=-594/173, 4-6=-594/171
BOT CHORD 7-8=-273/483, 6-7=-203/483
WEBS 3-7=0/270, 2-7=-171/308, 4-7=-174/312

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-9-14 to 2-2-2, Interior (1) 2-2-2 to 3-6-0, Exterior(2R) 3-6-0 to 9-6-0, Interior (1) 9-6-0 to 10-9-14, Exterior(2E) 10-9-14 to 13-9-14 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
4) Unbalanced snow loads have been considered for this design.
5) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 8 and 6. This connection is for uplift only and does not consider lateral forces.

LOAD CASE(S) Standard

March 25,2025

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	919 Serenity-Roof-B330 E BNS CP TMB GRH
25030124-01	E2	Common	1	1	I72215048 Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 13:32:02 Page: 1
ID:UVm5OFFw26J43YNC5QT_bbypar_-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:45.7

Plate Offsets (X, Y): [1:0-1-4,0-1-8], [3:0-1-4,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.91	Vert(LL)	-0.03	4-5	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.35	Vert(CT)	-0.06	5-6	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.10	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 74 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3 *Except* 6-1,4-3:2x6 SP No.2

BRACING
TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 4=0-5-8, 6=0-5-8
Max Horiz 6=148 (LC 11)
Max Uplift 4=-33 (LC 15), 6=-33 (LC 14)
Max Grav 4=584 (LC 21), 6=584 (LC 20)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-586/126, 2-3=-586/126, 1-6=-529/129, 3-4=-529/127
BOT CHORD 5-6=-184/342, 4-5=-123/322
WEBS 2-5=0/262, 1-5=-85/208, 3-5=-91/208

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-2-12 to 3-2-12, Exterior(2R) 3-2-12 to 9-9-4, Exterior(2E) 9-9-4 to 12-9-4 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
4) Unbalanced snow loads have been considered for this design.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 6 and 4. This connection is for uplift only and does not consider lateral forces.

LOAD CASE(S) Standard

March 25,2025

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	919 Serenity-Roof-B330 E BNS CP TMB GRH
25030124-01	EGE	Common Supported Gable	1	1	I72215049 Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 13:32:02 Page: 1
ID:hs_OLPz9_OqUDEXuG81pmYzF_Z1-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:42.4

Plate Offsets (X, Y): [6:0-2-8,Edge], [12:0-5-0,0-1-8], [19:0-5-0,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.17	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.08	Vert(CT)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.09	Horz(CT)	0.00	12	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MR								
BCDL	10.0										Weight: 81 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3
OTHERS 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS (size) 12=13-0-0, 13=13-0-0, 14=13-0-0, 15=13-0-0, 16=13-0-0, 17=13-0-0, 18=13-0-0, 19=13-0-0
Max Horiz 19=166 (LC 13)
Max Uplift 12=-36 (LC 11), 13=-116 (LC 15), 14=-86 (LC 15), 17=-84 (LC 14), 18=-120 (LC 14), 19=-54 (LC 10)
Max Grav 12=142 (LC 25), 13=182 (LC 26), 14=269 (LC 22), 15=198 (LC 22), 16=198 (LC 21), 17=269 (LC 21), 18=189 (LC 25), 19=156 (LC 26)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 2-19=-128/62, 1-2=0/37, 2-3=-110/103, 3-4=-72/76, 4-5=-89/196, 5-6=-74/153, 6-7=-73/153, 7-8=-89/196, 8-9=-59/76, 9-10=-90/81, 10-11=0/37, 10-12=-116/56
BOT CHORD 18-19=-78/157, 17-18=-78/157, 16-17=-78/157, 15-16=-78/157, 14-15=-78/157, 13-14=-78/157, 12-13=-78/157
WEBS 5-16=-166/9, 7-15=-166/0, 4-17=-226/166, 3-18=-155/153, 8-14=-226/165, 9-13=-150/160

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Corner(3E) -0-9-14 to 2-2-2, Exterior(2N) 2-2-2 to 3-6-0, Corner(3R) 3-6-0 to 9-6-0, Exterior(2N) 9-6-0 to 10-9-14, Corner(3E) 10-9-14 to 13-9-14 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
4) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
5) Unbalanced snow loads have been considered for this design.
6) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
7) All plates are 2x4 MT20 unless otherwise indicated.
8) Gable requires continuous bottom chord bearing.
9) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
10) Gable studs spaced at 2-0-0 oc.
11) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
12) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
13) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 54 lb uplift at joint 19, 36 lb uplift at joint 12, 84 lb uplift at joint 17, 120 lb uplift at joint 18, 86 lb uplift at joint 14 and 116 lb uplift at joint 13.

LOAD CASE(S) Standard

March 25,2025

ENGINEERING BY TRENCO A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	919 Serenity-Roof-B330 E BNS CP TMB GRH
25030124-01	F	Monopitch	6	1	I72215050 Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 13:32:03 Page: 1
ID:9J?nSM2QtleiTNQUoeql4rzF_lq-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:37.6

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.45	Vert(LL)	0.05	6-9	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.42	Vert(CT)	-0.08	6-9	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.51	Horz(CT)	0.01	5	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 49 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 5-8-1 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 8-3-12 oc bracing.

REACTIONS (size) 2=0-3-0, 5=0-1-8
Max Horiz 2=148 (LC 13)
Max Uplift 2=-184 (LC 10), 5=-169 (LC 10)
Max Grav 2=539 (LC 21), 5=555 (LC 21)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/17, 2-3=-952/493, 3-4=-104/66, 4-5=-184/101
BOT CHORD 2-6=-472/880, 5-6=-472/880
WEBS 3-6=-105/242, 3-5=-918/562

NOTES
1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior (1) 2-1-8 to 7-7-12, Exterior(2E) 7-7-12 to 10-7-12 zone; cantilever left and right exposed ; end vertical left and right exposed; porch left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
3) Unbalanced snow loads have been considered for this design.
4) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Bearings are assumed to be: , Joint 5 SP No.3 .
8) Bearing at joint(s) 5 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
9) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 2, 5.
10) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 2 and 5. This connection is for uplift only and does not consider lateral forces.

LOAD CASE(S) Standard

March 25,2025

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	919 Serenity-Roof-B330 E BNS CP TMB GRH
25030124-01	F1GE	Monopitch Supported Gable	1	1	I72215051 Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 13:32:03 Page: 1
ID:05Rb2nqdzWbg0FxJai2r9FzF_oh-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:25.4

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.16	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.11	Vert(CT)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	10.0										Weight: 14 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 3-7-8 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 2=3-5-8, 4=3-5-8, 5=3-5-8
Max Horiz 2=53 (LC 11)
Max Uplift 2=-50 (LC 10), 4=-255 (LC 21), 5=-87 (LC 14)
Max Grav 2=246 (LC 21), 4=53 (LC 14), 5=471 (LC 21)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/24, 2-3=-61/58, 3-4=-88/63, 3-5=-428/353
BOT CHORD 2-5=-15/66

NOTES
1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Corner(3E) -0-10-8 to 2-1-8, Exterior(2N) 2-1-8 to 3-7-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
4) Unbalanced snow loads have been considered for this design.
5) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
6) Gable studs spaced at 2-0-0 oc.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 255 lb uplift at joint 4, 50 lb uplift at joint 2 and 50 lb uplift at joint 2.

LOAD CASE(S) Standard

March 25,2025

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	919 Serenity-Roof-B330 E BNS CP TMB GRH
25030124-01	FGE	Monopitch Supported Gable	1	1	I72215052 Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 13:32:03 Page: 1
ID:_?Pus1XWS1h0GXUA82Y8iGzF_IC-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:35

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.18	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.06	Vert(CT)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.05	Horz(CT)	0.00	8	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 49 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3
OTHERS 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 2=10-7-8, 8=10-7-8, 9=10-7-8, 10=10-7-8, 11=10-7-8, 12=10-7-8
Max Horiz 2=148 (LC 13)
Max Uplift 2=-26 (LC 10), 8=-13 (LC 11), 9=-34 (LC 10), 10=-34 (LC 14), 11=-32 (LC 10), 12=-44 (LC 14)
Max Grav 2=155 (LC 21), 8=84 (LC 21), 9=227 (LC 21), 10=223 (LC 21), 11=189 (LC 21), 12=216 (LC 1)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/17, 2-3=-132/137, 3-4=-92/116, 4-5=-78/105, 5-6=-70/92, 6-7=-56/71, 7-8=-68/38
BOT CHORD 2-12=-46/82, 11-12=-46/82, 10-11=-46/82, 9-10=-46/82, 8-9=-46/82
WEBS 6-9=-186/114, 5-10=-181/133, 4-11=-159/123, 3-12=-164/143

NOTES
1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Corner(3E) -0-10-8 to 2-1-8, Exterior(2N) 2-1-8 to 7-7-12, Corner(3E) 7-7-12 to 10-7-12 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
4) Unbalanced snow loads have been considered for this design.
5) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
6) All plates are 2x4 MT20 unless otherwise indicated.
7) Gable studs spaced at 2-0-0 oc.
8) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
9) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 26 lb uplift at joint 2 and 26 lb uplift at joint 2.

LOAD CASE(S) Standard



March 25,2025

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	919 Serenity-Roof-B330 E BNS CP TMB GRH
25030124-01	G	Monopitch	9	1	I72215053 Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 13:32:03 Page: 1
ID:Dy_JjEEKvGAptckEgqDBdczF_tK-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:35

Plate Offsets (X, Y): [2:0-5-12,0-1-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.33	Vert(LL)	-0.06	8	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.39	Vert(CT)	-0.09	8	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.43	Horz(CT)	0.03	7	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	10.0										Weight: 41 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x6 SP No.2 *Except* 8-6:2x4 SP No.2
WEBS 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 4-8-12 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 7-10-7 oc bracing.

REACTIONS (size) 2=0-5-8, 7= Mechanical
Max Horiz 2=108 (LC 11)
Max Uplift 2=-75 (LC 10), 7=-67 (LC 14)
Max Grav 2=462 (LC 21), 7=478 (LC 21)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/17, 2-3=-1495/573, 3-4=-60/53, 4-5=-8/0, 4-7=-179/94
BOT CHORD 2-8=-600/1432, 7-8=-558/1308, 6-7=0/0
WEBS 3-8=-108/410, 3-7=-1332/607

NOTES
1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-10-8 to 1-11-13, Interior (1) 1-11-13 to 5-8-0, Exterior(2E) 5-8-0 to 8-8-0 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
3) Unbalanced snow loads have been considered for this design.
4) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Bearing at joint(s) 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 67 lb uplift at joint 7.
10) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 2. This connection is for uplift only and does not consider lateral forces.

LOAD CASE(S) Standard



March 25,2025

ENGINEERING BY TRENCO A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	919 Serenity-Roof-B330 E BNS CP TMB GRH
25030124-01	GSE	Monopitch Structural Gable	1	1	I72215054 Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 13:32:03 Page: 1
ID:j7LOAWWFe1s7RV5MhJbHFGzF_qO-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:35

Plate Offsets (X, Y): [2:0-5-12,0-1-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.23	Vert(LL)	-0.01	8-9	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.19	Vert(CT)	-0.03	8-9	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.22	Horz(CT)	0.00	8	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	10.0										Weight: 42 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x6 SP No.2 *Except* 9-7:2x4 SP No.2
WEBS 2x4 SP No.3
OTHERS 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 2=0-5-8, 8= Mechanical, 9=0-11-8
Max Horiz 2=108 (LC 11)
Max Uplift 2=-44 (LC 10), 8=-30 (LC 14), 9=-70 (LC 14)
Max Grav 2=242 (LC 21), 8=230 (LC 21), 9=468 (LC 21)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/17, 2-3=-162/58, 3-4=-59/41, 4-5=-39/45, 5-6=-8/0, 5-8=-136/67
BOT CHORD 2-9=-114/205, 8-9=-68/106, 7-8=0/0
WEBS 3-9=-339/189, 3-10=-103/104, 8-10=-115/113, 4-10=-62/52

NOTES
1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-10-8 to 1-11-13, Interior (1) 1-11-13 to 5-8-0, Exterior(2E) 5-8-0 to 8-8-0 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
4) Unbalanced snow loads have been considered for this design.
5) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
6) Gable studs spaced at 2-0-0 oc.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
9) Refer to girder(s) for truss to truss connections.
10) Bearing at joint(s) 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
11) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 30 lb uplift at joint 8 and 70 lb uplift at joint 9.
12) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 2. This connection is for uplift only and does not consider lateral forces.

LOAD CASE(S) Standard



March 25,2025

ENGINEERING BY TRENCO A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	919 Serenity-Roof-B330 E BNS CP TMB GRH
25030124-01	H1	Jack-Closed	3	1	I72215055 Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 13:32:03 Page: 1
ID:jzudvf5?HySB7qACgSkvP7y94VX-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f



Scale = 1:54.6

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.46	Vert(LL)	-0.16	4-5	>640	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.60	Vert(CT)	-0.32	4-5	>321	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.22	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 76 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3
OTHERS 2x6 SP No.2

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 1 Row at midpt 3-4

REACTIONS (size) 4=0-5-8, 5= Mechanical
Max Horiz 5=275 (LC 11)
Max Uplift 4=-146 (LC 14)
Max Grav 4=849 (LC 20), 5=390 (LC 20)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-5=-201/77, 1-2=-194/57, 2-3=-198/139, 3-4=-615/121
BOT CHORD 4-5=-131/297
WEBS 2-5=-218/191, 2-4=-298/210

NOTES
1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-1-12 to 3-1-12, Interior (1) 3-1-12 to 4-2-5, Exterior(2R) 4-2-5 to 8-5-4 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
3) Unbalanced snow loads have been considered for this design.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) All bearings are assumed to be User Defined .
7) Refer to girder(s) for truss to truss connections.
8) Bearing at joint(s) 4 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
9) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 4. This connection is for uplift only and does not consider lateral forces.
10) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 461 lb down and 113 lb up at 8-11-0 on top chord. The design/selection of such connection device(s) is the responsibility of others.
11) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard
1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-3=-60, 4-5=-20
Concentrated Loads (lb)
Vert: 3=-380 (F)

March 25,2025

ENGINEERING BY TRENCO A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	919 Serenity-Roof-B330 E BNS CP TMB GRH
25030124-01	H2	Jack-Closed	2	1	I72215056 Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 13:32:03 Page: 1
ID:A?EbZVSK3TRLQ4LGGcpFRfy94Xe-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:53

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.66	Vert(LL)	-0.25	4-5	>401	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.76	Vert(CT)	-0.50	4-5	>201	180		
TCDL	10.0	Rep Stress Incr	NO	WB	0.22	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	10.0										Weight: 74 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.1
WEBS 2x4 SP No.3
OTHERS 2x6 SP No.2

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 4= Mechanical, 5= Mechanical
Max Horiz 5=275 (LC 11)
Max Uplift 4=-149 (LC 14)
Max Grav 4=866 (LC 20), 5=380 (LC 20)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-5=-123/67, 1-2=-78/99, 2-3=-184/169, 3-4=-637/121
BOT CHORD 4-5=-142/282
WEBS 2-5=-296/127, 2-4=-302/235

NOTES
1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-1-12 to 3-1-12, Interior (1) 3-1-12 to 4-1-13, Exterior(2R) 4-1-13 to 8-5-4 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
3) Unbalanced snow loads have been considered for this design.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 149 lb uplift at joint 4.
8) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 461 lb down and 118 lb up at 8-5-4 on top chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard
1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-3=-60, 4-5=-20
Concentrated Loads (lb)
Vert: 3=-380

March 25,2025

ENGINEERING BY TRENCO A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	919 Serenity-Roof-B330 E BNS CP TMB GRH
25030124-01	I1	Monopitch	2	1	I72215057 Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 13:32:03 Page: 1
ID:TVTffuiZsp7mVnXghlb00Ay94Qs-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:61.1

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	1.00	Vert(LL)	-0.03	7-8	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.30	Vert(CT)	-0.04	7-8	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.50	Horz(CT)	0.01	7	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 80 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 1 Row at midpt 4-7

REACTIONS (size) 7= Mechanical, 9=0-5-8
Max Horiz 9=355 (LC 11)
Max Uplift 7=-156 (LC 11)
Max Grav 7=561 (LC 21), 9=488 (LC 21)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/35, 2-3=-375/95, 3-4=-208/189, 4-5=-17/0, 4-7=-238/80, 2-9=-444/145
BOT CHORD 8-9=-334/480, 7-8=-141/373, 6-7=0/0
WEBS 3-8=0/172, 3-7=-445/201, 2-8=-120/273

NOTES
1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-9-15 to 2-2-1, Interior (1) 2-2-1 to 7-2-0, Exterior(2E) 7-2-0 to 10-2-0 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60

2) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
3) Unbalanced snow loads have been considered for this design.
4) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 156 lb uplift at joint 7.

LOAD CASE(S) Standard



March 25,2025

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	919 Serenity-Roof-B330 E BNS CP TMB GRH
25030124-01	J1	Piggyback Base	1	1	I72215058 Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 13:32:03 Page: 1
ID:Nc3tSbUTdtzhFoU2aKqC93y92D7-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:69.2

Plate Offsets (X, Y): [4:0-3-12,0-1-12], [6:0-1-8,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.89	Vert(LL)	-0.20	6-8	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.95	Vert(CT)	-0.31	6-8	>682	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.50	Horz(CT)	0.01	6	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 154 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.2 *Except* 9-2,9-3,8-3:2x4 SP No.3
OTHERS 2x6 SP No.2

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (5-3-4 max.): 4-5.
BOT CHORD Rigid ceiling directly applied or 2-2-0 oc bracing.
WEBS 1 Row at midpt 5-6, 4-6, 3-9

REACTIONS (size) 6=0-5-8, 9=0-5-8
Max Horiz 9=304 (LC 14)
Max Uplift 6=-248 (LC 14), 9=-10 (LC 14)
Max Grav 6=1305 (LC 43), 9=955 (LC 44)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/37, 2-3=-249/125, 3-4=-800/100, 4-5=-31/1, 5-6=-778/145, 2-9=-309/141
BOT CHORD 8-9=-251/668, 6-8=-109/391
WEBS 4-6=-735/220, 3-9=-733/0, 4-8=-113/705, 3-8=-283/258

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior (1) 2-1-8 to 7-1-1, Exterior(2R) 7-1-1 to 14-4-4, Exterior(2E) 14-4-4 to 17-4-4 zone; cantilever left exposed ; end vertical left exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
4) Unbalanced snow loads have been considered for this design.
5) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
6) Provide adequate drainage to prevent water ponding.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
9) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 6 and 9. This connection is for uplift only and does not consider lateral forces.
10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
11) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 445 lb down and 70 lb up at 283568622 on top chord. The design/selection of such connection device(s) is the responsibility of others.
12) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard
1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-2=-60, 2-4=-60, 4-5=-60, 6-9=-20
Concentrated Loads (lb)
Vert: 5=-436 (F)

March 25,2025

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	919 Serenity-Roof-B330 E BNS CP TMB GRH
25030124-01	J1T	Piggyback Base	2	1	I72215059 Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 13:32:04 Page: 1

ID:Nc3tSbUTdtzhFoU2aKqC93y92D7-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:69.2

Plate Offsets (X, Y): [5:0-3-12,0-1-12], [7:0-1-12,0-2-12], [9:0-5-8,0-2-8], [11:0-2-12,0-3-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.86	Vert(LL)	-0.25	10-11	>839	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.82	Vert(CT)	-0.41	10-11	>502	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.47	Horz(CT)	0.03	7	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 179 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2 *Except* 12-3,9-8:2x4 SP No.3
WEBS 2x4 SP No.3 *Except* 9-5:2x4 SP No.2, 7-6:2x4 SP 2400F 2.0E
OTHERS 2x6 SP No.2

BRACING
TOP CHORD Structural wood sheathing directly applied or 5-8-4 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 5-6.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except:
6-0-0 oc bracing: 12-13.
WEBS 1 Row at midpt 6-7, 5-9

REACTIONS (size) 7=0-5-8, 13=0-5-8
Max Horiz 13=304 (LC 14)
Max Uplift 7=-244 (LC 14), 13=-10 (LC 14)
Max Grav 7=1273 (LC 43), 13=943 (LC 44)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/37, 2-3=-902/127, 3-4=-1016/252, 4-5=-678/86, 5-6=-159/34, 6-7=-1405/255, 2-13=-1016/148
BOT CHORD 12-13=-115/0, 11-12=0/40, 3-11=-252/157, 10-11=-255/705, 9-10=-111/456, 8-9=-16/19, 7-8=0/20
WEBS 4-11=-218/227, 4-10=-426/248, 5-10=-104/713, 5-9=-732/191, 7-9=-16/41, 6-9=-156/716, 11-13=-291/221, 2-11=-81/774

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-10-8 to 2-2-11, Interior (1) 2-2-11 to 6-9-12, Exterior(2R) 6-9-12 to 14-2-8, Exterior (2E) 14-2-8 to 17-2-8 zone; cantilever left exposed ; end vertical left exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
4) Unbalanced snow loads have been considered for this design.
5) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
6) Provide adequate drainage to prevent water ponding.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
9) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 7 and 13. This connection is for uplift only and does not consider lateral forces.
10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
11) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 523 lb down and 69 lb up at 17-2-8, and 445 lb down and 70 lb up at 283568622 on top chord. The design/selection of such connection device(s) is the responsibility of others.
12) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard
1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-2=-60, 2-5=-60, 5-6=-60, 12-13=-20, 9-11=-20, 7-8=-20
Concentrated Loads (lb)
Vert: 6=-436 (F)

March 25,2025

ENGINEERING BY TRENCO A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	919 Serenity-Roof-B330 E BNS CP TMB GRH
25030124-01	J02	Jack-Closed	3	1	I72215060 Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 13:32:04 Page: 1
ID:5qqplGlqPiFCjIDmL6TpVlypb7j-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:26.2

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.22	Vert(LL)	0.00	4-7	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.06	Vert(CT)	0.00	4-7	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.00	2	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	10.0										Weight: 16 lb	FT = 20%

LUMBER
TOP CHORD 2x6 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 2-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 2=0-5-8, 4= Mechanical
Max Horiz 2=57 (LC 13)
Max Uplift 2=-80 (LC 14), 4=-38 (LC 20)
Max Grav 2=417 (LC 21), 4=34 (LC 10)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/89, 2-3=-166/185, 3-4=-62/32
BOT CHORD 2-4=-161/133

NOTES
1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
3) Unbalanced snow loads have been considered for this design.
4) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Bearings are assumed to be: Joint 2 User Defined .
8) Refer to girder(s) for truss to truss connections.
9) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 4 and 2. This connection is for uplift only and does not consider lateral forces.

LOAD CASE(S) Standard

March 25,2025

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	919 Serenity-Roof-B330 E BNS CP TMB GRH
25030124-01	J02A	Jack-Closed	3	1	I72215061 Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 13:32:04 Page: 1
ID:VtS5FgNOjBLcVXLp15PXlDypb8C-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:25.7

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.08	Vert(LL)	0.00	4-7	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.03	Vert(CT)	0.00	4-7	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.00	2	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	10.0										Weight: 9 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 2-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 2=0-5-8, 4= Mechanical
Max Horiz 2=48 (LC 13)
Max Uplift 2=-26 (LC 14), 4=-14 (LC 14)
Max Grav 2=192 (LC 21), 4=81 (LC 21)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/34, 2-3=-62/65, 3-4=-65/37
BOT CHORD 2-4=-36/50

NOTES
1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
3) Unbalanced snow loads have been considered for this design.
4) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Bearings are assumed to be: Joint 2 User Defined .
8) Refer to girder(s) for truss to truss connections.
9) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 4. This connection is for uplift only and does not consider lateral forces.
10) H10A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 2. This connection is for uplift only and does not consider lateral forces.

LOAD CASE(S) Standard

March 25,2025

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	919 Serenity-Roof-B330 E BNS CP TMB GRH
25030124-01	K1	Roof Special	5	1	I72215062 Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 13:32:04 Page: 1
ID:jzudvf5?HySB7qACgSkvP7y94VX-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f



Scale = 1:50.9

Plate Offsets (X, Y): [3:0-4-4,Edge], [4:0-2-8,0-0-14]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.56	Vert(LL)	-0.05	5	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.38	Vert(CT)	-0.08	5-6	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.49	Horz(CT)	0.06	4	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	10.0										Weight: 48 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
WEBS	2x4 SP No.3
OTHERS	2x6 SP No.2

BRACING

TOP CHORD	Structural wood sheathing directly applied or 4-9-8 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS (size) 4=0-5-8, 6=0-5-8
Max Horiz 6=-200 (LC 10)
Max Uplift 4=-30 (LC 15), 6=-70 (LC 15)
Max Grav 4=371 (LC 21), 6=445 (LC 21)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD	1-6=-208/158, 1-2=-171/96, 2-3=-1308/91, 3-4=-318/46
BOT CHORD	5-6=-49/947, 4-5=-59/28
WEBS	2-6=-966/223, 2-5=0/560, 3-5=-50/1183

NOTES

1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-1-12 to 3-1-12, Interior (1) 3-1-12 to 4-9-7, Exterior(2E) 4-9-7 to 7-10-4 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60

2) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
3) Unbalanced snow loads have been considered for this design.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Bearing at joint(s) 4 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
7) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 6 and 4. This connection is for uplift only and does not consider lateral forces.

LOAD CASE(S) Standard

March 25,2025

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	919 Serenity-Roof-B330 E BNS CP TMB GRH
25030124-01	L01	Common Girder	1	**2**	I72215063 Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 13:32:04 Page: 1
ID:22T36Dt8B0CinE4y4jVg5VypZpe-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:46.6

Plate Offsets (X, Y): [6:0-8-0,0-8-0], [7:0-8-0,0-8-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.27	Vert(LL)	-0.04	6-7	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.29	Vert(CT)	-0.08	6-7	>999	180		
TCDL	10.0	Rep Stress Incr	NO	WB	0.61	Horz(CT)	0.01	5	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 226 lb	FT = 20%

LUMBER
TOP CHORD 2x6 SP No.2
BOT CHORD 2x10 SP 2400F 2.0E
WEBS 2x4 SP No.2 *Except* 6-4,7-2:2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 5-7-1 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 1=0-5-8, 5=0-5-8
Max Horiz 1=-124 (LC 36)
Max Grav 1=8010 (LC 5), 5=6474 (LC 6)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-7515/0, 2-3=-7402/0, 3-4=-7287/0, 4-5=-7409/0
BOT CHORD 1-7=0/5701, 6-7=0/4092, 5-6=0/5606
WEBS 3-6=0/4630, 4-6=-40/245, 3-7=0/4892, 2-7=-62/232

NOTES
1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
Bottom chords connected as follows: 2x10 - 4 rows staggered at 0-9-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) Unbalanced roof live loads have been considered for this design.
4) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
5) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
6) Unbalanced snow loads have been considered for this design.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
9) Use Simpson Strong-Tie HTU28 (20-16d Girder, 26-10dx1 1/2 Truss, Single Ply Girder) or equivalent spaced at 2-0-0 oc max. starting at 0-8-0 from the left end to 10-8-0 to connect truss(es) to back face of bottom chord.
10) Fill all nail holes where hanger is in contact with lumber.

LOAD CASE(S) Standard
1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-3=-60, 3-5=-60, 8-11=-20
Concentrated Loads (lb)
Vert: 7=-1909 (B), 10=-1912 (B), 16=-1909 (B), 17=-1909 (B), 18=-1909 (B), 19=-1909 (B)

March 25,2025

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	919 Serenity-Roof-B330 E BNS CP TMB GRH
25030124-01	L02	Common Supported Gable	1	1	I72215064 Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 13:32:04 Page: 1
ID:VKOF62y3jk3RPIlH2yoZM2ypb8k-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:41.8

Plate Offsets (X, Y): [6:0-2-8,Edge], [12:0-5-0,0-1-8], [19:0-5-0,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.16	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.08	Vert(CT)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.07	Horz(CT)	0.00	12	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MR								
BCDL	10.0										Weight: 82 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3
OTHERS 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS (size) 12=12-8-0, 13=12-8-0, 14=12-8-0, 15=12-8-0, 16=12-8-0, 17=12-8-0, 18=12-8-0, 19=12-8-0
Max Horiz 19=-164 (LC 12)
Max Uplift 12=-26 (LC 11), 13=-122 (LC 15), 14=-72 (LC 15), 17=-70 (LC 14), 18=-125 (LC 14), 19=-41 (LC 10)
Max Grav 12=158 (LC 25), 13=217 (LC 22), 14=221 (LC 22), 15=137 (LC 22), 16=137 (LC 21), 17=221 (LC 21), 18=218 (LC 25), 19=170 (LC 26)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 2-19=-140/110, 1-2=0/39, 2-3=-107/91, 3-4=-79/138, 4-5=-114/240, 5-6=-84/165, 6-7=-84/165, 7-8=-115/239, 8-9=-79/139, 9-10=-93/74, 10-11=0/39, 10-12=-135/105
BOT CHORD 18-19=-74/142, 17-18=-74/142, 16-17=-74/142, 15-16=-74/142, 14-15=-74/142, 13-14=-74/142, 12-13=-74/142
WEBS 5-16=-126/21, 7-15=-125/21, 4-17=-188/144, 3-18=-184/176, 8-14=-188/143, 9-13=-180/182

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Corner(3E) -0-10-8 to 2-4-0, Exterior(2N) 2-4-0 to 3-4-0, Corner(3R) 3-4-0 to 9-4-0, Exterior(2N) 9-4-0 to 10-4-0, Corner(3E) 10-4-0 to 13-6-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
4) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
5) Unbalanced snow loads have been considered for this design.
6) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
7) All plates are 2x4 MT20 unless otherwise indicated.
8) Gable requires continuous bottom chord bearing.
9) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
10) Gable studs spaced at 2-0-0 oc.
11) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
12) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
13) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 41 lb uplift at joint 19, 26 lb uplift at joint 12, 70 lb uplift at joint 17, 125 lb uplift at joint 18, 72 lb uplift at joint 14 and 122 lb uplift at joint 13.

LOAD CASE(S) Standard



March 25,2025

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	919 Serenity-Roof-B330 E BNS CP TMB GRH
25030124-01	M01	Common Girder	1	2	I72215065 Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 13:32:05 Page: 1

ID:bqiN8p7pNAdJ5qliznrIdjypZmk-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:84.1

Plate Offsets (X, Y): [1:Edge,0-3-11], [3:0-2-4,0-3-0], [7:0-3-8,0-3-0], [13:Edge,0-3-11], [16:0-5-8,0-1-8], [17:0-8-0,0-7-12], [24:0-8-0,0-7-4]

Loading	(psf)	Spacing	1-11-4	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.93	Vert(LL)	-0.06	15-16	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.30	Vert(CT)	-0.11	15-16	>999	180		
TCDL	10.0	Rep Stress Incr	NO	WB	0.68	Horz(CT)	0.01	1	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 567 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x10 SP 2400F 2.0E
WEBS	2x4 SP No.3 *Except* 24-3,17-7:2x4 SP 2400F 2.0E
OTHERS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 4-2-15 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 23-24,22-23,21-22.
JOINTS	1 Brace at Jt(s): 25, 26

REACTIONS (size) 1=0-5-8, 13=0-5-8, 21=0-5-8
Max Horiz 1=244 (LC 9)
Max Uplift 1=-605 (LC 12)
Max Grav 1=4270 (LC 5), 13=5443 (LC 22), 21=11033 (LC 21)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD	1-2=-2110/549, 2-4=-2016/2130, 4-5=-171/38, 5-6=-167/47, 6-8=-3017/2035, 8-9=-3171/0, 9-10=-4149/0, 10-11=-4151/0, 11-12=-4729/0, 12-13=-4654/0
BOT CHORD	1-24=-553/1624, 23-24=-406/136, 22-23=-406/134, 21-22=-406/134, 20-21=0/669, 18-20=0/669, 17-18=0/674, 16-17=0/3517, 15-16=0/3517, 14-15=0/3517, 13-14=0/3517
WEBS	3-24=-459/4979, 2-24=-256/177, 3-25=-3374/375, 21-25=-3728/410, 21-26=-5158/0, 7-26=-4681/0, 7-27=0/6210, 17-27=0/6344, 17-28=-2590/0, 10-28=-1824/0, 4-25=-1514/0, 22-25=-1118/0, 3-23=0/549, 6-26=-1396/0, 20-26=-883/0, 7-18=0/1034, 8-27=0/228, 9-28=0/1548, 16-28=0/2417, 11-15=0/858, 12-14=-192/89, 4-6=0/1666

NOTES

1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2x10 - 3 rows staggered at 0-5-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) Unbalanced roof live loads have been considered for this design.
4) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
5) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
6) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
7) Unbalanced snow loads have been considered for this design.
8) Gable studs spaced at 2-0-0 oc.
9) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
10) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
11) LGT2 Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 1. This connection is for uplift only and does not consider lateral forces.
12) Use Simpson Strong-Tie LUS26 (4-10d Girder, 3-10d Truss, Single Ply Girder) or equivalent spaced at 2-0-0 oc max. starting at 18-10-3 from the left end to 20-10-3 to connect truss(es) to front face of bottom chord.
13) Use Simpson Strong-Tie HTU26 (10-16d Girder, 14-10dx1 1/2 Truss) or equivalent spaced at 2-0-0 oc max. starting at 0-6-0 from the left end to 8-6-0 to connect truss(es) to back face of bottom chord.



March 25,2025

Continued on page 2

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

14) Use Simpson Strong-Tie LUS26 (4-10d Girder, 3-10d Truss, Single Ply Girder) or equivalent spaced at 2-0-0 oc max. starting at 10-6-0 from the left end to 18-6-0 to connect truss(es) to back face of bottom chord.
15) Use Simpson Strong-Tie HGUS28-2 (36-10d Girder, 12-10d Truss) or equivalent at 19-5-0 from the left end to connect truss(es) to back face of bottom chord.
16) Use Simpson Strong-Tie HTU26 (20-10d Girder, 14-10dx1 1/2 Truss, Single Ply Girder) or equivalent spaced at 2-1-8 oc max. starting at 20-4-8 from the left end to 24-6-0 to connect truss(es) to back face of bottom chord.
17) Fill all nail holes where hanger is in contact with lumber.
18) "NAILED" indicates 3-10d (0.148"x3") or 3-12d (0.148"x3.25") toe-nails per NDS guidlines.
19) LGT2 Hurricane ties must have two studs in line below the truss.

LOAD CASE(S) Standard

1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
   Uniform Loads (lb/ft)
   Vert: 1-5=-58, 5-13=-58, 29-32=-19
   Concentrated Loads (lb)
   Vert: 24=-1415 (B), 17=-2285 (B), 20=4 (F), 18=4 (F), 16=-61 (F), 15=-61 (F), 14=-61 (F), 31=-1424 (B), 35=-1415 (B), 36=-1415 (B), 37=-1415 (B), 38=-370 (B), 39=-370 (B), 40=-370 (B), 41=-360 (B), 42=-360 (B), 43=4 (F), 44=-1814 (B), 45=-1814 (B), 46=-1814 (B)

Job	Truss	Truss Type	Qty	Ply	919 Serenity-Roof-B330 E BNS CP TMB GRH
25030124-01	PB1	Piggyback	15	1	I72215066 Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 13:32:05 Page: 1
ID:iEW3YzpCkaFU49jPj8F7u4y94Qj-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:33.4

Plate Offsets (X, Y): [2:0-2-13,0-1-8], [4:0-2-13,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.47	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.45	Vert(CT)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.03	Horz(CT)	0.00	2	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	10.0										Weight: 37 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 2=9-0-0, 4=9-0-0, 6=9-0-0
Max Horiz 2=87 (LC 13)
Max Uplift 2=-48 (LC 14), 4=-59 (LC 15)
Max Grav 2=358 (LC 21), 4=358 (LC 22), 6=288 (LC 21)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/16, 2-3=-266/124, 3-4=-266/124, 4-5=0/16
BOT CHORD 2-6=-41/118, 4-6=-29/118
WEBS 3-6=-102/2

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-3-1 to 3-3-1, Exterior(2R) 3-3-1 to 7-1-9, Exterior(2E) 7-1-9 to 10-1-9 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
4) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
5) Unbalanced snow loads have been considered for this design.
6) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
7) Gable requires continuous bottom chord bearing.
8) Gable studs spaced at 4-0-0 oc.
9) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
10) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
11) N/A
12) See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

LOAD CASE(S) Standard

NORTH CAROLINA PROFESSIONAL SEAL 45844 ENGINEER ANDREW JOHNSON

March 25,2025

ENGINEERING BY TRENCO A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	919 Serenity-Roof-B330 E BNS CP TMB GRH
25030124-01	PB1GR	Piggyback	3	2	I72215067 Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 13:32:05 Page: 1
ID:nQ3TCLvnvyfTTDuVPZSo4yy90TY-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:33.4

Plate Offsets (X, Y): [2:0-5-0,0-0-14], [4:0-5-0,0-0-14]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.24	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.22	Vert(CT)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.01	Horz(CT)	0.00	2	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	10.0										Weight: 74 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 2=9-0-0, 4=9-0-0, 6=9-0-0
Max Horiz 2=-87 (LC 12)
Max Uplift 2=-48 (LC 14), 4=-59 (LC 15)
Max Grav 2=357 (LC 21), 4=357 (LC 22), 6=289 (LC 21)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/16, 2-3=-265/124, 3-4=-265/124, 4-5=0/16
BOT CHORD 2-6=-51/145, 4-6=-35/145
WEBS 3-6=-104/2

NOTES
1) 2-ply truss to be connected together as follows:
Top chords connected with 10d (0.131"x3") nails as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected with 10d (0.131"x3") nails as follows: 2x4 - 1 row at 0-9-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) Unbalanced roof live loads have been considered for this design.
4) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-3-1 to 3-3-1, Exterior(2R) 3-3-1 to 7-1-9, Exterior(2E) 7-1-9 to 10-1-9 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
5) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
6) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
7) Unbalanced snow loads have been considered for this design.
8) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
9) Gable requires continuous bottom chord bearing.
10) Gable studs spaced at 4-0-0 oc.
11) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
12) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
13) N/A
14) See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

LOAD CASE(S) Standard

March 25,2025

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	919 Serenity-Roof-B330 E BNS CP TMB GRH
25030124-01	PB2	Piggyback	2	1	I72215068 Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 13:32:05 Page: 1
ID:Rmslk9DbSapxNulK2kUs_ty916S-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:33.4

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.11	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.09	Vert(CT)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.06	Horz(CT)	0.00	6	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	10.0										Weight: 42 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 2=9-0-0, 6=9-0-0, 8=9-0-0, 9=9-0-0, 10=9-0-0
Max Horiz 2=-87 (LC 12)
Max Uplift 2=-8 (LC 15), 8=-97 (LC 15), 10=-98 (LC 14)
Max Grav 2=170 (LC 21), 6=170 (LC 22), 8=344 (LC 22), 9=100 (LC 28), 10=344 (LC 21)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/16, 2-3=-76/58, 3-4=-107/97, 4-5=-107/97, 5-6=-67/52, 6-7=0/16
BOT CHORD 2-10=-25/76, 9-10=-25/76, 8-9=-25/76, 6-8=-25/76
WEBS 4-9=-69/7, 3-10=-266/150, 5-8=-266/150

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-3-1 to 3-2-5, Exterior(2R) 3-2-5 to 7-2-5, Exterior(2E) 7-2-5 to 10-1-9 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
4) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
5) Unbalanced snow loads have been considered for this design.
6) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
7) Gable requires continuous bottom chord bearing.
8) Gable studs spaced at 2-0-0 oc.
9) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
10) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
11) N/A
12) See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

LOAD CASE(S) Standard

March 25,2025

ENGINEERING BY TRENCO A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	919 Serenity-Roof-B330 E BNS CP TMB GRH
25030124-01	PB3	Piggyback	3	1	I72215069 Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 13:32:05 Page: 1
ID:0KFbCGKRzmVpAJmH?1sNG4ypb9Y-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:39.3

Plate Offsets (X, Y): [2:0-2-13,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.30	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.28	Vert(CT)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.05	Horz(CT)	0.00	2	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	10.0										Weight: 28 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3
OTHERS 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 2=5-11-3, 5=5-11-3, 6=5-11-3
Max Horiz 2=121 (LC 13)
Max Uplift 2=-15 (LC 14), 5=-105 (LC 25), 6=-47 (LC 14)
Max Grav 2=194 (LC 21), 5=21 (LC 11), 6=373 (LC 25)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/16, 2-3=-122/105, 3-4=-54/89, 4-5=-45/69
BOT CHORD 2-6=-44/105, 5-6=-37/54
WEBS 3-6=-218/64

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-3-1 to 3-3-1, Exterior(2R) 3-3-1 to 5-2-5, Exterior(2E) 5-2-5 to 5-11-4 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
4) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
5) Unbalanced snow loads have been considered for this design.
6) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
7) Gable requires continuous bottom chord bearing.
8) Gable studs spaced at 4-0-0 oc.
9) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
10) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
11) N/A
12) See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

LOAD CASE(S) Standard

March 25,2025

ENGINEERING BY TRENCO A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	919 Serenity-Roof-B330 E BNS CP TMB GRH
25030124-01	V03	Valley	1	1	I72215070 Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 E Dec 5 2024 Print: 8.730 E Dec 5 2024 MiTek Industries, Inc. Tue Mar 25 14:59:35 Page: 1
ID:gMSi8YGJ8DtW4YuKCUHCZ1ypb9d-fyhn1WjBsWheMSrn2NN05PAtgfmKAUhcugYYhyzXWuO



Scale = 1:24.3

Plate Offsets (X, Y): [2:0-2-8,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.10	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.09	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.00	Horiz(TL)	0.00	3	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	10.0										Weight: 11 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2

BRACING
TOP CHORD Structural wood sheathing directly applied or 3-8-7 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 1=148/3-8-7, 3=148/3-8-7
Max Horiz 1=32 (LC 11)
Max Uplift 1=-12 (LC 14), 3=-12 (LC 15)
Max Grav 1=174 (LC 20), 3=174 (LC 21)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-227/85, 2-3=-127/61
BOT CHORD 1-3=-52/165

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
4) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
5) Unbalanced snow loads have been considered for this design.
6) Gable requires continuous bottom chord bearing.
7) Gable studs spaced at 4-0-0 oc.
8) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
9) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 12 lb uplift at joint 1 and 12 lb uplift at joint 3.

LOAD CASE(S) Standard

March 25,2025

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	919 Serenity-Roof-B330 E BNS CP TMB GRH
25030124-01	V06	Valley	1	1	I72215071 Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 13:32:06 Page: 1
ID:FnmZWXEQrIVxD49lXMjVxOypb9g-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:27.5

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.18	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.20	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.07	Horiz(TL)	0.00	4	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	10.0										Weight: 23 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-3-6 oc purlins.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS (size) 1=6-3-15, 3=6-3-15, 4=6-3-15
Max Horiz 1=-57 (LC 12)
Max Uplift 1=-3 (LC 21), 3=-3 (LC 10), 4=-56 (LC 14)
Max Grav 1=99 (LC 20), 3=99 (LC 21), 4=438 (LC 21)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-87/180, 2-3=-87/180
BOT CHORD 1-4=-144/131, 3-4=-144/131
WEBS 2-4=-341/163

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
4) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
5) Unbalanced snow loads have been considered for this design.
6) Gable requires continuous bottom chord bearing.
7) Gable studs spaced at 4-0-0 oc.
8) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
9) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 3 lb uplift at joint 1, 3 lb uplift at joint 3 and 56 lb uplift at joint 4.
11) Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 1, 3.

LOAD CASE(S) Standard



March 25,2025

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	919 Serenity-Roof-B330 E BNS CP TMB GRH
25030124-01	V07	Valley	1	1	I72215072
					Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 13:32:06 Page: 1
ID:JPfp5rCAKhFEzn?MPxh1szypb9i-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:29.3

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.26	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.27	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.09	Horiz(TL)	0.00	4	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	10.0										Weight: 27 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 7-3-10 oc purlins.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS (size) 1=7-3-10, 3=7-3-10, 4=7-3-10
Max Horiz 1=67 (LC 13)
Max Uplift 1=-19 (LC 21), 3=-19 (LC 20), 4=-75 (LC 14)
Max Grav 1=105 (LC 20), 3=105 (LC 21), 4=540 (LC 20)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-90/233, 2-3=-90/233
BOT CHORD 1-4=-182/153, 3-4=-182/153
WEBS 2-4=-428/202

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-0-5 to 3-0-5, Exterior(2R) 3-0-5 to 4-3-15, Exterior(2E) 4-3-15 to 7-3-15 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
4) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
5) Unbalanced snow loads have been considered for this design.
6) Gable requires continuous bottom chord bearing.
7) Gable studs spaced at 4-0-0 oc.
8) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
9) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 19 lb uplift at joint 1, 19 lb uplift at joint 3 and 75 lb uplift at joint 4.

LOAD CASE(S) Standard

March 25,2025

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	919 Serenity-Roof-B330 E BNS CP TMB GRH
25030124-01	V09	Valley	1	1	I72215073 Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 13:32:06 ID:N0X2g9Bwo4?WkTszIWeZmYypb9k-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:33.6

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.48	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.45	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.20	Horiz(TL)	0.01	4	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 38 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 9-10-9 oc purlins.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS (size) 1=9-10-9, 3=9-10-9, 4=9-10-9
Max Horiz 1=-93 (LC 12)
Max Uplift 1=-56 (LC 21), 3=-56 (LC 20), 4=-114 (LC 14)
Max Grav 1=94 (LC 20), 3=94 (LC 21), 4=804 (LC 20)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-120/392, 2-3=-120/392
BOT CHORD 1-4=-256/178, 3-4=-256/178
WEBS 2-4=-664/280

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-0-5 to 3-0-5, Exterior(2R) 3-0-5 to 6-10-14, Exterior(2E) 6-10-14 to 9-10-14 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
4) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
5) Unbalanced snow loads have been considered for this design.
6) Gable requires continuous bottom chord bearing.
7) Gable studs spaced at 4-0-0 oc.
8) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
9) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 56 lb uplift at joint 1, 56 lb uplift at joint 3 and 114 lb uplift at joint 4.

LOAD CASE(S) Standard



March 25,2025

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	919 Serenity-Roof-B330 E BNS CP TMB GRH
25030124-01	V10	Valley	1	1	I72215074
					Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 13:32:06 Page: 1
ID:FzBHp5cRse4BbFmx28JXNeypbAT-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:39.7

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.33	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.13	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.09	Horiz(TL)	0.00	5	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 44 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 1=10-10-14, 5=10-10-14, 6=10-10-14, 7=10-10-14, 8=10-10-14
Max Horiz 1=102 (LC 11)
Max Uplift 1=-49 (LC 12), 5=-37 (LC 21), 6=-133 (LC 15), 8=-139 (LC 14)
Max Grav 1=70 (LC 11), 5=61 (LC 15), 6=450 (LC 21), 7=248 (LC 20), 8=454 (LC 20)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-138/105, 2-3=-227/105, 3-4=-227/106, 4-5=-116/75
BOT CHORD 1-8=-39/70, 7-8=-20/70, 6-7=-20/70, 5-6=-49/71
WEBS 3-7=-159/7, 2-8=-474/271, 4-6=-473/264

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-0-5 to 3-0-5, Exterior(2R) 3-0-5 to 7-6-10, Exterior(2E) 7-6-10 to 10-6-10 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
4) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
5) Unbalanced snow loads have been considered for this design.
6) Gable requires continuous bottom chord bearing.
7) Gable studs spaced at 4-0-0 oc.
8) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
9) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 49 lb uplift at joint 1, 37 lb uplift at joint 5, 139 lb uplift at joint 8 and 133 lb uplift at joint 6.

LOAD CASE(S) Standard

March 25,2025

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	919 Serenity-Roof-B330 E BNS CP TMB GRH
25030124-01	V13	Valley	1	1	I72215075 Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 13:32:06 Page: 1
ID:u0OOmNZI25RuVUt_FbjMgaypbAY-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:41.7

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.33	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.12	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.11	Horiz(TL)	0.00	5	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 57 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS (size) 1=13-5-12, 5=13-5-12, 6=13-5-12, 7=13-5-12, 8=13-5-12
Max Horiz 1=-128 (LC 12)
Max Uplift 1=-27 (LC 10), 6=-145 (LC 15), 8=-149 (LC 14)
Max Grav 1=112 (LC 30), 5=89 (LC 24), 6=441 (LC 21), 7=283 (LC 21), 8=441 (LC 20)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-140/116, 2-3=-196/115, 3-4=-196/114, 4-5=-111/77
BOT CHORD 1-8=-46/109, 7-8=-46/88, 6-7=-46/88, 5-6=-46/88
WEBS 3-7=-200/0, 2-8=-376/193, 4-6=-376/193

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-0-5 to 2-9-3, Interior (1) 2-9-3 to 3-9-3, Exterior(2R) 3-9-3 to 9-9-3, Interior (1) 9-9-3 to 10-6-1, Exterior(2E) 10-6-1 to 13-6-1 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
4) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
5) Unbalanced snow loads have been considered for this design.
6) Gable requires continuous bottom chord bearing.
7) Gable studs spaced at 4-0-0 oc.
8) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
9) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 27 lb uplift at joint 1, 149 lb uplift at joint 8 and 145 lb uplift at joint 6.

LOAD CASE(S) Standard



March 25,2025

ENGINEERING BY TRENCO A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	919 Serenity-Roof-B330 E BNS CP TMB GRH
25030124-01	V17	Valley	1	1	I72215076 Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 13:32:06 Page: 1
ID:URiG8MWQlA3Je09PaT9f2yypbAb-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:51

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.36	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.19	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.29	Horiz(TL)	0.00	5	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 76 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS (size) 1=17-1-9, 5=17-1-9, 6=17-1-9, 8=17-1-9, 9=17-1-9
Max Horiz 1=162 (LC 11)
Max Uplift 1=-21 (LC 10), 6=-184 (LC 15), 9=-188 (LC 14)
Max Grav 1=119 (LC 25), 5=82 (LC 21), 6=524 (LC 25), 8=511 (LC 24), 9=531 (LC 24)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-147/268, 2-3=-98/200, 3-4=-98/181, 4-5=-109/235
BOT CHORD 1-9=-143/133, 8-9=-143/133, 6-8=-143/133, 5-6=-143/133
WEBS 3-8=-328/0, 2-9=-399/222, 4-6=-398/221

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-0-0 to 3-0-0, Interior (1) 3-0-0 to 5-6-12, Exterior(2R) 5-6-12 to 11-6-12, Interior (1) 11-6-12 to 13-8-11, Exterior(2E) 13-8-11 to 16-8-11 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
4) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
5) Unbalanced snow loads have been considered for this design.
6) Gable requires continuous bottom chord bearing.
7) Gable studs spaced at 4-0-0 oc.
8) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
9) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 21 lb uplift at joint 1, 188 lb uplift at joint 9 and 184 lb uplift at joint 6.
11) Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 1, 5.

LOAD CASE(S) Standard

March 25,2025

ENGINEERING BY TRENCO A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	919 Serenity-Roof-B330 E BNS CP TMB GRH
25030124-01	V20	Valley	1	1	I72215077 Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 13:32:06 ID:bfTll_TvhyZu9PreLd5jt6ypbAf-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:56.9

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.31	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.17	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.19	Horiz(TL)	0.01	7	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 100 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 1 Row at midpt 4-11

REACTIONS (size) 1=20-8-12, 7=20-8-12, 8=20-8-12, 10=20-8-12, 11=20-8-12, 12=20-8-12, 13=20-8-12
Max Horiz 1=198 (LC 11)
Max Uplift 1=-50 (LC 10), 7=-15 (LC 13), 8=-102 (LC 15), 10=-175 (LC 15), 12=-174 (LC 14), 13=-108 (LC 14)
Max Grav 1=132 (LC 25), 7=94 (LC 32), 8=339 (LC 30), 10=477 (LC 6), 11=396 (LC 27), 12=477 (LC 5), 13=347 (LC 24)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-210/163, 2-3=-174/125, 3-4=-198/175, 4-5=-198/149, 5-6=-129/73, 6-7=-168/100
BOT CHORD 1-13=-68/145, 12-13=-68/145, 11-12=-68/145, 10-11=-68/145, 8-10=-68/145, 7-8=-68/145
WEBS 4-11=-195/6, 3-12=-377/223, 2-13=-255/159, 5-10=-378/223, 6-8=-254/156

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-0-0 to 3-0-0, Interior (1) 3-0-0 to 7-4-6, Exterior(2R) 7-4-6 to 13-4-6, Interior (1) 13-4-6 to 17-3-15, Exterior(2E) 17-3-15 to 20-3-15 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
4) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
5) Unbalanced snow loads have been considered for this design.
6) All plates are 2x4 MT20 unless otherwise indicated.
7) Gable requires continuous bottom chord bearing.
8) Gable studs spaced at 4-0-0 oc.
9) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
10) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
11) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 50 lb uplift at joint 1, 15 lb uplift at joint 7, 174 lb uplift at joint 12, 108 lb uplift at joint 13, 175 lb uplift at joint 10 and 102 lb uplift at joint 8.
12) Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 1, 7.

LOAD CASE(S) Standard



March 25,2025

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Symbols

PLATE LOCATION AND ORIENTATION



Center plate on joint unless x, y offsets are indicated. Dimensions are in ft-in-sixteenths. Apply plates to both sides of truss and fully embed teeth.



For 4 x 2 orientation, locate plates 0- 1/16" from outside edge of truss.

This symbol indicates the required direction of slots in connector plates.

* Plate location details available in MiTek software or upon request.

PLATE SIZE

4 x 4

The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T or I bracing if indicated.

BEARING



Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number/letter where bearings occur. Min size shown is for crushing only.

Industry Standards:

ANSI/TPI1: National Design Specification for Metal Plate Connected Wood Truss Construction.
DSB-22: Design Standard for Bracing.
BCSI: Building Component Safety Information, Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses.

Numbering System



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

Product Code Approvals

ICC-ES Reports:

ESR-1988, ESR-2362, ESR-2685, ESR-3282
ESR-4722, ESL-1388

Design General Notes

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.

Lumber design values are in accordance with ANSI/TPI 1 section 6.3 These truss designs rely on lumber values established by others.

MiTek®

ENGINEERING BY TRENCO
A MiTek Affiliate

MiTek Engineering Reference Sheet: MII-7473 rev. 1/2/2023

General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor I bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TPI 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TPI 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TPI 1 Quality Criteria.
21. The design does not take into account any dynamic or other loads other than those expressly stated.