

Mark Morris, P.E.

#126, 1317-M, Summerville, SC 29483

843 209-5784, Fax (866)-213-4614

The truss drawing(s) listed below have been prepared by **Atlantic Building Components** under my direct supervision based on the parameters provided by the truss designers.

AST #: 58885

JOB: 25-3719-F01

JOB NAME: LOT 0.0019 CAMPBELL RIDGE

Wind Code: N/A

Wind Speed: Vult= N/A

Exposure Category: N/A

Mean Roof Height (feet): N/A

These truss designs comply with IRC 2015 as well as IRC 2018.

17 Truss Design(s)

Trusses:

F101, F102, F102A, F103, F104, F105, F106, F107, F107A, F108, F109, F110, F111, F112,



4/25/2025

Mark Morris

My license renewal date for the state of North Carolina is 12/31/2025

Warning !—Verify design parameters and read notes before use.

This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI

Run: 8.630 s Jul 12 2024 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Sat Apr 26 17:31:08 2025 Page 1
ID:YrqHY0sGK239HELXZ6g?zynRG-k0Ky3z2iodbbNlb5VTZgNN7A7abKIC7S4TLr?0zMo?X

0-1-8

$$\begin{array}{r} 24-9-0 \\ \hline 24-9-0 \\ \hline \end{array}$$

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.1(flat)	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.1(flat)	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3(flat)		
OTHERS	2x4 SP No.3(flat)		

REACTIONS. All bearings 24-9-0.
(lb) - Max Grav All reactions 250 lb or less at joint(s) 42, 22, 41, 40, 39, 38, 37, 36, 35, 34, 33, 32, 30, 29, 28, 27, 26, 25, 24, 23

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES- (6-9)

- 1) Gable requires continuous bottom chord bearing.
- 2) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
- 3) Gable studs spaced at 1-4-0 oc.
- 4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
- 5) CAUTION, Do not erect truss backwards.
- 6) Graphical bracing representation does not depict the size, type or the orientation of the brace on the member. Symbol only indicates that the member must be braced.
- 7) Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.
- 8) Web bracing shown is for lateral support of individual web members only. Refer to BCSI - Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses for additional bracing guidelines, including diagonal bracing.
- 9) SEE BCSI-B3 SUMMARY SHEET- PERMANENT RESTRAING/BRACING OF CHORDS & WEB MEMBERS FOR RECOMMENDED MINIMUM BRACING REQUIREMENTS OF TOP CHORD, BOTTOM CHORD, AND WEB PLANES. IN ADDITION TO THESE MINIMUM GUIDELINES, ALWAYS CONSULT THE PROJECT ARCHITECT OR ENGINEER FOR ADDITIONAL BRACING CONSIDERATIONS.


LOAD CASE(S) Standard



4/25/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Run: 8.630 s Jul 12 2024 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Sat Apr 26 17:31:08 2025 Page 1
ID:IYrqHYj0sGK239HELXZ6g?zynRG-k0KY3z2iodbbNlb5VtZgNN75vaTul7IS4TLr?0zMo?X




4/25/2025

Warning 1—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0019 CAMPBELL RIDGE 187 ALDEN WAY ANGIER, NC
25-3719-F01	F102A	Floor	4	1	
					# 58885

Run: 8.630 s Jul 12 2024 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Sat Apr 26 17:31:09 2025 Page 1
ID:YrqHYj0sGK239HELXZ6g?zynRG-CDuKGJ2KZwjR?RAH3a4vwagFU_me1ZYcJ75OXTzMo?W




LOADING (psf)	SPACING-	1-7-3	CSL	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.41	Vert(LL)	-0.12 17-18	>999	480	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.71	Vert(CT)	-0.16 17-18	>999	360		
BCLL 0.0	Rep Stress Incr	YES	WB 0.41	Horz(CT)	0.03 15	n/a	n/a		
BCDL 5.0	Code IRC2021/TPI2014		Matrix-SH						
									Weight: 129 lb FT = 20%F, 11%E

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.1(flat)	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.1(flat)	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing, Except:
WEBS	2x4 SP No.3(flat)		6-0-0 oc bracing: 24-25,23-24,22-23,20-22.
REACTIONS. (lb/size) 30=408/0-4-8 (min. 0-1-8), 23=1291/0-4-8 (min. 0-1-8), 15=539/0-7-14 (min. 0-1-8)			
Max Grav30=450(LC 3), 23=1291(LC 1), 15=562(LC 7)			

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.	
TOP CHORD	1-30=-448/0, 1-2=-257/0, 2-3=-918/0, 3-4=-1080/0, 4-5=-747/192, 5-6=0/653, 6-7=0/653, 7-8=0/1084, 8-9=-299/240, 9-10=-1262/0, 10-11=-1693/0, 11-12=-1633/0, 12-13=-1078/0
BOT CHORD	28-29=0/716, 27-28=0/1080, 26-27=0/1080, 25-26=0/1080, 24-25=-358/438, 23-24=-1084/0, 22-23=-704/0, 21-22=-57/894, 20-21=-57/894, 19-20=0/1693, 18-19=0/1693, 17-18=0/1693, 16-17=0/1498, 15-16=0/639
WEBS	7-23=-613/0, 2-28=-11/263, 2-29=-598/0, 1-29=0/471, 4-25=-551/0, 5-25=0/481, 5-24=-758/0, 7-24=0/693, 10-20=-638/0, 9-20=0/533, 9-22=-815/0, 8-22=0/852, 8-23=-787/0, 12-16=-546/0, 13-16=0/572, 13-15=-825/0

- NOTES-** (4-7)
- Unbalanced floor live loads have been considered for this design.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - CAUTION, Do not erect truss backwards.
 - Graphical bracing representation does not depict the size, type or the orientation of the brace on the member. Symbol only indicates that the member must be braced.
 - Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.
 - Web bracing shown is for lateral support of individual web members only. Refer to BCSI - Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses for additional bracing guidelines, including diagonal bracing.
 - SEE BCSI-B3 SUMMARY SHEET- PERMANENT RESTRAING/BRACING OF CHORDS & WEB MEMBERS FOR RECOMMENDED MINIMUM BRACING REQUIREMENTS OF TOP CHORD, BOTTOM CHORD, AND WEB PLANES. IN ADDITION TO THESE MINIMUM GUIDELINES, ALWAYS CONSULT THE PROJECT ARCHITECT OR ENGINEER FOR ADDITIONAL BRACING CONSIDERATIONS.

LOAD CASE(S) Standard



4/25/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0019 CAMPBELL RIDGE 187 ALDEN WAY ANGIER, NC
25-3719-F01	F103	Floor Supported Gable	1	1	Job Reference (optional) # 58885

Run: 8.630 s Jul 12 2024 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Sat Apr 26 17:31:10 2025 Page 1
ID:YrqHYj0sGK239HELXZ6g?zynRG-gPRIUf3yKerclbUdlb8SoCW0Hlm6jIXnqx3vzMo?V

0'-1'-8"
Scale = 1:42.4




Plate Offsets (X,Y)-- [1:Edge,0-1-8], [11:0-1-8,Edge], [23:Edge,0-1-8], [33:0-1-8,Edge], [43:Edge,0-1-8], [44:0-1-8,0-1-8]	
LOADING (psf)	SPACING- 1-7-3
TCLL 40.0	Plate Grip DOL 1.00
TCDL 10.0	Lumber DOL 1.00
BCLL 0.0	Rep Stress Incr YES
BCDL 5.0	Code IRC2021/TPI2014
CSI.	DEFL. in (loc) l/defl L/d
TC 0.05	Vert(LL) n/a - n/a 999
BC 0.01	Vert(CT) n/a - n/a 999
WB 0.03	Horz(CT) 0.00 23 n/a n/a
Matrix-SH	
PLATES GRIP	
MT20 244/190	
Weight: 110 lb FT = 20%F, 11%E	

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	
OTHERS 2x4 SP No.3(flat)	

REACTIONS. All bearings 25-8-14.
(lb) - Max Grav All reactions 250 lb or less at joint(s) 43, 23, 42, 41, 40, 39, 38, 37, 36, 35, 34, 33, 31, 30, 29, 28, 27, 26, 25, 24

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES- (6-9)
- Gable requires continuous bottom chord bearing.
 - Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - Gable studs spaced at 1'-4'-0" oc.
 - Recommend 2x6 strongbacks, on edge, spaced at 10'-0'-0" oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - CAUTION, Do not erect truss backwards.
 - Graphical bracing representation does not depict the size, type or the orientation of the brace on the member. Symbol only indicates that the member must be braced.
 - Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.
 - Web bracing shown is for lateral support of individual web members only. Refer to BCSI - Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses for additional bracing guidelines, including diagonal bracing.
 - SEE BCSI-B3 SUMMARY SHEET- PERMANENT RESTRAINING/BRACING OF CHORDS & WEB MEMBERS FOR RECOMMENDED MINIMUM BRACING REQUIREMENTS OF TOP CHORD, BOTTOM CHORD, AND WEB PLANES. IN ADDITION TO THESE MINIMUM GUIDELINES, ALWAYS CONSULT THE PROJECT ARCHITECT OR ENGINEER FOR ADDITIONAL BRACING CONSIDERATIONS.

LOAD CASE(S) Standard



4/25/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0019 CAMPBELL RIDGE 187 ALDEN WAY ANGIER, NC
25-3719-F01	F104	Floor Supported Gable	1	1	Job Reference (optional) # 58885

Run: 8.630 s Jul 12 2024 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Sat Apr 26 17:31:11 2025 Page 1
ID:YrqHYj0sGK239HELXZ6g?zynRG-8b?4h?4a5Yz9EIKgB?6N?7IhPnd1VZuumQaVbLzMo?U

0-1-8

Scale = 1:38.3




Plate Offsets (X,Y)--	[11:0-1-8,Edge], [32:0-1-8,Edge], [40:Edge,0-1-8]
-----------------------	---

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.06	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.01	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0	Rep Stress Incr	YES	WB 0.03	Horz(CT)	0.00	21	n/a	n/a		
BCDL 5.0	Code IRC2021/TPI2014		Matrix-SH							
									Weight: 99 lb	FT = 20%F, 11%E


LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	
OTHERS 2x4 SP No.3(flat)	

REACTIONS. All bearings 23-2-10.
(lb) - Max Uplift All uplift 100 lb or less at joint(s) 21
Max Grav All reactions 250 lb or less at joint(s) 40, 21, 39, 38, 37, 36, 35, 34, 33, 32, 31, 30, 28, 27, 26, 25, 24, 23, 22

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-** (7-10)
- 1) Gable requires continuous bottom chord bearing.
 - 2) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - 3) Gable studs spaced at 1-4-0 oc.
 - 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 21.
 - 5) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 6) CAUTION, Do not erect truss backwards.
 - 7) Graphical bracing representation does not depict the size, type or the orientation of the brace on the member. Symbol only indicates that the member must be braced.
 - 8) Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.
 - 9) Web bracing shown is for lateral support of individual web members only. Refer to BCSI - Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses for additional bracing guidelines, including diagonal bracing.
 - 10) SEE BCSI-B3 SUMMARY SHEET- PERMANENT RESTRAINING/BRACING OF CHORDS & WEB MEMBERS FOR RECOMMENDED MINIMUM BRACING REQUIREMENTS OF TOP CHORD, BOTTOM CHORD, AND WEB PLANES. IN ADDITION TO THESE MINIMUM GUIDELINES, ALWAYS CONSULT THE PROJECT ARCHITECT OR ENGINEER FOR ADDITIONAL BRACING CONSIDERATIONS.

LOAD CASE(S) Standard




4/25/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0019 CAMPBELL RIDGE 187 ALDEN WAY ANGIER, NC
25-3719-F01	F105	FLOOR	9	1	
					Job Reference (optional) # 58885

Run: 8.630 s Jul 12 2024 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Sat Apr 26 17:31:12 2025 Page 1
ID:YrqHYj0sGK239HELXZ6g?zynRG-coZTVL5Csr50svuskjdcYDldPBmNEpx2?4J28nzMo?T



LOADING (psf)	SPACING-	CSL	DEFL.	PLATES	GRIP
TCLL 40.0	1-4-0	TC 1.00	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.00	BC 0.83	Vert(LL) -0.04 12 >999 480		
BCLL 0.0	Lumber DOL 1.00	WB 0.88	Vert(CT) -0.24 12-13 >583 360		
BCDL 5.0	Rep Stress Incr NO	Matrix-SH	Horz(CT) 0.03 8 n/a n/a		
					Weight: 71 lb FT = 20%F, 11%E


LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD 2x4 SP SS(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (lb/size) 17=1195/0-4-8 (min. 0-1-8), 8=921/0-4-8 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-17=-1185/0, 1-2=-1466/0, 2-3=-3986/0, 3-4=-4800/0, 4-5=-3578/0, 5-6=-1966/0
BOT CHORD 15-16=0/2800, 14-15=0/2781, 13-14=0/4800, 12-13=0/3578, 11-12=0/3578, 10-11=0/3578, 9-10=0/963, 8-9=0/970
WEBS 3-13=-251/0, 4-12=-1038/0, 5-11=0/982, 1-16=0/1840, 2-16=-1736/0, 2-14=0/1506, 3-14=-1447/0, 4-13=0/1700, 5-10=-2012/0, 6-10=0/1264, 6-8=-1301/0

- NOTES-** (5-8)
- Unbalanced floor live loads have been considered for this design.
 - Load case(s) 1, 2, 3, 4, 5, 6 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - CAUTION. Do not erect truss backwards.
 - Graphical bracing representation does not depict the size, type or the orientation of the brace on the member. Symbol only indicates that the member must be braced.
 - Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.
 - Web bracing shown is for lateral support of individual web members only. Refer to BCSI - Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses for additional bracing guidelines, including diagonal bracing.
 - SEE BCSI-B3 SUMMARY SHEET- PERMANENT RESTRAING/BRACING OF CHORDS & WEB MEMBERS FOR RECOMMENDED MINIMUM BRACING REQUIREMENTS OF TOP CHORD, BOTTOM CHORD, AND WEB PLANES. IN ADDITION TO THESE MINIMUM GUIDELINES, ALWAYS CONSULT THE PROJECT ARCHITECT OR ENGINEER FOR ADDITIONAL BRACING CONSIDERATIONS.

- LOAD CASE(S)** Standard
- Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (plf)
Vert: 8-17=-7, 1-7=-67
Concentrated Loads (lb)
Vert: 3=-1267
 - Dead: Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (plf)
Vert: 8-17=-7, 1-7=-67



Job	Truss	Truss Type	Qty	Ply	LOT 0.0019 CAMPBELL RIDGE 187 ALDEN WAY ANGIER, NC
25-3719-F01	F105	FLOOR	9	1	Job Reference (optional) # 58885

Run: 8.630 s Jul 12 2024 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Sat Apr 26 17:31:12 2025 Page 2
ID:YrqHYj0sGK239HELXZ6g?zynRG-coZTVL5Csr50svuskjdcYDldPBmNEpx2?4J28nzMo?T

- LOAD CASE(S)** Standard
Concentrated Loads (lb)
Vert: 3=-1267
- 3) 1st chase Dead + Floor Live (unbalanced): Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (plf)
Vert: 8-17=-7, 1-5=-67, 5-7=-13
Concentrated Loads (lb)
Vert: 3=-1267
- 4) 2nd chase Dead + Floor Live (unbalanced): Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (plf)
Vert: 8-17=-7, 1-4=-13, 4-7=-67
Concentrated Loads (lb)
Vert: 3=-1267
- 5) 3rd chase Dead: Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (plf)
Vert: 8-17=-7, 1-5=-67, 5-7=-13
Concentrated Loads (lb)
Vert: 3=-1267
- 6) 4th chase Dead: Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (plf)
Vert: 8-17=-7, 1-4=-13, 4-7=-67
Concentrated Loads (lb)
Vert: 3=-1267



4/25/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Run: 8.630 s Jul 12 2024 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Sat Apr 26 17:31:12 2025 Page 1
ID:YrqHYj0sGK239HELXZ6g?zynRG-coZTVL5CsR50svuskjdcYDIpnBs?EyF2?4J28nzMo?

Structural drawing of a bridge truss. The drawing shows a side elevation of the truss structure. Key components include:

- Dimensions:**
 - Span length: 20.0
 - Panel length: 0.9.8
 - Truss height: 12.0
 - Scale: 1:19.2
- Members:**
 - Top chord: T1
 - Bottom chord: B1
 - Vertical members: 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13
 - Diagonal members: W1, W2
- Connections:**
 - Welded connections (W1, W2)
 - Bolted connections (indicated by circles with dots)
- Labels:**
 - Members are labeled with numbers 1 through 13 and their respective sizes (e.g., 3x6, 3x4, 1.5x3, 3x4 ||).
 - Connections are labeled with letters T1 and B1.

LOADING (psf)	SPACING- 1-7-3	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.21	Vert(LL) -0.06 9-10 >999 480	MT20	244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.41	Vert(CT) -0.08 10 >999 360		
BCLL 0.0	Rep Stress Incr YES	WB 0.28	Horz(CT) 0.02 7 n/a n/a		
BCDL 5.0	Code IRC2021/TPI2014	Matrix-SH		Weight: 61 lb	FT = 20%F, 11%E

REACTIONS. (lb/size) 14=509/0-4-8 (min. 0-1-8), 7=509/0-4-8 (min. 0-1-8)

NOTES- (3-6)

- 1) Unbalanced floor live loads have been considered for this design.
- 2) Recommend 2x6 strongbacks, on edge, spaced at 10'-0" o.c. and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
- 3) Graphical bracing representation does not depict the size, type or the orientation of the brace on the member. Symbol only indicates that the member must be braced.
- 4) Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.
- 5) Web bracing shown is for lateral support of individual web members only. Refer to BCSI - Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses for additional bracing guidelines, including diagonal bracing.
- 6) SEE BCSI-B3 SUMMARY SHEET- PERMANENT RESTRAINING/BRACING OF CHORDS & WEB MEMBERS FOR RECOMMENDED MINIMUM BRACING REQUIREMENTS OF TOP CHORD, BOTTOM CHORD, AND WEB PLANES. IN ADDITION TO THESE MINIMUM GUIDELINES, ALWAYS CONSULT THE PROJECT ARCHITECT OR ENGINEER FOR ADDITIONAL BRACING CONSIDERATIONS.

A circular professional engineer seal for the State of North Carolina. The outer ring contains the text "NORTH CAROLINA" at the top and "ENGINEER" at the bottom. Inside the ring, the word "PROFESSIONAL" is at the top and "SEAL" is in the center. Below "SEAL" is the number "28147". The name "MARK K. MORRIS" is written in a stylized, cursive font across the middle of the seal.

4/25/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0019 CAMPBELL RIDGE 187 ALDEN WAY ANGIER, NC
25-3719-F01	F107	Floor	5	1	Job Reference (optional) # 58885

Run: 8.630 s Jul 12 2024 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Sat Apr 26 17:31:12 2025 Page 1
ID:YrqHYj0sGK239HELXZ6g?zynRG-coZTVL5Csr50svuskjdcYDlpDBrJEyI2?4J28nzMo?T



Scale = 1:19.8




Plate Offsets (X,Y)-- [3:0-1-8,Edge], [4:0-1-8,Edge], [6:0-1-8,Edge], [14:Edge,0-1-8]															
LOADING (psf)		SPACING-		1-7-3		CSI.		DEFL.		in (loc) l/defl L/d		PLATES		GRIP	
TCLL 40.0		Plate Grip DOL		1.00		TC 0.25		Vert(LL)		-0.07 9-10 >999 480		MT20		244/190	
TCDL 10.0		Lumber DOL		1.00		BC 0.45		Vert(CT)		-0.09 9-10 >999 360					
BCLL 0.0		Rep Stress Incr		YES		WB 0.31		Horz(CT)		0.02 7 n/a n/a					
BCDL 5.0		Code IRC2021/TPI2014				Matrix-SH						Weight: 62 lb		FT = 20%F, 11%E	

LUMBER-

TOP CHORD 2x4 SP No.1(flat)
BOT CHORD 2x4 SP No.1(flat)
WEBS 2x4 SP No.3(flat)

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (lb/size) 14=523/0-4-8 (min. 0-1-8), 7=518/0-7-14 (min. 0-1-8)


FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-14=-522/0, 7-15=-514/0, 6-15=-514/0, 1-2=-400/0, 2-3=-1195/0, 3-4=-1469/0, 4-5=-1257/0, 5-6=-518/0
BOT CHORD 12-13=0/925, 11-12=0/1469, 10-11=0/1469, 9-10=0/1469, 8-9=0/1025
WEBS 3-12=-417/0, 2-12=0/352, 2-13=-682/0, 1-13=0/606, 4-9=-364/0, 5-9=0/314, 5-8=-661/0, 6-8=0/655

NOTES- (4-7)

- Unbalanced floor live loads have been considered for this design.
- Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
- CAUTION, Do not erect truss backwards.
- Graphical bracing representation does not depict the size, type or the orientation of the brace on the member. Symbol only indicates that the member must be braced.
- Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.
- Web bracing shown is for lateral support of individual web members only. Refer to BCSI - Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses for additional bracing guidelines, including diagonal bracing.
- SEE BCSI-B3 SUMMARY SHEET - PERMANENT RESTRAING/BRACING OF CHORDS & WEB MEMBERS FOR RECOMMENDED MINIMUM BRACING REQUIREMENTS OF TOP CHORD, BOTTOM CHORD, AND WEB PLANES. IN ADDITION TO THESE MINIMUM GUIDELINES, ALWAYS CONSULT THE PROJECT ARCHITECT OR ENGINEER FOR ADDITIONAL BRACING CONSIDERATIONS.

LOAD CASE(S) Standard




4/25/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0019 CAMPBELL RIDGE 187 ALDEN WAY ANGIER, NC
25-3719-F01	F107A	FLOOR	4	1	
					Job Reference (optional) # 58885

Run: 8.630 s Jul 12 2024 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Sat Apr 26 17:31:13 2025 Page 1
ID:YrqHYj0sGK239HELXZ6g?zynRG-5_7r6g6qd9EtT3T3IQ9r4QqsYb8izGLBEK3bgEzMo?S



LOADING (psf)	SPACING-	1-7-3	CSL	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.72	Vert(LL)	-0.05	12	>999	480	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.70	Vert(CT)	-0.21	12-13	>679	360		
BCLL 0.0	Rep Stress Incr	NO	WB 0.80	Horz(CT)	0.03	8	n/a	n/a		
BCDL 5.0	Code IRC2021/TPI2014		Matrix-SH							
									Weight: 72 lb	FT = 20%F, 11%E

LUMBER-			BRACING-		
TOP CHORD	2x4 SP No.1(flat)		TOP CHORD	Structural wood sheathing directly applied or 5-10-10 oc purlins, except end verticals.	
BOT CHORD	2x4 SP SS(flat)		BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.	
WEBS	2x4 SP No.3(flat)				

REACTIONS. (lb/size) 17=1116/0-4-8 (min. 0-1-8), 8=884/0-7-14 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


TOP CHORD 1-17=-1105/0, 1-2=-1343/0, 2-3=-3576/0, 3-4=-4267/0, 4-5=-3393/0, 5-6=-2039/0

BOT CHORD 15-16=0/2562, 14-15=0/2544, 13-14=0/4267, 12-13=0/3393, 11-12=0/3393, 10-11=0/3393, 9-10=0/1156, 8-9=0/1164

WEBS 4-12=-836/0, 5-11=0/801, 1-16=0/1685, 2-16=-1586/0, 2-14=0/1288, 3-14=-1229/0, 4-13=0/1290, 5-10=-1690/0, 6-10=0/1112, 6-8=-1424/0

- NOTES-** (5-8)
- Unbalanced floor live loads have been considered for this design.
 - Load case(s) 1, 2, 3, 4, 5, 6 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - CAUTION. Do not erect truss backwards.
 - Graphical bracing representation does not depict the size, type or the orientation of the brace on the member. Symbol only indicates that the member must be braced.
 - Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.
 - Web bracing shown is for lateral support of individual web members only. Refer to BCSI - Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses for additional bracing guidelines, including diagonal bracing.
 - SEE BCSI-B3 SUMMARY SHEET- PERMANENT RESTRAING/BRACING OF CHORDS & WEB MEMBERS FOR RECOMMENDED MINIMUM BRACING REQUIREMENTS OF TOP CHORD, BOTTOM CHORD, AND WEB PLANES. IN ADDITION TO THESE MINIMUM GUIDELINES, ALWAYS CONSULT THE PROJECT ARCHITECT OR ENGINEER FOR ADDITIONAL BRACING CONSIDERATIONS.

- LOAD CASE(S)** Standard
- Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (plf)
Vert: 8-17=-8, 1-7=-80
Concentrated Loads (lb)
Vert: 3=-960
 - Dead: Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (plf)
Vert: 8-17=-8, 1-7=-80



Continued on page 2

4/25/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0019 CAMPBELL RIDGE 187 ALDEN WAY ANGIER, NC
25-3719-F01	F107A	FLOOR	4	1	Job Reference (optional) # 58885

Run: 8.630 s Jul 12 2024 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Sat Apr 26 17:31:13 2025 Page 2
ID: lYrqHYj0sGK239HELXZ6g?zynRG-5_7r6g6qd9EtT3T3lQ9r4QqsYb8izGLBEk3bgEzMo?S

- LOAD CASE(S)** Standard
Concentrated Loads (lb)
Vert: 3=-960
- 3) 1st chase Dead + Floor Live (unbalanced): Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (plf)
Vert: 8-17=-8, 1-5=-80, 5-7=-16
Concentrated Loads (lb)
Vert: 3=-960
- 4) 2nd chase Dead + Floor Live (unbalanced): Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (plf)
Vert: 8-17=-8, 1-4=-16, 4-7=-80
Concentrated Loads (lb)
Vert: 3=-960
- 5) 3rd chase Dead: Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (plf)
Vert: 8-17=-8, 1-5=-80, 5-7=-16
Concentrated Loads (lb)
Vert: 3=-960
- 6) 4th chase Dead: Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (plf)
Vert: 8-17=-8, 1-4=-16, 4-7=-80
Concentrated Loads (lb)
Vert: 3=-960



4/25/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0019 CAMPBELL RIDGE 187 ALDEN WAY ANGIER, NC
25-3719-F01	F108	Floor Supported Gable	1	1	Job Reference (optional) # 58885

Run: 8.630 s Jul 12 2024 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Sat Apr 26 17:31:14 2025 Page 1
ID:YrqHYj0sGK239HELXZ6g?zynRG-ZAhDK06SOTMk5D2Fs7g4deNCI?elivgLSOo9CgzMo?R




Plate Offsets (X,Y)-- [1:Edge,0-1-8], [2:0-1-8,Edge], [4:Edge,0-1-8]							
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d
TCLL 40.0	Plate Grip DOL	1.00	TC 0.05	Vert(LL)	n/a -	n/a	999
TCDL 10.0	Lumber DOL	1.00	BC 0.01	Vert(CT)	n/a -	n/a	999
BCLL 0.0	Rep Stress Incr	YES	WB 0.03	Horz(CT)	0.00 4	n/a	n/a
BCDL 5.0	Code IRC2021/TPI2014		Matrix-P				
				PLATES	GRIP		
				MT20	244/190		
				Weight: 15 lb		FT = 20%F, 11%E	


LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 2-2-6 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	
OTHERS 2x4 SP No.3(flat)	

REACTIONS. (lb/size) 4=16/2-2-6 (min. 0-1-8), 6=55/2-2-6 (min. 0-1-8), 5=136/2-2-6 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES- (6-9)
- Gable requires continuous bottom chord bearing.
 - Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - Gable studs spaced at 1-4-0 oc.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - CAUTION, Do not erect truss backwards.
 - Graphical bracing representation does not depict the size, type or the orientation of the brace on the member. Symbol only indicates that the member must be braced.
 - Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.
 - Web bracing shown is for lateral support of individual web members only. Refer to BCSI - Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses for additional bracing guidelines, including diagonal bracing.
 - SEE BCSI-B3 SUMMARY SHEET - PERMANENT RESTRAING/BRACING OF CHORDS & WEB MEMBERS FOR RECOMMENDED MINIMUM BRACING REQUIREMENTS OF TOP CHORD, BOTTOM CHORD, AND WEB PLANES. IN ADDITION TO THESE MINIMUM GUIDELINES, ALWAYS CONSULT THE PROJECT ARCHITECT OR ENGINEER FOR ADDITIONAL BRACING CONSIDERATIONS.

LOAD CASE(S) Standard



4/25/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0019 CAMPBELL RIDGE 187 ALDEN WAY ANGIER, NC
25-3719-F01	F109	FLOOR	1	1	
Job Reference (optional)					# 58885

Run: 8.630 s Jul 12 2024 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Sat Apr 26 17:31:14 2025 Page 1
ID: lYrqHYj0sGK239HELXZ6g?zynRG-ZAhDK06SOTMk5D2Fs7g4deN1_?T5ij6LSOo9CgzMo?R





Plate Offsets (X,Y)-- [1:Edge,0-1-8], [4:0-1-8,Edge], [5:0-1-8,Edge], [6:0-1-8,Edge], [10:0-3-0,0-0-0], [16:Edge,0-1-8]	
LOADING (psf)	SPACING-- 1-7-3
TCLL 40.0	Plate Grip DOL 1.00
TCDL 10.0	Lumber DOL 1.00
BCLL 0.0	Rep Stress Incr NO
BCDL 5.0	Code IRC2021/TPI2014
CSL	TC 0.74
DEFL.	BC 0.75
Vert(LL) -0.05 11-12 >999 480	WB 0.77
Vert(CT) -0.20 11-12 >630 360	Matrix-SH
Horz(CT) 0.02 7 n/a n/a	
PLATES MT20	GRIP 244/190
Weight: 65 lb FT = 20%F, 11%E	

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP SS(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	
REACTIONS. (lb/size) 16=993/0-4-8 (min. 0-1-8), 7=871/0-7-14 (min. 0-1-8)	
FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.	
TOP CHORD 1-16=-984/0, 7-17=-796/0, 6-17=-795/0, 1-2=-1183/0, 2-3=-3111/0, 3-4=-3735/0, 4-5=-2550/0, 5-6=-894/0	
BOT CHORD 14-15=0/2253, 13-14=0/2238, 12-13=0/3735, 11-12=0/2550, 10-11=0/2550, 9-10=0/2550	
WEBS 4-11=-1017/0, 5-10=0/799, 1-15=0/1484, 2-15=-1392/0, 2-13=0/1090, 3-13=-1109/0, 4-12=0/1615, 5-9=-2065/0, 6-9=0/1127	

- NOTES-** (5-8)
- Unbalanced floor live loads have been considered for this design.
 - Load case(s) 1, 2, 3, 4, 5, 6 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - CAUTION. Do not erect truss backwards.
 - Graphical bracing representation does not depict the size, type or the orientation of the brace on the member. Symbol only indicates that the member must be braced.
 - Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.
 - Web bracing shown is for lateral support of individual web members only. Refer to BCSI - Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses for additional bracing guidelines, including diagonal bracing.
 - SEE BCSI-B3 SUMMARY SHEET- PERMANENT RESTRAING/BRACING OF CHORDS & WEB MEMBERS FOR RECOMMENDED MINIMUM BRACING REQUIREMENTS OF TOP CHORD, BOTTOM CHORD, AND WEB PLANES. IN ADDITION TO THESE MINIMUM GUIDELINES, ALWAYS CONSULT THE PROJECT ARCHITECT OR ENGINEER FOR ADDITIONAL BRACING CONSIDERATIONS.

- LOAD CASE(S)** Standard
- Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (plf)
Vert: 7-16=-8, 1-6=-80
Concentrated Loads (lb)
Vert: 3=-960
 - Dead: Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (plf)
Vert: 7-16=-8, 1-6=-80



Continued on page 2

4/25/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0019 CAMPBELL RIDGE 187 ALDEN WAY ANGIER, NC
25-3719-F01	F109	FLOOR	1	1	Job Reference (optional) # 58885

Run: 8.630 s Jul 12 2024 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Sat Apr 26 17:31:14 2025 Page 2
ID: lYrqHYj0sGK239HELXZ6g?zynRG-ZAhDK06SOTMk5D2Fs7g4deN1_?T5ij6LSOo9CgzMo?R

- LOAD CASE(S)** Standard
Concentrated Loads (lb)
Vert: 3=-960
- 3) 1st chase Dead + Floor Live (unbalanced): Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (plf)
Vert: 7-16=-8, 1-5=-80, 5-6=-16
Concentrated Loads (lb)
Vert: 3=-960
- 4) 2nd chase Dead + Floor Live (unbalanced): Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (plf)
Vert: 7-16=-8, 1-4=-16, 4-6=-80
Concentrated Loads (lb)
Vert: 3=-960
- 5) 3rd chase Dead: Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (plf)
Vert: 7-16=-8, 1-5=-80, 5-6=-16
Concentrated Loads (lb)
Vert: 3=-960
- 6) 4th chase Dead: Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (plf)
Vert: 7-16=-8, 1-4=-16, 4-6=-80
Concentrated Loads (lb)
Vert: 3=-960



4/25/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0019 CAMPBELL RIDGE 187 ALDEN WAY ANGIER, NC
25-3719-F01	F110	Floor	2	1	
					Job Reference (optional) # 58885

Run: 8.630 s Jul 12 2024 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Sat Apr 26 17:31:14 2025 Page 1
ID:YrqHYj0sGK239HELXZ6g?zynRG-ZAhDK06SOTMk5D2Fs7g4deN8_?XaisGLSo9CgzMo?R




Plate Offsets (X,Y)-- [3:0-1-8,Edge], [4:0-1-8,Edge], [13:Edge,0-1-8]							
LOADING (psf)		SPACING-		CS.		DEFL.	
TCLL	40.0	1-7-3		TC 0.29		in (loc) l/defl L/d	
TCDL	10.0	Plate Grip DOL 1.00		BC 0.46		Vert(LL) -0.07 10-11 >999 480	
BCLL	0.0	Lumber DOL 1.00		WB 0.25		Vert(CT) -0.09 10-11 >999 360	
BCDL	5.0	Rep Stress Incr YES		Matrix-SH		Horz(CT) 0.01 7 n/a n/a	
		Code IRC2021/TPI2014				PLATES GRIP	
						MT20 244/190	
						Weight: 54 lb FT = 20%F, 11%E	

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.1(flat)	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.1(flat)	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3(flat)		
REACTIONS. (lb/size) 13=455/0-4-8 (min. 0-1-8), 7=450/0-7-14 (min. 0-1-8)			
FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.			
TOP CHORD	1-13=-451/0, 1-2=-341/0, 2-3=-971/0, 3-4=-1096/0, 4-5=-724/0		
BOT CHORD	11-12=0/794, 10-11=0/1096, 9-10=0/1096, 8-9=0/1096, 7-8=0/388		
WEBS	3-11=-252/0, 2-12=-589/0, 1-12=0/517, 4-8=-476/0, 5-8=0/437, 5-7=-583/0		

- NOTES- (4-7)
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 3) CAUTION, Do not erect truss backwards.
 - 4) Graphical bracing representation does not depict the size, type or the orientation of the brace on the member. Symbol only indicates that the member must be braced.
 - 5) Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.
 - 6) Web bracing shown is for lateral support of individual web members only. Refer to BCSI - Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses for additional bracing guidelines, including diagonal bracing.
 - 7) SEE BCSI-B3 SUMMARY SHEET- PERMANENT RESTRAING/BRACING OF CHORDS & WEB MEMBERS FOR RECOMMENDED MINIMUM BRACING REQUIREMENTS OF TOP CHORD, BOTTOM CHORD, AND WEB PLANES. IN ADDITION TO THESE MINIMUM GUIDELINES, ALWAYS CONSULT THE PROJECT ARCHITECT OR ENGINEER FOR ADDITIONAL BRACING CONSIDERATIONS.

LOAD CASE(S) Standard




4/25/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0019 CAMPBELL RIDGE 187 ALDEN WAY ANGIER, NC
25-3719-F01	F111	FLOOR	1	1	
Job Reference (optional)					# 58885

Run: 8.630 s Jul 12 2024 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Sat Apr 26 17:31:14 2025 Page 1
ID:YrqHYj0sGK239HELXZ6g?zynRG-ZAhDK06SOTMk5D2Fs7g4deNz9?QsihnLSOo9CgzMo?R



LOADING (psf)		SPACING-		CSI.		DEFL.		PLATES		GRIP	
TCLL	40.0	Plate Grip DOL	1.00	TC	0.99	Vert(LL)	-0.03 13 >999 480	MT20	244/190		
TCDL	10.0	Lumber DOL	1.00	BC	0.96	Vert(CT)	-0.24 13-14 >493 360	MT20HS	187/143		
BCLL	0.0	Rep Stress Incr	NO	WB	0.92	Horz(CT)	0.02 10 n/a n/a				
BCDL	5.0	Code IRC2021/TPI2014		Matrix-SH							
										Weight: 98 lb	FT = 20%F, 11%E


LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.1(flat)	TOP CHORD	Structural wood sheathing directly applied or 4-3-4 oc purlins, except end verticals.
BOT CHORD	2x4 SP SS(flat)	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 10-11,9-10.
WEBS	2x4 SP No.3(flat) *Except* W2,W4: 2x4 SP No.2(flat)		

REACTIONS. All bearings 2-2-6 except (jt=length) 17=0-4-8.
(lb) - Max Uplift All uplift 100 lb or less at joint(s) 9
Max Grav All reactions 250 lb or less at joint(s) 8 except 17=1514(LC 1), 10=1500(LC 1), 10=1500(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-17=-1498/0, 1-2=-2099/0, 2-3=-5576/0, 3-4=-6521/0, 4-5=-3968/0, 5-6=-975/0
BOT CHORD 15-16=0/3976, 14-15=0/6521, 13-14=0/3968, 12-13=0/3968, 11-12=0/3968
WEBS 3-14=-1268/0, 6-10=-1065/0, 4-13=-1184/0, 5-12=0/1221, 1-16=0/2523, 2-16=-2327/0, 2-15=0/1985, 3-15=-1606/0, 4-14=0/3250, 5-11=-3681/0, 6-11=0/1574

- NOTES-** (7-10)
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) All plates are MT20 plates unless otherwise indicated.
 - 3) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 9.
 - 4) Load case(s) 1, 2, 3, 4, 5, 6 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.
 - 5) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 6) CAUTION, Do not erect truss backwards.
 - 7) Graphical bracing representation does not depict the size, type or the orientation of the brace on the member. Symbol only indicates that the member must be braced.
 - 8) Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.
 - 9) Web bracing shown is for lateral support of individual web members only. Refer to BCSI - Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses for additional bracing guidelines, including diagonal bracing.
 - 10) SEE BCSI-B3 SUMMARY SHEET- PERMANENT RESTRAING/BRACING OF CHORDS & WEB MEMBERS FOR RECOMMENDED MINIMUM BRACING REQUIREMENTS OF TOP CHORD, BOTTOM CHORD, AND WEB PLANES. IN ADDITION TO THESE MINIMUM GUIDELINES, ALWAYS CONSULT THE PROJECT ARCHITECT OR ENGINEER FOR ADDITIONAL BRACING CONSIDERATIONS.

LOAD CASE(S) Standard
1) Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (plf)
Vert: 8-17=-8, 1-7=-80



Job	Truss	Truss Type	Qty	Ply	LOT 0.0019 CAMPBELL RIDGE 187 ALDEN WAY ANGIER, NC
25-3719-F01	F111	FLOOR	1	1	Job Reference (optional) # 58885

Run: 8.630 s Jul 12 2024 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Sat Apr 26 17:31:15 2025 Page 2
ID: IYrqHYj0sGK239HELXZ6g?zynRG-1NFbXM759mUbjMdRqRBJ9rw8vPm5R81Uh2Yil6zM0?Q

- LOAD CASE(S)** Standard
- Concentrated Loads (lb)
Vert: 3=-2000
 - 2) Dead: Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (plf)
Vert: 8-17=-8, 1-7=-80
Concentrated Loads (lb)
Vert: 3=-2000
 - 3) 1st chase Dead + Floor Live (unbalanced): Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (plf)
Vert: 8-17=-8, 1-5=-80, 5-6=-16, 6-7=-80
Concentrated Loads (lb)
Vert: 3=-2000
 - 4) 2nd chase Dead + Floor Live (unbalanced): Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (plf)
Vert: 8-17=-8, 1-4=-16, 4-7=-80
Concentrated Loads (lb)
Vert: 3=-2000
 - 5) 3rd chase Dead: Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (plf)
Vert: 8-17=-8, 1-5=-80, 5-6=-16, 6-7=-80
Concentrated Loads (lb)
Vert: 3=-2000
 - 6) 4th chase Dead: Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (plf)
Vert: 8-17=-8, 1-4=-16, 4-7=-80
Concentrated Loads (lb)
Vert: 3=-2000




4/25/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0019 CAMPBELL RIDGE 187 ALDEN WAY ANGIER, NC
25-3719-F01	F112	Floor	1	1	
					# 58885

Run: 8.630 s Jul 12 2024 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Sat Apr 26 17:31:15 2025 Page 1
ID:IYrqHYj0sGK239HELXZ6g?zynRG-1NFbXM759mUbjMdRQrBJ9rwJrPu6RI7Uh2Yil6zM0?Q




LOADING (psf)	SPACING	1-4-0	CSI	DEFL.	in (loc)	L/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.29	Vert(LL)	-0.07 15-16	>999	480	MT20	244/190
TCDL 10.0	Lumber DOL	1.00	BC 0.45	Vert(CT)	-0.09 15-16	>999	360		
BCLL 0.0	Rep Stress Incr	YES	WB 0.27	Horz(CT)	0.02 13	n/a	n/a		
BCDL 5.0	Code IRC2021/TPI2014		Matrix-SH						
									Weight: 119 lb FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 22-23,21-22,20-21,18-20.
WEBS 2x4 SP No.3(flat)	
REACTIONS. (lb/size) 28=373/0-7-14 (min. 0-1-8), 13=373/0-7-14 (min. 0-1-8), 21=980/0-4-8 (min. 0-1-8) Max Grav28=394(LC 10), 13=395(LC 7), 21=980(LC 1)	

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 28-29=-391/0, 1-29=-391/0, 13-30=-391/0, 12-30=-391/0, 1-2=-346/0, 2-3=-893/0, 3-4=-1013/0, 4-5=-723/2, 5-6=-3/332, 6-7=-3/332, 7-8=0/386, 8-9=-700/27, 9-10=-1013/0, 10-11=-916/0, 11-12=-390/0
BOT CHORD 26-27=0/735, 25-26=0/1013, 24-25=0/1013, 23-24=0/1013, 22-23=-119/458, 21-22=-678/0, 20-21=-681/0, 19-20=-151/420, 18-19=-151/420, 17-18=0/1013, 16-17=0/1013, 15-16=0/1013, 14-15=0/774
WEBS 7-21=-963/0, 2-27=-506/0, 1-27=0/465, 4-23=-450/0, 5-23=0/397, 5-22=-625/0, 7-22=0/570, 9-18=-482/0, 8-18=0/418, 8-20=-630/0, 7-20=0/537, 11-14=-500/0, 12-14=0/493

- NOTES-** (4-7)
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 3) CAUTION, Do not erect truss backwards.
 - 4) Graphical bracing representation does not depict the size, type or the orientation of the brace on the member. Symbol only indicates that the member must be braced.
 - 5) Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.
 - 6) Web bracing shown is for lateral support of individual web members only. Refer to BCSI - Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses for additional bracing guidelines, including diagonal bracing.
 - 7) SEE BCSI-B3 SUMMARY SHEET- PERMANENT RESTRAINING/BRACING OF CHORDS & WEB MEMBERS FOR RECOMMENDED MINIMUM BRACING REQUIREMENTS OF TOP CHORD, BOTTOM CHORD, AND WEB PLANES. IN ADDITION TO THESE MINIMUM GUIDELINES, ALWAYS CONSULT THE PROJECT ARCHITECT OR ENGINEER FOR ADDITIONAL BRACING CONSIDERATIONS.

LOAD CASE(S) Standard



4/25/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.


Job	Truss	Truss Type	Qty	Ply	LOT 0.0019 CAMPBELL RIDGE 187 ALDEN WAY ANGIER, NC
25-3719-F01	F113	Floor Supported Gable	1	1	Job Reference (optional) # 58885

Run: 8.630 s Jul 12 2024 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Sat Apr 26 17:31:15 2025 Page 1
ID:YrqHYj0sGK239HELXZ6g?zynRG-1NFbXM759mUbjMdRqRBJ9rwNPP_zRmtUh2Yil6zMo?Q

0-1-8

0-1-8

Scale = 1:39.7



23-10-12
23-10-12

Plate Offsets (X,Y)-- [11:0-1-8,Edge], [32:0-1-8,Edge], [40:Edge,0-1-8]									
LOADING (psf)		SPACING-		CSI.		DEFL.		PLATES	
TCLL	40.0	Plate Grip DOL	2-0-0 1.00	TC	0.06	in (loc)	l/defl	MT20	GRIP
TCDL	10.0	Lumber DOL	1.00	BC	0.01	Vert(LL)	n/a - n/a		244/190
BCLL	0.0	Rep Stress Incr	YES	WB	0.03	Vert(CT)	n/a - n/a		
BCDL	5.0	Code IRC2021/TPI2014		Matrix-SH		Horz(CT)	0.00 21 n/a n/a		
								Weight: 101 lb FT = 20%F, 11%E	

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.1(flat)	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.1(flat)	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3(flat)		
OTHERS	2x4 SP No.3(flat)		

REACTIONS. All bearings 23-10-12.
(lb) - Max Grav All reactions 250 lb or less at joint(s) 40, 21, 39, 38, 37, 36, 35, 34, 33, 32, 31, 30, 28, 27, 26, 25, 24, 23, 22

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-** (5-8)
- 1) Gable requires continuous bottom chord bearing.
 - 2) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - 3) Gable studs spaced at 1-4-0 oc.
 - 4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 5) Graphical bracing representation does not depict the size, type or the orientation of the brace on the member. Symbol only indicates that the member must be braced.
 - 6) Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.
 - 7) Web bracing shown is for lateral support of individual web members only. Refer to BCSI - Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses for additional bracing guidelines, including diagonal bracing.
 - 8) SEE BCSI-B3 SUMMARY SHEET- PERMANENT RESTRAING/BRACING OF CHORDS & WEB MEMBERS FOR RECOMMENDED MINIMUM BRACING REQUIREMENTS OF TOP CHORD, BOTTOM CHORD, AND WEB PLANES. IN ADDITION TO THESE MINIMUM GUIDELINES, ALWAYS CONSULT THE PROJECT ARCHITECT OR ENGINEER FOR ADDITIONAL BRACING CONSIDERATIONS.

LOAD CASE(S) Standard




4/25/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0019 CAMPBELL RIDGE 187 ALDEN WAY ANGIER, NC
25-3719-F01	F114	Floor	24	1	
					Job Reference (optional) # 58885

Run: 8.630 s Jul 12 2024 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Sat Apr 26 17:31:16 2025 Page 1
ID: lYrqHYj0sGK239HELXZ6g?zynRG-VZpzki8jv4cSKWCezYiYi3SVdoEhAlrewiHGHZzMo?P



LOADING (psf)	SPACING-	1-7-3	CS.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 40.0	Plate Grip DOL	1.00	TC 0.22	Vert(LL)	-0.07	11-12	>999	480	MT20
TCDL 10.0	Lumber DOL	1.00	BC 0.42	Vert(CT)	-0.09	11	>999	360	244/190
BCLL 0.0	Rep Stress Incr	YES	WB 0.31	Horz(CT)	0.02	7	n/a	n/a	
BCDL 5.0	Code IRC2021/TPI2014		Matrix-SH						
					Weight: 62 lb FT = 20%F, 11%E				

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	

REACTIONS. (lb/size) 14=518/0-7-14 (min. 0-1-8), 7=523/0-4-8 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 14-15=-516/0, 1-15=-515/0, 6-7=-520/0, 1-2=-461/0, 2-3=-1227/0, 3-4=-1470/0, 4-5=-1227/0, 5-6=-459/0
BOT CHORD 12-13=0/975, 11-12=0/1470, 10-11=0/1470, 9-10=0/1470, 8-9=0/977
WEBS 3-12=-390/0, 2-12=0/331, 2-13=-670/0, 1-13=0/619, 4-9=-390/0, 5-9=0/331, 5-8=-674/0, 6-8=0/641

- NOTES- (4-7)
- Unbalanced floor live loads have been considered for this design.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - CAUTION, Do not erect truss backwards.
 - Graphical bracing representation does not depict the size, type or the orientation of the brace on the member. Symbol only indicates that the member must be braced.
 - Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.
 - Web bracing shown is for lateral support of individual web members only. Refer to BCSI - Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses for additional bracing guidelines, including diagonal bracing.
 - SEE BCSI-B3 SUMMARY SHEET - PERMANENT RESTRAING/BRACING OF CHORDS & WEB MEMBERS FOR RECOMMENDED MINIMUM BRACING REQUIREMENTS OF TOP CHORD, BOTTOM CHORD, AND WEB PLANES. IN ADDITION TO THESE MINIMUM GUIDELINES, ALWAYS CONSULT THE PROJECT ARCHITECT OR ENGINEER FOR ADDITIONAL BRACING CONSIDERATIONS.

LOAD CASE(S) Standard



4/25/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.

Job	Truss	Truss Type	Qty	Ply	LOT 0.0019 CAMPBELL RIDGE 187 ALDEN WAY ANGIER, NC
25-3719-F01	F115	Floor Supported Gable	1	1	Job Reference (optional) # 58885

Run: 8.630 s Jul 12 2024 Print: 8.630 s Jul 12 2024 MiTek Industries, Inc. Sat Apr 26 17:31:16 2025 Page 1
ID: IYrqHYj0sGK239HELXZ6g?zynRG-VZpzi8jv4cSKWCezYiYI3SYAoK8Ap4ewiHGHZzMo?P




Plate Offsets (X,Y)-- [4:Edge,0-1-8], [5:Edge,0-1-8]							
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	L/defl	L/d
TCLL 40.0	Plate Grip DOL	1.00	TC 0.06	Vert(LL)	n/a -	n/a	999
TCDL 10.0	Lumber DOL	1.00	BC 0.01	Vert(CT)	n/a -	n/a	999
BCLL 0.0	Rep Stress Incr	YES	WB 0.03	Horz(CT)	-0.00 4	n/a	n/a
BCDL 5.0	Code IRC2021/TPI2014		Matrix-P				
						Weight: 13 lb	FT = 20%F, 11%E


LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 1-7-14 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	
OTHERS 2x4 SP No.3(flat)	

REACTIONS. (lb/size) 5=74/1-7-14 (min. 0-1-8), 4=74/1-7-14 (min. 0-1-8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES- (6-9)
- 1) Gable requires continuous bottom chord bearing.
 - 2) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - 3) Gable studs spaced at 1-4-0 oc.
 - 4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 5) CAUTION, Do not erect truss backwards.
 - 6) Graphical bracing representation does not depict the size, type or the orientation of the brace on the member. Symbol only indicates that the member must be braced.
 - 7) Bearing symbols are only graphical representations of a possible bearing condition. Bearing symbols are not considered in the structural design of the truss to support the loads indicated.
 - 8) Web bracing shown is for lateral support of individual web members only. Refer to BCSI - Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses for additional bracing guidelines, including diagonal bracing.
 - 9) SEE BCSI-B3 SUMMARY SHEET - PERMANENT RESTRAING/BRACING OF CHORDS & WEB MEMBERS FOR RECOMMENDED MINIMUM BRACING REQUIREMENTS OF TOP CHORD, BOTTOM CHORD, AND WEB PLANES. IN ADDITION TO THESE MINIMUM GUIDELINES, ALWAYS CONSULT THE PROJECT ARCHITECT OR ENGINEER FOR ADDITIONAL BRACING CONSIDERATIONS.

LOAD CASE(S) Standard



4/25/2025

Warning !—Verify design parameters and read notes before use. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer – not truss designer or truss engineer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPI 1 *National Design Standard for Metal Plate Connected Wood Truss Construction* and BCSI 1-03 *Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses* from Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53719.