

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: BRAYDEN PRESERVE

INITIAL SYSTEM: ^{pump to} Approved 25% Reduction

DISTRIBUTION: SEPARATE

BENCHMARK: 100.0

NO. BEDROOMS: 4

SEPTIC TANK SIZE 1000

LOT 57

REPAIR: ^{pump to} Approved 25% Reduction

DISTRIBUTION SEPARATE

LOCATION TOP STAKE AC 59/60

LTAR 0.6 gpd / ft²

PUMP TANK SIZE 1000

LINE	FLAG COLOR	ELEVATION	LENGTH
------	------------	-----------	--------

Intial spike

1	P	97.00	50'
2	O	96.10	70'
3	P	95.80	80'
			<u>200'</u>
4	O	95.20	80'
5	P	95.20	80'
6	O	94.90	40'
			<u>200'</u>

BY M. EAKER

DATE 01/2024

TYPICAL PROFILE

0-10 LS (VFS, 40')
 10-40+ SEC (F, 30')
 CR 2 ≥ 34"

THERE SHALL BE NO GRADING,

CUTTING, LOGGING OR OTHER SOIL

DISTURBANCE IN SEPTIC AREA

HEALTH DEPARTMENT USE ONLY.

DESIGNS DO NOT GUARANTEE FUNCTIONALITY

P.O. Box 9321
Fayetteville, NC 28311
Phone/Fax (910) 322-4540
Email mike@southeasternsoil.com

