North Carolina 2018 - R402.1.5 Total UA

Property , NC 27546 Model: CC 1790 Community: NA

Organization

Southern Energy Manageme Justin Smith **Inspection Status** Results are projected



Builder

Template - Caviness & Cates - CC 1790 - Ci Caviness and Cates

CC 1790 slab

This report is based on a proposed design and does not confirm field enforcement of design elements.

Building UA

Elements	NC Reference	As Designed
Ceilings	31.6	27.8
Above-Grade Walls	156.3	120.8
Windows, Doors and Skylights	75.1	69.4
Slab Floor:	61.4	79.1
Framed Floors	12.8	13.9
Foundation Walls	0.0	0.0
Rim Joists	7.3	5.9
Overall UA (Design must be equal or lower):	344.5	316.9

Requirements

R402.1.5	Total UA alternative compliance passes by 8.0%.	The proposed home meets the UA requirement by 8.0%
R402.3.2	Average SHGC: 0.30 Max SHGC: 0.30	Average SHGC of 0.30 is greater than the maximum of 0.30.
R402.4.2.2	Air Leakage Testing	Air sealing is 0.28 CFM50 / $\mathrm{ft^2}$ Shell Area. It must not exceed 0.30 CFM50 / $\mathrm{ft^2}$ Shell Area.
R402.5	Area-weighted average fenestration SHGC	Area-weighted average fenestration SHGC is 0.3. The maximum allowed value is [No Limit].
R402.5	Area-weighted average fenestration U-Factor	
R404.1	Lighting Equipment	
Mandatory Checklist	Mandatory code requirements that are not checked by Ekotrope must be met.	2015 IECC Mandatory Checklist must be checked as complete.
R403.3.1	Duct Insulation	Duct insulation meets the requirements specified in North Carolina 2018 Code Section 403.3.1.
403.3.3	Duct Testing	

Design exceeds requirements for North Carolina 2018 Prescriptive compliance by 8%.

Name:	Justin Smith	Signature:	Justin Smith
Organization:	Southern Energy Management	Digitally signed:	9/8/25 at 3:29 PM

Property , NC 27546 Model: CC 1790 Community: NA

Organization Southern Energy Management Justin Smith

Inspection Status Results are projected



Template - Caviness & Cates - CC 1790 - CZ 4 slab - H Caviness and Cates CC 1790 slab

Number Of Floors: 2	
Has Electric Vehicle Ready Space: No	
Conditioned Volume [cu. ft.]: 15,880	
Residence Type: Single family detached	
Floor Number: N/A	
Community: NA	
IECC 2021 Climate Zone: 3A	
	Has Electric Vehicle Ready Space: No Conditioned Volume [cu. ft.]: 15,880 Residence Type: Single family detached Floor Number: N/A Community: NA

Envel	ope (Com	ponent	ts
-------	-------	-----	--------	----

Slab								
Name	Library Type	Perimeter	Floor Grade	Carpet F	R Exposed Masonry Area	Surface Area	Location	Enclosing
slab	Uninsulated	132	On Grade	1	0	780.0 ft²	Exposed Exterior	Conditioned Space

Slab Library List											
Name	Wall Construction Type	Slab Completely Insulated?	Underslab Insulation Width [t]	Perimeter Insulation Depth [t]	Perimeter Insulation R Value		Thermal Break	Effective R-value			
Uninsulated	Wood Frame / Other	No	0	0	0	No	No	0.00			

Framed Floor						
Name	Library Type	Carpet R	Floor Grade	Surface Area	Location	Effective R-value
over garage	R 19, 16"OC G1 Carpet	0	Above Grade	272.0 ft²	Unconditioned, attached garage	19.567

Rim Joist				
Name	Library Type	Surface Area	Location	Effective Insulation R-value
1st floor ambient	R 19 G1, 16"OC	96.0 ft²	Exposed Exterior	17.30
1st floor garage	R 19 G1, 16"OC	36.0 ft²	Unconditioned, attached garage	17.30

Wall						
Name	Library Type	Surface Color	Solar Absorptance	Surface Area	Location	Effective R-value
1st floor ambient	R 19 FG G1 16" O.C	Medium	0.75	868.0 ft²	Exposed Exterior	16.805
1st floor garage	R 19 FG G1 16" O.C	Medium	0.75	320.0 ft²	Unconditioned, attached garage	16.805
2nd floor ambient	R 19 FG G1 16" O.C	Medium	0.75	1,056.0 ft²	Exposed Exterior	16.805

Glazing								
Name	Library Type	Wall Assignment		Overhang Depth	Overhang Ft To Top	Overhang Ft To Bottom	Orientation	Surface Area
front 2nd unshaded	35/30	2nd floor ambient	Yes	0	0	0	Southwest	39.0 ft²
front shaded	35/30	1st floor ambient	Yes	5	1	5	Southwest	8.0 ft²

Property , NC 27546 Model: CC 1790 Community: NA

Project & Plan
Template - Caviness & Cates - CC 1790 - CZ 4 slab - HE CC 1790 slab

Organization

Southern Energy Management Justin Smith

Inspection Status Results are projected

Builder

Caviness and Cates

Name	Library Type	e Wali Assignment		Overhang Depth	Overhang Ft To Top	Overhang Ft To Bottom	Orientation	Surface Area
left 2nd unshaded	00,00	2nd floor ambient	Yes	0	0	0	Northwest	15.0 ft²
left unshaded	35/30	1st floor ambient	Yes	0	0	0	Northwest	30.0 ft ²
rear 2nd unshaded		2nd floor ambient	Yes	0	0	0	Northeast	36.0 ft²
rear unshaded	35/30	1st floor ambient	Yes	0	0	0	Northeast	33.5 ft²
right 2nd unshaded		2nd floor ambient	Yes	0	0	0	Southeast	15.0 ft²

Glazing Library List

Name	s Shgc	U-factor
35/30	0.3	0.350

Opaque Do	or								
Name	Library Type	Wall Assignment	Foundation Wall Assignment		Solar Absorptance		Surface Area	Location	Effective U- factor
front entry	Fiberglass R-5	1st floor ambient		0.9	0.75	Medium	20.0 ft² E	Exposed Exterior	0.200
garage entry	Fiberglass R-5	1st floor garage		0.9	0.75	Medium	18.0 ft²	Unconditioned, attached garage	0.200

Roof Ir	nsulat	tion								
	Name	Library Type	Attic Exterior Area [ft²]		Does the Roof have Eaves?		Surface Color	Solar Absorptance	Surface Area	Location
	attic	R 38 Attic BLOWN FG G1 2x6 16"OC NO Radiant Barrier	1,546.44	No	No	-	Dark	0.9	1,052.0 ft²	Vented Attic

Roof Insulation	Library List		Whole House Inf	iltration	
Name	Has Radiant Barrier	Effective R-value	Infiltration	Measurement Type	Shelter Class
R 38 Attic BLOWN FG G1 2x6 16"OC NO Radiant Barrier		37.887	1270 CFM at 50 Pa	Blower-door tested	4

Mechanicals, Lights & Water

Lighting					
% Interior Fluorescent Lighting		% Exterior Fluorescent Lighting		% Garage Fluorescent Lighting	% Garage LED Lighting
0	100	0	100	0	100

Conditioning Ed	Conditioning Equipment							
Name	Library Type	Serial Number	Heating Percent Load	Cooling Percent Load	Hot Water Percent Load			
Water Heating	z 50 gal. 0.92 EF Elec		0%	0%	100%	Unspecified		
whole house heat pump	z 36k 14.3 SEER2 7.5 HSPF2		100%	100%	0%	Unspecified		

Property , NC 27546 Model: CC 1790 Community: NA Project & Plan
Template - Caviness & Cates - CC 1790 - CZ 4 slab - HE
CC 1790 slab

OrganizationSouthern Energy Management
Justin Smith

Inspection Status Results are projected Builder Caviness and Cates

Equipment Type: z 36k 14.3 SEER2 7.5 HSPF2				
Equipment Type	Air Source Heat Pump			
Fuel Type	Electric			
Distribution Type	Forced Air			
Motor Type	ECM (Variable Speed)			
Heat Pump System Type	Ducted Split System			
Heating Efficiency	7.5 HSPF2			
Heating Capacity [kBtu/h]	36			
Backup Fuel Type	Electric			
Switchover Temperature [°F]	0			
Backup Heating Efficiency	1 COP			
Use default Supplemental Heat	Yes			
Cooling Efficiency	14.3 SEER2			
Cooling Capacity [kBtu/h]	36			

Equipment Type: z 50 gal. 0.92 EF Elec				
Water Heater				
livery (Radiant)				
Factor				

Distribution Type Forced Air Heating Equipment whole house heat pump Cooling Equipment whole house heat pump Sq. Feet Served 1,790 # Return Grilles 3 Supply Duct R Value 8 Return Duct R Value 8 Supply Duct Area [ft²] 483.3 Return Duct Area [ft²] 268.5 Leakage to Outdoors 71 CFM @ 25Pa (3.97 / 100 ft²) Total Leakage 71 CFM25 Total Leakage Duct Test Conditions Post-Construction Use Default Flow Rate Yes Duct 1 Duct Location Attic (well vented)
Cooling Equipment whole house heat pump Sq. Feet Served 1,790 # Return Grilles 3 Supply Duct R Value 8 Return Duct R Value 8 Supply Duct Area [ft²] 483.3 Return Duct Area [ft²] 268.5 Leakage to Outdoors 71 CFM @ 25Pa (3.97 / 100 ft²) Total Leakage 71 CFM25 Total Leakage Duct Test Conditions Use Default Flow Rate Yes Duct 1
Sq. Feet Served 1,790 # Return Grilles 3 Supply Duct R Value 8 Return Duct R Value 8 Supply Duct Area [ft²] 483.3 Return Duct Area [ft²] 268.5 Leakage to Outdoors 71 CFM @ 25Pa (3.97 / 100 ft²) Total Leakage 71 CFM25 Total Leakage Duct Test Conditions Post-Construction Use Default Flow Rate Yes Duct 1
Return Grilles 3 Supply Duct R Value 8 Return Duct R Value 8 Supply Duct Area [ft²] 483.3 Return Duct Area [ft²] 268.5 Leakage to Outdoors 71 CFM @ 25Pa (3.97 / 100 ft²) Total Leakage 71 CFM25 Total Leakage Duct Test Conditions Post-Construction Use Default Flow Rate Yes Duct 1
Supply Duct R Value 8 Return Duct R Value 8 Supply Duct Area [ft²] 483.3 Return Duct Area [ft²] 268.5 Leakage to Outdoors 71 CFM @ 25Pa (3.97 / 100 ft²) Total Leakage 71 CFM25 Total Leakage Duct Test Conditions Post-Construction Use Default Flow Rate Yes Duct 1
Return Duct R Value 8 Supply Duct Area [ft²] 483.3 Return Duct Area [ft²] 268.5 Leakage to Outdoors 71 CFM @ 25Pa (3.97 / 100 ft²) Total Leakage 71 CFM25 Total Leakage Duct Test Conditions Post-Construction Use Default Flow Rate Yes Duct 1
Supply Duct Area [ft²] 483.3 Return Duct Area [ft²] 268.5 Leakage to Outdoors 71 CFM @ 25Pa (3.97 / 100 ft²) Total Leakage 71 CFM25 Total Leakage Duct Test Conditions Post-Construction Use Default Flow Rate Yes Duct 1
Return Duct Area [ft²] 268.5 Leakage to Outdoors 71 CFM @ 25Pa (3.97 / 100 ft²) Total Leakage 71 CFM25 Total Leakage Duct Test Conditions Post-Construction Use Default Flow Rate Yes Duct 1
Leakage to Outdoors 71 CFM @ 25Pa (3.97 / 100 ft²) Total Leakage 71 CFM25 Total Leakage Duct Test Conditions Post-Construction Use Default Flow Rate Yes Duct 1
Total Leakage 71 CFM25 Total Leakage Duct Test Conditions Post-Construction Use Default Flow Rate Yes Duct 1
Total Leakage Duct Test Conditions Post-Construction Use Default Flow Rate Yes Duct 1
Use Default Flow Rate Yes Duct 1
Duct 1
Duct Location Attic (well vented)
Percent Supply Area 60
Percent Return Area 60
Duct 2
Duct Location Conditioned Space
Percent Supply Area 40
Percent Return Area 40

Water Distribution	
Water Fixture Type	Standard
Use Default Hot Water Pipe Length	No
Hot Water Pipe Length [ft]	66
At Least R3 Pipe Insulation?	No
Hot Water Recirculation System?	No
Drain Water Heat Recovery?	No

Appliances & Notes

Clothes Dryer	
Cef	3.01
Fuel Type	Electric
Field Utilization	Timer Controls
Is Outside Conditioned Space	No
Defaults Type	HERS Reference
Is Ventless	No
Is Heat Pump	No
Clothes Dryer Available	Yes

Clothes Washer	
Label Energy Rating	153 kWh/Year
Annual Gas Cost	\$12.00
Electric Rate	\$0.11/kWh
Gas Rate	\$1.22/Therm
Capacity	3.31
Imef	2.1547
Defaults Type	Custom
Load Type	Front-load
Loads Per Week	6
Is Outside Conditioned Space	No
Clothes Washer Available	Yes

Property , NC 27546 Model: CC 1790 Community: NA Project & Plan
Template - Caviness & Cates - CC 1790 - CZ 4 slab - HE
CC 1790 slab

Organization Southern Energy Management Justin Smith Inspection Status Results are projected Builder Caviness and Cates

Dishwasher	
Dishwasher Defaults Type	Custom
Dishwasher Size	Standard
Dishwasher Efficiency	270 kWh
Annual Gas Cost	\$22.23
Electric Rate	\$0.12/kWh
Gas Rate	\$1.09/Therm
Is Outside Conditioned Space	No
Dishwasher Available	Yes

Appliances and Controls	
Thermostat Cooling Setpoint	* * * * 75.0
Thermostat Heating Setpoint	* * * * 70.0
Range/Oven Fuel	Electric
Convection Oven?	No
Induction Range?	No
Range/Oven Outside Conditioned Space?	No
Refrigerator Consumption	538 kWh/Year
Refrigerator Outside Conditioned Space?	No

Notes

initial inputs JSm 09/08/25

-confirm HVAC specs -modeled to worst case orientation -confirm cfl lighting %

Components Not Found: Foundation Wall, Foundation Wall Library List, Skylight, Mechanical Ventilation, Onsite Generation, Solar Generation, Dehumidifier, Whole House Fan, Whole House Fan Library List, HVAC Grading (Not Conducted), Ceiling Fan