

RE: 24030108-01  
1002 Serenity-Roof-B326 BRH COP BR4

Trenco  
818 Soundside Rd  
Edenton, NC 27932

**Site Information:**

Customer: David Weekley Homes Project Name: 24030108-01  
Lot/Block: 1002 Model:  
Address: 1027 SERENITY WALK PARKWAY Subdivision: Serenity  
City: Fuquay Varina State: NC

**General Truss Engineering Criteria & Design Loads (Individual Truss Design Drawings Show Special Loading Conditions):**

Design Code: IRC2018/TPI2014  
Wind Code: ASCE 7-16  
Roof Load: 40.0 psf

Design Program: MiTek 20/20 8.7  
Wind Speed: 130 mph  
Floor Load: N/A psf

This package includes 38 individual, dated Truss Design Drawings and 0 Additional Drawings.

No.	Seal#	Truss Name	Date	No.	Seal#	Truss Name	Date
1	I65383268	D02	5/7/2024	21	I65383288	VLD6	5/7/2024
2	I65383269	B02	5/7/2024	22	I65383289	VLD7	5/7/2024
3	I65383270	D01	5/7/2024	23	I65383290	VLB1	5/7/2024
4	I65383271	A06	5/7/2024	24	I65383291	VLB2	5/7/2024
5	I65383272	A09	5/7/2024	25	I65383292	VLB3	5/7/2024
6	I65383273	A08	5/7/2024	26	I65383293	VLB4	5/7/2024
7	I65383274	A07	5/7/2024	27	I65383294	VLB5	5/7/2024
8	I65383275	A05	5/7/2024	28	I65383295	VLB6	5/7/2024
9	I65383276	G01	5/7/2024	29	I65383296	VLB7	5/7/2024
10	I65383277	A01	5/7/2024	30	I65383297	VLB8	5/7/2024
11	I65383278	A03	5/7/2024	31	I65383298	PBA2	5/7/2024
12	I65383279	A04	5/7/2024	32	I65383299	PBA	5/7/2024
13	I65383280	H01	5/7/2024	33	I65383300	PBA1	5/7/2024
14	I65383281	H02	5/7/2024	34	I65383301	C01	5/7/2024
15	I65383282	J01	5/7/2024	35	I65383302	C02	5/7/2024
16	I65383283	VLD1	5/7/2024	36	I65383303	B03	5/7/2024
17	I65383284	VLD2	5/7/2024	37	I65383304	B01	5/7/2024
18	I65383285	VLD3	5/7/2024	38	I65383305	E01	5/7/2024
19	I65383286	VLD4	5/7/2024				
20	I65383287	VLD5	5/7/2024				


The truss drawing(s) referenced above have been prepared by  
Truss Engineering Co. under my direct supervision  
based on the parameters provided by Carter Components (Sanford, NC)).

Truss Design Engineer's Name: Pohlman, Elizabeth

My license renewal date for the state of North Carolina is December 31, 2025.

North Carolina COA: C-0844

IMPORTANT NOTE: The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to TRENCO. Any project specific information included is for TRENCO customers file reference purpose only, and was not taken into account in the preparation of these designs. TRENCO has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.




Job	Truss	Truss Type	Qty	Ply	1002 Serenity-Roof-B326 BRH COP BR4	I65383268
24030108-01	D02	Common Girder	1	3	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Apr 25 2024 Print: 8.730 S Apr 25 2024 MiTek Industries, Inc. Mon May 06 11:58:40  
ID:ahvaep5BmWascBuTkn6buzRAib-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:58.3

Plate Offsets (X, Y): [1:0-9-0,0-5-0], [5:0-9-0,0-5-0], [6:0-9-12,0-6-0], [8:0-9-12,0-6-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.37	Vert(LL)	-0.09	8-14	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.52	Vert(CT)	-0.15	8-14	>999	180		
TCDL	10.0	Rep Stress Incr	NO	WB	0.86	Horz(CT)	0.02	5	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 544 lb	FT = 20%

#### LUMBER

TOP CHORD 2x6 SP No.2  
BOT CHORD 2x12 SP 2400F 2.0E  
WEBS 2x4 SP No.3 \*Except\* 8-3,6-3:2x4 SP No.2  
WEDGE Left: 2x4 SP No.3  
Right: 2x4 SP No.3

#### BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS

(size) 1=0-5-8, 5=0-5-8  
Max Horiz 1=-180 (LC 10)  
Max Grav 1=14904 (LC 21), 5=10832 (LC 6)

#### FORCES

(lb) - Maximum Compression/Maximum Tension  
TOP CHORD 3-4=-12461/0, 4-5=-12592/0, 1-2=-14114/0, 2-3=-14046/0  
BOT CHORD 1-8=0/10837, 6-8=0/7190, 5-6=0/9583  
WEBS 2-8=-232/269, 3-8=0/10561, 3-6=0/7003, 4-6=-148/268

#### NOTES

- 3-ply truss to be connected together as follows:  
Top chords connected with 10d (0.131"x3") nails as follows: 2x6 - 2 rows staggered at 0-9-0 oc.  
Bottom chords connected with Simpson SDS 1/4 x 4-1/2 screws as follows: 2x12 - 3 rows staggered at 0-4-0 oc.  
Web chords connected with 10d (0.131"x3") nails as follows: 2x4 - 1 row at 0-9-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Unbalanced roof live loads have been considered for this design.

4) Wind: ASCE 7-16; Vult=130mph (3-second gust)  
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60

5) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10

6) Unbalanced snow loads have been considered for this design.

7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.

8) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.

9) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

10) Use Simpson Strong-Tie HTU210 (32-10d Girder, 14-10dx1 1/2 Truss, Single Ply Girder) or equivalent spaced at 2-0-0 oc max. starting at 4-4-4 from the left end to 16-4-4 to connect truss(es) to back face of bottom chord.

11) Fill all nail holes where hanger is in contact with lumber.

12) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 8833 lb down and 522 lb up at 2-6-8 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

#### LOAD CASE(S) Standard

- Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15  
Uniform Loads (lb/ft)  
Vert: 3-5=-60, 1-3=-60, 9-12=-20  
Concentrated Loads (lb)

Vert: 7=-1900 (B), 8=-1900 (B), 6=-1900 (B), 15=-5487 (B), 16=-1904 (B), 18=-1900 (B), 19=-1900 (B), 20=-1900 (B)



May 7, 2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute ([www.tpinst.org](http://www.tpinst.org)) and **BCSI Building Component Safety Information** available from the Structural Building Component Association ([www.sbcacomponents.com](http://www.sbcacomponents.com))

ENGINEERING BY  
**TRENCO**  
A MiTek Affiliate

818 Soundside Road  
Edenton, NC 27932


Job	Truss	Truss Type	Qty	Ply	1002 Serenity-Roof-B326 BRH COP BR4	I65383269
24030108-01	B02	Common Girder	1	2	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Apr 25 2024 Print: 8.730 S Apr 25 2024 MiTek Industries, Inc. Mon May 06 11:58:39

Page: 1

ID: iFFKd9\_s5HOVK9vBFwqTAGzRAMn-RfC?PsB70Hq3NSgPqnL8w3uITXbGKwRCDoi7J4zJC?i



Scale = 1:75.3

Plate Offsets (X, Y): [1:Edge,0-2-13], [5:Edge,0-2-13], [6:0-8-0,0-5-0], [8:0-8-0,0-7-12], [9:0-8-0,0-5-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.26	Vert(LL)	-0.08	8-9	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.32	Vert(CT)	-0.14	8-9	>999	180	MT18HS	244/190
TCDL	10.0	Rep Stress Incr	NO	WB	0.95	Horz(CT)	0.02	6	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 425 lb	FT = 20%

#### LUMBER

TOP CHORD 2x6 SP No.2  
BOT CHORD 2x10 SP 2400F 2.0E  
WEBS 2x4 SP No.2  
WEDGE Left: 2x4 SP No.3

#### BRACING

TOP CHORD Structural wood sheathing directly applied or 5-2-1 oc purlins.  
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

**REACTIONS** (size) 1=0-5-8, 5=0-7-12, 6=0-5-8  
Max Horiz 1=-226 (LC 35)  
Max Uplift 1=-238 (LC 12), 5=-272 (LC 13), 6=-756 (LC 13)  
Max Grav 1=7853 (LC 5), 5=680 (LC 19), 6=11535 (LC 6)

#### FORCES


(lb) - Maximum Compression/Maximum Tension  
TOP CHORD 1-2=-8739/293, 2-3=-4456/244, 3-4=-4460/253, 4-5=-108/355  
BOT CHORD 1-9=-268/6662, 8-9=-268/6662, 6-8=-252/75, 5-6=-252/75  
WEBS 2-9=-121/5557, 2-8=-4535/335, 3-8=-190/5246, 4-8=-89/4874, 4-6=-6506/219

#### NOTES

- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:  
Top chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.  
Bottom chords connected as follows: 2x10 - 3 rows staggered at 0-5-0 oc.  
Web connected as follows: 2x4 - 1 row at 0-6-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust)  
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- All plates are MT20 plates unless otherwise indicated.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 1 and 5. This connection is for uplift only and does not consider lateral forces.
- LGT2 Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 6. This connection is for uplift only and does not consider lateral forces.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Use Simpson Strong-Tie HTU26 (20-10d Girder, 11-10dx1 1/2 Truss) or equivalent spaced at 2-0-0 oc max. starting at 2-0-0 from the left end to 15-10-0 to connect truss(es) to back face of bottom chord.

- Use Simpson Strong-Tie LUS26 (4-10d Girder, 3-10d Truss) or equivalent at 17-10-0 from the left end to connect truss(es) to back face of bottom chord.
  - Use Simpson Strong-Tie HTU26 (20-10d Girder, 11-10dx1 1/2 Truss, Single Ply Girder) or equivalent spaced at 2-0-0 oc max. starting at 19-10-0 from the left end to 21-10-0 to connect truss(es) to back face of bottom chord.
  - Fill all nail holes where hanger is in contact with lumber.
  - LGT2 Hurricane ties must have two studs in line below the truss.
- LOAD CASE(S)** Standard
- Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15  
Uniform Loads (lb/ft)  
Vert: 1-3=-60, 3-5=-60, 10-13=-20  
Concentrated Loads (lb)  
Vert: 7=-1817 (B), 9=-1817 (B), 18=-1817 (B), 19=-1817 (B), 20=-1817 (B), 21=-1817 (B), 22=-1817 (B), 23=-1817 (B), 24=-873 (B), 25=-873 (B), 26=-873 (B)



May 7, 2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY  
**TRENCO**  
A MiTek Affiliate


818 Soundside Road  
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1002 Serenity-Roof-B326 BRH COP BR4	I65383270
24030108-01	D01	Common Supported Gable	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Apr 25 2024 Print: 8.730 S Apr 25 2024 MiTek Industries, Inc. Mon May 06 11:58:40  
ID:8F2D7hHuvW?rb9K6OMb\_Y2zRqE-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:56.8

Plate Offsets (X, Y): [7:0-2-8,Edge]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.21	Vert(LL)	n/a	-	n/a	999	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.12	Vert(CT)	n/a	-	n/a	999	
TCDL	10.0	Rep Stress Incr	YES	WB	0.20	Horz(CT)	0.00	14	n/a	n/a	
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MR							
BCDL	10.0										
Weight: 126 lb FT = 20%											

#### LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
WEBS	2x4 SP No.3
OTHERS	2x4 SP No.3

#### BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS	(size)	14=18-5-0, 15=18-5-0, 16=18-5-0, 17=18-5-0, 18=18-5-0, 20=18-5-0, 21=18-5-0, 22=18-5-0, 23=18-5-0, 24=18-5-0
Max Horiz		24=224 (LC 13)
Max Uplift		14=50 (LC 11), 15=163 (LC 15), 16=47 (LC 15), 17=116 (LC 15), 21=114 (LC 14), 22=47 (LC 14), 23=168 (LC 14), 24=69 (LC 10)
Max Grav		14=189 (LC 28), 15=219 (LC 25), 16=173 (LC 22), 17=253 (LC 22), 18=225 (LC 22), 20=225 (LC 21), 21=253 (LC 21), 22=173 (LC 21), 23=226 (LC 24), 24=204 (LC 25)

#### FORCES

(lb) - Maximum Compression/Maximum Tension

TOP CHORD	2-24=-167/63, 1-2=0/39, 2-3=-165/140, 3-4=-104/90, 4-5=-92/115, 5-6=-114/233, 6-7=-91/169, 7-8=-91/169, 8-9=-114/233, 9-10=-77/115, 10-11=-89/71, 11-12=-153/116, 12-13=0/39, 12-14=-154/47
BOT CHORD	23-24=-106/187, 22-23=-106/187, 21-22=-106/187, 20-21=-106/187, 18-20=-106/187, 17-18=-106/187, 16-17=-106/187, 15-16=-106/187, 14-15=-106/187

#### WEBS


6-20=-185/8, 8-18=-185/6, 5-21=-213/162, 4-22=-133/94, 3-23=-159/159, 9-17=-213/162, 10-16=-133/92, 11-15=-155/167

#### NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Corner(3E) -0-10-8 to 2-2-12, Exterior(2N) 2-2-12 to 6-2-8, Corner(3R) 6-2-8 to 12-2-4, Exterior(2N) 12-2-4 to 16-2-4, Corner(3E) 16-2-4 to 19-3-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.

- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 69 lb uplift at joint 24, 50 lb uplift at joint 14, 114 lb uplift at joint 21, 47 lb uplift at joint 22, 168 lb uplift at joint 23, 116 lb uplift at joint 17, 47 lb uplift at joint 16 and 163 lb uplift at joint 15.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



May 7, 2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute ([www.tpinst.org](http://www.tpinst.org)) and **BCSI Building Component Safety Information** available from the Structural Building Component Association ([www.sbcacompnents.com](http://www.sbcacompnents.com))

ENGINEERING BY  
**TRENCO**  
A MiTek Affiliate

818 Soundside Road  
Edenton, NC 27932




Job	Truss	Truss Type	Qty	Ply	1002 Serenity-Roof-B326 BRH COP BR4	165383271
24030108-01	A06	Attic Girder	1	4	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Apr 25 2024 Print: 8.730 S Apr 25 2024 MiTek Industries, Inc. Mon May 06 11:58:36

Page: 1

ID:PgZvt1?lwruINEY\_xH4fkzR7p-RfC?PsB70Hq3NSgPqnL8w3uITXbGKwRCDoi7J4zJC?f



Job	Truss	Truss Type	Qty	Ply	1002 Serenity-Roof-B326 BRH COP BR4	I65383271
24030108-01	A06	Attic Girder	1	4	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Apr 25 2024 Print: 8.730 S Apr 25 2024 MiTek Industries, Inc. Mon May 06 11:58:36

Page: 2

ID:pGeZvt1?lwruINEY\_xH4fkzRAp7-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?i

- 4) Wind: ASCE 7-16; Vult=130mph (3-second gust)  
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat.  
II; Exp B; Enclosed; MWFRS (envelope) exterior zone;  
cantilever left and right exposed ; end vertical left and  
right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 5) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15  
Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate  
DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9;  
Cs=1.00; Ct=1.10
- 6) Unbalanced snow loads have been considered for this  
design.
- 7) This truss has been designed for greater of min roof live  
load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on  
overhangs non-concurrent with other live loads.
- 8) Provide adequate drainage to prevent water ponding.
- 9) All plates are 3x5 MT20 unless otherwise indicated.
- 10) This truss has been designed for a 10.0 psf bottom  
chord live load nonconcurrent with any other live loads.
- 11) \* This truss has been designed for a live load of 20.0psf  
on the bottom chord in all areas where a rectangle  
3-06-00 tall by 2-00-00 wide will fit between the bottom  
chord and any other members, with BCDL = 10.0psf.
- 12) Ceiling dead load (5.0 psf) on member(s). 7-50, 45-50,  
44-45, 44-47, 46-47, 43-46, 14-43; Wall dead load  
(5.0psf) on member(s).7-37, 14-23
- 13) Bottom chord live load (40.0 psf) and additional bottom  
chord dead load (5.0 psf) applied only to room. 34-37,  
32-34, 30-32, 28-30, 27-28, 24-27, 23-24
- 14) Refer to girder(s) for truss to truss connections.
- 15) Provide mechanical connection (by others) of truss to  
bearing plate capable of withstanding 407 lb uplift at joint  
18 and 5346 lb uplift at joint 21.
- 16) LGT4-SDS3 Simpson Strong-Tie connectors  
recommended to connect truss to bearing walls due to  
UPLIFT at jt(s) 42. This connection is for uplift only and  
does not consider lateral forces.
- 17) This truss is designed in accordance with the 2018  
International Residential Code sections R502.11.1 and  
R802.10.2 and referenced standard ANSI/TPI 1.
- 18) Graphical purlin representation does not depict the size  
or the orientation of the purlin along the top and/or  
bottom chord.
- 19) This truss has large uplift reaction(s) from gravity load  
case(s). Proper connection is required to secure truss  
against upward movement at the bearings. Building  
designer must provide for uplift reactions indicated.
- 20) LGT4 Hurricane ties must have four studs in line below  
the truss.
- 21) Hanger(s) or other connection device(s) shall be  
provided sufficient to support concentrated load(s) 9100  
lb down and 774 lb up at 15-11-0 on bottom chord. The  
design/selection of such connection device(s) is the  
responsibility of others.
- 22) Attic room checked for L/360 deflection.

#### LOAD CASE(S) Standard

- 1) Dead + Snow (balanced): Lumber Increase=1.15, Plate  
Increase=1.15  
Uniform Loads (lb/ft)  
Vert: 1-2=-60, 2-8=-60, 8-13=-60, 13-18=-60,  
42-51=-20, 23-37=-30, 7-50=-10, 45-50=-10,  
44-45=-10, 44-49=-10, 47-49=-10, 46-47=-10,  
43-46=-10, 14-43=-10  
Drag: 37-48=-10, 7-48=-10, 14-23=-10  
Concentrated Loads (lb)  
Vert: 38=-4881 (F)

#### WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute ([www.tpinst.org](http://www.tpinst.org)) and **BCSI Building Component Safety Information** available from the Structural Building Component Association ([www.sbcacomponents.com](http://www.sbcacomponents.com))

ENGINEERING BY  
**TRENCO**  
A MiTek Affiliate

818 Soundside Road  
Edenton, NC 27932


Job	Truss	Truss Type	Qty	Ply	1002 Serenity-Roof-B326 BRH COP BR4	165383272
24030108-01	A09	Attic Supported Gable	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Apr 25 2024 Print: 8.730 S Apr 25 2024 MiTek Industries, Inc. Mon May 06 11:58:38

Page: 1

ID:8kdnaNVfrYX75iJovJ26tzRBB2-RfC?PsB70Hq3NSgPqnL8w3uITxBGKWrCdoi7J4zJC?r




Scale = 1:90.8

Plate Offsets (X, Y): [6:0-5-0,0-4-8], [10:0-5-8,0-3-0], [15:0-5-8,0-3-0], [39:0-4-0,0-2-4], [54:0-4-0,0-2-4], [66:0-2-11,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.43	Vert(LL)	n/a	-	n/a	999	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.12	Vert(TL)	n/a	-	n/a	999	
TCDL	10.0	Rep Stress Incr	YES	WB	0.62	Horiz(TL)	0.02	27	n/a	n/a	
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH							
BCDL	10.0										
Weight: 504 lb FT = 20%											

<b>LUMBER</b>		Max Uplift	28=-89 (LC 14), 29=-189 (LC 15), 30=-17 (LC 14), 31=-49 (LC 15), 32=-43 (LC 15), 33=-44 (LC 15), 34=-45 (LC 15), 36=-46 (LC 15), 37=-124 (LC 38), 38=-1 (LC 10), 56=-115 (LC 38), 58=-45 (LC 14), 59=-50 (LC 14), 60=-37 (LC 14), 61=-47 (LC 14), 62=-28 (LC 14), 63=-119 (LC 14), 64=-109 (LC 15)	BOT CHORD	63-64=-79/168, 62-63=-79/168, 61-62=-79/168, 60-61=-79/168, 59-60=-79/168, 58-59=-79/168, 56-58=-79/168, 55-56=-79/168, 53-55=-85/183, 51-53=-63/129, 49-51=-57/117, 47-49=-68/129, 44-47=-58/112, 41-44=-64/115, 38-41=-80/140, 37-38=-78/164, 36-37=-78/164, 34-36=-78/164, 33-34=-78/164, 32-33=-78/164, 31-32=-78/164, 30-31=-78/164, 29-30=-78/164, 28-29=-78/164, 27-28=-78/164, 52-54=-16/38, 50-52=-21/50, 48-50=-14/38, 46-48=-14/38, 45-46=-14/38, 40-45=-22/54, 39-40=-19/51
TOP CHORD	2x6 SP No.2				
BOT CHORD	2x4 SP No.2 *Except* 35-27,57-42:2x4 SP 2400F 2.0E, 57-64:2x4 SP No.1	Max Grav	28=538 (LC 24), 29=71 (LC 18), 30=215 (LC 6), 31=164 (LC 49), 32=177 (LC 37), 33=216 (LC 43), 34=234 (LC 43), 36=217 (LC 43), 37=142 (LC 49), 38=1161 (LC 38), 41=327 (LC 20), 44=301 (LC 20), 47=230 (LC 20), 49=231 (LC 20), 51=301 (LC 20), 53=330 (LC 20), 55=1134 (LC 38), 56=144 (LC 47), 58=228 (LC 41), 59=239 (LC 41), 60=223 (LC 41), 61=191 (LC 35), 62=164 (LC 56), 63=286 (LC 47), 64=100 (LC 50)		
WEBS	2x4 SP No.3 *Except* 9-55,16-38,64-1:2x6 SP No.2, 16-66,66-9:2x4 SP No.2				
OTHERS	2x4 SP No.3 *Except* 0-0,0-0,0-0,0-0,0-0:2x4 SPF No.2(flat)				
<b>BRACING</b>					
TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (4-2-4 max.): 10-15.				
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing, Except: 10-0-0 oc bracing: 48-50,46-48,45-46,40-45,39-40.				
WEBS	T-Brace: 2x4 SPF No.2 - 9-54, 16-39, 17-37, 18-36, 8-56, 7-58				
	Fasten (2X) T and I braces to narrow edge of web with 10d (0.131"x3") nails, 6in o.c.,with 3in minimum end distance.				
	Brace must cover 90% of web length.				
JOINTS	1 Brace at Jt(s): 68, 69, 70, 71				
<b>REACTIONS</b> (size)					
	27=53-5-0, 28=53-5-0, 29=53-5-0, 30=53-5-0, 31=53-5-0, 32=53-5-0, 33=53-5-0, 34=53-5-0, 36=53-5-0, 37=53-5-0, 38=53-5-0, 41=53-5-0, 44=53-5-0, 47=53-5-0, 49=53-5-0, 51=53-5-0, 53=53-5-0, 55=53-5-0, 56=53-5-0, 58=53-5-0, 59=53-5-0, 60=53-5-0, 61=53-5-0, 62=53-5-0, 63=53-5-0, 64=53-5-0				
	Max Horiz 64=222 (LC 15)				
<b>FORCES</b>					
	(lb) - Maximum Compression/Maximum Tension				
TOP CHORD	1-2=-53/118, 2-3=-37/99, 3-4=-52/127, 4-5=-70/149, 5-7=-107/211, 7-8=-122/250, 8-9=-105/267, 9-10=-926/239, 10-11=-2068/439, 11-12=-2800/569, 12-13=-2800/569, 13-14=-2724/564, 14-15=-1991/436, 15-16=-812/241, 16-17=-104/278, 17-18=-123/270, 18-19=-109/246, 19-21=-89/222, 21-22=-70/199, 22-23=-52/176, 23-24=-48/153, 24-25=-69/135, 25-26=-156/123, 26-27=-142/144, 1-64=66/91				



May 7, 2024

Continued on page 2

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY  
**TRENCO**  
A MiTek Affiliate

818 Soundside Road  
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1002 Serenity-Roof-B326 BRH COP BR4
24030108-01	A09	Attic Supported Gable	1	1	I65383272
Job Reference (optional)					

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Apr 25 2024 Print: 8.730 S Apr 25 2024 MiTek Industries, Inc. Mon May 06 11:58:38

Page: 2

ID:8kdnaNVfrXy7X5iJovJ26tzRBB2-RfC?PsB70Hq3NSgPqnL8w3uITxbGKWrCDoi7J4zJC?f

WEBS 54-55=-1090/1, 9-54=-1078/106, **LOAD CASE(S)** Standard

38-39=-1116/28, 16-39=-1101/123,  
48-49=-115/0, 46-47=-115/0, 52-53=-171/0,  
53-54=-57/22, 50-51=-147/0, 51-52=-13/11,  
49-50=-11/13, 40-41=-173/0, 44-45=-148/0,  
40-44=-3/15, 45-47=-10/17, 15-65=-48/11,  
9-67=-16/694, 67-69=-15/688,  
68-69=-279/2058, 68-71=-412/2714,  
70-71=-276/1982, 65-70=-11/565,  
16-65=-13/579, 10-67=-15/15,  
12-68=-256/65, 11-69=-470/113,  
14-70=-483/114, 15-70=-281/1498,  
13-71=-239/66, 14-71=-148/778,  
13-68=-66/182, 39-41=-27/17,  
10-69=-279/1447, 11-68=-145/779,  
17-37=-86/159, 18-36=-176/71,  
19-34=-194/69, 21-33=-177/67,  
22-32=-128/68, 23-31=-118/69,  
24-30=-144/52, 25-29=-31/163,  
26-28=-346/91, 8-56=-87/150, 7-58=-187/70,  
6-59=-199/74, 5-60=-183/61, 4-61=-145/69,  
3-62=-120/62, 2-63=-168/118

#### NOTES

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust)  
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-2-12 to 5-6-14, Interior (1) 5-6-14 to 10-1-6, Exterior(2R) 10-1-6 to 38-11-10, Interior (1) 38-11-10 to 48-0-14, Exterior(2E) 48-0-14 to 53-5-0 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 4) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- 5) Unbalanced snow loads have been considered for this design.
- 6) Provide adequate drainage to prevent water ponding.
- 7) All plates are 2x4 MT20 unless otherwise indicated.
- 8) Gable requires continuous bottom chord bearing.
- 9) Gable studs spaced at 2-0-0 oc.
- 10) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 11) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 12) Ceiling dead load (5.0 psf) on member(s). 9-67, 67-69, 68-69, 68-71, 70-71, 65-70, 16-65; Wall dead load (5.0psf) on member(s).9-54, 16-39
- 13) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 109 lb uplift at joint 64, 1 lb uplift at joint 38, 124 lb uplift at joint 37, 46 lb uplift at joint 36, 45 lb uplift at joint 34, 44 lb uplift at joint 33, 43 lb uplift at joint 32, 49 lb uplift at joint 31, 17 lb uplift at joint 30, 189 lb uplift at joint 29, 89 lb uplift at joint 28, 115 lb uplift at joint 56, 45 lb uplift at joint 58, 50 lb uplift at joint 59, 37 lb uplift at joint 60, 47 lb uplift at joint 61, 28 lb uplift at joint 62 and 119 lb uplift at joint 63.
- 14) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 15) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- 16) Warning: Additional permanent and stability bracing for truss system (not part of this component design) is always required.
- 17) Attic room checked for L/360 deflection.

#### WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute ([www.tpinst.org](http://www.tpinst.org)) and **BCSI Building Component Safety Information** available from the Structural Building Component Association ([www.sbcacomponents.com](http://www.sbcacomponents.com))

ENGINEERING BY  
**TRENCO**  
A MiTek Affiliate

818 Soundside Road  
Edenton, NC 27932




Job	Truss	Truss Type	Qty	Ply	1002 Serenity-Roof-B326 BRH COP BR4	165383273
24030108-01	A08	Attic	6	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Apr 25 2024 Print: 8.730 S Apr 25 2024 MiTek Industries, Inc. Mon May 06 11:58:37

Page: 1

ID:h5TF02itZyfvWtVspKto8\_zRQij-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?r



Scale = 1:92.5

[2:0-5-0,0-4-8], [4:0-5-8,0-3-0], [9:0-5-8,0-3-0], [11:0-5-0,0-4-8], [13:Edge,0-0-11], [15:0-3-12,0-3-4], [17:0-6-12,0-3-0], [18:0-3-8,0-2-8], [20:0-3-8,0-2-8], [21:0-2-2,0-1-8], [23:0-3-8,0-2-8], [24:0-3-8,0-1-8], [26:0-3-8,0-1-8], [30:0-3-8,0-1-8], [31:0-3-8,0-1-8], [32:0-3-8,0-1-8], [36:0-3-8,0-2-8], [41:0-3-8,0-2-0], [43:0-3-8,0-2-0]

Plate Offsets (X, Y): [43:0-3-8,0-2-0]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.62	-0.47	27-29	>822	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	1.00	-0.77	27-29	>509	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.93	Horz(CT)	0.14	13	n/a	n/a	
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH		Attic	-0.35	19-33	>568	360	
BCDL	10.0										
Weight: 453 lb FT = 20%											


**LUMBER**  
**TOP CHORD** 2x6 SP No.2  
**BOT CHORD** 2x4 SP No.2 \*Except\* 37-35:2x4 SP No.1, 16-13,35-21:2x4 SP 2400F 2.0E  
**WEBS** 2x4 SP No.3 \*Except\* 3-34,10-17,37-1:2x6 SP No.2, 38-10,36-1,38-3:2x4 SP No.2, 33-32,31-30,29-28,19-18,20-23,24-26,15-19: 2x4 SP No.1  
**WEDGE** Right: 2x4 SP No.3  
**BRACING**  
**TOP CHORD** Structural wood sheathing directly applied or 2-11-0 oc purlins, except end verticals, and 2-0-0 oc purlins (3-8-14 max.): 4-9.  
**BOT CHORD** Rigid ceiling directly applied or 2-5-1 oc bracing.  
**WEBS** 1 Row at midpt 2-34, 11-19  
**JOINTS** 1 Brace at Jt(s): 41, 42, 43, 44  
**REACTIONS** (size) 13= Mechanical, 17=0-5-8, 37=0-5-8  
Max Horiz 37=-222 (LC 15)  
Max Uplift 17=-64 (LC 15), 37=-11 (LC 14)  
Max Grav 13=2293 (LC 47), 17=1772 (LC 39), 37=2946 (LC 37)  
**FORCES** (lb) - Maximum Compression/Maximum Tension  
**TOP CHORD** 1-3=-4036/14, 3-4=-2078/107, 4-5=-3066/337, 5-6=-3578/492, 6-7=-3578/492, 7-8=-3636/482, 8-9=-2881/356, 9-10=-1879/124, 10-12=-4101/51, 12-13=-4669/39, 1-37=-2945/55

**BOT CHORD** 36-37=-107/246, 34-36=-17/3372, 32-34=0/3291, 30-32=0/4893, 28-30=0/6218, 26-28=0/6109, 23-26=0/4206, 18-23=0/1402, 17-18=-2240/0, 15-17=-2057/0, 14-15=0/4054, 13-14=-56/4054, 31-33=-1860/0, 29-31=-3333/0, 27-29=-3224/0, 25-27=-3224/0, 24-25=-3224/0, 20-24=-1321/723, 19-20=-42/2039  
**WEBS** 2-36=-699/70, 2-34=-132/368, 33-34=-40/280, 3-33=0/1154, 17-19=-1413/169, 10-19=-33/1155, 11-15=-255/99, 12-15=-577/208, 12-14=0/244, 3-39=-2106/13, 39-41=-2044/13, 41-42=-1781/599, 42-44=-1691/1229, 43-44=-1896/449, 40-43=-2317/29, 10-40=-2457/29, 1-36=0/3431, 27-28=-104/36, 25-26=-393/0, 32-33=0/2241, 31-32=-836/0, 30-31=0/1561, 29-30=-322/34, 28-29=-400/61, 18-19=0/3886, 18-20=-1374/0, 20-23=0/2972, 23-24=-930/0, 24-26=0/2017, 4-39=0/305, 9-40=0/567, 4-41=-298/1341, 5-41=-433/119, 5-42=-167/660, 6-42=-200/79, 9-43=-292/1457, 8-43=-481/114, 8-44=-139/829, 7-44=-245/65, 7-42=-159/109, 15-19=0/5271, 11-19=-580/316

#### NOTES

- 1) Unbalanced roof live loads have been considered for this design.

- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCCL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-2-12 to 5-6-14, Interior (1) 5-6-14 to 10-1-6, Exterior(2R) 10-1-6 to 38-11-10, Interior (1) 38-11-10 to 48-0-14, Exterior(2E) 48-0-14 to 53-5-0 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- 4) Unbalanced snow loads have been considered for this design.
- 5) Provide adequate drainage to prevent water ponding.
- 6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.



May 7, 2024

Continued on page 2

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY  
**TRENCO**  
A MiTek Affiliate

818 Soundside Road  
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1002 Serenity-Roof-B326 BRH COP BR4	I65383273
24030108-01	A08	Attic	6	1	Job Reference (optional)	

- 7) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 8) Ceiling dead load (5.0 psf) on member(s). 3-39, 39-41, 41-42, 42-44, 43-44, 40-43, 10-40; Wall dead load (5.0psf) on member(s).3-33, 10-19
- 9) Bottom chord live load (40.0 psf) and additional bottom chord dead load (5.0 psf) applied only to room. 31-33, 29-31, 27-29, 25-27, 24-25, 20-24, 19-20
- 10) Refer to girder(s) for truss to truss connections.
- 11) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 37 and 17. This connection is for uplift only and does not consider lateral forces.
- 12) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 13) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- 14) Attic room checked for L/360 deflection.

LOAD CASE(S) Standard


Job	Truss	Truss Type	Qty	Ply	1002 Serenity-Roof-B326 BRH COP BR4	165383274
24030108-01	A07	Attic	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Apr 25 2024 Print: 8.730 S Apr 25 2024 MiTek Industries, Inc. Mon May 06 11:58:36

Page: 1

ID:1d5INYb\_SnpjqfH0e1reGzRBHO-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrcD0i7J4zJC?f



Scale = 1:93.8

[2:0-2-12,0-2-0], [3:0-5-0,0-4-8], [5:0-5-8,0-3-0], [10:0-5-8,0-3-0], [12:0-5-0,0-4-8], [14:Edge,0-0-11], [16:0-3-12,0-3-4], [19:0-3-8,0-2-8], [20:0-6-12,Edge], [21:0-3-8,0-2-8], [22:0-2-2,0-1-8], [24:0-3-8,0-2-8], [25:0-3-8,0-1-8], [26:0-3-8,0-1-8], [31:0-3-8,0-1-8], [33:0-3-8,0-1-8], [34:0-3-8,0-1-8], [38:0-3-8,0-2-8], [44:0-3-8,0-2-0], [45:0-3-8,0-2-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.98	Vert(LL)	-0.48	29-32	>819	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.99	Vert(CT)	-0.77	29-32	>506	180	MT18HS	244/190
TCDL	10.0	Rep Stress Incr	YES	WB	0.93	Horz(CT)	0.14	14	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH		Attic	-0.35	20-36	>568	360		
BCDL	10.0											
Weight: 453 lb    FT = 20%												

<b>LUMBER</b>		<b>BOT CHORD</b>		<b>WEBS</b>		<b>WEDGE</b>		<b>BRACING</b>		<b>REACTIONS</b>		<b>FORCES</b>		<b>NOTES</b>	
TOP CHORD	2x6 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2
BOT CHORD	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2
WEBS	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3
WEDGE	Right: 2x4 SP No.3	Right: 2x4 SP No.3	Right: 2x4 SP No.3	Right: 2x4 SP No.3	Right: 2x4 SP No.3	Right: 2x4 SP No.3	Right: 2x4 SP No.3	Right: 2x4 SP No.3	Right: 2x4 SP No.3	Right: 2x4 SP No.3	Right: 2x4 SP No.3	Right: 2x4 SP No.3	Right: 2x4 SP No.3	Right: 2x4 SP No.3	Right: 2x4 SP No.3
BRACING	Structural wood sheathing directly applied or 2-10-14 oc purlins, except end verticals, and 2-0-0 oc purlins (3-8-13 max.): 5-10.	Structural wood sheathing directly applied or 2-10-14 oc purlins, except end verticals, and 2-0-0 oc purlins (3-8-13 max.): 5-10.	Structural wood sheathing directly applied or 2-10-14 oc purlins, except end verticals, and 2-0-0 oc purlins (3-8-13 max.): 5-10.	Structural wood sheathing directly applied or 2-10-14 oc purlins, except end verticals, and 2-0-0 oc purlins (3-8-13 max.): 5-10.	Structural wood sheathing directly applied or 2-10-14 oc purlins, except end verticals, and 2-0-0 oc purlins (3-8-13 max.): 5-10.	Structural wood sheathing directly applied or 2-10-14 oc purlins, except end verticals, and 2-0-0 oc purlins (3-8-13 max.): 5-10.	Structural wood sheathing directly applied or 2-10-14 oc purlins, except end verticals, and 2-0-0 oc purlins (3-8-13 max.): 5-10.	Structural wood sheathing directly applied or 2-10-14 oc purlins, except end verticals, and 2-0-0 oc purlins (3-8-13 max.): 5-10.	Structural wood sheathing directly applied or 2-10-14 oc purlins, except end verticals, and 2-0-0 oc purlins (3-8-13 max.): 5-10.	Structural wood sheathing directly applied or 2-10-14 oc purlins, except end verticals, and 2-0-0 oc purlins (3-8-13 max.): 5-10.	Structural wood sheathing directly applied or 2-10-14 oc purlins, except end verticals, and 2-0-0 oc purlins (3-8-13 max.): 5-10.	Structural wood sheathing directly applied or 2-10-14 oc purlins, except end verticals, and 2-0-0 oc purlins (3-8-13 max.): 5-10.	Structural wood sheathing directly applied or 2-10-14 oc purlins, except end verticals, and 2-0-0 oc purlins (3-8-13 max.): 5-10.	Structural wood sheathing directly applied or 2-10-14 oc purlins, except end verticals, and 2-0-0 oc purlins (3-8-13 max.): 5-10.	Structural wood sheathing directly applied or 2-10-14 oc purlins, except end verticals, and 2-0-0 oc purlins (3-8-13 max.): 5-10.
TOP CHORD	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2
BOT CHORD	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2
WEBS	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3
JOINTS	1 Brace at Jt(s): 43, 44, 45, 46	1 Brace at Jt(s): 43, 44, 45, 46	1 Brace at Jt(s): 43, 44, 45, 46	1 Brace at Jt(s): 43, 44, 45, 46	1 Brace at Jt(s): 43, 44, 45, 46	1 Brace at Jt(s): 43, 44, 45, 46	1 Brace at Jt(s): 43, 44, 45, 46	1 Brace at Jt(s): 43, 44, 45, 46	1 Brace at Jt(s): 43, 44, 45, 46	1 Brace at Jt(s): 43, 44, 45, 46	1 Brace at Jt(s): 43, 44, 45, 46	1 Brace at Jt(s): 43, 44, 45, 46	1 Brace at Jt(s): 43, 44, 45, 46	1 Brace at Jt(s): 43, 44, 45, 46	1 Brace at Jt(s): 43, 44, 45, 46
REACTIONS	(size) 14= Mechanical, 18=0-5-8, 39=0-5-8	(size) 14= Mechanical, 18=0-5-8, 39=0-5-8	(size) 14= Mechanical, 18=0-5-8, 39=0-5-8	(size) 14= Mechanical, 18=0-5-8, 39=0-5-8	(size) 14= Mechanical, 18=0-5-8, 39=0-5-8	(size) 14= Mechanical, 18=0-5-8, 39=0-5-8	(size) 14= Mechanical, 18=0-5-8, 39=0-5-8	(size) 14= Mechanical, 18=0-5-8, 39=0-5-8	(size) 14= Mechanical, 18=0-5-8, 39=0-5-8	(size) 14= Mechanical, 18=0-5-8, 39=0-5-8	(size) 14= Mechanical, 18=0-5-8, 39=0-5-8	(size) 14= Mechanical, 18=0-5-8, 39=0-5-8	(size) 14= Mechanical, 18=0-5-8, 39=0-5-8	(size) 14= Mechanical, 18=0-5-8, 39=0-5-8	(size) 14= Mechanical, 18=0-5-8, 39=0-5-8
FORCES	(lb) - Maximum Compression/Maximum Tension	(lb) - Maximum Compression/Maximum Tension	(lb) - Maximum Compression/Maximum Tension	(lb) - Maximum Compression/Maximum Tension	(lb) - Maximum Compression/Maximum Tension	(lb) - Maximum Compression/Maximum Tension	(lb) - Maximum Compression/Maximum Tension	(lb) - Maximum Compression/Maximum Tension	(lb) - Maximum Compression/Maximum Tension	(lb) - Maximum Compression/Maximum Tension	(lb) - Maximum Compression/Maximum Tension	(lb) - Maximum Compression/Maximum Tension	(lb) - Maximum Compression/Maximum Tension	(lb) - Maximum Compression/Maximum Tension	(lb) - Maximum Compression/Maximum Tension
TOP CHORD	1-2=0/23, 2-4=-4062/10, 4-5=-2092/107, 5-6=-3079/340, 6-7=-3587/495, 7-8=-3587/495, 8-9=-3645/485, 9-10=-2887/358, 10-11=-1884/127, 11-13=-4121/49, 13-14=-4688/32, 2-39=-2988/71	1-2=0/23, 2-4=-4062/10, 4-5=-2092/107, 5-6=-3079/340, 6-7=-3587/495, 7-8=-3587/495, 8-9=-3645/485, 9-10=-2887/358, 10-11=-1884/127, 11-13=-4121/49, 13-14=-4688/32, 2-39=-2988/71	1-2=0/23, 2-4=-4062/10, 4-5=-2092/107, 5-6=-3079/340, 6-7=-3587/495, 7-8=-3587/495, 8-9=-3645/485, 9-10=-2887/358, 10-11=-1884/127, 11-13=-4121/49, 13-14=-4688/32, 2-39=-2988/71	1-2=0/23, 2-4=-4062/10, 4-5=-2092/107, 5-6=-3079/340, 6-7=-3587/495, 7-8=-3587/495, 8-9=-3645/485, 9-10=-2887/358, 10-11=-1884/127, 11-13=-4121/49, 13-14=-4688/32, 2-39=-2988/71	1-2=0/23, 2-4=-4062/10, 4-5=-2092/107, 5-6=-3079/340, 6-7=-3587/495, 7-8=-3587/495, 8-9=-3645/485, 9-10=-2887/358, 10-11=-1884/127, 11-13=-4121/49, 13-14=-4688/32, 2-39=-2988/71	1-2=0/23, 2-4=-4062/10, 4-5=-2092/107, 5-6=-3079/340, 6-7=-3587/495, 7-8=-3587/495, 8-9=-3645/485, 9-10=-2887/358, 10-11=-1884/127, 11-13=-4121/49, 13-14=-4688/32, 2-39=-2988/71	1-2=0/23, 2-4=-4062/10, 4-5=-2092/107, 5-6=-3079/340, 6-7=-3587/495, 7-8=-3587/495, 8-9=-3645/485, 9-10=-2887/358, 10-11=-1884/127, 11-13=-4121/49, 13-14=-4688/32, 2-39=-2988/71	1-2=0/23, 2-4=-4062/10, 4-5=-2092/107, 5-6=-3079/340, 6-7=-3587/495, 7-8=-3587/495, 8-9=-3645/485, 9-10=-2887/358, 10-11=-1884/127, 11-13=-4121/49, 13-14=-4688/32, 2-39=-2988/71	1-2=0/23, 2-4=-4062/10, 4-5=-2092/107, 5-6=-3079/340, 6-7=-3587/495, 7-8=-3587/495, 8-9=-3645/485, 9-10=-2887/358, 10-11=-1884/127, 11-13=-4121/49, 13-14=-4688/32, 2-39=-2988/71	1-2=0/23, 2-4=-4062/10, 4-5=-2092/107, 5-6=-3079/340, 6-7=-3587/495, 7-8=-3587/495, 8-9=-3645/485, 9-10=-2887/358, 10-11=-1884/127, 11-13=-4121/49, 13-14=-4688/32, 2-39=-2988/71	1-2=0/23, 2-4=-4062/10, 4-5=-2092/107, 5-6=-3079/340, 6-7=-3587/495, 7-8=-3587/495, 8-9=-3645/485, 9-10=-2887/358, 10-11=-1884/127, 11-13=-4121/49, 13-14=-4688/32, 2-39=-2988/71	1-2=0/23, 2-4=-4062/10, 4-5=-2092/107, 5-6=-3079/340, 6-7=-3587/495, 7-8=-3587/495, 8-9=-3645/485, 9-10=-2887/358, 10-11=-1884/127, 11-13=-4121/49, 13-14=-4688/32, 2-39=-2988/71	1-2=0/23, 2-4=-4062/10, 4-5=-2092/107, 5-6=-3079/340, 6-7=-3587/495, 7-8=-3587/495, 8-9=-3645/485, 9-10=-2887/358, 10-11=-1884/127, 11-13=-4121/49, 13-14=-4688/32, 2-39=-2988/71	1-2=0/23, 2-4=-4062/10, 4-5=-2092/107, 5-6=-3079/340, 6-7=-3587/495, 7-8=-3587/495, 8-9=-3645/485, 9-10=-2887/358, 10-11=-1884/127, 11-13=-4121/49, 13-14=-4688/32, 2-39=-2988/71	1-2=0/23, 2-4=-4062/10, 4-5=-2092/107, 5-6=-3079/340, 6-7=-3587/495, 7-8=-3587/495, 8-9=-3645/485, 9-10=-2887/358, 10-11=-1884/127, 11-13=-4121/49, 13-14=-4688/32, 2-39=-2988/71
BOT CHORD	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2
WEBS	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3
WEDGE	Right: 2x4 SP No.3	Right: 2x4 SP No.3	Right: 2x4 SP No.3	Right: 2x4 SP No.3	Right: 2x4 SP No.3	Right: 2x4 SP No.3	Right: 2x4 SP No.3	Right: 2x4 SP No.3	Right: 2x4 SP No.3	Right: 2x4 SP No.3	Right: 2x4 SP No.3	Right: 2x4 SP No.3	Right: 2x4 SP No.3	Right: 2x4 SP No.3	Right: 2x4 SP No.3
BRACING	Structural wood sheathing directly applied or 2-10-14 oc purlins, except end verticals, and 2-0-0 oc purlins (3-8-13 max.): 5-10.	Structural wood sheathing directly applied or 2-10-14 oc purlins, except end verticals, and 2-0-0 oc purlins (3-8-13 max.): 5-10.	Structural wood sheathing directly applied or 2-10-14 oc purlins, except end verticals, and 2-0-0 oc purlins (3-8-13 max.): 5-10.	Structural wood sheathing directly applied or 2-10-14 oc purlins, except end verticals, and 2-0-0 oc purlins (3-8-13 max.): 5-10.	Structural wood sheathing directly applied or 2-10-14 oc purlins, except end verticals, and 2-0-0 oc purlins (3-8-13 max.): 5-10.	Structural wood sheathing directly applied or 2-10-14 oc purlins, except end verticals, and 2-0-0 oc purlins (3-8-13 max.): 5-10.	Structural wood sheathing directly applied or 2-10-14 oc purlins, except end verticals, and 2-0-0 oc purlins (3-8-13 max.): 5-10.	Structural wood sheathing directly applied or 2-10-14 oc purlins, except end verticals, and 2-0-0 oc purlins (3-8-13 max.): 5-10.	Structural wood sheathing directly applied or 2-10-14 oc purlins, except end verticals, and 2-0-0 oc purlins (3-8-13 max.): 5-10.	Structural wood sheathing directly applied or 2-10-14 oc purlins, except end verticals, and 2-0-0 oc purlins (3-8-13 max.): 5-10.	Structural wood sheathing directly applied or 2-10-14 oc purlins, except end verticals, and 2-0-0 oc purlins (3-8-13 max.): 5-10.	Structural wood sheathing directly applied or 2-10-14 oc purlins, except end verticals, and 2-0-0 oc purlins (3-8-13 max.): 5-10.	Structural wood sheathing directly applied or 2-10-14 oc purlins, except end verticals, and 2-0-0 oc purlins (3-8-13 max.): 5-10.	Structural wood sheathing directly applied or 2-10-14 oc purlins, except end verticals, and 2-0-0 oc purlins (3-8-13 max.): 5-10.	Structural wood sheathing directly applied or 2-10-14 oc purlins, except end verticals, and 2-0-0 oc purlins (3-8-13 max.): 5-10.
TOP CHORD	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2
BOT CHORD	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2
WEBS	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3
JOINTS	1 Brace at Jt(s): 43, 44, 45, 46	1 Brace at Jt(s): 43, 44, 45, 46	1 Brace at Jt(s): 43, 44, 45, 46	1 Brace at Jt(s): 43, 44, 45, 46	1 Brace at Jt(s): 43, 44, 45, 46	1 Brace at Jt(s): 43, 44, 45, 46	1 Brace at Jt(s): 43, 44, 45, 46	1 Brace at Jt(s): 43, 44, 45, 46	1 Brace at Jt(s): 43, 44, 45, 46	1 Brace at Jt(s): 43, 44, 45, 46	1 Brace at Jt(s): 43, 44, 45, 46	1 Brace at Jt(s): 43, 44, 45, 46	1 Brace at Jt(s): 43, 44, 45, 46	1 Brace at Jt(s): 43, 44, 45, 46	1 Brace at Jt(s): 43, 44, 45, 46
REACTIONS	(size) 14= Mechanical, 18=0-5-8, 39=0-5-8	(size) 14= Mechanical, 18=0-5-8, 39=0-5-8	(size) 14= Mechanical, 18=0-5-8, 39=0-5-8	(size) 14= Mechanical, 18=0-5-8, 39=0-5-8	(size) 14= Mechanical, 18=0-5-8, 39=0-5-8	(size) 14= Mechanical, 18=0-5-8, 39=0-5-8	(size) 14= Mechanical, 18=0-5-8, 39=0-5-8	(size) 14= Mechanical, 18=0-5-8, 39=0-5-8	(size) 14= Mechanical, 18=0-5-8, 39=0-5-8	(size) 14= Mechanical, 18=0-5-8, 39=0-5-8	(size) 14= Mechanical, 18=0-5-8, 39=0-5-8	(size) 14= Mechanical, 18=0-5-8, 39=0-5-8	(size) 14= Mechanical, 18=0-5-8, 39=0-5-8	(size) 14= Mechanical, 18=0-5-8, 39=0-5-8	(size) 14= Mechanical, 18=0-5-8, 39=0-5-8
FORCES	(lb) - Maximum Compression/Maximum Tension	(lb) - Maximum Compression/Maximum Tension	(lb) - Maximum Compression/Maximum Tension	(lb) - Maximum Compression/Maximum Tension	(lb) - Maximum Compression/Maximum Tension	(lb) - Maximum Compression/Maximum Tension	(lb) - Maximum Compression/Maximum Tension	(lb) - Maximum Compression/Maximum Tension	(lb) - Maximum Compression/Maximum Tension	(lb) - Maximum Compression/Maximum Tension	(lb) - Maximum Compression/Maximum Tension	(lb) - Maximum Compression/Maximum Tension	(lb) - Maximum Compression/Maximum Tension	(lb) - Maximum Compression/Maximum Tension	(lb) - Maximum Compression/Maximum Tension
TOP CHORD	1-2=0/23, 2-4=-4062/10, 4-5=-2092/107, 5-6=-3079/340, 6-7=-3587/495, 7-8=-3587/495, 8-9=-3645/485, 9-10=-2887/358, 10-11=-1884/127, 11-13=-4121/49, 13-14=-4688/32, 2-39=-2988/71	1-2=0/23, 2-4=-4062/10, 4-5=-2092/107, 5-6=-3079/340, 6-7=-3587/495, 7-8=-3587/495, 8-9=-3645/485, 9-10=-2887/358, 10-11=-1884/127, 11-13=-4121/49, 13-14=-4688/32, 2-39=-2988/71	1-2=0/23, 2-4=-4062/10, 4-5=-2092/107, 5-6=-3079/340, 6-7=-3587/495, 7-8=-3587/495, 8-9=-3645/485, 9-10=-2887/358, 10-11=-1884/127, 11-13=-4121/49, 13-14=-4688/32, 2-39=-2988/71	1-2=0/23, 2-4=-4062/10, 4-5=-2092/107, 5-6=-3079/340, 6-7=-3587/495, 7-8=-3587/495, 8-9=-3645/485, 9-10=-2887/358, 10-11=-1884/127, 11-13=-4121/49, 13-14=-4688/32, 2-39=-2988/71	1-2=0/23, 2-4=-4062/10, 4-5=-2092/107, 5-6=-3079/340, 6-7=-3587/495, 7-8=-3587/495, 8-9=-3645/485, 9-10=-2887/358, 10-11=-1884/127, 11-13=-4121/49, 13-14=-4688/32, 2-39=-2988/71	1-2=0/23, 2-4=-4062/10, 4-5=-2092/107, 5-6=-3079/340, 6-7=-3587/495, 7-8=-3587/495, 8-9=-3645/485, 9-10=-2887/358, 10-11=-1884/127, 11-13=-4121/49, 13-14=-4688/32, 2-39=-2988/71	1-2=0/23, 2-4=-4062/10, 4-5=-2092/107, 5-6=-3079/340, 6-7=-3587/495, 7-8=-3587/495, 8-9=-3645/485, 9-10=-2887/358, 10-11=-1884/127, 11-13=-4121/49, 13-14=-4688/32, 2-39=-2988/71	1-2=0/23, 2-4=-4062/10, 4-5=-2092/107, 5-6=-3079/340, 6-7=-3587/495, 7-8=-3587/495, 8-9=-3645/485, 9-10=-2887/358, 10-11=-1884/127, 11-13=-4121/49, 13-14=-4688/32, 2-39=-2988/71	1-2=0/23, 2-4=-4062/10, 4-5=-2092/107, 5-6=-3079/340, 6-7=-3587/495, 7-8=-3587/495, 8-9=-3645/485, 9-10=-2887/358, 10-11=-1884/127, 11-13=-4121/49, 13-14=-4688/32, 2-39=-2988/71	1-2=0/23, 2-4=-4062/10, 4-5=-2092/107, 5-6=-3079/340, 6-7=-3587/495, 7-8=-3587/495, 8-9=-3645/485, 9-10=-2887/358, 10-11=-1884/127, 11-13=-4121/49, 13-14=-4688/32, 2-39=-2988/71	1-2=0/23, 2-4=-4062/10, 4-5=-2092/107, 5-6=-3079/340, 6-7=-3587/495, 7-8=-3587/495, 8-9=-3645/485, 9-10=-2887/358, 10-11=-1884/127, 11-13=-4121/49, 13-14=-4688/32, 2-39=-2988/71	1-2=0/23, 2-4=-4062/10, 4-5=-2092/107, 5-6=-3079/340, 6-7=-3587/495, 7-8=-3587/495, 8-9=-3645/485, 9-10=-2887/358, 10-11=-1884/127, 11-13=-4121/49, 13-14=-4688/32, 2-39=-2988/71	1-2=0/23, 2-4=-4062/10, 4-5=-2092/107, 5-6=-3079/340, 6-7=-3587/495, 7-8=-3587/495, 8-9=-3645/485, 9-10=-2887/358, 10-11=-1884/127, 11-13=-4121/49, 13-14=-4688/32, 2-39=-2988/71	1-2=0/23, 2-4=-4062/10, 4-5=-2092/107, 5-6=-3079/340, 6-7=-3587/495, 7-8=-3587/495, 8-9=-3645/485, 9-10=-2887/358, 10-11=-1884/127, 11-13=-4121/49, 13-14=-4688/32, 2-39=-2988/71	1-2=0/23, 2-4=-4062/10, 4-5=-2092/107, 5-6=-3079/340, 6-7=-3587/495, 7-8=-3587/495, 8-9=-3645/485, 9-10=-2887/358, 10-11=-1884/127, 11-13=-4121/49, 13-14=-4688/32, 2-39=-2988/71
BOT CHORD	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2	2x4 SP No.2
WEBS	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3	2x4 SP No.3
WEDGE	Right: 2x4 SP No.3	Right: 2x4 SP No.3	Right: 2x4 SP No.3	Right: 2x4 SP No.3	Right: 2x4 SP No.3	Right: 2x4 SP No.3	Right: 2x4 SP No.3	Right: 2x4 SP No.3	Right: 2x4 SP No.3	Right: 2x4 SP No.3	Right: 2x4 SP No.3	Right: 2x4 SP No.3			

Job	Truss	Truss Type	Qty	Ply	1002 Serenity-Roof-B326 BRH COP BR4	I65383274
24030108-01	A07	Attic	1	1	Job Reference (optional)	

- 7) All plates are MT20 plates unless otherwise indicated.
- 8) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 9) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 10) Ceiling dead load (5.0 psf) on member(s). 4-42, 42-44, 43-44, 43-46, 45-46, 41-45, 11-41; Wall dead load (5.0psf) on member(s).4-36, 11-20
- 11) Bottom chord live load (40.0 psf) and additional bottom chord dead load (5.0 psf) applied only to room. 34-36, 32-34, 29-32, 27-29, 25-27, 21-25, 20-21
- 12) Refer to girder(s) for truss to truss connections.
- 13) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 39 and 18. This connection is for uplift only and does not consider lateral forces.
- 14) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 15) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- 16) Attic room checked for L/360 deflection.

LOAD CASE(S) Standard

 **WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute ([www.tpinst.org](http://www.tpinst.org)) and **BCSI Building Component Safety Information** available from the Structural Building Component Association ([www.sbcacomponents.com](http://www.sbcacomponents.com))



818 Soundside Road  
Edenton, NC 27932




Job	Truss	Truss Type	Qty	Ply	1002 Serenity-Roof-B326 BRH COP BR4	165383275
24030108-01	A05	Attic Girder	1	4	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Apr 25 2024 Print: 8.730 S Apr 25 2024 MiTek Industries, Inc. Mon May 06 11:58:35

Page: 1

ID:VY0G5gMUgwQZrYxiBXltzRA\_fRfC?PsB70Hq3NSgPqnL8w3uTXbGKwRCDoi7J4zJC?f




Scale = 1:94.1

[7:0-6-4,0-2-4], [12:1-1-0,0-4-0], [14:0-5-0,0-4-8], [16:Edge,0-1-5], [17:0-5-0,0-4-8], [21:0-8-0,0-5-0], [34:0-3-4,Edge], [35:0-8-0,0-4-12], [35:0-1-8,0-6-15],

Plate Offsets (X, Y): [39:0-3-8,0-3-0], [46:0-2-12,0-2-8]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.94	Vert(LL)	-0.37	33-36	>999	240	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.60	Vert(CT)	-0.56	33-36	>703	180	
TCDL	10.0	Rep Stress Incr	NO	WB	0.97	Horz(CT)	0.11	16	n/a	n/a	
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH		Attic	-0.18	21-35	>999	360	
BCDL	10.0										
Weight: 2104 lb FT = 20%											

<b>LUMBER</b>			TOP CHORD	1-2=0/25, 2-3=-13595/787, 3-4=-17405/1036,	<b>NOTES</b>
TOP CHORD	2x6 SP No.2 *Except* 5-7:2x4 SP No.1			4-6=-18801/1123, 6-7=-5901/493,	1) 4-ply truss to be connected together with 10d
BOT CHORD	2x6 SP 2400F 2.0E *Except* 23-21,23-35:2x4 SP No.2, 38-40,17-16:2x6 SP No.2			7-8=-2690/499, 8-9=-2683/500,	(0.131"x3") nails as follows:
WEBS	2x4 SP No.3 *Except* 40-2,6-36,13-19,45-36,46-6,46-13:2x6 SP No.2, 39-2:2x4 SP No.2		BOT CHORD	9-10=-2405/1763, 10-11=-2405/1763, 11-12=-2057/988, 12-13=-3882/380, 13-15=-18187/1097, 15-16=-5584/329, 2-40=-11679/710	Top chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc, 2x4 - 1 row at 0-9-0 oc. Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc, 2x4 - 1 row at 0-9-0 oc. Web connected as follows: 2x6 - 2 rows staggered at 0-4-0 oc, Except member 36-45 2x6 - 3 rows staggered at 0-4-0 oc, member 13-19 2x6 - 2 rows staggered at 0-9-0 oc, 2x4 - 1 row at 0-9-0 oc. Attach BC w/ 1/2" diam. bolts (ASTM A-307) in the center of the member w/washers at 4-0-0 oc.
WEDGE	Right: 2x4 SP No.3			39-40=-129/435, 37-39=-737/12154, 36-37=-844/16242, 33-36=-707/14054, 31-33=-395/17238, 29-31=-7/18596, 27-29=0/19361, 24-27=-54/18028, 20-24=-378/14781, 18-20=-735/13006, 16-18=-241/4880, 32-35=-1124/0, 30-32=-2935/0, 28-30=-3797/0, 26-28=-3797/0, 25-26=-3797/0, 22-25=-2415/0, 21-22=-470/1841	2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
BRACING				35-36=-620/7425, 6-35=-537/8654, 19-21=-664/7226, 13-21=-524/7563, 14-18=-7994/467, 15-17=-6969/419, 32-33=-850/0, 33-35=0/3504, 30-31=-612/0, 31-32=0/1900, 29-30=0/904, 20-22=-1495/0, 24-25=-683/0, 22-24=0/3569, 25-27=0/1449, 9-41=-141/2636, 8-42=-606/63, 11-43=-637/113, 10-44=-153/32, 15-18=-391/7523, 20-21=0/2270, 14-19=-373/7032, 6-48=-11223/711, 42-48=-10400/662, 41-42=-11969/709, 41-44=-11973/710, 43-44=-17476/1058, 43-47=-13172/824, 13-47=-13557/845, 4-37=-719/158, 5-37=-2622/132, 3-39=-5345/374, 3-37=-246/4959, 2-39=-679/12888, 12-47=-149/2544, 9-42=-4491/349, 12-43=-4442/244, 28-29=-219/0, 26-27=-301/0, 5-36=-135/1913, 7-48=-150/2340, 7-42=-5736/319, 11-44=-789/354, 9-44=-6455/395	3) Unbalanced roof live loads have been considered for this design.
TOP CHORD	Structural wood sheathing directly applied or 4-7-10 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 7-12.		WEBS		
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 32-35,30-32,28-30,26-28,25-26,22-25.				
JOINTS	1 Brace at Jt(s): 35, 41, 42, 43, 44				
REACTIONS	(size) 16=20-5-8, 17=20-5-8, 18=20-5-8, 19=20-5-8, 40=0-5-8, 49=20-5-8				
	Max Horiz 40=-182 (LC 10)				
	Max Uplift 16=-151 (LC 13), 17=-319 (LC 12), 18=-240 (LC 13), 19=-10248 (LC 46), 40=-690 (LC 12), 49=-151 (LC 13)				
	Max Grav 16=3001 (LC 46), 17=7106 (LC 23), 18=4185 (LC 46), 19=1025 (LC 12), 40=11867 (LC 46), 49=3001 (LC 46)				
FORCES	(lb) - Maximum Compression/Maximum Tension				



May 7,2024

Continued on page 2

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY  
**TRENCO**  
A MiTek Affiliate

818 Soundside Road  
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1002 Serenity-Roof-B326 BRH COP BR4	I65383275
24030108-01	A05	Attic Girder	1	4	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Apr 25 2024 Print: 8.730 S Apr 25 2024 MiTek Industries, Inc. Mon May 06 11:58:35

Page: 2

ID:VIY0g5gMUGwQZRyxiBXYltzRA\_fRfC?PsB70Hq3NSgPqnL8w3uITXbGKWrcDoi7J4zJC?f

- 4) Wind: ASCE 7-16; Vult=130mph (3-second gust)  
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat.  
II; Exp B; Enclosed; MWFRS (envelope) exterior zone;  
cantilever left and right exposed ; end vertical left and  
right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 5) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15  
Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate  
DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9;  
Cs=1.00; Ct=1.10
- 6) Unbalanced snow loads have been considered for this  
design.
- 7) This truss has been designed for greater of min roof live  
load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on  
overhangs non-concurrent with other live loads.
- 8) Provide adequate drainage to prevent water ponding.
- 9) All plates are 4x5 MT20 unless otherwise indicated.
- 10) This truss has been designed for a 10.0 psf bottom  
chord live load nonconcurrent with any other live loads.
- 11) \* This truss has been designed for a live load of 20.0psf  
on the bottom chord in all areas where a rectangle  
3-06-00 tall by 2-00-00 wide will fit between the bottom  
chord and any other members, with BCDL = 10.0psf.
- 12) Ceiling dead load (5.0 psf) on member(s). 6-48, 42-48,  
41-42, 41-44, 43-44, 43-47, 13-47; Wall dead load  
(5.0psf) on member(s).6-35, 13-21
- 13) Bottom chord live load (40.0 psf) and additional bottom  
chord dead load (5.0 psf) applied only to room. 32-35,  
30-32, 28-30, 26-28, 25-26, 22-25, 21-22
- 14) Provide mechanical connection (by others) of truss to  
bearing plate capable of withstanding 10248 lb uplift at  
joint 19.
- 15) LGT4-SDS3 Simpson Strong-Tie connectors  
recommended to connect truss to bearing walls due to  
UPLIFT at jt(s) 40. This connection is for uplift only and  
does not consider lateral forces.
- 16) One H2.5A Simpson Strong-Tie connectors  
recommended to connect truss to bearing walls due to  
UPLIFT at jt(s) 16, 18, and 17. This connection is for  
uplift only and does not consider lateral forces.
- 17) This truss is designed in accordance with the 2018  
International Residential Code sections R502.11.1 and  
R802.10.2 and referenced standard ANSI/TPI 1.
- 18) Graphical purlin representation does not depict the size  
or the orientation of the purlin along the top and/or  
bottom chord.
- 19) This truss has large uplift reaction(s) from gravity load  
case(s). Proper connection is required to secure truss  
against upward movement at the bearings. Building  
designer must provide for uplift reactions indicated.
- 20) LGT4 Hurricane ties must have four studs in line below  
the truss.
- 21) Hanger(s) or other connection device(s) shall be  
provided sufficient to support concentrated load(s) 608  
lb down and 52 lb up at 28-7-12, and 9100 lb down and  
774 lb up at 16-0-12 on bottom chord. The design/  
selection of such connection device(s) is the  
responsibility of others.
- 22) Attic room checked for L/360 deflection.

#### LOAD CASE(S) Standard

- 1) Dead + Snow (balanced): Lumber Increase=1.15, Plate  
Increase=1.15  
Uniform Loads (lb/ft)  
Vert: 1-2=-60, 2-7=-60, 7-12=-60, 12-16=-60,  
40-49=-20, 21-35=-30, 6-48=-10, 42-48=-10,  
41-42=-10, 41-46=-10, 44-46=-10, 43-44=-10,  
43-47=-10, 13-47=-10  
Drag: 35-45=-10, 6-45=-10, 13-21=-10  
Concentrated Loads (lb)  
Vert: 36=-4881 (F), 60=-326 (F)

#### WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute ([www.tpinst.org](http://www.tpinst.org)) and **BCSI Building Component Safety Information** available from the Structural Building Component Association ([www.sbcacompnents.com](http://www.sbcacompnents.com))

ENGINEERING BY  
**TRENCO**  
A MiTek Affiliate

818 Soundside Road  
Edenton, NC 27932


Job	Truss	Truss Type	Qty	Ply	1002 Serenity-Roof-B326 BRH COP BR4	I65383276
24030108-01	G01	Monopitch	5	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Apr 25 2024 Print: 8.730 S Apr 25 2024 MiTek Industries, Inc. Mon May 06 11:58:40

Page: 1

ID: PdAAD85\_ICJN?UaWrZnF5zRQu2-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:64.4

Plate Offsets (X, Y): [3:0-5-0,0-4-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.49	Vert(LL)	-0.12	7-8	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.66	Vert(CT)	-0.20	7-8	>909	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.39	Horz(CT)	-0.01	7	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 123 lb	FT = 20%

#### LUMBER

TOP CHORD 2x6 SP No.2  
BOT CHORD 2x4 SP No.2  
WEBS 2x4 SP No.3 \*Except\* 9-2:2x6 SP No.2

#### BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.  
WEBS 1 Row at midpt 4-7, 3-7

**REACTIONS** (size) 7= Mechanical, 9=0-5-8  
Max Horiz 9=269 (LC 14)  
Max Uplift 7=219 (LC 14)  
Max Grav 7=825 (LC 5), 9=743 (LC 5)

**FORCES** (lb) - Maximum Compression/Maximum Tension


TOP CHORD 4-7=-321/119, 2-9=-646/82, 1-2=0/25,  
2-4=-678/91, 4-5=-12/0  
BOT CHORD 8-9=-322/219, 7-8=-199/606, 6-7=0/0  
WEBS 3-8=0/310, 3-7=-773/257, 2-8=0/485

#### NOTES

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust)  
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat.  
II; Exp B; Enclosed; MWFRS (envelope) exterior zone  
and C-C Exterior(2E) -0-8-6 to 2-3-10, Interior (1) 2-3-10  
to 12-11-0, Exterior(2E) 12-11-0 to 15-11-0 zone;  
cantilever left and right exposed; end vertical left  
exposed; C-C for members and forces & MWFRS for  
reactions shown; Lumber DOL=1.60 plate grip  
DOL=1.60
- 2) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15  
Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate  
DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9;  
Cs=1.00; Ct=1.10
- 3) Unbalanced snow loads have been considered for this  
design.

- 4) This truss has been designed for greater of min roof live  
load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on  
overhangs non-concurrent with other live loads.
- 5) This truss has been designed for a 10.0 psf bottom  
chord live load nonconcurrent with any other live loads.
- 6) \* This truss has been designed for a live load of 20.0psf  
on the bottom chord in all areas where a rectangle  
3-06-00 tall by 2-00-00 wide will fit between the bottom  
chord and any other members, with BCDL = 10.0psf.
- 7) Refer to girder(s) for truss to truss connections.
- 8) Provide mechanical connection (by others) of truss to  
bearing plate capable of withstanding 219 lb uplift at joint  
7.
- 9) This truss is designed in accordance with the 2018  
International Residential Code sections R502.11.1 and  
R802.10.2 and referenced standard ANSI/TPI 1.

**LOAD CASE(S)** Standard



May 7, 2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY  
**TRENCO**  
A MiTek Affiliate

818 Soundside Road  
Edenton, NC 27932


Job	Truss	Truss Type	Qty	Ply	1002 Serenity-Roof-B326 BRH COP BR4	165383277
24030108-01	A01	Piggyback Base Supported Gable	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Apr 25 2024 Print: 8.730 S Apr 25 2024 MiTek Industries, Inc. Mon May 06 11:58:33

Page: 1

ID:HvYYHe4LpHmiz2Dld9nw5TzRQov-RfC?PsB70Hq3NSgPqnL8w3uITXbGKwRCDoi7J4zJC?f



Scale = 1:91.3

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.12	Vert(LL)	n/a	-	n/a	999	MT20
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.05	Vert(CT)	n/a	-	n/a	999	244/190
TCDL	10.0	Rep Stress Incr	YES	WB	0.21	Horz(CT)	0.01	33	n/a	n/a	
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH							
BCDL	10.0										
Weight: 545 lb FT = 20%											

**LUMBER**  
TOP CHORD 2x6 SP No.2  
BOT CHORD 2x6 SP No.2  
WEBS 2x4 SP No.3  
OTHERS 2x4 SP No.3 \*Except\*  
49-17,48-18,46-19,45-20,44-22,50-16,51-15,  
52-14,53-12:2x4 SP No.2


**BRACING**  
TOP CHORD Structural wood sheathing directly applied or  
6-0-0 oc purlins, except end verticals, and  
2-0-0 oc purlins (6-0-0 max.): 13-21.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc  
bracing.  
WEBS 1 Row at midpt 23-43, 24-42, 11-55,  
10-56, 17-49, 18-48,  
19-46, 20-45, 22-44,  
16-50, 15-51, 14-52,  
12-53

**REACTIONS** (size) 33=53-1-8, 34=53-1-8, 35=53-1-8,  
36=53-1-8, 37=53-1-8, 38=53-1-8,  
39=53-1-8, 40=53-1-8, 42=53-1-8,  
43=53-1-8, 44=53-1-8, 45=53-1-8,  
46=53-1-8, 48=53-1-8, 49=53-1-8,  
50=53-1-8, 51=53-1-8, 52=53-1-8,  
53=53-1-8, 55=53-1-8, 56=53-1-8,  
57=53-1-8, 58=53-1-8, 59=53-1-8,  
60=53-1-8, 61=53-1-8, 62=53-1-8,  
63=53-1-8  
Max Horiz 62=186 (LC 12)

Max Uplift 33=36 (LC 11), 34=98 (LC 15),  
35=27 (LC 15), 36=47 (LC 15),  
37=43 (LC 15), 38=44 (LC 15),  
39=44 (LC 15), 40=43 (LC 15),  
42=46 (LC 15), 43=51 (LC 15),  
46=29 (LC 11), 48=28 (LC 11),  
49=25 (LC 10), 50=28 (LC 11),  
51=28 (LC 10), 55=53 (LC 14),  
56=46 (LC 14), 57=43 (LC 14),  
58=44 (LC 14), 59=45 (LC 14),  
60=27 (LC 14), 61=116 (LC 14),  
62=33 (LC 15), 63=36 (LC 11)  
Max Grav 33=135 (LC 28), 34=214 (LC 59),  
35=144 (LC 1), 36=164 (LC 45),  
37=159 (LC 1), 38=171 (LC 45),  
39=220 (LC 45), 40=230 (LC 45),  
42=229 (LC 45), 43=231 (LC 45),  
44=211 (LC 45), 45=192 (LC 40),  
46=220 (LC 40), 48=218 (LC 40),  
49=216 (LC 40), 50=218 (LC 40),  
51=220 (LC 40), 52=192 (LC 40),  
53=214 (LC 43), 55=235 (LC 43),  
56=233 (LC 43), 57=233 (LC 43),  
58=231 (LC 43), 59=188 (LC 43),  
60=158 (LC 1), 61=183 (LC 51),  
62=163 (LC 1), 63=135 (LC 28)

**FORCES** (lb) - Maximum Compression/Maximum  
Tension

**TOP CHORD** 2-62=123/161, 1-2=0/23, 2-3=69/80,  
3-4=73/64, 4-5=75/96, 5-6=85/148,  
6-7=98/192, 7-9=115/238, 9-10=130/283,  
10-11=146/329, 11-12=163/378,  
12-13=161/378, 13-14=151/373,  
14-15=151/373, 15-16=151/373,  
16-17=151/373, 17-18=151/373,  
18-19=151/373, 19-20=151/373,  
20-21=151/373, 21-22=161/378,  
22-23=163/378, 23-24=146/329,  
24-25=130/283, 25-27=115/238,  
27-28=98/198, 28-29=94/174,  
29-30=106/151, 30-31=120/128,  
31-32=141/106, 32-33=185/113



May 7, 2024

Continued on page 2

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY  
**TRENCO**  
A MiTek Affiliate

818 Soundside Road  
Edenton, NC 27932



Job	Truss	Truss Type	Qty	Ply	1002 Serenity-Roof-B326 BRH COP BR4
24030108-01	A01	Piggyback Base Supported Gable	1	1	I65383277
					Job Reference (optional)

- BOT CHORD

61-62=-86/181, 60-61=-86/181,  
59-60=-86/181, 58-59=-86/181,  
57-58=-86/181, 56-57=-86/181,  
55-56=-86/181, 53-55=-86/181,  
52-53=-86/181, 51-52=-86/181,  
50-51=-86/181, 49-50=-86/181,  
48-49=-86/181, 46-48=-86/181,  
45-46=-86/181, 44-45=-86/181,  
43-44=-86/181, 42-43=-86/181,  
40-42=-86/181, 39-40=-86/181,  
38-39=-86/181, 37-38=-86/181,  
36-37=-86/181, 35-36=-86/181,  
34-35=-86/181, 33-34=-86/181
- WEBS

23-43=-190/88, 24-42=-189/81,  
25-40=-190/77, 27-39=-180/77,  
28-38=-131/77, 29-37=-126/76,  
30-36=-128/81, 31-35=-119/104,  
32-34=-155/155, 11-55=-195/88,  
10-56=-193/81, 9-57=-193/77, 7-58=-192/77,  
6-59=-147/77, 5-60=-123/90, 4-61=-143/165,  
3-62=-174/99, 17-49=-176/57,  
18-48=-178/62, 19-46=-180/60,  
20-45=-152/14, 22-44=-171/10,  
16-50=-178/62, 15-51=-180/60,  
14-52=-152/8, 12-53=-174/0

- NOTES
- 1) Unbalanced roof live loads have been considered for this design.

2) Wind: ASCE 7-16; Vult=130mph (3-second gust)  
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Corner(3E) -0-8-6 to 4-6-8, Exterior(2N) 4-6-8 to 12-4-3, Corner(3R) 12-4-3 to 22-11-13, Exterior(2N) 22-11-13 to 26-1-3, Corner(3R) 26-1-3 to 36-6-8, Exterior(2N) 36-6-8 to 47-9-11, Corner(3E) 47-9-11 to 53-1-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60

3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.

4) TCLK: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10

5) Unbalanced snow loads have been considered for this design.

6) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.

7) Provide adequate drainage to prevent water ponding.

8) All plates are 2x4 MT20 unless otherwise indicated.

9) Gable requires continuous bottom chord bearing.

10) Gable studs spaced at 2-0-0 oc.

11) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.

12) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.

13) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 62, 33, 43, 42, 40, 39, 38, 37, 36, 35, 34, 55, 56, 57, 58, 59, 60, 61, 49, 48, 46, 50, and 51. This connection is for uplift only and does not consider lateral forces.

14) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

15) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.


LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	1002 Serenity-Roof-B326 BRH COP BR4	165383278
24030108-01	A03	Piggyback Base	8	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Apr 25 2024 Print: 8.730 S Apr 25 2024 MiTek Industries, Inc. Mon May 06 11:58:34  
ID:OFJfX3IDTxFBWzrBXohbzzRCTM-RfC?PsB70Hq3NSgPqnL8w3uITXbGKwrcDoi7J4zJC7f

Page: 1



Scale = 1:91.3

Plate Offsets (X, Y): [15:Edge,0-1-5], [27:0-3-8,0-2-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.65	Vert(LL)	-0.27	24-26	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.87	Vert(CT)	-0.49	23-24	>788	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.95	Horz(CT)	0.11	15	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 500 lb	FT = 20%

<b>LUMBER</b>			<b>BOT CHORD</b>		
TOP CHORD	2x6 SP No.2		27-28=-113/224, 26-27=-203/2366,		
BOT CHORD	2x6 SP No.2 *Except* 18-22:2x6 SP 2400F 2.0E		24-26=-33/2370, 23-24=-26/2480,		
WEBS	2x4 SP No.3 *Except* 28-2:2x6 SP No.2, 6-26,10-19,7-24,9-21,6-24,10-21:2x4 SP No.2		21-23=-26/2480, 20-21=-1/2308,		
WEDGE	Right: 2x4 SP No.3		19-20=-1/2308, 17-19=-50/3064,		
<b>BRACING</b>			16-17=-92/3362, 15-16=-92/3362		
TOP CHORD	Structural wood sheathing directly applied or 3-5-10 oc purlins, except end verticals, and 2-0-0 oc purlins (3-8-15 max.): 6-10.		14-16=-0/178, 5-26=-593/201, 3-26=0/401,		
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.		12-17=-77/636, 14-17=-415/178,		
WEBS	1 Row at midpt 5-26, 12-19, 11-19, 24-29, 21-30, 32-33		12-19=-879/183, 11-19=-455/168,		
JOINTS	1 Brace at Jt(s): 29, 30, 31		3-27=-741/130, 2-27=-98/2424,		
<b>REACTIONS</b>	(size) 15= Mechanical, 20=0-3-8, 28=0-5-8		6-26=-255/593, 10-19=-213/709,		
	Max Horiz 28=-187 (LC 12)		24-32=-505/217, 29-32=-487/222,		
	Max Uplift 15=-41 (LC 14), 20=-208 (LC 15), 28=-177 (LC 14)		7-29=-473/219, 21-33=-924/224,		
	Max Grav 15=1979 (LC 47), 20=962 (LC 45), 28=2305 (LC 37)		30-33=-909/232, 9-30=-885/228, 6-24=0/827,		
<b>FORCES</b>	(lb) - Maximum Compression/Maximum Tension		29-31=-12/48, 30-31=-159/27, 8-31=-230/81,		
TOP CHORD	1-2=0/25, 2-3=-2758/196, 3-5=-3077/260, 5-6=-3146/381, 6-7=-2573/237, 7-8=-3064/422, 8-9=-3064/422, 9-10=-2550/233, 10-11=-3066/316, 11-12=-3026/252, 12-14=-3534/218, 14-15=-3895/202, 2-28=-2356/204		10-21=-67/1102, 7-31=-297/676, 9-31=-283/816, 32-34=-67/36, 33-34=-67/36, 23-34=0/38		

#### NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-8-6 to 4-7-7, Interior (1) 4-7-7 to 10-1-12, Exterior(2R) 10-1-12 to 38-11-4, Interior (1) 38-11-4 to 47-9-11, Exterior(2E) 47-9-11 to 53-1-8 zone; end vertical left exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.

- 200.0lb AC unit load placed on the bottom chord, 24-6-8 from left end, supported at two points, 5-0-0 apart.
- Provide adequate drainage to prevent water ponding.
- All plates are 4x5 MT20 unless otherwise indicated.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 41 lb uplift at joint 15.
- One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 28 and 20. This connection is for uplift only and does not consider lateral forces.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



May 7, 2024

Continued on page 2

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY  
**TRENCO**  
A MiTek Affiliate

818 Soundside Road  
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1002 Serenity-Roof-B326 BRH COP BR4	I65383278
24030108-01	A03	Piggyback Base	8	1	Job Reference (optional)	

15) Graphical purlin representation does not depict the size  
or the orientation of the purlin along the top and/or  
bottom chord.

LOAD CASE(S) Standard


 **WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1 Quality Criteria and DSB-22** available from Truss Plate Institute ([www.tpinst.org](http://www.tpinst.org)) and **BCSI Building Component Safety Information** available from the Structural Building Component Association ([www.sbcacomponents.com](http://www.sbcacomponents.com))



818 Soundside Road  
Edenton, NC 27932

Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Apr 25 2024 Print: 8.730 S Apr 25 2024 MiTek Industries, Inc. Mon May 06 11:58:35 Page: 1  
ID:DGN6a6f8caCKWpHw1clz1BzRCZx-RfC?PsB70Hq3NSgPqnL8w3uTXbGKWrcDoi7J4zJC?f



May 7, 2024

Continued on page 2

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MITek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPH Quality Criteria and DSB-22** available from Truss Plate Institute ([www.tpinr.org](http://www.tpinr.org)) and **BCSI Building Component Safety Information** available from the Structural Building Component Association ([www.sbcacomponents.com](http://www.sbcacomponents.com))



818 Soundside Road  
Edenton, NC 27932



Job	Truss	Truss Type	Qty	Ply	1002 Serenity-Roof-B326 BRH COP BR4	I65383279
24030108-01	A04	Piggyback Base	3	1	Job Reference (optional)	

- 14) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 15) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- LOAD CASE(S)** Standard

**⚠ WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute ([www.tpinst.org](http://www.tpinst.org)) and **BCSI Building Component Safety Information** available from the Structural Building Component Association ([www.sbcacomponents.com](http://www.sbcacomponents.com))




818 Soundside Road  
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1002 Serenity-Roof-B326 BRH COP BR4	I65383280
24030108-01	H01	Monopitch Supported Gable	2	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Apr 25 2024 Print: 8.730 S Apr 25 2024 MiTek Industries, Inc. Mon May 06 11:58:40  
ID:kX6Xm09JsM8Rk\_RkgNonK3zRRGV-RfC?PsB70Hq3NSgPqnL8w3uTXbGKWrCDoi7J4zJC?i

Page: 1



Scale = 1:44.9

Plate Offsets (X, Y): [2:Edge,0-0-14], [2:0-2-5,Edge]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.75	Vert(LL)	n/a	-	n/a	999	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.21	Vert(CT)	n/a	-	n/a	999	
TCDL	10.0	Rep Stress Incr	YES	WB	0.69	Horz(CT)	-0.01	2	n/a	n/a	
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH							
BCDL	10.0										
										Weight: 67 lb	FT = 20%

#### LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
WEBS	2x4 SP 2400F 2.0E *Except* 17-9:2x4 SP No.3
OTHERS	2x4 SP No.3
WEDGE	Left: 2x4 SP No.3

#### BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing, Except: 10-0-0 oc bracing: 11-12.


REACTIONS	(size)	2=10-1-8, 12=10-1-8, 13=10-1-8, 14=10-1-8, 15=10-1-8, 16=10-1-8, 21=10-1-8
	Max Horiz	2=210 (LC 10), 21=210 (LC 10)
	Max Uplift	2=-3 (LC 14), 12=-264 (LC 14), 13=-11 (LC 21), 14=-26 (LC 10), 15=-155 (LC 14), 21=-3 (LC 14)
	Max Grav	2=1 (LC 21), 12=893 (LC 21), 13=98 (LC 7), 14=202 (LC 21), 15=171 (LC 21), 16=253 (LC 1), 21=1 (LC 21)

FORCES	(lb) - Maximum Compression/Maximum Tension	
	TOP CHORD	1-2=0/17, 2-3=-535/377, 3-4=-531/378, 4-5=-474/378, 5-7=-435/359, 7-8=-437/432, 8-9=-579/743, 9-10=-29/0
	BOT CHORD	2-16=-339/244, 15-16=-339/244, 14-15=-339/244, 13-14=-339/244, 12-13=-339/244, 11-12=0/0
	WEBS	12-17=-870/552, 8-17=-396/210, 9-17=-810/584, 3-16=-153/3, 4-15=-120/154, 5-14=-167/99, 7-13=-29/60

#### NOTES

- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-10-8 to 2-0-0, Interior (1) 2-0-0 to 13-1-8, Exterior(2E) 13-1-8 to 16-1-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 3 lb uplift at joint 2, 264 lb uplift at joint 12, 155 lb uplift at joint 15, 26 lb uplift at joint 14, 11 lb uplift at joint 13 and 3 lb uplift at joint 2.
- Non Standard bearing condition. Review required.

- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- LOAD CASE(S)** Standard



May 7, 2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY  
**TRENCO**  
A MiTek Affiliate

818 Soundside Road  
Edenton, NC 27932


Job	Truss	Truss Type	Qty	Ply	1002 Serenity-Roof-B326 BRH COP BR4	I65383281
24030108-01	H02	Monopitch	6	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Apr 25 2024 Print: 8.730 S Apr 25 2024 MiTek Industries, Inc. Mon May 06 11:58:40

Page: 1

ID:nLPVeuW3K4TytrtY3ILLguzRRHK-RfC?PsB70Hq3NSgPqnL8w3uITxbGKWrCDoi7J4zJC7f



Scale = 1:46

Plate Offsets (X, Y): [2:Edge,0-0-14], [2:0-2-5,Edge], [9:0-3-8,0-3-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.71	Vert(LL)	0.04	9-10	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.27	Vert(CT)	-0.04	9-10	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.71	Horz(CT)	-0.01	9	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 67 lb	FT = 20%

#### LUMBER

TOP CHORD 2x4 SP No.2  
 BOT CHORD 2x4 SP No.2  
 WEBS 2x4 SP No.3 \*Except\* 5-9:2x4 SP 2400F 2.0E  
 WEDGE Left: 2x4 SP No.3

#### BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.  
 BOT CHORD Rigid ceiling directly applied or 8-5-13 oc bracing.

#### REACTIONS

(size) 2=0-3-0, 9=0-5-8  
 Max Horiz 2=210 (LC 10)  
 Max Uplift 2=-99 (LC 10), 9=-379 (LC 20)  
 Max Grav 2=379 (LC 1), 9=1090 (LC 21)

#### FORCES


(lb) - Maximum Compression/Maximum Tension  
 TOP CHORD 1-2=0/17, 2-3=-368/225, 3-5=-447/428, 5-6=-594/757, 6-7=-29/0  
 BOT CHORD 2-10=-447/338, 9-10=-447/338, 8-9=0/0  
 WEBS 9-11=-840/532, 5-11=-358/182, 3-10=-315/219, 3-9=-563/753, 6-11=-825/599

#### NOTES

- Wind: ASCE 7-16; Vult=130mph (3-second gust)  
 Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior (1) 2-1-8 to 13-1-8, Exterior(2E) 13-1-8 to 16-1-8 zone; cantilever left exposed; porch left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.

- This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 9 and 2. This connection is for uplift only and does not consider lateral forces.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



May 7, 2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY  
**TRENCO**  
 A MiTek Affiliate


818 Soundside Road  
 Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1002 Serenity-Roof-B326 BRH COP BR4	I65383282
24030108-01	J01	Common	5	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Apr 25 2024 Print: 8.730 S Apr 25 2024 MiTek Industries, Inc. Mon May 06 11:58:40  
ID:yPXMLbyKekkHSiWSiZLGINzRR58-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrcDoi7J4zJC?f

Page: 1



Scale = 1:40.2

Plate Offsets (X, Y): [5:0-3-8,Edge], [6:0-4-0,0-3-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.37	Vert(LL)	-0.09	6-9	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.65	Vert(CT)	-0.19	6-9	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.21	Horz(CT)	0.02	5	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 75 lb	FT = 20%

#### LUMBER

TOP CHORD 2x4 SP No.2  
BOT CHORD 2x4 SP No.2  
WEBS 2x4 SP No.3  
WEDGE Right: 2x4 SP No.3

#### BRACING

TOP CHORD Structural wood sheathing directly applied or 5-1-6 oc purlins.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS** (size) 1=0-5-8, 5=0-5-8  
Max Horiz 1=71 (LC 14)  
Max Uplift 1=66 (LC 14), 5=64 (LC 15)  
Max Grav 1=747 (LC 20), 5=746 (LC 21)

#### FORCES


(lb) - Maximum Compression/Maximum Tension  
TOP CHORD 1-2=-1263/310, 2-3=-883/233, 3-4=-875/232, 4-5=-1219/301  
BOT CHORD 1-5=-223/1092  
WEBS 3-6=-53/478, 4-6=-407/160, 2-6=-445/175

#### NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-0-0 to 3-0-0, Interior (1) 3-0-0 to 5-7-8, Exterior(2R) 5-7-8 to 11-7-8, Interior (1) 11-7-8 to 14-0-8, Exterior(2E) 14-0-8 to 17-0-8 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.

- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Bearings are assumed to be: , Joint 5 User Defined .
- One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 1 and 5. This connection is for uplift only and does not consider lateral forces.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

**LOAD CASE(S)** Standard



May 7, 2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY  
**TRENCO**  
A MiTek Affiliate

818 Soundside Road  
Edenton, NC 27932




Job	Truss	Truss Type	Qty	Ply	1002 Serenity-Roof-B326 BRH COP BR4	I65383283
24030108-01	VLD1	Valley	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Apr 25 2024 Print: 8.730 S Apr 25 2024 MiTek Industries, Inc. Mon May 06 11:58:42  
ID:?VRASUfm0qfd3oFPBHC5FHzRQud-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:50.7

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.39	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.18	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.41	Horiz(TL)	0.00	5	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 76 lb	FT = 20%

#### LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
OTHERS	2x4 SP No.3

#### BRACING

TOP CHORD	Structural wood sheathing directly applied or 10-0-0 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.

#### REACTIONS

(size)	1=16-11-0, 5=16-11-0, 6=16-11-0, 8=16-11-0, 9=16-11-0, 14=16-11-0
Max Horiz	1=161 (LC 11)
Max Uplift	1=-58 (LC 10), 6=-184 (LC 15), 9=-189 (LC 14)
Max Grav	1=83 (LC 35), 5=1 (LC 30), 6=513 (LC 6), 8=656 (LC 24), 9=514 (LC 24), 14=1 (LC 30)

#### FORCES


(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=-105/374, 2-3=-24/322, 3-4=-1/301, 4-5=-143/306
BOT CHORD	1-9=-200/77, 8-9=-200/75, 6-8=-200/75, 5-6=-200/75
WEBS	3-8=-474/0, 2-9=-394/222, 4-6=-393/220

#### NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-0-5 to 3-0-5, Interior (1) 3-0-5 to 5-5-13, Exterior(2R) 5-5-13 to 11-5-13, Interior (1) 11-5-13 to 13-6-12, Exterior(2E) 13-6-12 to 16-6-12 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60

- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 58 lb uplift at joint 1, 189 lb uplift at joint 9 and 184 lb uplift at joint 6.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



May 7, 2024


**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY  
**TRENCO**  
A MiTek Affiliate

818 Soundside Road  
Edenton, NC 27932

Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Apr 25 2024 Print: 8.730 S Apr 25 2024 MiTek Industries, Inc. Mon May 06 11:58:42 Page: 1  
ID:Th ZaafOm8nUayabk?iKoVzRQuc-RfC?PsB70Hq3NSaPanL8w3uITXbGKWrcDOI7J4zJC?f



**LUMBER**  
TOP CHORD 2x4 SP No.2  
BOT CHORD 2x4 SP No.2  
OTHERS 2x4 SP No.3

**BRACING**  
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.  
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

**REACTIONS** (size) 1=14-6-13, 5=14-6-13, 6=14-6-13, 7=14-6-13, 8=14-6-13  
Max Horiz 1=138 (LC 13)  
Max Uplift 1=-24 (LC 10), 6=-155 (LC 15), 8=-158 (LC 14)  
Max Grav 1=123 (LC 25), 5=98 (LC 24), 6=457 (LC 21), 7=410 (LC 24), 8=457 (LC 20)

**FORCES** (lb) - Maximum Compression/Maximum Tension  
TOP CHORD 1-2=-154/148, 2-3=-172/123, 3-4=-172/112, 4-5=-122/112  
BOT CHORD 1-8=-62/127, 7-8=-62/101, 6-7=-62/101, 5-6=-62/101  
WEBS 3-7=-230/0, 2-8=-375/197, 4-6=-375/195

- 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 4) TCLK: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- 5) Unbalanced snow loads have been considered for this design.
- 6) Gable requires continuous bottom chord bearing.
- 7) Gable studs spaced at 4-0-0 oc.
- 8) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 9) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 24 lb uplift at joint 1, 158 lb uplift at joint 8 and 155 lb uplift at joint 6.
- 11) Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 1, 5.
- 12) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

- ## NOTES
- 1) Unbalanced roof live loads have been considered for this design.
  - 2) Wind: ASCE 7-16; Vult=130mph (3-second gust)  
 Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-0-0 to 3-3-6, Interior (1) 3-3-6 to 4-3-6, Exterior(2R) 4-3-6 to 10-3-6, Interior (1) 10-3-6 to 11-3-6, Exterior(2E) 11-3-6 to 14-6-13 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip  
 DOL = 1.60



May 7, 2024



Design valid for use only with MiTeK® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute ([www.tpinet.org](http://www.tpinet.org)) and **BCSI Building Component Safety Information** available from the Structural Building Components Association ([www.sbcacomponents.com](http://www.sbcacomponents.com))




818 Soundside Road  
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1002 Serenity-Roof-B326 BRH COP BR4	I65383285
24030108-01	VLD3	Valley	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Apr 25 2024 Print: 8.730 S Apr 25 2024 MiTek Industries, Inc. Mon May 06 11:58:42  
ID:kUxM45s?bF21LX?KCRTFVazRQqU-RfC?PsB70Hq3NSgPqnL8w3uTXbGKwRCDoi7J4zJC?i

Page: 1



Scale = 1:39.3

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.31	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.12	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.08	Horiz(TL)	0.00	5	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 50 lb	FT = 20%

#### LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
OTHERS	2x4 SP No.3

#### BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS

(size)	1=12-2-0, 5=12-2-0, 6=12-2-0, 7=12-2-0, 8=12-2-0
Max Horiz	1=-115 (LC 10)
Max Uplift	1=-32 (LC 10), 5=-4 (LC 11), 6=-136 (LC 15), 8=-139 (LC 14)
Max Grav	1=93 (LC 25), 5=72 (LC 24), 6=435 (LC 21), 7=261 (LC 21), 8=435 (LC 20)

#### FORCES


(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=-118/101, 2-3=-216/117, 3-4=-216/117, 4-5=-91/63
BOT CHORD	1-8=-32/78, 7-8=-32/73, 6-7=-32/73, 5-6=-32/73
WEBS	3-7=-174/0, 2-8=-398/218, 4-6=-398/218

#### NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-0-0 to 3-0-0, Exterior(2R) 3-0-0 to 9-2-0, Exterior(2E) 9-2-0 to 12-2-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60

- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 32 lb uplift at joint 1, 4 lb uplift at joint 5, 139 lb uplift at joint 8 and 136 lb uplift at joint 6.
- Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 1, 5.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



May 7, 2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute ([www.tpinst.org](http://www.tpinst.org)) and **BCSI Building Component Safety Information** available from the Structural Building Component Association ([www.sbcacomponents.com](http://www.sbcacomponents.com))

ENGINEERING BY  
**TRENCO**  
A MiTek Affiliate


818 Soundside Road  
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1002 Serenity-Roof-B326 BRH COP BR4	I65383286
24030108-01	VLD4	Valley	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Apr 25 2024 Print: 8.730 S Apr 25 2024 MiTek Industries, Inc. Mon May 06 11:58:42  
ID:kUxM45s?bF21LX?KCRTFVazRQqU-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?i

Page: 1



Scale = 1:33.3

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.46	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.43	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.19	Horiz(TL)	0.01	4	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 37 lb	FT = 20%

#### LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
OTHERS	2x4 SP No.3

#### BRACING

TOP CHORD	Structural wood sheathing directly applied or 9-8-10 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.

#### REACTIONS

(size)	1=9-8-10, 3=9-8-10, 4=9-8-10
Max Horiz	1=-91 (LC 10)
Max Uplift	1=-51 (LC 21), 3=-51 (LC 20), 4=-110 (LC 14)
Max Grav	1=95 (LC 20), 3=95 (LC 21), 4=784 (LC 21)

#### FORCES


(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=-117/380, 2-3=-117/380
BOT CHORD	1-4=-248/174, 3-4=-248/174
WEBS	2-4=-646/274

#### NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-0-5 to 3-0-5, Exterior(2R) 3-0-5 to 6-8-14, Exterior(2E) 6-8-14 to 9-8-14 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.

- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 51 lb uplift at joint 1, 51 lb uplift at joint 3 and 110 lb uplift at joint 4.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



May 7, 2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY  
**TRENCO**  
A MiTek Affiliate

818 Soundside Road  
Edenton, NC 27932


Job	Truss	Truss Type	Qty	Ply	1002 Serenity-Roof-B326 BRH COP BR4	I65383287
24030108-01	VLD5	Valley	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Apr 25 2024 Print: 8.730 S Apr 25 2024 MiTek Industries, Inc. Mon May 06 11:58:42

Page: 1

ID: CgVkJHRtdMZAuzhaXm9\_U1OzRQqT-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrcDoi7J4zJC?f



Scale = 1:29.3

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.26	Vert(LL)	n/a	-	n/a	999	MT20
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.27	Vert(TL)	n/a	-	n/a	999	244/190
TCDL	10.0	Rep Stress Incr	YES	WB	0.09	Horiz(TL)	0.00	4	n/a	n/a	
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MP							
BCDL	10.0										
Weight: 27 lb FT = 20%											

#### LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
OTHERS	2x4 SP No.3

#### BRACING

TOP CHORD	Structural wood sheathing directly applied or 7-3-13 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.

#### REACTIONS

(size)	1=7-3-13, 3=7-3-13, 4=7-3-13
Max Horiz	1=-68 (LC 12)
Max Uplift	1=-19 (LC 21), 3=-19 (LC 20), 4=-75 (LC 14)
Max Grav	1=105 (LC 20), 3=105 (LC 21), 4=541 (LC 21)

#### FORCES

(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=-91/234, 2-3=-91/234
BOT CHORD	1-4=-183/154, 3-4=-183/154
WEBS	2-4=-429/203

#### NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-0-5 to 3-0-5, Exterior(2R) 3-0-5 to 4-4-2, Exterior(2E) 4-4-2 to 7-4-2 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.

- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 19 lb uplift at joint 1, 19 lb uplift at joint 3 and 75 lb uplift at joint 4.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



May 7, 2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute ([www.tpinst.org](http://www.tpinst.org)) and **BCSI Building Component Safety Information** available from the Structural Building Component Association ([www.sbcacompnents.com](http://www.sbcacompnents.com))

ENGINEERING BY  
**TRENCO**  
A MiTek Affiliate

818 Soundside Road  
Edenton, NC 27932




Job	Truss	Truss Type	Qty	Ply	1002 Serenity-Roof-B326 BRH COP BR4	I65383288
24030108-01	VLD6	Valley	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Apr 25 2024 Print: 8.730 S Apr 25 2024 MiTek Industries, Inc. Mon May 06 11:58:42  
ID:CgVkhRtdMZAuzhaXm9\_U1OzRQqT-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrcDoi7J4zJC?f

Page: 1



Scale = 1:26.2

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.09	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.11	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.04	Horiz(TL)	0.00	4	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MP								
BCDL	10.0										Weight: 18 lb	FT = 20%

#### LUMBER

TOP CHORD 2x4 SP No.2  
BOT CHORD 2x4 SP No.2  
OTHERS 2x4 SP No.3

#### BRACING

TOP CHORD Structural wood sheathing directly applied or 4-11-0 oc purlins.  
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

#### REACTIONS

(size) 1=4-11-0, 3=4-11-0, 4=4-11-0  
Max Horiz 1=-44 (LC 10)  
Max Uplift 3=-7 (LC 15), 4=-34 (LC 14)  
Max Grav 1=89 (LC 20), 3=89 (LC 21), 4=301 (LC 20)

#### FORCES

(lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=-81/106, 2-3=-81/106  
BOT CHORD 1-4=-86/90, 3-4=-86/90  
WEBS 2-4=-215/100

#### NOTES

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust)  
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 4) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10

- 5) Unbalanced snow loads have been considered for this design.
- 6) Gable requires continuous bottom chord bearing.
- 7) Gable studs spaced at 4-0-0 oc.
- 8) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 9) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- 10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 7 lb uplift at joint 3 and 34 lb uplift at joint 4.
- 11) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



May 7, 2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute ([www.tpinst.org](http://www.tpinst.org)) and **BCSI Building Component Safety Information** available from the Structural Building Component Association ([www.sbcacompnents.com](http://www.sbcacompnents.com))

ENGINEERING BY  
**TRENCO**  
A MiTek Affiliate


818 Soundside Road  
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1002 Serenity-Roof-B326 BRH COP BR4	I65383289
24030108-01	VLD7	Valley	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Apr 25 2024 Print: 8.730 S Apr 25 2024 MiTek Industries, Inc. Mon May 06 11:58:42  
ID:CgVkhRtdMZAuzhaXm9\_U1OzRQqT-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrcDoi7J4zJC?f

Page: 1



Scale = 1:25.1

Plate Offsets (X, Y): [2:0-2-8,Edge]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.05	Vert(LL)	n/a	-	n/a	999	MT20
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.05	Vert(TL)	n/a	-	n/a	999	244/190
TCDL	10.0	Rep Stress Incr	YES	WB	0.00	Horiz(TL)	0.00	3	n/a	n/a	
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MP							
BCDL	10.0										
										Weight: 7 lb	FT = 20%

#### LUMBER

TOP CHORD 2x4 SP No.2

BOT CHORD 2x4 SP No.2

#### BRACING

TOP CHORD Structural wood sheathing directly applied or 2-6-3 oc purlins.

BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS** (size) 1=2-6-3, 3=2-6-3  
Max Horiz 1=21 (LC 11)  
Max Uplift 1=-9 (LC 14), 3=-9 (LC 15)  
Max Grav 1=114 (LC 20), 3=114 (LC 21)

**FORCES** (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=-144/62, 2-3=-144/62


BOT CHORD 1-3=-33/102

#### NOTES

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 4) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- 5) Unbalanced snow loads have been considered for this design.
- 6) Gable requires continuous bottom chord bearing.

- 7) Gable studs spaced at 4-0-0 oc.
- 8) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 9) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- 10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 9 lb uplift at joint 1 and 9 lb uplift at joint 3.
- 11) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

**LOAD CASE(S)** Standard



May 7, 2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute ([www.tpinst.org](http://www.tpinst.org)) and **BCSI Building Component Safety Information** available from the Structural Building Component Association ([www.sbcacompnents.com](http://www.sbcacompnents.com))

ENGINEERING BY  
**TRENCO**  
A MiTek Affiliate


818 Soundside Road  
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1002 Serenity-Roof-B326 BRH COP BR4	I65383290
24030108-01	VLB1	Valley	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Apr 25 2024 Print: 8.730 S Apr 25 2024 MiTek Industries, Inc. Mon May 06 11:58:41  
ID:uRu6rMLa1rlmrJyJNhjxpxzRQsR-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:58.7

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.31	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.17	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.21	Horiz(TL)	0.01	7	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 106 lb	FT = 20%

**LUMBER**  
TOP CHORD 2x4 SP No.2  
BOT CHORD 2x4 SP No.2  
OTHERS 2x4 SP No.3

**BRACING**  
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.


**WEBS** 1 Row at midpt 4-11  
**REACTIONS** (size) 1=21-7-8, 7=21-7-8, 8=21-7-8, 9=21-7-8, 11=21-7-8, 12=21-7-8, 13=21-7-8  
Max Horiz 1=-207 (LC 10)  
Max Uplift 1=-54 (LC 10), 7=-1 (LC 11), 8=-115 (LC 15), 9=-174 (LC 15), 12=-173 (LC 14), 13=-118 (LC 14)  
Max Grav 1=134 (LC 25), 7=119 (LC 27), 8=365 (LC 25), 9=473 (LC 6), 11=416 (LC 27), 12=473 (LC 5), 13=368 (LC 24)

**FORCES** (lb) - Maximum Compression/Maximum Tension  
TOP CHORD 1-2=-211/174, 2-3=-165/132, 3-4=-188/184, 4-5=-187/157, 5-6=-115/82, 6-7=-166/107  
BOT CHORD 1-13=-79/161, 12-13=-79/161, 11-12=-79/161, 9-11=-79/161, 8-9=-79/161, 7-8=-79/161  
WEBS 4-11=-209/4, 3-12=-376/222, 2-13=-264/163, 5-9=-376/222, 6-8=-265/161

**NOTES**  
1) Unbalanced roof live loads have been considered for this design.

- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-4-13 to 3-4-13, Interior (1) 3-4-13 to 7-10-1, Exterior(2R) 7-10-1 to 13-10-1, Interior (1) 13-10-1 to 18-7-13, Exterior(2E) 18-7-13 to 21-7-13 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 54 lb uplift at joint 1, 1 lb uplift at joint 7, 173 lb uplift at joint 12, 118 lb uplift at joint 13, 174 lb uplift at joint 9 and 115 lb uplift at joint 8.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

**LOAD CASE(S)** Standard



May 7, 2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY  
**TRENCO**  
A MiTek Affiliate


818 Soundside Road  
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1002 Serenity-Roof-B326 BRH COP BR4	I65383291
24030108-01	VLB2	Valley	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Apr 25 2024 Print: 8.730 S Apr 25 2024 MiTek Industries, Inc. Mon May 06 11:58:41  
ID:yJln\_UX?VSB69dbBmLUS1zzRQsC-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:52.2

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.31	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.17	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.29	Horiz(TL)	0.00	7	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH							
BCDL	10.0									Weight: 90 lb	FT = 20%

#### LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
OTHERS	2x4 SP No.3

#### BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS

(size)	1=19-2-11, 7=19-2-11, 8=19-2-11, 9=19-2-11, 11=19-2-11, 12=19-2-11, 13=19-2-11, 18=19-2-11
Max Horiz	1=-180 (LC 10)
Max Uplift	1=-107 (LC 12), 8=-54 (LC 15), 9=-193 (LC 15), 12=-174 (LC 14), 13=-100 (LC 14)
Max Grav	1=126 (LC 11), 7=0 (LC 13), 8=304 (LC 25), 9=477 (LC 25), 11=463 (LC 27), 12=480 (LC 5), 13=314 (LC 29), 18=0 (LC 13)

#### FORCES


(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=-218/205, 2-3=-217/187, 3-4=-207/267, 4-5=-207/241, 5-6=-124/66, 6-7=-72/43
BOT CHORD	1-13=-46/66, 12-13=-18/55, 11-12=-18/55, 9-11=-18/55, 8-9=-18/55, 7-8=-18/55
WEBS	4-11=-256/59, 3-12=-379/222, 2-13=-259/172, 5-9=-376/229, 6-8=-252/154

#### NOTES

- 1) Unbalanced roof live loads have been considered for this design.

- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-4-13 to 3-4-13, Interior (1) 3-4-13 to 6-7-10, Exterior(2R) 6-7-10 to 12-7-10, Interior (1) 12-7-10 to 16-3-0, Exterior(2E) 16-3-0 to 19-3-0 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 4) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- 5) Unbalanced snow loads have been considered for this design.
- 6) All plates are 2x4 MT20 unless otherwise indicated.
- 7) Gable requires continuous bottom chord bearing.
- 8) Gable studs spaced at 4-0-0 oc.
- 9) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 10) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 11) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 107 lb uplift at joint 1, 174 lb uplift at joint 12, 100 lb uplift at joint 13, 193 lb uplift at joint 9 and 54 lb uplift at joint 8.
- 12) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



May 7, 2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute ([www.tpinst.org](http://www.tpinst.org)) and **BCSI Building Component Safety Information** available from the Structural Building Component Association ([www.sbcacompnents.com](http://www.sbcacompnents.com))

ENGINEERING BY  
**TRENCO**  
A MiTek Affiliate

818 Soundside Road  
Edenton, NC 27932


Job	Truss	Truss Type	Qty	Ply	1002 Serenity-Roof-B326 BRH COP BR4	I65383292
24030108-01	VLB3	Valley	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Apr 25 2024 Print: 8.730 S Apr 25 2024 MiTek Industries, Inc. Mon May 06 11:58:41

Page: 1

ID:4pahjxh9RSqoCd5h0aDV3jzRQs?-RfC?PsB70Hq3NSgPqnL8w3uITxbGKWrCDoi7J4zJC?f



Scale = 1:50.5

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.38	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.18	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.41	Horiz(TL)	0.00	5	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH							
BCDL	10.0									Weight: 75 lb	FT = 20%

#### LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
OTHERS	2x4 SP No.3

#### BRACING

TOP CHORD	Structural wood sheathing directly applied or 10-0-0 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.

#### REACTIONS

(size)	1=16-9-14, 5=16-9-14, 6=16-9-14, 8=16-9-14, 9=16-9-14, 14=16-9-14
Max Horiz	1=-157 (LC 10)
Max Uplift	1=-64 (LC 10), 6=-183 (LC 15), 9=-187 (LC 14)
Max Grav	1=76 (LC 13), 5=1 (LC 25), 6=511 (LC 6), 8=654 (LC 24), 9=509 (LC 5), 14=1 (LC 25)

#### FORCES


(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=-104/370, 2-3=-25/319, 3-4=-2/298, 4-5=-139/302
BOT CHORD	1-9=-197/74, 8-9=-197/74, 6-8=-197/74, 5-6=-197/74
WEBS	3-8=-471/0, 2-9=-392/220, 4-6=-392/219

#### NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-4-13 to 3-4-13, Interior (1) 3-4-13 to 5-5-4, Exterior(2R) 5-5-4 to 11-5-4, Interior (1) 11-5-4 to 13-10-3, Exterior(2E) 13-10-3 to 16-10-3 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60

- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 64 lb uplift at joint 1, 187 lb uplift at joint 9 and 183 lb uplift at joint 6.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



May 7, 2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY  
**TRENCO**  
A MiTek Affiliate

818 Soundside Road  
Edenton, NC 27932




Job	Truss	Truss Type	Qty	Ply	1002 Serenity-Roof-B326 BRH COP BR4	I6583293
24030108-01	VLB4	Valley	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Apr 25 2024 Print: 8.730 S Apr 25 2024 MiTek Industries, Inc. Mon May 06 11:58:41

Page: 1

ID:CKtcSNrNSSyGdaBHoyY5SzRQro-RfC?PsB70Hq3NSgPqnL8w3uITXbGKwRcDoi7J4zJC?f



Scale = 1:43.5

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.31	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.16	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.14	Horiz(TL)	0.00	5	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH							
BCDL	10.0									Weight: 62 lb	FT = 20%

#### LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
OTHERS	2x4 SP No.3

#### BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.

#### REACTIONS

(size)	1=14-5-2, 5=14-5-2, 6=14-5-2, 7=14-5-2, 8=14-5-2
Max Horiz	1=-137 (LC 10)
Max Uplift	1=-29 (LC 10), 6=-154 (LC 15), 8=-156 (LC 14)
Max Grav	1=109 (LC 25), 5=100 (LC 24), 6=454 (LC 21), 7=402 (LC 24), 8=453 (LC 20)

#### FORCES


(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=-141/139, 2-3=-177/119, 3-4=-177/112, 4-5=-122/105
BOT CHORD	1-8=-59/119, 7-8=-59/100, 6-7=-59/100, 5-6=-59/100
WEBS	3-7=-223/0, 2-8=-374/196, 4-6=-375/195

#### NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-4-13 to 3-2-14, Interior (1) 3-2-14 to 4-2-14, Exterior(2R) 4-2-14 to 10-2-14, Interior (1) 10-2-14 to 11-2-14, Exterior(2E) 11-2-14 to 14-5-6 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60

- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 29 lb uplift at joint 1, 156 lb uplift at joint 8 and 154 lb uplift at joint 6.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



May 7, 2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute ([www.tpinst.org](http://www.tpinst.org)) and **BCSI Building Component Safety Information** available from the Structural Building Component Association ([www.sbcacompnents.com](http://www.sbcacompnents.com))

ENGINEERING BY  
**TRENCO**  
A MiTek Affiliate

818 Soundside Road  
Edenton, NC 27932


Job	Truss	Truss Type	Qty	Ply	1002 Serenity-Roof-B326 BRH COP BR4	I65383294
24030108-01	VLB5	Valley	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Apr 25 2024 Print: 8.730 S Apr 25 2024 MiTek Industries, Inc. Mon May 06 11:58:41

Page: 1

ID:vFTOYozalWjXT9L6tv8uVZzRQre-RfC?PsB70Hq3NSgPqnL8w3uITxbGKWrCDoi7J4zJC?f



Scale = 1:39.1

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.31	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.12	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.08	Horiz(TL)	0.00	5	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 50 lb	FT = 20%

#### LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
OTHERS	2x4 SP No.3

#### BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS

(size)	1=12-0-5, 5=12-0-5, 6=12-0-5, 7=12-0-5, 8=12-0-5
Max Horiz	1=-113 (LC 10)
Max Uplift	1=-38 (LC 10), 5=-6 (LC 11), 6=-136 (LC 15), 8=-138 (LC 14)
Max Grav	1=77 (LC 25), 5=71 (LC 29), 6=434 (LC 21), 7=259 (LC 21), 8=432 (LC 20)

#### FORCES


(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=-114/100, 2-3=-219/116, 3-4=-218/115, 4-5=-89/63
BOT CHORD	1-8=-32/73, 7-8=-31/73, 6-7=-31/73, 5-6=-31/73
WEBS	3-7=-172/0, 2-8=-400/215, 4-6=-401/220

#### NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-4-13 to 3-4-13, Exterior(2R) 3-4-13 to 9-0-10, Exterior(2E) 9-0-10 to 12-0-10 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60

- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 38 lb uplift at joint 1, 6 lb uplift at joint 5, 138 lb uplift at joint 8 and 136 lb uplift at joint 6.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



May 7, 2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY  
**TRENCO**  
A MiTek Affiliate


818 Soundside Road  
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1002 Serenity-Roof-B326 BRH COP BR4	I65383295
24030108-01	VLB6	Valley	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Apr 25 2024 Print: 8.730 S Apr 25 2024 MiTek Industries, Inc. Mon May 06 11:58:42  
ID:vFTOYoza1WjXT9L6tv8uVZzRQre-RfC?PsB70Hq3NSgPqnL8w3uITxbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:33.2

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.44	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.42	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.18	Horiz(TL)	0.00	4	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH							
BCDL	10.0									Weight: 37 lb	FT = 20%

#### LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
OTHERS	2x4 SP No.3

#### BRACING

TOP CHORD	Structural wood sheathing directly applied or 9-7-8 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.

#### REACTIONS

(size)	1=9-7-8, 3=9-7-8, 4=9-7-8
Max Horiz	1=-90 (LC 10)
Max Uplift	1=-58 (LC 20), 3=-47 (LC 20), 4=-106 (LC 14)
Max Grav	1=75 (LC 20), 3=94 (LC 21), 4=768 (LC 20)

#### FORCES


(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=-111/370, 2-3=-112/367
BOT CHORD	1-4=-241/170, 3-4=-241/170
WEBS	2-4=-632/266

#### NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-4-13 to 3-4-13, Exterior(2R) 3-4-13 to 6-7-13, Exterior(2E) 6-7-13 to 9-7-13 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.

- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 58 lb uplift at joint 1, 47 lb uplift at joint 3 and 106 lb uplift at joint 4.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



May 7, 2024


**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute ([www.tpinst.org](http://www.tpinst.org)) and **BCSI Building Component Safety Information** available from the Structural Building Component Association ([www.sbcacompnents.com](http://www.sbcacompnents.com))


ENGINEERING BY  
**TRENCO**  
A MiTek Affiliate

818 Soundside Road  
Edenton, NC 27932

Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Apr 25 2024 Print: 8.730 S Apr 25 2024 MiTek Industries, Inc. Mon May 06 11:58:42 Page: 1  
ID:vFTQYozalWlXT9L6tv8uVZzRQre-RfC?PsB70Hq3NSaPqnL8w3uITXbGKWrcDOI7J4zJC?f

LOAD CASE(S) Standard

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust)  
 Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-4-13 to 3-7-10, Exterior(2R) 3-7-10 to 4-3-0, Exterior(2E) 4-3-0 to 7-3-0 zone; cantilever left and right exposed ; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.



Design valid for use only with MiTeK® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1 Quality Criteria and DSB-22** available from Truss Plate Institute ([www.tpinst.org](http://www.tpinst.org)) and **BCSI Building Component Safety Information** available from the Structural Building Components Association ([www.sbcacompnents.com](http://www.sbcacompnents.com))

818 Soundside Road  
Edenton, NC 27932


Job	Truss	Truss Type	Qty	Ply	1002 Serenity-Roof-B326 BRH COP BR4	I65383297
24030108-01	VLB8	Valley	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Apr 25 2024 Print: 8.730 S Apr 25 2024 MiTek Industries, Inc. Mon May 06 11:58:42

Page: 1

ID:vFTOYoza1WjXT9L6tv8uVZzRQre-RfC?PsB70Hq3NSgPqnL8w3uITxbGKWrCDoi7J4zJC?f



Scale = 1:26

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.08	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.11	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.04	Horiz(TL)	0.00	3	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MP							
BCDL	10.0									Weight: 17 lb	FT = 20%

#### LUMBER

TOP CHORD 2x4 SP No.2  
BOT CHORD 2x4 SP No.2  
OTHERS 2x4 SP No.3

#### BRACING

TOP CHORD Structural wood sheathing directly applied or 4-9-14 oc purlins.  
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

#### REACTIONS

(size) 1=4-9-14, 3=4-9-14, 4=4-9-14  
Max Horiz 1=-43 (LC 10)  
Max Uplift 3=-7 (LC 15), 4=-30 (LC 14)  
Max Grav 1=58 (LC 20), 3=86 (LC 21), 4=286 (LC 20)

#### FORCES


(lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=-61/99, 2-3=-79/99  
BOT CHORD 1-4=-81/85, 3-4=-81/85  
WEBS 2-4=-204/92

#### NOTES

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust)  
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 4) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10

- 5) Unbalanced snow loads have been considered for this design.
  - 6) Gable requires continuous bottom chord bearing.
  - 7) Gable studs spaced at 4-0-0 oc.
  - 8) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 9) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
  - 10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 7 lb uplift at joint 3 and 30 lb uplift at joint 4.
  - 11) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- LOAD CASE(S)** Standard



May 7, 2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute ([www.tpinst.org](http://www.tpinst.org)) and **BCSI Building Component Safety Information** available from the Structural Building Component Association ([www.sbcacompnents.com](http://www.sbcacompnents.com))

ENGINEERING BY  
**TRENCO**  
A MiTek Affiliate

818 Soundside Road  
Edenton, NC 27932




Job	Truss	Truss Type	Qty	Ply	1002 Serenity-Roof-B326 BRH COP BR4	165383298
24030108-01	PBA2	Piggyback	2	4	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Apr 25 2024 Print: 8.730 S Apr 25 2024 MiTek Industries, Inc. Mon May 06 11:58:41

Page: 1

ID:m2dQdjvppkexqPVgwg5aZpRCX1-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrcDoi7J4zJC?f



Scale = 1:31.4

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.02	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.01	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.01	Horiz(TL)	0.00	9	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 207 lb	FT = 20%

#### LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
OTHERS	2x4 SP No.3

#### BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS

(size)	1=13-9-0, 2=13-9-0, 8=13-9-0, 9=13-9-0, 10=13-9-0, 11=13-9-0, 12=13-9-0, 13=13-9-0, 14=13-9-0, 15=13-9-0, 18=13-9-0
Max Horiz	1=52 (LC 14)
Max Uplift	1=-25 (LC 15), 2=-14 (LC 14), 8=-7 (LC 15), 9=-2 (LC 22), 10=-45 (LC 15), 11=-47 (LC 15), 13=-48 (LC 14), 14=-44 (LC 14), 15=-14 (LC 14), 18=-7 (LC 15)
Max Grav	1=24 (LC 18), 2=154 (LC 21), 8=142 (LC 22), 9=4 (LC 1), 10=233 (LC 22), 11=245 (LC 22), 12=144 (LC 21), 13=244 (LC 21), 14=234 (LC 21), 15=154 (LC 21), 18=142 (LC 22)

#### FORCES


(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=-56/69, 2-3=-48/32, 3-4=-55/50, 4-5=-62/105, 5-6=-62/105, 6-7=-55/40, 7-8=-29/26, 8-9=0/24
BOT CHORD	2-14=-15/54, 13-14=-15/54, 12-13=-15/54, 11-12=-15/54, 10-11=-15/54, 8-10=-15/54
WEBS	5-12=-103/0, 4-13=-208/121, 3-14=-181/90, 6-11=-208/121, 7-10=-180/91

#### NOTES

- 4-ply truss to be connected together as follows:  
Top chords connected with 10d (0.131"x3") nails as follows: 2x4 - 1 row at 0-9-0 oc.  
Bottom chords connected with 10d (0.131"x3") nails as follows: 2x4 - 1 row at 0-9-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-4-3 to 3-4-3, Interior (1) 3-4-3 to 3-10-8, Exterior(2R) 3-10-8 to 9-10-8, Interior (1) 9-10-8 to 10-4-13, Exterior(2E) 10-4-13 to 13-4-13 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.

- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 14 lb uplift at joint 2, 7 lb uplift at joint 8, 25 lb uplift at joint 1, 2 lb uplift at joint 9, 48 lb uplift at joint 13, 44 lb uplift at joint 14, 47 lb uplift at joint 11, 45 lb uplift at joint 10, 14 lb uplift at joint 2 and 7 lb uplift at joint 8.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

LOAD CASE(S) Standard



May 7, 2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute ([www.tpinst.org](http://www.tpinst.org)) and **BCSI Building Component Safety Information** available from the Structural Building Component Association ([www.sbcacomponents.com](http://www.sbcacomponents.com))

ENGINEERING BY  
**TRENCO**  
A MiTek Affiliate

818 Soundside Road  
Edenton, NC 27932


Job	Truss	Truss Type	Qty	Ply	1002 Serenity-Roof-B326 BRH COP BR4	165383299
24030108-01	PBA	Piggyback	2	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Apr 25 2024 Print: 8.730 S Apr 25 2024 MiTek Industries, Inc. Mon May 06 11:58:41

Page: 1

ID:RPY8AW\_GFKlcY3mFoYebvHzRQqK-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:31.4

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.08	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.04	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.04	Horz(CT)	0.00	8	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH							
BCDL	10.0										
										Weight: 52 lb	FT = 20%

#### LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
OTHERS	2x4 SP No.3

#### BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS

(size)	2=11-9-14, 8=11-9-14, 10=11-9-14, 11=11-9-14, 12=11-9-14, 13=11-9-14, 14=11-9-14, 15=11-9-14, 19=11-9-14
Max Horiz	2=52 (LC 18), 15=52 (LC 18)
Max Uplift	2=-9 (LC 15), 8=-11 (LC 15), 10=-45 (LC 15), 11=-47 (LC 15), 13=-47 (LC 14), 14=-45 (LC 14), 15=-9 (LC 15), 19=-11 (LC 15)
Max Grav	2=123 (LC 21), 8=123 (LC 22), 10=237 (LC 22), 11=244 (LC 22), 12=143 (LC 21), 13=244 (LC 21), 14=237 (LC 21), 15=123 (LC 21), 19=123 (LC 22)

#### FORCES

(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=-0/17, 2-3=-46/33, 3-4=-56/49, 4-5=-63/116, 5-6=-63/116, 6-7=-56/49, 7-8=-29/25, 8-9=0/17
BOT CHORD	2-14=-9/67, 13-14=-9/67, 12-13=-9/67, 11-12=-9/67, 10-11=-9/67, 8-10=-9/67
WEBS	5-12=-102/0, 4-13=-208/125, 3-14=-181/113, 6-11=-208/125, 7-10=-181/113

#### NOTES

- 1) Unbalanced roof live loads have been considered for this design.

- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Corner(3E) 0-4-3 to 3-4-3, Exterior(2N) 3-4-3 to 3-10-8, Corner(3R) 3-10-8 to 9-10-8, Exterior(2N) 9-10-8 to 10-4-13, Corner(3E) 10-4-13 to 13-4-13 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 4) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- 5) Unbalanced snow loads have been considered for this design.
- 6) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
- 7) All plates are 2x4 MT20 unless otherwise indicated.
- 8) Gable requires continuous bottom chord bearing.
- 9) Gable studs spaced at 2-0-0 oc.
- 10) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 11) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- 12) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 9 lb uplift at joint 2, 11 lb uplift at joint 8, 47 lb uplift at joint 13, 45 lb uplift at joint 14, 47 lb uplift at joint 11, 45 lb uplift at joint 10, 9 lb uplift at joint 2 and 11 lb uplift at joint 8.

- 13) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 14) See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

**LOAD CASE(S)** Standard



May 7, 2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute ([www.tpinst.org](http://www.tpinst.org)) and **BCSI Building Component Safety Information** available from the Structural Building Component Association ([www.sbcacomponents.com](http://www.sbcacomponents.com))

ENGINEERING BY  
**TRENCO**  
A MiTek Affiliate


818 Soundside Road  
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1002 Serenity-Roof-B326 BRH COP BR4	165383300
24030108-01	PBA1	Piggyback	18	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Apr 25 2024 Print: 8.730 S Apr 25 2024 MiTek Industries, Inc. Mon May 06 11:58:41  
ID:Cx19sF4HMnJTVINoGDnTDzRQqC-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:31.4

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.29	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.12	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.08	Horiz(TL)	0.00	7	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 47 lb	FT = 20%

#### LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
OTHERS	2x4 SP No.3

#### BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS

(size)	1=13-9-0, 2=13-9-0, 6=13-9-0, 7=13-9-0, 8=13-9-0, 9=13-9-0, 10=13-9-0, 11=13-9-0, 14=13-9-0
Max Horiz	1=52 (LC 14)
Max Uplift	1=-25 (LC 15), 7=-12 (LC 15), 8=-92 (LC 15), 10=-91 (LC 14)
Max Grav	1=47 (LC 21), 2=65 (LC 1), 6=52 (LC 1), 7=49 (LC 22), 8=439 (LC 22), 9=299 (LC 21), 10=440 (LC 21), 11=65 (LC 1), 14=52 (LC 1)

#### FORCES


(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=-56/65, 2-3=-54/49, 3-4=-124/93, 4-5=-124/93, 5-6=-35/49, 6-7=-20/16
BOT CHORD	2-10=-8/44, 9-10=-8/44, 8-9=-8/44, 6-8=-8/44
WEBS	4-9=-213/93, 3-10=-386/207, 5-8=-386/207

#### NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-4-3 to 3-4-3, Interior (1) 3-4-3 to 3-10-8, Exterior(2R) 3-10-8 to 9-10-8, Interior (1) 9-10-8 to 10-4-13, Exterior(2E) 10-4-13 to 13-4-13 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60

- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 25 lb uplift at joint 1, 12 lb uplift at joint 7, 91 lb uplift at joint 10 and 92 lb uplift at joint 8.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

LOAD CASE(S) Standard




May 7, 2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute ([www.tpinst.org](http://www.tpinst.org)) and **BCSI Building Component Safety Information** available from the Structural Building Component Association ([www.sbcacompnents.com](http://www.sbcacompnents.com))

ENGINEERING BY  
**TRENCO**  
A MiTek Affiliate

818 Soundside Road  
Edenton, NC 27932

Page: 1

818 Soundside Road  
Edenton, NC 27932




Job	Truss	Truss Type	Qty	Ply	1002 Serenity-Roof-B326 BRH COP BR4	I65383302
24030108-01	C02	Half Hip	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Apr 25 2024 Print: 8.730 S Apr 25 2024 MiTek Industries, Inc. Mon May 06 11:58:40  
ID:EGq646Pbf2EXC6nWUzpaijfwU-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:70.8

Plate Offsets (X, Y): [1:0-4-1,0-0-5], [7:0-1-12,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.92	Vert(LL)	-0.10	7-8	>999	240	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.65	Vert(CT)	-0.17	7-8	>999	180	
TCDL	10.0	Rep Stress Incr	YES	WB	0.64	Horz(CT)	0.03	7	n/a	n/a	
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH							
BCDL	10.0										
Weight: 146 lb FT = 20%											

#### LUMBER

TOP CHORD 2x4 SP No.2  
BOT CHORD 2x4 SP No.2  
WEBS 2x4 SP No.3 \*Except\* 11-7:2x6 SP No.2,  
6-7:2x4 SP No.2  
SLIDER Left 2x4 SP No.3 -- 1-6-0

#### BRACING

TOP CHORD Structural wood sheathing directly applied or  
2-2-0 oc purlins.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc  
bracing.  
WEBS 1 Row at midpt 6-7, 5-7

#### REACTIONS

(size) 1=0-4-0, 7=0-5-8  
Max Horiz 1=370 (LC 14)  
Max Uplift 1=-29 (LC 14), 7=-343 (LC 14)  
Max Grav 1=896 (LC 5), 7=1717 (LC 20)

#### FORCES

(lb) - Maximum Compression/Maximum  
Tension  
TOP CHORD 1-3=-1328/28, 3-5=-803/0, 5-6=-152/81  
BOT CHORD 1-10=-409/1130, 8-10=-316/1130,  
7-8=-157/661  
WEBS 6-7=-251/89, 3-10=0/254, 5-8=0/593,  
5-7=-972/229, 3-8=-562/184

#### NOTES

- Wind: ASCE 7-16; Vult=130mph (3-second gust)  
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat.  
II; Exp B; Enclosed; MWFRS (envelope) exterior zone  
and C-C Exterior(2E) 0-1-8 to 3-1-8, Interior (1) 3-1-8 to  
17-3-12, Exterior(2E) 17-3-12 to 20-3-12 zone; C-C for  
members and forces & MWFRS for reactions shown;  
Lumber DOL=1.60 plate grip DOL=1.60
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15  
Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate  
DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9;  
Cs=1.00; Ct=1.10

- Unbalanced snow loads have been considered for this design.
- Provide adequate drainage to prevent water ponding.
- All plates are 3x5 MT20 unless otherwise indicated.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 7 and 1. This connection is for uplift only and does not consider lateral forces.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 747 lb down and 129 lb up at 20-9-12 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

#### LOAD CASE(S) Standard

- Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15  
Uniform Loads (lb/ft)  
Vert: 1-6=-60, 7-12=-20  
Concentrated Loads (lb)  
Vert: 7=-747



May 7, 2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY  
**TRENCO**  
A MiTek Affiliate

818 Soundside Road  
Edenton, NC 27932




Job	Truss	Truss Type	Qty	Ply	1002 Serenity-Roof-B326 BRH COP BR4	I65383303
24030108-01	B03	Common Structural Gable	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Apr 25 2024 Print: 8.730 S Apr 25 2024 MiTek Industries, Inc. Mon May 06 11:58:39

Page: 1

ID: onyrlCEMWITAUsFyXbXALJy7LR6-RfC?PsB70Hq3NSgPqnL8w3uTXbGKWrcDoi7J4zJC?i



Scale = 1:70.2

Plate Offsets (X, Y): [10:0-2-8,Edge], [25:0-1-12,0-1-4]

Loading	(psf)	Spacing	1-11-4	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.24	Vert(LL)	0.05	22-23	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.22	Vert(CT)	-0.04	22-23	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.16	Horz(CT)	0.00	21	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MR								
BCDL	10.0											
											Weight: 188 lb	FT = 20%

#### LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
WEBS	2x4 SP No.3
OTHERS	2x4 SP No.3

#### BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

WEBS	1 Row at midpt	9-29, 11-28, 8-30, 12-27
------	----------------	--------------------------

#### REACTIONS (size)

21=0-3-8, 24=17-5-0, 26=17-5-0, 27=17-5-0, 28=17-5-0, 29=17-5-0, 30=17-5-0, 31=17-5-0, 32=17-5-0, 33=17-5-0, 34=17-5-0, 35=17-5-0
Max Horiz 35=262 (LC 12)
Max Uplift 24=248 (LC 15), 26=2 (LC 14), 27=168 (LC 15), 28=35 (LC 13), 29=55 (LC 13), 30=113 (LC 14), 31=84 (LC 14), 32=76 (LC 14), 33=54 (LC 14), 34=201 (LC 14), 35=178 (LC 10)
Max Grav 21=321 (LC 25), 24=497 (LC 31), 26=112 (LC 22), 27=211 (LC 22), 28=247 (LC 15), 29=258 (LC 15), 30=174 (LC 21), 31=211 (LC 5), 32=196 (LC 25), 33=195 (LC 25), 34=221 (LC 25), 35=349 (LC 31)

#### FORCES

(lb) - Maximum Compression/Maximum Tension
--

TOP CHORD	1-2=0/38, 2-3=-289/209, 3-4=-219/164, 4-5=-218/164, 5-7=-199/191, 7-8=-197/243, 8-9=-231/343, 9-10=-158/196, 10-11=-159/197, 11-12=-233/344, 12-13=-190/232, 13-15=-189/168, 15-16=-88/59, 16-17=-137/31, 17-18=-172/26, 18-19=0/38, 2-35=-272/142, 18-20=-187/36
BOT CHORD	34-35=-59/167, 33-34=-59/167, 32-33=-59/167, 31-32=-59/167, 30-31=-59/167, 29-30=-59/167, 28-29=-59/167, 27-28=-59/167, 26-27=-59/167, 24-26=-59/167, 23-24=-59/167, 22-23=-59/167, 21-22=-59/167, 20-21=-59/167
WEBS	9-29=-243/122, 11-28=-244/124, 8-30=-153/156, 7-31=-169/112, 5-32=-142/96, 4-33=-152/94, 3-34=-131/154, 12-27=-166/163, 13-26=-132/80, 15-24=-276/165, 16-23=-55/70, 17-22=-77/62

#### NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Corner(3E) -0-10-8 to 2-1-8, Exterior(2N) 2-1-8 to 8-6-12, Corner(3R) 8-6-12 to 14-6-12, Exterior(2N) 14-6-12 to 21-0-0, Corner(3E) 21-0-0 to 24-0-0 zone; cantilever left and right exposed ; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.

- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
- All plates are 2x4 MT20 unless otherwise indicated.
- Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.



May 7, 2024

Continued on page 2

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY  
**TRENCO**  
A MiTek Affiliate

818 Soundside Road  
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1002 Serenity-Roof-B326 BRH COP BR4	I65383303
24030108-01	B03	Common Structural Gable	1	1	Job Reference (optional)	

- 12) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 35, 29, 28, 30, 31, 32, 33, 34, 27, 26, and 24. This connection is for uplift only and does not consider lateral forces.
- 13) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute ([www.tpinst.org](http://www.tpinst.org)) and **BCSI Building Component Safety Information** available from the Structural Building Component Association ([www.sbcacomponents.com](http://www.sbcacomponents.com))



818 Soundside Road  
Edenton, NC 27932


Job	Truss	Truss Type	Qty	Ply	1002 Serenity-Roof-B326 BRH COP BR4	I65383304
24030108-01	B01	Common	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Apr 25 2024 Print: 8.730 S Apr 25 2024 MiTek Industries, Inc. Mon May 06 11:58:39

Page: 1

ID:Nseaq6A9EjNfxKX1O6yXnly7LSU-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC7f



Scale = 1:78.1

Plate Offsets (X, Y): [15:0-4-0,0-3-4]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.65	Vert(LL)	-0.47	15-18	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.86	Vert(CT)	-0.76	15-18	>272		
TCDL	10.0	Rep Stress Incr	YES	WB	0.47	Horz(CT)	0.07	2	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH							
BCDL	10.0										
										Weight: 134 lb	FT = 20%

#### LUMBER

TOP CHORD 2x4 SP No.2  
BOT CHORD 2x4 SP No.1  
WEBS 2x4 SP No.3  
SLIDER Left 2x6 SP No.2 -- 1-6-0

#### BRACING

TOP CHORD Structural wood sheathing directly applied or 5-6-15 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS** (size) 2=0-5-8, 13=0-3-8, 14=0-5-8  
Max Horiz 2=264 (LC 13)  
Max Uplift 2=-75 (LC 14), 13=-100 (LC 15), 14=-24 (LC 14)  
Max Grav 2=892 (LC 5), 13=492 (LC 25), 14=901 (LC 22)

#### FORCES


(lb) - Maximum Compression/Maximum Tension  
TOP CHORD 1-2=0/34, 2-4=-1144/150, 4-6=-639/184, 6-8=-597/176, 8-9=-303/117, 9-10=-247/0, 10-11=0/44, 10-12=-224/37  
BOT CHORD 2-14=-251/721, 13-14=0/167, 12-13=0/167  
WEBS 6-15=-97/412, 4-15=-368/237, 8-15=-45/421, 9-13=-269/293, 8-14=-827/75

#### NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior (1) 2-1-8 to 8-6-12, Exterior(2R) 8-6-12 to 14-6-12, Interior (1) 14-6-12 to 21-1-8, Exterior(2E) 21-1-8 to 24-1-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60

- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 2, 13, and 14. This connection is for uplift only and does not consider lateral forces.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

**LOAD CASE(S)** Standard



May 7, 2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY  
**TRENCO**  
A MiTek Affiliate

818 Soundside Road  
Edenton, NC 27932


Job	Truss	Truss Type	Qty	Ply	1002 Serenity-Roof-B326 BRH COP BR4	I65383305
24030108-01	E01	Common	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Apr 25 2024 Print: 8.730 S Apr 25 2024 MiTek Industries, Inc. Mon May 06 11:58:40

Page: 1

ID:5YjLyPhGJKHB5AEdSp6x7Qy7LK3-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrcDoi7J4zJC?f



Scale = 1:41.9

Loading	(psf)	Spacing	1-11-4	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.40	Vert(LL)	-0.01	8	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.29	Vert(CT)	-0.02	8	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.03	Horz(CT)	0.00	7	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MR								
BCDL	10.0											
											Weight: 37 lb	FT = 20%

#### LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
WEBS	2x4 SP No.3

#### BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS

(size)	7=0-3-8, 9=0-3-8
Max Horiz	9=-114 (LC 12)
Max Uplift	7=-38 (LC 15), 9=-38 (LC 14)
Max Grav	7=460 (LC 22), 9=460 (LC 21)

#### FORCES

(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=0/49, 2-3=-269/93, 3-4=-269/91, 4-5=0/49, 2-10=-375/176, 4-6=-375/174
BOT CHORD	9-10=-11/120, 8-9=-11/120, 7-8=-11/120, 6-7=-11/120
WEBS	3-8=-26/84

#### NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Exterior(2R) 2-1-8 to 5-4-8, Exterior(2E) 5-4-8 to 8-4-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.

- This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- H10A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 9 and 7. This connection is for uplift only and does not consider lateral forces.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

#### LOAD CASE(S)

Standard



May 7, 2024

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**



Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY  
**TRENCO**  
A MiTek Affiliate

818 Soundside Road  
Edenton, NC 27932

# Symbols

## PLATE LOCATION AND ORIENTATION




\* Plate location details available in MITek software or upon request.

## PLATE SIZE

**4 X 4**


The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

## LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T or I bracing if indicated.


## BEARING



Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number/letter where bearings occur. Min size shown is for crushing only.

**Industry Standards:**  
ANSI/TP1: National Design Specification for Metal Plate Connected Wood Truss Construction.  
DSB-22: Building Component Safety Information, Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses.

# Numbering System



**JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.**

**CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.**

# Product Code Approvals

ICC-ES Reports:  
ESR-1988, ESR-2362, ESR-2685, ESR-3282  
ESR-4722, ESL-1388

# Design General Notes

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.  
Lumber design values are in accordance with ANSI/TP1 section 6.3. These truss designs rely on lumber values established by others.

© 2023 MITek® All Rights Reserved

# General Safety Notes

**Failure to Follow Could Cause Property Damage or Personal Injury**

1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor I bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TP1 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TP1 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TP1 1 Quality Criteria.
21. The design does not take into account any dynamic or other loads other than those expressly stated.

**MITek®**

ENGINEERING BY  
**TRENCO**  
A MITek Affiliate

MITek Engineering Reference Sheet: MII-7473 rev. 1/2/2023