




Carter Sanford Component Plant
298 Harvey Faulk Rd
Sanford, NC 27332

Phone #:919-775-1450



Builder: David Weekley Homes

Model: B326 A CP TMB GRH

THE PLACEMENT PLAN NOTES:

1. The Placement Plan is a diagram for truss installation. It is not an engineered drawing and has not been reviewed by an engineer. The Owner/Building Designer is responsible for obtaining an engineer's review if one is required by the local jurisdiction.
2. The responsibilities of the Owner, Contractor, Building Designer, Component Designer and Component Manufacturer shall be as set forth in ANSI/TPI 1. Capitalized terms shall be as defined in ANSI/TP 1 unless otherwise indicated.
3. Each Component is designed as an individual component utilizing information provided by others. The Owner/Building Designer is responsible for reviewing all Component Submittal Packages and individual Component Design Drawings for compliance with the Construction Documents and compatibility with the overall Building design.
4. Contractor will not proceed with component installation until the Owner/Building Designer has reviewed the Component Submittal Package. Questions on the suitability of any Component will be resolved by the Building Designer.
5. The Building Designer and Contractor are responsible for all temporary and permanent bracing.
6. The Placement Plan assumes the building is dimensionally correct, structurally sound, and in a suitable condition to support each Component during installation and thereafter, including but not limited to installation of all bearing points. Proper design and construction of all structural components, including foundations, headers, beams, walls and columns are the responsibility of the Owner, Building Designer and Contractor.
7. Do not cut, drill, or modify any Component without first consulting the Component Manufacturer or Building Designer. Damaged Components shall not be installed unless directed by the Building Designer or approved by the Component Manufacturer.
8. Components must be handled and installed following all applicable safety standards and best practices, including but not limited to BCSI, OSHA, TPI and local codes. Failure to properly handle, brace or otherwise install Component can result in serious injury or death.
9. All uplift connectors shown within these documents are recommendations only. Per ANSI/TPI 1, all uplift connectors are the responsibility of the building designer and or contractor.

Approved By: _____

Date: _____

General Notes:

** CUTTING OR DRILLING OF COMPONENTS SHOULD NOT BE DONE WITHOUT CONTACTING COMPONENT SUPPLIER FIRST. CUSTOMER TAKES FULL RESPONSIBILITY FOR COMPONENTS IF CUT BEFORE AUTHORIZATION.

** ALL BEARING POINTS MUST BE INSTALLED PRIOR TO SETTING ANY COMPONENTS.



** DAMAGED COMPONENTS SHOULD NOT BE INSTALLED UNLESS TOLD TO BY THE COMPONENT PLANT.

** FRAMER MUST REFER TO PLANS WHILE SETTING COMPONENTS.

** TRIANGULAR SYMBOL NEAR END OF TRUSS INDICATES LEFT END OF TRUSS AS SHOWN ON INDIVIDUAL TRUSS DRAWINGS.

** PLUMBING DROPS NOTED ARE IN THE APPROXIMATE LOCATIONS PER PLAN. BUILDER TO VERIFY LOCATIONS BEFORE SETTING TRUSSES.

** REFER TO FINAL TRUSS ENGINEERING SHEETS FOR PLY TO PLY CONNECTIONS.



Revisions	
00/00/00	Name
00/00/00	Name
00/00/00	Name
00/00/00	Name
00/00/00	Name

THIS IS A TRUSS PLACEMENT DIAGRAM ONLY. These trusses are designed as individual components to be incorporated into the building design at the specification of the building designer. See individual design sheets for each truss design identified on the placement drawing. The building designer is responsible for temporary and permanent bracing of the roof and floor systems and for the overall structure. The design of the truss support structure including headers, beams, walls, and columns is the responsibility of the building designer. For general guidance regarding the bracing, consult "Bracing of Wood Truss" available from the Truss Plate Institute, 583 D'Onofrio Drive, Madison, WI 53179.



David Weekley Homes

920 Serenity-Roof-B326 A CP
TMB GRH

COMPONENT PLAN

Scale: NTS

Date: 5/20/2025
Designer:

Project Number: 25050065-01
Sheet Number:

1/1

RE: 25050065
920 Serenity-Roof-B326 A CP TRAY GRH

Trenco
818 Soundside Rd
Edenton, NC 27932

Site Information:

Customer: David Weekley Homes Project Name: 25050065
Lot/Block: 920 Model:
Address: 980 Serenity Walk Parkway Subdivision: Serenity
City: Fuquay-Varina State: NC

General Truss Engineering Criteria & Design Loads (Individual Truss Design Drawings Show Special Loading Conditions):

Design Code: IRC2021/TPI2014 Design Program: MiTek 20/20 8.7
Wind Code: ASCE 7-16 Wind Speed: 130 mph
Roof Load: 40.0 psf Floor Load: N/A psf

This package includes 38 individual, dated Truss Design Drawings and 0 Additional Drawings.

No.	Seal#	Truss Name	Date	No.	Seal#	Truss Name	Date
1	I72213077	VLB8	3/25/2025	21	I72213097	D02	3/25/2025
2	I72213078	VLD6	3/25/2025	22	I72213098	D01	3/25/2025
3	I72213079	VLB7	3/25/2025	23	I72213099	VLB1	3/25/2025
4	I72213080	VLD5	3/25/2025	24	I72213100	G01	3/25/2025
5	I72213081	PBA2	3/25/2025	25	I72213101	C01	3/25/2025
6	I72213082	PBA	3/25/2025	26	I72213102	C02	3/25/2025
7	I72213083	PBA1	3/25/2025	27	I72213103	B02	3/25/2025
8	I72213084	H01	3/25/2025	28	I72213104	B01	3/25/2025
9	I72213085	H02	3/25/2025	29	I72213105	A05	3/25/2025
10	I72213086	VLB6	3/25/2025	30	I72213106	A03T	3/25/2025
11	I72213087	VLD4	3/25/2025	31	I72213107	A04T	3/25/2025
12	I72213088	J01	3/25/2025	32	I72213108	A06	3/25/2025
13	I72213089	VLB5	3/25/2025	33	I72213109	A09	3/25/2025
14	I72213090	VLD3	3/25/2025	34	I72213110	A08	3/25/2025
15	I72213091	VLB4	3/25/2025	35	I72213111	A07	3/25/2025
16	I72213092	VLD2	3/25/2025	36	I72213112	A01	3/25/2025
17	I72213093	VLB3	3/25/2025	37	I72213113	A03	3/25/2025
18	I72213094	VLD1	3/25/2025	38	I72213114	A04	3/25/2025
19	I72213095	VLB2	3/25/2025				
20	I72213096	E01	3/25/2025				


The truss drawing(s) referenced above have been prepared by
Truss Engineering Co. under my direct supervision
based on the parameters provided by Carter Components (Sanford, NC)).

Truss Design Engineer's Name: Johnson, Andrew

My license renewal date for the state of North Carolina is December 31, 2025.

North Carolina COA: C-0844

IMPORTANT NOTE: The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to TRENCO. Any project specific information included is for TRENCO customers file reference purpose only, and was not taken into account in the preparation of these designs. TRENCO has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.



March 25, 2025


Job	Truss	Truss Type	Qty	Ply	920 Serenity-Roof-B326 A CP TRAY GRH	I72213077
25050065	VLB8	Valley	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 12:40:05

Page: 1

ID:vFTOY0za1WjXT9L6tv8uVzZRQre-RfC?PsB70Hq3NSgPqnL8w3uITxbGKWrCDoi7J4zJC?f



Scale = 1:26

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.09	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.11	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.04	Horiz(TL)	0.00	4	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	10.0											
											Weight: 17 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
OTHERS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 4-9-13 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS

(size)	1=4-9-13, 3=4-9-13, 4=4-9-13
Max Horiz	1=-43 (LC 10)
Max Uplift	3=-7 (LC 15), 4=-33 (LC 14)
Max Grav	1=88 (LC 20), 3=88 (LC 21), 4=292 (LC 20)

FORCES

(lb) - Maximum Compression/Maximum Tension

TOP CHORD	1-2=-80/102, 2-3=-80/102
BOT CHORD	1-4=-82/87, 3-4=-82/87
WEBS	2-4=-207/95

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10

- Unbalanced snow loads have been considered for this design.
 - Gable requires continuous bottom chord bearing.
 - Gable studs spaced at 4-0-0 oc.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 7 lb uplift at joint 3 and 33 lb uplift at joint 4.
- LOAD CASE(S)** Standard



March 25, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	920 Serenity-Roof-B326 A CP TRAY GRH	I72213078
25050065	VLD6	Valley	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 12:40:06
ID:CgVkhRtdMZAuzhaXm9_U1OzRQqT-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:26.2

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.09	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.11	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.04	Horiz(TL)	0.00	4	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	10.0										Weight: 18 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 4-11-6 oc purlins.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS

(size) 1=4-11-6, 3=4-11-6, 4=4-11-6
Max Horiz 1=44 (LC 13)
Max Uplift 3=-7 (LC 15), 4=-35 (LC 14)
Max Grav 1=89 (LC 20), 3=89 (LC 21), 4=303 (LC 21)

FORCES

(lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=-82/108, 2-3=-82/108
BOT CHORD 1-4=-87/91, 3-4=-87/91
WEBS 2-4=-218/101

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust)
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10

- Unbalanced snow loads have been considered for this design.
 - Gable requires continuous bottom chord bearing.
 - Gable studs spaced at 4-0-0 oc.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 7 lb uplift at joint 3 and 35 lb uplift at joint 4.
- LOAD CASE(S)** Standard



March 25, 2025


WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 12:40:05 Page: 1
ID:vFTQYozalWlXT9L6tv8uVZzRQre-RfC?PsB70Hq3NSaPqnL8w3uITXbGKWrcDOI7J4zJC?f



LUMBER		4) TCELL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
TOP CHORD	2x4 SP No.2	
BOT CHORD	2x4 SP No.2	
OTHERS	2x4 SP No.3	
BRACING		5) Unbalanced snow loads have been considered for this design.
TOP CHORD	Structural wood sheathing directly applied or 7-2-10 oc purlins.	6) Gable requires continuous bottom chord bearing.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.	7) Gable studs spaced at 4-0-0 oc.
REACTIONS	(size) 1=7-2-10, 3=7-2-10, 4=7-2-10	8) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
	Max Horiz 1=-67 (LC 10)	9) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
	Max Uplift 1=-17 (LC 21), 3=-17 (LC 20), 4=-73 (LC 14)	
	Max Grav 1=105 (LC 20), 3=105 (LC 21), 4=530 (LC 20)	10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 17 lb uplift at joint 1, 17 lb uplift at joint 3 and 73 lb uplift at joint 4.
FORCES	(lb) - Maximum Compression/Maximum Tension	LOAD CASE(S) Standard
TOP CHORD	1-2=-88/228, 2-3=-88/228	
BOT CHORD	1-4=-178/151, 3-4=-178/151	
WERS	2-4=-419/199	

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust)
 Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-0-5 to 3-0-5, Exterior(2R) 3-0-5 to 4-2-14, Exterior(2E) 4-2-14 to 7-2-14 zone; cantilever left and right exposed ; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Truss designed for roof loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITER REFERENCE PAGE MIT-7473 (rev. 1/2/2023) BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only on parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinet.org) and **BCSI Building Component Safety Information** available from the Structural Building Components Association (www.sbcacompnents.com)


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	920 Serenity-Roof-B326 A CP TRAY GRH	I72213080
25050065	VLD5	Valley	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 12:40:05
ID:CgVkhRtdMZAuzhaXm9_U1OzRQqT-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:29.3

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.27	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.27	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.09	Horiz(TL)	0.00	4	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	10.0											
											Weight: 27 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
OTHERS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 7-4-3 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS

(size)	1=7-4-3, 3=7-4-3, 4=7-4-3
Max Horiz	1=68 (LC 11)
Max Uplift	1=-19 (LC 21), 3=-19 (LC 20), 4=-76 (LC 14)
Max Grav	1=105 (LC 20), 3=105 (LC 21), 4=545 (LC 20)

FORCES


(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=-92/236, 2-3=-92/236
BOT CHORD	1-4=-184/155, 3-4=-184/155
WEBS	2-4=-432/204

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-0-5 to 3-0-5, Exterior(2R) 3-0-5 to 4-4-8, Exterior(2E) 4-4-8 to 7-4-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.

- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 19 lb uplift at joint 1, 19 lb uplift at joint 3 and 76 lb uplift at joint 4.

LOAD CASE(S) Standard



March 25, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932


Job	Truss	Truss Type	Qty	Ply	920 Serenity-Roof-B326 A CP TRAY GRH	172213081
25050065	PBA2	Piggyback	2	4	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 12:40:04

Page: 1

ID:m2dQdjvppkexqPVgwg5aZPzRCX1-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWRCDoi7J4zJC?f



Scale = 1:31.5

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.07	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.03	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.02	Horz(CT)	0.00	15	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH							
BCDL	10.0										
										Weight: 188 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
OTHERS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(size)	2=11-10-14, 6=11-10-14, 8=11-10-14, 9=11-10-14, 10=11-10-14
Max Horiz	2=52 (LC 18)
Max Uplift	2=-11 (LC 15), 6=-4 (LC 11), 8=-87 (LC 15), 10=-87 (LC 14)
Max Grav	2=86 (LC 1), 6=86 (LC 1), 8=423 (LC 22), 9=302 (LC 21), 10=423 (LC 21)

FORCES

(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=0/17, 2-3=-53/45, 3-4=-123/96, 4-5=-123/96, 5-6=-33/45, 6-7=0/17
BOT CHORD	2-10=-8/47, 9-10=-2/46, 8-9=-2/46, 6-8=-8/47
WEBS	4-9=-215/91, 3-10=-375/198, 5-8=-375/198

NOTES

- 4-ply truss to be connected together as follows:
Top chords connected with 10d (0.131"x3") nails as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected with 10d (0.131"x3") nails as follows: 2x4 - 1 row at 0-9-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Unbalanced roof live loads have been considered for this design.

- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-4-3 to 3-4-3, Interior (1) 3-4-3 to 3-11-0, Exterior(2R) 3-11-0 to 9-11-0, Interior (1) 9-11-0 to 10-5-13, Exterior(2E) 10-5-13 to 13-5-13 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- N/A

- See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

LOAD CASE(S) Standard



March 25, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	920 Serenity-Roof-B326 A CP TRAY GRH	172213082
25050065	PBA	Piggyback	2	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 12:40:04
ID:RPY8AW_GFKlcY3mFoYebvHzRQqK-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWCDoi7J4zJC?f

Page: 1



Scale = 1:31.5

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.08	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.04	Vert(CT)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.04	Horz(CT)	0.00	8	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 52 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
OTHERS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(size)	2=11-10-14, 8=11-10-14, 10=11-10-14, 11=11-10-14, 12=11-10-14, 13=11-10-14, 14=11-10-14
Max Horiz	2=52 (LC 18)
Max Uplift	2=-9 (LC 15), 8=-12 (LC 15), 10=-45 (LC 15), 11=-47 (LC 15), 13=-47 (LC 14), 14=-46 (LC 14)
Max Grav	2=125 (LC 21), 8=125 (LC 22), 10=240 (LC 22), 11=243 (LC 22), 12=143 (LC 22), 13=243 (LC 21), 14=240 (LC 21)

FORCES

(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=0/17, 2-3=-46/33, 3-4=-56/49, 4-5=-64/107, 5-6=-64/107, 6-7=-56/42, 7-8=-30/26, 8-9=0/17
BOT CHORD	2-14=-9/58, 13-14=-9/58, 12-13=-9/58, 11-12=-9/58, 10-11=-9/58, 8-10=-9/58
WEBS	5-12=-102/0, 4-13=-207/121, 3-14=-183/88, 6-11=-207/121, 7-10=-183/88

NOTES

- Unbalanced roof live loads have been considered for this design.

- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-4-3 to 3-4-3, Interior (1) 3-4-3 to 3-11-0, Exterior(2R) 3-11-0 to 9-11-0, Interior (1) 9-11-0 to 10-5-13, Exterior(2E) 10-5-13 to 13-5-13 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- N/A

- See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

LOAD CASE(S)

Standard



March 25, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	920 Serenity-Roof-B326 A CP TRAY GRH	172213083
25050065	PBA1	Piggyback	18	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 12:40:04
ID:Cx19sF4HMnJTVINoGDnTDzzRQqC-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:31.5

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.28	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.12	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.07	Horz(CT)	0.00	15	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH							
BCDL	10.0									Weight: 47 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
OTHERS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(size)	2=11-10-14, 6=11-10-14, 8=11-10-14, 9=11-10-14, 10=11-10-14
Max Horiz	2=52 (LC 18)
Max Uplift	2=-11 (LC 15), 6=-4 (LC 11), 8=-87 (LC 15), 10=-87 (LC 14)
Max Grav	2=87 (LC 1), 6=87 (LC 1), 8=423 (LC 22), 9=301 (LC 21), 10=423 (LC 21)

FORCES

(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=0/17, 2-3=-54/45, 3-4=-124/96, 4-5=-124/96, 5-6=-34/45, 6-7=0/17
BOT CHORD	2-10=-7/46, 9-10=-2/46, 8-9=-2/46, 6-8=-7/46
WEBS	4-9=-214/91, 3-10=-377/199, 5-8=-377/199

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-4-3 to 3-4-3, Interior (1) 3-4-3 to 3-11-0, Exterior(2R) 3-11-0 to 9-11-0, Interior (1) 9-11-0 to 10-5-13, Exterior(2E) 10-5-13 to 13-5-13 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60

- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- N/A

- See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

LOAD CASE(S) Standard



March 25, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	920 Serenity-Roof-B326 A CP TRAY GRH	172213084
25050065	H01	Monopitch Supported Gable	2	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 12:40:03
ID:kX6Xm09JsM8Rk_RkgNonK3zRRGV-RfC?PsB70Hq3NSgPqnL8w3uTXbGKWrCDoi7J4zJC?i

Page: 1



Scale = 1:45.8

Plate Offsets (X, Y): [2:Edge,0-0-14], [2:0-2-5,Edge], [10:0-0-8,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.99	Vert(LL)	n/a	-	n/a	999	MT20
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.35	Vert(CT)	n/a	-	n/a	999	244/190
TCDL	10.0	Rep Stress Incr	YES	WB	0.24	Horz(CT)	-0.07	17	n/a	n/a	
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH							
BCDL	10.0										
										Weight: 68 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
WEBS	2x4 SP No.3 *Except* 8-12:2x4 SP No.2
OTHERS	2x4 SP No.3
WEDGE	Left: 2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals. Except: 9-5-0 oc bracing: 12-17
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.
JOINTS	1 Brace at Jt(s): 18


REACTIONS	(size) 2=10-1-0, 12=10-1-0, 13=10-1-0, 14=10-1-0, 15=10-1-0, 16=10-1-0, 17=10-1-0
	Max Horiz 2=180 (LC 10)
	Max Uplift 2=-3 (LC 14), 12=-69 (LC 21), 14=-18 (LC 10), 15=-155 (LC 14), 17=-278 (LC 14)
	Max Grav 2=1 (LC 21), 12=34 (LC 10), 13=131 (LC 1), 14=172 (LC 1), 15=203 (LC 21), 16=234 (LC 27), 17=877 (LC 21)

FORCES	(lb) - Maximum Compression/Maximum Tension
TOP CHORD	1-2=0/17, 2-3=-665/417, 3-4=-664/425, 4-5=-584/421, 5-7=-529/403, 7-8=-532/474, 8-9=-624/628, 9-10=-624/695, 10-11=-45/0, 12-17=0/0, 8-17=-368/305
BOT CHORD	2-16=-380/356, 15-16=-380/356, 14-15=-380/356, 13-14=-380/356, 12-13=-380/356
WEBS	3-16=-144/0, 4-15=-135/227, 5-14=-163/151, 7-13=-35/60, 17-18=-791/645, 10-18=-800/661, 9-18=-25/25

NOTES

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Corner(3E) -0-10-8 to 2-0-0, Exterior(2N) 2-0-0 to 16-0-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- 4) Unbalanced snow loads have been considered for this design.
- 5) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
- 6) All plates are 2x4 MT20 unless otherwise indicated.
- 7) Gable studs spaced at 2-0-0 oc.
- 8) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 9) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- 10) Bearing at joint(s) 17 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 11) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 69 lb uplift at joint 12.

LOAD CASE(S) Standard



March 25, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	920 Serenity-Roof-B326 A CP TRAY GRH	172213085
25050065	H02	Monopitch	6	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 12:40:04
ID:nLPVeuW3K4TytrtY3ILLguzRRHK-RfC?PsB70Hq3NSgPqnL8w3uITxbGKWrCDoi7J4zJC7f

Page: 1



Scale = 1:48.2

Plate Offsets (X, Y): [2:Edge,0-0-14], [2:0-2-5,Edge], [6:0-0-8,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.78	Vert(LL)	0.03	9-10	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.36	Vert(CT)	-0.05	9-10	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.50	Horz(CT)	0.01	9	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 66 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3 *Except* 5-9:2x4 SP No.1
WEDGE Left: 2x4 SP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
Except:
5-3-0 oc bracing: 9-11
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 2=0-3-0, 9=0-5-8
Max Horiz 2=207 (LC 10)
Max Uplift 2=-100 (LC 10), 9=-371 (LC 10)
Max Grav 2=377 (LC 1), 9=1084 (LC 21)


FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/17, 2-3=-368/82, 3-5=-393/465,
5-6=-456/707, 6-7=-45/0, 9-11=-847/467,
5-11=-321/163
BOT CHORD 2-10=-230/338, 9-10=-230/338, 8-9=0/0
WEBS 3-10=-124/211, 3-9=-614/478, 6-11=-811/468

NOTES

- Wind: ASCE 7-16; Vult=130mph (3-second gust)
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat.
II; Exp B; Enclosed; MWFRS (envelope) exterior zone
and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior (1) 2-1-8
to 16-0-0 zone; cantilever left exposed ; porch left and
right exposed;C-C for members and forces & MWFRS
for reactions shown; Lumber DOL=1.60 plate grip
DOL=1.60
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15
Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate
DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9;
Cs=1.00; Ct=1.10

- Unbalanced snow loads have been considered for this design.
- This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 9 and 2. This connection is for uplift only and does not consider lateral forces.

LOAD CASE(S) Standard



March 25,2025


WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 12:40:05 Page: 1
ID:vFTOYzoa1WjXT9L6tv8uVZzRQre-RfC?PsB70Hq3NSaPqnL8w3uITXbGKWrcD0i7J4zJC?f



- 4) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- 5) Unbalanced snow loads have been considered for this design.
- 6) Gable requires continuous bottom chord bearing.
- 7) Gable studs spaced at 4'-0" oc.
- 8) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 9) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3'-6"-0" tall by 2'-0"-0" wide will fit between the bottom chord and any other members.
- 10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 49 lb uplift at joint 1, 49 lb uplift at joint 3 and 108 lb uplift at joint 4.

LOAD CASE(S) Standard




Job	Truss	Truss Type	Qty	Ply	920 Serenity-Roof-B326 A CP TRAY GRH	172213087
25050065	VLD4	Valley	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 12:40:05
ID:kUxM45s?bF21LX?KCRTFVazRQqU-RfC?PsB70Hq3NSgPqnL8w3uTXbGKwRCDoi7J4zJC?i

Page: 1



Scale = 1:33.4

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.46	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.44	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.19	Horiz(TL)	0.01	4	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 37 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
OTHERS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 9-9-0 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS

(size)	1=9-9-0, 3=9-9-0, 4=9-9-0
Max Horiz	1=-91 (LC 10)
Max Uplift	1=-52 (LC 21), 3=-52 (LC 20), 4=-111 (LC 14)
Max Grav	1=94 (LC 20), 3=94 (LC 21), 4=788 (LC 20)

FORCES


	(lb) - Maximum Compression/Maximum Tension
TOP CHORD	1-2=-117/382, 2-3=-117/382
BOT CHORD	1-4=-249/175, 3-4=-249/175
WEBS	2-4=-650/275

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-0-5 to 3-0-5, Exterior(2R) 3-0-5 to 6-9-5, Exterior(2E) 6-9-5 to 9-9-5 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.

- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 52 lb uplift at joint 1, 52 lb uplift at joint 3 and 111 lb uplift at joint 4.

LOAD CASE(S) Standard



March 25, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	920 Serenity-Roof-B326 A CP TRAY GRH	172213088
25050065	J01	Common	5	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 12:40:04
ID:yPXMlbyKekkHSiWSiZLGInzRR58-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrcDoi7J4zJC?f

Page: 1



Scale = 1:40.3

Plate Offsets (X, Y): [5:0-3-8,Edge], [6:0-4-0,0-3-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.38	Vert(LL)	-0.09	6-9	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.64	Vert(CT)	-0.19	6-9	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.21	Horz(CT)	0.02	5	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 75 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3
WEDGE Right: 2x4 SP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 5-1-15 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 1=0-5-8, 5=0-5-8
Max Horiz 1=71 (LC 14)
Max Uplift 1=66 (LC 14), 5=64 (LC 15)
Max Grav 1=747 (LC 20), 5=746 (LC 21)

FORCES

(lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-1256/309, 2-3=-879/232, 3-4=-871/231,
4-5=-1211/300
BOT CHORD 1-5=-221/1083
WEBS 3-6=-51/474, 4-6=-401/159, 2-6=-439/174

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust)
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-0-0 to 3-0-0, Interior (1) 3-0-0 to 5-7-8, Exterior(2R) 5-7-8 to 11-7-8, Interior (1) 11-7-8 to 14-0-8, Exterior(2E) 14-0-8 to 17-0-8 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.

- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Bearings are assumed to be: , Joint 5 SP No.2 .
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 66 lb uplift at joint 1.
- One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 5. This connection is for uplift only and does not consider lateral forces.

LOAD CASE(S) Standard



March 25, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	920 Serenity-Roof-B326 A CP TRAY GRH	I72213089
25050065	VLB5	Valley	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 12:40:05
ID:vFTOYozalWjXT9L6tv8uVZzRQre-RfC?PsB70Hq3NSgPqnL8w3uITxBGKWrCDoi7J4zJC?f

Page: 1



Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.31	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.12	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.08	Horiz(TL)	0.00	5	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 50 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(size) 1=12-0-3, 5=12-0-3, 6=12-0-3,
7=12-0-3, 8=12-0-3
Max Horiz 1=114 (LC 11)
Max Uplift 1=-34 (LC 10), 5=-6 (LC 11),
6=-136 (LC 15), 8=-139 (LC 14)
Max Grav 1=91 (LC 30), 5=70 (LC 24), 6=434
(LC 21), 7=259 (LC 20), 8=434 (LC 20)

FORCES


(lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-114/101, 2-3=-218/115, 3-4=-218/115,
4-5=-88/63
BOT CHORD 1-8=-32/75, 7-8=-31/73, 6-7=-31/73,
5-6=-31/73
WEBS 3-7=-172/0, 2-8=-401/220, 4-6=-401/220

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust)
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-0-5 to 3-0-5, Exterior(2R) 3-0-5 to 9-0-8, Exterior(2E) 9-0-8 to 12-0-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60

- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 34 lb uplift at joint 1, 6 lb uplift at joint 5, 139 lb uplift at joint 8 and 136 lb uplift at joint 6.

LOAD CASE(S) Standard



March 25, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	920 Serenity-Roof-B326 A CP TRAY GRH	I72213090
25050065	VLD3	Valley	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 12:40:05
ID:kUxM45s?bF21LX?KCRTFVazRQqU-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?i

Page: 1



Scale = 1:39.3

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.31	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.12	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.08	Horiz(TL)	0.00	5	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 50 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
OTHERS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(size)	1=12-1-13, 5=12-1-13, 6=12-1-13, 7=12-1-13, 8=12-1-13
Max Horiz	1=-115 (LC 12)
Max Uplift	1=-33 (LC 10), 5=-5 (LC 11), 6=-136 (LC 15), 8=-140 (LC 14)
Max Grav	1=94 (LC 25), 5=73 (LC 24), 6=434 (LC 21), 7=261 (LC 21), 8=434 (LC 20)

FORCES


(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=-117/101, 2-3=-216/116, 3-4=-216/116, 4-5=-91/63
BOT CHORD	1-8=-32/79, 7-8=-32/74, 6-7=-32/74, 5-6=-32/74
WEBS	3-7=-174/0, 2-8=-397/217, 4-6=-397/217

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-0-5 to 3-0-5, Exterior(2R) 3-0-5 to 9-2-2, Exterior(2E) 9-2-2 to 12-2-2 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60

- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 33 lb uplift at joint 1, 5 lb uplift at joint 5, 140 lb uplift at joint 8 and 136 lb uplift at joint 6.

LOAD CASE(S) Standard



March 25, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932


Job	Truss	Truss Type	Qty	Ply	920 Serenity-Roof-B326 A CP TRAY GRH	I72213091
25050065	VLB4	Valley	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 12:40:05

Page: 1

ID:CKtcSNrNSSyGdaBHoyY5SzRQro-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrcDoi7J4zJC?f



Scale = 1:43.4

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.31	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.16	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.14	Horiz(TL)	0.00	5	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH							
BCDL	10.0									Weight: 62 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
OTHERS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS

(size)	1=14-5-0, 5=14-5-0, 6=14-5-0, 7=14-5-0, 8=14-5-0
Max Horiz	1=-137 (LC 10)
Max Uplift	1=-24 (LC 10), 6=-154 (LC 15), 8=-157 (LC 14)
Max Grav	1=123 (LC 25), 5=99 (LC 24), 6=454 (LC 21), 7=403 (LC 24), 8=454 (LC 20)

FORCES


(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=-152/140, 2-3=-177/118, 3-4=-177/112, 4-5=-121/105
BOT CHORD	1-8=-59/126, 7-8=-59/100, 6-7=-59/100, 5-6=-59/100
WEBS	3-7=-223/0, 2-8=-374/196, 4-6=-374/195

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-0-5 to 3-2-13, Interior (1) 3-2-13 to 4-2-13, Exterior(2R) 4-2-13 to 10-2-13, Interior (1) 10-2-13 to 11-2-13, Exterior(2E) 11-2-13 to 14-5-5 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60

- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 24 lb uplift at joint 1, 157 lb uplift at joint 8 and 154 lb uplift at joint 6.

LOAD CASE(S) Standard



March 25, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932


Job	Truss	Truss Type	Qty	Ply	920 Serenity-Roof-B326 A CP TRAY GRH	172213092
25050065	VLD2	Valley	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 12:40:05

Page: 1

ID:Th_ZgqfOm8nUgyqbk?jKoVzRQuc-RfC?PsB70Hq3NSgPqnL8w3uITxbGKWrCDoi7J4zJC?f



Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.31	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.16	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.15	Horiz(TL)	0.00	5	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 63 lb	FT = 20%

LUMBER		
TOP CHORD	2x4 SP No.2	
BOT CHORD	2x4 SP No.2	
OTHERS	2x4 SP No.3	
BRACING		
TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins.	
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.	
REACTIONS	(size)	1=14-6-10, 5=14-6-10, 6=14-6-10, 7=14-6-10, 8=14-6-10
	Max Horiz	1=138 (LC 11)
	Max Uplift	1=-24 (LC 10), 6=-156 (LC 15), 8=-159 (LC 14)
	Max Grav	1=124 (LC 25), 5=99 (LC 24), 6=456 (LC 21), 7=407 (LC 24), 8=456 (LC 20)
FORCES	(lb) - Maximum Compression/Maximum Tension	
TOP CHORD		1-2=-153/145, 2-3=-173/121, 3-4=-173/111, 4-5=-121/110
BOT CHORD		1-8=-61/127, 7-8=-61/101, 6-7=-61/101, 5-6=-61/101
WEBS		3-7=-227/0, 2-8=-375/197, 4-6=-375/196

- NOTES**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-0-5 to 3-3-10, Interior (1) 3-3-10 to 4-3-10, Exterior(2R) 4-3-10 to 10-3-10, Interior (1) 10-3-10 to 11-3-10, Exterior(2E) 11-3-10 to 14-6-14 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60

- 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 4) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- 5) Unbalanced snow loads have been considered for this design.
- 6) Gable requires continuous bottom chord bearing.
- 7) Gable studs spaced at 4-0-0 oc.
- 8) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 9) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 24 lb uplift at joint 1, 159 lb uplift at joint 8 and 156 lb uplift at joint 6.

LOAD CASE(S) Standard



March 25, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932


Job	Truss	Truss Type	Qty	Ply	920 Serenity-Roof-B326 A CP TRAY GRH	172213093
25050065	VLB3	Valley	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 12:40:04

Page: 1

ID:4pahjxh9RSqoCd5h0aDV3jzRQs?-RfC?PsB70Hq3NSgPqnL8w3uITxbGKWrCDoi7J4zJC?f



Scale = 1:50.5

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.35	Vert(LL)	n/a	-	n/a	999	MT20
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.18	Vert(TL)	n/a	-	n/a	999	244/190
TCDL	10.0	Rep Stress Incr	YES	WB	0.26	Horiz(TL)	0.00	5	n/a	n/a	
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH							
BCDL	10.0										
Weight: 75 lb FT = 20%											

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
OTHERS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS

(size)	1=16-9-13, 5=16-9-13, 6=16-9-13, 8=16-9-13, 9=16-9-13
Max Horiz	1=-161 (LC 10)
Max Uplift	1=-22 (LC 10), 6=-182 (LC 15), 9=-185 (LC 14)
Max Grav	1=124 (LC 30), 5=106 (LC 21), 6=519 (LC 6), 8=493 (LC 24), 9=520 (LC 24)

FORCES


(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=-145/248, 2-3=-111/187, 3-4=-111/167, 4-5=-120/211
BOT CHORD	1-9=-128/136, 8-9=-128/136, 6-8=-128/136, 5-6=-128/136
WEBS	3-8=-307/0, 2-9=-395/219, 4-6=-395/218

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-0-5 to 3-0-5, Interior (1) 3-0-5 to 5-5-3, Exterior(2R) 5-5-3 to 11-5-3, Interior (1) 11-5-3 to 13-10-2, Exterior(2E) 13-10-2 to 16-10-2 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60

- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 22 lb uplift at joint 1, 185 lb uplift at joint 9 and 182 lb uplift at joint 6.

LOAD CASE(S) Standard



March 25, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	920 Serenity-Roof-B326 A CP TRAY GRH	I72213094
25050065	VLD1	Valley	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 12:40:05
ID:?VRASUfm0qfd3oFPBHC5FHzRQud-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1



Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.39	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.18	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.42	Horiz(TL)	0.00	5	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 76 lb	FT = 20%

LUMBER		
TOP CHORD	2x4 SP No.2	
BOT CHORD	2x4 SP No.2	
OTHERS	2x4 SP No.3	
BRACING		
TOP CHORD	Structural wood sheathing directly applied or 10-0-0 oc purlins.	
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.	
REACTIONS	(size)	1=16-11-6, 5=16-11-6, 6=16-11-6, 8=16-11-6, 9=16-11-6
	Max Horiz	1=161 (LC 11)
	Max Uplift	1=-58 (LC 10), 6=-184 (LC 15), 9=-190 (LC 14)
	Max Grav	1=83 (LC 35), 5=1 (LC 25), 6=513 (LC 25), 8=657 (LC 24), 9=516 (LC 24)
FORCES	(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=-105/376, 2-3=-23/323, 3-4=-1/302, 4-5=-144/307	
BOT CHORD	1-9=-201/77, 8-9=-201/75, 6-8=-201/75, 5-6=-201/75	
WEBS	3-8=-476/0, 2-9=-394/222, 4-6=-394/220	

- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-0-5 to 3-0-5, Interior (1) 3-0-5 to 5-6-0, Exterior(2R) 5-6-0 to 11-6-0, Interior (1) 11-6-0 to 13-7-3, Exterior(2E) 13-7-3 to 16-7-3 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60

- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 58 lb uplift at joint 1, 190 lb uplift at joint 9 and 184 lb uplift at joint 6.

LOAD CASE(S) Standard



March 25, 2025


WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 12:40:04 Page: 1
ID:vJln UX?VSB9dbBmLUS1zzRQsC-RfC?PsB70Hg3NSqPqnL8w3ulTXbGKWrcDOi7J4zJC?f



LUMBER		Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-0-5 to 3-0-5, Interior (1) 3-0-5 to 6-7-10, Exterior(2R) 6-7-10 to 12-7-10, Interior (1) 12-7-10 to 16-2-14, Exterior(2E) 16-2-14 to 19-2-14 zone; cantilever left and right exposed ; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
TOP CHORD	2x4 SP No.2	3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
BOT CHORD	2x4 SP No.2	
OTHERS	2x4 SP No.3	
BRACING		4) TCELL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins.	5) Unbalanced snow loads have been considered for this design. 6) All plates are 2x4 MT20 unless otherwise indicated. 7) Gable requires continuous bottom chord bearing. 8) Gable studs spaced at 4-0-0 oc. 9) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads. 10) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.	
REACTIONS	(size) 1=19-2-10, 7=19-2-10, 8=19-2-10, 10=19-2-10, 11=19-2-10, 12=19-2-10, 13=19-2-10 Max Horiz 1=184 (LC 10) Max Uplift 1=71 (LC 12), 7=26 (LC 13), 8=89 (LC 15), 10=175 (LC 15), 12=174 (LC 14), 13=95 (LC 14) Max Grav 1=113 (LC 14), 7=82 (LC 15), 8=318 (LC 25), 10=480 (LC 6), 11=374 (LC 27), 12=480 (LC 5), 13=326 (LC 24)	
FORCES		11) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 71 lb uplift at joint 1, 26 lb uplift at joint 7, 174 lb uplift at joint 12, 95 lb uplift at joint 13, 175 lb uplift at joint 10 and 89 lb uplift at joint 8
TOP CHORD	(lb) - Maximum Compression/Maximum Tension 1-2=-220/155, 2-3=-184/117, 3-4=-209/163, 4-5=-209/139, 5-6=-142/63, 6-7=-180/97	
BOT CHORD	1-13=-78/140, 12-13=-61/140, 11-12=-61/140, 10-11=-61/140, 8-10=-61/140, 7-8=-61/140	
WEBS	4-11=-181/5, 3-12=-379/222, 2-13=-258/170, 5-10=-379/222, 6-8=-258/168	
NOTES		
1) Unbalanced roof live loads have been considered for this design.		

March 25.2025



818 Soundside Road
Edenton, NC 27932


Job	Truss	Truss Type	Qty	Ply	920 Serenity-Roof-B326 A CP TRAY GRH	172213096
25050065	E01	Common Supported Gable	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 12:40:03

Page: 1

ID:onyrlCEMWITAUsFyYbXALJy7LR6-RfC?PsB70Hq3NSgPqnL8w3uITxBGKwRCDoi7J4zJC?f



Scale = 1:53.1

Plate Offsets (X, Y): [8:0-2-8,Edge]

Loading	(psf)	Spacing	1-11-4	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.18	Vert(LL)	n/a	-	n/a	999	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.11	Vert(CT)	n/a	-	n/a	999	
TCDL	10.0	Rep Stress Incr	YES	WB	0.15	Horz(CT)	0.00	16	n/a	n/a	
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MR							
BCDL	10.0										
Weight: 130 lb FT = 20%											

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
WEBS	2x4 SP No.3
OTHERS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS (size)	16=17-6-0, 17=17-6-0, 18=17-6-0, 19=17-6-0, 21=17-6-0, 22=17-6-0, 23=17-6-0, 24=17-6-0, 25=17-6-0, 26=17-6-0, 27=17-6-0, 28=17-6-0
Max Horiz	28=209 (LC 13)
Max Uplift	16=135 (LC 13), 17=215 (LC 15), 18=70 (LC 15), 19=77 (LC 15), 21=84 (LC 15), 24=83 (LC 14), 25=77 (LC 14), 26=69 (LC 14), 27=231 (LC 14), 28=187 (LC 12)
Max Grav	16=226 (LC 15), 17=200 (LC 13), 18=170 (LC 31), 19=206 (LC 22), 21=214 (LC 22), 22=136 (LC 22), 23=136 (LC 21), 24=214 (LC 21), 25=206 (LC 21), 26=169 (LC 25), 27=233 (LC 12), 28=261 (LC 11)

FORCES

(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	2-28=-168/112, 1-2=0/38, 2-3=-204/166, 3-4=-116/115, 4-5=-92/94, 5-6=-76/160, 6-7=-104/251, 7-8=-76/166, 8-9=-76/166, 9-10=-104/251, 10-11=-72/160, 11-12=-69/73, 12-13=-90/87, 13-14=-185/126, 14-15=0/38, 14-16=-142/80

BOT CHORD	27-28=-98/172, 26-27=-98/172, 25-26=-98/172, 24-25=-98/172, 23-24=-98/172, 22-23=-98/172, 21-22=-98/172, 19-21=-98/172, 18-19=-98/172, 17-18=-98/172, 16-17=-98/172
WEBS	7-23=-141/22, 9-22=-141/22, 6-24=-181/127, 5-25=-167/114, 4-26=-150/120, 3-27=-124/148, 10-21=-181/127, 11-19=-167/114, 12-18=-150/120, 13-17=-111/144

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Corner(3E) -0-10-8 to 2-1-8, Exterior(2N) 2-1-8 to 5-9-0, Corner(3R) 5-9-0 to 11-9-0, Exterior(2N) 11-9-0 to 15-4-8, Corner(3E) 15-4-8 to 18-4-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
- All plates are 2x4 MT20 unless otherwise indicated.

- Gable requires continuous bottom chord bearing.
- Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-0-00 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 187 lb uplift at joint 28, 135 lb uplift at joint 16, 83 lb uplift at joint 24, 77 lb uplift at joint 25, 69 lb uplift at joint 26, 231 lb uplift at joint 27, 84 lb uplift at joint 21, 77 lb uplift at joint 19, 70 lb uplift at joint 18 and 215 lb uplift at joint 17.

LOAD CASE(S) Standard



March 25, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932


Job	Truss	Truss Type	Qty	Ply	920 Serenity-Roof-B326 A CP TRAY GRH	I72213097
25050065	D02	Common Girder	1	2	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 12:40:03

Page: 1

ID:ahvaep5BsMWascBuTkn6buzRAib-RfC?PsB70Hq3NSgPqnLw3uITXbGKWrCDoi7J4zJC?f



Scale = 1:59.2

Plate Offsets (X, Y): [1:0-8-0,0-9-4], [3:0-5-0,0-5-12], [5:0-0-8,0-2-0], [10:0-3-12,0-8-5], [11:0-5-12,0-1-8], [12:0-8-0,0-9-0], [13:0-9-12,0-6-0], [14:0-9-8,0-3-8], [15:0-3-8,0-9-8]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.43	Vert(LL)	-0.10	14-15	>999	240	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.57	Vert(CT)	-0.17	14-15	>999	180	
TCDL	10.0	Rep Stress Incr	NO	WB	0.92	Horz(CT)	0.04	10	n/a	n/a	
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH							
BCDL	10.0										
Weight: 487 lb FT = 20%											

LUMBER

TOP CHORD 2x8 SP 2400F 2.0E
 BOT CHORD 2x12 SP 2400F 2.0E
 WEBS 2x4 SP No.3 *Except* 13-6:2x4 SP No.1, 5-14:2x4 SP No.2
 SLIDER Left 2x4 SP No.3 -- 1-6-0, Right 2x4 SP No.3 -- 1-6-0

BRACING

TOP CHORD Structural wood sheathing directly applied or 5-11-12 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 1=(0-5-8 + bearing block), (req. 0-6-2), 10=0-5-8
 Max Horiz 1=-176 (LC 10)
 Max Grav 1=14865 (LC 21), 10=10712 (LC 6)

FORCES


(lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-3=-15578/0, 3-4=-14258/0, 4-5=-12125/0, 5-6=-9492/0, 6-7=-9463/0, 7-8=-11050/0, 8-10=-12158/0
 BOT CHORD 1-16=0/10988, 15-16=0/10988, 14-15=0/11862, 13-14=0/9117, 11-13=0/9123, 10-11=0/9123
 WEBS 6-13=0/10728, 7-13=-1571/0, 7-12=0/2918, 8-12=-1103/0, 8-11=0/1625, 4-14=-4425/101, 4-15=-208/3373, 5-14=0/5105, 5-13=-3189/0, 3-16=-421/1446, 3-15=0/2222

NOTES

- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
 Top chords connected as follows: 2x8 - 2 rows staggered at 0-9-0 oc.
 Bottom chords connected as follows: 2x12 - 6 rows staggered at 0-5-0 oc.
 Web connected as follows: 2x4 - 1 row at 0-9-0 oc, Except member 5-14 2x4 - 1 row at 0-5-0 oc, member 3-16 2x4 - 2 rows staggered at 0-2-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- 2x12 SP 2400F 2.0E bearing block 12" long at jt. 1 attached to each face with 6 rows of 10d (0.131"x3") nails spaced 3" o.c. 24 Total fasteners per block. Bearing is assumed to be SP 2400F 2.0E.
- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Use Simpson Strong-Tie HTU210 (32-10dx1 1/2 Girder, 14-10dx1 1/2 Truss, Single Ply Girder) or equivalent at 4-4-12 from the left end to connect truss(es) to back face of bottom chord.
- Use Simpson Strong-Tie HTU28 (20-16d Girder, 26-10dx1 1/2 Truss, Single Ply Girder) or equivalent spaced at 2-0-0 oc max. starting at 6-4-12 from the left end to 16-4-12 to connect truss(es) to back face of bottom chord.
- Fill all nail holes where hanger is in contact with lumber.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 8867 lb down and 535 lb up at 2-7-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard

- Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
 Uniform Loads (lb/ft)
 Vert: 1-6=-60, 6-10=-60, 17-21=-20
 Concentrated Loads (lb)



March 25, 2025

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
 A MiTek Affiliate

818 Soundside Road
 Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	920 Serenity-Roof-B326 A CP TRAY GRH
25050065	D02	Common Girder	1	2	I72213097
					Job Reference (optional)

Vert: 14=-1893 (B), 16=-5499 (B), 27=-1897 (B),
28=-1893 (B), 29=-1893 (B), 30=-1893 (B), 31=-1893 (B), 32=-1893 (B)

 **WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)




818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	920 Serenity-Roof-B326 A CP TRAY GRH	I72213098
25050065	D01	Common Supported Gable	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 12:40:03
ID:8F2D?hHuvW?rb9K6OMb_YzRQrE-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:56.9

Plate Offsets (X, Y): [7:0-2-8,Edge]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.21	Vert(LL)	n/a	-	n/a	999	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.12	Vert(CT)	n/a	-	n/a	999	
TCDL	10.0	Rep Stress Incr	YES	WB	0.20	Horz(CT)	0.00	14	n/a	n/a	
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MR							
BCDL	10.0										
Weight: 127 lb FT = 20%											

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
WEBS	2x4 SP No.3
OTHERS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS	(size)	14=18-6-0, 15=18-6-0, 17=18-6-0, 18=18-6-0, 19=18-6-0, 20=18-6-0, 21=18-6-0, 22=18-6-0, 23=18-6-0, 24=18-6-0
Max Horiz		24=225 (LC 12)
Max Uplift		14=50 (LC 11), 15=163 (LC 15), 17=47 (LC 15), 18=116 (LC 15), 21=115 (LC 14), 22=46 (LC 14), 23=168 (LC 14), 24=69 (LC 10)
Max Grav		14=190 (LC 25), 15=221 (LC 26) 17=172 (LC 22), 18=253 (LC 22), 19=224 (LC 22), 20=224 (LC 21), 21=253 (LC 21), 22=172 (LC 21), 23=228 (LC 25), 24=205 (LC 26)

FORCES

(lb) - Maximum Compression/Maximum Tension

TOP CHORD	2-24=-168/63, 1-2=0/39, 2-3=-164/140, 3-4=-105/90, 4-5=-92/118, 5-6=-116/235, 6-7=-94/171, 7-8=-94/171, 8-9=-116/235, 9-10=-77/117, 10-11=-90/72, 11-12=-152/117, 12-13=0/39, 12-14=-155/47
BOT CHORD	23-24=-106/187, 22-23=-106/187, 21-22=-106/187, 20-21=-106/187, 19-20=-106/187, 18-19=-106/187, 17-18=-106/187, 15-17=-106/187, 14-15=-106/187

WEBS

6-20=-185/8, 8-19=-185/7, 5-21=-213/162, 4-22=-142/93, 3-23=-174/160, 9-18=-213/163, 10-17=-143/91, 11-15=-168/168

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Corner(3E) -0-10-8 to 2-3-4, Exterior(2N) 2-3-4 to 6-3-0, Corner(3R) 6-3-0 to 12-2-12, Exterior(2N) 12-2-12 to 16-2-12, Corner(3E) 16-2-12 to 19-4-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.

12) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.

13) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 69 lb uplift at joint 24, 50 lb uplift at joint 14, 115 lb uplift at joint 21, 46 lb uplift at joint 22, 168 lb uplift at joint 23, 116 lb uplift at joint 18, 47 lb uplift at joint 17 and 163 lb uplift at joint 15.

LOAD CASE(S) Standard



March 25, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	920 Serenity-Roof-B326 A CP TRAY GRH	I72213099
25050065	VLB1	Valley	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 12:40:04
ID:uRu6rMLa1rlmrJyJNhjxpxzRQsR-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:58.7

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.31	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.17	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.21	Horiz(TL)	0.01	7	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH							
BCDL	10.0										
										Weight: 106 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
OTHERS	2x4 SP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.

BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

WEBS 1 Row at midpt 4-11

REACTIONS	(size)	1=21-7-6, 7=21-7-6, 8=21-7-6, 10=21-7-6, 11=21-7-6, 12=21-7-6, 13=21-7-6
	Max Horiz	1=207 (LC 11)
	Max Uplift	1=-48 (LC 10), 7=-6 (LC 11), 8=-114 (LC 15), 10=-174 (LC 15), 12=-173 (LC 14), 13=-120 (LC 34)
	Max Grav	1=149 (LC 25), 7=109 (LC 32), 8=362 (LC 25), 10=473 (LC 6), 11=414 (LC 27), 12=473 (LC 5), 13=370 (LC 24)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD	1-2=-213/174, 2-3=-164/132, 3-4=-188/181, 4-5=-188/154, 5-6=-116/82, 6-7=-168/107
BOT CHORD	1-13=-76/154, 12-13=-76/154, 11-12=-76/154, 10-11=-76/154, 8-10=-76/154, 7-8=-76/154
WEBS	4-11=-208/3, 3-12=-376/222, 2-13=-265/163, 5-10=-376/222, 6-8=-264/161

NOTES

- 1) Unbalanced roof live loads have been considered for this design.

- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-0-5 to 2-10-0, Interior (1) 2-10-0 to 7-10-0, Exterior(2R) 7-10-0 to 13-10-0, Interior (1) 13-10-0 to 18-3-3, Exterior(2E) 18-3-3 to 21-3-3 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 4) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- 5) Unbalanced snow loads have been considered for this design.
- 6) All plates are 2x4 MT20 unless otherwise indicated.
- 7) Gable requires continuous bottom chord bearing.
- 8) Gable studs spaced at 4-0-0 oc.
- 9) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 10) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 11) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 48 lb uplift at joint 1, 6 lb uplift at joint 7, 173 lb uplift at joint 12, 120 lb uplift at joint 13, 174 lb uplift at joint 10 and 114 lb uplift at joint 8.

LOAD CASE(S) Standard



March 25, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	920 Serenity-Roof-B326 A CP TRAY GRH	I72213100
25050065	G01	Monopitch	5	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 12:40:03
ID: PdAAD85_ICJN?UaWrZnF5zRQu2-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:64.6

Plate Offsets (X, Y): [2:0-2-0,0-1-8], [3:0-4-0,0-3-4]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.95	Vert(LL)	-0.12	7-8	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.67	Vert(CT)	-0.20	7-8	>923	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.39	Horz(CT)	-0.01	7	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0											
Weight: 106 lb											FT = 20%	

LUMBER

TOP CHORD 2x4 SP No.1 *Except* 1-3:2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3 *Except* 4-7:2x4 SP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 1 Row at midpt 4-7, 3-7

REACTIONS

(size) 7= Mechanical, 9=0-5-8
Max Horiz 9=273 (LC 14)
Max Uplift 7=221 (LC 14)
Max Grav 7=831 (LC 5), 9=754 (LC 5)

FORCES

(lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/27, 2-4=-677/119, 4-5=-12/0,
4-7=-328/122, 2-9=-655/84

BOT CHORD 8-9=-334/218, 7-8=-195/603, 6-7=0/0

WEBS 3-8=0/313, 3-7=-768/250, 2-8=0/486

NOTES

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust)
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat.
II; Exp B; Enclosed; MWFRS (envelope) exterior zone
and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior (1) 2-1-8
to 12-11-8, Exterior(2E) 12-11-8 to 15-11-8 zone;
cantilever left and right exposed; end vertical left
exposed; C-C for members and forces & MWFRS for
reactions shown; Lumber DOL=1.60 plate grip
DOL=1.60
- 2) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15
Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate
DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9;
Cs=1.00; Ct=1.10
- 3) Unbalanced snow loads have been considered for this
design.

- 4) This truss has been designed for greater of min roof live
load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on
overhangs non-concurrent with other live loads.
- 5) This truss has been designed for a 10.0 psf bottom
chord live load nonconcurrent with any other live loads.
- 6) * This truss has been designed for a live load of 20.0psf
on the bottom chord in all areas where a rectangle
3-06-00 tall by 2-00-00 wide will fit between the bottom
chord and any other members, with BCDL = 10.0psf.
- 7) Refer to girder(s) for truss to truss connections.
- 8) Provide mechanical connection (by others) of truss to
bearing plate capable of withstanding 221 lb uplift at joint
7.

LOAD CASE(S) Standard



March 25, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932


Job	Truss	Truss Type	Qty	Ply	920 Serenity-Roof-B326 A CP TRAY GRH	I72213101
25050065	C01	Half Hip	4	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 12:40:02

Page: 1

ID:Je5w06f8goBW?T4xbCQ60Kyfk?K-RfC?PsB70Hq3NSgPqnL8w3uITxbGKWrCDoi7J4zJC?f



Scale = 1:71.5

Plate Offsets (X, Y): [2:0-3-1,0-0-1], [8:0-1-12,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.83	Vert(LL)	-0.08	8-9	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.62	Vert(CT)	-0.14	8-9	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.79	Horz(CT)	0.03	8	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 148 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
WEBS	2x4 SP No.3 *Except* 7-8:2x4 SP No.2
OTHERS	2x6 SP No.2
SLIDER	Left 2x4 SP No.3 -- 1-6-0

BRACING

TOP CHORD	Structural wood sheathing directly applied or 4-8-11 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	1 Row at midpt 7-8, 6-8

REACTIONS

(size)	2=0-5-8, 8=0-5-8
Max Horiz	2=387 (LC 14)
Max Uplift	2=-49 (LC 14), 8=-342 (LC 14)
Max Grav	2=954 (LC 5), 8=1731 (LC 21)

FORCES

(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=0/23, 2-4=-1437/30, 4-6=-824/0, 6-7=-166/102, 7-8=-270/93
BOT CHORD	2-11=-399/1321, 9-11=-320/1321, 8-9=-159/721
WEBS	4-11=0/263, 4-9=-691/185, 6-9=0/637, 6-8=-1026/227


NOTES

- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior (1) 2-1-8 to 17-4-4, Exterior(2E) 17-4-4 to 20-4-4 zone; end vertical left exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10

- Unbalanced snow loads have been considered for this design.
- This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
- All plates are 3x5 MT20 unless otherwise indicated.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 8 and 2. This connection is for uplift only and does not consider lateral forces.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 752 lb down and 128 lb up at 20-7-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard

- Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-7=-60, 8-13=-20
Concentrated Loads (lb)
Vert: 8=-747



March 25, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932


Job	Truss	Truss Type	Qty	Ply	920 Serenity-Roof-B326 A CP TRAY GRH	I72213102
25050065	C02	Half Hip	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 12:40:03

Page: 1

ID:EGq646Pbf2EXC6nWUJzpaijfwU-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:71.3

Plate Offsets (X, Y): [1:0-5-1,Edge], [7:0-1-12,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.82	Vert(LL)	-0.08	7-8	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.63	Vert(CT)	-0.14	7-8	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.75	Horz(CT)	0.03	7	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 146 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
WEBS	2x4 SP No.3 *Except* 6-7:2x4 SP No.2
OTHERS	2x6 SP No.2
SLIDER	Left 2x4 SP No.3 -- 1-6-0

BRACING

TOP CHORD	Structural wood sheathing directly applied or 4-7-1 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	1 Row at midpt 6-7, 5-7

REACTIONS

(size)	1=0-3-8, 7=0-5-8
Max Horiz	1=370 (LC 14)
Max Uplift	1=-30 (LC 14), 7=-342 (LC 14)
Max Grav	1=900 (LC 5), 7=1714 (LC 20)

FORCES

(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-3=-1401/30, 3-5=-812/0, 5-6=-162/100, 6-7=-265/93
BOT CHORD	1-10=-405/1286, 8-10=-319/1286, 7-8=-159/716
WEBS	3-10=0/254, 3-8=-658/185, 5-8=0/624, 5-7=-1018/227

NOTES

- Wind: ASCE 7-16; Vult=130mph (3-second gust)
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-2-0 to 3-2-0, Interior (1) 3-2-0 to 17-4-4, Exterior(2E) 17-4-4 to 20-4-4 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10

- Unbalanced snow loads have been considered for this design.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 7 and 1. This connection is for uplift only and does not consider lateral forces.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 752 lb down and 129 lb up at 20-7-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard

- Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-6=-60, 7-12=-20
Concentrated Loads (lb)
Vert: 7=-747



March 25, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	920 Serenity-Roof-B326 A CP TRAY GRH	172213103
25050065	B02	Common Girder	1	2	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 12:40:02
ID:FFKd9_s5HOVK9vBFwqTAGzRAMn-RfC?PsB70Hq3NSgPqnL8w3uITxbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:75.4

Plate Offsets (X, Y): [1:Edge,0-2-5], [3:0-0-12,0-1-12], [11:0-4-0,0-7-8], [12:0-8-0,0-2-0], [13:0-8-0,0-3-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.29	Vert(LL)	-0.08	12-13	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.34	Vert(CT)	-0.16	12-13	>999	180		
TCDL	10.0	Rep Stress Incr	NO	WB	0.95	Horz(CT)	0.02	9	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 479 lb	FT = 20%

LUMBER

TOP CHORD 2x6 SP No.2
BOT CHORD 2x10 SP 2400F 2.0E
WEBS 2x4 SP No.2
WEDGE Left: 2x4 SP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 4-9-7 oc purlins.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

WEBS 1 Row at midpt 5-9

REACTIONS

(size) 1=0-5-8, 7=0-7-12, 9=0-5-8
Max Horiz 1=-227 (LC 35)
Max Uplift 1=-178 (LC 12), 7=-209 (LC 12), 9=-722 (LC 13)
Max Grav 1=8363 (LC 5), 7=679 (LC 19), 9=11648 (LC 6)

FORCES

(lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-9914/224, 2-3=-7502/211, 3-4=-4644/202, 4-5=-4588/219, 5-6=-66/182, 6-7=-154/503
BOT CHORD 1-13=-246/7510, 12-13=-246/7510, 11-12=-146/5754, 9-11=-24/1717, 8-9=-165/77, 7-8=-316/57
WEBS 2-13=-48/3318, 2-12=-2569/179, 3-12=-149/5505, 3-11=-4474/268, 4-11=-181/5497, 5-11=-101/3899, 5-9=-6639/232, 6-9=-278/313, 6-8=-548/17

NOTES

- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
Bottom chords connected as follows: 2x10 - 2 rows staggered at 0-5-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc, Except member 2-13 2x4 - 2 rows staggered at 0-7-0 oc, member 3-12 2x4 - 1 row at 0-7-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat II; Exp B; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 1 and 7. This connection is for uplift only and does not consider lateral forces.
- LGT2 Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 9. This connection is for uplift only and does not consider lateral forces.
- Use Simpson Strong-Tie HTU26 (20-10d Girder, 14-10dx1 1/2 Truss, Single Ply Girder) or equivalent spaced at 2-0-0 oc max. starting at 2-0-0 from the left end to 15-10-0 to connect truss(es) to back face of bottom chord.
- Use Simpson Strong-Tie LUS26 (4-10d Girder, 3-10d Truss, Single Ply Girder) or equivalent at 17-10-0 from the left end to connect truss(es) to back face of bottom chord.
- Use Simpson Strong-Tie HTU26 (10-16d Girder, 14-10dx1 1/2 Truss) or equivalent spaced at 2-0-0 oc max. starting at 19-10-0 from the left end to 21-10-0 to connect truss(es) to back face of bottom chord.
- Fill all nail holes where hanger is in contact with lumber.
- LGT2 Hurricane ties must have two studs in line below the truss.

LOAD CASE(S) Standard



March 25, 2025

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	920 Serenity-Roof-B326 A CP TRAY GRH
25050065	B02	Common Girder	1	2	I72213103
					Job Reference (optional)

- 1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-4=-60, 4-7=-60, 14-17=-20
Concentrated Loads (lb)
Vert: 10=-1868 (B), 13=-1877 (B), 12=-1877 (B), 8=-839 (B), 21=-1877 (B), 22=-1877 (B), 23=-1877 (B), 24=-1868 (B), 25=-1868 (B), 26=-839 (B), 27=-875 (B)

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)



818 Soundside Road
Edenton, NC 27932


Job	Truss	Truss Type	Qty	Ply	920 Serenity-Roof-B326 A CP TRAY GRH	I72213104
25050065	B01	Common	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 12:40:02

Page: 1

ID:Nseaq6A9EjNfxKX1O6yXnly7LSU-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrcDoi7J4zJC?f



Scale = 1:76.3

Plate Offsets (X, Y): [2:0-7-7,Edge], [24:0-0-0,0-0-10]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.37	Vert(LL)	0.07	18-19	>917	240	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.57	Vert(CT)	-0.16	23-31	>999	180	
TCDL	10.0	Rep Stress Incr	YES	WB	0.51	Horz(CT)	0.02	17	n/a	n/a	
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH							
BCDL	10.0										
Weight: 173 lb FT = 20%											

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
WEBS	2x4 SP No.3 *Except* 17-15:2x6 SP No.2, 6-20:2x4 SP No.2
OTHERS	2x4 SP No.3
SLIDER	Left 2x6 SP No.2 -- 1-6-0

BRACING

TOP CHORD	Structural wood sheathing directly applied or 5-5-4 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
JOINTS	1 Brace at Jt(s): 24, 25, 27

REACTIONS	(size) 2=0-5-8, 17=0-3-8, 21=0-5-8
	Max Horiz 2=265 (LC 13)
	Max Uplift 2=-50 (LC 14), 21=-225 (LC 15)
	Max Grav 2=853 (LC 21), 17=446 (LC 22), 21=753 (LC 22)


FORCES

	(lb) - Maximum Compression/Maximum Tension
TOP CHORD	1-2=0/34, 2-4=-911/79, 4-6=-760/90, 6-7=-332/144, 7-8=-315/186, 8-9=-280/153, 9-11=-301/119, 11-12=-323/75, 12-13=-203/16, 13-14=-293/12, 14-15=-345/1, 15-16=0/42, 15-17=-343/0
BOT CHORD	2-23=-214/696, 21-23=-41/499, 20-21=-11/617, 19-20=-37/231, 18-19=-37/231, 17-18=-37/231
WEBS	4-23=-237/181, 21-28=-541/345, 6-26=-463/113, 25-26=-468/121, 24-25=-413/70, 24-27=-407/54, 27-28=-419/70, 20-28=-471/86, 23-24=-69/89, 6-23=0/345, 8-25=-128/164, 7-26=-31/42, 9-24=-184/31, 11-27=-81/63, 12-28=-382/221, 13-19=-20/49, 14-18=-65/82

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior (1) 2-1-8 to 8-7-0, Exterior(2R) 8-7-0 to 14-7-0, Interior (1) 14-7-0 to 21-0-8, Exterior(2E) 21-0-8 to 24-0-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with any other live loads.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 2 and 21. This connection is for uplift only and does not consider lateral forces.

LOAD CASE(S) Standard



March 25, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932


Job	Truss	Truss Type	Qty	Ply	920 Serenity-Roof-B326 A CP TRAY GRH	I72213105
25050065	A05	Attic Girder	1	4	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 12:39:58

Page: 1

ID:VIY0g5MuQwQZRxixBYltzRA_fRfC?PsB70Hq3NSgPqnL8w3uITXbGKwRcDoi7J4zJC?f



loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.90	Vert(LL)	-0.50	38-41	>786	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.97	Vert(CT)	-0.75	37-39	>521	180	MT20HS	187/143
TCDL	10.0	Rep Stress Incr	Yes	WB	0.90	Horz(CT)	0.19	17	n/a	n/a	MT18HS	244/190
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH		Attic	-0.25	22-40	>786	360		
BCDL	10.0											
											Weight: 2038 lb	FT = 20%

Weight: 2038 lb FT = 20%

LUMBER		BOT CHORD	44-45=-135/447, 42-44=-746/12300, 41-42=-859/16424, 35-41=-691/17026, 33-35=0/18312, 30-33=0/18937, 27-30=0/18075, 24-27=-276/15568, 21-24=-796/12213, 19-21=-801/16246, 18-19=-744/15345, 17-18=-116/2119, 39-40=-463/400, 37-39=-484/352, 36-37=-2838/0, 34-36=-2838/0, 32-34=-3460/0, 31-32=-3460/0, 29-31=-3460/0, 26-29=-2304/11, 23-26=-334/2811, 22-23=-334/2811		
TOP CHORD	2x6 SP No.2 *Except* 5-7:2x4 SP No.1				
BOT CHORD	2x4 SP No.1 *Except* 43-38,43-45:2x6 SP No.2, 28-22:2x4 SP No.2, 20-25:2x4 SP 2400F 2.0E				
WEBS	2x4 SP No.3 *Except* 13-21:2x6 SP 2400F 2.0E, 6-46,45-2,41-47,41-6,46-13:2x6 SP No.2, 44-2,17-16,18-16:2x4 SP No.2				
OTHERS	2x4 SP No.3				
BRACING		WEBS	3-44=-5379/378, 3-42=-243/5005, 4-42=-738/165, 5-41=-143/1775, 21-22=-702/6462, 13-22=-533/7444, 6-48=-11396/734, 48-49=-10999/710, 49-50=-11217/674, 50-51=-11256/676, 51-52=-16199/977, 52-53=-12725/800, 13-53=-13377/838, 2-44=-694/13017, 40-41=-669/7654, 6-40=-544/8799, 7-48=-152/2425, 8-49=-517/66, 9-50=-135/2511, 10-51=-208/56, 11-52=-259/67, 12-53=-210/3528, 22-24=0/2232, 38-40=0/2717, 23-24=-618/0, 38-39=-599/0, 24-26=-2199/0, 37-38=-951/52, 26-27=0/2939, 35-37=0/1803, 27-28=-844/13, 35-36=-959/22, 27-29=-306/163, 34-35=-126/263, 29-30=0/1059, 33-34=-8/744, 30-31=-512/0, 32-33=-320/10, 7-49=-4545/252, 9-49=-4572/360, 9-51=-5105/312, 10-52=-2495/281, 12-52=-5632/326, 14-19=-486/150, 15-19=-142/1131, 14-21=-406/499, 5-42=-2504/138, 15-18=-968/147, 16-18=-656/13277		
TOP CHORD	Structural wood sheathing directly applied or 2-2-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 7-12.				
BOT CHORD	Rigid ceiling directly applied or 2-2-0 oc bracing.				
JOINTS	1 Brace at Jt(s): 49, 50, 51, 52, 40, 26, 37, 29, 34				
REACTIONS	(size) 17=0-5-8, 21=0-3-8, 45=0-5-8 Max Horiz 45=-192 (LC 10) Max Uplift 17=-453 (LC 12), 21=-5416 (LC 45), 45=-702 (LC 12) Max Grav 17=9309 (LC 46), 21=791 (LC 12), 45=11962 (LC 46)				
FORCES	(lb) - Maximum Compression/Maximum Tension				
TOP CHORD	1-2=0/24, 2-3=-13751/804, 3-4=-17677/1059, 4-6=-18994/1151, 6-7=-5812/482, 7-8=-3051/527, 8-9=-3048/525, 9-10=-3645/710, 10-11=-1646/1592, 11-12=-1646/1592, 12-13=-4646/432, 13-15=-18211/1130, 15-16=-17291/899, 2-45=-11768/721, 16-17=-9139/483				


1) 4-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc, 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc, 2x4 - 1 row at 0-7-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc, 2x6 - 2 rows staggered at 0-9-0 oc, Except member 41-47 2x6 - 3 rows staggered at 0-4-0 oc, member 6-41 2x6 - 2 rows staggered at 0-4-0 oc.
Attach BC w/ 1/2" diam. bolts (ASTM A-307) in the center of the member w/ washers at 4-0-0 oc.

2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.

3) Unbalanced roof live loads have been considered for this design.

NOTES

- 4-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc, 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc, 2x4 - 1 row at 0-7-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc, 2x6 - 2 rows staggered at 0-9-0 oc, Except member 41-47 2x6 - 3 rows staggered at 0-4-0 oc, member 6-41 2x6 - 2 rows staggered at 0-4-0 oc.
Attach BC w/ 1/2" diam. bolts (ASTM A-307) in the center of the member w/washers at 4-0-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Unbalanced roof live loads have been considered for this design.



March 25, 2025

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinet.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	920 Serenity-Roof-B326 A CP TRAY GRH
25050065	A05	Attic Girder	1	4	I72213105
					Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 12:39:58

Page: 2

ID:VIY0g5gMUGwQZRyxiBXYltzRA_fRfC?PsB70Hq3NSgPqnL8w3uITXbGKWrcDoi7J4zJC?f

- 4) Wind: ASCE 7-16; Vult=130mph (3-second gust)
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat.
II; Exp B; Enclosed; MWFRS (envelope) exterior zone;
cantilever left and right exposed ; end vertical left and
right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 5) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15
Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate
DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9;
Cs=1.00; Ct=1.10
- 6) Unbalanced snow loads have been considered for this
design.
- 7) This truss has been designed for greater of min roof live
load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on
overhangs non-concurrent with other live loads.
- 8) Provide adequate drainage to prevent water ponding.
- 9) All plates are MT20 plates unless otherwise indicated.
- 10) All plates are 2x4 MT20 unless otherwise indicated.
- 11) This truss has been designed for a 10.0 psf bottom
chord live load nonconcurrent with any other live loads.
- 12) * This truss has been designed for a live load of 20.0psf
on the bottom chord in all areas where a rectangle
3-06-00 tall by 2-00-00 wide will fit between the bottom
chord and any other members, with BCDL = 10.0psf.
- 13) Ceiling dead load (5.0 psf) on member(s). 6-48, 48-49,
49-50, 50-51, 51-52, 52-53, 13-53; Wall dead load
(5.0psf) on member(s).13-22, 6-40
- 14) Bottom chord live load (40.0 psf) and additional bottom
chord dead load (5.0 psf) applied only to room. 39-40,
37-39, 36-37, 34-36, 32-34, 31-32, 29-31, 28-29, 26-28,
23-26, 22-23
- 15) Bearings are assumed to be: , Joint 17 SP No.1 .
- 16) Provide mechanical connection (by others) of truss to
bearing plate capable of withstanding 5416 lb uplift at
joint 21.
- 17) LGT4-SDS3 Simpson Strong-Tie connectors
recommended to connect truss to bearing walls due to
UPLIFT at jt(s) 45. This connection is for uplift only and
does not consider lateral forces.
- 18) One H2.5A Simpson Strong-Tie connectors
recommended to connect truss to bearing walls due to
UPLIFT at jt(s) 17. This connection is for uplift only and
does not consider lateral forces.
- 19) Graphical purlin representation does not depict the size
or the orientation of the purlin along the top and/or
bottom chord.
- 20) This truss has large uplift reaction(s) from gravity load
case(s). Proper connection is required to secure truss
against upward movement at the bearings. Building
designer must provide for uplift reactions indicated.
- 21) LGT4 Hurricane ties must have four studs in line below
the truss.
- 22) Hanger(s) or other connection device(s) shall be
provided sufficient to support concentrated load(s) 608
lb down and 52 lb up at 28-8-4, and 9100 lb down and
774 lb up at 16-1-4 on bottom chord. The design/
selection of such connection device(s) is the
responsibility of others.
- 23) Attic room checked for L/360 deflection.

LOAD CASE(S) Standard

- 1) Dead + Snow (balanced): Lumber Increase=1.15, Plate
Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-2=-60, 2-7=-60, 7-12=-60, 12-16=-60,
17-45=-20, 22-40=-30, 6-48=-10, 48-49=-10,
46-49=-10, 46-50=-10, 50-51=-10, 51-52=-10,
52-53=-10, 13-53=-10
Drag: 13-22=-10, 40-47=-10, 6-47=-10
Concentrated Loads (lb)
Vert: 41=-4881 (F), 63=-326 (F)


WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 12:39:57 Page: 1
ID:OFJF x3IDT xFbWWzrBXohbzzRCTM-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



LUMBER		BOT CHORD	25-26=20/37, 24-25=0/25, 3-24=1152/125, 23-24=254/1996, 22-23=216/2976, 21-22=22/81, 5-22=489/170, 20-21=56/218, 19-20=5/2486, 17-19=5/2486, 16-17=0/2353, 14-16=39/2994, 13-14=85/3518	5) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
TOP CHORD	2x6 SP No.2			6) 200.0lb AC unit load placed on the bottom chord, 24-7-0 from left end, supported at two points, 5-0-0 apart.
BOT CHORD	2x6 SP No.2 *Except* 25-3,5-21:2x4 SP No.3, 18-15:2x6 SP 2400F 2.0E			7) Provide adequate drainage to prevent water ponding.
WEBS	2x4 SP No.3 *Except* 22-6,20-6,7-20,17-10,10-15,9-17:2x4 SP No.2, 26-2:2x6 SP No.2	WEBS	4-22=192/133, 20-22=0/2236, 6-22=269/1125, 6-20=100/524, 20-27=541/210, 27-30=520/215, 7-30=507/212, 10-17=91/900, 10-15=194/937, 11-15=918/319, 11-14=220/819, 12-14=331/236, 17-28=857/228, 28-31=838/236, 9-31=819/232, 4-23=294/78, 3-23=2/1077, 24-26=110/202, 2-24=192/2298, 27-29=71/37, 28-29=71/37, 19-29=0/48, 30-32=21/40, 31-32=122/27, 8-32=252/89, 7-32=298/701, 9-32=285/802	8) All plates are 2x4 MT20 unless otherwise indicated.
BRACING				9) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
TOP CHORD	Structural wood sheathing directly applied or 3-4-2 oc purlins, except end verticals, and 2-0-0 oc purlins (3-10-0 max.): 6-10.			10) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing. Except:			11) Refer to girder(s) for truss to truss connections.
1 Row at midpt	5-22			12) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 25 lb uplift at joint 13.
WEBS	1 Row at midpt 6-20, 20-30, 10-17, 17-31, 27-28			13) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 26 and 16. This connection is for uplift only and does not consider lateral forces.
JOINTS	1 Brace at Jt(s): 30, 31, 32			
REACTIONS	(size) 13= Mechanical, 16=0-3-8, 26=0-5-8	NOTES		
	Max Horiz 26=-187 (LC 12)	1) Unbalanced roof live loads have been considered for this design.		
	Max Uplift 13=-25 (LC 14), 16=-196 (LC 15), 26=-168 (LC 14)	2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TC DL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-8-6 to 4-7-9, Interior (1) 4-7-9 to 10-1-10, Exterior(2R) 10-1-10 to 39-2-5, Interior (1) 39-2-5 to 47-11-2, Exterior(2E) 47-11-2 to 53-3-0 zone; end vertical left exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60		
	Max Grav 13=2019 (LC 47), 16=915 (LC 39), 26=2271 (LC 37)	3) T CLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); h=1.0; Rough Cat B; Fully Exposed; Co. 0.0		
FORCES	(lb) - Maximum Compression/Maximum Tension			
TOP CHORD	1-2=0/25, 2-3=-2253/192, 3-4=-3433/248, 4-6=-3373/359, 6-7=-2575/221, 7-8=-3092/426, 8-9=-3092/426, 9-10=-2560/220, 10-12=-4030/301, 12-13=-4071/191, 2-26=-2398/217			

- ## NOTES
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-16; Vult=130mph (3-second gust)
 Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-8-6 to 4-7-9, Interior (1) 4-7-9 to 10-1-10, Exterior(2R) 10-1-10 to 39-2-5, Interior (1) 39-2-5 to 47-11-2, Exterior(2E) 47-11-2 to 53-3-0 zone; end vertical left exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 3) TCLK: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
 - 4) Unbalanced snow loads have been considered for this design.



March 25, 2025

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinet.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbccomponents.com)



818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	920 Serenity-Roof-B326 A CP TRAY GRH
25050065	A03T	Piggyback Base	3	1	I72213106
					Job Reference (optional)

14) Graphical purlin representation does not depict the size
or the orientation of the purlin along the top and/or
bottom chord.

LOAD CASE(S) Standard


 **WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)



818 Soundside Road
Edenton, NC 27932

Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 12:39:58 Page: 1
ID:DGN6a6f8caCKWpHw1clz1BzRCZx-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCD0i7J4zJC?f




LUMBER		BOT CHORD	24-25=20/36, 23-24=0/26, 3-23=-1130/127, 22-23=-240/1962, 21-22=-193/2917, 20-21=-267/102, 5-21=-487/169, 19-20=-59/232, 18-19=0/2417, 16-18=0/2417, 14-16=-90/2202, 13-14=-333/1271	5) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
TOP CHORD	2x6 SP No.2			6) 200.0lb AC unit load placed on the bottom chord, 24-7-0 from left end, supported at two points, 5-0-0 apart.
BOT CHORD	2x6 SP No.2 *Except* 24-3,5-20:2x4 SP No.3			7) Provide adequate drainage to prevent water ponding.
WEBS	2x4 SP No.3 *Except* 21-6,19-6,9-16,16-10,15-10,19-7:2x4 SP No.2, 25-2:2x6 SP No.2	WEBS	4-21=-211/137, 19-21=0/2155, 6-21=-271/1137, 6-19=-292/537, 16-27=-832/233, 27-30=-821/241, 9-30=-804/238, 10-16=-21/1309, 11-15=0/612, 11-14=-2325/258, 12-14=-458/257, 10-15=-366/8, 19-26=-494/262, 26-29=-478/269, 7-29=-467/266, 4-22=-275/80, 3-22=-5/1051, 23-25=-110/203, 2-23=-176/2258, 26-28=-67/38, 27-28=-67/38, 18-28=0/35, 29-31=-44/87, 30-31=-151/38, 7-31=-299/750, 8-31=-305/98, 9-31=-274/850	8) All plates are 2x4 MT20 unless otherwise indicated.
BRACING				9) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
TOP CHORD	Structural wood sheathing directly applied or 3-11-11 oc purlins, except end verticals, and 2-0-0 oc purlins (3-10-10 max.): 6-10.			10) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
BOT CHORD	Rigid ceiling directly applied or 2-2-0 oc bracing. Except:			11) Refer to girder(s) for truss to truss connections.
1 Row at midpt	5-21			12) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 198 lb uplift at joint 13.
WEBS	1 Row at midpt 6-19, 16-30, 10-15, 19-29, 26-27			13) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 14 and 25. This connection is for uplift only and does not consider lateral forces.
WEBS	2 Rows at 1/3 pts 11-14			
JOINTS	1 Brace at Jt(s): 29, 30, 31			
REACTIONS	(size) 13= Mechanical, 14=0-5-8, 25=0-5-8 25=127/10 C 12)	NOTES		
		1) Unbalanced roof live loads have been considered for this design		

March 25, 2025

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiteTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI 1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Components Association (www.sbcacompnents.com)



818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	920 Serenity-Roof-B326 A CP TRAY GRH
25050065	A04T	Piggyback Base	2	1	I72213107
Job Reference (optional)					

14) Graphical purlin representation does not depict the size
or the orientation of the purlin along the top and/or
bottom chord.

LOAD CASE(S) Standard

 **WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)



818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	920 Serenity-Roof-B326 A CP TRAY GRH	172213108
25050065	A06	Attic Girder	1	4	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 12:39:59

Page: 1

ID: pGeZvt1?lwrujNEy_xH4fkzRAp7-RfC?PsB70Hq3NSgPqnL8w3uTXbGKwRCDoi7J4zJC?i




Plate Offsets (X, Y): [7:0-8-0,0-3-4], [9:0-8-0,0-2-4], [12:0-10-8,0-2-12], [18:Edge,0-2-4], [23:0-3-8,0-2-8], [28:0-3-0,0-3-0], [39:0-4-12,Edge], [42:0-8-0,0-4-12], [45:0-3-8,0-3-0]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.93	Vert(LL)	-0.49	39-42	>803	240	MT20HS	187/143
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.72	Vert(CT)	-0.73	39-42	>532	180	MT20	244/190
TCDL	10.0	Rep Stress Incr	NO	WB	0.87	Horz(CT)	0.21	18	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH		Attic	-0.24	23-41	>812	360		
BCDL	10.0											
Weight: 2017 lb											FT = 20%	

LUMBER
TOP CHORD 2x6 SP No.2 *Except* 7-5:2x4 SP 2400F 2.0E
BOT CHORD 2x4 SP 2400F 2.0E *Except* 28-23,28-41:2x4 SP No.2, 44-46:2x6 SP No.2, 44-39:2x6 SP 2400F 2.0E
WEBS 2x4 SP No.3 *Except* 46-2,42-47,6-42,6-51,51-13:2x6 SP No.2, 13-22:2x6 SP 2400F 2.0E, 45-2:2x4 SP No.2
OTHERS 2x4 SP No.3
SLIDER Right 2x4 SP No.3 -- 1-6-0

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 7-12.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
JOINTS 1 Brace at Jt(s): 50, 51, 52, 53, 41, 38, 35, 30, 26


REACTIONS (size) 18= Mechanical, 22=0-5-8, 46=0-5-8
Max Horiz 46=190 (LC 10)
Max Uplift 18=420 (LC 12), 22=-5361 (LC 45), 46=683 (LC 12)
Max Grav 18=8887 (LC 46), 22=792 (LC 12), 46=11746 (LC 46)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 7-8=-3092/528, 8-9=-3089/526, 9-10=-3727/713, 10-11=-1715/1441, 11-12=-1715/1441, 12-13=-4561/424, 13-15=-17753/1087, 15-16=-17925/1006, 16-18=-17697/900, 2-46=-11550/702, 1-2=0/24, 2-3=-13497/782, 3-4=-17366/1032, 4-6=-18564/1120, 6-7=-5994/479

BOT CHORD 45-46=-123/440, 43-45=-731/12074, 42-43=-832/16073, 36-42=-684/17253, 34-36=0/17880, 31-34=0/17942, 29-31=0/16739, 25-29=-151/14334, 22-25=-772/12128, 20-22=-780/16089, 19-20=-741/15543, 18-19=-741/15543, 40-41=-1028/0, 38-40=-1102/0, 37-38=-2921/0, 35-37=-2921/0, 33-35=-3019/0, 32-33=-3019/0, 30-32=-3019/0, 26-30=-1178/736, 24-26=-370/3083, 23-24=-370/3083
WEBS 3-45=-5311/373, 4-43=-700/162, 41-42=-617/7143, 6-41=-530/8717, 22-23=-712/6595, 13-23=-513/7229, 6-48=-10655/685, 48-50=-10276/663, 50-52=-11090/661, 52-53=-15532/928, 49-53=-12360/771, 13-49=-12997/808, 2-45=-673/12777, 15-20=-220/184, 16-19=-11/162, 16-20=-132/757, 15-22=-640/213, 3-43=-237/4930, 7-48=-147/2364, 12-49=-204/3451, 8-50=-471/64, 9-51=-120/2271, 10-52=-109/92, 11-53=-268/67, 12-53=-5376/307, 10-53=-2531/278, 9-52=-4653/281, 9-50=-4233/347, 7-50=-4773/262, 39-40=-446/0, 39-41=0/2886, 38-39=-859/135, 36-38=0/1265, 36-37=-671/19, 35-36=-160/340, 34-35=-22/133, 33-34=-116/0, 31-32=-558/0, 30-31=0/1422, 29-30=-818/0, 28-29=-736/19, 26-29=0/2289, 25-26=-1725/0, 24-25=-569/0, 23-25=0/1636, 5-42=-124/1475, 5-43=-2258/111

NOTES

- 4-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc, 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc, 2x4 - 1 row at 0-9-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc, 2x6 - 3 rows staggered at 0-4-0 oc, Except member 6-42 2x6 - 2 rows staggered at 0-4-0 oc, member 13-22 2x6 - 2 rows staggered at 0-9-0 oc.
Attach BC w/ 1/2" diam. bolts (ASTM A-307) in the center of the member w/washers at 4-0-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Unbalanced roof live loads have been considered for this design.



March 25, 2025

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinet.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	920 Serenity-Roof-B326 A CP TRAY GRH
25050065	A06	Attic Girder	1	4	I72213108
Job Reference (optional)					

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 12:39:59
ID:pGeZvt1?lwruINEY_xH4fkzRAp7-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?i

Page: 2

- 4) Wind: ASCE 7-16; Vult=130mph (3-second gust)
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat.
II; Exp B; Enclosed; MWFRS (envelope) exterior zone;
cantilever left and right exposed ; end vertical left and
right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 5) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15
Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate
DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9;
Cs=1.00; Ct=1.10
- 6) Unbalanced snow loads have been considered for this
design.
- 7) This truss has been designed for greater of min roof live
load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on
overhangs non-concurrent with other live loads.
- 8) Provide adequate drainage to prevent water ponding.
- 9) All plates are MT20 plates unless otherwise indicated.
- 10) All plates are 2x4 MT20 unless otherwise indicated.
- 11) This truss has been designed for a 10.0 psf bottom
chord live load nonconcurrent with any other live loads.
- 12) * This truss has been designed for a live load of 20.0psf
on the bottom chord in all areas where a rectangle
3-06-00 tall by 2-00-00 wide will fit between the bottom
chord and any other members, with BCDL = 10.0psf.
- 13) Ceiling dead load (5.0 psf) on member(s). 6-48, 48-50,
50-51, 51-52, 52-53, 49-53, 13-49; Wall dead load
(5.0psf) on member(s).6-41, 13-23
- 14) Bottom chord live load (40.0 psf) and additional bottom
chord dead load (5.0 psf) applied only to room. 40-41,
38-40, 37-38, 35-37, 33-35, 32-33, 30-32, 28-30, 26-28,
24-26, 23-24
- 15) Refer to girder(s) for truss to truss connections.
- 16) Provide mechanical connection (by others) of truss to
bearing plate capable of withstanding 420 lb uplift at joint
18 and 5361 lb uplift at joint 22.
- 17) LGT4-SDS3 Simpson Strong-Tie connectors
recommended to connect truss to bearing walls due to
UPLIFT at jt(s) 46. This connection is for uplift only and
does not consider lateral forces.
- 18) Graphical purlin representation does not depict the size
or the orientation of the purlin along the top and/or
bottom chord.
- 19) This truss has large uplift reaction(s) from gravity load
case(s). Proper connection is required to secure truss
against upward movement at the bearings. Building
designer must provide for uplift reactions indicated.
- 20) LGT4 Hurricane ties must have four studs in line below
the truss.
- 21) Hanger(s) or other connection device(s) shall be
provided sufficient to support concentrated load(s) 9100
lb down and 774 lb up at 16-1-4 on bottom chord. The
design/selection of such connection device(s) is the
responsibility of others.
- 22) Attic room checked for L/360 deflection.

LOAD CASE(S) Standard

- 1) Dead + Snow (balanced): Lumber Increase=1.15, Plate
Increase=1.15
Uniform Loads (lb/ft)
Vert: 7-12=-60, 12-18=-60, 46-54=-20, 23-41=-30,
6-48=-10, 48-50=-10, 50-51=-10, 51-52=-10,
52-53=-10, 49-53=-10, 13-49=-10, 1-2=-60, 2-7=-60
Drag: 41-47=-10, 6-47=-10, 13-23=-10
Concentrated Loads (lb)
Vert: 42=-4881 (F)

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932


Job	Truss	Truss Type	Qty	Ply	920 Serenity-Roof-B326 A CP TRAY GRH	I72213109
25050065	A09	Attic Supported Gable	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 E Dec 5 2024 Print: 8.730 E Dec 5 2024 MiTek Industries, Inc. Tue Mar 25 14:36:20

Page: 1

ID:8kdnaNvfrYx7X5iJovJ26tzRBB2-xz0AgCsPvWBIINs3yJuM8e_ky7L0HHBaaScLJCzXXE9




Scale = 1:90.9
Plate Offsets (X, Y): [7:0-2-6,Edge], [11:0-5-13,0-3-6], [16:0-6-0,0-3-8], [40:Edge,0-2-4], [46:0-3-0,0-3-0], [58:Edge,0-2-4], [72:0-2-8,0-2-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.44	Vert(LL)	-0.01	10	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.11	Vert(CT)	-0.01	10	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.65	Horz(CT)	0.02	28	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 504 lb	FT = 20%

LUMBER		Max Uplift		TOP CHORD	
TOP CHORD	2x6 SP No.2	28=-48 (LC 14), 29=-99 (LC 15),		1-68=-88/57, 1-2=-63/38, 2-3=-55/112,	
BOT CHORD	2x4 SP No.2	30=-29 (LC 15), 31=-47 (LC 15),		3-78=-65/168, 4-78=-58/174, 4-79=-81/212,	
WEBS	2x4 SP No.3 *Except* 10-59,17-39:2x6 SP No.2, 72-17,72-10:2x4 SP No.2	32=-41 (LC 15), 33=-44 (LC 15),		5-79=-72/222, 5-80=-100/260, 6-80=-94/267,	
OTHERS	2x4 SP No.3	34=-44 (LC 15), 35=-45 (LC 15),		6-7=-120/303, 7-8=-119/313, 8-9=-135/359,	
BRACING		Max Grav			
TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (4-1-8 max.): 11-16.	28=160 (LC 27), 29=237 (LC 43),		9-10=-115/375, 10-11=-903/328,	
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 48-51.	30=147 (LC 22), 31=165 (LC 39),		11-12=-2147/593, 12-13=-2147/593,	
WEBS	1 Row at midpt 10-58, 17-40, 18-38, 19-37, 9-60, 8-62	32=149 (LC 22), 33=172 (LC 43),		13-81=-2804/764, 14-81=-2804/764,	
JOINTS	1 Brace at Jt(s): 71, 72, 73, 74, 55, 52, 47, 44	34=219 (LC 43), 35=235 (LC 43),		14-15=-2132/593, 15-16=-2132/593,	
REACTIONS (lb/size)					
28=123/53-6-0, 29=235/53-6-0,		37=208 (LC 43), 38=113 (LC 49),		16-17=-894/327, 17-18=-121/375,	
30=147/53-6-0, 31=165/53-6-0,		39=1110 (LC 38), 42=333 (LC 20),		18-19=-143/366, 19-20=-131/322,	
32=149/53-6-0, 33=161/53-6-0,		45=369 (LC 20), 48=319 (LC 20),		20-21=-105/275, 21-82=-106/270,	
34=160/53-6-0, 35=169/53-6-0,		51=319 (LC 20), 53=368 (LC 20),		22-82=-111/265, 22-83=-88/230,	
37=126/53-6-0, 38=22/53-6-0,		56=330 (LC 20), 59=1119 (LC 38),		23-83=-94/224, 23-24=-102/205,	
39=916/53-6-0, 42=156/53-6-0,		60=123 (LC 47), 62=222 (LC 41),		24-25=-122/182, 25-84=-141/160,	
45=138/53-6-0, 48=121/53-6-0,		63=242 (LC 41), 64=231 (LC 41),		26-84=-147/150, 26-27=-170/134,	
51=121/53-6-0, 53=135/53-6-0,		65=181 (LC 41), 66=165 (LC 21),		27-28=-220/127	
56=149/53-6-0, 59=930/53-6-0,		67=164 (LC 41), 68=122 (LC 21)			
60=13/53-6-0, 62=142/53-6-0,					
63=170/53-6-0, 64=160/53-6-0,					
65=157/53-6-0, 66=163/53-6-0,					
67=152/53-6-0, 68=115/53-6-0					
Max Horiz 68=-221 (LC 15)					

FORCES

(lb) - Maximum Compression/Maximum Tension



March 25, 2025

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	920 Serenity-Roof-B326 A CP TRAY GRH I72213109
25050065	A09	Attic Supported Gable	1	1	Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 E Dec 5 2024 Print: 8.730 E Dec 5 2024 MiTek Industries, Inc. Tue Mar 25 14:36:20

Page: 2

ID:8kdnaNVfrXy7X5iJovJ26tzRBB2-xz0AgCsPvWBIInS3yJuM8e_ky7L0HHBaaScLJCzXXE9

BOT CHORD	67-68=-96/212, 66-67=-96/212, 65-66=-96/212, 64-65=-96/212, 63-64=-96/212, 62-63=-96/212, 61-62=-96/212, 60-61=-96/212, 59-60=-96/212, 56-59=-104/213, 53-56=-52/140, 51-53=-32/126, 48-51=-56/104, 45-48=-32/125, 43-45=-48/139, 42-43=-48/139, 39-42=-82/200, 38-39=-87/212, 37-38=-87/212, 36-37=-87/212, 35-36=-87/212, 34-35=-87/212, 33-34=-87/212, 32-33=-87/212, 31-32=-87/212, 30-31=-87/212, 29-30=-87/212, 28-29=-87/212, 57-58=-11/91, 55-57=-11/91, 54-55=-30/114, 52-54=-30/114, 50-52=-39/108, 49-50=-39/108, 47-49=-39/108, 46-47=-31/112, 44-46=-30/115, 41-44=-11/84, 40-41=-11/84	12) Bottom chord live load (40.0 psf) and additional bottom chord dead load (5.0 psf) applied only to room. 57-58, 55-57, 54-55, 52-54, 50-52, 49-50, 47-49, 46-47, 44-46, 41-44, 40-41 13) Bearings are assumed to be: , Joint 28 User Defined crushing capacity of 425 psi. 14) N/A
	56-59=-104/213, 53-56=-52/140, 51-53=-32/126, 48-51=-56/104, 45-48=-32/125, 43-45=-48/139, 42-43=-48/139, 39-42=-82/200, 38-39=-87/212, 37-38=-87/212, 36-37=-87/212, 35-36=-87/212, 34-35=-87/212, 33-34=-87/212, 32-33=-87/212, 31-32=-87/212, 30-31=-87/212, 29-30=-87/212, 28-29=-87/212, 57-58=-11/91, 55-57=-11/91, 54-55=-30/114, 52-54=-30/114, 50-52=-39/108, 49-50=-39/108, 47-49=-39/108, 46-47=-31/112, 44-46=-30/115, 41-44=-11/84, 40-41=-11/84	15) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord. 16) Attic room checked for L/360 deflection.
WEBS	56-59=-104/213, 53-56=-52/140, 51-53=-32/126, 48-51=-56/104, 45-48=-32/125, 43-45=-48/139, 42-43=-48/139, 39-42=-82/200, 38-39=-87/212, 37-38=-87/212, 36-37=-87/212, 35-36=-87/212, 34-35=-87/212, 33-34=-87/212, 32-33=-87/212, 31-32=-87/212, 30-31=-87/212, 29-30=-87/212, 28-29=-87/212, 57-58=-11/91, 55-57=-11/91, 54-55=-30/114, 52-54=-30/114, 50-52=-39/108, 49-50=-39/108, 47-49=-39/108, 46-47=-31/112, 44-46=-30/115, 41-44=-11/84, 40-41=-11/84	LOAD CASE(S) Standard

NOTES

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TC DL=6.0psf; BC DL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Corner(3E) 0-1-12 to 5-5-15, Exterior(2N) 5-5-15 to 12-3-13, Corner(3R) 12-3-13 to 23-3-2, Exterior(2N) 23-3-2 to 25-10-14, Corner(3R) 25-10-14 to 36-10-3, Exterior(2N) 36-10-3 to 48-1-13, Corner(3E) 48-1-13 to 53-6-0 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 4) T CLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- 5) Unbalanced snow loads have been considered for this design.
- 6) Provide adequate drainage to prevent water ponding.
- 7) All plates are 2x4 MT20 unless otherwise indicated.
- 8) Gable studs spaced at 2-0-0 oc.
- 9) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 10) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- 11) Ceiling dead load (5.0 psf) on member(s). 10-69, 69-71, 71-72, 72-74, 73-74, 70-73, 17-70; Wall dead load (5.0psf) on member(s).10-58, 17-40


 **WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932

Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 12:40:01 Page: 1



March 25, 2025

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with Mitek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Components Association (www.sbcacomponents.com)



818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	920 Serenity-Roof-B326 A CP TRAY GRH
25050065	A08	Attic	6	1	I72213110
					Job Reference (optional)

- 8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 9) Ceiling dead load (5.0 psf) on member(s). 4-43, 42-43, 42-44, 44-45, 45-46, 46-47, 11-47; Wall dead load (5.0psf) on member(s).4-37, 11-20
- 10) Bottom chord live load (40.0 psf) and additional bottom chord dead load (5.0 psf) applied only to room. 36-37, 34-36, 33-34, 31-33, 29-31, 28-29, 26-28, 25-26, 23-25, 21-23, 20-21
- 11) Refer to girder(s) for truss to truss connections.
- 12) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- 13) Attic room checked for L/360 deflection.

LOAD CASE(S) Standard


⚠ WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)



818 Soundside Road
Edenton, NC 27932


Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 12:40:00 Page: 1



Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI 1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Components Association (www.sbcacomponents.com)



ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	920 Serenity-Roof-B326 A CP TRAY GRH
25050065	A07	Attic	1	1	I72213111
Job Reference (optional)					

- 7) All plates are MT20 plates unless otherwise indicated.
- 8) All plates are 2x4 MT20 unless otherwise indicated.
- 9) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 10) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 11) Ceiling dead load (5.0 psf) on member(s). 5-44, 43-44, 43-45, 45-46, 46-47, 47-48, 12-48; Wall dead load (5.0psf) on member(s).5-38, 12-21
- 12) Bottom chord live load (40.0 psf) and additional bottom chord dead load (5.0 psf) applied only to room. 37-38, 35-37, 34-35, 32-34, 30-32, 29-30, 27-29, 26-27, 24-26, 22-24, 21-22
- 13) Refer to girder(s) for truss to truss connections.
- 14) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- 15) Attic room checked for L/360 deflection.

LOAD CASE(S) Standard


 **WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)




818 Soundside Road
Edenton, NC 27932


Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 12:39:56 Page: 1
ID:HyYYHe4LpHmiz2Dld9nw5tZrQov-RfC?PsB70Hg3NSqPnL8w3uITxbGKWRCDoi7J4zJC?i



REACTIONS (size)	33=53-3-0, 34=53-3-0, 35=53-3-0, 36=53-3-0, 37=53-3-0, 38=53-3-0, 39=53-3-0, 40=53-3-0, 42=53-3-0, 43=53-3-0, 44=53-3-0, 46=53-3-0, 47=53-3-0, 48=53-3-0, 49=53-3-0, 50=53-3-0, 51=53-3-0, 52=53-3-0, 53=53-3-0, 55=53-3-0, 56=53-3-0, 57=53-3-0, 58=53-3-0, 59=53-3-0, 60=53-3-0, 61=53-3-0, 62=53-3-0	6-7=-75/201, 7-8=-90/246, 8-9=-106/291, 9-11=-124/338, 11-12=-144/387, 12-13=-146/383, 13-14=-140/380, 14-15=-140/380, 15-16=-140/380, 16-17=-140/380, 17-18=-140/380, 18-19=-140/380, 19-20=-140/380, 20-21=-140/380, 21-22=-146/383, 22-23=-144/387, 23-24=-124/338, 24-25=-106/291, 25-27=-90/246, 27-28=-75/201, 28-29=-59/160, 29-30=-63/137, 30-31=-71/112, 31-32=-124/100, 32-33=-134/117
	Max Horiz 62=-186 (LC 12)	
Max Uplift	34=-66 (LC 14), 35=-170 (LC 15), 36=-15 (LC 14), 37=-50 (LC 15), 38=-42 (LC 15), 39=-44 (LC 15), 40=-43 (LC 15), 42=-46 (LC 15), 43=-52 (LC 15), 47=-29 (LC 11), 48=-28 (LC 11), 49=-25 (LC 10), 50=-28 (LC 11), 51=-29 (LC 10), 55=-52 (LC 14), 56=-46 (LC 14), 57=-43 (LC 14), 58=-44 (LC 14), 59=-46 (LC 14), 60=-22 (LC 14), 61=-137 (LC 14), 62=-88 (LC 15)	



Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Components Association (www.sbcacomponents.com)



Job	Truss	Truss Type	Qty	Ply	920 Serenity-Roof-B326 A CP TRAY GRH
25050065	A01	Piggyback Base Supported Gable	1	1	I72213112
					Job Reference (optional)

WEBS 17-49=-176/57, 18-48=-177/62,
19-47=-180/61, 20-46=-159/6, 22-44=-177/2,
23-43=-190/87, 24-42=-189/81,
25-40=-190/77, 27-39=-181/77,
28-38=-132/77, 29-37=-125/77,
30-36=-138/78, 31-35=-65/120,
32-34=-244/137, 16-50=-177/62,
15-51=-180/61, 14-52=-159/1, 12-53=-178/0,
11-55=-194/87, 9-56=-193/81, 8-57=-193/77,
7-58=-194/77, 6-59=-157/77, 5-60=-115/91,
4-61=-186/159, 3-62=-226/263

NOTES

- 1) Unbalanced roof live loads have been considered for this design.

2) Wind: ASCE 7-16; Vult=130mph (3-second gust)
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Corner(3E) -0-8-6 to 4-7-0, Exterior(2N) 4-7-0 to 12-4-2, Corner(3R) 12-4-2 to 22-11-14, Exterior(2N) 22-11-14 to 26-2-2, Corner(3R) 26-2-2 to 36-7-0, Exterior(2N) 36-7-0 to 47-11-2, Corner(3E) 47-11-2 to 53-3-0 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60

3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.

4) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10

5) Unbalanced snow loads have been considered for this design.

6) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.

7) Provide adequate drainage to prevent water ponding.

8) All plates are 2x4 MT20 unless otherwise indicated.

9) Gable requires continuous bottom chord bearing.

10) Gable studs spaced at 2-0-0 oc.

11) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.

12) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.

13) N/A
- 14) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.


LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	920 Serenity-Roof-B326 A CP TRAY GRH	I72213113
25050065	A03	Piggyback Base	5	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 12:39:57
ID:OFJFx3IDTxFbWWzrBXohbzzRCTM-RfC?PsB70Hq3NSgPqnL8w3uITXbGKwrcDoi7J4zJC?f

Page: 1



Scale = 1:94.5

Plate Offsets (X, Y): [2:0-4-14,0-2-8], [10:0-5-0,0-4-8], [14:0-5-0,0-4-8], [16:0-5-0,0-4-8]


Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.72	Vert(LL)	-0.35	18-20	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.88	Vert(CT)	-0.53	18-20	>728	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.98	Horz(CT)	0.11	12	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 470 lb	FT = 20%

LUMBER			WEBS		
TOP CHORD	2x6 SP No.2		2-20=-63/2672, 18-22=-489/243,		
BOT CHORD	2x6 SP No.2 *Except* 16-14:2x6 SP 2400F		22-25=-474/253, 6-25=-460/257,		
	2.0E		16-23=-864/226, 23-26=-848/235,		
WEBS	2x4 SP No.3 *Except* 21-2:2x6 SP No.2,		8-26=-827/232, 3-20=-817/329,		
	20-2-6-18-8-16,20-5,18-5,16-9,14-9:2x4 SP		5-20=-272/480, 5-18=0/904, 9-16=-92/938,		
	No.2		10-14=-918/319, 9-14=-189/969,		
WEDGE	Right: 2x4 SP No.3		10-13=-222/799, 11-13=-330/236,		
			22-24=-38/54, 23-24=-38/54, 17-24=0/41,		
BRACING			25-27=-25/40, 26-27=-131/27, 7-27=-257/88,		
TOP CHORD	Structural wood sheathing directly applied or		6-27=-296/722, 8-27=-283/812		
	3-1-4 oc purlins, except end verticals, and				
	2-0-0 oc purlins (3-8-7 max.): 5-9.				
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc				
	bracing.				
WEBS	1 Row at midpt 18-25, 16-26, 5-20, 9-16,				
	22-23				
JOINTS	1 Brace at Jt(s): 25,				
	26, 27				
REACTIONS	(size) 12= Mechanical, 15=0-3-8,				
	21=0-5-8				
	Max Horiz 21=-187 (LC 12)				
	Max Uplift 12=-29 (LC 14), 15=-198 (LC 15),				
	21=-170 (LC 14)				
	Max Grav 12=2089 (LC 47), 15=852 (LC 39),				
	21=2368 (LC 37)				
FORCES	(lb) - Maximum Compression/Maximum				
	Tension				
TOP CHORD	1-2=0/25, 2-3=-3226/217, 3-5=-3342/411,				
	5-6=-2713/224, 6-7=-3232/430,				
	7-8=-3232/430, 8-9=-2696/223,				
	9-11=-4171/305, 11-12=-4214/194,				
	2-21=-2411/219				
BOT CHORD	20-21=-132/276, 18-20=-26/2497,				
	17-18=-2/2590, 15-17=-2/2590,				
	13-15=-46/3134, 12-13=-88/3645				

- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-8-6 to 4-7-9, Interior (1) 4-7-9 to 10-1-10, Exterior(2R) 10-1-10 to 39-2-5, Interior (1) 39-2-5 to 47-11-2, Exterior(2E) 47-11-2 to 53-3-0 zone; end vertical left exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
 - Unbalanced snow loads have been considered for this design.
 - This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 200.0lb AC unit load placed on the bottom chord, 24-7-0 from left end, supported at two points, 5-0-0 apart.
 - Provide adequate drainage to prevent water ponding.
 - All plates are 2x4 MT20 unless otherwise indicated.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.

- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 29 lb uplift at joint 12.
- One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 21 and 15. This connection is for uplift only and does not consider lateral forces.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard



March 25, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932


Job	Truss	Truss Type	Qty	Ply	920 Serenity-Roof-B326 A CP TRAY GRH	I72213114
25050065	A04	Piggyback Base	1	1	Job Reference (optional)	

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Fri Mar 21 12:39:58

Page: 1

ID:DGN6a6f8caCKWpHw1clz1BzRCZx-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWCrD0i7J4zJC?f



Scale = 1:94.5

Plate Offsets (X, Y): [2:0-4-14,0-2-8], [10:0-5-0,0-4-8], [14:0-5-0,0-4-8], [15:0-5-0,0-4-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.70	Vert(LL)	-0.41	17-19	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.99	Vert(CT)	-0.60	17-19	>911	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.87	Horz(CT)	0.09	12	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 469 lb	FT = 20%

LUMBER
TOP CHORD 2x6 SP No.2
BOT CHORD 2x6 SP No.2
WEBS 2x4 SP No.3 *Except* 20-2:2x6 SP No.2, 19-2,6-17,15-8,15-9,14-9,19-5,17-5:2x4 SP No.2

BRACING
TOP CHORD Structural wood sheathing directly applied or 3-2-8 oc purlins, except end verticals, and 2-0-0 oc purlins (3-8-11 max.): 5-9.
BOT CHORD Rigid ceiling directly applied or 2-2-0 oc bracing.

WEBS 1 Row at midpt 17-24, 15-25, 9-14, 5-19, 5-17, 21-22
WEBS 2 Rows at 1/3 pts 10-13
JOINTS 1 Brace at Jt(s): 24, 25, 26

REACTIONS (size) 12= Mechanical, 13=0-5-8, 20=0-5-8
Max Horiz 20=187 (LC 12)
Max Uplift 12=-211 (LC 14), 13=-386 (LC 15), 20=-154 (LC 14)
Max Grav 12=896 (LC 37), 13=2413 (LC 39), 20=2303 (LC 37)


FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/25, 2-3=-3159/195, 3-5=-3275/389, 5-6=-2618/234, 6-7=-3185/440, 7-8=-3185/440, 8-9=-2599/234, 9-11=-2806/538, 11-12=-1552/470, 2-20=-2365/214
BOT CHORD 19-20=-131/273, 17-19=0/2415, 16-17=0/2503, 13-16=-101/2503, 12-13=-357/1335

WEBS
2-19=-55/2613, 17-21=-468/312, 21-24=-457/317, 6-24=-443/319, 15-22=-863/241, 22-25=-855/249, 8-25=-836/246, 9-15=-29/1395, 9-14=-352/52, 10-14=0/565, 10-13=-2213/265, 11-13=-455/258, 3-19=-817/329, 5-19=-283/531, 5-17=-66/856, 21-23=-37/56, 22-23=-37/56, 16-23=0/30, 24-26=-50/91, 25-26=-169/43, 7-26=-264/87, 8-26=-283/842, 6-26=-311/741

- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-8-6 to 4-7-9, Interior (1) 4-7-9 to 10-1-10, Exterior(2R) 10-1-10 to 39-2-5, Interior (1) 39-2-5 to 47-11-2, Exterior(2E) 47-11-2 to 53-3-0 zone; cantilever left and right exposed; end vertical left and right exposed; porch right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
 - Unbalanced snow loads have been considered for this design.
 - This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 200.0lb AC unit load placed on the bottom chord, 24-7-0 from left end, supported at two points, 5-0-0 apart.
 - Provide adequate drainage to prevent water ponding.
 - All plates are 2x4 MT20 unless otherwise indicated.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.

- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 211 lb uplift at joint 12.
- One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 20 and 13. This connection is for uplift only and does not consider lateral forces.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard



March 25, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932

Symbols

PLATE LOCATION AND ORIENTATION



* Plate location details available in MITek software or upon request.

PLATE SIZE

4 X 4

The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T or I bracing if indicated.

BEARING




Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number/letter where bearings occur. Min size shown is for crushing only.

Industry Standards:

ANSI/TP1: National Design Specification for Metal Plate Connected Wood Truss Construction.
DSB-22: Building Component Safety Information, Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses.

Numbering System



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

Product Code Approvals

ICC-ES Reports:
ESR-1988, ESR-2362, ESR-2685, ESR-3282
ESR-4722, ESL-1388

Design General Notes

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.

Lumber design values are in accordance with ANSI/TP1 1 section 6.3. These truss designs rely on lumber values established by others.

© 2023 MITek® All Rights Reserved

General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor I bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TP1 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TP1 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TP1 1 Quality Criteria.
21. The design does not take into account any dynamic or other loads other than those expressly stated.

MITek®

ENGINEERING BY
TRENCO
A MITek Affiliate

MITek Engineering Reference Sheet: MII-7473 rev. 1/2/2023