COLLEX475INVENTORYMARKEDPLAN

DOGWOOD **REVISION LIST - STRUCTURAL:**

- 1.) ADDED I-JOIST SERIES/SPACING (11-16)
- 2) CHANGED FRAMING AND REMOVED ECOTINGS AND FOUNDATION SUPPORT FOR THE REMOVED VALUET IN REDROOM 3 (11.16)
- 3.) ADDED FRAMING FOR CHASE AT SECOND FLOOR (11-16)
- 4.) ADDED/REMOVED EXTRA JOISTS IN CRAWL (11-16)
- 5.) ADDED PLUMBING DIMENSIONS WITH OPTIONAL MASTER MATH ON MONO (11-16)
- 6.) CHANGED ALL GARAGE HEADERS TO (3) PLY (11-16)
- 7.) CHANGED DOUBLE STUD POCKETS TO TRIPLE STUD POCKETS (11-18)
- 8.) REMOVED BRICK FROM REAR PORCH (11-18)
- 9). REMOVED INTERIOR WALL BRACING PANELS (11-18)
- 10.) 2018 CODE UPDATE (6-19)
- 11) CHANGE 2X6 EXTERIOR WALLS TO 2X4 EXTERIOR WALLS (3.11.20).
- 12.) SQUARE FOOTAGES CHANGE ON SECOND FLOOR BETWEEN ALL ELEVATIONS DUE TO CLOSET BUMP OUT (B ELEVATIONS) AND BEDROOM 4 BUMP OUT (C ELEVATIONS) (08-13-20)
- 13.) SQUARE FOOTAGE OF FIRST FLOOR CHANGES WITH B ELEVATIONS DUE TO BUMP OUT IN FOYER (08-13-20)
- 14.) CHANGED ALL EXTERIOR WALLS FROM 2X6 TO 2X4 EXCEPT WHERE SHADED (11-01-20)
- 15.) REMOVED HEADER FROM STANDARD OWNER'S BATHROOM FOR TRANSOM WINDOW THAT WAS REMOVED (09-07-22'
- 16.) BASEMENT INTERIOR WALLS CHANGED FROM 2X4 TO 2X6 (09-28-22)
- 17.) CHANGED WALL BETWEEN FAMILY ROOM AND KITCHEN TO 2X6 (09-28-22)
- 18.) CHANGED OPENING FROM FOYER TO FAMILY ROOM FROM 4'-6" TO 4'-4" (09-28-22)

DOGWOOD **REVISION LIST - ARCHITECTURAL:**

- CREATED ELEVATIONS TO BE IN STANDARDS WITH OTHER PLANS (SEE SHEETS A-1 THROUGH
- CHANGED COLUMNS ON FLEVATIONS TO
- STANDARD COLUMNS
- CHANGED GARAGE DOORS TO REPRESENT
- STANDARD GARAGE DOOR FOR EACH ELEVATION FIXED COVERED PORCH TO KEEP COLUMNS
- FROM OVERLAPPING EDGE OF CONCRETE REMOVED GRIDS FROM TRANSOMS ABOVE
- FRONT DOOR
- ADDED NOTE FOR GARAGE DOOR "GARAGE DOOR PER SPECIFICATIONS AND GLASS INSERT (TOP PANEL ONLY)*
- MOVED ROOF PLANS TO SHEETS \$4
- ROOF ABOVE COVERED PATIO CHANGED TO SHED ROOF (SEE ON SIDE AND REAR ELEVATIONS).
- REMOVED OPTION FOR FIREPLACE IN OWNER'S
- CREATED SLAB INTERFACE PLAN (SEE SHEET A-4 THROUGH A-4.2)
- MOVED ALL OPTIONS OFF BASE PLAN AND PLACED ON SEPARATE SHEET
- ADDED NOTE FOR FLUSH COUNTERTOP ON
- ISLAND AND 34 1/2" H. WALL UNDER
- CHANGED PATIO SIZE TO STANDARD 12'X10'
- ADDED OPTIONAL GAS LINE
- 15. CHANGED NAME OF "FLEX ROOM" TO "STUDY" CHANGED "BREAKFAST ROOM" TO "CASUAL
- ADDED 2ND HOSE BIB
- CALLED OUT '45' WALL WITH CAP' AS STANDARD
- CHANGED ALL EXTERIOR WALLS FROM 2X6 TO
- 2X4 EXCEPT WHERE SHADED
- ADDED NOTE "OPT. REF."
- ADDED NOTE 'OPT. W/D'
- ADDED NOTE "WASHER ALWAYS TO BE LOCATED
- TO THE LEFT OF DRYER
- ADDED PDS ATTIC ACCESS
- VERIFIED VENTILATION AND LIGHT REQUIREMENTS AT OWNER'S BEDROOM MEETS.
- CODE (11/01/20)
- SOUARE FOOTAGES ARE UPDATED AND CHANGED DUE TO MOVEMENT OF WALL DOWN CENTER OF HOUSE TO KEEP WALLS FROM
- MOVING BETWEEN ELEVATION CHOICES
- SOUARE FOOTAGE OF COVERED PORCH CHANGED DUE TO KEEPING COLUMNS FROM OVERLAPPING CONCRETE EDGE
- CREATED PARTIAL PLANS FOR B & C ELEVATIONS
- (FLOOR, SLAB, & ELECTRICAL)
- REMOVED ALL WALL OUTLETS
- REMOVED ALL PHONE OUTLETS
- REMOVED ALL TV OUTLETS
- PLACED STANDARD 3 BULB LIGHT IN KITCHEN
- VERIFIED COACH LIGHT LOCATIONS (SEE ELEVS

- PLACED DASHED FANS WHERE APPLICABLE WITH NOTE 'STD. LIGHT, OPT. FAN/LT PREWIRE'
- LIPDATED ELECTRICAL KEY
- REMOVED UNDER CABINET LIGHTINGS VERIFIED CO2 DETECTOR LOCATIONS
- SHOWED PENDANT LIGHTS AS OPTIONAL
- SHOWED CAN LIGHTS IN KITCHEN AND FAMILY ROOM AS "OPTIONAL CAN LIGHTS"
- PLACED OPTIONAL FLOOD LIGHTS
- PLACED OPTIONAL FLOOR OUTLET IN FAMILY ROOM
 - PLACED CALCULATIONS FOR SOFFIT AND RIDGE
- VENT REQUIREMENTS CHANGED LAYOUT FOR BASE OWNER'S
- BATHROOM
- ADDED OPTIONAL OWNER'S BATH 2 & OWNER'S BATH 3
- REMOVED "OPTIONAL COVERED DECK AT
 - FEBRUARY 01, 2022
- ADDED OPTIONAL DOUBLE GARAGE DOOR
- FLOOR PLAN TO FIRST FLOOR OPTIONS SHEET (02-01-22
- ADDED OPTIONAL BASEMENT TO PLANS (02-01-22) REMOVED TRANSOM WINDOW FROM OWNER'S
- CHANGED BASEMENT INTERIOR WALLS TO 2X6
- (09-28-22)
- CHANGED WALL BETWEEN FAMILY ROOM AND
- KITCHEN TO 2X6 (09-28-22)
- CHANGED OPENING FROM FOYER TO FAMILY
- ROOM FROM 4'-6" TO 4'-4" (09-28-22) RECENTERED WINDOWS AND FIREPLACE IN
- EAMILY ROOM (09-28-22). CREATED CHASE ON TUB SIDE OF OWNER'S BATH
- 2 BY REMOVING SOME DEPTH FROM EXISTING CHASE ON SHOWER SIDE TO GET CLEARANCE
- FOR TUBS FAUCET (11-01-23) CREATED FOUAL CHASE IN SHOWER LOCATION
- FOR PRIMARY OWNER'S BATH 2 (11.01.23)
- WINDOW OF OWNER'S BATH 2 MOVED BY 7"
- CHANGED OWNER'S BEDROOM TO PRIMARY BEDROOM (11-01-23)
- CHANGED OWNER'S BATH TO PRIMARY
- BATH(11-01-23)




SHEET COVER

ATE-IANUARY 17, 201

DRAWN BY:










ENGINEERED BY:

SLAB INTERFACE PLAN

A-4







W FULL BRICK VENES	R
Int FLOOR	1379 SQ FT
2nd B 0009	1726 5Q FT.
TOTAL	1105 50 FT
GURLOE	5/5 50 FT
PROVI PORCH	98 5Q FT.
STD, REAR PATIO	120 SQ. FT.
OPT. BASEMENT:	U65 50. FT.
In FLOOR OPTIONS	
OPT. FIREPLACE:	B 5Q FT.
2nd FLOOR OPTIONS	
OPT, OWNER'S EXTENDED W.C.,	121 8Q.FT.
UN-EATED OPTIONS	
OPT I-CAR GARAGE:	24Ø 5Q, FT,
OPT, REAR COVERED PORCH	DØ 50. FT.
OPT, 12169' EXTENDED PATIO	15 8Q.FT.
OPT, EXTENDED PATIO:	193 5Q, FT.
OPT. EXTENDED COVERED PORCH	193 8Q.FT.
OPT, COVERED DECK:	120 SQ. FT.



THE AMERICAN CONTROL STETLING CHOCK TO CONTROL STETLING CHOCK TO CONTROL STETLING CHOCK WITHOUT STETLING WITHOUT STETLING CHOCK WITHOUT S

DREAM FINDERS HOMES DOGWOOD


DATE: JANUARY 17, 2019 REV:: FEBRUARY 01, 2022

SCALE: 1/4"-1'-0" DRAWN BY:

ENGINEERED BY:

FIRST FLOOR PLAN

A-6





AND STATEMENT OF THE ST

DREAM FINDERS HOMES DOGWOOD

DATE: JANUARY 17, 2019 REV.: FEBRUARY 01, 2022


SCALE: 1/4"-1'-0"


DRAWN BY: ENGINEERED BY:

REVIEWED BY:

SECOND FLOOR PLAN

A-7







THE ADMINISTRY BY AND THE ADMINISTRY BY AND THO ADMINISTRY BY AND THE ADMINISTRY BY AND

DREAM FINDERS HOMES DOGWOOD

DATE: JANUARY 17, 2019 REV.: FEBRUARY 01, 2022

SCALE: 1/4"-1'0"


DRAWN BY: ENGINEERED BY: REVIEWED BY:

ELEVATIONS A-1 & A-2 ROOF PLAN

A-8

TOTAL UNDER ROOF AREA: $\frac{1870}{LOWER; \, \underline{3.11}} \quad \begin{array}{c} SQ, FT, \ /\ 300 = \\ \end{array} \quad \begin{array}{c} \frac{1870}{6.23} \\ \end{array} \quad \begin{array}{c} SQ, FT, \\ SQ, FT, \\ \end{array}$ VENTING AREA REQUIRED: TOTAL REQUIREMENTS: LOWER AREA VENTING SOFFIT VENT UPPER AREA VENTING
RIDGE VENT UPPER AREA VENTING PROVIDED: TOTAL AREA PROVIDED
SOFFIT AND RIDGE VENT

10.162







WE BE ANSE UT (ATOMS DISSON ANTERALS AND SISONOS-BREET) ANTERALS AND SISONOS-BREET ANTERAL DAND VARNI NA ATUAL CONSTRUCTION ANTERAL DOSTONOS ON TO THE DEPENDENT OF THE ATOM SISONOS ON THE REPRESENDENT OF THE ATOM SISONOS ON THE REPRESENDENT OF THE ATOM SISONOS ON THE ATOM SISON

DREAM FINDERS HOMES DOGWOOD


DATE: JANUARY 17, 2019 REV:: FEBRUARY 01, 2022


SCALE: I/4"-1'0" DRAWN BY:


ENGINEERED BY:


ROOF PLAN OPTIONS

A-8.3









TYPICAL STAIR DETAIL (NTS)

* * STAIR NOTES:

RALING BALUSTERS SHALL BE SPACED SO THAT A 4" SPHERE

THE TRUMSHLAR OPENINGS FORTED BY THE RISER, TREAD AND BOTTOM RAIL OF A GUIARD AT THE OPENING OF A STAIRMAY ARE PERMITTED TO BE A SUCH A SIZE THAT A SPHERE OF 8 NOTES CANNOT PASS THROUGH

OPENINGS FOR REQUIRED GUARDS ON THE SIDES OF STAIR
TREADS SHALL NOT ALLOW A SPHERE 4 3/8 INCHES TO PASS
THROUGH


HANDRAILS

HADRALS FOR STANSAYS SHALL BE CONTINUAS FOR THE RLL LEWISH OF THE FLIGHT FROM A POINT DIRECTLY ABOVE THE TOP RESER OF THE FLIGHT TO A POINT DIRECTLY ABOVE THE LOUBST ROSER, HADRALL ENDS SHALL BE RETURNED A SHALL TEMPRISE IN FLIGHT, FOR SEA SHATT TEMPRISLS. HADRALS ADJACENT TO A WALL SHALL HAVE A SPACE OF MOT LESS TAIN LIT YOUR DETERMENT THE WALL AS ON HADDRALS.

CONTINUOUS GRASPABLE HANDRALL MIST MEET TYPE ONE OR TYPE TUD CRITERIA

ZONE 3R-30 INSULATION (MEET THE CI
REGUIREMENT OF INSULATION EXTENDING
ACROSS THE TOP PLATE
R-30 INSULATION MY HEEL LESS THAN 9'
ZONE 4.
R-30 INSULATION MY HEEL ACATER
THAN 9' ROOF PITCH AS PER DRAWINGS 06B/PLYWOOD SHEATHING-PER CODE RAFTERS/ROOF TRUSSES AS SPEC. TOP OF PLATE TOP PLATE(5) AS SPEC Zone 3 or Zone 4-R-15 INSULATION OR R-13 CAVITY INSULATION +R-2.5 CI TOP OF SECOND FLOOR FLOOR SHEATHING GLUED AND-NAILED ON FLOOR SYSTEM TOP PLATE(6) AS SPEC. HEADERS AT OPENINGS AS SPEC: -STUD FRAMING (UNO) UV TRTD. BOTTOM PLATE(S) BOTTOM PLATE(6) TRTD. SILL PLATE (UNO -MONOLITHIC SLAB AS SPEC.

WALL SECTION W/ SLAB W/ STD. SIDING SHOWN (NTS)



WALL SECTION W/ CRAWL SPACE W/ STD. SIDING SHOWN (NTS)

DREAM FINDERS HOMES

THOSE NEW BUTCHES, MEDITERS, ENTRY E

DREAM FINDERS HOMES DOGWOOD

DATE: JANUARY 17, 2019 REV.: FEBRUARY 01, 2022

SCALE: I/4"-1'0" DRAWN BY:

ENGINEERED BY: REVIEWED BY:

WALL SECTIONS AND STAIR DETAIL

AD-1

120V GFI OUTLET

120V BASEBOARD OUTLET

4-PLEX

FLOOR MOUNTED 120*

FLOOR MOUNTED 120V GFI

WEATHERPROOF

220V OUTLET 120V DEDICATED CIRCUIT

220V DEDICATED CIRCUIT

SPECIAL PURPOSE (240 V, ETC.)

WALL MOUNT LIGHT

CEILING MOUNT LIGHT

. Ф PENDANT LIGHT

MINI CAN LIGHT

Ø **⊙** EVERALL LIGHT

FLUORESCENT LIGHT

UNDERCABINET LIGHT
FLOOD LIGHT

SWITCH

3-WAY SWITCH

4-WAY SWITCH

DIMMER SWITCH

TV CONNECTION

₩-CONDUIT FOR COMPONENT WIRING

SPEAKER

COMBO SMOKE/ CARBON MONOXIDE DETECTOR

Ø

110 V SMOKE DETECTOR

3 EXHAUST FAN LOW VOLTAGE PANEL



ELECTRICAL NOTES:

PROVIDE AND INSTALL GROUND FAULT CIRCUIT-INTERRUPTERS (G.F.L.) AS INDICATED ON PLANS OR AS ITEM NO. 4 AND 5 BELOW INDICATES.

UNLESS OTHERWISE INDICATED, INSTALL
SWITCHES AND RECEPTACLES AT THE
FOLLOWING HEIGHTS ABOVE FINISHED FLOOR:
SWITCHES ... 42*
OUTLETS ... 14*
COUNTY HEIGHTONE ... 14* (UNLESS ABV

COUNTERTOP)
TELEVISION...14° ALL SMOKE DETECTORS SHALL BE HARDWIRED INTO AN ELECTRICAL POWER SOURCE AND SHALL BE DEJUPPED WITH A MONITORED BATTERY BACKUP PROVIDE AND INSTALL LOCALLY CERTIFIED SMOKE DETECTORS.


ALL 15A AND 20A RECEPTACLES IN SLEEPING ROOMS, PAMILY ROOMS, DINING ROOMS, LIVING ROOMS, DINING ROOMS, LIVING ROOMS, LIVING ROOMS, DENS, SUNROOMS, RECREATION ROOMS, CLOSETS, HALLWAYS, AND SIMILAR AREAS WILL REQUIRE A COMBINATION TYPE AF GL DEVICE AND TAMPER-PROOF RECEPTACLES.

ALL 15A AND 20A 120V RECEPTACLES LOCATED IN THE GARAGE AND UTILITY ROOMS SHALL BE G.F.C.I. PROTECTED (G.F.I).

IT IS THE RESPONSIBILITY OF THE LICENSED ELECTRICIAN TO ENSURE THAT ALL ELECTRICAL WORK IS IN FULL COMPILANCE WITH ALL APPLICABLE LOCAL STANDARDS, CODES, AND ORDINANCES.

EVERY BUILDING HAVING A FOSSIL-FUEL-BURNING HEATER OR APPLIANCE, FIREPLACE, OR AN ATTACHED CARAGE SHALL HAVE AN OPERATIONAL CARBON MONOXIDE DETECTOR INSTALLED WITHIN 10 FEET OF EACH ROOM USED FOR SLEEPING TURPOSES.

ALARMS SHALL RECEIVE THEIR PRIMARY FOWER FROM THE BULDING WRING WHEN SUCH WIRN'S SERVED FROM THE LOCAL FOWER FROM THE SEAL FOWER FROM THE LOCAL FROM T





THERE, REMOTICING, DESTRUCTS, TOTANG, TOTANG,

DREAM FINDERS HOMES DOGWOOD


DATE: JANUARY 17, 2019 REV.: FEBRUARY 01, 2022

SCALE: 1/4"-1'-0" DRAWN BY:

ENGINEERED BY-REVIEWED BY:

FIRST FLOOR ELECTRICAL PLAN

E-1



4-PLEX

FLOOR MOUNTED 120

FLOOR MOUNTED 120V GFI

WALL MOUNT LIGHT

CEILING MOUNT LIGHT

PENDANT LIGHT

MINI CAN LIGHT

EVERALL LIGHT

FLUORESCENT LIGHT \equiv

UNDERCABINET LIGHT
FLOOD LIGHT

SWITCH

3-WAY SWITCH

4-WAY SWITCH

DIMMER SWITCH

TV CONNECTION

₩-CONDUIT FOR COMPONENT WIRING SPEAKER

Ø

COMBO SMOKE/ CARBON MONOXIDE DETECTOR

110 V SMOKE DETECTOR




ELECTRICAL NOTES:

PROVIDE AND INSTALL GROUND FAULT CIRCUIT-INTERRUPTERS (G.F.L.) AS INDICATED ON PLANS OR AS ITEM NO. 4 AND 5 BELOW INDICATES.

UNLESS OTHERWISE INDICATED, INSTALL
SWITCHES AND RECEPTACLES AT THE
FOLLOWING HEIGHTS ABOVE FINISHED FLOOR:
SWITCHES ... 42*
OUTLETS ... 14*
COUNTY LELEPHONE ... 14* (UNLESS ABV

COUNTERTOP)
TELEVISION...14°

- ALL SMOKE DETECTORS SHALL BE HARDWIRED INTO AN ELECTRICAL POWER SOURCE AND SHALL BE EQUIPPED WITH A MONITORED BATTERY BACKUP PROVIDE AND INSTALL LOCALLY CERTIFIED SMOKE DETECTORS.
- ALL 15A AND 20A RECEPTACLES IN SLEEPING ROOMS, PAMILY ROOMS, DINING ROOMS, LIVING ROOMS, DINING ROOMS, LIVING ROOMS, LIVING ROOMS, CLOSETS, HALLWAYS, AND SIMILAR AREAS WILL REQUIRE A COMBINATION TYPE AF GL DEVICE AND TAMPER-PROOF RECEPTACLES.
- ALL 15A AND 20A 120V RECEPTACLES LOCATED IN THE GARAGE AND UTILITY ROOMS SHALL BE G.F.C.I. PROTECTED (G.F.I).
- IT IS THE RESPONSIBILITY OF THE LICENSED ELECTRICIAN TO ENSURE THAT ALL ELECTRICAL WORK IS IN FULL COMPILANCE WITH ALL APPLICABLE LOCAL STANDARDS, CODES, AND ORDINANCES.
- EVERY BUILDING HAVING A FOSSIL-FUEL-BURNING HEATER OR APPLIANCE, FIREPLACE, OR AN ATTACHED CARAGE SHALL HAVE AN OPERATIONAL CARBON MONOXIDE DETECTOR INSTALLED WITHIN 10 FEET OF EACH ROOM USED FOR SLEEPING TURPOSES.
- ALARMS SHALL RECEIVE THEIR PRIMARY POWER FROM THE BUILDING WIRING WHEN SUCH WIRING SERVICE FROM THE LOCAL POWER WIRING SERVICE FROM THE LOCAL POWER OF THE LOCAL POWE



Second Floor Plan SCALE: 1/4"=1"-0" ON 22x34 AND 1/8"=1"-0" ON 11x17

THE SECRETARY OF STREET OF THE OPTICAL STREET OF THE OPTICAL STREET OF OLD AND STREET ON STREE

DREAM FINDERS HOMES DOGWOOD

DATE: JANUARY 17, 2019 REV.: FEBRUARY 01, 2022

SCALE: 1/4"-1'-0" DRAWN BY:

ENGINEERED BY-REVIEWED BY:

SECOND FLOOR ELECTRICAL PLAN

E-2



4-PLEX

FLOOR MOUNTED 120 FLOOR MOUNTED 128V GFI 220V OUTLET

120V DEDICATED CIRCUIT 220V DEDICATED CIRCUIT

SPECIAL PURPOSE (240 V, ETC.) Δ WALL MOUNT LIGHT

CEILING MOUNT LIGHT ф О PENDANT LIGHT

Ø EVERALL LIGHT FLUORESCENT LIGHT \equiv

烃 UNDERCABINET LIGHT FLOOD LIGHT SWITCH 3-WAY SWITCH 4-WAY SWITCH DIMMER SWITCE

₽-CONDUIT FOR COME

SPEAKER Ø COMBO SMOKE/ CARBON MONOXIDE DETECTOR

110 V SMOKE DETECTOR EXHAUST FAN



ELECTRICAL NOTES:

PROVIDE AND INSTALL GROUND FAULT CIRCUIT-INTERRUPTERS (G.F.L.) AS INDIGATED ON PLANS OR AS ITEM NO. 4 AND 5 BELOW

UNLESS OTHERWISE INDICATED, INSTALL
SWITCHES AND RECEPT ACLES AT THE
FOLLOWING HEIGHTS ABOVE FINISHED FLOORSVITCHES ... 42
OUTLETS ... 14
TELEPHONE ... 14 (UNLESS ABV COUNTERTOP) TELEVISION...14°

ALL SMOKE DETECTORS SHALL BE HARDWIRED INTO AN ELECTRICAL POWER SOURCE AND SHALL BE EQUIPPED WITH A MONITORED BATTLERY BACKUP. PROVIDE AND INSTALL LOCALLY CERTIFIED SMOKE DETECTORS.

ALL 15A AND 20A RECEPTACLES IN SLEEPING ROOMS, FAMILY ROOMS, DINING ROOMS, LIVING ROOMS, DINING ROOMS, LIVING ROOMS, DENS, SUNROOMS, RECREATION ROOMS, CLOSETS, HALLWAYS, AND SIMILAR RAEAS WILL REQUIRE A GOMBINATION TYPE A F.C.I. DEVICE AND TAMPER-PROOF RECEPTACLES.

ALL 15A AND 20A 120V RECEPTACLES LOCATED IN THE GARAGE AND UTILITY ROOMS SHALL BE G.F.C.I. PROTECTED (G.F.I).


IT IS THE RESPONSIBILITY OF THE LICENSED ELECTRICIAN TO ENSURE THAT ALL ELECTRICAL. WORK IS IN FULL COMPLIANCE WITH ALL APPLICABLE LOCAL STANDARDS, CODES, AND ORDINANCES.

EVERY BUILDING HAVING A FOSSIL-FUEL-BURNING HEATER OR APPLIANCE, FIREPLACE, OR AN ATTACHED EARAGE SHALL HAVE AN OPERATIONAL CARBON MONOXIDE DETECTOR INSTALLED WITHIN 10 FEET OF EACH ROOM USED FOR SLEEPING TURPOSES.


ALARMS SHALL RECEIVE THEIR PRIMARY POWER FROM THE BUILDING WHEN SUCH WIRING IS SEVED FROM THE LOCAL POWER UTILITY. SUCH ALARMS SHALL HAVE BATTERY BACKUP. COMBINATION SMOCKEGABON MONOXIDE ALARMS SHALL BE LISTED OR LABELED BY A NATIONALLY RECOGNIZED TESTING LABORATORY




SCALE: 1/4"-1'-0" ON 22x34 AND 1/8"=1'-0" ON 11x17



Optional Primary Bath 3 SCALE: 1/4"=1'-0" ON 22x34 AND 1/8"=1'-0" ON 11x17




Optional Primary Bath 2 SCALE: 1/4"=1"=0" ON 22x34 AND 1/8"=1'-0" ON 11x17



SCALE: 1/4"=1'-0" ON 22x34 AND 1/8"=1'-0" ON 11x17



SCALE: 1/4"=1'-0" ON 22x34 AND 1/8"-1'-0" ON 11x17



Optional Bedroom 6 & Bath 4 ILO Loft

w/ Elev. A

SCALE: 1/4"=1'-0" ON 22x34 AND 1/8"=1'-0" ON 11x17

Bath




Optional Bedroom 6 & Bath 4 ILO Loft

w/ Elev. B SCALE: 1/4"=1'-0" ON 22x34 AND 1/8"=1'-0" ON 11x17



Optional Bedroom 6 & Bath 4 ILO Loft w/ Elev. C

SCALE: 1/4"=1'-0" ON 22x34 AND 1/8"=1'-0" ON 11x17



Optional Open Rail ILO 45" Wall w/ Cap

SCALE: 1/4"=1"-0" ON 22x34 AND 1/8"=1"-0" ON 11x17



Optional Open Rail ILO 45" Wall w/ Cap

w/ Elev. A SCALE: 1/4"=1'-0" ON 22x34 AND



Optional Open Rail Optional Open Rail ILO 45" Wall w/ Cap ILO 45" Wall w/ Cap

w/ Elev. B

SCALE: 1/4"=1'-0" ON 22x34 AND 1/8"=1'-0" ON 11x17

w/ Elev. C SCALE: 1/4"=1'-0" ON 22x34 AND 1/8"=1'-0" ON 11x17



PRICES PROMOTIONS, I TIOON PLANS, ELEVATI IMPRISSIONS ARE SUBS SQUARE FROM ACE AND AND YOUR PLAN THOU PROUGE ON LOT WILL PROOP THE ACE ACE AND PLOT PLAN THOO RENDERINGS ARE ARTIFED AND THE COPYMOTIED PRO STHE PLANS IS STRECT SALES CONSULTANT PO PREAM TRY PER STREET AND THE PLANS IS STRECT ALLS CONSULTANT PO PREAM TRY PER STREET

DREAM FINDERS HOMES DOGWOOD

DATE: JANUARY 17, 2019

REV.: FEBRUARY 01, 2022 SCALE: 1/4"-1'0"

DRAWN BY: ENGINEERED BY-

REVIEWED BY:

SECOND FLOOR ELECTRICAL PLAN - OPTIONS

E-2.1



1900 AM DRIVE, SUITE 201, QUAKERTOWN, PA 18951 www.kse-eng.com (215) 804-4449

DOGWOOD

LH

NORTH CAROLINA

THESE DRAWINGS ARE TO BE USED IN CONJUNCTION WITH AND COORDINATED WITH THE ARCHITECTURAL, CMIL, MECHANICAL, RECEITRICAL, AND PLUMBING DRAWINGS. THIS COORDINATION IS NOT THE RESPONSIBILITY OF THE STRUCTURAL RONICER OF RECORD (SER). SHOULD ANY DISCEPANCIES BECOME APPARENT, THE CONTRACTOR SHALL NOTIFY KSE ENGINEERING, P.C. BEFORE CONSTRUCTION BEGINS. IT IS THE INTENT OF THE ENGINEER LISTED ON THESE THAT THESE DOCUMENTS BE ACCURATE, PROMING LICENSED PROFESSIONALS CLEAR INFORMATION. EVERY ATTEMPT HAS BEEN MADE TO PREVENT ERROR. THE BUILDER AND ALL SUBCONTRACTORS ARE REQUIRED TO REVIEW ALL OF THE INFORMATION OF THE SOULMENTS PRIOR TO THE COMMENCEMENT OF ANY WORK. THE ENGINEER IS NOT RESPONSIBLE FOR ANY PLAN ERRORS, OMISSIONS, OR MISINTEPRETATIONS UNDERSTEATED AND ALL SOUR MISINTEPRETATIONS OF THE PROFESSION OF THE MISINTEPRETATIONS UNDERSTEATED AND ALL SOUR MISINTEPRETATIONS OF THE STRUCTURE OF THE MISINTEP FOR TO TO CONSTRUCTION. ALL CONSTRUCTION MUST BE IN ACCORDANCE TO THE INFORMATION FOUND IN THESE DOCUMENTS.

DESIGN SPECIFICATIONS:

DESIGN BUILDING CODE (REFERRED TO HEREIN AS 'THE BUILDING CODE'):

2018 NORTH CAROLINA RESIDENTIAL CODE. WALL BRACING PER INTERNATIONAL RESIDENTIAL CODE 2015 EDITION.

DESIGN LIVE LOADS:
- ROOF = 20 PSF (LOAD DURATION FACTOR=1.25)

- NON-1-20 PER CONTROL WITH LIMITED STORAGE = 20 PSF (WHERE SPECIFIED ON PLANS)

 HABITABLE ATTICS AND ATTICS SERVED WITH FIXED STAIRS = 30 PSF
- FLOOR (SLEEPING AREAS) = 30 PSF
- DECK = 40 PSF

 BALCONY = 40 PSF

 STAIRS = 40 PSF

- DESIGN DEAD LOADS:

 ROOF TRUSS = 17 PSF (TC=7, BC=10)

 FLOOR TRUSS = 15 PSF (TC=10, BC=5)

 FLOOR JOIST = 10 PSF

 - QUEEN ANNE BRICK = 25 PSF

NOTE: STRUCTURAL FRAMING HAS NOT BEEN DESIGNED FOR TILE, GRANITE, MARBLE OR OTHER MATERIALS HEAVIER THAN THE ABOVE LOADING UNLESS SPECIFICALLY NOTED ON PLANS..

- DESIGN WIND LOADS:

 ULTIMATE WIND SPEED = Up to 130 MPH
 - EXPOSURE CATEGORY = B

ASSUMED SOIL BEARING CAPACITY = 2000 PSF

ASSUMED LATERAL SOIL PRESSURE = 45 PCF

FROST DEPTH = 12"

SEISMIC DESIGN CATEGORY = B

ENGINEERED LUMBER SHALL HAVE THE FOLLOWING MINIMUM DESIGN VALUES:

- TIJ 210 SERIES (SERIES AND SPACING PER PLANS)

 LSL: E=1,550,000 PSI, F₈=2,325 PSI, F₈=310 PSI, F₆=900 PSI

 LVL: E=2,000,000 PSI, F₈=2,600 PSI, F₈=285 PSI, F₇=750 PSI

 PSI: E=2,100,000 PSI, F₈=2,900 PSI, F₈=290 PSI, F₆=625 PSI

THIS PLAN HAS BEEN DESIGNED PER THE 2018 EDITION OF THE NC RESIDENTIAL CODE.
WHERE FRAMING, FOUNDATION, OR OTHER STRUCTURAL ITEMS DO NOT COMPLY WITH THE PRESCRIPTIVE METHODS OF THE CODE, THOSE ITEMS HAVE BEEN DESIGNED IN ACCORDANCE WITH ACCEPTED ENGINEERING PRACTICE PER NCRC R301.1.3.





130 M.P.H. Dogwood Model

Cover g Project #: 105-16007 Designed By:KRK Checked By: Issue Date: 4/9/19

Re-Issue: 10/10/22 Scale: 1/8*=1'-0" @ 1/4"=1'-0" @ 22x34

- GENERAL STRUCTURAL NOTES:

 1. THE DESIGN PROFESSIONAL WHOSE SEAL APPEARS ON THESE DRAWINGS IS THE STRUCTURAL ENGINEER OF RECORD (SER) FOR DAMINGS IS THE STRUCTURE ENGINEER OF RECOUNT (SER) THIS PROJECT. THE SER BEARS THE RESPONSIBILITY OF THE PRIMARY STRUCTURAL ELEMENTS AND THE PERFORMANCE OF THIS STRUCTURE. NO OTHER PARTY MAY REXISE, ALTER, OR DELETE ANY STRUCTURE. ASPECTS OF THESE CONSTRUCTION DOCUMENTS WITHOUT WRITTEN ASPECTS OF THESE CONSTRUCTION DOCUMENTS WITHOUT WRITTEN ASPECIS OF THESE CONSTRUCTION DOCUMENTS WITHOUT WRITHER FOR CONSENT OF KEE ENDINEERING, P.C. OR THE SER, FOR THE PURPOSES OF THESE CONSTRUCTION DOCUMENTS, THE SER AND KSE ENGINEERING SHALL BE CONSIDERED THE SAME ENTITY. THE STRUCTURE IS ONLY STABLE IN ITS COMPLETED FORM. THE CONTRACTOR SHALL PROVINCE ALL REQUIRED LEMPORARY BRACKING
- DURING CONSTRUCTION TO STABILIZE THE STRUCTURE
- DURING CURSINGUION TO STABILIZE THE STROCTURE.

 THE SER IS NOT RESPONSIBLE FOR CONSTRUCTION SEQUENCES,
 METHODS, OR TECHNIQUES IN CONNECTION WITH THE CONSTRUCTION
 OF THIS STRUCTURE. THE SER WILL NOT BE HELD RESPONSIBLE FOR THE CONTRACTOR'S FAILURE TO CONFORM TO THE CONTRACT
- THE CONTRACTOR'S FALURE TO CONFON TO THE CONTRACT DOCUMENTS, SHOULD ANY NON-COMPONITORS COCUR. THE SER DOES NOT CERTIFY DIMENSIONAL ACCURACY OR RECHIEFURLAL LAYOUT INCLUDING ROOF GEOMETHY. THE SER ASSUMES NO LUBBLITY FOR CHANGES MADE TO THESE FLANS BY OTHERS, OR FOR CONSTRUCTION METHODS. OR FOR ANY DEVARION OF CONSTRUCTION METHODS. OR FOR ANY DEVARION OF CONSTRUCTION IF ANY DISCREPANCES ARE NOTED ON THE PLANS. ANY STRUCTURAL ELEMENTS OR DETAILS NOT FULLY DEVELOPED ON THE CONSTRUCTION DRAWINGS SHALL BE COMPLETED UNDER THE SHOP DRAWINGS SHALL BE COMPLETED WIDDER THE SHOP DRAWINGS SHALL BE SUBMITTED TO SEE ENGINEERING FOR REVIEW SHOP THE SHOP DRAWINGS OF ROMENSIONS, OR FOR ACTUAL FILED CONDITIONS, IS DRAWINGS FOR DIMENSIONS, OR FOR ACTUAL FIELD CONDITIONS, IS NOT THE RESPONSIBILITY OF THE SER OR KSE ENGINEERING, P.C. VERIFICATION OF ASSUMED FIELD CONDITIONS IS NOT THE
- RESPONSIBILITY OF THE SER. THE CONTRACTOR SHALL VERIFY THE FIELD CONDITIONS FOR ACCURACY AND REPORT ANY DISCREPANCIES TO KSE ENGINEERING, P.C. BEFORE CONSTRUCTION BEGINS.
 THE SER IS NOT RESPONSIBLE FOR ANY SECONDARY STRUCTURAL ELEMENTS OR NON-STRUCTURAL ELEMENTS, EXCEPT FOR THE
- FLEMENTS SPECIFICALLY NOTED ON THE STRUCTURAL DRAWINGS THIS STRUCTURE AND ALL CONSTRUCTION SHALL CONFORM TO ALL APPLICABLE SECTIONS OF THE BUILDING CODE AND ANY LOCAL CODES OR RESTRICTIONS.
- 9. DO NOT SCALE DRAWINGS. WRITTEN DIMENSIONS TAKE PRECEDENCE OVER SCALED DIMENSIONS ALL DIMENSIONS ARE TO EACE OF STUD OR TO FACE OF FRAMING LINESS OTHERWISE NOTED
- 10. PROVIDE MOISTURE PROTECTION AND FLASHING PER ARCHITECTURAL

FOUNDATIONS:

- FOUNDATIONS SHALL BE CONSTRUCTED IN ACCORDANCE WITH CHAPTER 4 OF THE BUILDING CODE.

 CONTRACTOR IS SOLELY RESPONSIBLE FOR VERIFYING THE SUITABILITY
- OF THE SITE SOIL CONDITIONS AT THE TIME OF CONSTRUCTION. THE BUILDER SHALL FURNISH ANY AND ALL REPORTS RECEIVED FROM THE GEOTECHNICAL ENGINEER ON THE STUDY OF THE PROPOSED SITE TO THE DESIGNER, STRUCTURAL ENGINEER, AND GENERAL CONTRACTOR
- MAXIMUM DEPTH OF UNBALANCED FILL AGAINST MASONRY WALLS TO BE AS SPECIFIED IN THE BUILDING CODE.
- THE SER HAS NOT PERFORMED A SUBSURFACE INVESTIGATION VERIFICATION OF THE ASSUMED VALUE IS THE RESPONSIBILITY OF THE OWNER OR THE CONTRACTOR. SHOULD ANY ADVERSE SOIL CONDITION BE ENCOUNTERED, THE SER MUST BE CONTACTED BEFORE PROCEEDING.
- THE BOTTOM OF ALL FOOTINGS SHALL EXTEND BELOW THE FROST LINE FOR THE REGION IN WHICH THE STRUCTURE IS TO BE CONSTRUCTED, BUT NOT LESS THAN A MINIMUM OF 12" BELOW GRADE, ALL FOOTINGS TO HAVE A MINIMUM PROJECTION OF 2" ON SACH SIDE OF FOUNDATION WALLS, MAXIMUM FOOTING PROJECTION SHALL NOT EXCEED THE THICKNESS OF THE FOOTING.
- 6. WOOD SILL PLATES SHALL BE ANCHORED TO THE FOUNDATION WITH 1/2" ANCHOR BOLTS WITH MINIMUM 7" EMBEDMENT SPACED A MAYIMUM OF 6'-0" O.C. INSTALL MINIMUM 2 ANCHOR BOLTS PER SECTION, 12" MAYIMUM FROM CORNERS &" DIAMETER v 8" LONG SIMPSON TITEN HD OR USP SCREW-BOLT+ SCREWS MAY BE SUBSTITUTED ON A 1 FOR 1 ANY FILL SHALL BE PLACED UNDER THE DIRECTION OR
- RECOMMENDATION OF A LICENSED PROFESSIONAL ENGINEER. THE RESULTING SOIL SHALL BE COMPACTED TO A MINIMUM OF 95% MAXIMUM DRY DENSITY.
- MAXIMOM DRY DENSITY.

 EXCAVATIONS OF FOOTINGS SHALL BE LINED TEMPORARILY WITH A 6
 MIL POLYETHYLENE MEMBRANE IF PLACEMENT OF CONCRETE DOES NOT OCCUR WITHIN 24 HOURS OF EXCAVATION
- NOT OCCUR WITHIN 24 HOURS OF EXCAVATION.

 NO CONCRETE SHALL BE PLACED AGAINST ANY SUBGRADE CONTAINING WATER, ICE, FROST, OR LOOSE MATERIAL.

 10. PROVIDE FOUNDATION WATERPROOFING AND DRAIN WITH POSITIVE
- SLOPE TO OUTLET AS REQUIRED BY SITE CONDITIONS (SEE ARCHITECTURAL PLANS AND DETAILS).

 11. NONE OF THE FOUNDATION DESIGNS IN THESE DOCUMENTS ARE SUITABLE.
- FOR INSTALLATION IN SHRINK/SWELL CONDITIONS. REFER TO GEOTECHNICAL ENGINEER FOR APPROPRIATE DESIGN. 12. LOTS SHALL BE GRADED TO DRAIN SURFACE WATER AWAY FROM
- FOUNDATION WALLS. THE GRADE SHALL FALL A MINIMUM OF 6 INCHES
- WITHIN THE FIRST TEN FEET.

 CRAWL SPACE TO BE GRADED LEVEL AND CLEAR OF ALL DEBRIS.

 PROVIDE MINIMUM 6 MIL APPROVED VAPOR BARRIER. ALL JOINTS TO BE LAPPED MINIMUM 12" AND SEALED.

CONCRETE & REINFORCING

- CONCRETE DESIGN BASED ON ACI 318 AND ACI 318.1 OR ACI 332.
 CONCRETE SHALL HAVE A NORMAL WEIGHT AGGREGATE AND A MINIMUM
 COMPRESSIVE STRENGTH (f'c) = 3,000 PSI MINIMUM AT 28 DAYS PER CODE (VARIES W/ WEATHER), UNLESS OTHERWISE NOTED ON THE PLAN. CONCRETE SHALL BE PROPORTIONED, MIXED, AND PLACED IN
- ACCORDANCE WITH THE LATEST EDITIONS OF ACI 318: "BUILDING CODE REQUIREMENTS FOR REINFORCED CONCRETE" AND ACI 301 "SPECIFICATIONS FOR STRUCTURAL CONCRETE FOR BUILDINGS"
- AIR ENTRAINED CONCRETE MUST BE USED FOR ALL STRUCTURAL ELEMENTS EXPOSED TO FREEZE/THAW CYCLES AND DEICING CHEMICALS. ARE ENTRAINMENT AMOUNTS (IN PERCENT) SHALL BE WITHIN -1% TO +2% OF 5% FOR FOOTINGS AND EXTERIOR SLABS.

 NO ADMIXTURES SHALL BE ADDED TO ANY STRUCTURAL CONCRETE
- WITHOUT WRITTEN PERMISSION OF THE SER, WATER ADDED TO CONCRETE ON SITE SHALL NOT EXCEED THAT ALLOWED BY THE MIX
- CONCRETE SLABS-ON-GRADE SHALL BE CONSTRUCTED IN ACCORDANCE WITH ACI 302.1R: "GUIDE FOR CONCRETE SLAB AND SLAB CONSTRUCTION"
- CONTROL OR SAW CUT JOINTS (CUT OR TOOLED) SHALL BE SPACED IN INTERIOR SLABS-ON-GRADE AT A MAXIMUM OF 15'-0" O.C. AND IN EXTERIOR SLABS-ON-GRADE AT A MAXIMUM OF 10'-0" UNLESS OTHERWISE NOTED. CARE SHALL BE TAKEN TO AVOID RE-ENTRANT CORNERS
- CONTROL OR SAW CUT JOINTS SHALL BE PRODUCED USING CONVENTIONAL CUT OR TOOLED PROCESSES WITHIN 4 TO 12 HOURS AFTER THE SLAB HAS BEEN FINISHED.
- ALL WELDED WIRE FABRIC (W.W.F.) FOR CONCRETE SLABS-ON-GRADE SHALL BE PLACED AT MID-DEPTH OF SLAB. THE W.W.F. SHALL BE SECURELY SUPPORTED DURING THE CONCRETE POUR. FIBROUS CONCRETE REINFORCEMENT, OR POLYPROPYLENE FIBERS MAY BE USED IN LIEU OF W.W.F. APPLICATION OF POLYPROPYLENE FIBERS PER CUBIC YARD OF CONCRETE SHALL BE PER MANUFACTURER AND COMPLY WIT ASTM C1116, ANY LOCAL BUILDING CODE REQUIREMENTS AND SHALL MEET OR EXCEED CURRENT INDUSTRY STANDARD.
- POLYPROPYLENE REINFORCING TO BE 100% VIRGIN, CONTAINING NO REPROCESSED OLEFIN MATERIALS AND SPECIFICALLY MANUFACTURED FOR USE AS CONCRETE SECONDARY REINFORCEMENT.

 10. STEEL REINFORCING BARS SHALL BE NEW BILLET STEEL CONFORMING
- TO ASTM A615, GRADE 60.
- TO ASIM ABITS, GRADE 60.

 11. DETAILING, FABRICATION, AND PLACEMENT OF REINFORCING STEEL SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF ACI 315: "MANUAL OF STANDARD PRACTICE FOR DETAILING CONCRETE STRUCTURES". 12. HORIZONTAL FOOTING AND WALL REINFORCEMENT SHALL BE
- CONTINUOUS AND SHALL HAVE 90° BENDS, OR CORNER BARS WITH
- THE SAME SIZE/SPACING AS THE HORIZONTAL REINFORCEMENT 13. PROVIDE REINFORCEMENT LAP AS NOTED BELOW, UNLESS NOTED
- OTHERWISE: #4 BARS 30" LENGTH #5 BARS - 38" LENGTH
- #8 BARS 45" LENGTH
 WHERE REINFORCING DOWELS ARE REQUIRED, THEY SHALL BE
 EQUIVALENT IN SIZE AND SPACING TO THE VERTICAL REINFORCEMENT. EQUIVALENT IN SIZE AND SPACING TO THE VERTICAL KINFORCEMENT.

 THE DOWLE SHALL EXTEND 48 BAR DIAMETERS VERTICALLY AND 20 BAR DIAMETERS INTO THE FOOTING. SEE KSE FOUNDATION DETAILS.

 15. WHERE FOOTING BOTTOMS ARE TO BE STEPPED AT SLOPING GRADE
- CONDITIONS, PROVIDE CONTINUOUS REINFORCING WITH Z BARS (TO
- MATCH FOOTING REINFORCING) AS REQUIRED.

 BAR SUPPORT ACCESSORIES SHALL BE PROVIDED IN ACCORDANCE WITH
 THE LATEST ACI MANUAL OF STANDARD PRACTICE FOR DETAILING REINFORCED CONCRETE STRUCTURES, EXCEPT THAT REINFORCING SHALL BE CHAIRED ON THE BOTTOM AND/OR THE SIDES ON BOLSTERS SPACED NOT MORE THAN 4 FEET ON CENTER, NO ROCKS, CMU, CLAY THE OR BRICK SHALL BE LISED TO SUPPORT REINFORCING.
- TILE, OR BRICK SHALL BE USED TO SUPPORT REINFORCING.

 17. FOR GRADE SUPPORTED SLABS, SLAB REINFORCING SHALL BE HELD IN
 PLACE BY BAR SUPPORTS AND ACCESSORIES AS DESCRIBED IN THE
 CRSI MANUAL OF STANDARD PRACTICE. BAR SUPPORTS SHALL BE SPACED A MAXIMUM OF 4'-0" O.C. BOTH WAYS IN STRAIGHT LINES ON THE MESH GRID.

MASONRY

- ALL MASONRY SHALL CONFORM TO ASTM C-90, F = 1500 PSI, ALL BRICK SHALL CONFORM TO ASTM C-216, F'm=1500 PSI. ALL MORTAR SHALL BE TYPE 'S' (TYPE 'M' BELOW GRADE) AND CONFORM TO ASTM C-270. COARSE GROUT SHALL CONFORM TO ASTM C-476 WITH A MAXIMUM AGGREGATE SIZE OF 34" AND A MINIMUM COMPRESSIVE STRENGTH OF 2,000
- ALL MASONRY WORK SHALL BE IN ACCORDANCE WITH "BUILDING CODE REQUIREMENTS FOR MASONRY STRUCTURES" ACI 530/ASCE 5/TMS 402 AND "SPECIFICATIONS FOR MASONRY STRUCTURES" ACI 530.1 / ASCE 6/TMS 602.
- THE UNSUPPORTED HEIGHT OF SOLID MASONRY PIERS SHALL NOT EXCEED TEN TIMES THEIR LEAST DIMENSION. UNFILLED HOLLOW PIERS MAY BE USED IF THE UNSUPPORTED HEIGHT IS NOT MORE THAN FOUR TIMES THEIR LEAST DIMENSION
- IMES THEIR LEAST DIMENSION.

 EACH CRAWL SPACE PIER SHALL BEAR IN THE MIDDLE THIRD OF ITS
 RESPECTIVE FOOTING AND EACH GIRDER SHALL BEAR IN THE MIDDLE
 THIRD OF THE PIERS. PILASTERS TO BE BONDED TO PERIMETER FOUNDATION WALL.
- TOP COURSE OF MASONRY SHALL BE GROUTED SOLID HORIZONTAL WALL JOINT REINFORCEMENT SHALL BE STANDARD 9 GAGE GALVANIZED LADDER OR TRUSS TYPE SPACED AT 16" O.C., UNLESS SHOWN OTHERWISE ON THE DRAWINGS.
- SPICED WIRE REINFORCEMENT SHALL BE LAPPED AT LEAST 6" AND CONTAIN AT LEAST ONE CROSS WIRE OF EACH PIECE OF REINFORCEMENT WITHIN THE 6". LAP WITH STANDARD "I" AND "L" SHAPED PIECES AT INTERSECTIONS AND CORNERS.

WOOD FRAMING:

- SOLID SAWN WOOD FRAMING MEMBERS SHALL CONFORM TO THE SPECIFICATIONS LISTED IN THE LATEST EDITION OF THE "NATIONAL DESIGN SPECIFICATION FOR WOOD CONSTRUCTION** (NDS) LINESS OTHERWISE NOTED, ALL WOOD FRAMING MEMBERS ARE DESIGNED TO
- SPRUCE-PINE-FIR (SPF) WITH THE FOLLOWING MINIMUM DESIGN
- VALUES: E=1,400,000 PSI, F_b=875 PSI, F_v=135 PSI
- 1.1. FRAMING: SPF #2.
- 1.2. PLATES: SPF #2. 1.3. STUDS: SPF STUD GRADE.
- WALL STUD SPACING, (MAXIMUM 10' NOMINAL PLATE HEIGHT): 1 & 2 STORY EXTERIOR AND INTERIOR BEARING: 2x4 @ 16" O.C. OR 2x6 @ 24" O.C., U.N.O BOTTOM OF 3 STORIES EXTERIOR AND INTERIOR BEARING: 2x6 @ 16" O.C., U.N.O. INTERIOR NON-BEARING:
- 2x @ 24" O.C., U.N.O.
 ALL LUMBER EXPOSED TO WEATHER OR IN CONTACT WITH CONCRETE SHALL BE PRESERVATIVE TREATED SOUTHERN YELLOW PINE #2 OR RETTER
- BELIER.

 ANCHOR SILL PLATES IN ACCORDANCE W/ GENERAL STRUCTURAL NOTES.

 ALL BEAMS SPECIFIED ARE MINIMUM SIZES ONLY, LARGER MEMBERS MAY
 BE SUBSTITUTED AS NEEDED FOR EASE OF CONSTRUCTION.
- BE SUBSTITUTED AS RECEIPT FOR PASE OF CONSTRUCTION.
 NAILS SHALL BE COMMON WIRE MAILS UNLESS OTHERWISE NOTED.
 BOLT HOLES AND LEAD HOLES FOR LAG SCREWS SHALL BE IN
 ACCORDANCE WITH NDS SPECIFICATIONS.
- INDIVIDUAL STUDS FORMING A COLUMN SHALL BE ATTACHED WITH (2) 10d NAILS @ 6" O.C. STAGGERED. THE STUD COLUMN SHALL BE FULLY BLOCKED AT ALL FLOOR LEVELS TO ENSURE PROPER LOAD
- TRANSFER, WALL SHEATHING SHALL BE NAILED TO EDGE OF FACH STUD. FACE NAIL ALL MULTI-PLY BEAMS AND HEADERS WITH (2) ROWS 16d COMMON NAILS @ 16" O.C., STAGGERED, OR PER MANUFACTURER'S SPECIFICATIONS FOR ENGINEERED LUMBER. APPLY NAILING FROM BOTH
- 10 FASTEN 4-PLY REAMS WITH (1) K" DIAMETER THROUGH BOLT W/ NUTS AND WASHERS AT 12" O.C. STAGGERED TOP AND BOTTOM, 1/2" MINIMUM EDGE DISTANCE, (UNLESS OTHERWISE NOTED)
- ALL BEAMS AND HEADERS SHALL HAVE (1)2x JACK STUD & (1)2x KING STUD UNLESS OTHERWISE NOTED. THE NUMBER OF STUDS INDICATED ON PLANS ARE THE TOTAL NUMBER OF JACK STUDS REQUIRED, UNLESS OTHERWISE NOTED
- (1) STUD UP TO 6' OPENING

 (2) PROVIDE KING STUDS AT EACH END OF HEADERS AS NOTED BELOW.

 (3) STUD UP TO 6' OPENING
- (2) STUDS UP TO 8' OPENING
- 13. ALL BEAMS TO BE CONTINUOUSLY SUPPORTED LATERALLY AND SHALL REAR FULL WINTH ON THE SUPPORTING WALLS OR COLLIMNS INDICATED BEAR FULL WIDTH ON THE SUPPORTING WALLS OR COLUMNS INDICATED WITH A MINIMUM OF TWO STUDS, UNLESS OTHERWISE NOTED. ALL BEAM SPLICES SHALL OCCUR OVER SUPPORTS.

 SOLID BLOCKING TO BE PROVIDED AT ALL POINT LOADS THROUGH FLOOR
- LEVELS TO THE FOUNDATION OR TO OTHER STRUCTURAL COMPONENTS ALL LUMBER SPECIFIED ON DRAWINGS IS INTENDED FOR DRY USE ONLY IDISTURE CONTENT <19%) UNLESS OTHERWISE NOTED
- ALL WATERPROOFING AND FIRE SAFETY SYSTEMS ARE THE RESPONSIBILITY OF THE CONTRACTOR AND ARE TO BE DESIGNED AND DETAILED BY OTHERS
- DEFALLED BY UTHERS.
 ANY WOOD FRAME INTERIOR BEARING WALL STUDS THAT HAVE HOLES IN THE CENTER OF THE STUD UP TO 1" DIAMETER SHALL HAVE STUD PROTECTION SHIELDS. ALL HOLES OVER 1" IN DIAMETER FOR PLUMBING
- PROTECTION SHIELDS. ALL HOLES OVER 1" IN DIMACTER FOR PLUMBING LINES, ETC. SHILL BE REPRIZED WITH SIMPS ON INSEC OR USP STS1 STUD SHOES, PYPICAL, UNLESS OTHERWISE NOTED.

 18. BEARRING WALLS SHALL BE SHAPHED ON NOT LESS THAN ONE SIDE WITH OSB OR CYPSUM BOARD. BRIDGING SHALL BE INSTALLED NOT GREATER THAN 4 FEET APART MESSIFED VERFOLLLY FROM EITHER END OT PRE-STUD ON LEU OF SHEATHINK.

 19. DIACONAL, BRACING, SHALL BE INSTALLED. AT EACH END OF BASEMENT
- BEARING WALLS AND NOT MORE THAN 20' ON CENTER.

EXTERIOR WOOD FRAMED DECKS:

- DECKS ARE TO BE FRAMED IN ACCORDANCE WITH APPLICABLE BUILDING CODES AND AS REFERENCED ON THE STRUCTURAL PLANS, EITHER THROUGH CODE REFERENCES OR CONSTRUCTION DETAILS.
 PRESERVATIVE TREATED WOOD FRAMING TO BE SOUTHERN YELLOW
- PINE #2 OR BETTER. GUARD RAILS REQUIRED AT DECKS, DESIGN BY OTHERS TO MEET
- MINIMUM CODE REQUIREMENTS.
 PROVIDE DECK LATERAL LOAD AND BRACING CONNECTIONS PER BUILDING

RAFTER FRAMED ROOF CONSTRUCTION:

- PROVIDE 2x4x4"-0" RAFTER TIES AT 48" O.C.
 RAFTERS SHALL BE SUPPORTED BY PURLINS AND PURLIN BRACES
 AS SHOWN ON THE PLAN. PURLIN BRACES SHALL NOT BEAR ON AS SHOWN ON THE PLAN. POLICIE BRACES SHALL NOT BEAR ON ANY CEILING JOIST, STRONGBACK OR HEADER UNLESS SPECIFICALLY SHOWN ON PLAN. RAFTERS MAY BE SPLICED AT PURLIN LOCATIONS. CEILING JOISTS SHALL HAVE LATERAL SUPPORT W/ 1x4 FLAT
- BRACING ON TOP FDGE OF JOIST AT LODGE JOIST ENDS (WHERE JOISTS NOT FASTENED TO RAFTERS) OR FULL DEPTH BLOCKING. FASTEN END OF BRACING TO RAFTER OR GABLE END FRAMING
- FASTEN RAFTER AND CEILING JOIST WITH (6) 12d NAILS UNLESS
- PROVIDE VERTICAL 2x6 STRONGBACKS AT CELLING JOISTS @ 8'-0" O.C. TIE STRONGBACK ENDS TO GABLE STUDS OR RAFTERS WHERE POSSIBLE. PROVIDE BLOCKING BETWEEN TOP PLATES AND STRONGBACKS. PROVIDE 2x4 FLAT FASTENED TO EACH JOIST WITH (2) 12d NAILS. FASTEN STRONGBACK TO 2x4 FLAT WITH 12d NAILS @ 12" O.C. AND FASTENED TO EACH JOIST WITH (1) 12d TOENAIL.

WOOD TRUSSES (FLOOR & ROOF):

- THE WOOD TRUSS MANUFACTURER/FABRICATOR IS RESPONSIBLE FOR THE DESIGN OF THE WOOD TRUSSES. SUBMIT SEALED SHOP DRAWINGS AND SUPPORTING CALCULATIONS TO THE SER FOR REVIEW PRIOR TO FABRICATION. THE SER SHALL HAVE A MINIMUM OF (5) DAYS FOR PRIME THE SET STRUCE THE SET SHALL BE FOR OVERALL COMPLIANCE
 OF THE DESIGN DOCUMENTS. THE SET SHALL ASSUME NO
 RESPONSIBILITY FOR THE CORRECTNESS OF THE STRUCTURAL DESIGN
 FOR THE FORD TRUCES. FOR THE WOOD TRUSSES.
- THE WOOD TRUSSES SHALL BE DESIGNED FOR ALL REQUIRED LOADINGS AS SPECIFIED IN THE LOCAL BUILDING CODE, THE ASCE STANDARD "MINIMUM DESIGN LOADS FOR BUILDINGS AND OTHER STRUCTURES." (ASCE 7), AND THE LOADING REQUIREMENTS SHOWN ON THESE SPECIFICATIONS. THE TRUSS DRAWINGS SHALL BE COORDINATED WITH ALL OTHER CONSTRUCTION DOCUMENTS AND PROVISIONS PROVIDED FOR LOADS SHOWN ON THESE DRAWINGS INCLUDING BUT NOT LIMITED TO HVAC FOLIPMENT PIPING AND ARCHITECTURAL FIXTURES ATTACHED TO THE TRUSSES
- THE TRUSSES SHALL BE DESIGNED, FABRICATED, AND ERECTED IN ACCORDANCE WITH THE LATEST EDITION OF THE ANSI/TPI 1: "NATI DESIGN STANDARD FOR METAL PLATE CONNECTED WOOD TRUSS CONSTRUCTION"
- THE TRUSS MANUFACTURER SHALL PROVIDE ADEQUATE BRACING INFORMATION IN ACCORDANCE WITH "BUILDING COMPONENT SAFETY INFORMATION GUIDE TO GOOD PRACTICE FOR HANDLING, INSTALLING, RESTRAINING & BRACING OF METAL PLATE CONNECTED WOOD TRUSSES' (RCSI) THIS REACING BOTH TEMPORARY AND PERMANENT SHALL RE SHOWN ON THE SHOP DRAWINGS. ALSO, THE SHOP DRAWINGS SHALL SHOW THE REQUIRED ATTACHMENTS FOR THE TRUSSES.
- STUM INC. RESUMED ALMANMENTS TUM THE INCOSES.

 THE CONTRACTOR IS RESPONSIBLE FOR INSTALLAND TEMPORARY BRACING AND SHORMS FOR THE FLOOK AND ROOF TRUSSES AS REQUIRED DIRING CONSTRUCTION. AT A MINMAM, CONTRACTOR SHALL FOLLOW THE REQUIREMENTS OF THE LATEST BOSS. THE CONTRACTOR SHALL KEEP A COPY OF THE BOSS JUMBARY SHEETS ON SITE.
- THE CONTRACTOR IS RESPONSIBLE FOR INSTALLING ALL PERMANENT THE CONTROLOR'S RESPONDED FOR INSTITUTION ALL PERMANENT TRUSS BRACING SHOWN IN THE STRUCTURAL DRAWINGS AND IN THE TRUSS DESIGNS. ALL CONTINUOUS LATERAL BRACING OF WEBS REQUIRES BRACES, REFET TO BCSI SUMMARY SHEET BS POR TYPES OF DIAGONAL BRACES TO PROVIDE AT EACH CONTINUOUS LATERAL BRACE LINE. SUCH DIAGONAL BRACES SHALL NOT BE SPACED MORE THAN 20 FEET O.C. DIAGONAL BRACES SHALL BE FASTENED TO EACH TRUSS WEB WITH A MINIMUM OF TWO 10d FACE NAILS. WHERE CONTINUOUS LATERA BRACING CANNOT BE INSTALLED, DUE TO A MINIMUM OF THREE ADJACENT TRUSSES NOT BEING IDENTICAL. THE CONTRACTOR SHALL COORDINATE WITH THE TRUSS SPECIALTY ENGINEER/MANUFACTURER TO DETERMINE WHAT TYPE OF ALTERNATE BRACE (I.E., T OR L BRACE, ETC.) IS REQUIRED
- ANY CHORDS OR TRUSS WERS SHOWN ON THESE DRAWINGS HAVE REEN SHOWN AS A REFERENCE ONLY. THE FINAL DESIGN OF THE TRUSSES SHALL BE PER THE MANUFACTURER.
- TRUSS LAYOUT AND PLACEMENT BY MANUFACTURER TO COINCIDE WITH THE SUPPORT LOCATIONS SHOWN ON THE SEALED STRUCTURAL DRAWINGS. TRUSS PROFILES TO BE SEALED BY THE TRUSS MANUFACTURER. TRUSS PLANS TO BE COORDINATED WITH THE SEALED
- TRUSS MANUFACTURER TO PROVIDE REQUIRED UPLIFT CONNECTORS FOR ALL TRUSSES
- PROVIDE SIMPSON H2.5A, USP RT7 OR EQUIVALENT AT EACH TRUSS TO TOP PLATE CONNECTION, UNLESS OTHERWISE NOTED.

- WOOD STRUCTURAL PANELS:

 1. FABRICATION AND PLACEMENT OF STRUCTURAL WOOD SHEATHING SHALL BE IN ACCORDANCE WITH THE APA DESIGN/CONSTRUCTION GUIDE "RESIDENTIAL AND COMMERCIAL," AND ALL OTHER APPLICABLE
- REQUIRED WOOD SHEATHING SHALL BEAR THE MARK OF THE
- APA.

 WOOD WALL SHEATHING SHALL COMPLY WITH THE REQUIREMENTS OF LOCAL BUILDING CODES FOR THE APPROPRIATE STATE AS INDICATED ON THESE DRAWINGS. REFER TO WALL BRACING NOTES IN PLAN SET FOR MORE INFORMATION. EXTERIOR WALLS TO BE FULLY SHEATHED LISING 74." OSR OR PLYWOOD MINIMUM AT RRACED WALL PANELS PROVIDE BLOCKING AT ALL SHEET EDGES NOT FALLING ON STUDS
- OR PLATES.
 ROOF SHEATHING SHALL BE APA RATED SHEATHING EXPOSURE 1 OR
 2. ROOF SHEATHING SHALL BE CONTINUOUS OVER TWO SUPPORTS MINIMUM AND ATTACHED TO ITS SUPPORTING ROOF FRAMING WITH MINIMUM AND ATTACHED IT IS SOFTWIND ROOF FRAMING WITH 88 NAILS AT 6" O.C. AT PANEL EDGES AND AT 12" O.C. IN PANEL FIELD UNLESS OTHERWISE NOTED ON THE PLANS. SHEATHING SHALL BE APPLIED WITH THE LONG DIRECTION PERPENDICULAR TO FRAMING BE APPLIED WITH THE LONG DIRECTION PERPENDICULAR TO FRAMIN'S SHEATHING SHALL HAVE A SPAN RATING CONSISTENT WITH THE FRAMING SPACING, PROVIDE SUITABLE EDGE SUPPORT BY USE OF PLYWOOD CLIPS OR LUMBER BLOCKING UNLESS OTHERWISE NOTED. PANEL END JOINTS SHALL OCCUR OVER FRAMING, ROOF SHEATHING
- TO BE $\frac{7}{6}$ OSB MINIMUM. WOOD FLOOR SHEATHING SHALL BE APA RATED SHEATHING EXPOSURE 1 OR 2. ATTACH SHEATHING TO ITS SUPPORTING FRAMING WITH (1) 104 NAIL AT 6" O.C. AT PANEL EDGES AND AT 12" O.C. IN PANEL FIELD UNLESS OTHERWISE NOTED ON THE PLANS. SHEATHING SHALL BE APPLIED PERPENDICULAR TO FRAMING SHEATHING SHALL HAVE A SPAN RATING CONSISTENT WITH THE SHEATHING SHALL HAVE A SHAN KATING CONSISTENT WITH THE FRAMING SPACING. PROVIDE SUITABLE EDGE SUPPORT BY USE OF T&G PLYWOOD OR LUMBER BLOCKING UNLESS OTHERWISE NOTED. PANEL END JOINTS SHALL OCCUR OVER FRAMING.
- SHEATHING SHALL HAVE A 1/4" GAP AT PANEL ENDS AND EDGES AS RECOMMENDED IN ACCORDANCE WITH THE APA.

STRUCTURAL FIBERBOARD PANELS

- OCTURAL FIBERBOARD SHEATHING SHALL ONLY BE USED WHERE SPECIFICALLY NOTED ON THE STRUCTURAL PLANS.
 FABRICATION AND PLACEMENT OF STRUCTURAL FIBERBOARD
 - SHEATHING SHALL BE IN ACCORDANCE WITH THE APPLICABLE AFA STANDARDS
- FIBERBOARD WALL SHEATHING SHALL COMPLY WITH THE REQUIREMENTS OF LOCAL BUILDING CODES FOR THE APPROPRIATE STATE AS INDICATED ON THESE DRAWINGS. REFER TO WALL BRACING NOTES IN PLAN SET FOR MORE INFORMATION
- SHEATHING SHALL HAVE A 1/8" GAP AT PANEL ENDS AND EDGES AS RECOMMENDED IN ACCORDANCE WITH THE AFA.


- STRUCTURAL STEEL:

 1. STRUCTURAL STEEL SHALL BE FABRICATED AND ERECTED IN ACCORDANCE WITH THE AMERICAN INSTITUTE OF STEEL CONSTRUCTION "CODE OF STANDARD PRACTICE FOR STEEL BUILDINGS AND BRIDGES" AND OF THE MANUAL OF STEEL CONSTRUCTION "LOAD RESISTANCE FACTOR DESIGN" LATEST EDITIONS.
- ALL STEEL SHALL HAVE A MINIMUM YIELD STRESS (F,) OF 50 KSI UNLESS OTHERWISE NOTED.
 WELDING SHALL CONFORM TO THE LATEST EDITION OF THE AMERICAN WELDING SOCIETY'S STRUCTURAL WELDING CODE AWA
- DII.1. ELECTRODES FOR SHOP AND FIELDING WELDING SHALL BE CLASS E70XX. ALL WELDING SHALL BE PERFORMED BY A CERTIFIED WELDER PER THE ABOVE STANDARDS. ALL STEEL BEAMS TO BE SUPPORTED AT EACH END WITH A
- MINIMUM BEARING LENGTH OF 3½" AND FULL FLANGE WIDTH UNLESS OTHERWISE NOTED. BEAMS MUST BE ATTACHED AT EACH END WITH A MINIMUM OF FOUR 16d NAILS OR (2) 1/2" x 4" LAG SCREWS UNLESS OTHERWISE NOTED.

 INSTALL 2x WOOD PLATE ON TOP OF STEEL BEAMS, RIPPED TO
- MATCH BEAM WIDTH, FASTEN PLATE TO BEAM W/ HILTI X-DNI 52 P8 PINS AT 12" O.C. STAGGERED OR 1/2" DIAMETER BOLTS AT 24"

MECHANICAL FASTENERS:

- ALL MEAL HARDWARE AND FASTENERS TO BE SIMPSON STRONG-TIE OR APPROVED EQUIVALENT. ALL HARDWARE AND FASTENERS IN CONTACT WITH PRESERVATIVE
- PRESSURE TREATED LUMBER SHALL BE HOT DIPPED GALVANIZED IN ACCORDANCE WITH ASTM A 153 G-185
- MANY OF THE NEW PRESSURE TREATED WOODS USE CHEMICALS
 THAT ARE CORROSIVE TO STEEL. IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIEY THE TYPE OF WOOD TREATMENT AND SELECT APPROPRIATE CONNECTORS THAT WILL RESIST THE APPLICABLE CORROSIVE CHEMICALS.



BRICK	VENEER LINTEL SC	HEDULE
SPAN	LINTEL SIZE	END BEARING
UP TO 3'-0"	3½"x3½"x¼"	4"
UP TO 6'-3"	5"x3½"x5/6" L.L.V.	8"
UP TO 9'-6"	6"x3½"x5/6" L.L.V.	12*
l t	NOT DESIGNED TO BE BOLTE INLESS SPECIFIED ON UNIT PL	ANS.
SDANS OVER	A'_O" SHALL BE SHORED LID	LINTIL CLIPED



Q 8951

RINC

Ш

ш

NGINE

Ш

S

I

a.

 \leq

130

2


Carolina

Not

Structural

eneral d Š Project #: 105-19000 Designed By: KRK Checked By: Issue Date: 1/1/19

1/4"=1'-0" @ 22x34



ENGINEERING
FE, SUITE 201, CUAKERTOWN, PA 18951
COM
(215) 804-4449 KSE



LEGEND

======= ⇒ BEARING WALL ABOVE

PROVIDE SOLID BLOCKING

WITHIN FLOOR SYSTEM TO MATCH POST SIZE ABOVE.

 $\hbox{${\tt IIIIIIIII}$} \implies \hbox{${\tt INTERIOR}$} \hbox{${\tt BEARING}$} \hbox{${\tt WALL}$}$

BRACED WALL PANEL
48" WSP (SEE KSE STRUCTURA (SEE KSE STRUCTURAL DETAILS SET FOR BRACED WALL PANEL SHEATHING FASTENING & BLOCKING DETAILS)

ZZZZZZZZ ⇒ LOCATION OF DOOR ABOVE

REFER TO KSE STRUCTURAL DETAILS SET FOR GENERAL STRUCTURAL NOTES AND TYPICAL DETAILS




Monolithic Slab Fou Elevations 'A-1', 'A Dogwood Model — I Up to 130 M.P.H. Carolina Division Project #: 105-16007 Designed By: KRK Checked By:

Issue Date: 4/9/19 Re-Issue: 10/10/22


 \approx Plan -3′&

Foundation F ', 'A-2', 'A-- LH


Scale: 1/8"=1'-0" @ 11x17 1/4"=1'-0" @ 22x34




PARTIAL FOUNDATION PLAN OPTIONAL EXTENDED COVERED PATIO



MONOLITHIC SLAB FOUNDATION PLAN OPTIONAL 1-CAR CARRIAGE GARAGE



PARTIAL FOUNDATION PLAN OPTIONAL 2-CAR SIDE LOAD GARAGE ELEVATION A





PROVIDE SOLID BLOCKING

WITHIN FLOOR SYSTEM TO MATCH POST SIZE ABOVE. ======= ⇒ BEARING WALL ABOVE

 $\hbox{${\rm IIIIIIIII}$} \implies \hbox{${\rm INTERIOR}$} \hbox{${\rm BEARING}$} \hbox{${\rm WALL}$}$ BRACED WALL PANEL
48" WSP (SEE KSE STRUCTURAL (SEE KSE STRUCTURAL DETAILS SET FOR BRACED WALL PANEL SHEATHING FASTENING &

BLOCKING DETAILS) ZZZZZZZZ ⇒ LOCATION OF DOOR ABOVE

REFER TO KSE STRUCTURAL DETAILS SET FOR GENERAL STRUCTURAL NOTES AND TYPICAL DETAILS



ENGINEERING
FE, SUITE 201, CUAKERTOWN, PA 18951
COM
(215) 804-4449 KSE



Plans Foundation Options Dogwood Model — I Up to 130 M.P.H. Carolina Division Slab

Monolithic Project #: 105-16007

Designed By: KRK Checked By: Issue Date: 4/9/19 Re-Issue: 10/10/22

Scale: 1/8"=1'-0" @ 11x17 1/4"=1'-0" @ 22x34





Stone

≩



REFER TO KSE STRUCTURAL DETAILS SET FOR GENERAL STRUCTURAL NOTES AND TYPICAL DETAILS

PLAN DESIGNED WITH 9' WALL PLATES

FLOOR FRAMING TO BE 14" DEEP TJI 110 SERIES OR EQUAL, SPACING PER MANUFACTURER.

KEYNOTES:

32" CS-WSP

pantry ER SUPPLIER

14" I-JOISTS PER SUPPLIER

14" I-JOISTS PER SUPPLIER

4x4 P.T. POST W/ SIMPSON ABA44 BASE AND

BCS2-2/4 CAP (TYP.)

CS-WSP

2-car

garage

(3)134"x14" LVL CONT.

CS-WSP

LINE OF BRICK ® 20 CELEVATION 'A-2' W/ BRICK, CS-PF

VERIFY PER ELEVATION

RIM BOARD

(1)2×10 (1)2×10 casual dining 14" I-JOISTS PER SUPPLIER

kitchen

dining

room

RIM BOARD

SECOND FLOOR FRAMING PLAN

ELEVATIONS 'A-1', 'A-2' & 'A-3' W/ STONE

covered porch

DOUBLE JOIST

foyer

47* -WSP

67" CS-WSP

14" I-JOISTS PER SUPPLIER

family room

storage

powder

14" I-JOISTS PER SUPPLIER

-2x4 LEDGER w/ (2)12d NAILS @ 16" O.C.

(1)2x10 (1)2x10

COFFERED

CEILING

CS-EVW(2) DESIGNED TO REPLACE 95" OF CS-WSP. STRAP AROUND OPENIN'S PER DETAIL C/SD-3

room

study (3)134"x14" LVL FLUSH

(4) INSTALL ONE PANEL CS-PF PORTAL FRAME PER DETAIL A OR B/SD-4.

5) INSTALL TWO PANEL CS-PF PORTAL FRAME PER DETAIL A OR B/SD-4.




Carolina Division Elevations Dogwood 1 Up to Project #: 105-16007 Designed By: KRK Checked By: Issue Date: 4/9/19 Re-Issue: 10/10/22 Scale: 1/8"=1'-0" @ 11x17 1/4"=1'-0" @ 22x34


levations


130 M.P.H.


Model




PARTIAL FRAMING PLAN OPTIONAL EXTENDED COVERED PATIO
















PROVIDE SOLID BLOCKING

⇒ WITHIN FLOOR SYSTEM TO

MATCH POST SIZE ABOVE.

⇒ BRACED WALL PANEL (SEE KSE STRUCTURAL DETAILS SET FOR BRACED WALL PANEL SHEATHING FASTENING & BLOCKING DETAILS)

REFER TO KSE STRUCTURAL DETAILS SET FOR GENERAL STRUCTURAL NOTES AND TYPICAL DETAILS

PLAN DESIGNED WITH 9' WALL PLATES

FLOOR FRAMING TO BE 14" DEEP TJI 110 SERIES OR EQUAL, SPACING PER MANUFACTURER.

KEYNOTES:

(4) INSTALL ONE PANEL CS-PF PORTAL FRAME PER DETAIL A OR B/SD-4.

(5) INSTALL TWO PANEL CS-PF PORTAL FRAME PER DETAIL A OR B/SD-4.



HOH

ENGINEERING
E. SUITE 201, CUAKERTOWN, PA 18951
com (215) 804 - 4449

SE

Second Floor Framing

Second Floor Framing

Populous Table Pales

Second Floor Framing

Populous Table Pales

Carolina Division

Plans

Issue Date: 4/9/19
Re-Issue: 10/10/22
Scale: 1/8"=1'-0" @ 11x17
1/4"=1'-0" @ 22x34

Checked By:

S - 2.3



Stone

≥

Model

Elevations Dogwood levations


Project #: 105-16007

Designed By: KRK

Checked By: Issue Date: 4/9/19 Re-Issue: 10/10/22 Scale: 1/8"=1'-0" @ 11x17 1/4"=1'-0" @ 22x34

Carolina Division

Up to



TRAY CEILING

> BLOCKING DETAILS) REFER TO KSE STRUCTURAL DETAILS SET FOR GENERAL STRUCTURAL NOTES AND TYPICAL DETAILS

PLAN DESIGNED WITH 8' WALL PLATES

KEYNOTES: CONNECT STUD AT END OF BRACED
WALL PANEL TO FRAMING BELOW WITH A
30" LONG SIMPSON CS22 COIL STRAP WITH MIN 8-10d NAILS EACH END.

(10) 8 x8' HVAC PLATFORM TRUSSES DESIGNED TO SUPPORT HVAC UNITS.

(1) 2x6 OVERFRAMING W/ 2x8 RIDGE AND VALLEY PLATES OR VALLEY SET TRUSSES @ 24" O.C. (TYP.)



ROOF FRAMING PLAN ELEVATIONS 'A-1', 'A-2' & 'A-3' W/ STONE

ROOF TRUSSES DESIGNED TO FORM FLOOR BELOW.

loft

-ROOF TRUSSES @ 24" O.C.

> owner's bedroom /

> > -75

ROOF TRUSSES-

bedroom 3

==!

ROOF TRUSSES @ 24" O.C.

LINE OF OPT. TRAY CEILING

open to

below

(11)

ROOF TRUSSES-@ 24" O.C.

bath 2

w.i.c.

LINE UP GIRDER-Y TRUSS WITH INSIDE FACE OF WALL

ROOF TRUSSES DESIGNED TO FORM FLOOR BELOW.

w.i.c.

w.i.c.

bedroom 4

ROOF TRUSSES

(1)2x10 (1)2x10

bedroom 2

① \ 32 \cs-wsp

owner's

bath


-===











(C)METHOD GB(1) AND GB(2) INTERSECTION DETAILS

(A) TYPICAL BRACED WALL PANEL TO FLOOR/CEILING CONNECTION BRACED WALL PANELS PARALLEL TO 1-JOISTS B TYPICAL BRACED WALL PANEL TO FLOOR/CEILING CONNECTION BRACED WALL PANELS PERPENDICULAR TO 1-JOISTS

WALL PANEL

2x4 CLEAT WITH (2)10d NAILS AT CHORDS AND

(4)10d NAILS AT BLOCKING (TYP.)-

8d TOENAILS AT 6" O.C.

ALONG BRACED WALL PANEL

-BRACED WALL PANEL

BELOW WALL

- 8d NAIL @ 6" O.C. AT ALL EDGES AND 12" O.C. TYPICAL AT ALL OTHER

MEMBERS

∼16d NAIL

OUTSIDE CORNER PLAN VIEW

@ 12" O.C.

-GYPSUM BOARD

-(3)16d NAILS AT

16" O.C. ALONG BRACED WALL PANEL

LSL/LVL BLOCKING AT 16" O.C. ALONG BRACED WALL PANEL

(3)8d TOENAILS

EACH BLOCK ALONG BRACED

WALL PANEL


-BRACED WALL

-(3)16d NAILS EACH BLOCK ALONG BRACED WALL PANEL

LSL/LVL BLOCKING AT 16" O.C. ALONG

BRACED WALL PANEL

PANEL



(D) TYPICAL EXTERIOR CORNER WALL FRAMING

EXTERIOR SHEATHING

-CONTINUOUS RIM LOCATE JOIST BOARD ON WALL-\

-8d TOENAILS AT 6" O.C.

ALONG BRACED WALL
PANEL

-BRACED WALL

-(3)16d NAILS AT

16" O.C. ALONG BRACED WALL PANEL

凼

-CONTINUOUS RIM

BOARD

GYPSUM BOARD

16d NAIL

@ 12"00 EXTERIOR SHEATHING-

INSIDE CORNER PLAN VIEW

PANEL

E ROOF TRUSS BEARING/BLOCKING AT BRACED WALL PANELS ONLY REQUIRED AT BRACED WALL PANELS



Details

Scale: 1/8"=1'-0" @ 11x17 1/4"=1'-0" @ 22x34

130 M.P.H.

9 Up to North

Carolina

1/2" (MIN) GYPSUM WALLBOARD. FASTEN TO WALL ALL SUPPORTS (STUDS, PLATES, BLOCKING) WITH

1.25" TYPE W SCREWS AT 7" O.C.

(OR 5d COOLER NAILS AT 7" O.C.)

BRACED

BRACED WALL INTERSECTIONS MAY

BE FRAMED USING EITHER THE 3-STUD OR THE T-PLATE METHOD.

(C)METHOD GB(1) AND GB(2) INTERSECTION DETAILS

2x6 FULL HEIGHT STUD AT WALL INTERSECTION -(2x8 STUD AT

INTERSECTING 2x6 WALL)

"T" PLATE WALL INTERSECTION

2x4 BLOCKING BTWN VERTICAL WALL STUDS AT ALL HORIZONTAL GYPSUM

SHEATHING JOINTS.

3-STUD WALL INTERSECTION





130 M.P.H. 9 Up to North


Carolina

105-190<u>00</u> Designed By:KRK Checked By:


Issue Date: 1/1/19

Scale: 1/8"=1'-0" @ 11x17 1/4"=1'-0" @ 22x34





B TYPICAL BRACED WALL PANEL TO FLOOR / CEILING CONNECTION BRACED WALL PANELS PERPENDICULAR TO TRUSSES



(D) TYPICAL EXTERIOR CORNER WALL FRAMING

EXTERIOR SHEATHING

GYPSUM BOARD-

16d NAIL

@ 12" 0.0 EXTERIOR SHEATHING

INSIDE CORNER PLAN VIEW

- 8d NAIL @ 6" O.C. AT ALL EDGES AND 12" O.C. TYPICAL AT ALL OTHER

MEMBERS

∼16d NAIL

OUTSIDE CORNER PLAN VIEW


@ 12" O.C.

-GYPSUM BOARD


E ROOF TRUSS BEARING/BLOCKING AT BRACED WALL PANELS ONLY REQUIRED AT BRACED WALL PANELS








A TYPICAL HOLD DOWN DETAIL



B TYPICAL HOLD DOWN DETAIL



(C)HOLD DOWN AT STEMWALL SLAB FOUNDATION

-FLOOR SYSTEM,

-2x6 EXTERIOR WALL


-A36 ALL THREAD ROD DRILLED

AND EPOXIED 6" INTO FOOTING USING SIMPSON "SET"/"ET" OR USP CIA-GEL ADHESIVE.

SEE PLANS

STRAP, SEE PLANS-FOR TYPE AND


LOCATION.




(C)HOLD DOWN AT STEMWALL SLAB

-SIMPSON HOLD DOWN INSTALLED PER HOLD DOWN SCHEDULE THIS SHEET

- A36 ALL THREAD ROD DRILLED AND EPOXIED 6" INTO FOOTING USING SIMPSON "SET" OR "ET" ADHESIVE.



(E)HOLD DOWN AT CRAWL SPACE FOUNDATION



F HOLD DOWN AT BASEMENT FOUNDATION

G HOLD DOWN AT BASEMENT FOUNDATION STEM WALL

	HOLD	DOWN SCH	EDULE
HOLD SIMPSON	DOWN USP	ALL THREAD ROD	FASTENERS
LTTP2	N.A.	½" DIA.	(12)0.148"x2½" LONG NAILS
HTT4	HTT16	%" DIA.	(18)0.148"x2½" LONG NAILS
HTT5	HTT45	%" DIA.	(26)0.148"x2½" LONG NAILS

	HOLD	DOWN SCH	EDULE
HOLD SIMPSON	DOWN USP	ALL THREAD ROD	FASTENERS
LTTP2	N.A.	3/5" DIA.	(12)0.148"x2½" LONG NAILS
HTT4	HTT16		(18)0.148"x2½" LONG NAILS
HTT5	HTT45	%" DIA.	(26)0.148"x2½" LONG NAILS




130 M.P.H. Carolina

9 Up to North

Details

Down

PIOH




B METHOD CS-PF: CONTINUOUS PORTAL FRAME PANEL CONSTRUCTION TWO BRACED WALL SEGMENTS

	BRACED WALI	_ PANEL AN	ND ENGINEERED SHEAR WALL SCHEDULE
PANEL TYPES	PANEL TYPE	MATERIAL	FASTENERS
WSP	INTERMITTENT WOOD STRUCTURAL PANEL	7/16" OSB	6D OR 8D COMMON NAILS AT 6" O.C. AT SHEET EDGES AND 12" O.C. AT INTERMEDIATE SUPPORTS. <u>ENGINEERED ALTERNATIVE</u> : 16 GAGE BY 1.75" LONG STAPLES AT 3" O.C. AT SHEET EDGES AND 6" O.C. AT INTERMEDIATE SUPPORTS
GB(1)	INTERMITTENT GYPSUM BOARD (SHEATHING ONE FACE OF WALL)	1/2* GYPSUM	1.5" LONG GALV. ROOFING NAILS, 6d COMMON NAILS, OR 1.25" LONG TYPE W DRYWALL SCREWS AT 7" O.C. AT SHEET EDGES AND INTERMEDIATE SUPPORTS.
GB(1)-4	INTERMITTENT GYPSUM BOARD (SHEATHING ONE FACE OF WALL)	1/2" GYPSUM	1.5" LONG GALV. ROOFING NAILS, 6d COMMON NAILS, OR 1.25" LONG TYPE W DRYWALL SCREWS AT 4" O.C. AT SHEET EDGES AND INTERMEDIATE SUPPORTS.
GB(2)	INTERMITTENT GYPSUM BOARD (SHEATHING BOTH FACES OF WALL)	1/2" GYPSUM	1.5" LONG GALV. ROOFING NAILS, 6d COMMON NAILS, OR 1.25" LONG TYPE W DRYWALL SCREWS AT 7" O.C. AT SHEET EDGES AND INTERMEDIATE SUPPORTS.
CS-WSP	CONTINUOUS SHEATHED WOOD STRUCTURAL PANEL	7/16" OSB	6D OR 8D COMMON NAILS AT 6" O.C. AT SHEET EDGES AND 12" O.C. AT INTERMEDIATE SUPPORTS. <u>ENGINEERED ALTERNATIVE</u> : 16 GAGE BY 1.75" LONG STAPLES AT 3" O.C. AT SHEET EDGES AND 6" O.C. AT INTERMEDIATE SUPPORTS
CS-PF	CONTINUOUS SHEATHED PORTAL FRAME	7/16" OSB	NAILING PER DETAIL
PFH	PORTAL FRAME WITH HOLD DOWNS	7/16" OSB	NAILING PER DETAIL
CS-ESW(1)	ENGINEERED SHEAR WALL, TYPE 1	7/16" OSB	BD COMMON NAILS AT 6" O.C. AT SHEET EDGES AND 12" O.C. AT INTERMEDIATE SUPPORTS. CONTINUOUS OSB AROUND DOOR/WINDOW OPENINGS
CS-ESW(2)	ENGINEERED SHEAR WALL, TYPE 2	7/16" OSB	8D COMMON NAILS AT 4" O.C. AT SHEET EDGES AND 12" O.C. AT INTERMEDIATE SUPPORTS. CONTINUOUS OSB AROUND DOOR/WINDOW OPENINGS
CS-ESW(3)	ENGINEERED SHEAR WALL, TYPE 3	7/16" OSB	8D COMMON NAILS AT 3" O.C. AT SHEET EDGES AND 12" O.C. AT INTERMEDIATE SUPPORTS. CONTINUOUS OSB AROUND DOOR/WINDOW OPENINGS

BRACED WALL PANEL NOTES:

- ALL BRACED WALL PANELS, EXCEPT GB(1) & GB(2), SHALL HAVE 2x BLOCKING BETWEEN WALL STUDS AT ALL HORIZONTAL SHEET EDGES.
- 2. PROVIDE NAILING/BLOCKING ABOVE AND BELOW ALL BRACED WALL PANELS PER KSE BRACED WALL DETAILS.
- SHEATH ALL EXTERIOR WALLS OF THE HOUSE WITH 1/46" O.S.B., OR 15/32" PLYWOOD, FASTENED PER IRC. AT EXTERIOR CORNERS SHEATHING SHALL BE FASTENED PER KSE BRACED WALL DETAILS. AT INTERIOR WALL INTERSECTIONS, FASTEN STUDS & WALL BRACING PER KSE BRACED WALL DETAILS.
- BRACED WALL PANELS AND ENGINEERED SHEAR WALLS ARE PROVIDED PER IRC. PANEL LENGTHS SHOWN ON PLANS ARE THE MINIMUM LENGTH REQUIRED.



© WINDOW OR DOOR REINFORCEMENT IN ENGINEERED SHEAR WALL ONLY REQUIRED WHERE SPECIFED ON PLANS





Detail \approx Notes Wall Braced

Carolina 2 9 105-19000

130 M.P.H.

Designed By:KRK Checked By:

Issue Date: 1/1/19

1/4"=1'-0" @ 22x34

METHOD PFH: PORTAL FRAME WITH HOLD-DOWNS

MONOLITHIC SLAB OR BASEMENT FOUNDATION






Detail Frame Portal

Up to North 105-19000 Designed By: KRK


130 M.P.H.

Checked By: Issue Date: 1/1/19


1/4"=1'-0" @ 22x34




C I-JOIST LADDER BLOCKING AS REQUIRED @ PARALLEL WALLS



E BUILT-UP STUD DETAIL SUPPORTING BEAM



BALLOON FRAMED WALL DETAIL N.T.S.



130 M.P.H. Carolina

Designed By: KRK
Checked By:
Issue Date: 1/1/19

Scale: 1/8"=1'-0" @ 11x17 1/4"=1'-0" @ 22x34

SD-5








Miscellaneous Framing Detail


130 M.P.H. Carolina


Issue Date: 1/1/19
Re-Issue:
Scale: 1/8"=1'-0" @ 11x

Scale: 1/8"=1'-0" @ 11x17 1/4"=1'-0" @ 22x34

CD 6







8" MINIMIM

EXTERIOR GRADE~

MONOLITHIC CONCRETES

12" MINIMUM

BELOW GRADE

RECESSED SHOWER

FOUNDATION SECTION
THICKENED SLAB @ RECESSED SHOWER

CONCRETE SLAB, SEE PLAN

-ISOLATED PAD FOOTING, SEE PLAN FOR SIZE

K FOUNDATION SECTION ISOLATED PAD FOOTING

-INSTALL ½" DIA. ANCHOR BOLTS, SEE FOUNDATION NOTES.

GROUP 1 CLASSIFIED SOIL

-4" GRAVEL FILL OR

-THICKENED SLAB, SEE PLAN.

CONCRETE SLAB POURED

4 4

WIDTH

J FOUNDATION SECTION THICKENED SLAB

MONOLITHICALLY WITH FOOTING, SEE PLAN, - FOOTING, SEE PLAN.

8" DEEP x 16" WIDE THICKENED SLAB, SEE PLAN.



Details

Project #: 105-19000
Designed By: KRK
Checked By:

130 M.P.H.

9

Carolina


ENGINEERING
E. SUITE 201, QUAKERTOWN, PA 18951
com (215) 804-4449

S

Issue Date: 1/1/19
Re-Issue:
Scale: 1/8"=1'-0" @ 11

Scale: 1/8"=1'-0" @ 11x17 1/4"=1'-0" @ 22x34

SD-7



THICKENED SLAB @ RECESSED SHOWER

S

ENGINEERING
E. SUITE 201, QUAKERTOWN, PA 18951
com (215) 804-4449

130 M.P.H. Carolina 105-19000

Designed By: KRK Checked By: Issue Date: 1/1/19

Scale: 1/8"=1"-0" @ 11x17 1/4"=1'-0" @ 22x34



130 M.P.H. Carolina 9 ra w Up to North 105-19000 Designed By: KRK Checked By: Issue Date: 1/1/19

Scale: 1/8"=1"-0" @ 11x17 1/4"=1"-0" @ 22x34

VERTICALLY AND SHALL
SUPPORT NOT MORE THAN 2
SQUARE FEET OF WALL AREA— -ENGINEERED RIM BOARD FLOOR JOIST, FLOOR JOIST, SEE PLAN MASONRY VENEER-INSTALL ½" DIA. ANCHOR BOLTS, SEE FOUNDATION -P.T. PLATE NOTES. -INSTALL ½" DIA. ANCHOR BOLTS, SEE FOUNDATION P.T. PLATE 4'-0" MAX. UNBALANCED F NOTES. -8" CMU WALL, TOP COURSE GROUTED SOLID -8" CMU WALL TOP TURN DOWN PORCH — SLAB TO BELOW TOP OF FOUNDATION WALL TURN DOWN PORCH-SLAB TO BELOW TOP COURSE GROUTED SOLID -12" CMU GROUTED SOLID @ BRICK OF FOUNDATION WALL CONCRETE FOOTING, CONCRETE FOOTING, SEE PLAN. SEE PLAN SEE ARCHITECTURAL DETAILS FOR WATERPROOFING AT PORCH SLAB/WOOD FRAMING. C FOUNDATION SECTION
EXTERIOR WALL AT PORCH FOUNDATION SECTION

EXTERIOR WALL AT PORCH W/ MASONRY VENEER

-2x STUD WALL W/ PLATE, SEE PLAN.

-CONCRETE SLAB POURED MONOLITHICALLY WITH

FOOTING, SEE PLAN.

4" GRAVEL FILL OR

CONCRETE FOOTING,

-COMPACTED SOIL

SEE PLAN

GROUP 1 CLASSIFIED SOIL

VENEER TIES SHALL BE SPACED NOT MORE THAN

24" O.C. HORIZONTALLY AND

P.T. PLATE

FOUNDATION SECTION

GARAGE SPACE

-2x STUD WALL W/ PLATE, SEE PLAN.

FLOOR JOIST,
SEE PLAN
INSTALL ½" DIA. ANCHOR
BOLTS, SEE FOUNDATION
NOTES.

12" CMU GROUTED

CONCRETE FOOTING,

-2x STUD WALL W/ PLATE, SEE PLAN.

FLOOR JOIST,

-ENGINEERED RIM BOARD

INSTALL ½" DIA. ANCHOR BOLTS, SEE FOUNDATION NOTES.

-8" CMU WALL TOP COURSE GROUTED SOLID

-CONCRETE FOOTING,

SEE PLAN.


SOLID @ BRICK

P.T. PLATE


SEE PLAN.

LIVING SPACE

-ENGINEERED RIM BOARD







VENEER TIES SHALL BE SPACED NOT MORE THAN

-2x STUD WALL W/ PLATE, SEE PLAN.

-FLOOR JOIST,

SEE PLAN

INSTALL ½" DIA. ANCHOR-BOLTS, SEE FOUNDATION NOTES.

2'-0" MAXIMUM

EXTERIOR GRADE-

INSTALL ½" DIA. ANCHOR BOLTS. SEE FOUNDATION

GRAD

NOTES

EXTERIOR GRADE

GIRDER PER-

CMU PIER GROUTED — SOLID, SEE SCHEDULE FOR SIZE AND HEIGHT

PLAN

ABOVE GRADE -

-ENGINEERED RIM BOARD

-8" CMU WALL TOP COURSE GROUTED SOLID

CONCRETE FOOTING,


SEE PLAN.


A FOUNDATION SECTION EXTERIOR WALL


FLOOR JOIST, SEE PLAN


FOUNDATION SECTION INTERIOR PIER

CONCRETE FOOTING SEE PLAN.













G FOUNDATION SECTION
GARAGE DOOR

RECESS @

GARAGE DOOR

TIEN AND TOOTHING SOTTEBOLE		
PIER HEIGHT PIER SIZE MIN. FOOTING SIZE		
UP TO 2'-8" 8" x 16" 24" x 24" x 12" U.N.O.		
UP TO 5'-4" 16" x 16" 24" x 24" x 12" U.N.O.		
UP TO 8'-0" 16" x 16" 30" x 30" x 12" U.N.O.		
NOTE:		
PIERS SHALL BE CAPPED WITH 8" OF SOLID		
MASONRY OR CONCRETE OR TOP COURSE FILLED		
SOLID WITH CONCRETE/MORTAR.		
PIERS OVER 5'-4" SHALL BE BE FILLED SOLIDLY		
WITH CONCRETE OR TYPE M OR S MORTAR.		
FOR PIERS OVER 8'-0" CONTACT KSE		
ENGINEERING FOR PIER AND FOOTING DESIGN.		

ENGINEERING
E. SUITE 201, QUAKERTOWN, PA 18951
com (215) 804-4449

S

Details Foundation Basement

105-19000 Designed By:KRK Checked By:


130 M.P.H.

Carolina

Issue Date: 1/1/19

1/4"=1'-0" @ 22x34






VENEER


GRADE

Ħ,

JUBALANCED F



A FOUNDATION ELEVATION STEPPED SIDEWALL



NOTE: BLOCKING AND SIMPSON STRAPS ARE NOT REQUIRED IF WALL IS SHEATHED ON ONE FACE WITH GYPSUM WALL BOARD

(D) BASEMENT BEARING WALL BRACING DETAIL

Wall Foundation Basement

Details

Up to North 105-19000 Designed By:KRK Checked By:

130 M.P.H. Carolina

þ

Issue Date: 1/1/19

Scale: 1/8"=1'-0" @ 11x17 1/4"=1'-0" @ 22x34