

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: Elyse Meadow

LOT 59

Pump
INITIAL SYSTEM: APPROVED 25% REDUCTION

Pump
REPAIR Approved 25% Reduction

DISTRIBUTION: SERIAL

DISTRIBUTION SERIAL

BENCHMARK: 100.0

LOCATION FL To S 60/61

NO. BEDROOMS: 3

LTAR 0.3 gpd/ft²

LINE	FLAG COLOR	ELEVATION	LENGTH
1	B	97.50	45
2	W	97.33	60
3	R	96.50	90
4	B	95.67	95
5A	W	95.33	10
			300
5B	W	95.33	90
6	R	94.93	90
7	B	94.17	90
8	W	93.67	90
9	R	93.08	90
			440

BY B.C. Raynor

DATE 03/15/2024

TYPICAL PROFILE

THERE SHALL BE NO GRADING,

0-15 LS VFR GR

CUTTING, LOGGING OR OTHER SOIL

15-36 SCLAY Fi SBK

DISTURBANCE IN SEPTIC AREA

UR2 ≥ 28" (Bc + mid)

HEALTH DEPARTMENT USE ONLY.

DESIGNS DO NOT GUARANTEE FUNCTIONALITY

Southeastern Soil & Environmental Associates LLC
PO Box 9321 Fayetteville, NC 28311
Mike@southeasternsoil.com
(910) 822-4540

~~Elyse-Meadow~~
Preliminary Septic Evaluation

