

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: Elyse Meadow

INITIAL SYSTEM: Pump APPROVED 25% REDUCTION

DISTRIBUTION: SERIAL OR D-BOX

BENCHMARK: 100.0

NO. BEDROOMS: 3

LOT 61

REPAIR Pump Approved 25% Reduction

DISTRIBUTION SERIAL OR D-BOX

LOCATION FC Right/ROW T-5

LTAR 0.3 gpd/ft²

LINE	FLAG COLOR	ELEVATION	LENGTH
I { 1	R	97.91	100
2	Y	97.75	115
3	G	97.50	115
			330
R { 4	R	97.50	115
5	Y	97.00	115
6	G	96.67	115
			345

BY B.C. RAYNOR

TYPICAL PROFILE

0-10 LS VFR GR

10-36 Clay fi SBK

OR 2 ≥ 32"

DATE 03/15/2024

THERE SHALL BE NO GRADING,

CUTTING, LOGGING OR OTHER SOIL

DISTURBANCE IN SEPTIC AREA

HEALTH DEPARTMENT USE ONLY.

DESIGNS DO NOT GUARANTEE FUNCTIONALITY

Southeastern Soil & Environmental Associates LLC
PO Box 9321 Fayetteville, NC 28311
Mike@southeasternsoil.com
(910) 822-4540

Elyse Meadow
Preliminary Septic Evaluation

