

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: EUYE MEADOWS

INITIAL SYSTEM: Approved 25% Reduction

DISTRIBUTION: SERIAL

BENCHMARK: 100.0

NO. BEDROOMS: 4

SEPTIC TANK SIZE 1000

LOT 70

REPAIR: Approved 25% Reduction

DISTRIBUTION SERIAL

LOCATION TOP STAKE 55'

LTAR 0.4 GPD/FT²

PUMP TANK SIZE 1000

LINE	FLAG COLOR	ELEVATION	LENGTH
1	Y	97.40	95'
2	R	97.10	95'
3	Y	97.00	95'
4A	R	96.80	15'
			<u>30'</u>
4B	R	96.80	30'
5	Y	96.70	90'
6	R	96.40	90'
7	Y	96.40	90'
			<u>350 AVAILABLE</u>

Initial
540' per

BY M. EATON

TYPICAL PROFILE

0-10 LS / VF, w/gl

10-36+ SCL / F, thin

cr > 34"

DATE 03/2024

THERE SHALL BE NO GRADING,

CUTTING, LOGGING OR OTHER SOIL

DISTURBANCE IN SEPTIC AREA

HEALTH DEPARTMENT USE ONLY.

DESIGNS DO NOT GUARANTEE FUNCTIONALITY

Southeastern Soil & Environmental Associates LLC
PO Box 9321 Fayetteville, NC 28311
Mike@southeasternsoil.com
(910) 822-4540

Elyse Meadow
Preliminary Septic Evaluation

