

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: EUYSE MEADOWS  
pump to

INITIAL SYSTEM: Approved 25% Reduction

DISTRIBUTION: SERIAL

BENCHMARK: 100.0

NO. BEDROOMS: 4

SEPTIC TANK SIZE 1000

LOT 71

REPAIR: Approved 25% Reduction  
pump to

DISTRIBUTION SERIAL

LOCATION TOP STAKE 551

LTAR 0.4 GPD/FTL

PUMP TANK SIZE 1000

| LINE | FLAG COLOR | ELEVATION | LENGTH |
|------|------------|-----------|--------|
|------|------------|-----------|--------|

Initial  
system

|    |   |       |             |
|----|---|-------|-------------|
| 1  | L | 96.30 | 85'         |
| 2  | O | 96.10 | 95'         |
| 3  | L | 95.80 | 100'        |
| 4A | O | 95.50 | 40'         |
|    |   |       | <u>320'</u> |
| 4B | O | 95.50 | 70'         |
| 5  | L | 95.10 | 120'        |
| 6  | O | 94.90 | 120'        |
|    |   |       | <u>310'</u> |

BY M. EATON

TYPICAL PROFILE

0-10 LS / VF, w/pt  
10-36+ silt / F, thin  
cr 2 ≥ 34"

DATE 03/2024

THERE SHALL BE NO GRADING,  
CUTTING, LOGGING OR OTHER SOIL  
DISTURBANCE IN SEPTIC AREA

HEALTH DEPARTMENT USE ONLY.

DESIGNS DO NOT GUARANTEE FUNCTIONALITY

Elyse Meadow  
Preliminary Septic Evaluation

