
WILMINGTON -A, B, C PLAN ID: 2800 - RIGHT HAND - NORTH CAROLINA

DATE:	REVISION:
09/18/2017	INITIAL RELEASE OF PLANS
10/20/2017	CLIENT REVISIONS
11/01/2017	REMOVED PORCH RAILING FROM ELEVATION 'C' FLATTENED BAR TOP AT KITCHEN REVISED SIZE OF WINDOW AT BASE OF STAIRS REVISED MASTER BEDROOM TO OWNER'S BEDROOM
02/07/2018	ELECTRICAL REVISIONS
06/11/2018	CLIENT REVISIONS
11/14/2018	CLIENT REVISIONS
01/09/2019	REVISED CODE REFERENCES
07/23/2019	CLIENT REVISIONS
12/13/2019	CLIENT REVISIONS
02/28/2020	CLIENT REVISIONS

SH	EET INDEX:
CS	ARCHITECTURALS - COVERSHEET
	ARCHITECTURALS - QUICK VIEW
Α	ARCHITECTURALS - ELEVATIONS A
1B	ARCHITECTURALS - ELEVATIONS B
1C	ARCHITECTURALS - ELEVATIONS C
3A	ARCHITECTURALS - FLOOR PLANS A
3B	ARCHITECTURALS - FLOOR PLANS B
3C	ARCHITECTURALS - FLOOR PLANS C
4	ELECTRICAL - FLOOR PLANS


MODEL WILM	NGTON' SQUARE FOC	DTAGES
AREA		ELEV 'C'
Ist FLOOR		1225
2nd FLOOR		1595
TOTAL LIVING		2824
GARAGE		411 5
PORCH		72 9

Mason Ridge Lot 28 98 Charlies Bend Way Spring Lake, NC 28390



REVIEWERS STAMP LOCATION

SF SF SF SF









 \wedge




N.C ATTIC VENT CALCULATION	FOR MODEL 'WILMINGTON': 1:15	50 RATIO.		
THE NET FREE VENTILATING AREA SHALL NOT BE LESS THAN I/ISO OF THE AREA OF THE SPACE VENTILATED, PROVIDED THAT AT LEAST 50 PERCENT AND NOT MORE THAN &0 PERCENT OF THE REQUIRED VENTILATING AREA IS PROVIDED BY VENTILATORS LOCATED IN THE UPPER PORTION OF THE SPACE TO BE VENTILATED AT LEAST 3 FEET ABOVE THE EAVE OR CORNICE VENTS WITH THE BALANCE OF THE REQUIRED VENTILATION PROVIDED BY EAVE OR CORNICE VENTS. EXCEPTIONS: I. EXCLOSED ATTIC/RAFTER SPACES REQUIRING LESS THAN I SQ FT OF VENTILATION MAY BE VENTED WITH CONTINUOUS SOFFIT VENTILATION ONLY. 2. ENCLOSED ATTIC/RAFTER SPACES OVER UNCONDITIONED SPACE MAY BE VENTED WITH CONTINUOUS SOFFIT VENT ONLY. GENERAL CONTRACTOR SHALL VERIFY THE NET FREE VENTILATION OF THE VENT PRODUCT SELECTED BY OWNER. VERIFY WITH MANUFACTURER OF HIGH AND LOW VENTS TO BE USED FOR MINIMUM CALCULATED VENTS REQUIRED. THE REQUIRED VENTILATION SHALL BE MAINTAINED. PROVIDE INSULATION STOP SUCH THAT INSULATION DOES NOT OBSTRUCT FREE AIR MOVEMENT AS REQUIRED BY THE BUILDING OFFICIAL. ALL OVERLAP FRAMED ROOF AREAS SHALL HAVE OPENINGS BETMEEN THE ADJACENT ATTICS IN THE ROOF SHEATHING (AS ALLOWED BY THE STRUCTURAL ENGINEER) TO ALLOW PASSAGE AND ATTIC VENTILATION BETWEEN THE TWO OR ISOLATED ATTIC SPACES SHALL BE VENTED INDEPENDENTLY TO CBC REQUIREMENTS. PER DEVELOPER, AT ALL CANTILEVERED FLOORS, CANTILEVERED ARCHITECTURAL POP-OUTS, AND ANY DOUBLE FRAMING PROJECTIONS THAT ARE SEPARATED FROM THE VENTILATIONS SHOW ABOVE, PROVIDE A CONTINUOUS 2" CORROSION RESISTANT SOFFIT VENT AT UNDERSIDE OF FRAMED ELEMENT.	(PER NCRC SECTION R806.2) I SQUARE INCH VENT FOR EVERY ISO SQUARE INCHES OF C *144 SQ. IN. = 1 SQ. FT. BLDG. CEILING (SF) X 144 = BLDG (SQ. IN.) BLDG. (SQ. IN.) / ISO = SQ. IN. OF VENT REQUIRED SQ. IN. OF VENT REQUIRED / 2 = 50% AT HIGH & 50% AT L ROOF AREA I = 1787 SF I636 SQ. FT. X 144 = 235584 SQ. IN. 235584 SQ. IN. / ISO = I570.56 SQ. IN. OF VENT REQ'D I570.56 SQ. IN. / 2 = 785.28 SQ. IN. 785.28 SQ. IN. OF VENT AT HIGH & 785.28 SQ. IN. OF VENT AT L ROOF AREA 2 = 72 SF 72 SQ. FT. X 144 = I0368 SQ. IN. I0368 SQ. IN. / ISO = 69.12 SQ. IN. OF VENT REQ'D 69.12 SQ. IN. / 2 = 34.56 SQ. IN 34.56 SQ. IN. OF VENT AT HIGH & 34.56 SQ. IN. OF VENT AT LO	LOW REQUIRED.		
NOTES: - ALL ROOF DRAINAGE SHALL BE PIPED TO STREET OR APPROVED DRAINAGE FACILITY. - DASHED LINES INDICATE WALL BELOW. - LOCATE GUTTER AND DOWNSPOUTS PER BUILDER. - PITCHED ROOFS AS NOTED.	- TRUSS MANUFACTURER SHALL SUBMIT STRUCTURAL CALCS AND SHOT TO THE BUILDER'S GENERAL CONTRACTOR AND BUILDING DEPARTME FOR REVIEW PRIOR TO FABRICATIONS. - ALL PLUMBING VENTS SHALL BE COMBINED INTO A MINIMUM AMOUNT PENETRATIONS. ALL ROOF PENETRATIONS SHALL OCCUR TO THE REAR OF THE MAIN RIDGE.	NT		
N.C ATTIC VENT CALCULATION	FOR MODEL 'WILMINGTON': 1:3	00 RATIO.		
AS AN ALTERNATE TO THE I/I5O RATIO LISTED ABOVE, THE NET FREE CROSS-VENTILATION AREA MAY BE REDUCED TO I/300 WHEN A CLASS I OR II VAPOR RETARDER IS INSTALLED ON THE WARM - IN - WINTER SIDE OF THE CEILING. GENERAL CONTRACTOR SHALL VERIFY THE NET FREE VENTILATION OF THE VENT PRODUCT SELECTED BY OWNER. VERIFY WITH MANUFACTURER OF HIGH AND LOW VENTS TO BE USED FOR MINIMUM CALCULATED VENTS REQUIRED. THE REQUIRED VENTILATION SHALL BE MAINTAINED. PROVIDE INSULATION STOP SUCH THAT INSULATION DOES NOT OBSTRUCT FREE AIR MOVEMENT AS REQUIRED BY THE BUILDING OFFICIAL. ALL OVERLAP FRAMED ROOF AREAS SHALL HAVE OPENINGS BETWEEN THE ADJACENT ATTICS IN THE ROOF SHEATHING (AS ALLOWED BY THE STRUCTURAL ENGINEER) TO ALLOW PASSAGE AND ATTIC VENTILATION BETWEEN THE TWO OR ISOLATED ATTIC SPACES SHALL BE VENTED INDEPENDENTLY TO CBC REQUIREMENTS. PER DEVELOPER, AT ALL CANTILEVERED FLOORS, CANTILEVERED ARCHITECTURAL POP-OUTS, AND ANY DOUBLE FRAMING PROJECTIONS THAT ARE SEPARATED FROM THE VENTING CALCULATIONS SHOWN ABOVE, PROVIDE A CONTINUOUS 2" CORROSION RESISTANT SOFFIT VENT AT UNDERSIDE OF FRAMED ELEMENT.	(FER NCRC SECTION R806.2) I SQUARE INCH VENT FOR EVERY 300 SQUARE INCHES OF $(*)$ *144 SQ, IN. = I SQ, FT. BLDG, CEILING (SF) X 144 = BLDG (SQ, IN) BLDG, (SQ, IN) / 300 = SQ, IN. OF VENT REQUIRED SQ, IN. OF VENT REQUIRED / 2 = 50% AT HIGH & 50% AT L ROOF AREA I: = 1636 SF 1636 SQ, FT. X 144 = 235584 SQ, IN. 235584 SQ, IN. / 300 = 785.28 SQ, IN. OF VENT REQ'D 785.28 SQ, IN. / 300 = 785.28 SQ, IN. OF VENT REQ'D 785.28 SQ, IN. / 2 = 342.64 SQ, IN 342.64 SQ, IN. OF VENT AT HIGH & 342.64 SQ, IN. OF VENT ROOF AREA 2: = 72 SF 72 SQ, FT. X 144 = 10368 SQ, IN. 10366 SQ, IN. / 300 = 34.56 SQ, IN. OF VENT REQ'D 34.56 SQ, IN. / 2 = 17.28 SQ, IN 17.28 SQ, IN. OF VENT AT HIGH & 17.28 SQ, IN. OF VENT AT H	.ow. At low required.		
UNDERSIDE OF FRAMED ELEMENT. NOTES:				
 GRADE CONDITIONS MAY VARY FOR INDIVIDUAL SIT BUILDER SHALL VERIFY AND COORDINATE PER ACTU WINDOW HEAD HEIGHTS: IST FLOOR = 6'-8" U.N.O. ON ELEVATIONS. 2ND FLOOR = 7'-O" U.N.O. ON ELEVATIONS. ROOFING: PITCHED SHINGLES PER DEVELOPER. WINDOWS: MANUFACTURER PER DEVELOPER. DIVIDEI ENTRY DOOR: AS SELECTED BY DEVELOPER. GARAGE DOORS: AS SELECTED BY DEVELOPER, RA ALL EXTERIOR MATERIALS TO BE INSTALLED PER M PROTECTION AGAINST DECAY: (ALL PORTIONS OF A PORCH, SCREEN PORCH OR DE THE HEADER DOWN, INCLUDING POST, RAILS, PICKETS INSULATION: PER TABLE NIIO2.I.2. EXTERIOR WALLS: INSULATION: PER TABLE NIIO2.I.2. EXTERIOR WALLS: R-15 BATTS MINIMUM. GEILING WITH ATTIC ABOVE: R-38 BATTS MINIMUM. ATTIC KNEEWALL: R-19 BATTS MINIMUM. CRAWL SPACE FLOORING: R-19 BATTS MINIMUM. 	D LITES AS SHOWN ON THE EXTERIOR ELEVATIONS ISED PANEL AS SHOWN. ANUFACTURER'S WRITTEN INSTRUCTIONS. ECK FROM THE BOTTOM OF 5, STEPS AND FLOOR STRUCTURE.) VERIFY VERIFY VERIFY VERIFY	2" EAVE	CI # G G G G G G G G G G G G G G G G G G G	
KEY NOTES:			5CALE: 1/4"=1'-0	<mark> (</mark>
MASONRY: 1 ADHERED STONE VENEER AS SELECTED BY DEVELOPE 2 MASONRY FULL BRICK AS SELECTED BY DEVELOPE 3 MASONRY FULL STONE AS SELECTED BY DEVELOPE 4 8" SOLDIER COURSE. 5 ROWLOCK COURSE 6 N/A TYPICALS: 7 CORROSION RESISTANT SCREEN LOUVERED VENTS, 8 CODE APPROVED TERMINATION CHIMNEY CAP. 9 CORROSION RESISTANT ROOF TO WALL FLASHING. OF FLASHING PER NCRC R905.2.8.3	R. HEIGHT AS NOTED. R. HEIGHT AS NOTED. SIZE AS NOTED.		JUALE: 1/4 -1-U	
O STANDING SEAM METAL ROOF, INSTALL PER MANUF	CATURER'S WRITTEN INSTRUCTIONS.	皇政		
 III DECORATIVE WROUGHT IRON. SEE DETAILS. <u>SIDING:</u> VINYL SHAKE SIDING PER DEVELOPER WITH VINYL COR (AT SPECIFIED LOCATIONS: FIBER CEMENT SHAKE SIDING PER DEVELOPER WITH VINYL LAP SIDING PER DEVELOPER WITH VINYL COR (AT SPECIFIED LOCATIONS: FIBER CEMENT LAP SIDING PER DEVELOPER WIX4 VINYL WAVY SIDING PER DEVELOPER WITH VINYL COR (AT SPECIFIED LOCATIONS: FIBER CEMENT WAVY SIDING PER DEVELOPER WIX4 VINYL BOARD AND BATT SIDING WIX3 BATTS AT 12" (COMPARISON: FIBER CEMENT PANEL SIDING WIX3 BATTS AT 12" (COMPARISON: FIBER CEMENT TRIM OR EQUAL, U.N.O. SIZE AS NOTED (AT SPECIFIC LOCATIONS: IX FIBER CEMENT TRIM OR EQUAL, U.N.O. SIZE AS NOTED. (AT SPECIFIC LOCATIONS: FALSE VINYL SHUTTERS, TYPE AS SHOWN. SIZE AS NOTED. 	K4 CORNER TRIM BOARD.) RNER TRIM PER DEVELOPER. CORNER TRIM BOARD.) ORNER TRIM PER DEVELOPER. 4 CORNER TRIM BOARD.) NITH VINYL CORNER TRIM PER DEVELOPER. D.C. PER DEVELOPER W/ IX4 CORNER TRIM BOARD.) TED	1-9 1-9 9-1 1-9		
ALL WINDOWS WHOSE OPENING IS LESS THAN 24" ABO THE FINISH FLOOR AND WHOSE OPENING IS GREATER T 72" ABOVE THE OUTSIDE WALKING SURFACE MUST HAV WINDOW OPENING LIMITING DEVICES COMPLYING WITH T NCRC SECTION R3I2.2.1 AND R3I2.2.2.	√E HAN E		Rear Elevatio scale: 1/84-11-04 at 224/0344 Layout 1/164-11-04 at	





L NOTES SEE (IEIGHTS:	GENERAL NOTES ON TITLE SHEET AND DETAILS.	KEY NOTES FOR NORTH CAROLINA:	
-8" U.N.O. ON E	LEVATIONS.	FIRE PROTECTION:	5 FAU 8'X8' PLATFORM. VERIFY WITH TRUSS MANUFACTURE
'-0" U.N.O. ON E	ELEVATIONS.	HOUSE TO GARAGE FIRE SEPARATION. GARAGE/HOUSE SEPARATION AT VERTICAL SURFACES SHALL BE PROTECTED	(6'-6" MIN. CLEAR HEIGHT TO HORIZONTAL MEMBERS, 2"X6" OVER 2"X4" BOTTOM CHORD. OF TRUSS, VERIFY W
5 TO WINDOWS	AND DOORS ARE TO CENTERLINE.	WITH ONE (1) LAYER 1/2" GYPSUM BOARD. (PER NCRC TABLE R302.6.)	6 A/C CONDENSER PAD. (VERIFY)
SEND:		GARAGE/HOUSE SEPARATION AT HORIZONTIAL SURFACES SHALL BE PROTECTED WITH ONE (1) LAYER 5/8" TYPE 'X' GYPSUM BOARD. (PER NCRC TABLE R302.6.)	7 PRE-FABRICATED METAL FIREPLACE. INSTALL PER MANUFACTURER'S WRITTEN INSTRUCTIONS.
ARTITION	ZZZZZZ FULL HEIGHT 2X6 WOOD STUD PARTITION	2 HOUSE TO GARAGE DOOR SEPARATION. PROVIDE 1-3/8" SOLID CORE DOOR OR APPROVED 20 MINUTE RATED DOOR. (PER NCRC SECTION R302.5.1.)	8 ATTIC ACCESS LARGE ENOUGH TO REMOVE LARGEST PIE OF EQUIPMENT BUT NOT LESS THAN 30"x22". FIRE RATED ACCESS AS NOTED. (PER NCRC 807.1)
EER	STUD WALL BELOW HEIGHT AND STUD SIZE AS NOTED	3 BENEATH STAIRS AND LANDINGS. 1/2" GYPSUM BOARD ON WALLS AND CEILING OF ENCLOSED ACCESSIBLE AREAS. (PER NCRC SECTION R302.7.) IN CONCEALED SPACES BETWEEN STAIR STRINGERS PROVIDE	ATTIC ACCESS LADDER, VERIFY LOCATION AND SIZE WIT (25 I/2" X 54" SIZE.) FOR GARAGE TO ATTIC SEPARATIO NCRC 302.5.I EXCEPTION. <u>TYPICALS:</u>
d Wall Ize as noted	DRYWALL OPENING. HEIGHT AS NOTED ON PLAN.	FIREBLOCKING PER R302.II <u>MEP'S</u> GAS WATER HEATER ON 18" HIGH PLATFORM. (PER CHAPTER 5 NCRC-PLUMBING)	 TEMPERED SAFETY GLASS. (PER NCRC SECTION 308.4) PLYWOOD SHELF ABOVE WITH DRYWALL FINISH OVER. HE HALF WALL, HEIGHT AS NOTED.

			PROVIDE ADEQUATE SUPPORT FOR FUTURE CLNG FAN
			owner's bedroom
		WiC — 8'-1" clg	
NOTES:		7	
 PROVIDE GROUNDING ELECTRICAL ROI PROVIDE AND INSTALL ARC FAULT CIRELECTRICAL CODE (NEC) AND MEETING ALL EXHAUST FANS SHALL HAVE BACK FAN/LIGHTS IN WET/DAMP LOCATIONS S ELECTRICAL SYSTEMS ARE SHOWN FOR OTHERS. THE CONTRACTOR SHALL BE IN ATIONAL FIRE PROTECTION ASSOCIATION PROVIDE AND INSTALL LOCALLY CERTIFIED NATIONAL FIRE PROTECTION ASSOCIATION PROVIDE AND INSTALL GROUND FAULT CIRCODE (NEC) AND MEETING THE REQUIREMENT ELECTRICAL CONTRACTOR TO PROVIDE RE HVAC CONTRACTOR TO VERIFY THERMOST. ALL ELECTRICAL AND MECHANICAL EQUIPM 	CUIT-INTERRUPTERS (AFCI) AS REQUIRED BY NATIONAL THE REQUIREMENTS OF ALL GOVERNING CODES. DRAFT DAMPERS. HALL BE LABLED "SUITABLE FOR WET OR DAMP LOCATIONS." INTENT ONLY. THESE SYSTEMS SHALL BE ENGINEERED BY RESPONSIBLE FOR PROPER INSTALLATION AND PLACEMENT. O SMOKE DETECTORS AND CO2 DETECTORS AS REQUIRED BY (NFPA) AND MEETING THE REQUIREMENTS OF ALL GOVERNING CODES. CUIT-INTERRUPTERS (GFI) AS REQUIRED BY NATIONAL ELECTRICAL TS OF ALL GOVERNING CODES. EQUIRED DIRECT HOOK-UPS/CUTOFFS. AT LOCATIONS.		bed 2 8'-1" clg PROVIDE ADEQUATE SUPPORT FOR FUTURE cLNG FAN
	RE SUBJECT TO RELOCATION DUE TO FIELD CONDITIONS. 6 REQUIRED FOR ATTIC FURNACE PER CODE AND 15.		
LEGEND:			
DUPLEX OUTLET		-	BEL
Ø GFI GROUND-FAULT CIRCUIT-INTERRUPTER DUPLEX OUTLET	HO- WALL MOUNTED INCANDESCENT LIGHT FIXTURE RECESSED INCANDESCENT LIGHT FIXTURE	_	L
	Image: Second	-	
 	CEILING MOUNTED LED LIGHT FIXTURE (VP) = VAPOR PROOF EXHAUST FAN (VENT TO EXTERIOR)	-	
\$ WALL SWITCH		-	
\$ 3 THREE-WAY SWITCH	(VENT TO EXTERIOR)	-	and Elacia Dian
	TECH HUB SYSTEM	_	<u>2nd Floor Plan</u>
어 CHIMES 다 PUSHBUTTON SWITCH		-	SCALE: I/4"=I'-0" AT 22"X34" LAYOUT I/8"=I'-0" AT II"XI7" I
IIOV SMOKE ALARM W BATTERY BACKUP IIOV SMOKE ALARM CO2 DETECTOR COMBO	(PROVIDE ADEQUATE SUPPORT) CEILING FAN WITH INCANDESCENT LIGHT FIXTURE (PROVIDE ADEQUATE SUPPORT)	-	
THERMOSTAT	· ✓ ✓ · ──⊗ GAS SUPPLY WITH VALVE	-	
Image: matrix telephone Image: Television			
ELECTRIC PANEL DISCONNECT SWITCH	-X WALL SCONCE		



DESIGN SPECIFICATIONS:

Construction Type: Commerical 🗆 Residential 🛛

Applicable Building Codes:

• 2018 North Carolina Residential Buildina Code with All Local Amendments

esign Lo	oads: Roof Live Load	40				
1.	1.1. Convent	ional 2x				
2.	Roof Dead Loo	ads				
7						
3.	Snow					
Л	Floor Live Loa			•••••		1.0
4.						40 P9
		ger Garage				50 PS
5.	Floor Dead Lo					
ĥ					130 MDU	IJ PS
0.	Ultimate Desig				IJU MFH	R
					•••••••••••••••••••••••••••••••••••••••	
	6.3. Wind Bo					
	6.3.1.	Vx =				
	6.3.2.	J				
7.	Component an	d Cladding (ir	n PSF)			
	MEAN ROOF HT.	UP TO 30'	30'1"-35'	35'1"-40'	40'1"-45'	
	ZONE 1	16.7,-18.0	17.5,-18.9	18.2,-19.6	18.7,-20.2	
	ZONE 2	16.7,-21.0	17.5,-22.1	18.2,-22.9	18.7,-23.5	
	ZONE 3	16.7,-21.0	17.5,-22.1	18.2,-22.9	18.7,-23.5	
	ZONE 4	18.2,-19.0	19.2,-20.0	19.9,-20.7	20.4,-21.3	
	ZONE 5	18.2,-24.0	19.2,-25.2	19.9,-26.1	20.4,-26.9	

8. Seismic

	8.1.	Site Class	_
	8.3. 8.4.	Design Category Importance Factor Seismic Use Group Spectral Response Acceleration 8.5.1. Sms = %g 8.5.2. Sm1 = %g	. C . 1.0
	8.6.	Seismic Base Shear 8.6.1. Vx = 8.6.2. Vy =	
	8.7.	Basic Structural System (check one) ⊠ Bearing Wall □ Building Frame □ Moment Frame □ Dual w/ Special Moment Frame □ Dual w/ Intermediate R/C or Special Steel □ Inverted Pendulum	
		Arch/Mech Components Anchored	No
9.		Lateral Design Control: Seismic 🗆 Wind 🛛 ned Soil Bearing Capacity	2000psf



UES PROFESSIONAL SOLUTIONS 29, INC

FORMERLY SUMMIT ENGINEERING, LABORATORY, & **TESTING INC.**

STRUCTURAL PLANS PREPARED FOR:

WILMINGTON – RH PROJECT ADDRESS: OWNER: DR Horton, Inc. 8001 Arrowridge Blvd. TBD Charlotte, NC 28273 DESIGNER: GMD Design Group 102 Fountain Brook Circle Suite C Cary, NC 27511 These drawings are to be coordinated with the architectural, mechanical, plumbing, electrical, and civil drawings. This coordination is not the responsibility of the structural engineering of record (SER). Should any discrepancies become apparent, the contractor shall notify UES Professional Solutions 29, Inc. (UES) before construction begins. PLAN ABBREVIATIONS: AB ANCHOR BOLT PT PRESSURE TREATED AFF ABOVE FINISHED FLOOR RS ROOF SUPPORT CJ CEILING JOIST SC STUD COLUMN CLR CLEAR SJ SINGLE JOIST

DJ DOUBLE JOIST

EE EACH END

EW EACH WAY NTS NOT TO SCALE

OC ON CENTER

DSP DOUBLE STUD POCKET

PSF POUNDS PER SQUARE FOOT

PSI POUNDS PER SQUARE INCH

contractor shall notify UES immediately.

SPF SPRUCE PINE FIR

TJ TRIPLE JOIST

TYP TYPICAL

Roof truss and floor joist layouts, and their corresponding loading details, were not provided to UES Professional Solutions 29, Inc. (UES) prior to the initial

design. Therefore, truss and joist directions were assumed based on the information provided by <u>DR Horton, Inc</u>. Subsequent plan revisions based on roof

truss and floor joist layouts shall be noted in the revision list, indicating the date the layouts were provided. Should any discrepancies become apparent, the

SST SIMPSON STRONG-TIE

TSP TRIPLE STUD POCKET

WWF WELDED WIRE FABRIC

SYP SOUTHERN YELLOW PINE

UNO UNLESS NOTED OTHERWISE


<u>Sheet list:</u>

Sheet No.	Description
CS1	Cover Sheet, Specifications, Revisions
S1.0m	Monolithic Slab Foundation
S1.0s	Stem Wall Foundation
S1.0c	Crawl Space Foundation
S1.0b	Basement Foundation
S2.0	Basement Plan
S3.0	First Floor Plan
S4.0	Second Floor Plan
S5.0	Roof Framing Plan

<u>REVISION LIST:</u>

Revision No.	Date	Project No.	Description
1	5.16.17	12611R	Revised garage slab note. Revised roof overframing. Verified roof truss layouts provided by 84 Lumber on 3.28.11. Verified floor joist layouts provided by 84 Lumber on 8.2.15
2	6.14.17	12611R2	Added stem wall foundation plan
3	4.23.18	17862	Added crawl space foundation plan
4	7.10.18	17862R	Revised per new architectural files dated 6.12.18
5	8.30.18	17862R2	Added dimensions at tapered porch columns
6	10.5.18	17862R3	Included stick framing option at extended porch
7	11.30.18	17862R4	Revised NC version only for 2018 NCRC
8	3.1.21	T0091	Added OX-IS Structural Insulated Sheating Option
9	6.29.21	T0091	Updated OX-IS chart and Stud Change
10	12.18.24	A20117.00 087.000	Update Crawl Space Notes

DR HORTON PROJECT	SIGN-OFF:
Manager	Signature
Operations	
Operations System	
Operations Product Development	



 FOUNDATIONS: 1. The structural engineer has not performed a subsurface investigation. Verification of this assumed value is the responsibility of the owner or the contractor. Should any adverse soil condition be encountered the SER must be contacted before proceeding. 2. The bottom of all footings shall extend below the frost line for the region in which the structure is to be constructed. However, the bottom of all footings shall be a minimum of 12" below grade. 	 10. All welded wire fabric (W.W.F.) for concrete slabs-on-grade shall be placed at mid-depth of slab. The W.W.F. shall be securely supported during the concrete pour. <u>CONCRETE REINFORCEMENT:</u> 1. Fibrous concrete reinforcement, or fibermesh, specified in concrete place on grade may be used for control of 	8.
 investigation. Verification of this assumed value is the responsibility of the owner or the contractor. Should any adverse soil condition be encountered the SER must be contacted before proceeding. 2. The bottom of all footings shall extend below the frost line for the region in which the structure is to be constructed. However, the bottom of all footings shall 	The W.W.F. shall be securely supported during the concrete pour. <u>CONCRETE REINFORCEMENT:</u> 1. Fibrous concrete reinforcement, or fibermesh, specified	
responsibility of the owner or the contractor. Should any adverse soil condition be encountered the SER must be contacted before proceeding. 2. The bottom of all footings shall extend below the frost line for the region in which the structure is to be constructed. However, the bottom of all footings shall	concrete pour. <u>CONCRETE REINFORCEMENT:</u> 1. Fibrous concrete reinforcement, or fibermesh, specified	
any adverse soil condition be encountered the SER must be contacted before proceeding. 2. The bottom of all footings shall extend below the frost line for the region in which the structure is to be constructed. However, the bottom of all footings shall	<u>CONCRETE REINFORCEMENT:</u> 1. Fibrous concrete reinforcement, or fibermesh, specified	
must be contacted before proceeding. 2. The bottom of all footings shall extend below the frost line for the region in which the structure is to be constructed. However, the bottom of all footings shall	1. Fibrous concrete reinforcement, or fibermesh, specified	
2. The bottom of all footings shall extend below the frost line for the region in which the structure is to be constructed. However, the bottom of all footings shall	1. Fibrous concrete reinforcement, or fibermesh, specified	
line for the region in which the structure is to be constructed. However, the bottom of all footings shall		9.
constructed. However, the bottom of all footings shall		
	in concrete slabs-on-grade may be used for control of	10.
L I DE CIMINIMUM OT LZ DELOW CRACE	cracking due to shrinkage and thermal	
	expansion/contraction, lowered water migration, an	
3. Any fill shall be placed under the direction or	increase in impact capacity, increased abrasion	11.
recommendation of a licensed professional engineer.	resistance, and residual strength.	
4. The resulting soil shall be compacted to a minimum of	2. Fibermesh reinforcing to be 100% virgin polypropylene	
		WO
	specifically manufactured for use as concrete secondary	1
	3. Application of fibermesh per cubic yard of concrete	
	shall equal a minimum of 0.1% by volume (1.5 pounds	
containing water, ice, frost, or loose material.	per cubic vard)	
1. Structural steel shall be fabricated and erected in		
accordance with the American Institute of Steel		
Construction "Code of Standard Practice for Steel		
		2.
	9	
	with the same size/spacing as the horizontal	
	reinforcement with a class B tension splice.	
American Welding Society's Structural Welding Code AWS	8. Lap reinforcement as required, a minimum of 40 bar	
D1.1. Electrodes and consumables for both shop and	diameters for tension or compression unless otherwise	.3
field welding shall be 70ksi. All welding shall be		
performed by a certified welder per the above		
standards.	9. Where reinforcing dowels are required, they shall be	
CONCRETE:		
1. Concrete shall be nominal weight concrete with no		4.
	5	
		5
		J.
Buildings".		
3. Air entrained concrete must be used for all structural	(SYP) #2.	
	2. LVL or PSL engineered wood shall have the following	
	minimum design values:	\underline{EX}
	2.1. E = 1,900,000 psi	1.
j j	2.2. $Fb = 2600 \text{ psi}$	
5		
		WO
		1.
for Concrete Slab and Slab Construction".		
6. The concrete slab—on—grade has been designed using a		
subgrade modulus of k=250 pci and a design loading		2.
of 200 psf. The SER is not responsible for differential		
settlement, slab cracking or other future defects		3.
resulting from unreported conditions not in accordance		
with the above assumptions.		
7. Control or saw cut joints shall be spaced in interior		
5	continuous from the sole plate to the double top plate.	
	Studs shall only be discontinuous at headers for	
	window/door openings. A minimum of one king stud	
	shall be placed at each end of the header. King studs	
	shall be continuous.	
joint.		
	 95% maximum dry density. Excavations of footings shall be lined temporarily with a 6 mil polysthylene membrane if placement of concrete does not occur within 24 hours of excavation. No concrete shall be placed against any subgrade containing water, ice, frost, or loose material. STRUCTURAL STEFI: Structural steel shall be fabricated and erected in accordance with the American Institute of Steel Buildings and Bridges" and the manual of Steel Construction "Load Resistance Factor Design" latest editions. Structural steel shall receive one coat of shop applied rust-inhibitive point. All steel shall have a minimum yield stress (F_x) of 36 ksi unless otherwise noted. Welding shall conform to the lotest edition of the American Welding Society's Structural Welding Code AWS D11. Electrodes and consumables for both shop and field welding shall be 70ksi. All welding shall be performed by a certified welder per the above standards. CONCRETE: Concrete shall be nominal weight concrete with no aggregate larger than 3/4" and a minimum compressive strength (f-) at 28 days of 3000 psi, unless otherwise noted on the plan. Concrete shall be proportioned, mixed, and placed in accordance with the latest editions of ACI 318: "Building". Air entrained concrete must be used for all structural elements exposed to freeze/thaw cycles and deicing chemicols. Air entrainment amounts (in percent) shall be within -1% to +2% of target values as follows: Footings: 5% No admixtures shall be added to any structural concrete slab and on gate structural field explores on deicing chemicols. Air entrainment amounts (in percent) shall be within -1% to +2% of target values as follows: Footings: 5% No admixtures shall be added to any structural concrete slab anon-grade shall be added in accordance with the latest version of ACI 302.: "Guide for Concrete slab anon-grade shall be construction". <!--</td--><td> b) becomenting on characteristic descension of the theorem is the theore</td>	 b) becomenting on characteristic descension of the theorem is the theore

8. Individual studs forming a column shall be attached with one 10d nail @ 6" O.C. staggered. The stud column shall be continuous to the foundation or beam. The column shall be properly blocked at all floor levels to ensure proper load transfer.

- 9. Multi-ply beams shall have each ply attached with (3) 12d nails @ 12" O.C.
- 10. Four and five ply beams shall be bolted together with (2) rows of 1/2" diameter through bolts staggered @ 16" O.C. unless noted otherwise.
- 11. All fasteners that will be exposed to the elements shall be hot dipped galvanized.

WOOD TRUSSES:

- 1. The wood truss manufacturer/fabricator is responsible for the design of the wood trusses. Submit sealed shop drawings and supporting calculations to the SER for review prior to fabrication. The SER shall have a minimum of five (5) days for review. The review by the SER shall review for overall compliance with the design documents. The SER shall assume no responsibility for the correctness for the structural design for the wood trusses.
- 2. The wood trusses shall be designed for all required loadings as specified in the local building code, the ASCE Standard "Minimum Design Loads for Buildings and Other Structures." (ASCE 7-16), and the loading requirements shown on these specifications. The truss drawings shall be coordinated with all other construction documents and provisions provided for loads shown on these drawings including but not limited to HVAC equipment, piping, and architectural fixtures attached to the trusses.
- 3. The trusses shall be designed, fabricated, and erected in accordance with the latest edition of the "National Design Specification for Wood Construction." (NDS) and "Design Specification for Metal Plate Connected Wood Trusses."
- 4. The truss manufacturer shall provide adequate bracing information in accordance with "Commentary and Recommendations for Handling, Installing, and Bracing Metal Plate Connected Wood Trusses" (HIB-91). This bracing, both temporary and permanent, shall be shown on the shop drawings. Also, the shop drawings shall show the required attachments for the trusses.
- 5. Any chords or truss webs shown on these drawings have been shown as a reference only. The final design of the trusses shall be per the manufacturer.

EXTERIOR WOOD FRAMED DECKS:

1. Decks are to be framed in accordance with local building codes and as referenced on the structural plans, either through code references or construction details.

WOOD STRUCTURAL PANELS:

- 1. Fabrication and placement of structural wood sheathing shall be in accordance with the APA Design/Construction Guide "Residential and Commercial," and all other applicable APA standards.
- 2. All structurally required wood sheathing shall bear the mark of the APA.
- 3. Wood wall sheathing shall comply with the requirements of local building codes for the appropriate state as indicated on these drawings. Refer to wall bracing notes in plan set for more information. Sheathing shall be applied with the long direction perpendicular to framing, unless noted otherwise.


4. Roof sheathing shall be APA rated sheathing exposure 1 or 2. Roof sheathing shall be continuous over two supports and attached to its supporting roof framing with (1)—8d CC nail at 6"o/c at panel edges and at 12"o/c in panel field unless otherwise noted on the plans. Sheathing shall be applied with the long direction perpendicular to framing. Sheathing shall have a span rating consistent with the framing spacing. Use suitable edge support by use of plywood clips or lumber blocking unless otherwise noted. Panel end joints shall occur over framing. Apply building paper over the sheathing as required by the state Building Code. 5. Wood floor sheathing shall be APA rated sheathing exposure 1 or 2. Attach sheathing to its supporting framing with (1)-8d CC ringshank nail at 6"o/c at panel edges and at 12"o/c in panel field unless otherwise noted on the plans. Sheathing shall be applied perpendicular to framing. Sheathing shall have a span rating consistent with the framing spacing. Use suitable edge support by use of T&G plywood or lumber blocking unless otherwise noted. Panel end joints shall occur over framing. Apply building paper over the sheathing as required by the state Building Code. 6. Sheathing shall have a 1/8" gap at panel ends and edges as recommended in accordance with the APA. STRUCTURAL FIBERBOARD PANELS:

- AFA standards.
- the mark of the AFA.

1. Fabrication and placement of structural fiberboard sheathing shall be in accordance with the applicable

2. All structurally required fiberboard sheathing shall bear 3. Fiberboard wall sheathing shall comply with the

requirements of local building codes for the appropriate state as indicated on these drawings. Refer to wall bracing notes in plan set for more information. 4. Sheathing shall have a 1/8" gap at panel ends and edges are recommended in accordance with the AFA.



FOUNDATION NOTES:

- 1. FOUNDATIONS TO BE CONSTRUCTED IN ACCORDANCE WITH CHAPTER 4 OF THE 2018 NORTH CAROLINA RESIDENTIAL BUILDING CODE WITH ALL LOCAL AMENDMENTS.
- 2. STRUCTURAL CONCRETE TO BE $F_c = 3000$ PSI, PREPARED AND PLACED IN
- ACCORDANCE WITH ACI STANDARD 318.
- 3. FOOTINGS TO BE PLACED ON UNDISTURBED EARTH, BEARING A MINIMUM OF 12" BELOW ADJACENT FINISHED GRADE, OR AS OTHERWISE DIRECTED BY THE CODE ENFORCEMENT OFFICIAL.
- 4. FOOTING SIZES BASED ON A PRESUMPTIVE SOIL BEARING CAPACITY OF 2000 PSF. CONTRACTOR IS SOLELY RESPONSIBLE FOR VERIFYING THE SUITABILITY OF THE SITE SOIL CONDITIONS AT THE TIME OF CONSTRUCTION.
- 5. FOOTINGS AND PIERS SHALL BE CENTERED UNDER THEIR RESPECTIVE ELEMENTS. PROVIDE 2" MINIMUM FOOTING PROJECTION FROM THE FACE OF MASONRY.
- 6. MAXIMUM DEPTH OF UNBALANCED FILL AGAINST MASONRY WALLS TO BE AS SPECIFIED IN SECTION R404.1 OF THE 2018 NORTH CAROLINA RESIDENTIAL BUILDING CODE.
- PILASTERS TO BE BONDED TO PERIMETER FOUNDATION WALL.
 PROVIDE FOUNDATION WATERPROOFING, AND DRAIN WITH POSITIVE SLOPE TO
- OUTLET AS REQUIRED BY SITE CONDITIONS. 9. PROVIDED PERIMETER INSULATION FOR ALL FOUNDATIONS PER 2018 NORTH
- CAROLINA RESIDENTIAL BUILDING CODE. 10. CORBEL FOUNDATION WALL AS REQUIRED TO ACCOMMODATE BRICK VENEERS.
- CRAWL SPACE TO BE GRADED LEVEL, AND CLEARED OF ALL DEBRIS.
 FOUNDATION ANCHORAGE SHALL BE CONSTRUCTED PER THE 2018 NORTH CAROLINA RESIDENTIAL CODE SECTION R403.1.6. MINIMUM 1/2" DIA. BOLTS SPACED AT 6'-0" ON CENTER WITH A 7" MINIMUM EMBEDMENT INTO MASONRY OR CONCRETE. ANCHOR BOLTS SHALL BE 12" FROM THE END OF EACH PLATE SECTION. MINIMUM (2) ANCHOR BOLTS PER PLATE SECTION. ANCHOR BOLTS SHALL BE LOCATED IN THE CENTER THIRD OF THE PLATE.
- 9. ABBREVIATIONS:

DJ = DOUBLE JOIST	SJ = SINGLE JOIST
GT = GIRDER TRUSS	FT = FLOOR TRUSS
SC = STUD COLUMN	DR = DOUBLE RAFTER
EE = EACH END	TR = TRIPLE RAFTER
TJ = TRIPLE JOIST	OC = ON CENTER
CL = CENTER LINE	PL = POINT LOAD

- 10. ALL PIERS TO BE 16"x16" MASONRY AND ALL PILASTERS TO BE 8"x16" MASONRY, TYPICAL. (UNO)
- WALL FOOTINGS TO BE CONTINUOUS CONCRETE, SIZES PER STRUCTURAL PLAN.
 A FOUNDATION EXCAVATION OBSERVATION SHOULD BE CONDUCTED BY A PROFESSIONAL GEOTECHNICAL ENGINEER, OR HIS QUALIFIED REPRESENTATIVE. IF ISOLATED AREAS OF YIELDING MATERIALS AND/OR POTENTIALLY EXPANSIVE SOILS ARE OBSERVED IN THE FOOTING EXCAVATIONS AT THE TIME OF CONSTRUCTION, UES PROFESSIONAL SOLUTIONS 29, INC. (UES) MUST BE PROVIDED THE OPPORTUNITY TO REVIEW THE FOOTING DESIGN PRIOR TO CONCRETE PLACEMENT.
 ALL FOOTINGS & SLABS ARE TO BEAR ON UNDISTURBED SOIL OR 95%
- COMPACTED FILL, VERIFIED BY ENGINEER OR CODE OFFICIAL.

REFER TO BRACED WALL PLAN FOR PANEL LOCATIONS AND ANY REQUIRED HOLDOWNS. ADDITIONAL INFORMATION PER SECTION R602.10.8 AND FIGURES R602.10.6.5, R602.10.7, R602.10.8(1) AND R602.10.8(2) OF THE 2015 IRC

NOTE: ALL EXTERIOR FOUNDATION DIMENSIONS ARE TO FRAMING AND <u>NOT</u> BRICK VENEER, UNO

NOTE: A 4" CRUSHED STONE BASE COURSE IS NOT REQUIRED WHEN SLAB IS INSTALLED ON WELL-DRAINED OR SAND-GRAVEL MIXTURE SOILS CLASSIFIED AS GROUP PER TABLE R405.1

REINFORCE GARAGE PORTAL WALLS PER FIGURE R602.10.9 OF THE 2015 IRC.

BEAM POCKETS MAY BE SUBSTITUTED FOR MASONRY PILASTERS AT GIRDER ENDS. BEAM POCKETS SHALL HAVE A MINIMUM 4" SOLID MASONRY BEARING.

NOTE: REDUCE JOIST SPACING UNDER TILE FLOORS, GRANITE COUNTERTOPS AND/OR ISLANDS.


THESE PLANS ARE DESIGNED IN ACCORDANCE WITH ARCHITECTURAL PLANS PROVIDED BY <u>DR HORTON</u> COMPLETED/REVISED ON <u>02/28/2020</u>. IT IS THE RESPONSIBILITY OF THE CLIENT TO NOTIFY UES PROFESSIONAL SOLUTIONS 29, INC. (UES) IF ANY CHANGES ARE MADE TO THE ARCHITECTURAL PLANS PRIOR TO CONSTRUCTION. UES PROFESSIONAL SOLUTIONS 29, INC. (UES) CANNOT GUARANTEE THE ADEQUACY OF THESE STRUCTURAL PLANS WHEN USED WITH ARCHITECTURAL PLANS DATED DIFFERENTLY THAN THE DATE LISTED ABOVE.

STRUCTURAL MEMBERS ONLY

ENGINEERING SEAL APPLIES ONLY TO STRUCTURAL COMPONENTS ON THIS DOCUMENT, SEAL DOES NOT INCLUDE CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, PROCEDURES OR SAFETY PRECAUTIONS. ANY DEVIATIONS OR DISCREPANCIES ON PLANS ARE TO BE BROUGHT TO THE IMMEDIATE ATTENTION OF UES PROFESSIONAL SOLUTIONS 29, INC. (UES) FAILURE TO DO SO WILL VOID (UES) LIABILITY.


STRUCTURAL ANALYSIS BASED ON 2018 NCRC.

CRAWL SPACE FOUNDATION PLAN SCALE: 1/4"=1'-0" ON 22"x34" OR 1/8"=1'-0" ON 11"x17"




18"x24" MIN. CRAWL SPACE ACCESS DOOR TO BE LOCATED IN FIELD PER BUILDER. PROVIDE MIN. (2) 2x10 HEADER OVER DOOR w/ MIN. 4" BEARING EACH END. AVOID SHOWN POINT LOADS.

DECK FLOOR JOISTS SHALL BE SPACED AT MAX. 12" ON CENTER WHEN DECKING INSTALLED DIAGONALLY




METHOD	MATERIAL	MIN. THICKNESS	@ PANEL EDGES	@ INTERMEDIATE SUPPORTS
CS-WSP	WOOD STRUCTURAL PANEL	3/8"	6d COMMON NAILS @ 6"O.C.	6d COMMON NAILS @ 12" O.C.
GB	GYPSUM BOARD	1/2"	5d COOLER NAILS** @ 7" O.C.	5d COOLER NAILS** @ 7" O.C.
WSP	WOOD STRUCTURAL PANEL	3/8"	6d COMMON NAILS @ 6"O.C.	6d COMMON NAILS @ 12" O.C.
PF	WOOD STRUCTURAL PANEL	7/16"	PER FIGURE R602.10.6.4	PER FIGURE R602.10.6.4
		**OR EQUIVALENT	PER TABLE R702.3.5	
CODE WITH A CONTRACTOR CONTRACTOR RESPONSIBLE CONTRACTOR RESIST ALL F PROPERTIES MICROLLAM PARALLAM ALL WOOD M COLUMNS AN ALL BEAMS S EACH END U ALL REINFOR SHALL HAVE FOUNDATION RESIDENTIAL CENTER WIT BOLTS SHALL BOLTS SHALL BOLTS SHALL BOLTS SHALL BOLTS SHALL BOLTS SHALL BOLTS PER F OF THE PLA CONTRACTOR RAFTERS. FLITCH BEAM TOGETHER WI EQUIVALENT (2) BOLTS S ALL NON-LO FOR NON-LC THAN 2'-0" DROPPED. (U ABBREVIATION DJ = DOUE GT = GIRDI SC = STUE EE = EACH	LL LOCAL AMENDMENTS SHALL VERIFY ALL DIM F THE DRAWING FOR TH FOR ANY DEVIATIONS IS RESPONSIBLE FOR FORCES ENCOUNTERED USED IN THE DESIGN A (LVL): $F_b = 2600$ F (PSL): $F_b = 2900$ F EMBERS SHALL BE #2 D JOISTS SHALL BE #2 SHALL BE SUPPORTED NLESS NOTED OTHERWIS CING STEEL SHALL BE A MINIMUM COVER OF ANCHORAGE SHALL BE CODE SECTION R403.1. H A 7" MINIMUM EMBEL DE 12" FROM THE EN PLATE SECTION. ANCHO E. TO PROVIDED LOOKOU S, 4-PLY LVLS AND 3 TH 1/2" DIA. THRU BC CONNECTIONS PER DET HALL BE LOCATED MINI AD BEARING HEADERS OF CRIPPLE WALL ABO NLESS NOTED OTHERWINS: BLE JOIST ST TH S ST S ST S COLUMN I END E JOIST	S. MENSIONS. CONTRAC HIS SPECIFIC PROJEC FROM THIS PLAN. PROVIDING TEMPORA DURING ERECTION. RE AS FOLLOWS: PSI, $F_v = 285$ PSI, PSI, $F_v = 290$ PSI, SYP/#2 SPF UNLESS SYP/#2 SPF UNLESS SYP/#2 SPF (UNO) WITH A (2) 2×4 #2 SE. GRADE 60 BARS CO 3". CONSTRUCTED PER 6. MINIMUM 1/2" DI/ DMENT INTO MASONF D OF EACH PLATE S R BOLTS SHALL BE TS WHEN CEILING JC -PLY SIDE LOADED LTS SPACED AT 24' AIL 1/D3f. MIN. EDG MUM 6" FROM EACH SHALL BE (1) FLAT EXCEEDING 8'-0" IN VE, SHALL BE (2) F SE) SINGLE JOIST	RY BRACING REQUIRED TO E = 1.9x10 ⁶ PSI E = 1.25x10 ⁶ PSI S NOTED ON PLAN. ALL STUD). SYP/#2 SPF STUD COLUMN A NFORMING TO ASTM A615 AN THE 2018 NORTH CAROLINA A. BOLTS SPACED AT 6'-O" (C RY OR CONCRETE. ANCHOR SECTION. MINIMUM (2) ANCHO LOCATED IN THE CENTER THIN DISTS SPAN PERPENDICULAR C.C. (MAX) STAGGERED OR E DISTANCE SHALL BE 2" AN END OF THE BEAM. 2x4 SYP #2/SPF #2, DROPPI I WIDTH AND/OR WITH MORE LAT 2x4 SYP #2/SPF #2,	AT D DN R RD TO
WALL ABOY LOAD BEAF	DESIGNATES JOIST SUF /E. PROVIDE BLOCKING RING WALL. EAM SIZES SHOWN ARE DEPTH FOR EASE OF C	UNDER JOIST SUPPO)RTED	
R602.10.8 A	Y REQUIRED HOLDOWNS ND FIGURES R602.10.6.) AND R602.10.8(2) OF	5, R602.10.7,		
PLANS PROVIE IT IS THE RES SOLUTIONS 29 ARCHITECTURA SOLUTIONS 29 THESE STRUC	ARE DESIGNED IN ACC DED BY <u>DR HORTON</u> CO DONSIBILITY OF THE CL D, INC. (UES) IF ANY CO AL PLANS PRIOR TO CO D, INC. (UES) CANNOT O TURAL PLANS WHEN US ENTLY THAN THE DATE	MPLETED/REVISED C JENT TO NOTIFY UE HANGES ARE MADE INSTRUCTION. UES GUARANTEE THE ADE GUARANTEE THE ADE	IN <u>02/28/2020.</u> S PROFESSIONAL TO THE PROFESSIONAL EQUACY OF	
FRAMED WI	IBER NOTED AS PRESSI TH NON-PRESSURE TR ETY OF THE MEMBER IS INTRUSION.	EATED LUMBER PRO'	VIDED	
	UCE JOIST SPACING UN DUNTERTOPS AND/OR 1			
ENGINEERIN COMPONENT INCLUDE CO SEQUENCES ANY DEVIAT BE BROUGH	URAL MEM S SEAL APPLIES S ON THIS DOCU ONSTRUCTION ME PROCEDURES C TIONS OR DISCRE TO THE IMME NAL SOLUTIONS 2	ONLY TO STR JMENT, SEAL D ANS, METHODS PR SAFETY PRI PANCIES ON P DIATE ATTENTIO	RUCTURAL DOES NOT , TECHNIQUES, ECAUTIONS. PLANS ARE TO ON OF UES	

SCALE: 1/4"=1'-0" ON 22"x34" OR 1/8"=1'-0" ON 11"x17"



MIN. 4" P.T. POSTS OR COL. RATED FOR 2000# (MIN, TYP) ATTACH POSTS TO -HEADER w/ SST CS16 STRAPS OR (4) 16d NAILS AND ATTACH POSTS TO FOUNDATION w/ SST ABA44 POST BASE OR EQUIV. (TYP)

FIRST F	LOOR BRACIN	NG (FT)
CONTI	NUOUS SHEATHING M	ETHOD
	REQUIRED	PROVIDED
BWL 1-1	4.8	26.5
BWL 1-2	4.8	13.5
BWL 1-3	4.3	13.1
BWL 1-A	11.5	41.0
BWL 1-B	11.5	36.0



FIRST FLOOR FRAMING PLAN - ELEVATION A6. ON SCHEMATIC, SHADED WALLS INDICATE BRACED WALL PANELS.

TAG	ADER SCHEDU size	JACKS (EACH END)
А	(2) 2x6	(1)
В	(2) 2x8	(2)
С	(2) 2x10	(2)
D	(2) 2x12	(2)
E	(2) 9–1/4" LSL/LVL	(3)
F	(3) 2x6	(1)
G	(3) 2x8	(2)
Н	(3) 2x10	(2)
	(3) 2x12	(2)
HEADER SIZES MAY I ALL HEADERS TO BE	N ON PLANS ARE MINI BE USED FOR EASE OF DROPPED UNLESS NO CRRIDE SC LISTED ABO'	CONSTRUCTION. TED OTHERWISE. SC

LINTEL SCHEDULE					
TAG	SIZE	OPENING SIZE			
	L3x3x1/4"	LESS THAN 6'-0"			
2	L5x3x1/4"	6'-0" TO 10'-0"			
3	L5x3-1/2"x5/16"	greater than 10'—0"			
4	L5x3–1/2"x5/16" ROLLED OR EQUIV.	ALL ARCHED OPENINGS			
SECURE LINTEL TO HEADER w/ (2) 1/2" DIAMETER LAG SCREWS STAGGERED @ 16" O.C. (TYP FOR ③)					
ALL HEADERS WHERE BRICK IS USED, TO BE: (1)(UNO)					

WALL STUD SCHEDULE

1ST & 2ND FLOOR LOAD BEARING STUDS: 2x4 STUDS @ 16" O.C. OR 2x6 STUDS @ 24" O.C. 1ST FLOOR LOAD BEARING STUDS w/ WALK-UP ATTIC: 2x4 STUDS @ 12" O.C. OR 2x6 STUDS @ 16" O.C. BASEMENT LOAD BEARING STUDS: 2x4 STUDS @ 12" O.C. OR 2x6 STUDS @ 16" O.C. NON-LOAD BEARING STUDS (ALL FLOORS): 2x4 STUDS @ 24" O.C. TWO STORY WALLS: 2x4 STUDS @ 12" O.C. OR 2x6 STUDS @ 16" O.C. BALLOON FRAMED w/ CROSS BRACING @ 6'-0" O.C. VERTICALLY


KING STUD R	EQUIREMENTS
OPENING WIDTH	KINGS (EACH END)
LESS THAN 3'-0"	(1)
3'-0 TO 4'-0"	(2)
4'-0" TO 8'-0"	(3)
8'-0" TO 12'-0"	(5)
12'-0" TO 16'-0"	(6)


APPLY TO PORTAL FRAMED OPENINGS

BRACED WALL NOTES:

- 1) WALLS SHALL BE DESIGNED IN ACCORDANCE WITH SECTION R602.10 FROM THE 2015 INTERNATIONAL RESIDENTIAL CODE AS ALLOWED PER SECTION R602.10 OF THE 2018 NC RESIDENTIAL CODE.
- 1. WALLS ARE DESIGNED FOR SEISMIC ZONES A-C AND ULTIMATE WIND SPEEDS UP TO 130 MPH.
- 2. REFER TO ARCHITECTURAL PLAN FOR DOOR/WINDOW OPENING SIZES. 3. BRACING MATERIALS, METHODS AND FASTENERS SHALL BE IN ACCORDANCE WITH IRC TABLE R602.10.4.
- 4. ALL BRACED WALL PANELS SHALL BE FULL WALL HEIGHT AND SHALL NOT EXCEED 10 FEET FOR ISOLATED PANEL METHOD AND 12 FEET FOR CONTINUOUS SHEATHING METHOD WITHOUT ADDITIONAL ENGINEERING CALCULATIONS.
- 5. MINIMUM PANEL LENGTH SHALL BE PER TABLE R602.10.5. 6. THE INTERIOR SIDE OF EXTERIOR WALLS AND BOTH SIDES OF INTERIOR WALLS SHALL BE SHEATHED CONTINUOUSLY WITH MINIMUM 1/2" GYPSUM
- BOARD (UNO). 7. FOR CONTINUOUS SHEATHING METHOD, EXTERIOR WALLS SHALL BE SHEATHED ON ALL SHEATHABLE SURFACES INCLUDING INFILL AREAS BETWEEN BRACED WALL PANELS, ABOVE AND BELOW WALL OPENINGS,
- AND ON GABLE END WALLS. 8. FLOORS SHALL NOT BE CANTILEVERED MORE THAN 24" BEYOND THE FOUNDATION OR BEARING WALL BELOW WITHOUT ADDITIONAL
- ENGINEERING CALCULATIONS. 9. A BRACED WALL PANEL SHALL BE LOCATED WITHIN 10 FEET OF EACH END OF A BRACED WALL LINE.
- 10. THE MAXIMUM EDGE DISTANCE BETWEEN BRACED WALL PANELS SHALL NOT EXCEED 20 FEET.
- 11. MASONRY OR CONCRETE STEM WALLS WITH A LENGTH OF 48" OR LESS SUPPORTING A BRACED WALL PANEL SHALL BE DESIGNED IN ACCORDANCE WITH FIGURE R602.10.9 OF THE 2015 IRC.
- 12. BRACED WALL PANEL CONNECTIONS TO FLOOR/CEILING SHALL BE CONSTRUCTED IN ACCORDANCE WITH SECTION R602.10.8
- 13. BRACED WALL PANEL CONNECTIONS TO ROOF SHALL BE CONSTRUCTED IN ACCORDANCE WITH SECTION R602.10.8.2 AND FIGURES R602.10.8(1)&(2)&(3).
- 14. CRIPPLE WALLS AND WALK OUT BASEMENT WALLS SHALL BE DESIGNED IN ACCORDANCE WITH SECTION R602.10.11
- 15. PORTAL WALLS SHALL BE DESIGNED IN ACCORDANCE WITH FIGURE R602.10.6.4 (UNO)
- 17. ABBREVIATIONS:

GB = GYPSUM BOARD WSP = WOOD STRUCTURAL PANEL CS-XXX = CONT. SHEATHED ENG = ENGINEERED SOLUTION PF = PORTAL FRAME PF-ENG = ENG. PORTAL FRAME






ENGINEERING SEAL APPLIES ONLY TO STRUCTURAL COMPONENTS ON THIS DOCUMENT, SEAL DOES NOT INCLUDE CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, PROCEDURES OR SAFETY PRECAUTIONS. ANY DEVIATIONS OR DISCREPANCIES ON PLANS ARE TO BE BROUGHT TO THE IMMEDIATE ATTENTION OF UES PROFESSIONAL SOLUTIONS 29, INC. (UES) FAILURE TO DO SO WILL VOID (UES) LIABILITY.

STRUCTURAL ANALYSIS BASED ON 2018 NCRC.

FIRST FLOOR FRAMING PLAN SCALE: 1/4"=1'-0" ON 22"x34" OR 1/8"=1'-0" ON 11"x17"



	REQUIRED	BRACED W.	ALL PANEL CONNECT	FIONS
			REQUIRED	CONNECTION
METHOD	MATERIAL	MIN. THICKNESS	@ PANEL EDGES	@ INTERMEDIATE SUPPORTS
CS-WSP	WOOD STRUCTURAL PANEL	3/8"	6d COMMON NAILS @ 6" O.C.	6d COMMON NAILS @ 12" O.C.
GB	GYPSUM BOARD	1/2"	5d COOLER NAILS** @ 7" O.C.	5d COOLER NAILS** @ 7" O.C.
WSP	WOOD STRUCTURAL PANEL	3/8"	6d COMMON NAILS @ 6" O.C.	6d COMMON NAILS © 12" O.C.
PF	WOOD STRUCTURAL PANEL	7/16"	PER FIGURE R602.10.6.4	PER FIGURE R602.10.6.4

<u>GENERAL STRUCTURAL NOTES:</u>

- 1. CONSTRUCTION SHALL CONFORM TO 2018 NORTH CAROLINA RESIDENTIAL BUILDING CODE WITH ALL LOCAL AMENDMENTS.
- 2. CONTRACTOR SHALL VERIFY ALL DIMENSIONS. CONTRACTOR SHALL COMPLY WITH THE CONTENTS OF THE DRAWING FOR THIS SPECIFIC PROJECT. ENGINEER IS NOT RESPONSIBLE FOR ANY DEVIATIONS FROM THIS PLAN.
- 3. CONTRACTOR IS RESPONSIBLE FOR PROVIDING TEMPORARY BRACING REQUIRED TO RESIST ALL FORCES ENCOUNTERED DURING ERECTION.
- 4. PROPERTIES USED IN THE DESIGN ARE AS FOLLOWS: MICROLLAM (LVL): $F_b = 2600$ PSI, $F_v = 285$ PSI, $E = 1.9 \times 10^6$ PSI
- PARALLAM (PSL): $F_b = 2900$ PSI, $F_v = 290$ PSI, $E = 1.25 \times 10^6$ PSI
- 5. ALL WOOD MEMBERS SHALL BE #2 SYP/#2 SPF UNLESS NOTED ON PLAN. ALL STUD COLUMNS AND JOISTS SHALL BE #2 SYP/#2 SPF (UNO).
- 6. ALL BEAMS SHALL BE SUPPORTED WITH A (2) 2x4 #2 SYP/#2 SPF STUD COLUMN AT EACH END UNLESS NOTED OTHERWISE.
- 7. ALL REINFORCING STEEL SHALL BE GRADE 60 BARS CONFORMING TO ASTM A615 AND SHALL HAVE A MINIMUM COVER OF 3".
- 8. FOUNDATION ANCHORAGE SHALL BE CONSTRUCTED PER THE 2018 NORTH CAROLINA RESIDENTIAL CODE SECTION R403.1.6. MINIMUM 1/2" DIA. BOLTS SPACED AT 6'-0" ON CENTER WITH A 7" MINIMUM EMBEDMENT INTO MASONRY OR CONCRETE. ANCHOR BOLTS SHALL BE 12" FROM THE END OF EACH PLATE SECTION. MINIMUM (2) ANCHOR BOLTS PER PLATE SECTION. ANCHOR BOLTS SHALL BE LOCATED IN THE CENTER THIRD OF THE PLATE.
- 9. CONTRACTOR TO PROVIDED LOOKOUTS WHEN CEILING JOISTS SPAN PERPENDICULAR TO RAFTERS.
- 10. FLITCH BEAMS, 4-PLY LVLS AND 3-PLY SIDE LOADED LVLS SHALL BE BOLTED TOGETHER WITH 1/2" DIA. THRU BOLTS SPACED AT 24" O.C. (MAX) STAGGERED OR EQUIVALENT CONNECTIONS PER DETAIL 1/D3f. MIN. EDGE DISTANCE SHALL BE 2" AND (2) BOLTS SHALL BE LOCATED MINIMUM 6" FROM EACH END OF THE BEAM.
- 11. ALL NON-LOAD BEARING HEADERS SHALL BE (1) FLAT 2x4 SYP #2/SPF #2, DROPPED. FOR NON-LOAD BEARING HEADERS EXCEEDING 8'-0" IN WIDTH AND/OR WITH MORE THAN 2'-0" OF CRIPPLE WALL ABOVE, SHALL BE (2) FLAT 2x4 SYP #2/SPF #2, DROPPED. (UNLESS NOTED OTHERWISE)
- 12. ABBREVIATIONS:
 - DJ = DOUBLE JOIST SJ = SINGLE JOIST GT = GIRDER TRUSS FT = FLOOR TRUSSSC = STUD COLUMNEE = EACH END
 - TJ = TRIPLE JOIST CL = CENTER LINE
- DR = DOUBLE RAFTERTR = TRIPLE RAFTEROC = ON CENTERPL = POINT LOAD

NOTE:

IIII DESIGNATES JOIST SUPPORTED LOAD BEARING WALL ABOVE. PROVIDE BLOCKING UNDER JOIST SUPPORTED LOAD BEARING WALL.

JOIST & BEAM SIZES SHOWN ARE MINIMUMS. BUILDER MAY INCREASE DEPTH FOR EASE OF CONSTRUCTION.

INSTALL ANY REQUIRED HOLDOWNS PER SECTION R602.10.8 AND FIGURES R602.10.6.5, R602.10.7, R602.10.8(1) AND R602.10.8(2) OF THE 2015 IRC

NOTE: MEMBER NOTED AS PRESSURE TREATED MAY BE FRAMED WITH NON-PRESSURE TREATED LUMBER PROVIDED THE ENTIRETY OF THE MEMBER IS WRAPPED TO PREVENT MOISTURE INTRUSION.

THESE PLANS ARE DESIGNED IN ACCORDANCE WITH ARCHITECTURAL PLANS PROVIDED BY <u>DR HORTON</u> COMPLETED/REVISED ON 02/28/2020. IT IS THE RESPONSIBILITY OF THE CLIENT TO NOTIFY UES PROFESSIONAL SOLUTIONS 29, INC. (UES) IF ANY CHANGES ARE MADE TO THE ARCHITECTURAL PLANS PRIOR TO CONSTRUCTION. UES PROFESSIONAL SOLUTIONS 29, INC. (UES) CANNOT GUARANTEE THE ADEQUACY OF THESE STRUCTURAL PLANS WHEN USED WITH ARCHITECTURAL PLANS DATED DIFFERENTLY THAN THE DATE LISTED ABOVE.

STRUCTURAL MEMBERS ONLY

ENGINEERING SEAL APPLIES ONLY TO STRUCTURAL COMPONENTS ON THIS DOCUMENT, SEAL DOES NOT INCLUDE CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, PROCEDURES OR SAFETY PRECAUTIONS. ANY DEVIATIONS OR DISCREPANCIES ON PLANS ARE TO BE BROUGHT TO THE IMMEDIATE ATTENTION OF UES PROFESSIONAL SOLUTIONS 29, INC. (UES) FAILURE TO DO SO WILL VOID (UES) LIABILITY.

STRUCTURAL ANALYSIS BASED ON 2018 NCRC.


FIRST FLOOR FRAMING PLAN

SCALE: 1/4"=1'-0" ON 22"x34" OR 1/8"=1'-0" ON 11"x17"

BWL 2-1	(2) (2) (2)
BWL 2-2	A
	BWL 2-B

BWL 2-B

SECOND	FLOOR BRAC	ING (FT)		
CONTINUOUS SHEATHING METHOD				
	REQUIRED	PROVIDED		
BWL 2-1	6.8	30.1		
BWL 2-2	6.8	21.1		
BWL 2-A	5.9	41.0		
BWL 2-B	5.9	37.1		



PF = PORTAL FRAME PF-ENG = ENG. PORTAL FRAME

- GB = GYPSUM BOARD WSP = WOOD STRUCTURAL PANELCS-XXX = CONT. SHEATHED ENG = ENGINEERED SOLUTION
- 16. ON SCHEMATIC, SHADED WALLS INDICATE BRACED WALL PANELS. 17. ABBREVIATIONS:
- 12. BRACED WALL PANEL CONNECTIONS TO FLOOR/CEILING SHALL BE CONSTRUCTED IN ACCORDANCE WITH SECTION R602.10.8 13. BRACED WALL PANEL CONNECTIONS TO ROOF SHALL BE CONSTRUCTED IN ACCORDANCE WITH SECTION R602.10.8.2 AND FIGURES R602.10.8(1)&(2)&(3).

14. CRIPPLE WALLS AND WALK OUT BASEMENT WALLS SHALL BE DESIGNED

15. PORTAL WALLS SHALL BE DESIGNED IN ACCORDANCE WITH FIGURE

IN ACCORDANCE WITH SECTION R602.10.11

R602.10.6.4 (UNO)

- SUPPORTING A BRACED WALL PANEL SHALL BE DESIGNED IN ACCORDANCE WITH FIGURE R602.10.9 OF THE 2015 IRC.
- NOT EXCEED 20 FEET. 11. MASONRY OR CONCRETE STEM WALLS WITH A LENGTH OF 48" OR LESS
- END OF A BRACED WALL LINE. 10. THE MAXIMUM EDGE DISTANCE BETWEEN BRACED WALL PANELS SHALL
- ENGINEERING CALCULATIONS. 9. A BRACED WALL PANEL SHALL BE LOCATED WITHIN 10 FEET OF EACH
- 8. FLOORS SHALL NOT BE CANTILEVERED MORE THAN 24" BEYOND THE FOUNDATION OR BEARING WALL BELOW WITHOUT ADDITIONAL
- 7. FOR CONTINUOUS SHEATHING METHOD, EXTERIOR WALLS SHALL BE SHEATHED ON ALL SHEATHABLE SURFACES INCLUDING INFILL AREAS BETWEEN BRACED WALL PANELS, ABOVE AND BELOW WALL OPENINGS, AND ON GABLE END WALLS.
- WALLS SHALL BE SHEATHED CONTINUOUSLY WITH MINIMUM 1/2" GYPSUM BOARD (UNO).
- CALCULATIONS. 5. MINIMUM PANEL LENGTH SHALL BE PER TABLE R602.10.5. 6. THE INTERIOR SIDE OF EXTERIOR WALLS AND BOTH SIDES OF INTERIOR
- 4. ALL BRACED WALL PANELS SHALL BE FULL WALL HEIGHT AND SHALL NOT EXCEED 10 FEET FOR ISOLATED PANEL METHOD AND 12 FEET FOR CONTINUOUS SHEATHING METHOD WITHOUT ADDITIONAL ENGINEERING
- 3. BRACING MATERIALS, METHODS AND FASTENERS SHALL BE IN ACCORDANCE WITH IRC TABLE R602.10.4.
- 2. REFER TO ARCHITECTURAL PLAN FOR DOOR/WINDOW OPENING SIZES.
- SPEEDS UP TO 130 MPH.
- SECTION R602.10 OF THE 2018 NC RESIDENTIAL CODE. 1. WALLS ARE DESIGNED FOR SEISMIC ZONES A-C AND ULTIMATE WIND
- FROM THE 2015 INTERNATIONAL RESIDENTIAL CODE AS ALLOWED PER

<u>two_story_walls</u>:

VERTICALLY

BRAG	CED WA	<u>ll note</u>	<u>S:</u>				
1)					ACCORDANCE		

8'-0" TO 12'-0"	(5)
12'-0" TO 16'-0"	(6)
KING STUD REQUIREM APPLY TO PORTAL	ENTS ABOVE DO NOT FRAMED OPENINGS

2x4 STUDS @ 12" O.C. OR 2x6 STUDS @ 16" O.C.

BALLOON FRAMED w/ CROSS BRACING @ 6'-0'' O.C.

LESS THAN 3'-0"

3'-0 TO 4'-0"

4'-0" TO 8'-0"

KING STUD REQUIREMENTS

OPENING WIDTH KINGS (EACH END)

(2)

O NOT

WALL STUD SCHEDULE
<u>1ST & 2ND FLOOR LOAD BEARING STUDS:</u>
2x4 STUDS @ 16" O.C. OR 2x6 STUDS @ 24" O.C.
<u>1ST FLOOR LOAD BEARING STUDS w/ WALK-UP ATTIC:</u>
2x4 STUDS @ 12" O.C. OR 2x6 STUDS @ 16" O.C.
BASEMENT LOAD BEARING STUDS:
2x4 STUDS @ 12" O.C. OR 2x6 STUDS @ 16" O.C.
<u>NON–LOAD BEARING STUDS (ALL FLOORS):</u>
2x4 STUDS @ 24" O.C.


SECURE LINTEL TO HEADER w/(2) 1/2" DIAMETER LAG

ALL HEADERS WHERE BRICK IS USED, TO BE: (1)(UNO)

SCREWS STAGGERED @ 16" O.C. (TYP FOR (3))

ALL HEADERS TO BE	ERRIDE SC LISTED ABO	TED OTHERWISE. SC
L	INTEL SCHEDUL	Ē
TAG	SIZE	OPENING SIZE
	L3x3x1/4"	LESS THAN 6'-0"
2	L5x3x1/4"	6'-0" TO 10'-0"
3	L5x3-1/2"x5/16"	greater than 10'—0'
4	L5x3-1/2"x5/16" ROLLED OR EQUIV.	ALL ARCHED OPENINGS

HEADER SCHEDULE					
TAG	SIZE	JACKS (EACH END)			
A	(2) 2x6	(1)			
В	(2) 2x8	(2)			
С	(2) 2x10	(2)			
D	(2) 2x12	(2)			
E	(2) 9–1/4" LSL/LVL	(3)			
F	(3) 2x6	(1)			
G	(3) 2x8	(2)			
Н	(3) 2x10	(2)			
	(3) 2x12	(2)			
	HEADER SIZES SHOWN ON PLANS ARE MINIMUMS. GREATER HEADER SIZES MAY BE USED FOR EASE OF CONSTRUCTION.				



TRUS	SS UPLIFT C	ONNECTOR SC	HEDULE		
MAX. UPLIFT	ROOF TO WALL	FLOOR TO FLOOR	FLOOR TO FND		
600 LBS	H2.5A	PER WALL SHEATHIN	G & FASTENERS		
1200 LBS	(2) H2.5A	CS16 (END = 11")	DTT2Z		
1450 LBS	HTS20	CS16 (END = 11")	DTT2Z		
2000 LBS	(2) MTS20	(2) CS16 (END = 11")	DTT2Z		
2900 LBS	(2) HTS20	(2) CS16 (END = 11")	HTT4		
3685 LBS	LGT3-SDS2.5	MSTC52	HTT4		
PRODUCTS MA 2. UPLIFT VA 3. REFER TC TRUSS TO TR MANUFACTURE	3685 LBSLGT3-SDS2.5MSTC52HTT41. ALL PRODUCTS LISTED ARE SIMPSON STRONG-TIE. EQUIVALENT PRODUCTS MAY BE USED PER MANUFACTURER'S SPECIFICATIONS. 2. UPLIFT VALUES LISTED ARE FOR SYP #2 GRADE MEMBERS. 3. REFER TO TRUSS LAYOUT PER MANUF. FOR UPLIFT VALUES AND TRUSS TO TRUSS CONNECTIONS. CONNECTORS SPECIFIED BY TRUSS MANUFACTURER OVERRIDE THOSE LISTED ABOVE. 4. CONTACT UES FOR REQUIRED CONNECTORS WHEN LOADS EXCEED				

NOTE: 1ST PLY OF ALL SHOWN GIRDER TRUSSES TO ALIGN WITH INSIDE FACE OF WALL (TYP, UNO)

NOTE: ROOF TRUSSES SHALL BE SPACED TO SUPPORT FALSE FRAMED DORMER WALLS (TYP, UNO)

REFER TO DETAIL 5/D3F FOR EYEBROW, RETURN OR SHED ROOF FRAMING REQUIREMENTS. (TYP FOR ROOFS PROTRUDING MAXIMUM 24" FROM STRUCTURE)

NOTE: TRUSS UPLIFT LOADS SHALL BE DETERMINED PER TRUSS MANUFACTURER IN ACCORDANCE WITH SECTION R802.11.1.1. WALL SHEATHING AND FASTENERS HAVE BEEN DESIGNED TO RESIST THE WIND UPLIFT LOAD PATH IN ACCORDANCE WITH METHOD 3 OF SECTION R602.3.5 OF THE 2018 IRC. REFER TO BRACED WALL PLANS FOR SHEATHING AND FASTENER REQUIREMENTS.

THESE PLANS ARE DESIGNED IN ACCORDANCE WITH ARCHITECTURAL PLANS PROVIDED BY <u>DR HORTON</u> COMPLETED/REVISED ON <u>02/28/2020</u>. IT IS THE RESPONSIBILITY OF THE CLIENT TO NOTIFY UES PROFESSIONAL SOLUTIONS 29, INC. (UES) IF ANY CHANGES ARE MADE TO THE ARCHITECTURAL PLANS PRIOR TO CONSTRUCTION. UES PROFESSIONAL SOLUTIONS 29, INC. (UES) CANNOT GUARANTEE THE ADEQUACY OF THESE STRUCTURAL PLANS WHEN USED WITH ARCHITECTURAL PLANS DATED DIFFERENTLY THAN THE DATE LISTED ABOVE.


STRUCTURAL MEMBERS ONLY

ENGINEERING SEAL APPLIES ONLY TO STRUCTURAL COMPONENTS ON THIS DOCUMENT, SEAL DOES NOT INCLUDE CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, PROCEDURES OR SAFETY PRECAUTIONS. ANY DEVIATIONS OR DISCREPANCIES ON PLANS ARE TO BE BROUGHT TO THE IMMEDIATE ATTENTION OF UES PROFESSIONAL SOLUTIONS 29, INC. (UES) FAILURE TO DO SO WILL VOID (UES) LIABILITY.


STRUCTURAL ANALYSIS BASED ON 2018 NCRC.

ROOF FRAMING PLAN

SCALE: 1/4"=1'-0" ON 22"x34" OR 1/8"=1'-0" ON 11"x17"



<u> Roof Framing Plan – Elevation C</u>



uuuu	ion Type: Con	nmerical 🗆	Residential	\boxtimes		
201	Building Code 18 North Caroli CE 7—10: Minir	na Residential				S
In Lo	ads: Roof Live Load	40				
1.	1.1. Conven ⁴ 1.2. Truss	tional 2x				20 PSF
2.	Roof Dead Loo 2.1. Convent	ads tional 2x				10 PSF
3.	2.2. Truss Snow					
		ince Factor				
4.	4.1. Typ. Dw 4.2. Sleeping 4.3. Decks	velling g Areas				30 PSF 40 PSF
5.	Floor Dead Lo 5.1. Convent 5.2. I-Joist	ads tional 2x				10 PSF 15 PSF
6.	5.3. Floor Ti Ultimate Wind					
	Exposure					В
8.	Component an					1.0
	MEAN ROOF HT.	UP TO 30'	30'1"-35'	35'1"-40'	40'1"-45'	
	ZONE 1		17.5,-18.9			
		16.7,-21.0		18.2,-22.9		
				18.2,-22.9	18.7,-23.5	
	ZONE 3	16.7,-21.0	17.5,-22.1	· · · · · · · · · · · · · · · · · · ·		
	ZONE 3 ZONE 4	18.2,-19.0	19.2,-20.0	19.9,-20.7	20.4,-21.3	
0	ZONE 3 ZONE 4 ZONE 5			· · · · · · · · · · · · · · · · · · ·	20.4,-21.3 20.4,-26.9	
9.	ZONE 3 ZONE 4 ZONE 5 Seismic 9.1. Site Clo 9.2. Design 9.3. Importa 9.4. Seismic 9.5. Basic S	18.2,-19.0 18.2,-24.0 Category nce Factor Use Group Use Group Bearing Wa □ Building Fro □ Moment Fr	19.2,-20.0 19.2,-25.2 em (check or III ame ame	19.9,-20.7 19.9,-26.1 e)		C 1.0
9.	ZONE 3 ZONE 4 ZONE 5 Seismic 9.1. Site Clo 9.2. Design 9.3. Importa 9.4. Seismic 9.5. Basic S	18.2,-19.0 18.2,-24.0 18.2,-24.0 Sss Category Use Group Use Jos Dual w/ In Inverted Pe	19.2,-20.0 19.2,-25.2 em (check or Ill ame ame becial Moment termediate R _/ endulum	19.9,-20.7 19.9,-26.1 e) Frame ′C or Special	20.4,-26.9	C 1.0 1

GENERAL STRUCTURAL NOTES:

- The design professional whose seal appears on these drawings is the structural engineer of record (SER) for this project. The SER bears the responsibility of the primary structural elements and the performance of this structure. No other party may revise, alter, or delete any structural aspects of these construction documents without written permission of UES Professional Solutions 29, Inc. (UES) or the SER. For the purposes of these construction documents the SER and UES shall be considered the same entity.
- 2. The structure is only stable in its completed form. The contractor shall provide all required temporary bracing during construction to stabilize the structure.
- 3. The SER is not responsible for construction sequences, methods, or techniques in connection with the construction of this structure. The SER will not be held responsible for the contractor's failure to conform to the contract documents. should any non-conformities occur.
- 4. Any structural elements or details not fully developed on the construction drawings shall be completed under the direction of a licensed professional engineer. These shop drawings shall be submitted to UES for review before any construction begins. The shop drawings will be reviewed for overall compliance as it relates to the structural design of this project. Verification of the shop drawings for dimensions, or for actual field conditions, is not the responsibility of the SER or UES.
- 5. Verification of assumed field conditions is not the responsibility of the SER. The contractor shall verify the field conditions for accuracy and report any discrepancies to UES before construction begins.
- 6. The SER is not responsible for any secondary structural elements or non-structural elements, except for the elements specifically noted on the structural drawings.
- . This structure and all construction shall conform to all applicable sections of the international residential code.
- 8. This structure and all construction shall conform to all applicable sections of local building codes.
- 9. All structural assemblies are to meet or exceed to requirements of the current local building code.

FOUNDATIONS:

The structural engineer has not performed a subsurface investigation. Verification of this assumed value is the responsibility of the owner or the contractor. Should any adverse soil condition be encountered the SER must be contacted before proceeding.

- 2. The bottom of all footings shall extend below the frost line for the region in which the structure is to be constructed. However, the bottom of all footings shall be a minimum of 12" below grade.
- 3. Any fill shall be placed under the direction or recommendation of a licensed professional engineer.
- 4. The resulting soil shall be compacted to a minimum of 95% maximum dry density.
- 5. Excavations of footings shall be lined temporarily with a 6 mil polyethylene membrane if placement of concrete does not occur within 24 hours of excavation.
- 6. No concrete shall be placed against any subgrade containing water, ice, frost, or loose material.

STRUCTURAL STEEL:

- . Structural steel shall be fabricated and erected in accordance with the American Institute of Steel Construction "Code of Standard Practice for Steel Buildings and Bridges" and the manual of Steel Construction "Load Resistance Factor Design" latest editions.
- 2. Structural steel shall receive one coat of shop applied
- rust-inhibitive paint. 3. All steel shall have a minimum yield stress (F_v) of 36 ksi unless
- otherwise noted. 4. Welding shall conform to the latest edition of the American
- Welding Society's Structural Welding Code AWS D1.1. Electrodes for shop and field welding shall be class E70XX. All welding shall be performed by a certified welder per the above standards.

CONCRETE:

- . Concrete shall have a normal weight aggregate and a minimum compressive strength (f'c) at 28 days of 3000 psi, unless otherwise noted on the plan.
- Concrete shall be proportioned, mixed, and placed in accordance with the latest editions of ACI 318: "Building Code Requirements for Reinforced Concrete" and ACI 301: "Specifications for Structural Concrete for Buildings".
- 3. Air entrained concrete must be used for all structural elements exposed to freeze/thaw cycles and deicing chemicals. Air entrainment amounts (in percent) shall be within -1% to +2% of target values as follows:
- 3.1. Footings: 5%
- 3.2. Exterior Slabs: 5% 4. No admixtures shall be added to any structural concrete without written permission of the SER.

- 5. Concrete slabs—on—grade shall be constructed in accordance with ACI 302.1R-96: "Guide for Concrete Slab and Slab Construction". 6. The concrete slab-on-grade has been designed using a subgrade modulus of k=250 pci and a design loading of 200 psf. The SER is not responsible for differential settlement, slab cracking or other future defects resulting from unreported conditions not in accordance with the above assumptions. 7. Control or saw cut joints shall be spaced in interior

- supported during the concrete pour.

CONCRETE REINFORCEMENT:

- 1. Fibrous concrete reinforcement, or fibermesh, specified in concrete slabs-on-grade may be used for control of cracking due to shrinkage and thermal expansion/contraction, lowered water migration, an increase in impact capacity, increased abrasion resistance, and residual strength.
- 2. Fibermesh reinforcing to be 100% virgin polypropylene fibers containing no reprocessed olefin materials and specifically
- manufactured for use as concrete secondary reinforcement.

- standard.
- ASTM A615, grade 60.
- 7. Horizontal footing and wall reinforcement shall be continuous and shall have 90° bends, or corner bars with the same size/spacing as the horizontal reinforcement with a class B tension splice. 8. Lap reinforcement as required, a minimum of 40 bar diameters for tension or compression unless otherwise noted. Splices in masonry shall be a minimum of 48 bar diameters.

		T ENGINEE TESTING I	RING, LABORATORY, & NC.
\subset	STRUCTUR		
\subset		RAL PLANS PF	REPARED FOR:
\bigcirc	TANDARD		AILS (OX-IS)
PROJE TBD	CT ADDRESS:	DR 800	NER: Horton Carolinas Division 01 Arrowridge Blvd arlotte, NC 28273
Duiuti	, GA 30097		
electric structu the co	al, and civil drawings. Th ral engineering of record ntractor shall notify UES	nis coordinatio (SER). Shoul	on is not the responsibility of the
electric structu the co constru	al, and civil drawings. Th ral engineering of record ntractor shall notify UES action begins.	nis coordinatio (SER). Shoul	on is not the responsibility of the d any discrepancies become appc
electric structu the co constru <u>PLAN</u>	al, and civil drawings. Th ral engineering of record ntractor shall notify UES Iction begins. ABBREVIATIONS:	nis coordinatio (SER). Shoul Professional S	on is not the responsibility of the d any discrepancies become appa Solutions 29, Inc. (UES) before
electric structu the co constru	al, and civil drawings. Th ral engineering of record ntractor shall notify UES action begins.	nis coordinatio (SER). Shoul	on is not the responsibility of the d any discrepancies become appa Solutions 29, Inc. (UES) before PRESSURE TREATED
electric structu the co constru <u>PLAN</u> AB	al, and civil drawings. Th ral engineering of record htractor shall notify UES Iction begins. ABBREVIATIONS: ANCHOR BOLT	nis coordinatio (SER). Shoul Professional S	d any discrepancies become appa Solutions 29, Inc. (UES) before PRESSURE TREATED ROOF SUPPORT
electric structu the co constru <u>PLAN</u> <u>AB</u> AFF	al, and civil drawings. Th ral engineering of record ntractor shall notify UES Iction begins. ABBREVIATIONS: ANCHOR BOLT ABOVE FINISHED FLOOR	nis coordinatio (SER). Shoul Professional S PT PT RS	on is not the responsibility of the d any discrepancies become appa Solutions 29, Inc. (UES) before PRESSURE TREATED ROOF SUPPORT STUD COLUMN
electric structu the co constru <u>PLAN</u> AB AFF CJ	al, and civil drawings. Th ral engineering of record ntractor shall notify UES action begins. ABBREVIATIONS: ANCHOR BOLT ABOVE FINISHED FLOOR CEILING JOIST CLEAR DOUBLE JOIST	nis coordinatio (SER). Shoul Professional S PT RS SC	on is not the responsibility of the d any discrepancies become appa Solutions 29, Inc. (UES) before PRESSURE TREATED ROOF SUPPORT STUD COLUMN SINGLE JOIST
electric structu the co constru PLAN AB AFF CJ CLR DJ DSP	al, and civil drawings. Th ral engineering of record ntractor shall notify UES action begins. ABBREVIATIONS: ANCHOR BOLT ABOVE FINISHED FLOOR CEILING JOIST CLEAR DOUBLE JOIST DOUBLE STUD POCKET	nis coordinatio (SER). Shoul Professional S PT RS SC SC SC SC SC SC SC	on is not the responsibility of the d any discrepancies become appa Solutions 29, Inc. (UES) before PRESSURE TREATED ROOF SUPPORT STUD COLUMN SINGLE JOIST SINGLE JOIST SPRUCE PINE FIR SIMPSON STRONG-TIE
electric structu the co constru PLAN AB AFF CJ CLR DJ DSP EE	al, and civil drawings. Th ral engineering of record ntractor shall notify UES action begins. ABBREVIATIONS: ANCHOR BOLT ABOVE FINISHED FLOOR CEILING JOIST CLEAR DOUBLE JOIST DOUBLE STUD POCKET EACH END	nis coordinatio (SER). Shoul Professional S PT RS SC SJ SPI SYF	on is not the responsibility of the d any discrepancies become appa Solutions 29, Inc. (UES) before PRESSURE TREATED ROOF SUPPORT STUD COLUMN SINGLE JOIST SPRUCE PINE FIR SIMPSON STRONG-TIE SOUTHERN YELLOW PINE
electric structu the co constru PLAN AFF CJ CLR DJ DSP EE EW	al, and civil drawings. Th ral engineering of record ntractor shall notify UES action begins. ABBREVIATIONS: ANCHOR BOLT ABOVE FINISHED FLOOR CEILING JOIST CLEAR DOUBLE JOIST DOUBLE STUD POCKET EACH END EACH WAY	nis coordinatio (SER). Shoul Professional S PT RS SC SC SC SP SC SY SY TJ	on is not the responsibility of the d any discrepancies become appa Solutions 29, Inc. (UES) before PRESSURE TREATED ROOF SUPPORT STUD COLUMN SINGLE JOIST SIMPSON STRONG-TIE SOUTHERN YELLOW PINE TRIPLE JOIST
electric structu the co constru PLAN AB AFF CJ CLR DJ DSP EE EW NTS	al, and civil drawings. Th ral engineering of record ntractor shall notify UES action begins. ABBREVIATIONS: ANCHOR BOLT ABOVE FINISHED FLOOR CEILING JOIST CLEAR DOUBLE JOIST DOUBLE STUD POCKET EACH END EACH WAY NOT TO SCALE	nis coordinatio (SER). Shoul Professional S PT RS SC SPF SS SYF TJ TJ	on is not the responsibility of the d any discrepancies become appa Solutions 29, Inc. (UES) before PRESSURE TREATED ROOF SUPPORT STUD COLUMN SINGLE JOIST SPRUCE PINE FIR SIMPSON STRONG-TIE SOUTHERN YELLOW PINE TRIPLE JOIST P TRIPLE STUD POCKET
electric structu the co constru PLAN AFF CJ CLR DJ DSP EE EW NTS OC	al, and civil drawings. Th ral engineering of record ntractor shall notify UES action begins. ABBREVIATIONS: ANCHOR BOLT ABOVE FINISHED FLOOR CEILING JOIST CLEAR DOUBLE JOIST DOUBLE JOIST DOUBLE STUD POCKET EACH END EACH WAY NOT TO SCALE ON CENTER	nis coordinatio (SER). Shoul Professional S PT RS SC SC SC SC SC SC SC SC SC SC SC SC SC	on is not the responsibility of the d any discrepancies become appa Solutions 29, Inc. (UES) before PRESSURE TREATED ROOF SUPPORT STUD COLUMN SINGLE JOIST SUD COLUMN SINGLE JOIST SPRUCE PINE FIR SIMPSON STRONG-TIE SOUTHERN YELLOW PINE TRIPLE JOIST P TRIPLE STUD POCKET P TYPICAL
electric structu the co constru PLAN AB AFF CJ CLR DJ DSP EE EW NTS	al, and civil drawings. Th ral engineering of record ntractor shall notify UES action begins. ABBREVIATIONS: ANCHOR BOLT ABOVE FINISHED FLOOR CEILING JOIST CLEAR DOUBLE JOIST DOUBLE STUD POCKET EACH END EACH WAY NOT TO SCALE	nis coordinatio (SER). Shoul Professional S PT RS SC SPF SS SYF TJ TJ TSF TYF	on is not the responsibility of the d any discrepancies become appo Solutions 29, Inc. (UES) before PRESSURE TREATED ROOF SUPPORT STUD COLUMN SINGLE JOIST STUD COLUMN SINGLE JOIST SPRUCE PINE FIR SIMPSON STRONG-TIE SOUTHERN YELLOW PINE TRIPLE JOIST P TRIPLE STUD POCKET P TYPICAL D UNLESS NOTED OTHERWISE

	1			
D1c		Crawl Space Foundation Details		
D1b		Basement Foundation Details		
D1f			Framing Details	
REVISION L	IST			
	<u></u>			
Revision No.	Date	Project No.	Description	
1	5.11.17		Added box bay detail (2/D2f). Added deck option: with basement. Revised deck options with stem w and crawl space foundations	
2	7.12.17		Revised stem wall insulation note.	
3	2.15.18		Revised garage door detail, NC only	
4	2.28.18		Added high-wind foundation details	
5	12.19.18		Revised per 2018 NCRC	
6	2.19.19		Revised per Mecklenburg County Comments	
7	3.1.19		Revised stem wall deck attachment and roof sheathing on wall sections.	
8	3.6.19		Corrected dimensions at perimeter footings	
9	3.2.20		Added tall turndown detail	
10	3.18.20		Added balloon framing detail	
11	10.20.20		Added alternate two-pour detail for slab and added note for crawl girder above grade	
12	3.1.21		Added OX—IS Standard Details	
13	5.18.21		Updated OX—IS Standard Details	
14	02.14.23		Added 4/D2m — Tall Slab Detail w/ Siding	
15	08.10.23		Updated (Hit HY150 Adhesive) for HY200 Adhesive	
16	04.01.24		Added Hilti Kwik Bolt KBI 1/2-5 TO Wall Anchor Schedule	
17	4.26.24		Update Wall Anchor Schedule	
18	5.06.24		Update Wall Anchor Schedule	

Description

Cover Sheet, Specifications, Revisions

Monolithic Slab Foundation Details

Stem Wall Foundation Details

<u>Sheet list:</u>

Sheet No. CS1

D1m

D1s

slabs—on—grade at a maximum of 15'—0" O.C. and in exterior slabs-on-grade at a maximum of 10'-0" unless otherwise noted. 8. Control or saw cut joints shall be produced using conventional process within 4 to 12 hours after the slab has been finished 9. Reinforcing steel may not extend through a control joint. Reinforcing steel may extend through a saw cut joint. 10. All welded wire fabric (W.W.F.) for concrete slabs-on-grade shall be placed at mid-depth of slab. The W.W.F. shall be securely

3. Application of fibermesh per cubic yard of concrete shall equal a minimum of 0.1% by volume (1.5 pounds per cubic yard) 4. Fibermesh shall comply with ASTM C1116, any local building code requirements, and shall meet or exceed the current industry

5. Steel reinforcing bars shall be new billet steel conforming to

6. Detailing, fabrication, and placement of reinforcing steel shall be in accordance with the latest edition of ACI 315: "Manual of Standard Practice for Detailing Concrete Structures"

- 9. Where reinforcing dowels are required , they shall be equivalent in size and spacing to the vertical reinforcement. The dowel shall extend 48 bar diameters vertically and 20 bar diameters into the footing.
- 10. Where reinforcing steel is required vertically, dowels shall be provided unless otherwise noted.
- 11. Unless otherwise specified, concrete reinforcing is not required.

WOOD FRAMING:

- 1. Solid sawn wood framing members shall conform to the specifications listed in the latest edition of the "National Design Specification for Wood Construction" (NDS). Unless otherwise noted, all wood framing members are designed to be Spruce-Yellow-Pine(SYP)#2.
- 2. LVL or PSL engineered wood shall have the following minimum design

values:				
1.	F	=	1.900.000	DS

۱.	E =	1,900,0	υυ μ
2.	$F_h =$	2600 p	osi

- 2.3. F_v = 285 psi
- 2.4. F_c = 700 psi
- 3. Wood in contact with concrete, masonry, or earth shall be pressure treated in accordance with AWPA standard C-15. All other moisture exposed wood shall be treated in accordance with AWPA standard C-2
- 4. Nails shall be common wire nails unless otherwise noted.
- 5. Lag screws shall conform to ANSI/ASME standard B18.2.1-1981. Lead holes for lag screws shall be in accordance with NDS specifications.
- 6. All beams shall have full bearing on supporting framing members unless otherwise noted.
- 7. Exterior and load bearing stud walls are to be 2x4 SYP #2 @ 16" O.C. unless otherwise noted. Studs shall be continuous from the sole plate to the double top plate. Studs shall only be discontinuous at headers for window/door openings. A minimum of one king stud shall be placed at each end of the header. King studs shall be continuous.
- 8. Individual studs forming a column shall be attached with one 10d nail @ 6" O.C. staggered. The stud column shall be continuous to the foundation or beam. The column shall be properly blocked at all floor levels to ensure proper load transfer.
- 9. Multi-ply beams shall have each ply attached with (3) 10d nails @ 24"O.C.

10. Flitch beams, 4-ply beams and 3-ply side loaded beams shall be bolted together with (2) rows of 1/2" diameter through bolts staggered @ 24" O.C. per schedule unless noted otherwise. Min. edge distance shall be 2" and (2) bolts shall be located a min. 6" from each end of the beam.

WOOD TRUSSES:

- 1. The wood truss manufacturer/fabricator is responsible for the design of the wood trusses. Submit sealed shop drawings and supporting calculations to the SER for review prior to fabrication. The SER shall have a minimum of five (5) days for review. The review by the SER shall review for overall compliance with the design documents. The SER shall assume no responsibility for
- the correctness for the structural design for the wood trusses. 2. The wood trusses shall be designed for all required loadings as specified in the local building code, the ASCE Standard "Minimum Desian Loads for Buildings and Other Structures." (ASCE 7-05). and the loading requirements shown on these specifications. The truss drawings shall be coordinated with all other construction documents and provisions provided for loads shown on these drawings including but not limited to HVAC equipment, piping, and architectural fixtures attached to the trusses.
- 3. The trusses shall be designed, fabricated, and erected in accordance with the latest edition of the "National Design Specification for Wood Construction." (NDS) and "Design Specification for Metal Plate Connected Wood Trusses."
- 4. The truss manufacturer shall provide adequate bracing information in accordance with "Commentary and Recommendations for Handling, Installing, and Bracing Metal Plate Connected Wood Trusses" (HIB-91). This bracing, both temporary and permanent, shall be shown on the shop drawings. Also, the shop drawings shall show the required attachments for the trusses.
- 5. Any chords or truss webs shown on these drawings have been shown as a reference only. The final design of the trusses shall be per the manufacturer.

EXTERIOR WOOD FRAMED DECKS:

1. Decks are to be framed in accordance with local building codes and as referenced on the structural plans, either through code references or construction details.

Manager	Signature	
Operations		
Operations System		
Operations Product Development		


UES PROFESSIONAL SOLUTIONS 29, INC. CARGENERITY SUMMIT ENGINEERING, LBORATORY, & TESTING, INC. 10121 Pineville Distribution SF Pineville, NC 28134 Office: 704.504.1125 WWW.teamues.com UES PROFESSIONAL SOLUTIONS 29, INC. No. F-1454 OF AUTHON
CLIENT: DR Horton Carolina Division 8001 Arrowridge Blvd. Charlotte, NC 28273
PROJECT: standard Details (0X-IS) Coversheet
O5.06.2024 SEAL O20222 GINEER O2022 O20222 GINEER O2022 O202

C21

WOOD STRUCTURAL PANELS: 1. Fabrication and placement of structural wood sheathing shall be in accordance with the APA Design/Construction Guide "Residential and Commercial," and all other applicable APA

standards. 2. All structurally required wood sheathing shall bear the mark of the APA.

- 3. Wood wall sheathing shall comply with the requirements of local building codes for the appropriate state as indicated on these drawings. Refer to wall bracing notes in plan set for more information. Sheathing shall be applied with the long direction perpendicular to framing, unless noted otherwise.
- 4. Roof sheathing shall be APA rated sheathing exposure 1 or 2. Roof sheathing shall be continuous over two supports and attached to its supporting roof framing with (1)-8d CC nail at 6"o/c at panel edges and at 12"o/c in panel field unless otherwise noted on the plans. Sheathing shall be applied with the long direction perpendicular to framing. Sheathing shall have a span rating consistent with the framing spacing. Use suitable edge support by use of plywood clips or lumber blocking unless otherwise noted. Panel end joints shall occur over framing. Apply building paper over the sheathing as required by the state Building Code.
- 5. Wood floor sheathing shall be APA rated sheathing exposure 1 or 2. Attach sheathing to its supporting framing with (1)-8d CC ringshank nail at 6"o/c at panel edges and at 12"o/c in panel field unless otherwise noted on the plans. Sheathing shall be applied perpendicular to framing. Sheathing shall have a span rating consistent with the framing spacing. Use suitable edge support by use of T&G plywood or lumber blocking unless otherwise noted. Panel end joints shall occur over framing. Apply building paper over the sheathing as required by the state Building Code.
- 5. Sheathing shall have a 1/8" gap at panel ends and edges as recommended in accordance with the APA.



L AND HEIGHT 3	CHEDOLL
HOLLOW	SOLID
UP TO 32" HEIGHT	UP TO 5'-0" HEIGHT
UP TO 48" HEIGHT	UP TO 9'-0" HEIGHT
UP TO 64" HEIGHT	UP TO 12'-0" HEIGHT*
	UP TO 12'-0" HEIGHT*
:ont. rebar w/ #3 s	STIRRUPS @ 16" O.C.
MIN. LAP JOINTS	


RIES	WIDTH BASED (ON SOIL BEARIN	g capacity
	1500 PSF	2000 PSF	2500 PSF
- STD.	16"	16"	16"
– BRICK VENEER	21"*	21"*	21"*
- STD.	16"	16"	16"
– BRICK VENEER	21"*	21"*	21"*
– STD.	23"	18"	18"
– BRICK VENEER	32"*	24"*	24"*
CLEDGE HAS BEEN A	DDED TO THE	CRAWL SPACE	
WIDTH FOR BRICK S	UPPORT		


	MIN. CONC.	SPACING	INTERIOR	EXTERIOR
	EMBEDMENT		WALL	WALL
w/	7"	6'-0"	YES	YES
	4"	5'-0"	NO	YES
1/2"ø – 8"	6-1/2"	6'-0"	YES	YES
ed Rod	7"	6'-0"	YES	YES
ESIVE				
OLT,	7"	6'-0"	YES	YES –2
r equivalent				

2. EXPANSION ANCHORS MAY BE INSTALLED ONLY AS ALLOWED PER MANUFACTURE SPECIFICATIONS.

<u>NOTES:</u>

- 1. REFER TO GENERAL NOTES & SPECIFICATIONS ON COVERSHEET FOR ADDITIONAL INFORMATION.
- 2. PROVIDE 6 MIL VAPOR BARRIER UNDER ALL SLABS-ON-GRADE. 3. SEE ARCH. DWGS. FOR ALL TOP OF THE SLAB ELEVATIONS, SLOPES AND DEPRESSIONS.
- 4. REFER TO STRUCTURAL PLANS AND FRAMING DETAILS FOR BRACED WALL PANEL LAYOUT, DIMENSIONS, ATTACHMENT AND CONNECTIONS
- 5. REFER TO LOCAL AND STATEWIDE CODES FOR ADDITIONAL AMENDMENTS AND REQUIREMENTS NOT SHOWN
- 6. PERIMETER INSULATION SHOWN AS REQUIRED BY LOCAL CLIMATE ZONE. INSTALL PER TABLE N1102.1.2 OF THE 2018 NCRC





DECK ATTACHMENT SCHEDULE	(ALL STRUCTURES EXCEPT BRICK)
--------------------------	------------------------------	---

		/
FASTENERS	MAX. 8'-0" JOIST	MAX. 16'-0" JOIST
	SPAN	SPAN
5/8" GALV. BOLTS w/ NUT & WASHER ^b	(1) @ 3'-6" O.C.	(1) @ 1'-8" O.C.
AND	AND	AND
12d COMMON GALV. NAILS ^C	(2) @ 8" O.C.	(3) @ 6" O.C.

a. ATTACHMENT INTERPOLATION BETWEEN 8' AND 16' JOIST SPANS IS ALLOWED. b. MINIMUM EDGE DISTANCE FOR BOLTS IS $2\frac{1}{2}$ ".

c. NAILS MUST PENETRATE THE SUPPORTING STRUCTURE BAND A MINIMUM OF $1\frac{1}{2}$ "

DECK ATTACHMENT SCHEDULE (BRICK STRUCTURES)


FASTENERS	MAX. 8'-0" JOIST	MAX. 16'-0" JOIST
	SPAN	SPAN
5/8" GALV. BOLTS w∕ NUT & WASHER♭	(1) @ 2'-4" O.C.	(1) @ 1'-4" O.C.

a. ATTACHMENT INTERPOLATION BETWEEN 8' AND 16' JOIST SPANS IS ALLOWED. b. MINIMUM EDGE DISTANCE FOR BOLTS IS $2\frac{1}{2}$ ".

CRAWL SPACE FOOTING WIDTH

# OF STORIES	WIDTH BASED	ON SOIL BEARIN	G
	1500 PSF	2000 PSF	25
1 STORY – STD.	16"	16"	16
1 STORY – BRICK VENEER	21"*	21"*	2
2 STORY – STD.	16"	16"	16
2 STORY – BRICK VENEER	21"*	21"*	2
3 STORY – STD.	23"	18"	18
3 STORY – BRICK VENEER	32"*	24"*	24
*5" BRICK LEDGE HAS BEEN A	ADDED TO THE	CRAWL SPACE	

FOOTING WIDTH FOR BRICK SUPPORT




CAPACITY 2500 PSF 1"* 1"* 74"*


*BRICK TIES SPACED @ 16" O.C. HORIZ. & 24" O.C. VERT. AND 3/16"Ø WEEP HOLES @ 33" O.C. LOCATED A MINIMUM OF 4" ABOVE THE EARTH

NOTES:

- 1. REFER TO GENERAL NOTES & SPECIFICATIONS ON COVERSHEET FOR ADDITIONAL INFORMATION.
- 2. PROVIDE 6 MIL VAPOR BARRIER UNDER ALL SLABS-ON-GRADE. 3. SEE ARCH. DWGS. FOR ALL TOP OF THE SLAB ELEVATIONS, SLOPES AND DEPRESSIONS.
- 4. REFER TO STRUCTURAL PLANS AND FRAMING DETAILS FOR BRACED WALL PANEL LAYOUT, DIMENSIONS, ATTACHMENT AND CONNECTIONS
- 5. REFER TO LOCAL AND STATEWIDE CODES FOR ADDITIONAL AMENDMENTS AND REQUIREMENTS NOT SHOWN
- 6. PERIMETER INSULATION SHOWN AS REQUIRED BY LOCAL CLIMATE ZONE. INSTALL PER TABLE N1102.1.2 OF THE 2018 NCRC

DRAWING DATE: 05/06/2024 SCALE: 22x34 1/4"=1'-0" 11x17 1/8"=1'-0" PROJECT #: A21117.00066.000 DRAWN BY: MGC CHECKED BY: GWS ORIGINAL INFORMATION PROJECT # DATE 1/31/2017 REFER TO COVER SHEET FOR A COMPLETE LIST OF REVISIONS D2c






ADE


<u>NOTES:</u>

- 1. REFER TO GENERAL NOTES & SPECIFICATIONS ON COVERSHEET FOR ADDITIONAL INFORMATION.
- PROVIDE 6 MIL VAPOR BARRIER UNDER ALL SLABS-ON-GRADE.
 SEE ARCH. DWGS. FOR ALL TOP OF THE SLAB ELEVATIONS,
- SLOPES AND DEPRESSIONS.
 4. REFER TO STRUCTURAL PLANS AND FRAMING DETAILS FOR BRACED WALL PANEL LAYOUT, DIMENSIONS, ATTACHMENT AND CONNECTIONS
- 5. REFER TO LOCAL AND STATEWIDE CODES FOR ADDITIONAL AMENDMENTS AND REQUIREMENTS NOT SHOWN
- 6. PERIMETER INSULATION SHOWN AS REQUIRED BY LOCAL CLIMATE ZONE. INSTALL PER TABLE N1102.1.2 OF THE 2018 NCRC




D4c 3/4" = 1'-0"


D4C/3/4" = 1'-0" -SIMILAR w/ BRICK AND STONE -BRICK TIES SPACED @ 16" O.C. HORIZ. & 24" O.C. VERT. -MIN. 3/16"¢ WEEP HOLES @ 33" O.C.





<u>NOTES:</u>


- 1. REFER TO GENERAL NOTES & SPECIFICATIONS ON COVERSHEET FOR ADDITIONAL INFORMATION.
- PROVIDE 6 MIL VAPOR BARRIER UNDER ALL SLABS-ON-GRADE.
 SEE ARCH. DWGS. FOR ALL TOP OF THE SLAB ELEVATIONS,
- SLOPES AND DEPRESSIONS.4. REFER TO STRUCTURAL PLANS AND FRAMING DETAILS FOR BRACED WALL PANEL LAYOUT, DIMENSIONS, ATTACHMENT AND CONNECTIONS
- 5. REFER TO LOCAL AND STATEWIDE CODES FOR ADDITIONAL AMENDMENTS AND REQUIREMENTS NOT SHOWN
- 6. PERIMETER INSULATION SHOWN AS REQUIRED BY LOCAL CLIMATE ZONE. INSTALL PER TABLE N1102.1.2 OF THE 2018 NCRC




















√	Δ		Δ	· . . Þ
	⊲ ⊿ 	2		 I:








General Notes:	** CUTTING OR DRILLING OF COMPONENTS SHOULD NOT BE DONE WITHOUT CONTACTING COMPONENT SUPPLIER
-----------------------	---

			Proc	lucts	
Net Qty	Plies			Product	Length
11	1			11 7/8" PJI-40	42' 0"
9	1			11 7/8" PJI-40	24' 0"
6	2			11 7/8" PJI-40	24' 0"
5	1			11 7/8" PJI-40	14' 0"
2	2			11 7/8" PJI-40	14' 0"
6	2			11 7/8" PJI-40	12' 0"
14	1	1 1/8" >	< 11 7/8"	APA Rim Board	12' 0"
8	1			11 7/8" PJI-40	2'0"
6	1			11 7/8" PJI-40	2' 0"
				Accessories	
			- •:		
	1	let Qty	Plies	Product	Length
		39	1	3/4" 4×8 OSB	

KEMPSVILLE BUILDING MATERIALS IS NOT RESPONSIBLE FOR THE DESIGN OR CALCULATION OF ANY AND ALL I-JOIST AND LVL/PSL BEAM MATERIAL. ALL ENGINEERING AND INFORMATION FOR THIS MATERIAL IS TO BE PROVIDED BY THE ENGINEER OF RECORD MARKED ON APPROVED SET OF PLANS. ALL BEAM PLACEMENTS ARE PER THE ENGINEERING RECEIVED. ALL CONNECTION DETAILS TO BE PROVIDED BY ENGINEER OF RECORD. REFER TO ENGINEER OR RECORD FOR ALL MULTI-PLY LVL/ I-JOIST CONNECTION PATTERNS. BUILDER TO VERIFY ALL MATERIAL LENGTHS, QUANTITIES, AND SIZES PRIOR TO ORDERING.



** PLUMBING DROPS NOTED ARE IN APPROXIMATE LOCATIONS PER PLAN. BUILDER MUST VERY LOCATIONS BEFORE SETTING JOISTS.

INTERIOR -SUPPORT

8d NAILS AT 6"c/c-TO TOP PLATE

PJI JOIST ATTACHMENT —/ PER 25 DETAIL

PJI I-JOIST BLOCKING REQUIRED BELOW ALL INTERIOR SUPPORTS

PJI BLOCKING PANEL PER 20 DETAIL

2g

TRANSFER LOAD FROM ABOVE TO BEARING BELOW INSTALL SQUASH BLOCKS PER 24 MATCH BEARING AREA OF BLOCKS IN RIM CAWITY TO POST ABOVE EXAMPLE 3-2x6 POST REQUIRES 3-2x6 SQUASH BLOCKS

20

ELOCKING PANELS ONLY REQUIRED FOR LATERAL STABILITY WHERE FLOOR JOISTS ARE NOT CONTINUC OVER SUPPORT. REFER TO DETAIL 2G.

PJI I-JOIST MAX VERTICAL LOAD TRANSFER 2000PLF

G. LUMBER SQUASH BLOCKS TO BE CUT X6" HIGHER THAN I-JOIST

 SQUASH BLOCK
 (D)

 1"x 3 1/2" APA RIM*
 1900

 1"x 5 1/2" APA RIM*
 3000

 1 x 5 1/2" APA RIM*
 2600

 1 1/8"x 5 1/2" APA RIM*
 2600

 1 -2x4
 4000

 1 -2x4
 1900


PROVIDE LATER BRACING AS PER DETAIL 29, 26 & 2c

2d

LUMBER SQUASH —/ BLOCKS TO BE CUT ¥6" HIGHER THAN I-JOIST

DOUBLE SQUASH BLOCK


MINIMUM 1-2x4 SQUASH BLOCK



38' 0"


** DAMAGED FLOOR JOISTS SHOULD NOT BE INSTA	DAMAGED FLOOR JOISTS SHOULD NOT BE INSTALLED UNLESS APPROVED BY COMPONENT PLANT.	** DIMENSIONS ARE READ AS: FOOT-INCH-SIXTEENTH.	** FRAMER MUST REFER TO PLANS WHILE SETTING COMPONENTS.	VENTS.
Date: Desig Projec	DR Horton		ement Plan Only . All designs of C Code Requirements along with es. This is NOT an engineered	00/00 00/00 00/00 00/00
1/4" = // 07/09 ner: DV t #: 250 Sheet Num	28 Mason Ridge Wilmington C		pracement plan. This pracement plan is created from plans provided by the customer using Manufactures guidelines. It is the responsibility of the EOR, or builder to review and approve all bearing conditions, connections, spans, loading, product usage, and quantities. Do not notch or drill holes in beams or)/00)/00)/00
9/25 V 070039	FLOOR JOIST LAYOUT		flanges on joists without prior approval from the manufacturing Representative unless following hole guidlines in the installation guide of product. Builder takes full responsibility for doing so and NO Back charge will be accepted.	ns Name Name Name Name

LABEL LEGEND




				Produ	cts		
N	let Qty	Plies			l	Product	Length
	11	1			14"	PJI-40	38' 0"
	10	1			14"	PJI-40	24' 0"
	7	1			14"	PJI-40	20' 0"
	10	1			14"	PJI-40	18' 0"
	2	1			14"	PJI-40	8' 0"
	1	1			14"	PJI-40	6' 0"
	5	1			14"	PJI-40	4' 0"
	2	2	2.1 RigidLa	m SP LV	'L 1-3/4	× 9-1/4	8' 0"
	2	2	2.1 RigidLa	m SP LV	'L 1-3/4	× 9-1/4	6' 0"
	2	2	2.1 RigidLarr	N SP LVL	_ 1-3/4 ×	: 11-7/8	20' 0"
	1	1	2.1 Rigio	dLam SF	2 LVL 1-3	/4 × 14	8' 0"
	1	1	2.1 Rigio	dLam SF	PLVL 1-3	/4 × 14	6' 0"
	2	2	2.1 Rigio	dLam SF	PLVL 1-3	/4 × 14	4' 0"
	17	1	1 1/3	8" x 14"	APA Rir	n Board	12' 0"
	11	1			14"	PJI-40	2' 0"
						sories	
			Net Qty	Plies		Product	Length
			50	1	3/4" 4>	k8 OSB	
			Сог	nnector	Summar	У	
	Web Sti	ff Bo	acker Blocks	F	roduct	Manut	f Qty
	1	10	No	IUS2	2.56/14	Simpsor	n 8
	1	10	No	IUS2	2.56/14	Simpsor	n 9
							JNDER /
							S FROM
				IY	PICAL	AIALL	LOCATI


KEMPSVILLE BUILDING MATERIALS IS NOT RESPONSIBLE FOR THE DESIGN OR CALCULATION OF ANY AND ALL LVL/PSL BEAM MATERIAL. ALL ENGINEERING AND INFORMATION FOR THIS MATERIAL IS TO BE PROVIDED BY THE ENGINEER OF RECORD MARKED ON APPROVED SET OF PLANS. ALL BEAM PLACEMENTS ARE PER THE ENGINEERING RECEIVED. ALL CONNECTION DETAILS TO BE PROVIDED BY ENGINEER OF RECORD. REFER TO ENGINEER OR RECORD FOR ALL MULTI-PLY LVL CONNECTION PATTERNS. BUILDER TO VERIFY ALL MATERIAL LENGTHS, QUANTITIES, AND SIZES PRIOR TO ORDERING.



** PLUMBING DROPS NOTED ARE IN APPROXIMATE LOCATIONS PER PLAN. BUILDER MUST VERY LOCATIONS BEFORE SETTING JOISTS.



38' 0"



8' 0"

	DAMAGED FLOOR JOISTS SHOULD NOT BE INSTALLED UNLESS APPROVED BY COMPONENT PLANT.	DIMENSIONS ARE READ AS: FOOT-INCH-SIXTEENTH.	FRAMER MUST REFER TO PLANS WHILE SETTING COMPUNENTS.	NENTS.
Date: Desig Projec	DR Horton			00/00 00/00 00/00 00/00
: 1/4" // 07/0	28 Mason Ridge			0/00 0/00 0/00
= 1'-0')9/25 W 507003		Lumber	usage, and quantities. Do not notch or drill noles in beams or flanges on joists without prior approval from the manufacturing Representative unless following hole guidlines in the installation guide of product. Builder takes full responsibility for doing so	ons Name Name Name Name
-			and NO Back charge will be accepted.	e e e



- **BBO** = Beam by Others **PBO** = Post by Others
- **GBO** = Girder by Others
- **J** = I-Joist
- FB = Flush Beam
- **DB** = Dropped Beam **RB** = Roof Beam
- **BP** = Blocking Panels
- SB = Squash Blocks
- HANGER MUST SUPPORT TOP FLANGE OF JOIST, FILLER BLOCK REQUIRED IF HANGER IS NOT FULL DEPTH OF JOST

** REFER TO INSTALLATION GUIDE FOR PLY TO PLY CONNECTIONS.

BEFORE INSTALLING A BACKER BLOCK TO A DOUBLE I-JOIST, DRIVE 3 ADDITIONAL 10d NAILS THROUGH WEBS AND FILLER BLOCK WHERE THE BACKER BLOCK WILL FIT CLINCH INSTALL BACKER TIGHT TO TOP FLANGE USE 12 10d NAILS, CLINCH WHEN POSSIBLE, MAX CAPACIY FOR HANGER FOR THIS DETAIL IS 1280 LBS

- DOUBLE PJI I-JOIST HEADER

FOR HANGER CAPACITY SEE HANGER MAUNFACTURES RECOMMENDATIONS VERIFY DOUBLE PJI I-JOIST CAPACITY TO SUPPORT CONCENTRATED LOADS

NOTE UNLESS HANGER SIDES LATERALLY SUPPORT THE TOP FLANGE, BEARING STIFFENERS SHALL BE USED

BACKER BLOCK REQUIRED (BOTH SIDES FOR FACE MOUNT HANGERS SEE HANGER MANUFATURED INSTALL DETAILS

2h

BACKER BLOCKS MUST BE LONG ENOUGH TO PERMIT REQUIRED NAILING WITHOUT SPLITTING

Series Thickness Min Depth

PJI80 & PJI90 1 ½" 7 ¼"

MIN GRADE BACKER BLOCK SHALL BE UTILITY GRADE SPF (SOUTH) OR BETTER FOR SOLD SAWN LUMBER AND SHALL BE RATED SHEATHING GRADE FOR WOOD STRUCTURAL PANELS **FOR FACE MOUNT HANGERS, USE NET JOIST DEPTH MINUS 1 1/4" FOR JOISTS WITH 1 1/2" THICK FLANGES