

Trenco
818 Soundside Rd
Edenton, NC 27932

Re: P-10651A-1
1215 Plan V4-Roof

The truss drawing(s) referenced below have been prepared by Truss Engineering Co. under my direct supervision based on the parameters provided by Peak Truss Builders, LLC.

Pages or sheets covered by this seal: I68139546 thru I68139552

My license renewal date for the state of North Carolina is December 31, 2024.

North Carolina COA: C-0844



September 11, 2024

Gilbert, Eric

IMPORTANT NOTE: The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to MiTek or TRENCO. Any project specific information included is for MiTek's or TRENCO's customers file reference purpose only, and was not taken into account in the preparation of these designs. MiTek or TRENCO has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.


Job	Truss	Truss Type	Qty	Ply	1215 Plan V4-Roof	I68139546
P-10651A-1	A01	Common Supported Gable	2	1	Job Reference (optional)	

Peak Truss Builders, LLC, New Hill, NC - 27562,

Run: 8.73 S Aug 15 2024 Print: 8.730 S Aug 15 2024 MiTek Industries, Inc. Wed Sep 11 08:28:20

Page: 1

ID:at7hzA4hhM?iFcs5wiAsYqz_4CO-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.11	Vert(LL)	n/a	-	n/a	999	MT20
TCDL	10.0	Lumber DOL	1.15	BC	0.10	Vert(CT)	n/a	-	n/a	999	244/190
BCLL	0.0*	Rep Stress Incr	YES	WB	0.18	Horz(CT)	0.00	20	n/a	n/a	
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MS							
Weight: 156 lb FT = 20%											

LUMBER
TOP CHORD 2x4 SP No.1
BOT CHORD 2x4 SP No.1
OTHERS 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 10-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS (size) 2=26-11-0, 18=26-11-0, 20=26-11-0, 21=26-11-0, 22=26-11-0, 23=26-11-0, 24=26-11-0, 25=26-11-0, 26=26-11-0, 28=26-11-0, 29=26-11-0, 30=26-11-0, 31=26-11-0, 32=26-11-0, 33=26-11-0, 34=26-11-0
Max Horiz 2=-107 (LC 9), 34=-107 (LC 9)
Max Uplift 2=-21 (LC 7), 20=-46 (LC 11), 21=-30 (LC 11), 22=-38 (LC 11), 23=-36 (LC 11), 24=-39 (LC 11), 25=-33 (LC 11), 28=-33 (LC 11), 29=-39 (LC 11), 30=-36 (LC 11), 31=-37 (LC 11), 32=-37 (LC 11), 33=-35 (LC 11), 34=-21 (LC 7)
Max Grav 2=104 (LC 20), 20=268 (LC 1), 21=97 (LC 17), 22=178 (LC 1), 23=156 (LC 21), 24=158 (LC 1), 25=172 (LC 21), 26=235 (LC 1), 28=171 (LC 1), 29=158 (LC 20), 30=161 (LC 1), 31=159 (LC 1), 32=166 (LC 20), 33=148 (LC 16), 34=104 (LC 20)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/27, 2-3=-131/159, 3-4=-95/157, 4-5=-54/151, 5-7=-29/147, 7-8=-19/141, 8-9=-31/175, 9-10=-46/212, 10-11=-46/202, 11-12=-31/141, 12-13=-16/130, 13-15=-2/130, 15-16=-20/133, 16-17=-55/119, 17-18=-113/138, 18-19=0/27
BOT CHORD 2-33=-92/147, 32-33=-92/147, 31-32=-92/147, 30-31=-92/147, 29-30=-92/147, 28-29=-92/147, 26-28=-92/147, 25-26=-92/147, 24-25=-92/147, 23-24=-92/147, 22-23=-92/147, 21-22=-92/147, 20-21=-92/147, 18-20=-92/147
WEBS 10-26=-195/0, 9-28=-131/116, 8-29=-118/74, 7-30=-121/66, 5-31=-119/67, 4-32=-124/70, 3-33=-105/86, 11-25=-133/113, 12-24=-117/75, 13-23=-119/66, 15-22=-127/70, 16-21=-90/73, 17-20=-162/114

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=120mph (3-second gust) Vasd=95mph; TCCL=6.0psf; BCDL=6.0psf; h=30ft; B=20ft; L=27ft; eave=2ft; Cat. II; Exp B; Enclosed; MWFRS (directional) and C-C Corner (3) -1-0-0 to 2-0-0, Exterior (2) 2-0-0 to 13-5-8, Corner (3) 13-5-8 to 16-5-8, Exterior (2) 16-5-8 to 27-11-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 2-0-0 oc.

- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
 - All bearings are assumed to be SPF No.2.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 21 lb uplift at joint 2, 33 lb uplift at joint 28, 39 lb uplift at joint 29, 36 lb uplift at joint 30, 37 lb uplift at joint 31, 37 lb uplift at joint 32, 35 lb uplift at joint 33, 33 lb uplift at joint 25, 39 lb uplift at joint 24, 36 lb uplift at joint 23, 38 lb uplift at joint 22, 30 lb uplift at joint 21, 46 lb uplift at joint 20 and 21 lb uplift at joint 2.
 - Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 18.
- LOAD CASE(S)** Standard



September 11, 2024

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1215 Plan V4-Roof	I68139547
P-10651A-1	A02	Attic	22	1	Job Reference (optional)	

Peak Truss Builders, LLC, New Hill, NC - 27562,

Run: 8.73 S Aug 15 2024 Print: 8.730 S Aug 15 2024 MiTek Industries, Inc. Wed Sep 11 08:28:21
ID:at7hzA4hhM?iFcs5wiAsYqz_4CO-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:64.9

Plate Offsets (X, Y): [2:0-2-0,Edge], [5:0-3-10,0-2-0], [6:0-3-0,Edge], [7:0-3-10,0-2-0], [10:0-2-0,Edge], [13:0-2-0,2-4-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.92	Vert(LL)	-0.32	12-20	>994	360	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.71	Vert(CT)	-0.50	12-20	>641	240		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.21	Horz(CT)	0.04	10	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MS		Wind(LL)	0.16	12-20	>999	240	Weight: 176 lb	FT = 20%

LUMBER

TOP CHORD 2x6 SP No.1 *Except* 1-3,9-11:2x6 SP No.2
BOT CHORD 2x6 SP No.2
WEBS 2x4 SP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(size) 2=0-3-8, 10=0-3-8
Max Horiz 2=-107 (LC 9)
Max Uplift 2=-168 (LC 11), 10=-168 (LC 11)
Max Grav 2=1164 (LC 17), 10=1164 (LC 18)

FORCES


(lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/27, 2-4=-1812/214, 4-5=-1443/271, 5-6=-218/1315, 6-7=-218/1315, 7-8=-1443/271, 8-10=-1812/214, 10-11=0/27
BOT CHORD 2-14=-61/1527, 12-14=-61/1527, 10-12=-61/1527
WEBS 8-12=0/442, 4-14=0/442, 5-7=-2980/547

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=120mph (3-second gust) Vasd=95mph; TCDL=6.0psf; BCDL=6.0psf; h=30ft; B=20ft; L=27ft; eave=4ft; Cat. II; Exp B; Enclosed; MWFRS (directional) and C-C Exterior (2) -1-0-0 to 2-0-0, Interior (1) 2-0-0 to 13-5-8, Exterior (2) 13-5-8 to 16-5-8, Interior (1) 16-5-8 to 27-11-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.

- Bottom chord live load (25.0 psf) and additional bottom chord dead load (0.0 psf) applied only to room. 12-14
- All bearings are assumed to be SPF No.2 .
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 168 lb uplift at joint 2 and 168 lb uplift at joint 10.
- Attic room checked for L/360 deflection.

LOAD CASE(S) Standard



September 11, 2024


WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932

Peak Truss Builders, LLC, New Hill, NC - 27562, Run: 8.73 S Aug 15 2024 Print: 8.730 S Aug 15 2024 MiTek Industries, Inc. Wed Sep 11 08:28:22 Page: 1
ID:at7hz44hhm?Fcs5wiAsYqz 4CO-RfC?PsB70Hq3NSqPanL8w3u1tXBGKWRCDoi7J4zJC?f

[illegible]

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-10; Vult=120mph (3-second gust)
Vasd=95mph; TCDFL=6.0psf; BCDL=6.0psf; h=30ft;
B=20ft; L=20ft; eave=4ft; Cat. II; Exp B; Enclosed;
MWFRS (directional) and C-C Exterior (2) zone;
cantilever left and right exposed ; end vertical left and
right exposed; C-C for members and forces & MWFRS
for reactions shown; Lumber DOL=1.60 plate grip
DOL=1.60
- 3) Truss designed for wind loads in the plane of the truss
only. For studs exposed to wind (normal to the face),
see Standard Industry Gable End Details as applicable,
or consult qualified building designer as per ANSI/TP1.
- 4) Gable requires continuous bottom chord bearing.
- 5) Gable studs spaced at 4-0-0 oc.
- 6) * This truss has been designed for a live load of 20.0psf
on the bottom chord in all areas where a rectangle
3-06-00 tall by 2-00-00 wide will fit between the bottom
chord and any other members.
- 7) All bearings are assumed to be SPF No.2.

LOAD CASE(S) Standard



 WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Components Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliat


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1215 Plan V4-Roof	I68139549
P-10651A-1	B02	Valley	1	1	Job Reference (optional)	

Peak Truss Builders, LLC, New Hill, NC - 27562,

Run: 8.73 S Aug 15 2024 Print: 8.730 S Aug 15 2024 MiTek Industries, Inc. Wed Sep 11 08:28:22
ID:at7hzA4hhM?iFcs5wiAsYqz_4CO-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:26.5

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.11	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.11	Vert(TL)	n/a	-	n/a	999		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.07	Horiz(TL)	0.00	3	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MP							Weight: 24 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.1
BOT CHORD 2x4 SP No.1
OTHERS 2x4 SP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 7-1-1 oc purlins.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS

(size) 1=7-1-1, 3=7-1-1, 4=7-1-1
Max Horiz 1=40 (LC 10)
Max Uplift 4=73 (LC 11)
Max Grav 1=72 (LC 20), 3=72 (LC 21), 4=470 (LC 1)

FORCES

(lb) - Maximum Compression/Maximum Tension


TOP CHORD 1-2=-65/191, 2-3=-65/191
BOT CHORD 1-4=-152/72, 3-4=-152/72
WEBS 2-4=-325/80

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=120mph (3-second gust)
Vasd=95mph; TCDL=6.0psf; BCDL=6.0psf; h=30ft; B=20ft; L=20ft; eave=4ft; Cat. II; Exp B; Enclosed; MWFRS (directional) and C-C Exterior (2) 0-0-6 to 3-0-6, Interior (1) 3-0-6 to 3-6-14, Exterior (2) 3-6-14 to 6-6-14, Interior (1) 6-6-14 to 7-1-7 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.

- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- All bearings are assumed to be SPF No.2 .
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 73 lb uplift at joint 4.

LOAD CASE(S) Standard



September 11, 2024

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1215 Plan V4-Roof	I68139550
P-10651A-1	B03	Valley	1	1	Job Reference (optional)	

Peak Truss Builders, LLC, New Hill, NC - 27562,

Run: 8.73 S Aug 15 2024 Print: 8.730 S Aug 15 2024 MiTek Industries, Inc. Wed Sep 11 08:28:22
ID:at7hzA4hhM?iFcs5wiAsYqz_4CO-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:31.9

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.21	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.20	Vert(TL)	n/a	-	n/a	999		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.14	Horiz(TL)	0.00	3	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MS							Weight: 36 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.1
BOT CHORD	2x4 SP No.1
OTHERS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 10-0-0 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS	(size)	1=10-1-1, 3=10-1-1, 4=10-1-1
	Max Horiz	1=-57 (LC 9)
	Max Uplift	1=-26 (LC 21), 3=-26 (LC 20), 4=-124 (LC 11)
	Max Grav	1=75 (LC 20), 3=75 (LC 21), 4=740 (LC 1)

FORCES


	(lb) - Maximum Compression/Maximum Tension
TOP CHORD	1-2=-65/340, 2-3=-65/340
BOT CHORD	1-4=-246/105, 3-4=-246/105
WEBS	2-4=-566/147

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=120mph (3-second gust) Vasd=95mph; TCDL=6.0psf; BCDL=6.0psf; h=30ft; B=20ft; L=20ft; eave=4ft; Cat. II; Exp B; Enclosed; MWFRS (directional) and C-C Exterior (2) 0-0-6 to 3-0-6, Interior (1) 3-0-6 to 5-0-14, Exterior (2) 5-0-14 to 8-0-14, Interior (1) 8-0-14 to 10-1-7 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.

- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- All bearings are assumed to be SPF No.2 .
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 26 lb uplift at joint 1, 26 lb uplift at joint 3 and 124 lb uplift at joint 4.

LOAD CASE(S) Standard



September 11, 2024

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1215 Plan V4-Roof	I68139551
P-10651A-1	B04	Valley	1	1	Job Reference (optional)	

Peak Truss Builders, LLC, New Hill, NC - 27562,

Run: 8.73 S Aug 15 2024 Print: 8.730 S Aug 15 2024 MiTek Industries, Inc. Wed Sep 11 08:28:22
ID:at7hzA4hhM?iFcs5wiAsYqz_4CO-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:36.3

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.39	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.32	Vert(TL)	n/a	-	n/a	999		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.30	Horiz(TL)	0.01	3	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MS							Weight: 47 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.1
BOT CHORD 2x4 SP No.1
OTHERS 2x4 SP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 10-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS (size) 1=13-1-1, 3=13-1-1, 4=13-1-1
Max Horiz 1=75 (LC 10)
Max Uplift 1=-79 (LC 21), 3=-79 (LC 20), 4=-202 (LC 11)
Max Grav 1=52 (LC 20), 3=52 (LC 21), 4=1082 (LC 1)


FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=-125/556, 2-3=-125/556
BOT CHORD 1-4=-407/169, 3-4=-407/169
WEBS 2-4=-865/238

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=120mph (3-second gust)
Vasd=95mph; TCDL=6.0psf; BCDL=6.0psf; h=30ft; B=20ft; L=20ft; eave=4ft; Cat. II; Exp B; Enclosed; MWFRS (directional) and C-C Exterior (2) 0-0-6 to 3-0-6, Interior (1) 3-0-6 to 6-6-14, Exterior (2) 6-6-14 to 9-6-14, Interior (1) 9-6-14 to 13-1-7 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.

- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
 - All bearings are assumed to be SPF No.2 .
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 79 lb uplift at joint 1, 79 lb uplift at joint 3 and 202 lb uplift at joint 4.
- LOAD CASE(S)** Standard



September 11, 2024

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompoments.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1215 Plan V4-Roof	I68139552
P-10651A-1	B05	Valley	1	1	Job Reference (optional)	

Peak Truss Builders, LLC, New Hill, NC - 27562,

Run: 8.73 S Aug 15 2024 Print: 8.730 S Aug 15 2024 MiTek Industries, Inc. Wed Sep 11 08:28:22
ID:at7hzA4hhM?iFcs5wiAsYqz_4CO-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCdoi7J4zJC?f

Page: 1



Scale = 1:40.7

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.04	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.03	Vert(TL)	n/a	-	n/a	999		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.05	Horiz(TL)	0.00	9	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MS							Weight: 78 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.1
BOT CHORD	2x4 SP No.1
OTHERS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(size)	1=16-1-1, 9=16-1-1, 10=16-1-1, 11=16-1-1, 12=16-1-1, 13=16-1-1, 14=16-1-1, 15=16-1-1, 17=16-1-1
Max Horiz	1=93 (LC 10)
Max Uplift	10=40 (LC 11), 11=53 (LC 11), 12=49 (LC 11), 14=49 (LC 11), 15=53 (LC 11), 17=40 (LC 11)
Max Grav	1=81 (LC 17), 9=68 (LC 1), 10=184 (LC 1), 11=155 (LC 17), 12=171 (LC 21), 13=140 (LC 1), 14=171 (LC 20), 15=154 (LC 16), 17=184 (LC 1)

FORCES

(lb) - Maximum Compression/Maximum Tension


TOP CHORD	1-2=-103/79, 2-3=-73/64, 3-4=-62/54, 4-5=-91/108, 5-6=-91/108, 6-7=-47/54, 7-8=-48/36, 8-9=-77/56
BOT CHORD	1-17=-53/83, 15-17=-53/70, 14-15=-53/70, 13-14=-53/70, 12-13=-53/70, 11-12=-53/70, 10-11=-53/70, 9-10=-53/70
WEBS	5-13=-101/1, 4-14=-129/73, 3-15=-118/78, 2-17=-122/61, 6-12=-129/73, 7-11=-119/78, 8-10=-122/61

NOTES

- Unbalanced roof live loads have been considered for this design.

- Wind: ASCE 7-10; Vult=120mph (3-second gust) Vasd=95mph; TCDL=6.0psf; BCDL=6.0psf; h=30ft; B=20ft; L=20ft; eave=2ft; Cat. II; Exp B; Enclosed; MWFRS (directional) and C-C Corner (3) 0-0-6 to 3-0-6, Exterior (2) 3-0-6 to 8-0-14, Corner (3) 8-0-14 to 11-0-14, Exterior (2) 11-0-14 to 16-1-7 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 2-0-0 oc.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- All bearings are assumed to be SPF No.2.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 49 lb uplift at joint 14, 53 lb uplift at joint 15, 40 lb uplift at joint 17, 49 lb uplift at joint 12, 53 lb uplift at joint 11 and 40 lb uplift at joint 10.

LOAD CASE(S) Standard



September 11, 2024

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.




Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MITEK Affiliate

818 Soundside Road
Edenton, NC 27932

Symbols

PLATE LOCATION AND ORIENTATION



* Plate location details available in MITek software or upon request.

PLATE SIZE

4 X 4


The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T or I bracing if indicated.

BEARING



Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number/letter where bearings occur. Min size shown is for crushing only.

Industry Standards:

ANSI/TP1: National Design Specification for Metal Plate Connected Wood Truss Construction.
DSB-22: Building Component Safety Information, Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses.

Numbering System

