


|          |       |            |     |     |                                 |
|----------|-------|------------|-----|-----|---------------------------------|
| Job      | Truss | Truss Type | Qty | Ply | MUNGO HOMES - TELFAIR 2ND FLR   |
| 72512298 | F200  | Truss      | 5   | 1   | Job Reference (optional) 67 LLP |

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Joy Perry

Run: 8.83 S Apr 11 2025 Print: 8.830 S Apr 11 2025 MiTek Industries, Inc. Wed Apr 30 20:47:4t

Page: 1

ID:a?q6?771yTv6SHVH?OLZqv2z8gqv-FSghmO0nQmjvy548Evsz1g6jGQfCmqAcf4u8ujzL5fl



Scale = 1:43.7

Plate Offsets (X, Y): [10:0-1-8,Edge]

| Loading | (psf) | Spacing         | 2-0-0           | CSI       |      | DEFL     | in    | (loc) | l/defl | L/d | PLATES        | GRIP            |
|---------|-------|-----------------|-----------------|-----------|------|----------|-------|-------|--------|-----|---------------|-----------------|
| TCLL    | 40.0  | Plate Grip DOL  | 1.00            | TC        | 0.71 | Vert(LL) | -0.32 | 11-12 | >595   | 480 | MT20          | 244/190         |
| TCDL    | 10.0  | Lumber DOL      | 1.00            | BC        | 0.75 | Vert(CT) | -0.43 | 11-12 | >439   | 360 |               |                 |
| BCLL    | 0.0   | Rep Stress Incr | YES             | WB        | 0.61 | Horz(CT) | 0.05  | 9     | n/a    | n/a |               |                 |
| BCDL    | 5.0   | Code            | IRC2015/TPI2014 | Matrix-SH |      |          |       |       |        |     | Weight: 77 lb | FT = 20%F, 12%E |

| LUMBER    |                   | BRACING   |                                                                                       |
|-----------|-------------------|-----------|---------------------------------------------------------------------------------------|
| TOP CHORD | 2x4 SP SS(flat)   | TOP CHORD | Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals. |
| BOT CHORD | 2x4 SP SS(flat)   | BOT CHORD | Rigid ceiling directly applied or 10-0-0 oc bracing.                                  |
| WEBS      | 2x4 SP No.3(flat) |           |                                                                                       |
| OTHERS    | 2x4 SP No.3(flat) |           |                                                                                       |

| REACTIONS | (lb/size)                                                                                               | 9=858/0-3-8, (min. 0-1-8), 14=858/0-3-8, (min. 0-1-8) |
|-----------|---------------------------------------------------------------------------------------------------------|-------------------------------------------------------|
| FORCES    | (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.                            |                                                       |
| TOP CHORD | 2-3=-2391/0, 3-4=-3135/0, 4-5=-2950/0, 5-6=-2950/0, 6-7=-2950/0                                         |                                                       |
| BOT CHORD | 13-14=0/1852, 12-13=0/2903, 11-12=0/3260, 10-11=0/2950, 9-10=0/1854                                     |                                                       |
| WEBS      | 6-10=-421/0, 2-14=-1986/0, 2-13=0/700, 3-13=-667/0, 3-12=0/302, 4-11=-561/170, 7-9=-1987/0, 7-10=0/1281 |                                                       |

- NOTES**
- Unbalanced floor live loads have been considered for this design.
  - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.



|                 |               |                     |          |          |                                                           |
|-----------------|---------------|---------------------|----------|----------|-----------------------------------------------------------|
| Job<br>72512298 | Truss<br>F201 | Truss Type<br>Truss | Qty<br>1 | Ply<br>1 | MUNGO HOMES - TELFAIR 2ND FLR<br>Job Reference (optional) |
|-----------------|---------------|---------------------|----------|----------|-----------------------------------------------------------|

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Joy Perry

Run: 8.83 S Apr 11 2025 Print: 8.830 S Apr 11 2025 MiTek Industries, Inc. Wed Apr 30 20:47:4; ID:a?q6?71yTv6SHVH?OlZqv2z8gqv-f1MqOP2gjh5UpZpv2PgflkF1eg?zBu2M26oV2zL5fF

Page: 1




Plate Offsets (X, Y): [9:0-1-8,Edge], [12:0-1-8,Edge]

| Loading | (psf) | Spacing         | 2-0-0           | CSI       |      | DEFL     | in    | (loc) | l/defl | L/d | PLATES        | GRIP            |
|---------|-------|-----------------|-----------------|-----------|------|----------|-------|-------|--------|-----|---------------|-----------------|
| TCLL    | 40.0  | Plate Grip DOL  | 1.00            | TC        | 0.67 | Vert(LL) | -0.30 | 13-14 | >627   | 480 | MT20          | 244/190         |
| TCDL    | 10.0  | Lumber DOL      | 1.00            | BC        | 0.74 | Vert(CT) | -0.41 | 13-14 | >458   | 360 |               |                 |
| BCLL    | 0.0   | Rep Stress Incr | YES             | WB        | 0.61 | Horz(CT) | 0.03  | 9     | n/a    | n/a |               |                 |
| BCDL    | 5.0   | Code            | IRC2015/TPI2014 | Matrix-SH |      |          |       |       |        |     | Weight: 78 lb | FT = 20%F, 12%E |

| LUMBER                    | BRACING                                                                                         |
|---------------------------|-------------------------------------------------------------------------------------------------|
| TOP CHORD 2x4 SP SS(flat) | TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals. |
| BOT CHORD 2x4 SP SS(flat) | BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.                                  |
| WEBS 2x4 SP No.3(flat)    |                                                                                                 |
| OTHERS 2x4 SP No.3(flat)  |                                                                                                 |

REACTIONS (lb/size) 9=851/0-2-15, (min. 0-1-8), 16=845/0-3-8, (min. 0-1-8)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-2344/0, 3-4=-3059/0, 4-5=-2840/0, 5-6=-2840/0, 6-7=-2840/0, 7-8=-903/0, 8-9=-908/0

BOT CHORD 15-16=0/1821, 14-15=0/2842, 13-14=0/3166, 12-13=0/2840, 11-12=0/1765

WEBS 6-12=-432/0, 2-16=-1952/0, 2-15=0/681, 3-15=-648/0, 3-14=0/283, 4-13=-564/137, 9-11=0/1127, 7-11=-1122/0, 7-12=0/1286

- NOTES
- Unbalanced floor live loads have been considered for this design.
  - Provide mechanical connection (by others) of truss to bearing plate at joint(s) 9.
  - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
  - Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.
  - CAUTION, Do not erect truss backwards.






|                 |               |                     |           |          |                                                           |
|-----------------|---------------|---------------------|-----------|----------|-----------------------------------------------------------|
| Job<br>72512298 | Truss<br>F203 | Truss Type<br>Truss | Qty<br>10 | Ply<br>1 | MUNGO HOMES - TELFAIR 2ND FLR<br>Job Reference (optional) |
|-----------------|---------------|---------------------|-----------|----------|-----------------------------------------------------------|

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Joy Perry

Run: 8.83 S Apr 11 2025 Print: 8.830 S Apr 11 2025 MiTek Industries, Inc. Wed Apr 30 20:47:4 ID:gybFDKc1Jhrnb30WAXcCoLz1jXX-7DvCc3IU\_DLRIoVtIwvBWGO21jiaCaisL1UzL5fE

Page: 1



Scale = 1:55

Plate Offsets (X, Y): [5:0-3-0,Edge], [8:0-3-0,Edge], [9:0-2-4,Edge], [15:0-2-0,Edge], [17:0-3-0,Edge], [18:0-3-0,Edge], [19:0-3-0,Edge]

| Loading | (psf) | Spacing         | 2-0-0           | CSI       | DEFL | in       | (loc) | l/defl | L/d  | PLATES | GRIP                           |
|---------|-------|-----------------|-----------------|-----------|------|----------|-------|--------|------|--------|--------------------------------|
| TCLL    | 40.0  | Plate Grip DOL  | 1.00            | TC        | 0.81 | Vert(LL) | -0.30 | 18-19  | >760 | 480    | MT18HS 244/190                 |
| TCDL    | 10.0  | Lumber DOL      | 1.00            | BC        | 0.64 | Vert(CT) | -0.49 | 18-19  | >456 | 360    | MT20 244/190                   |
| BCLL    | 0.0   | Rep Stress Incr | NO              | WB        | 0.89 | Horz(CT) | 0.08  | 13     | n/a  | n/a    |                                |
| BCDL    | 5.0   | Code            | IRC2015/TPI2014 | Matrix-SH |      |          |       |        |      |        | Weight: 115 lb FT = 20%F, 12%E |

| LUMBER    |                   |  | BRACING   |                                                                                        |  |
|-----------|-------------------|--|-----------|----------------------------------------------------------------------------------------|--|
| TOP CHORD | 2x4 SP No.1(flat) |  | TOP CHORD | Structural wood sheathing directly applied or 4-9-13 oc purlins, except end verticals. |  |
| BOT CHORD | 2x4 SP SS(flat)   |  | BOT CHORD | Rigid ceiling directly applied or 10-0-0 oc bracing.                                   |  |
| WEBS      | 2x4 SP No.3(flat) |  |           |                                                                                        |  |
| OTHERS    | 2x4 SP No.3(flat) |  |           |                                                                                        |  |

|           |                                                                              |                                                                                                                                                                 |
|-----------|------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------|
| REACTIONS | (lb/size)                                                                    | 13=1397/0-3-8, (min. 0-1-8), 22=1160/0-3-8, (min. 0-1-8)                                                                                                        |
| FORCES    | (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown. |                                                                                                                                                                 |
| TOP CHORD |                                                                              | 2-3=-3494/0, 3-4=-5117/0, 4-5=-5099/0, 5-6=-6511/0, 6-7=-6511/0, 7-8=-6511/0, 8-9=-6511/0, 9-10=-4074/0, 10-11=-4079/0                                          |
| BOT CHORD |                                                                              | 21-22=0/2608, 20-21=0/4397, 19-20=0/4386, 18-19=0/5883, 17-18=0/6511, 16-17=0/5184, 15-16=0/5184, 14-15=0/3016, 13-14=0/3024                                    |
| WEBS      |                                                                              | 7-18=-468/0, 8-17=-407/0, 2-22=-2799/0, 2-21=0/1154, 3-21=-1175/0, 3-19=0/916, 5-19=-949/0, 5-18=0/1118, 9-17=0/1553, 9-15=-1370/0, 11-15=0/1341, 11-13=-3240/0 |

- NOTES
- Unbalanced floor live loads have been considered for this design.
  - All plates are MT20 plates unless otherwise indicated.
  - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Load case(s) 1 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.
  - Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

|              |                                                                         |
|--------------|-------------------------------------------------------------------------|
| LOAD CASE(S) | Standard                                                                |
| 1)           | Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00 |
|              | Uniform Loads (lb/ft)                                                   |
|              | Vert: 13-22=-10, 1-5=-100, 5-25=-140, 12-25=-176                        |



This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.




|                 |               |                     |          |          |                                                           |
|-----------------|---------------|---------------------|----------|----------|-----------------------------------------------------------|
| Job<br>72512298 | Truss<br>F204 | Truss Type<br>Truss | Qty<br>2 | Ply<br>1 | MUNGO HOMES - TELFAIR 2ND FLR<br>Job Reference (optional) |
|-----------------|---------------|---------------------|----------|----------|-----------------------------------------------------------|

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Joy Perry

Run: 8.83 S Apr 11 2025 Print: 8.830 S Apr 11 2025 MiTek Industries, Inc. Wed Apr 30 20:47:4 ID:a?q6?71yTv6SHVH?OIzqv2z8gqv-cPTap53wFILC3sz60TR8kjpYaRKfR7QLpMbvZxzL5fD

Page: 1



|                       |       |                                |                 |            |      |             |       |       |        |     |               |                 |
|-----------------------|-------|--------------------------------|-----------------|------------|------|-------------|-------|-------|--------|-----|---------------|-----------------|
| Plate Offsets (X, Y): |       | [8:0-1-8,Edge], [9:0-1-8,Edge] |                 |            |      |             |       |       |        |     |               |                 |
| <b>Loading</b>        | (psf) | <b>Spacing</b>                 | 2-0-0           | <b>CSI</b> |      | <b>DEFL</b> | in    | (loc) | l/defl | L/d | <b>PLATES</b> | <b>GRIP</b>     |
| TCLL                  | 40.0  | Plate Grip DOL                 | 1.00            | TC         | 0.86 | Vert(LL)    | -0.15 | 7-8   | >859   | 480 | MT20          | 244/190         |
| TCDL                  | 30.0  | Lumber DOL                     | 1.00            | BC         | 0.86 | Vert(CT)    | -0.29 | 7-8   | >454   | 360 |               |                 |
| BCLL                  | 0.0   | Rep Stress Incr                | YES             | WB         | 0.48 | Horz(CT)    | 0.03  | 7     | n/a    | n/a |               |                 |
| BCDL                  | 5.0   | Code                           | IRC2015/TPI2014 | Matrix-SH  |      |             |       |       |        |     | Weight: 55 lb | FT = 20%F, 12%E |

**LUMBER**  
TOP CHORD 2x4 SP No.2(flat)  
BOT CHORD 2x4 SP No.2(flat)  
WEBS 2x4 SP No.3(flat)  
OTHERS 2x4 SP No.3(flat)

**BRACING**  
TOP CHORD Structural wood sheathing directly applied or 5-6-0 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS** (lb/size) 7=816/0-3-8, (min. 0-1-8), 10=816/0-3-8, (min. 0-1-8)

**FORCES** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-2128/0, 3-4=-2128/0, 4-5=-2128/0  
BOT CHORD 9-10=0/1647, 8-9=0/2128, 7-8=0/1639  
WEBS 3-9=-377/0, 2-10=-1762/0, 2-9=0/751, 5-7=-1754/0, 5-8=0/668

**NOTES**  
1) Unbalanced floor live loads have been considered for this design.  
2) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.  
3) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.



|          |       |            |     |     |                               |
|----------|-------|------------|-----|-----|-------------------------------|
| Job      | Truss | Truss Type | Qty | Ply | MUNGO HOMES - TELFAIR 2ND FLR |
| 72512298 | F205  | Truss      | 3   | 1   | Job Reference (optional)      |

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Joy Perry

Run: 8.83 S Apr 11 2025 Print: 8.830 S Apr 11 2025 MiTek Industries, Inc. Wed Apr 30 20:47:4

Page: 1

ID:a?q6?71yTv6SHVH?OlZqv2z8gqv-cPTap53wFILC3sz60TR8kjbXROnR9nLpMbvZxzL5fD




Plate Offsets (X, Y): [7:0-2-0,Edge], [10:0-2-0,Edge]

| Loading | (psf) | Spacing         | 2-0-0           | CSI       |      | DEFL     | in    | (loc) | l/defl | L/d | PLATES        | GRIP            |
|---------|-------|-----------------|-----------------|-----------|------|----------|-------|-------|--------|-----|---------------|-----------------|
| TCLL    | 40.0  | Plate Grip DOL  | 1.00            | TC        | 0.65 | Vert(LL) | -0.12 | 7-8   | >999   | 480 | MT20          | 244/190         |
| TCDL    | 10.0  | Lumber DOL      | 1.00            | BC        | 0.59 | Vert(CT) | -0.19 | 7-8   | >647   | 360 |               |                 |
| BCLL    | 0.0   | Rep Stress Incr | YES             | WB        | 0.33 | Horz(CT) | 0.02  | 7     | n/a    | n/a |               |                 |
| BCDL    | 5.0   | Code            | IRC2015/TPI2014 | Matrix-SH |      |          |       |       |        |     | Weight: 52 lb | FT = 20%F, 12%E |

| LUMBER    |                   |  | BRACING   |                                                                                       |
|-----------|-------------------|--|-----------|---------------------------------------------------------------------------------------|
| TOP CHORD | 2x4 SP No.2(flat) |  | TOP CHORD | Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals. |
| BOT CHORD | 2x4 SP No.2(flat) |  | BOT CHORD | Rigid ceiling directly applied or 10-0-0 oc bracing.                                  |
| WEBS      | 2x4 SP No.3(flat) |  |           |                                                                                       |
| OTHERS    | 2x4 SP No.3(flat) |  |           |                                                                                       |

**REACTIONS** (lb/size) 7=567/ Mechanical, 10=567/ Mechanical


**FORCES** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-1396/0, 3-4=-1396/0, 4-5=-1396/0

BOT CHORD 9-10=0/1129, 8-9=0/1396, 7-8=0/1112

WEBS 3-9=-308/0, 2-10=-1207/0, 2-9=0/534, 5-7=-1190/0, 5-8=0/458

- NOTES**
- Unbalanced floor live loads have been considered for this design.
  - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.



|          |       |            |     |     |                               |
|----------|-------|------------|-----|-----|-------------------------------|
| Job      | Truss | Truss Type | Qty | Ply | MUNGO HOMES - TELFAIR 2ND FLR |
| 72512298 | F206  | Truss      | 1   | 1   | Job Reference (optional)      |

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Joy Perry

Run: 8.83 S Apr 11 2025 Print: 8.830 S Apr 11 2025 MiTek Industries, Inc. Wed Apr 30 20:47:4

Page: 1

ID:a?q6771yTv6SHVH?OlZqv2z8gqv-cPTap53wFILC3sz60TR8kjbpcRKKR3zLpMbvZxzL5fD




Plate Offsets (X, Y): [2:0-3-0,Edge], [3:0-3-0,Edge], [4:0-3-0,Edge]

| Loading | (psf) | Spacing         | 2-0-0           | CSI       |      | DEFL     | in    | (loc) | l/defl | L/d | PLATES        | GRIP            |
|---------|-------|-----------------|-----------------|-----------|------|----------|-------|-------|--------|-----|---------------|-----------------|
| TCLL    | 40.0  | Plate Grip DOL  | 1.00            | TC        | 0.67 | Vert(LL) | -0.09 | 5-6   | >865   | 480 | MT20          | 244/190         |
| TCDL    | 10.0  | Lumber DOL      | 1.00            | BC        | 0.85 | Vert(CT) | -0.12 | 5-6   | >623   | 360 |               |                 |
| BCLL    | 0.0   | Rep Stress Incr | YES             | WB        | 0.77 | Horz(CT) | 0.02  | 5     | n/a    | n/a |               |                 |
| BCDL    | 5.0   | Code            | IRC2015/TPI2014 | Matrix-SH |      |          |       |       |        |     | Weight: 44 lb | FT = 20%F, 12%E |

| LUMBER    |                   | BRACING   |                                                                                       |
|-----------|-------------------|-----------|---------------------------------------------------------------------------------------|
| TOP CHORD | 2x4 SP No.2(flat) | TOP CHORD | Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals. |
| BOT CHORD | 2x4 SP No.1(flat) | BOT CHORD | Rigid ceiling directly applied or 10-0-0 oc bracing.                                  |
| WEBS      | 2x4 SP No.3(flat) |           |                                                                                       |
| OTHERS    | 2x4 SP No.3(flat) |           |                                                                                       |

| REACTIONS | (lb/size)                                                                    | 5=1247/ Mechanical, 8=1002/0-3-8, (min. 0-1-8) |
|-----------|------------------------------------------------------------------------------|------------------------------------------------|
| FORCES    | (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown. |                                                |
| TOP CHORD | 5-10=-254/0, 4-10=-253/0, 2-3=-2660/0                                        |                                                |
| BOT CHORD | 7-8=0/2660, 6-7=0/2660, 5-6=0/2660                                           |                                                |
| WEBS      | 2-8=-2829/0, 3-5=-2815/0                                                     |                                                |


- NOTES**
- Unbalanced floor live loads have been considered for this design.
  - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Load case(s) 8, 10 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.
  - Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

- LOAD CASE(S)** Standard
- Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00  
Uniform Loads (lb/ft)  
Vert: 5-8=-10, 1-4=-100  
Concentrated Loads (lb)  
Vert: 3=-1560
  - 1st chase Dead + Floor Live (unbalanced): Lumber Increase=1.00, Plate Increase=1.00  
Uniform Loads (lb/ft)  
Vert: 5-8=-10, 1-3=-100, 3-4=-20  
Concentrated Loads (lb)  
Vert: 3=-425
  - 3rd chase Dead: Lumber Increase=1.00, Plate Increase=1.00  
Uniform Loads (lb/ft)  
Vert: 5-8=-10, 1-3=-100, 3-4=-20  
Concentrated Loads (lb)  
Vert: 3=-425





UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Joy Perry Run: 8.83 S Apr 11 2025 Print: 8.830 S Apr 11 2025 MiTek Industries, Inc. Wed Apr 30 20:47:41 Page: 1  
ID:a?g6?71vTv6SHVH?OIzQvz28ggv-4c1z1R4Y0cT3g0XIaAzNGxMIFrjeAZUU20LS5nzL5fC



|                  |                                                                                                                                                                                                            |                                                                                     |                                                                                       |
|------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------|
| <b>LUMBER</b>    |                                                                                                                                                                                                            | <b>BRACING</b>                                                                      |                                                                                       |
| TOP CHORD        | 2x4 SP SS(flat)                                                                                                                                                                                            | TOP CHORD                                                                           | Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals. |
| BOT CHORD        | 2x4 SP SS(flat)                                                                                                                                                                                            | BOT CHORD                                                                           | Rigid ceiling directly applied or 10-0-0 oc bracing, Except:                          |
| WEBS             | 2x4 SP No.3(flat)                                                                                                                                                                                          |                                                                                     | 6-0-0 oc bracing: 19-21,18-19.                                                        |
| OTHERS           | 2x4 SP No.3(flat)                                                                                                                                                                                          |                                                                                     |                                                                                       |
| <b>REACTIONS</b> | (lb/size)                                                                                                                                                                                                  | 15=733/0-3-8, (min. 0-1-8), 21=1896/0-3-0, (min. 0-1-8), 24=719/0-3-8, (min. 0-1-8) |                                                                                       |
|                  | Max Grav                                                                                                                                                                                                   | 15=760 (LC 14), 21=1896 (LC 1), 24=765 (LC 8)                                       |                                                                                       |
| <b>FORCES</b>    | (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.                                                                                                                               |                                                                                     |                                                                                       |
| TOP CHORD        | 2-3=-1790/0, 3-28=-1790/0, 4-28=-1790/0, 4-5=-1790/0, 5-6=0/1362, 6-7=0/1362, 7-8=0/1352, 8-9=-888/270, 9-10=-2383/0, 10-11=-2383/0, 11-12=-2383/0, 12-13=-2072/0                                          |                                                                                     |                                                                                       |
| BOT CHORD        | 23-24=0/1551, 22-23=0/1790, 21-22=0/979, 20-21=-518/178, 19-20=-518/178, 18-19=9/1640, 17-18=0/2383, 16-17=0/2434, 15-16=0/1619                                                                            |                                                                                     |                                                                                       |
| WEBS             | 4-22=-382/0, 10-18=-440/0, 7-21=-291/0, 2-24=-1644/0, 2-23=0/318, 5-21=-2040/0, 5-22=0/1064, 8-21=-1349/0, 8-19=0/964, 9-19=-1047/0, 9-18=0/1097, 13-15=-1735/0, 13-16=0/590, 12-16=-471/0, 12-17=-337/179 |                                                                                     |                                                                                       |

- NOTES**
- 1) Unbalanced floor live loads have been considered for this design.
  - 2) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 3) Load case(s) 1 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.
  - 4) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
  - 5) CAUTION. Do not erect truss backwards.

1) Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00  
Uniform Loads (lb/ft)  
Vert: 15-24=-10, 1-27=-140, 27-28=-176, 7-28=-140, 7-14=-100



This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCE and Truss Plate Institute.



|          |       |            |     |     |                               |
|----------|-------|------------|-----|-----|-------------------------------|
| Job      | Truss | Truss Type | Qty | Ply | MUNGO HOMES - TELFAIR 2ND FLR |
| 72512298 | F209  | Truss      | 5   | 1   | Job Reference (optional)      |

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Joy Perry

Run: 8.83 S Apr 11 2025 Print: 8.830 S Apr 11 2025 MiTek Industries, Inc. Wed Apr 30 20:47:4t

Page: 1

ID:a?q6?71yTv6SHVH?OIzqv2z8gqv-YobLEn5BnbvwlA6U8tUcp8usMF3EvxxeGg40epzL5fB




Plate Offsets (X, Y): [3:0-4-0,Edge], [5:0-3-0,Edge], [6:0-1-12,Edge], [12:0-1-8,Edge], [13:0-1-8,Edge]

| Loading | (psf) | Spacing         | 2-0-0           | CSI       | DEFL | in       | (loc) | l/defl | L/d  | PLATES        | GRIP            |
|---------|-------|-----------------|-----------------|-----------|------|----------|-------|--------|------|---------------|-----------------|
| TCLL    | 40.0  | Plate Grip DOL  | 1.00            | TC        | 0.97 | Vert(LL) | -0.19 | 11-12  | >925 | 480           | 244/190         |
| TCDL    | 30.0  | Lumber DOL      | 1.00            | BC        | 0.66 | Vert(CT) | -0.38 | 11-12  | >464 | 360           |                 |
| BCLL    | 0.0   | Rep Stress Incr | NO              | WB        | 0.86 | Horz(CT) | 0.06  | 10     | n/a  | n/a           |                 |
| BCDL    | 5.0   | Code            | IRC2015/TPI2014 | Matrix-SH |      |          |       |        |      |               |                 |
|         |       |                 |                 |           |      |          |       |        |      | Weight: 84 lb | FT = 20%F, 12%E |

| LUMBER    |                   |  | BRACING   |                                                                                                                                               |  |
|-----------|-------------------|--|-----------|-----------------------------------------------------------------------------------------------------------------------------------------------|--|
| TOP CHORD | 2x4 SP No.2(flat) |  | TOP CHORD | Structural wood sheathing directly applied or 4-1-9 oc purlins, except end verticals.<br>Rigid ceiling directly applied or 10-0-0 oc bracing. |  |
| BOT CHORD | 2x4 SP SS(flat)   |  | BOT CHORD |                                                                                                                                               |  |
| WEBS      | 2x4 SP No.3(flat) |  |           |                                                                                                                                               |  |
| OTHERS    | 2x4 SP No.3(flat) |  |           |                                                                                                                                               |  |

REACTIONS (lb/size) 10=1135/0-3-8, (min. 0-1-8), 14=1144/ Mechanical

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 3-4=-4248/0, 4-17=-4248/0, 5-17=-4248/0, 5-18=-4248/0, 6-18=-4248/0, 6-7=-3187/0, 7-8=-3188/0

BOT CHORD 13-14=0/2649, 12-13=0/4248, 11-12=0/3909, 10-11=0/2439

WEBS 4-13=-584/0, 3-14=-2818/0, 3-13=0/1816, 8-10=-2614/0, 8-11=0/975, 6-11=-917/0, 6-12=0/710

- NOTES
- Unbalanced floor live loads have been considered for this design.
  - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Load case(s) 1 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.
  - Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard


1) Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00

Uniform Loads (lb/ft)

Vert: 10-14=-10, 1-17=-140, 17-18=-176, 9-18=-140



UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Joy Perry Run: 8.83 S Apr 11 2025 Print: 8.830 S Apr 11 2025 MiTek Industries, Inc. Wed Apr 30 20:47:46 ID:a?g6?71yTv6SHVH?OIzqv2z8gqv-YobLEn5BnvwIa6U8tUcp8uvZF?av?aeGg40epzL5fB



|                  |                                                                                                                                                                                           |                                                         |                |                                                                                       |  |
|------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------|----------------|---------------------------------------------------------------------------------------|--|
| <b>LUMBER</b>    |                                                                                                                                                                                           |                                                         | <b>BRACING</b> |                                                                                       |  |
| TOP CHORD        | 2x4 SP No.2(flat)                                                                                                                                                                         |                                                         | TOP CHORD      | Structural wood sheathing directly applied or 2-2-0 oc purlins, except end verticals. |  |
| BOT CHORD        | 2x4 SP No.1(flat)                                                                                                                                                                         |                                                         | BOT CHORD      | Rigid ceiling directly applied or 2-2-0 oc bracing.                                   |  |
| WEBS             | 2x4 SP No.3(flat)                                                                                                                                                                         |                                                         |                |                                                                                       |  |
| OTHERS           | 2x4 SP No.3(flat)                                                                                                                                                                         |                                                         |                |                                                                                       |  |
| <b>REACTIONS</b> | (lb/size)                                                                                                                                                                                 | 13=949/0-3-8, (min. 0-1-8), 20=1405/0-3-8, (min. 0-1-8) |                |                                                                                       |  |
|                  | Max Grav                                                                                                                                                                                  | 13=975 (LC 4), 20=1405 (LC 1)                           |                |                                                                                       |  |
| <b>FORCES</b>    | (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.                                                                                                              |                                                         |                |                                                                                       |  |
| TOP CHORD        | 2-3=0/612, 3-4=0/611, 4-5=-1942/0, 5-6=-3330/0, 6-7=-4164/0, 7-8=-4164/0, 8-9=-4164/0, 9-10=-4164/0, 10-11=-2838/0                                                                        |                                                         |                |                                                                                       |  |
| BOT CHORD        | 20-21=-298/0, 19-20=-239/1071, 18-19=0/2794, 17-18=0/3825, 16-17=0/3825, 15-16=0/4164, 14-15=0/3474, 13-14=0/2152                                                                         |                                                         |                |                                                                                       |  |
| WEBS             | 7-16=-278/0, 8-15=-256/0, 2-21=0/320, 2-20=-514/0, 4-20=-1585/0, 4-19=0/1175, 5-19=-1146/0, 5-18=0/732, 6-18=-692/0, 6-16=-50/851, 11-13=-2309/0, 11-14=0/893, 10-14=-828/0, 10-15=0/1001 |                                                         |                |                                                                                       |  |

- 



UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Joy Perry Run: 8.83 S Apr 11 2025 Print: 8.830 S Apr 11 2025 MiTek Industries, Inc. Wed Apr 30 20:47:46 ID:a?g6?71yTv6SHVH?OIzQv2z8gqv-YobLEn5BnvwIA6U8tUcp8uuBF\_qv?TeGg40epzL5fE



| <b>Loading</b> | (psf) | <b>Spacing</b>  | 2-0-0           | <b>CSI</b> |      | <b>DEFL</b> | in    | (loc) | l/defl | L/d | <b>PLATES</b> | <b>GRIP</b>     |
|----------------|-------|-----------------|-----------------|------------|------|-------------|-------|-------|--------|-----|---------------|-----------------|
| TCLL           | 40.0  | Plate Grip DOL  | 1.00            | TC         | 0.85 | Vert(LL)    | -0.35 | 13-14 | >619   | 480 | MT18HS        | 244/190         |
| TCDL           | 10.0  | Lumber DOL      | 1.00            | BC         | 1.00 | Vert(CT)    | -0.48 | 14    | >450   | 360 | MT20          | 244/190         |
| BCLL           | 0.0   | Rep Stress Incr | YES             | WB         | 0.64 | Horz(CT)    | 0.08  | 11    | n/a    | n/a |               |                 |
| BCDL           | 5.0   | Code            | IRC2015/TP12014 | Matrix-SH  |      |             |       |       |        |     | Weight: 89 lb | FT = 20%F, 12%E |

|           |                                                                              |                                                                                                                                                 |
|-----------|------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------|
| REACTIONS | (lb/size)                                                                    | 11=986/0-3-8, (min. 0-1-8), 18=986/0-3-8, (min. 0-1-8)                                                                                          |
| FORCES    | (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown. |                                                                                                                                                 |
| TOP CHORD |                                                                              | 2-3=-2102/0, 3-4=-3461/0, 4-5=-4251/0, 5-6=-4251/0, 6-7=-4251/0, 7-8=-4251/0, 8-9=-2876/0                                                       |
| BOT CHORD |                                                                              | 17-18=0/1235, 16-17=0/2938, 15-16=0/3943, 14-15=0/3943, 13-14=0/4251, 12-13=0/3525, 11-12=0/2178                                                |
| WEBS      |                                                                              | 6-13=-264/0, 2-18=-1547/0, 2-17=0/1128, 3-17=-1089/0, 3-16=0/680, 4-16=-627/0, 4-14=-84/732, 9-11=-2337/0, 9-12=0/908, 8-12=-845/0, 8-13=0/1040 |

- | NOTES |                                                                                                                                                                                                            |
|-------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 1)    | Unbalanced floor live loads have been considered for this design.                                                                                                                                          |
| 2)    | All plates are MT20 plates unless otherwise indicated.                                                                                                                                                     |
| 3)    | This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.                                                     |
| 4)    | Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means. |



This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.




|                 |               |                     |          |          |                                                           |
|-----------------|---------------|---------------------|----------|----------|-----------------------------------------------------------|
| Job<br>72512298 | Truss<br>F212 | Truss Type<br>Truss | Qty<br>3 | Ply<br>1 | MUNGO HOMES - TELFAIR 2ND FLR<br>Job Reference (optional) |
|-----------------|---------------|---------------------|----------|----------|-----------------------------------------------------------|

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Joy Perry

Run: 8.83 S Apr 11 2025 Print: 8.830 S Apr 11 2025 MiTek Industries, Inc. Wed Apr 30 20:47:47

Page: 1

ID:a?q6?71yTv6SHVH?OIzQvZz8qqv-0\_9JS76pYDjmwKhhb?rLMR4tfK4eRJnVKqZAFzL5fA



|                       |  |       |                 |  |                 |           |  |      |  |          |       |                                 |       |        |     |               |  |                 |  |  |  |  |  |
|-----------------------|--|-------|-----------------|--|-----------------|-----------|--|------|--|----------|-------|---------------------------------|-------|--------|-----|---------------|--|-----------------|--|--|--|--|--|
| Plate Offsets (X, Y): |  |       |                 |  |                 |           |  |      |  |          |       | [1:0-1-8,Edge], [15:0-1-8,Edge] |       |        |     |               |  |                 |  |  |  |  |  |
| Loading               |  | (psf) | Spacing         |  | 2-0-0           | CSI       |  | DEFL |  | in       | (loc) | l/defl                          | L/d   | PLATES |     | GRIP          |  |                 |  |  |  |  |  |
| TCLL                  |  | 40.0  | Plate Grip DOL  |  | 1.00            | TC        |  | 0.79 |  | Vert(LL) |       | -0.32                           | 15-16 | >659   | 480 | MT20          |  | 244/190         |  |  |  |  |  |
| TCDL                  |  | 10.0  | Lumber DOL      |  | 1.00            | BC        |  | 1.00 |  | Vert(CT) |       | -0.44                           | 15-16 | >479   | 360 | MT18HS        |  | 244/190         |  |  |  |  |  |
| BCLL                  |  | 0.0   | Rep Stress Incr |  | YES             | WB        |  | 0.66 |  | Horz(CT) |       | 0.02                            | 12    | n/a    | n/a |               |  |                 |  |  |  |  |  |
| BCDL                  |  | 5.0   | Code            |  | IRC2015/TPI2014 | Matrix-SH |  |      |  |          |       |                                 |       |        |     | Weight: 90 lb |  | FT = 20%F, 12%E |  |  |  |  |  |

|               |                   |                |                                                                                       |
|---------------|-------------------|----------------|---------------------------------------------------------------------------------------|
| <b>LUMBER</b> |                   | <b>BRACING</b> |                                                                                       |
| TOP CHORD     | 2x4 SP No.2(flat) | TOP CHORD      | Structural wood sheathing directly applied or 4-8-2 oc purlins, except end verticals. |
| BOT CHORD     | 2x4 SP No.1(flat) | BOT CHORD      | Rigid ceiling directly applied or 10-0-0 oc bracing, Except:                          |
| WEBS          | 2x4 SP No.3(flat) |                | 2-2-0 oc bracing: 16-17                                                               |
| OTHERS        | 2x4 SP No.3(flat) |                | 1-4-12 oc bracing: 15-16.                                                             |

|                  |                                                                                                                                    |                                                       |
|------------------|------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------|
| <b>REACTIONS</b> | (lb/size)                                                                                                                          | 1=977/0-3-8, (min. 0-1-8), 12=971/0-3-8, (min. 0-1-8) |
| <b>FORCES</b>    | (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.                                                       |                                                       |
| TOP CHORD        | 1-2=-1123/0, 2-3=-1119/0, 3-4=-2770/0, 4-5=-3829/0, 5-6=-3829/0, 6-7=-3829/0, 7-8=-4128/0, 8-9=-4128/0, 9-10=-2823/0               |                                                       |
| BOT CHORD        | 18-19=0/2095, 17-18=0/3415, 16-17=0/4128, 15-16=0/4128, 14-15=0/3453, 13-14=0/3453, 12-13=0/2142                                   |                                                       |
| WEBS             | 1-19=0/1396, 3-19=-1271/0, 3-18=0/879, 4-18=-839/0, 4-17=0/529, 7-17=-752/124, 10-12=-2297/0, 10-13=0/887, 9-13=-821/0, 9-15=0/978 |                                                       |

- NOTES**
- 1) Unbalanced floor live loads have been considered for this design.
  - 2) All plates are MT20 plates unless otherwise indicated.
  - 3) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 4) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
  - 5) Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.
  - 6) CAUTION, Do not erect truss backwards.



|          |       |            |     |     |                               |
|----------|-------|------------|-----|-----|-------------------------------|
| Job      | Truss | Truss Type | Qty | Ply | MUNGO HOMES - TELFAIR 2ND FLR |
| 72512298 | FG1   | Truss      | 1   | 1   | Job Reference (optional)      |

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Joy Perry

Run: 8.83 S Apr 11 2025 Print: 8.830 S Apr 11 2025 MiTek Industries, Inc. Wed Apr 30 20:47:47

Page: 1

ID:a?q6?71yTv6SHVH?OlZqv2z8gqv-0\_9jS76pYDjmwKhhib?rLMR9xfNZr?nVKqZAFzL5fA




Plate Offsets (X, Y): [2:0-2-12,Edge], [4:0-2-12,Edge], [5:0-3-0,Edge], [6:Edge,0-1-8], [8:Edge,0-1-8]

| Loading | (psf) | Spacing         | 2-0-0           | CSI       | DEFL | in       | (loc) | l/defl | L/d  | PLATES        | GRIP            |
|---------|-------|-----------------|-----------------|-----------|------|----------|-------|--------|------|---------------|-----------------|
| TCLL    | 40.0  | Plate Grip DOL  | 1.00            | TC        | 0.47 | Vert(LL) | -0.03 | 7      | >999 | 480           | 244/190         |
| TCDL    | 10.0  | Lumber DOL      | 1.00            | BC        | 0.78 | Vert(CT) | -0.05 | 7      | >999 | 360           |                 |
| BCLL    | 0.0   | Rep Stress Incr | NO              | WB        | 0.68 | Horz(CT) | 0.02  | 6      | n/a  | n/a           |                 |
| BCDL    | 5.0   | Code            | IRC2015/TPI2014 | Matrix-SH |      |          |       |        |      |               |                 |
|         |       |                 |                 |           |      |          |       |        |      | Weight: 40 lb | FT = 20%F, 12%E |

| LUMBER    |                   | BRACING   |                                                                                        |
|-----------|-------------------|-----------|----------------------------------------------------------------------------------------|
| TOP CHORD | 2x4 SP No.2(flat) | TOP CHORD | Structural wood sheathing directly applied or 5-10-8 oc purlins, except end verticals. |
| BOT CHORD | 2x4 SP No.2(flat) | BOT CHORD | Rigid ceiling directly applied or 10-0-0 oc bracing.                                   |
| WEBS      | 2x4 SP No.3(flat) |           |                                                                                        |
| OTHERS    | 2x4 SP No.3(flat) |           |                                                                                        |


|           |                                                                                                          |                                                        |
|-----------|----------------------------------------------------------------------------------------------------------|--------------------------------------------------------|
| REACTIONS | (lb/size)                                                                                                | 6=2099/0-3-8, (min. 0-1-8), 8=2197/0-7-0, (min. 0-1-8) |
| FORCES    | (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.                             |                                                        |
| TOP CHORD | 8-9=-573/0, 1-9=-572/0, 6-10=-447/0, 5-10=-446/0, 2-12=-3179/0, 3-12=-3179/0, 3-13=-3179/0, 4-13=-3179/0 |                                                        |
| BOT CHORD | 7-8=0/2399, 6-7=0/2431                                                                                   |                                                        |
| WEBS      | 3-7=-1063/0, 2-8=-2859/0, 2-7=0/957, 4-6=-2907/0, 4-7=0/918                                              |                                                        |

- NOTES**
- 1) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 2) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
  - 3) Use Simpson Strong-Tie THA422 (6-16d Girder, 6-10d Truss) or equivalent spaced at 2-0-0 oc max. starting at 0-7-0 from the left end to 4-7-0 to connect truss(es) to front face of top chord.
  - 4) Use Simpson Strong-Tie THA422 (6-16d Girder, 6-10d Truss) or equivalent at 1-4-8 from the left end to connect truss(es) to back face of top chord.
  - 5) Use Simpson Strong-Tie THA422 (6-16d Girder, 6-10d Truss) or equivalent spaced at 2-0-0 oc max. starting at 3-4-8 from the left end to 5-4-8 to connect truss(es) to back face of top chord.
  - 6) Fill all nail holes where hanger is in contact with lumber.
  - 7) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

| LOAD CASE(S)                                                                     | Standard |
|----------------------------------------------------------------------------------|----------|
| 1) Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00       |          |
| Uniform Loads (lb/ft)                                                            |          |
| Vert: 6-8=-10, 1-5=-100                                                          |          |
| Concentrated Loads (lb)                                                          |          |
| Vert: 2=-467 (B), 4=-742 (F), 11=-772 (F), 12=-742 (F), 13=-467 (B), 14=-501 (B) |          |



UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Joy Perry Run: 8.83 S Apr 11 2025 Print: 8.830 S Apr 11 2025 MiTek Industries, Inc. Wed Apr 30 20:47:41 Page: 1  
ID:a?g6?71yTv6SHVH?OIzqv2z8gqv-UBj5fT6RIXrdXUGfFIW4uZ EQ2jHNtHxk Z6iizL5f9



| <b>Loading</b> | (psf) | <b>Spacing</b>  | 2-0-0           | <b>CSI</b> |      | <b>DEFL</b> | in    | (loc) | I/defl | L/d | <b>PLATES</b> | <b>GRIP</b>     |
|----------------|-------|-----------------|-----------------|------------|------|-------------|-------|-------|--------|-----|---------------|-----------------|
| TCLL           | 40.0  | Plate Grip DOL  | 1.00            | TC         | 0.87 | Vert(LL)    | -0.07 | 9     | >999   | 480 | M18AHS        | 186/179         |
| TCDL           | 10.0  | Lumber DOL      | 1.00            | BC         | 0.75 | Vert(CT)    | -0.12 | 9-10  | >778   | 360 | MT20          | 244/190         |
| BCLL           | 0.0   | Rep Stress Incr | NO              | WB         | 0.75 | Horz(CT)    | 0.03  | 7     | n/a    | n/a |               |                 |
| BCDL           | 5.0   | Code            | IRC2015/TPI2014 | Matrix-SH  |      |             |       |       |        |     | Weight: 72 lb | FT = 20%F, 12%E |

|                  |           |                                                          |
|------------------|-----------|----------------------------------------------------------|
| <b>REACTIONS</b> | (lb/size) | 7=4220/0-3-8, (min. 0-2-15), 12=4488/0-7-0, (min. 0-3-0) |
|                  | Max Grav  | 7=4333 (LC 4), 12=4488 (LC 1)                            |

|               |                                                                                                              |
|---------------|--------------------------------------------------------------------------------------------------------------|
| <b>FORCES</b> | (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.                                 |
| TOP CHORD     | 1-12=-1069/0, 6-7=-353/0, 2-13=-6177/0, 3-13=-6177/0, 3-14=-8139/0, 4-14=-8139/0, 4-15=-6565/0, 5-15=-6565/0 |
| BOT CHORD     | 11-12=0/4168, 10-11=0/8130, 9-10=0/8139, 8-9=0/8154, 7-8=0/4853                                              |
| WEBS          | 3-10=-404/377, 4-9=-451/333, 5-7=-6260/0, 5-8=0/2743, 4-8=-2868/0, 2-12=-5376/0, 2-11=0/3121, 3-11=-3263/0   |

- 1) Unbalanced floor live loads have been considered for this design.
- 2) All plates are MT20 plates unless otherwise indicated.
- 3) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 4) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
- 5) Use Simpson Strong-Tie THAC422 (6-16d Girder, 6-16d Truss) or equivalent spaced at 2-0-0 oc max. starting at 1-4-8 from the left end to 7-4-8 to connect truss(es) to front face of top chord.
- 6) Use Simpson Strong-Tie THAC422 (6-16d Girder, 6-16d Truss) or equivalent spaced at 2-0-0 oc max. starting at 0-2-2 from the left end to 6-9-8 to connect truss(es) to back face of top chord.
- 7) Fill all nail holes where hanger is in contact with lumber.
- 8) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

**LOAD CASE(S)** Standard

1) Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00

Uniform Loads (lb/ft)

Vert: 7-12=-10, 1-6=-100


Concentrated Loads (lb)

Vert: 1=-1092 (B), 3=-467 (F), 4=-1044 (B), 5=-1044 (B), 2=-467 (F), 13=-1044 (B), 14=-1044 (B), 15=-467 (F), 16=-1159 (F)



This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.

|          |       |            |     |     |                               |
|----------|-------|------------|-----|-----|-------------------------------|
| Job      | Truss | Truss Type | Qty | Ply | MUNGO HOMES - TELFAIR 2ND FLR |
| 72512298 | K200  | Truss      | 1   | 1   | Job Reference (optional)      |



Scale = 1:36.7

| Loading | (psf) | Spacing         | 2-0-0           | CSI      | DEFL | in        | (loc) | l/defl | L/d | PLATES | GRIP          |                 |
|---------|-------|-----------------|-----------------|----------|------|-----------|-------|--------|-----|--------|---------------|-----------------|
| TCLL    | 40.0  | Plate Grip DOL  | 1.00            | TC       | 0.08 | Vert(LL)  | n/a   | -      | n/a | 999    | MT20          | 244/190         |
| TCDL    | 10.0  | Lumber DOL      | 1.00            | BC       | 0.01 | Vert(TL)  | n/a   | -      | n/a | 999    |               |                 |
| BCLL    | 0.0   | Rep Stress Incr | YES             | WB       | 0.03 | Horiz(TL) | 0.00  | 14     | n/a | n/a    |               |                 |
| BCDL    | 5.0   | Code            | IRC2015/TPI2014 | Matrix-R |      |           |       |        |     |        | Weight: 67 lb | FT = 20%F, 12%E |

|               |                   |                |                                                                                       |
|---------------|-------------------|----------------|---------------------------------------------------------------------------------------|
| <b>LUMBER</b> |                   | <b>BRACING</b> |                                                                                       |
| TOP CHORD     | 2x4 SP No.2(flat) | TOP CHORD      | Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals. |
| BOT CHORD     | 2x4 SP No.2(flat) | BOT CHORD      | Rigid ceiling directly applied or 10-0-0 oc bracing.                                  |
| WEBS          | 2x4 SP No.3(flat) |                |                                                                                       |
| OTHERS        | 2x4 SP No.3(flat) |                |                                                                                       |


**REACTIONS** All bearings 15-11-8.  
(lb) - Max Grav All reactions 250 (lb) or less at joint(s) 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26

**FORCES** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES**
- 1) All plates are 1.5x3 (||) MT20 unless otherwise indicated.
  - 2) Gable requires continuous bottom chord bearing.
  - 3) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
  - 4) Gable studs spaced at 1-4-0 oc.
  - 5) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 6) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.



|          |       |            |     |     |                               |
|----------|-------|------------|-----|-----|-------------------------------|
| Job      | Truss | Truss Type | Qty | Ply | MUNGO HOMES - TELFAIR 2ND FLR |
| 72512298 | K201  | Truss      | 1   | 1   | Job Reference (optional)      |



| Loading | (psf) | Spacing         | 2-0-0           | CSI      | DEFL | in        | (loc) | l/defl | L/d | PLATES | GRIP          |                 |
|---------|-------|-----------------|-----------------|----------|------|-----------|-------|--------|-----|--------|---------------|-----------------|
| TCLL    | 40.0  | Plate Grip DOL  | 1.00            | TC       | 0.09 | Vert(LL)  | n/a   | -      | n/a | 999    | MT20          | 244/190         |
| TCDL    | 10.0  | Lumber DOL      | 1.00            | BC       | 0.02 | Vert(TL)  | n/a   | -      | n/a | 999    |               |                 |
| BCLL    | 0.0   | Rep Stress Incr | YES             | WB       | 0.03 | Horiz(TL) | 0.00  | 18     | n/a | n/a    |               |                 |
| BCDL    | 5.0   | Code            | IRC2015/TPI2014 | Matrix-R |      |           |       |        |     |        | Weight: 80 lb | FT = 20%F, 12%E |

| LUMBER                      | BRACING                                                                                           |
|-----------------------------|---------------------------------------------------------------------------------------------------|
| TOP CHORD 2x4 SP No.2(flat) | TOP CHORD Structural wood sheathing directly applied or 6'-0'-0 oc purlins, except end verticals. |
| BOT CHORD 2x4 SP No.2(flat) | BOT CHORD Rigid ceiling directly applied or 10'-0'-0 oc bracing.                                  |
| WEBS 2x4 SP No.3(flat)      |                                                                                                   |
| OTHERS 2x4 SP No.3(flat)    |                                                                                                   |

| REACTIONS       | All bearings 19'-0'-0.                                                                                |
|-----------------|-------------------------------------------------------------------------------------------------------|
| (lb) - Max Grav | All reactions 250 (lb) or less at joint(s) 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32 |


| FORCES | (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown. |
|--------|------------------------------------------------------------------------------|
|--------|------------------------------------------------------------------------------|

- NOTES**
- 1) All plates are 1.5x3 (J) MT20 unless otherwise indicated.
  - 2) Gable requires continuous bottom chord bearing.
  - 3) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
  - 4) Gable studs spaced at 1'-4'-0 oc.
  - 5) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 6) Recommend 2x6 strongbacks, on edge, spaced at 10'-0'-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.





|                 |               |                     |          |          |                                                           |
|-----------------|---------------|---------------------|----------|----------|-----------------------------------------------------------|
| Job<br>72512298 | Truss<br>K203 | Truss Type<br>Truss | Qty<br>1 | Ply<br>1 | MUNGO HOMES - TELFAIR 2ND FLR<br>Job Reference (optional) |
|-----------------|---------------|---------------------|----------|----------|-----------------------------------------------------------|




| Loading | (psf) | Spacing         | 2-0-0           | CSI      |      | DEFL      | in   | (loc) | l/defl | L/d | PLATES        | GRIP            |
|---------|-------|-----------------|-----------------|----------|------|-----------|------|-------|--------|-----|---------------|-----------------|
| TCLL    | 40.0  | Plate Grip DOL  | 1.00            | TC       | 0.08 | Vert(LL)  | n/a  | -     | n/a    | 999 | MT20          | 244/190         |
| TCDL    | 10.0  | Lumber DOL      | 1.00            | BC       | 0.02 | Vert(TL)  | n/a  | -     | n/a    | 999 |               |                 |
| BCLL    | 0.0   | Rep Stress Incr | YES             | WB       | 0.03 | Horiz(TL) | 0.00 | 5     | n/a    | n/a |               |                 |
| BCDL    | 5.0   | Code            | IRC2015/TPI2014 | Matrix-R |      |           |      |       |        |     | Weight: 18 lb | FT = 20%F, 12%E |

|                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |                |                                                                                       |
|------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------|---------------------------------------------------------------------------------------|
| <b>LUMBER</b>    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | <b>BRACING</b> |                                                                                       |
| TOP CHORD        | 2x4 SP No.2(flat)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | TOP CHORD      | Structural wood sheathing directly applied or 3-5-0 oc purlins, except end verticals. |
| BOT CHORD        | 2x4 SP No.2(flat)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | BOT CHORD      | Rigid ceiling directly applied or 10-0-0 oc bracing.                                  |
| WEBS             | 2x4 SP No.3(flat)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |                |                                                                                       |
| OTHERS           | 2x4 SP No.3(flat)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |                |                                                                                       |
| <b>REACTIONS</b> | All bearings 3-5-0.<br>(lb) - Max Grav All reactions 250 (lb) or less at joint(s) 5, 6, 7, 8                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                |                                                                                       |
| <b>FORCES</b>    | (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                |                                                                                       |
| <b>NOTES</b>     | 1) Gable requires continuous bottom chord bearing.<br>2) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).<br>3) Gable studs spaced at 1-4-0 oc.<br>4) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.<br>5) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means. |                |                                                                                       |



|          |       |            |     |     |                               |
|----------|-------|------------|-----|-----|-------------------------------|
| Job      | Truss | Truss Type | Qty | Ply | MUNGO HOMES - TELFAIR 2ND FLR |
| 72512298 | K204  | Truss      | 1   | 1   | Job Reference (optional)      |



| Loading | (psf) | Spacing         | 2-0-0           | CSI      | DEFL | in        | (loc) | I/defl | L/d | PLATES | GRIP           |                 |
|---------|-------|-----------------|-----------------|----------|------|-----------|-------|--------|-----|--------|----------------|-----------------|
| TCLL    | 40.0  | Plate Grip DOL  | 1.00            | TC       | 0.08 | Vert(LL)  | n/a   | -      | n/a | 999    | MT20           | 244/190         |
| TCDL    | 10.0  | Lumber DOL      | 1.00            | BC       | 0.02 | Vert(TL)  | n/a   | -      | n/a | 999    |                |                 |
| BCLL    | 0.0   | Rep Stress Incr | YES             | WB       | 0.03 | Horiz(TL) | 0.00  | 22     | n/a | n/a    |                |                 |
| BCDL    | 5.0   | Code            | IRC2015/TPI2014 | Matrix-R |      |           |       |        |     |        | Weight: 108 lb | FT = 20%F, 12%E |

|               |                   |                |                                                                                       |
|---------------|-------------------|----------------|---------------------------------------------------------------------------------------|
| <b>LUMBER</b> |                   | <b>BRACING</b> |                                                                                       |
| TOP CHORD     | 2x4 SP No.2(flat) | TOP CHORD      | Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals. |
| BOT CHORD     | 2x4 SP No.2(flat) | BOT CHORD      | Rigid ceiling directly applied or 10-0-0 oc bracing.                                  |
| WEBS          | 2x4 SP No.3(flat) |                |                                                                                       |
| OTHERS        | 2x4 SP No.3(flat) |                |                                                                                       |

|                  |                                                                                                                               |
|------------------|-------------------------------------------------------------------------------------------------------------------------------|
| <b>REACTIONS</b> | All bearings 26-0-8.                                                                                                          |
| (lb) - Max Grav  | All reactions 250 (lb) or less at joint(s) 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 36, 37, 38, 39, 40, 41, 42, 43 |

|               |                                                                              |
|---------------|------------------------------------------------------------------------------|
| <b>FORCES</b> | (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown. |
|---------------|------------------------------------------------------------------------------|

- NOTES**
- 1) All plates are 1.5x3 (J) MT20 unless otherwise indicated.
  - 2) Gable requires continuous bottom chord bearing.
  - 3) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
  - 4) Gable studs spaced at 1-4-0 oc.
  - 5) Bearing at joint(s) 22 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
  - 6) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 7) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.



|                 |               |                     |          |          |                                                           |
|-----------------|---------------|---------------------|----------|----------|-----------------------------------------------------------|
| Job<br>72512298 | Truss<br>K205 | Truss Type<br>Truss | Qty<br>1 | Ply<br>1 | MUNGO HOMES - TELFAIR 2ND FLR<br>Job Reference (optional) |
|-----------------|---------------|---------------------|----------|----------|-----------------------------------------------------------|

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Joy Perry

Run: 8.83 S Apr 11 2025 Print: 8.830 S Apr 11 2025 MiTek Industries, Inc. Wed Apr 30 20:47:45

Page: 1

ID:a?q6?71yTv6SHVH?OIzqv2z8gqv-yNHTsp733qzU9er3p01JRnWbXSE36Vi4zeJgE8zL5f8




Plate Offsets (X, Y): [2:0-3-0,Edge]

| Loading | (psf) | Spacing         | 2-0-0           | CSI      |      | DEFL     | in   | (loc) | l/defl | L/d | PLATES        | GRIP            |
|---------|-------|-----------------|-----------------|----------|------|----------|------|-------|--------|-----|---------------|-----------------|
| TCLL    | 40.0  | Plate Grip DOL  | 1.00            | TC       | 0.08 | Vert(LL) | n/a  | -     | n/a    | 999 | MT20          | 244/190         |
| TCDL    | 10.0  | Lumber DOL      | 1.00            | BC       | 0.01 | Vert(CT) | n/a  | -     | n/a    | 999 |               |                 |
| BCLL    | 0.0   | Rep Stress Incr | YES             | WB       | 0.03 | Horz(CT) | 0.00 | 18    | n/a    | n/a |               |                 |
| BCDL    | 5.0   | Code            | IRC2015/TPI2014 | Matrix-R |      |          |      |       |        |     | Weight: 77 lb | FT = 20%F, 12%E |

| LUMBER    |                   | BRACING   |                                                                                       |
|-----------|-------------------|-----------|---------------------------------------------------------------------------------------|
| TOP CHORD | 2x4 SP No.2(flat) | TOP CHORD | Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals. |
| BOT CHORD | 2x4 SP No.2(flat) | BOT CHORD | Rigid ceiling directly applied or 10-0-0 oc bracing.                                  |
| WEBS      | 2x4 SP No.3(flat) |           |                                                                                       |
| OTHERS    | 2x4 SP No.3(flat) |           |                                                                                       |

**REACTIONS** All bearings 18-3-8.  
(lb) - Max Grav All reactions 250 (lb) or less at joint(s) 18, 19, 20, 21, 22, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33

**FORCES** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES**
- 1) All plates are 1.5x3 (||) MT20 unless otherwise indicated.
  - 2) Gable requires continuous bottom chord bearing.
  - 3) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
  - 4) Gable studs spaced at 1-4-0 oc.
  - 5) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 6) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
  - 7) CAUTION, Do not erect truss backwards.



This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.

