



HARNETT COUNTY ENVIROMENTAL HEALTH

File/Permit #: SFD2507-0096

CDP #:

IMPROVEMENT PERMIT (IP)

☒ New☐ Expansion☐ Repair☐ System Relocation☐ Change of Use

Owner: BENJAMIN STOUT REAL ESTATE SERVICES INC

Applicant: BENJAMIN STOUT REAL ESTATE SERVICES INC

Property Location: 124 BAXLEY DR DUNN, NC 28334

PIN/Lot Identifier: 1508-61-2904.000

Subdivision: ILAS WAY

Lot #: 14 Block: Section:

Facility Type: SFD 38' x 58' Number of bedrooms: 3 Number of Occupants: 6 Other:

Design Daily Flow: 360 GPD LTAR (Initial): .3 gpd/ft² LTAR (Repair): .3 gpd/ft²

Wastewater System Type: 25% Reduction System (Initial)

Pump Required: ☐ Yes ☐ No ☒ May be required Usable Depth to Limiting Condition (Initial): 40"

Wastewater System Type 50% Reduction System (Repair)

Pump Required: ☒ Yes ☐ No ☐ May be required Usable Depth to Limiting Condition (Repair): 40"Effluent Standard: ☒ DSE ☐ HSE ☐ Other: Type of Water Supply: ☐ Private well ☒ Municipal Supply ☐ Other:

Permit conditions:

No Foundation or Gutter Drains to be Directed Towards Septic System. (Route Water Line to be 10' Off any part of Septic)

No Cutting or Grading of Soil in Septic Area or Repair Area

Stay 50' Off Existing neighboring Well with Any part of Septic

The issuance of this permit in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This permit is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of 15A NCAC 18E and to the conditions of this permit.

Authorized Agent's Printed Name: Ren Levocz

Date: 08/12/2025

Authorized Agent's Signature: 

Expiration Date: 08/12/2030

CONSTRUCTION AUTHORIZATION (CA)

☒ New☐ Expansion☐ Repair☐ System Relocation☐ Change of Use

Owner: BENJAMIN STOUT REAL ESTATE SERVICES INC

Applicant: BENJAMIN STOUT REAL ESTATE SERVICES INC

Property Location: 124 BAXLEY DR DUNN, NC 28334

PIN/Lot Identifier: 1508-61-2904.000

Subdivision: ILAS WAY

Lot #: 14 Block: Section:

Facility Type: SFD 38' x 58' Number of bedrooms: 3 Number of Occupants: 6 Other:

Design Daily Flow: 360 GPD LTAR: .3 gpd/ft²Effluent Standard: ☒ DSE ☐ HSE ☐ Other: Type of Water Supply: ☐ Private well ☒ Municipal Supply ☐ Other:

Installation Requirements/Conditions

Wastewater System Type: 25% Reduction System

Pump Required: ☐ Yes ☐ No ☒ May be required

Septic Tank Size: 1,000 gallons Total Trench Length: 300' feet Trench Spacing: 9' feet on center

Pump Tank Size: gallons Maximum Trench Depth: 18"-28" inches Soil Cover: 6" inches

Trench Width: 36" inches Distribution Method: ☒ Serial ☒ D-Box or Parallel ☐ Pressure Manifold ☐ Other:Artificial Drainage Required: Yes ☐ No ☒ If yes, please specify details:Management Entity Required: ☐ Yes ☒ No Minimum O&M Requirements:

Permit conditions:

No Foundation or Gutter Drains to be Directed Towards Septic System. (Route Water Line to be 10' Off any part of Septic)

No Cutting or Grading of Soil in Septic Area or Repair Area

Stay 50' Off Existing neighboring Well with Any part of Septic

The requirements of 15A NCAC 18E are incorporated by reference into this permit and shall be met. Systems shall be installed in accordance with the attached site sketch. This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be affected by a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of 15A NCAC 18E, or 15A NCAC 18A .1900, as applicable, and to the conditions of this permit.

Authorized Agent's Printed Name: Ren Levocz

Date: 08/12/25

Authorized Agent's Signature: 

Expiration Date: 08/12/2030

Owner/Legal Representative Signature:

Date:

***See attached site sketch**

Harnett County Environmental Health

SITE SKETCH

PIN 1508-61-2904.000

Permit Number SFD2507-0096

BENJAMIN STOUT REAL ESTATE SERVICES INC

ILAS WAY Lot 14

Applicant's Name

Subdivision/Section/Lot Number

Ren Levocz

08/12/2025

Authorized State Agent

Date

System components represent approximate contours only. The contractor must flag the system prior to beginning the installation to ensure that the proper grade is maintained.

Scale = NTS

