




Carter Sanford Component Plant
298 Harvey Faulk Rd
Sanford, NC 27332

Phone #:919-775-1450



Builder: David Weekley Homes

Model: B326 A CP TMB BDRM4 GRH

THE PLACEMENT PLAN NOTES:

1. The Placement Plan is a diagram for truss installation. It is not an engineered drawing and has not been reviewed by an engineer. The Owner/Building Designer is responsible for obtaining an engineer's review if one is required by the local jurisdiction.
2. The responsibilities of the Owner, Contractor, Building Designer, Component Designer and Component Manufacturer shall be as set forth in ANSI/TPI 1. Capitalized terms shall be as defined in ANSI/TP 1 unless otherwise indicated.
3. Each Component is designed as an individual component utilizing information provided by others. The Owner/Building Designer is responsible for reviewing all Component Submittal Packages and individual Component Design Drawings for compliance with the Construction Documents and compatibility with the overall Building design.
4. Contractor will not proceed with component installation until the Owner/Building Designer has reviewed the Component Submittal Package. Questions on the suitability of any Component will be resolved by the Building Designer.
5. The Building Designer and Contractor are responsible for all temporary and permanent bracing.
6. The Placement Plan assumes the building is dimensionally correct, structurally sound, and in a suitable condition to support each Component during installation and thereafter, including but not limited to installation of all bearing points. Proper design and construction of all structural components, including foundations, headers, beams, walls and columns are the responsibility of the Owner, Building Designer and Contractor.
7. Do not cut, drill, or modify any Component without first consulting the Component Manufacturer or Building Designer. Damaged Components shall not be installed unless directed by the Building Designer or approved by the Component Manufacturer.
8. Components must be handled and installed following all applicable safety standards and best practices, including but not limited to BCSI, OSHA, TPI and local codes. Failure to properly handle, brace or otherwise install Component can result in serious injury or death.
9. All uplift connectors shown within these documents are recommendations only. Per ANSI/TPI 1, all uplift connectors are the responsibility of the building designer and or contractor.

Approved By: _____

Date: _____

General Notes:

General Notes: ** CUTTING OR DRILLING OF COMPONENTS SHOULD NOT BE DONE WITHOUT CONTACTING COMPONENT SUPPLIER FIRST. CUSTOMER TAKES FULL RESPONSIBILITY FOR COMPONENTS IF CUT BEFORE AUTHORIZATION.

ALL BEARING POINTS MUST BE INSTALLED PRIOR TO SETTING ANY COMPONENTS.

Revisions	
00/00/00	Name
00/00/00	Name
00/00/00	Name
00/00/00	Name
00/00/00	Name



THIS IS A TRUSS PLACEMENT DIAGRAM ONLY. These trusses are designed as individual components to be incorporated into the building design at the specification of the building designer. See individual design sheets for each truss design identified on the placement drawing. The building designer is responsible for temporary and permanent bracing of the roof and floor systems and for the overall structure. The design of the truss support structure including headers, beams, walls, and columns is the responsibility of the building designer. For more information regarding the design and bracing of Wood Truss Company's products, please contact the Truss Place Branching Office. **Truss Place Branching Office** is available from the Truss Place Institute, 583 D Onifrio Drive, Madison, WI 53719.



David Weekley Homes
1007 Serenity-Roof-B326 A CP TMB BDRM4 GRH
ROOF PLACEMENT PLAN

Scale:	NTS
Date:	7/28/2025
Designer:	Nick Darr
Project Number:	25070152-01
Sheet Number:	1/1

FRAMER MUST REFER TO PLANS WHILE SETTING COMPONENTS. ** DAMAGED COMPONENTS SHOULD NOT BE INSTALLED UNLESS TOLD TO BY THE COMPONENT PLANT. ** TRUSS TO TRUSS CONNECTIONS ARE TOE-NAILED, UNLESS NOTED OTHERWISE.



GRIDERS MUST BE FULLY CONNECTED TOGETHER PRIOR TO ADDING ANY LOADS.

ALL UPLIFT CONNECTORS SHOWN WITHIN THESE DOCUMENTS ARE RECOMMENDATIONS ONLY. PER ANSIT/PTI 1, ALL UPLIFT CONNECTORS ARE THE RESPONSIBILITY OF THE BLDG DESIGNER AND OR CONTRACTOR.

★★ TRIANGULAR SYMBOL NEAR END OF TRUSS INDICATES LEFT END OF TRUSS AS SHOWN ON INDIVIDUAL TRUSS DRAWINGS

PLUMBING DROPS NOTED ARE IN THE APPROXIMATE LOCATIONS PER PLAN. BUILDER TO VERIFY LOCATIONS BEFORE SETTING TRUSSES.

REFER TO FINAL TRUSS ENGINEERING SHEETS FOR PLY TO PLY CONNECTIONS

Trenco
818 Soundside Rd
Edenton, NC 27932

Re: 25070152-01
1007 Serenity-Roof-B326 A CP TMB BDRM4 GRH

The truss drawing(s) referenced below have been prepared by Truss Engineering Co. under my direct supervision based on the parameters provided by Carter Components (Sanford, NC)).

Pages or sheets covered by this seal: I75198365 thru I75198402

My license renewal date for the state of North Carolina is December 31, 2025.

North Carolina COA: C-0844



July 28, 2025

Gilbert, Eric


IMPORTANT NOTE: The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to MiTek or TRENCO. Any project specific information included is for MiTek's or TRENCO's customers file reference purpose only, and was not taken into account in the preparation of these designs. MiTek or TRENCO has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.

Job	Truss	Truss Type	Qty	Ply	1007 Serenity-Roof-B326 A CP TMB BDRM4 GRH I75198365
25070152-01	A01	Piggyback Base Supported Gable	1	1	Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Sun Jul 27 23:59:18
ID:HvYYHe4LpHmiz2Dld9nw5TzRQov-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrcDoi7J4zJC?f

Page: 1



Scale = 1:94.5

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.13	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.12	Vert(CT)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.21	Horz(CT)	0.01	33	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 546 lb	FT = 20%

LUMBER
TOP CHORD 2x6 SP No.2
BOT CHORD 2x6 SP No.2
WEBS 2x4 SP No.3
OTHERS 2x4 SP No.3 *Except*
49-17,48-18,47-19,46-20,44-22,50-16,51-15,
52-14,53-12:2x4 SP No.2


BRACING
TOP CHORD Structural wood sheathing directly applied or
6-0-0 oc purlins, except end verticals, and
2-0-0 oc purlins (10-0-0 max.): 13-21.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc
bracing.
WEBS 1 Row at midpt 17-49, 18-48, 19-47,
20-46, 22-44, 23-43,
24-42, 16-50, 15-51,
14-52, 12-53, 11-55, 9-56

REACTIONS (size)
33=53-3-0, 34=53-3-0, 35=53-3-0,
36=53-3-0, 37=53-3-0, 38=53-3-0,
39=53-3-0, 40=53-3-0, 42=53-3-0,
43=53-3-0, 44=53-3-0, 46=53-3-0,
47=53-3-0, 48=53-3-0, 49=53-3-0,
50=53-3-0, 51=53-3-0, 52=53-3-0,
53=53-3-0, 55=53-3-0, 56=53-3-0,
57=53-3-0, 58=53-3-0, 59=53-3-0,
60=53-3-0, 61=53-3-0, 62=53-3-0
Max Horiz 62=186 (LC 12)
Max Uplift 34=66 (LC 14), 35=170 (LC 15),
36=15 (LC 14), 37=50 (LC 15),
38=42 (LC 15), 39=44 (LC 15),
40=43 (LC 15), 42=46 (LC 15),
43=52 (LC 15), 47=29 (LC 11),
48=28 (LC 11), 49=25 (LC 10),
50=28 (LC 11), 51=29 (LC 10),
55=52 (LC 14), 56=46 (LC 14),
57=43 (LC 14), 58=44 (LC 14),
59=46 (LC 14), 60=22 (LC 14),
61=137 (LC 14), 62=88 (LC 15)

Max Grav 34=419 (LC 1), 35=81 (LC 13),
36=197 (LC 41), 37=152 (LC 59),
38=174 (LC 45), 39=221 (LC 45),
40=230 (LC 45), 42=229 (LC 45),
43=230 (LC 45), 44=217 (LC 45),
46=199 (LC 40), 47=220 (LC 40),
48=217 (LC 40), 49=216 (LC 40),
50=217 (LC 40), 51=220 (LC 40),
52=199 (LC 40), 53=218 (LC 43),
55=234 (LC 43), 56=233 (LC 43),
57=233 (LC 43), 58=233 (LC 43),
59=199 (LC 43), 60=150 (LC 58),
61=257 (LC 51), 62=133 (LC 58)

FORCES (lb) - Maximum Compression/Maximum
Tension
TOP CHORD 2-62=245/191, 1-2=0/23, 2-3=100/91,
3-4=74/121, 4-5=48/115, 5-6=58/156,
6-7=75/201, 7-8=90/246, 8-9=106/291,
9-11=124/338, 11-12=144/387,
12-13=146/383, 13-14=140/380,
14-15=140/380, 15-16=140/380,
16-17=140/380, 17-18=140/380,
18-19=140/380, 19-20=140/380,
20-21=140/380, 21-22=146/383,
22-23=144/387, 23-24=124/338,
24-25=106/291, 25-27=90/246,
27-28=75/201, 28-29=59/160,
29-30=63/137, 30-31=71/112,
31-32=124/100, 32-33=134/117

BOT CHORD 61-62=81/150, 60-61=81/150,
59-60=81/150, 58-59=81/150,
57-58=81/150, 56-57=81/150,
55-56=81/150, 53-55=81/150,
52-53=81/150, 51-52=81/150,
50-51=81/150, 49-50=81/150,
48-49=81/150, 47-48=81/150,
46-47=81/150, 44-46=81/150,
43-44=81/150, 42-43=81/150,
40-42=81/150, 39-40=81/150,
38-39=81/150, 37-38=81/150,
36-37=81/150, 35-36=81/150,
34-35=81/150, 33-34=81/150



July 28,2025

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1007 Serenity-Roof-B326 A CP TMB BDRM4 GRH I75198365
25070152-01	A01	Piggyback Base Supported Gable	1	1	Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Sun Jul 27 23:59:18
ID:HvYYHe4LpHmiz2Dld9nw5TzRQov-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f


Page: 2

WEBS 17-49=-176/57, 18-48=-177/62,
19-47=-180/61, 20-46=-159/6, 22-44=-177/2,
23-43=-190/87, 24-42=-189/81,
25-40=-190/77, 27-39=-181/77,
28-38=-132/77, 29-37=-125/77,
30-36=-138/78, 31-35=-65/120,
32-34=-244/137, 16-50=-177/62,
15-51=-180/61, 14-52=-159/1, 12-53=-178/0,
11-55=-194/87, 9-56=-193/81, 8-57=-193/77,
7-58=-194/77, 6-59=-157/77, 5-60=-115/91,
4-61=-186/159, 3-62=-226/263

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust)
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Corner(3E) -0-8-6 to 4-7-0, Exterior(2N) 4-7-0 to 12-4-2, Corner(3R) 12-4-2 to 22-11-14, Exterior(2N) 22-11-14 to 26-2-2, Corner(3R) 26-2-2 to 36-7-0, Exterior(2N) 36-7-0 to 47-11-2, Corner(3E) 47-11-2 to 53-3-0 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
- Provide adequate drainage to prevent water ponding.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- N/A
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard



July 28,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1007 Serenity-Roof-B326 A CP TMB BDRM4 GRH I75198366
25070152-01	A03	Piggyback Base	5	1	Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Sun Jul 27 23:59:20
ID:OFJfX3IDTxFbWWzrBXohbzzRCTM-RfC?PsB70Hq3NSgPqnL8w3uITxbGKWrCDoi7J4zJC?f

Page: 1




Scale = 1:94.5									
Plate Offsets (X, Y): [2:0-4-14,0-2-8], [10:0-5-0,0-4-8], [12:Edge,0-0-7], [14:0-5-0,0-4-8], [16:0-5-0,0-4-8], [25:0-4-0,0-3-12]									
Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.74	Vert(LL)	-0.36	21-23	>999
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.68	Vert(CT)	-0.69	21-23	>563
TCDL	10.0	Rep Stress Incr	YES	WB	0.98	Horz(CT)	0.11	12	n/a
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH					
BCDL	10.0								
									PLATES
									MT20
									GRIP
									244/190
									Weight: 471 lb FT = 20%

LUMBER	
TOP CHORD	2x6 SP No.2
BOT CHORD	2x6 SP 2400F 2.0E *Except* 28-26:2x6 SP No.2, 24-18:2x4 SP No.2
WEBS	2x4 SP No.3 *Except* 28-2:2x6 SP No.2, 27-2,6-25,8-16,27-5,25-5,16-9,14-9:2x4 SP No.2
WEDGE	Right: 2x4 SP No.3
BRACING	
TOP CHORD	Structural wood sheathing directly applied or 2-10-2 oc purlins, except end verticals, and 2-0-0 oc purlins (3-5-2 max.): 5-9.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 22-24,20-22,19-20,18-19.
WEBS	1 Row at midpt 25-29, 16-30, 5-27
JOINTS	1 Brace at Jt(s): 29, 30, 31
REACTIONS	(size) 12= Mechanical, 15=0-3-8, 28=0-5-8
	Max Horiz 28=187 (LC 12)
	Max Uplift 15=186 (LC 15), 28=107 (LC 14)
	Max Grav 12=2365 (LC 47), 15=905 (LC 39), 28=2709 (LC 37)
FORCES	(lb) - Maximum Compression/Maximum Tension
TOP CHORD	1-2=0/25, 2-3=3702/130, 3-5=3816/324, 5-6=3328/112, 6-7=3782/329, 7-8=3782/329, 8-9=3312/111, 9-11=4730/202, 11-12=4776/91, 2-28=2741/158
BOT CHORD	27-28=129/293, 25-27=0/3055, 23-25=0/3218, 21-23=0/3218, 17-21=0/3218, 15-17=0/3218, 13-15=0/3644, 12-13=50/4146, 22-24=49/45, 20-22=49/45, 19-20=49/45, 18-19=49/45

WEBS	2-27=0/3095, 24-25=524/195, 24-29=483/243, 6-29=468/248, 16-18=924/201, 18-30=834/229, 8-30=815/226, 3-27=816/329, 5-27=334/417, 5-25=0/1298, 9-16=25/1286, 10-14=918/321, 9-14=209/853, 10-13=225/785, 11-13=331/236, 20-21=63/0, 29-31=24/33, 30-31=128/22, 7-31=251/91, 6-31=306/702, 8-31=292/786, 22-23=187/0, 17-19=167/0
NOTES	
1)	Unbalanced roof live loads have been considered for this design.
2)	Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-8-6 to 4-7-9, Interior (1) 4-7-9 to 10-1-10, Exterior(2R) 10-1-10 to 39-2-5, Interior (1) 39-2-5 to 47-11-2, Exterior(2E) 47-11-2 to 53-3-0 zone; end vertical left exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3)	TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
4)	Unbalanced snow loads have been considered for this design.
5)	This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
6)	200.0lb AC unit load placed on the bottom chord, 24-7-0 from left end, supported at two points, 5-0-0 apart.
7)	Provide adequate drainage to prevent water ponding.
8)	All plates are 2x4 MT20 unless otherwise indicated.
9)	This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.

- 10) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 11) Refer to girder(s) for truss to truss connections.
- 12) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 28 and 15. This connection is for uplift only and does not consider lateral forces.
- 13) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard



July 28,2025


WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932

Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Sun Jul 27 23:59:20 Page: 1
ID:OFJfX3IDTxFbWWzrBXohbzzRCTM-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWwCDoi7J4zJC?f



LUMBER		BOT CHORD	32-33=19/41, 31-32=0/24, 3-31=1-1345/90, 30-31=199/2293, 29-30=-123/3476, 28-29=-40/48, 5-29=-489/170, 27-28=-58/225, 25-27=0/3125, 23-25=0/3125, 21-23=0/3125, 17-21=0/3125, 16-17=0/2928, 14-16=0/3517, 13-14=-48/4031, 24-26=-83/35, 22-24=-83/35, 20-22=-83/35, 19-20=-83/35	5) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with any other live loads.
TOP CHORD	2x6 SP No.2			6) 200.0lb AC unit load placed on the bottom chord, 24-7-0 from left end, supported at two points, 5-0-0 apart.
BOT CHORD	2x6 SP 2400F 2.0E *Except* 33-32,31-29:2x6 SP No.2, 32-3,5-28:2x4 SP No.3, 26-19:2x4 SP No.2			7) Provide adequate drainage to prevent water ponding.
WEBS	2x4 SP No.3 *Except* 27-29,29-6,27-6,7-27,17-10,10-15,9-17,31-2: 2x4 SP No.2, 33-2:2x6 SP No.2			8) All plates are 2x4 MT20 unless otherwise indicated.
WEDGE	Right: 2x4 SP No.3	WEBS	4-29=-164/163, 27-29=0/2829, 6-29=-281/1113, 6-27=0/839, 26-27=-575/196, 26-34=-526/218, 7-34=-512/215, 10-17=-21/1228, 10-15=-211/827, 11-15=-918/320, 11-14=-225/803, 12-14=-332/236, 17-19=-907/200, 19-35=-834/227, 9-35=-815/224, 4-30=-325/61, 3-30=0/1300, 31-33=-110/203, 2-31=-128/2647, 22-23=-71/0, 34-36=-19/34, 35-36=-125/21, 8-36=-246/92, 7-36=-310/678, 9-36=-293/776, 24-25=-178/0, 20-21=-157/0	9) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
BRACING				10) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
TOP CHORD	Structural wood sheathing directly applied or 3-0-12 oc purlins, except end verticals, and 2-0-0 oc purlins (3-6-4 max.): 6-10.			11) Refer to girder(s) for truss to truss connections.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 24-26,22-24,20-22,19-20.			12) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 33 and 16. This connection is for uplift only and does not consider lateral forces.
1 Row at midpt	5-29			13) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
WEBS	1 Row at midpt 27-34, 17-35			
JOINTS	1 Brace at Jt(s): 34, 35, 36			
REACTIONS		NOTES		


July 28, 2025

Job	Truss	Truss Type	Qty	Ply	1007 Serenity-Roof-B326 A CP TMB BDRM4 GRH I75198368
25070152-01	A04	Piggyback Base	1	1	Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Sun Jul 27 23:59:20
ID:DGN6a6f8caCKWpHw1clz1BzRCZx-RfC?PsB70Hq3NSgPqL8w3uITXbGKWrCD0i7J4zJC?f

Page: 1



Scale = 1:94.5

Plate Offsets (X, Y): [2:0-4-14,0-2-8], [10:0-5-0,0-4-8], [14:0-5-0,0-4-8], [15:0-6-0,0-5-4], [24:0-4-0,0-3-12]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.72	Vert(LL)	-0.38	24-26	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.69	Vert(CT)	-0.59	21	>922	180	MT20HS	187/143
TCDL	10.0	Rep Stress Incr	YES	WB	0.87	Horz(CT)	0.09	12	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 470 lb	FT = 20%

LUMBER
TOP CHORD 2x6 SP No.2
BOT CHORD 2x6 SP No.2 *Except* 23-17:2x4 SP No.2,
15-14,25-15:2x6 SP 2400F 2.0E
WEBS 2x4 SP No.3 *Except* 27-2:2x6 SP No.2,
26-2,6-24,15-8,15-9,14-9,13-10,26-5,24-5:2x
4 SP No.2

BRACING
TOP CHORD Structural wood sheathing directly applied or
2-11-10 oc purlins, except end verticals, and
2-0-0 oc purlins (3-5-4 max.): 5-9.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc
bracing.
WEBS 1 Row at midpt 24-28, 15-29, 9-14, 5-26
WEBS 2 Rows at 1/3 pts 10-13
JOINTS 1 Brace at Jt(s): 28,
29, 30

REACTIONS (size) 12= Mechanical, 13=0-5-8,
27=0-5-8
Max Horiz 27=187 (LC 12)
Max Uplift 12=191 (LC 14), 13=316 (LC 15),
27=94 (LC 14)
Max Grav 12=904 (LC 37), 13=2728 (LC 39),
27=2617 (LC 37)


FORCES (lb) - Maximum Compression/Maximum
Tension
TOP CHORD 1-2=0/25, 2-3=3597/112, 3-5=3711/306,
5-6=3179/129, 6-7=3691/345,
7-8=3691/345, 8-9=3159/130,
9-11=3212/498, 11-12=1512/429,
2-27=2668/157
BOT CHORD 26-27=128/288, 24-26=0/2926,
22-24=0/3074, 20-22=0/3074, 16-20=0/3074,
13-16=26/3074, 12-13=320/1306,
21-23=47/48, 19-21=47/48, 18-19=47/48,
17-18=47/48

WEBS 2-26=0/3003, 23-24=505/251,
23-28=464/328, 6-28=450/332,
15-17=912/218, 17-29=846/243,
8-29=823/240, 9-15=0/1828, 9-14=559/0,
10-14=0/723, 10-13=2614/176,
11-13=453/257, 3-26=816/329,
5-26=324/484, 5-24=0/1196, 19-20=53/0,
28-30=47/84, 29-30=169/37, 7-30=259/89,
8-30=290/821, 6-30=318/725,
21-22=181/0, 16-18=204/0

- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-8-6 to 4-7-9, Interior (1) 4-7-9 to 10-1-10, Exterior(2R) 10-1-10 to 39-2-5, Interior (1) 39-2-5 to 47-11-2, Exterior(2E) 47-11-2 to 53-3-0 zone; cantilever left and right exposed; end vertical left and right exposed; porch right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
 - Unbalanced snow loads have been considered for this design.
 - This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 200.0lb AC unit load placed on the bottom chord, 24-7-0 from left end, supported at two points, 5-0-0 apart.
 - Provide adequate drainage to prevent water ponding.
 - All plates are MT20 plates unless otherwise indicated.
 - All plates are 2x4 MT20 unless otherwise indicated.

- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 191 lb uplift at joint 12.
- One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 27 and 13. This connection is for uplift only and does not consider lateral forces.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard



July 28,2025


WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932


Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Sun Jul 27 23:59:21 Page: 1
ID:DGN6a6f8caCKWpHw1clz1BzRCZx-RIC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC7f



LUMBER		BOT CHORD	31-32=-19/42, 30-31=-0/24, 3-30=-1304/95, 29-30=-188/2232, 28-29=-104/3375, 27-28=-45/85, 5-28=-487/170, 26-27=-61/245, 24-26=0/2997, 22-24=0/2997, 20-22=0/2997, 16-20=0/2997, 14-16=-8/2705, 13-14=-284/1224, 23-25=-78/34, 21-23=-78/34, 19-21=-78/34, 18-19=-78/34
TOP CHORD	2x6 SP No.2		
BOT CHORD	2x6 SP No.2 *Except* 31-3,5-27:2x4 SP No.3, 27-17,17-15:2x6 SP 2400F 2.0E, 25-18:2x4 SP No.2		
WEBS	2x4 SP No.3 *Except* 26-28,28-6,26-6,9-16,16-10,14-11,15-10,26-7		
	2x4 SP No.2, 32-2:2x6 SP No.2		
OTHERS	2x4 SP No.3	WEBS	4-28=-187/154, 26-28=0/2690, 6-28=-284/1138, 6-26=-206/805, 16-18=-837/208, 18-34=-809/231, 9-34=-792/229, 10-16=0/1746, 11-15=0/760, 11-14=-2701/171, 12-14=-456/256, 10-15=-601/0, 25-26=-533/245, 25-33=-484/270, 7-33=-473/267, 4-29=-306/63, 3-29=0/1257, 30-32=-110/203, 2-30=-115/2571, 21-22=-60/0, 33-35=-39/79, 34-35=-141/31, 7-35=-305/737, 8-35=-300/100, 9-35=-277/832, 23-24=-171/0, 19-20=-195/0
BRACING			
TOP CHORD	Structural wood sheathing directly applied or 3-8-7 oc purlins, except end verticals, and 2-0-0 oc purlins (3-6-11 max.): 6-10.		
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing. Except:		
1 Row at midpt	5-28		
WEBS	1 Row at midpt 6-26, 16-34, 10-15, 26-33		
WEBS	2 Rows at 1/3 pts 11-14		
JOINTS	1 Brace at Jt(s): 33, 34, 35		
REACTIONS	(size) 13= Mechanical, 14=0-5-8, 32=0-5-8	NOTES	
	Max Horiz 32=-187 (LC 12)	1) Unbalanced roof live loads have been considered for this design.	
	Max Uplift 13=-170 (LC 14), 14=-311 (LC 15), 32=-90 (LC 14)	2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TC DL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-8-6 to 4-7-9, Interior (1) 4-7-9 to 10-1-10, Exterior(2R) 10-1-10 to 39-2-5, Interior (1) 39-2-5 to 47-11-2, Exterior(2E) 47-11-2 to 53-3-0 zone; cantilever left and right exposed ; end vertical left and right exposed; porch right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60	
	Max Grav 13=831 (LC 43), 14=2808 (LC 39), 32=2531 (LC 37)	3) TC LL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10	
FORCES	(lb) - Maximum Compression/Maximum Tension		
TOP CHORD	1-2=0/25, 2-3=-2515/119, 3-4=-3879/123, 4-6=-3876/217, 6-7=-3065/124, 7-8=-3633/336, 8-9=-3633/336, 9-10=-3047/125, 10-12=-3074/457, 12-13=-1427/387, 2-32=-2672/140		

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)



Job	Truss	Truss Type	Qty	Ply	1007 Serenity-Roof-B326 A CP TMB BDRM4 GRH I75198369
25070152-01	A04T	Piggyback Base	2	1	Job Reference (optional)

- 13) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 14 and 32. This connection is for uplift only and does not consider lateral forces.
14) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- LOAD CASE(S)** Standard



July 28,2025


Job	Truss	Truss Type	Qty	Ply	1007 Serenity-Roof-B326 A CP TMB BDRM4 GRH
25070152-01	A05	Attic Girder	1	4	I75198370
Job Reference (optional)					

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Sun Jul 27 23:59:21


Page: 1

ID:VIY0g5gMUgWQZRxixBYltzRA_fRfC?PsB70Hq3NSgPqnL8w3uITxbGKwRCDoi7J4zJC?f




loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.90	Vert(LL)	-0.50	38-41	>786	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.97	Vert(CT)	-0.75	37-39	>521	180	MT20HS	187/143
TCDL	10.0	Rep Stress Incr	Yes	WB	0.90	Horz(CT)	0.19	17	n/a	n/a	MT18HS	244/190
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH		Attic	-0.25	22-40	>786	360		
BCDL	10.0											
											Weight: 2038 lb	FT = 20%

LUMBER		BOT CHORD		44-45=-135/447, 42-44=-746/12300, 41-42=-859/16424, 35-41=-691/17026, 33-35=0/18312, 30-33=0/18937, 27-30=0/18075, 24-27=-276/15568, 21-24=-796/12213, 19-21=-801/16246, 18-19=-744/15345, 17-18=-116/2119, 39-40=-463/400, 37-39=-484/352, 36-37=-2838/0, 34-36=-2838/0, 32-34=-3460/0, 31-32=-3460/0, 29-31=-3460/0, 26-29=-2304/11, 23-26=-334/2811, 22-23=-334/2811	1) 4-ply truss to be connected together with 10d (0.131"x3") nails as follows: Top chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc, 2x4 - 1 row at 0-9-0 oc. Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc, 2x4 - 1 row at 0-7-0 oc. Web connected as follows: 2x4 - 1 row at 0-9-0 oc, 2x6 - 2 rows staggered at 0-9-0 oc, Except member 41-47 2x6 - 3 rows staggered at 0-4-0 oc, member 6-41 2x6 - 2 rows staggered at 0-4-0 oc. Attach BC w/ 1/2" diam. bolts (ASTM A-307) in the center of the member w/washers at 4-0-0 oc.		
TOP CHORD	2x6 SP No.2 *Except* 5-7:2x4 SP No.1						
BOT CHORD	2x4 SP No.1 *Except* 43-38,43-45:2x6 SP No.2, 28-22:2x4 SP No.2, 20-25:2x4 SP 2400F 2.0E						
WEBS	2x4 SP No.3 *Except* 13-21:2x6 SP 2400F 2.0E, 6-46,45-2,41-47,41-6,46-13:2x6 SP No.2, 44-2,17-16,18-16:2x4 SP No.2						
OTHERS	2x4 SP No.3						
BRACING							
TOP CHORD	Structural wood sheathing directly applied or 2-2-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 7-12.	WEBS				2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.	
BOT CHORD	Rigid ceiling directly applied or 2-2-0 oc bracing.					3) Unbalanced roof live loads have been considered for this design.	
JOINTS	1 Brace at Jt(s): 49, 50, 51, 52, 40, 26, 37, 29, 34						
REACTIONS							
(size) 17=0-5-8, 21=0-3-8, 45=0-5-8							
Max Horiz 45=-192 (LC 10)							
Max Uplift 17=-453 (LC 12), 21=-5416 (LC 45), 45=-702 (LC 12)							
Max Grav 17=9309 (LC 46), 21=791 (LC 12), 45=11962 (LC 46)							
FORCES							
(lb) - Maximum Compression/Maximum Tension							
TOP CHORD	1-2=0/24, 2-3=-13751/804, 3-4=-17677/1059, 4-6=-18994/1151, 6-7=-5812/482, 7-8=-3051/527, 8-9=-3048/525, 9-10=-3645/710, 10-11=-1646/1592, 11-12=-1646/1592, 12-13=-4646/432, 13-15=-18211/1130, 15-16=-17291/899, 2-45=-11768/721, 16-17=-9139/483						



NOTES



July 28, 2025

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinet.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1007 Serenity-Roof-B326 A CP TMB BDRM4 GRH I75198370
25070152-01	A05	Attic Girder	1	4	Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,


Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Sun Jul 27 23:59:21
ID:VIY0g5gMUgwQZRyxiBXYltzRA_fRfC?PsB70Hq3NSgPqnL8w3uITXbGKWrcDoi7J4zJC?f

Page: 2

- 4) Wind: ASCE 7-16; Vult=130mph (3-second gust)
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat.
II; Exp B; Enclosed; MWFRS (envelope) exterior zone;
cantilever left and right exposed ; end vertical left and
right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 5) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15
Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate
DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9;
Cs=1.00; Ct=1.10
- 6) Unbalanced snow loads have been considered for this
design.
- 7) This truss has been designed for greater of min roof live
load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on
overhangs non-concurrent with other live loads.
- 8) Provide adequate drainage to prevent water ponding.
- 9) All plates are MT20 plates unless otherwise indicated.
- 10) All plates are 2x4 MT20 unless otherwise indicated.
- 11) This truss has been designed for a 10.0 psf bottom
chord live load nonconcurrent with any other live loads.
- 12) * This truss has been designed for a live load of 20.0psf
on the bottom chord in all areas where a rectangle
3-06-00 tall by 2-00-00 wide will fit between the bottom
chord and any other members, with BCDL = 10.0psf.
- 13) Ceiling dead load (5.0 psf) on member(s). 6-48, 48-49,
49-50, 50-51, 51-52, 52-53, 13-53; Wall dead load
(5.0psf) on member(s).13-22, 6-40
- 14) Bottom chord live load (40.0 psf) and additional bottom
chord dead load (5.0 psf) applied only to room. 39-40,
37-39, 36-37, 34-36, 32-34, 31-32, 29-31, 28-29, 26-28,
23-26, 22-23
- 15) Bearings are assumed to be: , Joint 17 SP No.1 .
- 16) Provide mechanical connection (by others) of truss to
bearing plate capable of withstanding 5416 lb uplift at
joint 21.
- 17) LGT4-SDS3 Simpson Strong-Tie connectors
recommended to connect truss to bearing walls due to
UPLIFT at jt(s) 45. This connection is for uplift only and
does not consider lateral forces.
- 18) One H2.5A Simpson Strong-Tie connectors
recommended to connect truss to bearing walls due to
UPLIFT at jt(s) 17. This connection is for uplift only and
does not consider lateral forces.
- 19) Graphical purlin representation does not depict the size
or the orientation of the purlin along the top and/or
bottom chord.
- 20) This truss has large uplift reaction(s) from gravity load
case(s). Proper connection is required to secure truss
against upward movement at the bearings. Building
designer must provide for uplift reactions indicated.
- 21) LGT4 Hurricane ties must have four studs in line below
the truss.
- 22) Hanger(s) or other connection device(s) shall be
provided sufficient to support concentrated load(s) 608
lb down and 52 lb up at 28-8-4, and 9100 lb down and
774 lb up at 16-1-4 on bottom chord. The design/
selection of such connection device(s) is the
responsibility of others.
- 23) Attic room checked for L/360 deflection.

LOAD CASE(S) Standard

- 1) Dead + Snow (balanced): Lumber Increase=1.15, Plate
Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-2=-60, 2-7=-60, 7-12=-60, 12-16=-60,
17-45=-20, 22-40=-30, 6-48=-10, 48-49=-10,
46-49=-10, 46-50=-10, 50-51=-10, 51-52=-10,
52-53=-10, 13-53=-10
Drag: 13-22=-10, 40-47=-10, 6-47=-10
Concentrated Loads (lb)
Vert: 41=-4881 (F), 63=-326 (F)



July 28, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932


Job	Truss	Truss Type	Qty	Ply	1007 Serenity-Roof-B326 A CP TMB BDRM4 GRH I75198371
25070152-01	A06	Attic Girder	1	4	Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Sun Jul 27 23:59:22

Page: 1

ID:pGeZvt1?lwrjuiNEY_xH4fkzRAp7-RfC?PsB70Hq3NSgPqnL8w3uTXbGKwRCDoi7J4zJC?i



Job	Truss	Truss Type	Qty	Ply	1007 Serenity-Roof-B326 A CP TMB BDRM4 GRH I75198371
25070152-01	A06	Attic Girder	1	4	Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,


Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Sun Jul 27 23:59:22
ID:pGeZvt1?lwruINEY_xH4fkzRAp7-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?i

Page: 2

- 4) Wind: ASCE 7-16; Vult=130mph (3-second gust)
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat.
II; Exp B; Enclosed; MWFRS (envelope) exterior zone;
cantilever left and right exposed ; end vertical left and
right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 5) TCLK: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15
Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate
DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9;
Cs=1.00; Ct=1.10
- 6) Unbalanced snow loads have been considered for this
design.
- 7) This truss has been designed for greater of min roof live
load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on
overhangs non-concurrent with other live loads.
- 8) Provide adequate drainage to prevent water ponding.
- 9) All plates are MT20 plates unless otherwise indicated.
- 10) All plates are 2x4 MT20 unless otherwise indicated.
- 11) This truss has been designed for a 10.0 psf bottom
chord live load nonconcurrent with any other live loads.
- 12) * This truss has been designed for a live load of 20.0psf
on the bottom chord in all areas where a rectangle
3-06-00 tall by 2-00-00 wide will fit between the bottom
chord and any other members, with BCDL = 10.0psf.
- 13) Ceiling dead load (5.0 psf) on member(s). 6-48, 48-50,
50-51, 51-52, 52-53, 49-53, 13-49; Wall dead load
(5.0psf) on member(s).6-41, 13-23
- 14) Bottom chord live load (40.0 psf) and additional bottom
chord dead load (5.0 psf) applied only to room. 40-41,
38-40, 37-38, 35-37, 33-35, 32-33, 30-32, 28-30, 26-28,
24-26, 23-24
- 15) Refer to girder(s) for truss to truss connections.
- 16) Provide mechanical connection (by others) of truss to
bearing plate capable of withstanding 420 lb uplift at joint
18 and 5361 lb uplift at joint 22.
- 17) LGT4-SDS3 Simpson Strong-Tie connectors
recommended to connect truss to bearing walls due to
UPLIFT at jt(s) 46. This connection is for uplift only and
does not consider lateral forces.
- 18) Graphical purlin representation does not depict the size
or the orientation of the purlin along the top and/or
bottom chord.
- 19) This truss has large uplift reaction(s) from gravity load
case(s). Proper connection is required to secure truss
against upward movement at the bearings. Building
designer must provide for uplift reactions indicated.
- 20) LGT4 Hurricane ties must have four studs in line below
the truss.
- 21) Hanger(s) or other connection device(s) shall be
provided sufficient to support concentrated load(s) 9100
lb down and 774 lb up at 16-1-4 on bottom chord. The
design/selection of such connection device(s) is the
responsibility of others.
- 22) Attic room checked for L/360 deflection.

LOAD CASE(S) Standard

- 1) Dead + Snow (balanced): Lumber Increase=1.15, Plate
Increase=1.15
Uniform Loads (lb/ft)
Vert: 7-12=-60, 12-18=-60, 46-54=-20, 23-41=-30,
6-48=-10, 48-50=-10, 50-51=-10, 51-52=-10,
52-53=-10, 49-53=-10, 13-49=-10, 1-2=-60, 2-7=-60
Drag: 41-47=-10, 6-47=-10, 13-23=-10
Concentrated Loads (lb)
Vert: 42=-4881 (F)



July 28, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)


ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiteTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI 1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Components Association (www.sbcacomponents.com)



ENGINEERING BY
TRENCO
A MiteTek Affiliate

818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1007 Serenity-Roof-B326 A CP TMB BDRM4 GRH I75198372
25070152-01	A07	Attic	1	1	Job Reference (optional)


Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Sun Jul 27 23:59:23
ID:1d5INYb_SnpjqifH0e1reGzRBHO-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrcDoi7J4zJC?f

Page: 2

- 7) All plates are MT20 plates unless otherwise indicated.
- 8) All plates are 2x4 MT20 unless otherwise indicated.
- 9) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 10) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 11) Ceiling dead load (5.0 psf) on member(s). 5-44, 43-44, 43-45, 45-46, 46-47, 47-48, 12-48; Wall dead load (5.0psf) on member(s).5-38, 12-21
- 12) Bottom chord live load (40.0 psf) and additional bottom chord dead load (5.0 psf) applied only to room. 37-38, 35-37, 34-35, 32-34, 30-32, 29-30, 27-29, 26-27, 24-26, 22-24, 21-22
- 13) Refer to girder(s) for truss to truss connections.
- 14) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- 15) Attic room checked for L/360 deflection.

LOAD CASE(S) Standard



July 28, 2025


WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1007 Serenity-Roof-B326 A CP TMB BDRM4 GRH
25070152-01	A08	Attic	6	1	I75198373
Job Reference (optional)					



Job	Truss	Truss Type	Qty	Ply	1007 Serenity-Roof-B326 A CP TMB BDRM4 GRH I75198373
25070152-01	A08	Attic	6	1	Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Sun Jul 27 23:59:24
ID:1d5INYb_SnpjqiH0e1reGzRBHO-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrcDoi7J4zJC?f

Page: 2

- 8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 9) Ceiling dead load (5.0 psf) on member(s). 4-43, 42-43, 42-44, 44-45, 45-46, 46-47, 11-47; Wall dead load (5.0psf) on member(s). 4-37, 11-20
- 10) Bottom chord live load (40.0 psf) and additional bottom chord dead load (5.0 psf) applied only to room. 36-37, 34-36, 33-34, 31-33, 29-31, 28-29, 26-28, 25-26, 23-25, 21-23, 20-21
- 11) Refer to girder(s) for truss to truss connections.
- 12) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- 13) Attic room checked for L/360 deflection.

LOAD CASE(S) Standard



July 28, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1007 Serenity-Roof-B326 A CP TMB BDRM4 GRH
25070152-01	A09	Attic Supported Gable	1	1	I75198374
Job Reference (optional)					

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 E May 9 2024 Print: 8.730 E May 9 2024 MiTek Industries, Inc. Mon Jul 28 15:18:43

Page: 1

ID:8kdnaNvfrXy7X5iJovJ26tzRBB2-HBTEFDfBtCiv_XjL9FVUY?YAEHnlfB2mKtSyTW1h





Plate Offsets (X, Y): [7:0-2-6,Edge], [11:0-5-12,0-3-0], [16:0-5-12,0-3-0], [40:Edge,0-2-4], [46:0-3-0,0-3-0], [58:Edge,0-2-4], [72:Edge,0-4-6]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.44	Vert(LL)	-0.01	10	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.11	Vert(CT)	-0.01	10	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.65	Horz(CT)	0.02	28	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0											
Weight: 504 lb FT = 20%												

LUMBER		Max Uplift		TOP CHORD	
TOP CHORD	2x6 SP No.2	28=-48 (LC 14), 29=-99 (LC 15), 30=-29 (LC 15), 31=-47 (LC 15), 32=-41 (LC 15), 33=-44 (LC 15), 34=-44 (LC 15), 35=-45 (LC 15), 37=-49 (LC 15), 38=-132 (LC 40), 39=-46 (LC 10), 59=-13 (LC 10), 60=-127 (LC 40), 62=-50 (LC 14), 63=-45 (LC 14), 64=-43 (LC 14), 65=-44 (LC 14), 66=-37 (LC 14), 67=-76 (LC 14), 68=-20 (LC 15), 75=-48 (LC 14)		1-68=-88/57, 1-2=-63/38, 2-3=-65/112, 3-4=-77/174, 4-5=-88/222, 5-6=-100/267, 6-8=-120/313, 8-9=-135/359, 9-10=-115/375, 10-11=-903/328, 11-12=-2147/593, 12-13=-2147/593, 13-14=-2804/764, 14-15=-2132/593, 15-16=-2132/593, 16-17=-894/327, 17-18=-121/375, 18-19=-143/366, 19-20=-137/322, 20-22=-121/275, 22-23=-109/230, 23-24=-102/205, 24-25=-122/182, 25-26=-147/160, 26-27=-170/134, 27-28=-220/127	
BOT CHORD	2x4 SP No.2				
WEBS	2x4 SP No.3 *Except* 10-59,17-39:2x6 SP No.2, 72-17,72-10:2x4 SP No.2				
OTHERS	2x4 SP No.3				
BRACING		Max Grav			
TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (4-1-8 max.): 11-16.				
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 48-51.				
WEBS	1 Row at midpt 10-58, 17-40, 18-38, 19-37, 9-60, 8-62				
JOINTS	1 Brace at Jt(s): 71, 72, 73, 74, 55, 52, 47, 44				
REACTIONS					
(lb/size)	28=123/53-6-0, 29=235/53-6-0, 30=147/53-6-0, 31=165/53-6-0, 32=149/53-6-0, 33=161/53-6-0, 34=160/53-6-0, 35=169/53-6-0, 37=126/53-6-0, 38=22/53-6-0, 39=916/53-6-0, 42=156/53-6-0, 45=138/53-6-0, 48=121/53-6-0, 51=121/53-6-0, 53=135/53-6-0, 56=149/53-6-0, 59=930/53-6-0, 60=13/53-6-0, 62=142/53-6-0, 63=170/53-6-0, 64=160/53-6-0, 65=157/53-6-0, 66=163/53-6-0, 67=152/53-6-0, 68=115/53-6-0, 75=123/53-6-0				
Max Horiz	68=-221 (LC 15)				

FORCES

(lb) - Maximum Compression/Maximum Tension



July 28,2025

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1007 Serenity-Roof-B326 A CP TMB BDRM4 GRH I75198374
25070152-01	A09	Attic Supported Gable	1	1	Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 E May 9 2024 Print: 8.730 E May 9 2024 MiTek Industries, Inc. Mon Jul 28 15:18:43


Page: 2

ID:8kdnANvfrXy7X5iJovJ26tzRBB2-HBTEFDIFbBiciv_XjL9FVUY?YAEHnlfbf2mKiSyTW1h

BOT CHORD	67-68=-96/212, 66-67=-96/212, 65-66=-96/212, 64-65=-96/212, 63-64=-96/212, 62-63=-96/212, 60-62=-96/212, 59-60=-96/212, 56-59=-104/213, 53-56=-52/140, 51-53=-32/126, 48-51=-56/104, 45-48=-32/125, 42-45=-48/139, 39-42=-82/200, 38-39=-87/212, 37-38=-87/212, 35-37=-87/212, 34-35=-87/212, 33-34=-87/212, 32-33=-87/212, 31-32=-87/212, 30-31=-87/212, 29-30=-87/212, 28-29=-87/212, 57-58=-11/91, 55-57=-11/91, 54-55=-30/114, 52-54=-30/114, 50-52=-39/108, 49-50=-39/108, 47-49=-39/108, 44-47=-31/115, 41-44=-11/84, 40-41=-11/84	12) Bottom chord live load (40.0 psf) and additional bottom chord dead load (5.0 psf) applied only to room. 57-58, 55-57, 54-55, 52-54, 50-52, 49-50, 47-49, 46-47, 44-46, 41-44, 40-41 13) N/A 14) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord. 15) Attic room checked for L/360 deflection.
WEBS	5-64=-191/76, 25-31=-129/79, 26-30=-116/94, 27-29=-189/180, 58-59=-1090/31, 10-58=-1096/109, 39-40=-1083/62, 17-40=-1093/151, 18-38=-74/171, 19-37=-168/77, 20-35=-195/80, 22-34=-179/77, 23-33=-131/78, 24-32=-118/72, 9-60=-84/167, 8-62=-183/80, 6-63=-201/81, 4-65=-142/83, 3-66=-126/114, 2-67=-134/143, 56-58=-91/14, 56-57=-203/0, 41-42=-202/0, 45-46=-181/0, 53-54=-181/0, 48-49=-218/0, 50-51=-218/0, 10-69=-39/644, 69-71=-37/638, 71-74=-441/2725, 73-74=-447/2775, 70-73=-42/627, 17-70=-44/635, 11-69=-24/19, 16-70=-27/20, 12-71=-256/67, 13-72=-1/25, 15-73=-236/67, 14-74=-22/53, 11-71=-325/1558, 13-71=-654/189, 13-74=-65/152, 14-73=-715/182, 16-73=-327/1553, 55-56=-118/22, 53-55=-120/0, 52-53=-121/0, 51-52=-100/0, 47-48=-100/0, 45-47=-118/0, 44-45=-125/0, 42-44=-112/20, 40-42=-103/10	LOAD CASE(S) Standard

NOTES

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TC DL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Corner(3E) 0-1-12 to 5-5-15, Exterior(2N) 5-5-15 to 12-3-13, Corner(3R) 12-3-13 to 23-3-2, Exterior(2N) 23-3-2 to 25-10-14, Corner(3R) 25-10-14 to 36-10-3, Exterior(2N) 36-10-3 to 48-1-13, Corner(3E) 48-1-13 to 53-6-0 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 4) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- 5) Unbalanced snow loads have been considered for this design.
- 6) Provide adequate drainage to prevent water ponding.
- 7) All plates are 2x4 MT20 unless otherwise indicated.
- 8) Gable studs spaced at 2-0-0 oc.
- 9) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 10) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- 11) Ceiling dead load (5.0 psf) on member(s). 10-69, 69-71, 71-72, 72-74, 73-74, 70-73, 17-70; Wall dead load (5.0psf) on member(s). 10-58, 17-40



July 28, 2025


WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932

Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Sun Jul 27 23:59:25 Page: 1
ID:Nseaq6A9EjNfXKX1O6vXnly7LSU-RfC?PsB70Hq3NSqPqnL8w3ulTXbGKWrcDoi7J4zJC?f



NUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3 *Except* 17-15:2x6 SP No.2, 6-20:2x4 SP No.2
OTHERS 2x4 SP No.3
SLIDER Left 2x6 SP No.2 -- 1-6-0

BRACING
TOP CHORD Structural wood sheathing directly applied or 5-5-4 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
JOINTS 1 Brace at Jt(s): 24, 25, 27

REACTIONS (size) 2=0-5-8, 17=0-3-8, 21=0-5-8
Max Horiz 2=265 (LC 13)
Max Uplift 2=-50 (LC 14), 21=-225 (LC 15)
Max Grav 2=853 (LC 21), 17=446 (LC 22), 21=753 (LC 22)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/34, 2-4=-911/79, 4-6=-760/90, 6-7=-332/144, 7-8=-315/186, 8-9=-280/153, 9-11=-301/119, 11-12=-323/75, 12-13=-203/16, 13-14=-293/12, 14-15=-345/1, 15-16=0/42, 15-17=-343/0
BOT CHORD 2-23=-214/696, 21-23=-41/499, 20-21=-116/17, 19-20=-37/231, 18-19=-37/231, 17-18=-37/231
WEBS 4-23=-237/181, 21-28=-541/345, 6-26=-463/113, 25-26=-468/121, 24-25=-413/70, 24-27=-407/54, 27-28=-419/70, 20-28=-471/86, 23-24=-69/89, 6-23=0/345, 8-25=-128/164, 7-26=-31/42, 9-24=-184/31, 11-27=-81/63, 12-28=-382/221, 13-19=-20/49, 14-18=-65/82

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust)
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior (1) 2-1-8 to 8-7-0, Exterior(2R) 8-7-0 to 14-7-0, Interior (1) 14-7-0 to 21-0-8, Exterior(2E) 21-0-8 to 24-0-8 zone; cantilever left and right exposed ; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 4) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- 5) Unbalanced snow loads have been considered for this design.
- 6) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
- 7) All plates are 2x4 MT20 unless otherwise indicated.
- 8) Gable studs spaced at 2-0-0 oc.
- 9) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 10) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- 11) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 2 and 21. This connection is for uplift only and does not consider lateral forces.

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITER REFERENCE PAGE MIT-7473 Rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only on parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinet.org) and **BCSI Building Component Safety Information** available from the Structural Building Components Association (www.sbcacompnents.com)


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1007 Serenity-Roof-B326 A CP TMB BDRM4 GRH
25070152-01	B02	Common Girder	1	2	I75198376
Job Reference (optional)					

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 E May 9 2024 Print: 8.730 E May 9 2024 MiTek Industries, Inc. Mon Jul 28 15:19:50
ID:IFFKd9_s5HOVK9vBFwqTAGzRAMn-HGaxXTXva4tzsMBcidOCFqMdoaoi?XAgEdExGVytW0d

Page: 1



Scale = 1:70.7

Plate Offsets (X, Y): [1:Edge,0-2-13], [3:0-0-8,0-1-8], [11:0-8-0,0-7-12], [12:0-8-0,0-2-8], [13:0-8-0,0-3-0]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.35	Vert(LL)	-0.10	12-13	>999	240	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.38	Vert(CT)	-0.18	12-13	>999	180	
TCDL	10.0	Rep Stress Incr	NO	WB	0.76	Horz(CT)	0.02	9	n/a	n/a	
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH							
BCDL	10.0										
Weight: 481 lb FT = 20%											

LUMBER

TOP CHORD 2x6 SP No.2
BOT CHORD 2x10 SP 2400F 2.0E
WEBS 2x4 SP No.2
WEDGE Left: 2x6 SP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 4-5-3 oc purlins.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

WEBS 1 Row at midpt 3-11, 5-9

REACTIONS (lb/size) 1=7991/0-5-8, 7=593/0-7-12, 9=11455/0-5-8
Max Horiz 1=227 (LC 8)
Max Uplift 7=405 (LC 12)
Max Grav 1=9397 (LC 5), 7=620 (LC 19), 9=12966 (LC 6)

FORCES

(lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-11144/0, 2-3=-8435/0, 3-4=-5225/0, 4-5=-5166/0, 5-6=-59/184, 6-7=-108/621
BOT CHORD 1-13=0/8447, 12-13=0/8447, 11-12=0/6474, 9-11=0/1933, 8-9=-205/45, 7-8=-401/17
WEBS 2-13=0/3750, 2-12=-2886/0, 3-12=0/6202, 3-11=-5013/0, 4-11=0/6225, 5-11=0/4395, 5-9=-7460/0, 6-9=-199/506, 6-8=-708/0

NOTES


- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
Bottom chords connected as follows: 2x10 - 4 rows staggered at 0-4-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc, Except member 2-13 2x4 - 1 row at 0-3-0 oc, member 3-12 2x4 - 1 row at 0-6-0 oc.

- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- One RT7 MiTek connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 7. This connection is for uplift only and does not consider lateral forces.

- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 2330 lb down at 2-0-0, 2330 lb down at 4-0-0, 2330 lb down at 6-0-0, 2330 lb down at 8-0-0, 2330 lb down at 10-0-0, 2266 lb down at 12-0-0, 2258 lb down at 14-0-0, 2257 lb down at 15-10-0, 811 lb down and 182 lb up at 17-10-0, and 811 lb down and 182 lb up at 19-10-0, and 918 lb down and 203 lb up at 21-10-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard

- Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-4=-60, 4-7=-60, 14-17=-20
Concentrated Loads (lb)
Vert: 10=-1959 (B), 13=-1967 (B), 12=-1967 (B), 8=-811 (B), 21=-1967 (B), 22=-1967 (B), 23=-1967 (B), 24=-1959 (B), 25=-1959 (B), 26=-811 (B), 27=-852 (B)



July 28, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1007 Serenity-Roof-B326 A CP TMB BDRM4 GRH I75198377
25070152-01	C01	Half Hip	4	1	Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Sun Jul 27 23:59:25
ID:Je5w06f8goBW?T4xbCQ60Kyfk?K-RfC?PsB70Hq3NSgPqnL8w3uITxbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:71.5

Plate Offsets (X, Y): [2:0-3-1,0-0-1], [8:0-1-12,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.83	Vert(LL)	-0.08	8-9	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.62	Vert(CT)	-0.14	8-9	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.79	Horz(CT)	0.03	8	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 148 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
WEBS	2x4 SP No.3 *Except* 7-8:2x4 SP No.2
OTHERS	2x6 SP No.2
SLIDER	Left 2x4 SP No.3 -- 1-6-0

BRACING

TOP CHORD	Structural wood sheathing directly applied or 4-8-11 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	1 Row at midpt 7-8, 6-8

REACTIONS

(size)	2=0-5-8, 8=0-5-8
Max Horiz	2=387 (LC 14)
Max Uplift	2=-49 (LC 14), 8=-342 (LC 14)
Max Grav	2=954 (LC 5), 8=1731 (LC 21)

FORCES

(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=0/23, 2-4=-1437/30, 4-6=-824/0, 6-7=-166/102, 7-8=-270/93
BOT CHORD	2-11=-399/1321, 9-11=-320/1321, 8-9=-159/721
WEBS	4-11=0/263, 4-9=-691/185, 6-9=0/637, 6-8=-1026/227


NOTES

- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior (1) 2-1-8 to 17-4-4, Exterior(2E) 17-4-4 to 20-4-4 zone; end vertical left exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10

- Unbalanced snow loads have been considered for this design.
- This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
- All plates are 3x5 MT20 unless otherwise indicated.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 8 and 2. This connection is for uplift only and does not consider lateral forces.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 752 lb down and 128 lb up at 20-7-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard

- Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-7=-60, 8-13=-20
Concentrated Loads (lb)
Vert: 8=-747



July 28, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932


Job	Truss	Truss Type	Qty	Ply	1007 Serenity-Roof-B326 A CP TMB BDRM4 GRH I75198378
25070152-01	C02	Half Hip	1	1	Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Sun Jul 27 23:59:25

Page: 1

ID:EGq646Pbf2EXC6nWUJzpaijfwU-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWRCDoi7J4zJC?f



Scale = 1:71.3

Plate Offsets (X, Y): [1:0-5-1,Edge], [7:0-1-12,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.82	Vert(LL)	-0.08	7-8	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.63	Vert(CT)	-0.14	7-8	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.75	Horz(CT)	0.03	7	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 146 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
WEBS	2x4 SP No.3 *Except* 6-7:2x4 SP No.2
OTHERS	2x6 SP No.2
SLIDER	Left 2x4 SP No.3 -- 1-6-0

BRACING

TOP CHORD	Structural wood sheathing directly applied or 4-7-1 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	1 Row at midpt 6-7, 5-7

REACTIONS

(size)	1=0-3-8, 7=0-5-8
Max Horiz	1=370 (LC 14)
Max Uplift	1=-30 (LC 14), 7=-342 (LC 14)
Max Grav	1=900 (LC 5), 7=1714 (LC 20)

FORCES

(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-3=-1401/30, 3-5=-812/0, 5-6=-162/100, 6-7=-265/93
BOT CHORD	1-10=-405/1286, 8-10=-319/1286, 7-8=-159/716
WEBS	3-10=0/254, 3-8=-658/185, 5-8=0/624, 5-7=-1018/227


NOTES

- Wind: ASCE 7-16; Vult=130mph (3-second gust)
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-2-0 to 3-2-0, Interior (1) 3-2-0 to 17-4-4, Exterior(2E) 17-4-4 to 20-4-4 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10

- Unbalanced snow loads have been considered for this design.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 7 and 1. This connection is for uplift only and does not consider lateral forces.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 752 lb down and 129 lb up at 20-7-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard

- Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-6=-60, 7-12=-20
Concentrated Loads (lb)
Vert: 7=-747



July 28, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1007 Serenity-Roof-B326 A CP TMB BDRM4 GRH I75198379
25070152-01	D01	Common Supported Gable	1	1	Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Sun Jul 27 23:59:25
ID:8F2D?hHuvW?rb9K6OMb_YzRQRf-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:56.9

Plate Offsets (X, Y): [7:0-2-8, Edge]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.21	Vert(LL)	n/a	-	n/a	999	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.12	Vert(CT)	n/a	-	n/a	999	
TCDL	10.0	Rep Stress Incr	YES	WB	0.20	Horz(CT)	0.00	14	n/a	n/a	
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MR							
BCDL	10.0										
Weight: 127 lb FT = 20%											

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
WEBS	2x4 SP No.3
OTHERS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS	(size)	14=18-6-0, 15=18-6-0, 17=18-6-0, 18=18-6-0, 19=18-6-0, 20=18-6-0, 21=18-6-0, 22=18-6-0, 23=18-6-0, 24=18-6-0
	Max Horiz	24=225 (LC 12)
	Max Uplift	14=50 (LC 11), 15=163 (LC 15), 17=47 (LC 15), 18=116 (LC 15), 21=115 (LC 14), 22=46 (LC 14), 23=168 (LC 14), 24=69 (LC 10)
	Max Grav	14=190 (LC 25), 15=221 (LC 26), 17=172 (LC 22), 18=253 (LC 22), 19=224 (LC 22), 20=224 (LC 21), 21=253 (LC 21), 22=172 (LC 21), 23=228 (LC 25), 24=205 (LC 26)

FORCES

(lb) - Maximum Compression/Maximum Tension

TOP CHORD	2-24=-168/63, 1-2=0/39, 2-3=-164/140, 3-4=-105/90, 4-5=-92/118, 5-6=-116/235, 6-7=-94/171, 7-8=-94/171, 8-9=-116/235, 9-10=-77/117, 10-11=-90/72, 11-12=-152/117, 12-13=0/39, 12-14=-155/47
BOT CHORD	23-24=-106/187, 22-23=-106/187, 21-22=-106/187, 20-21=-106/187, 19-20=-106/187, 18-19=-106/187, 17-18=-106/187, 15-17=-106/187, 14-15=-106/187

WEBS

6-20=-185/8, 8-19=-185/7, 5-21=-213/162, 4-22=-142/93, 3-23=-174/160, 9-18=-213/163, 10-17=-143/91, 11-15=-168/168


NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Corner(3E) -0-10-8 to 2-3-4, Exterior(2N) 2-3-4 to 6-3-0, Corner(3R) 6-3-0 to 12-2-12, Exterior(2N) 12-2-12 to 16-2-12, Corner(3E) 16-2-12 to 19-4-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.

12) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.

13) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 69 lb uplift at joint 24, 50 lb uplift at joint 14, 115 lb uplift at joint 21, 46 lb uplift at joint 22, 168 lb uplift at joint 23, 116 lb uplift at joint 18, 47 lb uplift at joint 17 and 163 lb uplift at joint 15.

LOAD CASE(S) Standard



July 28, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1007 Serenity-Roof-B326 A CP TMB BDRM4 GRH I75198380
25070152-01	D02	Common Girder	1	2	Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Sun Jul 27 23:59:26
ID:ahvaep5BsMwascBuTkn6buzRAib-RfC?PsB70Hq3NSgPqnLw3uITxbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:59.2

Plate Offsets (X, Y): [1:0-8-0,0-9-4], [3:0-5-0,0-5-12], [5:0-0-8,0-2-0], [10:0-3-12,0-8-5], [11:0-5-12,0-1-8], [12:0-8-0,0-9-0], [13:0-9-12,0-6-0], [14:0-9-8,0-3-8], [15:0-3-8,0-9-8]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.43	Vert(LL)	-0.10	14-15	>999	240	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.57	Vert(CT)	-0.17	14-15	>999	180	
TCDL	10.0	Rep Stress Incr	NO	WB	0.92	Horz(CT)	0.04	10	n/a	n/a	
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH							
BCDL	10.0										
Weight: 487 lb FT = 20%											

LUMBER

TOP CHORD 2x8 SP 2400F 2.0E
BOT CHORD 2x12 SP 2400F 2.0E
WEBS 2x4 SP No.3 *Except* 13-6:2x4 SP No.1,
5-14:2x4 SP No.2
SLIDER Left 2x4 SP No.3 -- 1-6-0, Right 2x4 SP No.3
-- 1-6-0

BRACING

TOP CHORD Structural wood sheathing directly applied or
5-11-12 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc
bracing.

REACTIONS (size) 1=(0-5-8 + bearing block), (req.
0-6-2), 10=0-5-8
Max Horiz 1=-176 (LC 10)
Max Grav 1=14865 (LC 21), 10=10712 (LC 6)

FORCES


(lb) - Maximum Compression/Maximum
Tension
TOP CHORD 1-3=-15578/0, 3-4=-14258/0, 4-5=-12125/0,
5-6=-9492/0, 6-7=-9463/0, 7-8=-11050/0,
8-10=-12158/0
BOT CHORD 1-16=0/10988, 15-16=0/10988,
14-15=0/11862, 13-14=0/9117, 11-13=0/9123,
10-11=0/9123
WEBS 6-13=0/10728, 7-13=-1571/0, 7-12=0/2918,
8-12=-1103/0, 8-11=0/1625, 4-14=-4425/101,
4-15=-208/3373, 5-14=0/5105, 5-13=-3189/0,
3-16=-421/1446, 3-15=0/2222

NOTES

- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x8 - 2 rows staggered at 0-9-0 oc.
Bottom chords connected as follows: 2x12 - 6 rows staggered at 0-5-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc, Except member 5-14 2x4 - 1 row at 0-5-0 oc, member 3-16 2x4 - 2 rows staggered at 0-2-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- 2x12 SP 2400F 2.0E bearing block 12" long at jt. 1 attached to each face with 6 rows of 10d (0.131"x3") nails spaced 3" o.c. 24 Total fasteners per block. Bearing is assumed to be SP 2400F 2.0E.
- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Use Simpson Strong-Tie HTU210 (32-10dx1 1/2 Girder, 14-10dx1 1/2 Truss, Single Ply Girder) or equivalent at 4-4-12 from the left end to connect truss(es) to back face of bottom chord.
- Use Simpson Strong-Tie HTU28 (20-16d Girder, 26-10dx1 1/2 Truss, Single Ply Girder) or equivalent spaced at 2-0-0 oc max. starting at 6-4-12 from the left end to 16-4-12 to connect truss(es) to back face of bottom chord.
- Fill all nail holes where hanger is in contact with lumber.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 8867 lb down and 535 lb up at 2-7-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S)

- Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-6=-60, 6-10=-60, 17-21=-20
Concentrated Loads (lb)



July 28,2025

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1007 Serenity-Roof-B326 A CP TMB BDRM4 GRH I75198380
25070152-01	D02	Common Girder	1	2	Job Reference (optional)

Vert: 14=-1893 (B), 16=-5499 (B), 27=-1897 (B),
28=-1893 (B), 29=-1893 (B), 30=-1893 (B), 31=-1893 (B), 32=-1893 (B)




July 28,2025

Job	Truss	Truss Type	Qty	Ply	1007 Serenity-Roof-B326 A CP TMB BDRM4 GRH I75198381
25070152-01	E01	Common Supported Gable	1	1	Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Sun Jul 27 23:59:26
ID:onyrlCEMWITAUsFyYbXALJy7LR6-RfC?PsB70Hq3NSgPqnL8w3uTXbGKwRCDoi7J4zJC?i

Page: 1



Scale = 1:53.1

Plate Offsets (X, Y): [8:0-2-8,Edge]

Loading	(psf)	Spacing	1-11-4	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.18	Vert(LL)	n/a	-	n/a	999	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.11	Vert(CT)	n/a	-	n/a	999	
TCDL	10.0	Rep Stress Incr	YES	WB	0.15	Horz(CT)	0.00	16	n/a	n/a	
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MR							
BCDL	10.0										
Weight: 130 lb FT = 20%											

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
WEBS	2x4 SP No.3
OTHERS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS (size)	16=17-6-0, 17=17-6-0, 18=17-6-0, 19=17-6-0, 21=17-6-0, 22=17-6-0, 23=17-6-0, 24=17-6-0, 25=17-6-0, 26=17-6-0, 27=17-6-0, 28=17-6-0
Max Horiz	28=209 (LC 13)
Max Uplift	16=135 (LC 13), 17=215 (LC 15), 18=70 (LC 15), 19=77 (LC 15), 21=84 (LC 15), 24=83 (LC 14), 25=77 (LC 14), 26=69 (LC 14), 27=231 (LC 14), 28=187 (LC 12)
Max Grav	16=226 (LC 15), 17=200 (LC 13), 18=170 (LC 31), 19=206 (LC 22), 21=214 (LC 22), 22=136 (LC 22), 23=136 (LC 21), 24=214 (LC 21), 25=206 (LC 21), 26=169 (LC 25), 27=233 (LC 12), 28=261 (LC 11)

FORCES

(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	2-28=-168/112, 1-2=0/38, 2-3=-204/166, 3-4=-116/115, 4-5=-92/94, 5-6=-76/160, 6-7=-104/251, 7-8=-76/166, 8-9=-76/166, 9-10=-104/251, 10-11=-72/160, 11-12=-69/73, 12-13=-90/87, 13-14=-185/126, 14-15=0/38, 14-16=-142/80

BOT CHORD	27-28=-98/172, 26-27=-98/172, 25-26=-98/172, 24-25=-98/172, 23-24=-98/172, 22-23=-98/172, 21-22=-98/172, 19-21=-98/172, 18-19=-98/172, 17-18=-98/172, 16-17=-98/172
WEBS	7-23=-141/22, 9-22=-141/22, 6-24=-181/127, 5-25=-167/114, 4-26=-150/120, 3-27=-124/148, 10-21=-181/127, 11-19=-167/114, 12-18=-150/120, 13-17=-111/144

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Corner(3E) -0-10-8 to 2-1-8, Exterior(2N) 2-1-8 to 5-9-0, Corner(3R) 5-9-0 to 11-9-0, Exterior(2N) 11-9-0 to 15-4-8, Corner(3E) 15-4-8 to 18-4-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
- All plates are 2x4 MT20 unless otherwise indicated.

- Gable requires continuous bottom chord bearing.
- Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 187 lb uplift at joint 28, 135 lb uplift at joint 16, 83 lb uplift at joint 24, 77 lb uplift at joint 25, 69 lb uplift at joint 26, 231 lb uplift at joint 27, 84 lb uplift at joint 21, 77 lb uplift at joint 19, 70 lb uplift at joint 18 and 215 lb uplift at joint 17.

LOAD CASE(S) Standard



July 28, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1007 Serenity-Roof-B326 A CP TMB BDRM4 GRH I75198382
25070152-01	G01	Monopitch	5	1	Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Sun Jul 27 23:59:26
ID: PdAAD85_ICJN?UaWrZnF5zRQu2-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:64.6

Plate Offsets (X, Y): [2:0-2-0,0-1-8], [3:0-4-0,0-3-4]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.95	Vert(LL)	-0.12	7-8	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.67	Vert(CT)	-0.20	7-8	>923	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.39	Horz(CT)	-0.01	7	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 106 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.1 *Except* 1-3:2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3 *Except* 4-7:2x4 SP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or
2-2-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc
bracing.
WEBS 1 Row at midpt 4-7, 3-7

REACTIONS

(size) 7= Mechanical, 9=0-5-8
Max Horiz 9=273 (LC 14)
Max Uplift 7=221 (LC 14)
Max Grav 7=831 (LC 5), 9=754 (LC 5)

FORCES

(lb) - Maximum Compression/Maximum
Tension

TOP CHORD 1-2=0/27, 2-4=-677/119, 4-5=-12/0,
4-7=-328/122, 2-9=-655/84

BOT CHORD 8-9=-334/218, 7-8=-195/603, 6-7=0/0


WEBS 3-8=0/313, 3-7=-768/250, 2-8=0/486

NOTES

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust)
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat.
II; Exp B; Enclosed; MWFRS (envelope) exterior zone
and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior (1) 2-1-8
to 12-11-8, Exterior(2E) 12-11-8 to 15-11-8 zone;
cantilever left and right exposed ; end vertical left
exposed;C-C for members and forces & MWFRS for
reactions shown; Lumber DOL=1.60 plate grip
DOL=1.60
- 2) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15
Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate
DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9;
Cs=1.00; Ct=1.10
- 3) Unbalanced snow loads have been considered for this
design.

- 4) This truss has been designed for greater of min roof live
load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on
overhangs non-concurrent with other live loads.
- 5) This truss has been designed for a 10.0 psf bottom
chord live load nonconcurrent with any other live loads.
- 6) * This truss has been designed for a live load of 20.0psf
on the bottom chord in all areas where a rectangle
3-06-00 tall by 2-00-00 wide will fit between the bottom
chord and any other members, with BCDL = 10.0psf.
- 7) Refer to girder(s) for truss to truss connections.
- 8) Provide mechanical connection (by others) of truss to
bearing plate capable of withstanding 221 lb uplift at joint
7.

LOAD CASE(S) Standard



July 28, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1007 Serenity-Roof-B326 A CP TMB BDRM4 GRH I75198383
25070152-01	H01	Monopitch Supported Gable	2	1	Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Sun Jul 27 23:59:26
ID:kX6Xm09JsM8Rk_RkgNonK3zRRGV-RfC?PsB70Hq3NSgPqnL8w3uTXbGKwRCDoi7J4zJC?i

Page: 1



Scale = 1:43.9

Plate Offsets (X, Y): [2:Edge,0-0-14], [2:0-2-5,Edge], [10:0-0-8,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.99	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.36	Vert(CT)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.26	Horz(CT)	-0.08	17	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 68 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3 *Except* 8-12:2x4 SP No.2
OTHERS 2x4 SP No.3
WEDGE Left: 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals. Except: 9-5-0 oc bracing: 12-17
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

JOINTS 1 Brace at Jt(s): 18
REACTIONS (size) 2=10-1-0, 12=10-1-0, 13=10-1-0, 14=10-1-0, 15=10-1-0, 16=10-1-0, 17=10-1-0
Max Horiz 2=180 (LC 10)
Max Uplift 2=48 (LC 21), 12=72 (LC 21), 13=9 (LC 10), 14=41 (LC 14), 15=26 (LC 10), 16=98 (LC 14), 17=271 (LC 10)
Max Grav 2=123 (LC 14), 12=39 (LC 10), 13=129 (LC 1), 14=172 (LC 21), 15=158 (LC 1), 16=217 (LC 21), 17=875 (LC 21)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/17, 2-3=-710/428, 3-4=-650/422, 4-5=-606/425, 5-7=-544/407, 7-8=-542/476, 8-9=-633/630, 9-10=-632/697, 10-11=-45/0, 12-17=0/0, 8-17=-364/285
BOT CHORD 2-16=-383/370, 15-16=-383/370, 14-15=-383/370, 13-14=-383/370, 12-13=-383/370


WEBS 3-16=-145/179, 4-15=-125/117, 5-14=-168/172, 7-13=-33/56, 17-18=-793/656, 10-18=-801/669, 9-18=-21/26

NOTES

- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Corner(3E) -0-10-8 to 2-0-0, Exterior(2N) 2-0-0 to 16-0-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Bearing at joint(s) 17 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.

- 11) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 72 lb uplift at joint 12.
- 12) N/A

13) Non Standard bearing condition. Review required.
LOAD CASE(S) Standard



July 28, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1007 Serenity-Roof-B326 A CP TMB BDRM4 GRH I75198384
25070152-01	H02	Monopitch	6	1	Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Sun Jul 27 23:59:26
ID:nLPVeuW3K4TytrtY3ILLguzRRHK-RfC?PsB70Hq3NSgPqnL8w3uITxbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:48.2

Plate Offsets (X, Y): [2:Edge,0-0-14], [2:0-2-5,Edge], [6:0-0-8,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.78	Vert(LL)	0.03	9-10	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.36	Vert(CT)	-0.05	9-10	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.50	Horz(CT)	0.01	9	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 66 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3 *Except* 5-9:2x4 SP No.1
WEDGE Left: 2x4 SP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
Except:
5-3-0 oc bracing: 9-11
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(size) 2=0-3-0, 9=0-5-8
Max Horiz 2=207 (LC 10)
Max Uplift 2=-100 (LC 10), 9=-371 (LC 10)
Max Grav 2=377 (LC 1), 9=1084 (LC 21)

FORCES


(lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/17, 2-3=-368/82, 3-5=-393/465,
5-6=-456/707, 6-7=-45/0, 9-11=-847/467,
5-11=-321/163
BOT CHORD 2-10=-230/338, 9-10=-230/338, 8-9=0/0
WEBS 3-10=-124/211, 3-9=-614/478, 6-11=-811/468

NOTES

- Wind: ASCE 7-16; Vult=130mph (3-second gust)
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat.
II; Exp B; Enclosed; MWFRS (envelope) exterior zone
and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior (1) 2-1-8
to 16-0-0 zone; cantilever left exposed ; porch left and
right exposed;C-C for members and forces & MWFRS
for reactions shown; Lumber DOL=1.60 plate grip
DOL=1.60
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15
Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate
DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9;
Cs=1.00; Ct=1.10

- Unbalanced snow loads have been considered for this design.
- This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 9 and 2. This connection is for uplift only and does not consider lateral forces.

LOAD CASE(S) Standard



July 28,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job 25070152-01	Truss J01	Truss Type Common	Qty 5	Ply 1	1007 Serenity-Roof-B326 A CP TMB BDRM4 GRH I75198385 Job Reference (optional)
--------------------	--------------	----------------------	----------	----------	---

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Sun Jul 27 23:59:26
ID:yPXMlbyKekkHSiWSiZLGInzRR58-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrcDoi7J4zJC?f

Page: 1



Scale = 1:40.3

Plate Offsets (X, Y): [5:0-3-8,Edge], [6:0-4-0,0-3-0]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.38	Vert(LL)	-0.09	6-9	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.64	Vert(CT)	-0.19	6-9	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.21	Horz(CT)	0.02	5	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0											
Weight: 75 lb											FT = 20%	

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3
WEDGE Right: 2x4 SP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 5-1-15 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 1=0-5-8, 5=0-5-8
Max Horiz 1=71 (LC 14)
Max Uplift 1=-66 (LC 14), 5=-64 (LC 15)
Max Grav 1=747 (LC 20), 5=746 (LC 21)

FORCES


(lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-1256/309, 2-3=-879/232, 3-4=-871/231,
4-5=-1211/300
BOT CHORD 1-5=-221/1083
WEBS 3-6=-51/474, 4-6=-401/159, 2-6=-439/174

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust)
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-0-0 to 3-0-0, Interior (1) 3-0-0 to 5-7-8, Exterior(2R) 5-7-8 to 11-7-8, Interior (1) 11-7-8 to 14-0-8, Exterior(2E) 14-0-8 to 17-0-8 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.

- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Bearings are assumed to be: , Joint 5 SP No.2 .
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 66 lb uplift at joint 1.
- One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 5. This connection is for uplift only and does not consider lateral forces.

LOAD CASE(S) Standard



July 28,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1007 Serenity-Roof-B326 A CP TMB BDRM4 GRH I75198386
25070152-01	PBA	Piggyback	2	1	Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Sun Jul 27 23:59:26
ID:RPY8AW_GFKlcY3mFoYebvHzRQqK-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1



Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.08	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.04	Vert(CT)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.04	Horz(CT)	0.00	8	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 52 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size)
2=11-10-14, 8=11-10-14,
10=11-10-14, 11=11-10-14,
12=11-10-14, 13=11-10-14,
14=11-10-14
Max Horiz 2=52 (LC 18)
Max Uplift 2=-9 (LC 15), 8=-12 (LC 15),
10=-45 (LC 15), 11=-47 (LC 15),
13=-47 (LC 14), 14=-46 (LC 14)
Max Grav 2=125 (LC 21), 8=125 (LC 22),
10=240 (LC 22), 11=243 (LC 22),
12=143 (LC 22), 13=243 (LC 21),
14=240 (LC 21)


FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/17, 2-3=-46/33, 3-4=-56/49,
4-5=-64/107, 5-6=-64/107, 6-7=-56/42,
7-8=-30/26, 8-9=0/17
BOT CHORD 2-14=-9/58, 13-14=-9/58, 12-13=-9/58,
11-12=-9/58, 10-11=-9/58, 8-10=-9/58
WEBS 5-12=-102/0, 4-13=-207/121, 3-14=-183/88,
6-11=-207/121, 7-10=-183/88

NOTES
1) Unbalanced roof live loads have been considered for this design.

- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-4-3 to 3-4-3, Interior (1) 3-4-3 to 3-11-0, Exterior(2R) 3-11-0 to 9-11-0, Interior (1) 9-11-0 to 10-5-13, Exterior(2E) 10-5-13 to 13-5-13 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- N/A

LOAD CASE(S) Standard

- See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.



July 28, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1007 Serenity-Roof-B326 A CP TMB BDRM4 GRH 175198387
25070152-01	PBA1	Piggyback	18	1	Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Sun Jul 27 23:59:27
ID:Cx19sF4HMnJTVINoGDnTDzzRQqC-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:31.5

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.28	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.12	Vert(CT)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.07	Horz(CT)	0.00	15	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0											
Weight: 47 lb											FT = 20%	

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
OTHERS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(size)	2=11-10-14, 6=11-10-14, 8=11-10-14, 9=11-10-14, 10=11-10-14
Max Horiz	2=52 (LC 18)
Max Uplift	2=-11 (LC 15), 6=-4 (LC 11), 8=-87 (LC 15), 10=-87 (LC 14)
Max Grav	2=87 (LC 1), 6=87 (LC 1), 8=423 (LC 22), 9=301 (LC 21), 10=423 (LC 21)

FORCES

(lb) - Maximum Compression/Maximum Tension

TOP CHORD	1-2=0/17, 2-3=-54/45, 3-4=-124/96, 4-5=-124/96, 5-6=-34/45, 6-7=0/17
BOT CHORD	2-10=-7/46, 9-10=-2/46, 8-9=-2/46, 6-8=-7/46
WEBS	4-9=-214/91, 3-10=-377/199, 5-8=-377/199

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-4-3 to 3-4-3, Interior (1) 3-4-3 to 3-11-0, Exterior(2R) 3-11-0 to 9-11-0, Interior (1) 9-11-0 to 10-5-13, Exterior(2E) 10-5-13 to 13-5-13 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60

- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- N/A

- See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

LOAD CASE(S) Standard



July 28,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1007 Serenity-Roof-B326 A CP TMB BDRM4 GRH I75198388
25070152-01	PBA2	Piggyback	2	4	Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Sun Jul 27 23:59:27
ID:m2dQdjvppkexqPVgwg5aZPzRCX1-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWRCDoi7J4zJC?f

Page: 1



Scale = 1:31.5

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.07	Vert(LL)	n/a	-	n/a	999	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.03	Vert(CT)	n/a	-	n/a	999	
TCDL	10.0	Rep Stress Incr	YES	WB	0.02	Horz(CT)	0.00	15	n/a	n/a	
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH							
BCDL	10.0										
Weight: 188 lb FT = 20%											

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
OTHERS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(size)	2=11-10-14, 6=11-10-14, 8=11-10-14, 9=11-10-14, 10=11-10-14
Max Horiz	2=52 (LC 18)
Max Uplift	2=-11 (LC 15), 6=-4 (LC 11), 8=-87 (LC 15), 10=-87 (LC 14)
Max Grav	2=86 (LC 1), 6=86 (LC 1), 8=423 (LC 22), 9=302 (LC 21), 10=423 (LC 21)

FORCES

(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=0/17, 2-3=-53/45, 3-4=-123/96, 4-5=-123/96, 5-6=-33/45, 6-7=0/17
BOT CHORD	2-10=-8/47, 9-10=-2/46, 8-9=-2/46, 6-8=-8/47
WEBS	4-9=-215/91, 3-10=-375/198, 5-8=-375/198

NOTES

- 4-ply truss to be connected together as follows:
Top chords connected with 10d (0.131"x3") nails as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected with 10d (0.131"x3") nails as follows: 2x4 - 1 row at 0-9-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Unbalanced roof live loads have been considered for this design.

- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-4-3 to 3-4-3, Interior (1) 3-4-3 to 3-11-0, Exterior(2R) 3-11-0 to 9-11-0, Interior (1) 9-11-0 to 10-5-13, Exterior(2E) 10-5-13 to 13-5-13 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- N/A

- See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

LOAD CASE(S) Standard



July 28, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1007 Serenity-Roof-B326 A CP TMB BDRM4 GRH
25070152-01	VLB1	Valley	1	1	I75198389
Job Reference (optional)					

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Sun Jul 27 23:59:27
ID:uRu6rMLa1rlmrJyJNhjxpxzRQsR-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:58.7

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.31	Vert(LL)	n/a	-	n/a	999	MT20
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.17	Vert(TL)	n/a	-	n/a	999	244/190
TCDL	10.0	Rep Stress Incr	YES	WB	0.21	Horiz(TL)	0.01	7	n/a	n/a	
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH							
BCDL	10.0										
Weight: 106 lb FT = 20%											

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
OTHERS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

WEBS	1 Row at midpt	4-11
------	----------------	------

REACTIONS	(size)	1=21-7-6, 7=21-7-6, 8=21-7-6, 10=21-7-6, 11=21-7-6, 12=21-7-6, 13=21-7-6
	Max Horiz	1=-207 (LC 10)
	Max Uplift	1=-54 (LC 10), 7=-1 (LC 11), 8=-115 (LC 15), 10=-174 (LC 15), 12=-173 (LC 14), 13=-118 (LC 14)
	Max Grav	1=134 (LC 25), 7=119 (LC 27), 8=364 (LC 25), 10=473 (LC 6), 11=416 (LC 27), 12=473 (LC 5), 13=367 (LC 24)

FORCES

(lb) - Maximum Compression/Maximum Tension


TOP CHORD	1-2=-211/174, 2-3=-165/132, 3-4=-188/184, 4-5=-188/157, 5-6=-116/82, 6-7=-166/107
BOT CHORD	1-13=-79/161, 12-13=-79/161, 11-12=-79/161, 10-11=-79/161, 8-10=-79/161, 7-8=-79/161
WEBS	4-11=-209/4, 3-12=-376/222, 2-13=-264/163, 5-10=-376/222, 6-8=-265/161

NOTES

- 1) Unbalanced roof live loads have been considered for this design.

- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-4-13 to 3-4-13, Interior (1) 3-4-13 to 7-10-0, Exterior(2R) 7-10-0 to 13-10-0, Interior (1) 13-10-0 to 18-7-11, Exterior(2E) 18-7-11 to 21-7-11 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 4) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- 5) Unbalanced snow loads have been considered for this design.
- 6) All plates are 2x4 MT20 unless otherwise indicated.
- 7) Gable requires continuous bottom chord bearing.
- 8) Gable studs spaced at 4-0-0 oc.
- 9) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 10) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 11) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 54 lb uplift at joint 1, 1 lb uplift at joint 7, 173 lb uplift at joint 12, 118 lb uplift at joint 13, 174 lb uplift at joint 10 and 115 lb uplift at joint 8.

LOAD CASE(S) Standard



July 28, 2025


WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932

Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Sun Jul 27 23:59:27 Page: 1
ID:vJln UX?VSB9dbBmLUS1zzRQsC-RfC?PsB70Hg3NSqPqnL8w3uITXBGKwKCDoi7J4zJC?f



July 28, 2025

Design valid for use only with MiTeK® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinet.org) and **BCSI Building Component Safety Information** available from the Structural Building Components Association (www.sbcacomponents.com)


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1007 Serenity-Roof-B326 A CP TMB BDRM4 GRH
25070152-01	VLB3	Valley	1	1	I75198391
Job Reference (optional)					

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Sun Jul 27 23:59:27
ID:4pahjxh9RSqoCd5h0aDV3jzRQs?-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:50.5

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.38	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.18	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.41	Horiz(TL)	0.00	5	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH							
BCDL	10.0									Weight: 75 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
OTHERS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 10-0-0 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS

(size)	1=16-9-13, 5=16-9-13, 6=16-9-13, 8=16-9-13, 9=16-9-13
Max Horiz	1=-157 (LC 10)
Max Uplift	1=-64 (LC 10), 6=-183 (LC 15), 9=-187 (LC 14)
Max Grav	1=76 (LC 13), 5=1 (LC 25), 6=510 (LC 6), 8=654 (LC 24), 9=509 (LC 5)

FORCES


(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=-104/370, 2-3=-25/319, 3-4=-2/298, 4-5=-139/301
BOT CHORD	1-9=-197/74, 8-9=-197/74, 6-8=-197/74, 5-6=-197/74
WEBS	3-8=-470/0, 2-9=-392/220, 4-6=-392/218

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-4-13 to 3-4-13, Interior (1) 3-4-13 to 5-5-3, Exterior(2R) 5-5-3 to 11-5-3, Interior (1) 11-5-3 to 13-10-2, Exterior(2E) 13-10-2 to 16-10-2 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60

- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 64 lb uplift at joint 1, 187 lb uplift at joint 9 and 183 lb uplift at joint 6.

LOAD CASE(S) Standard



July 28,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1007 Serenity-Roof-B326 A CP TMB BDRM4 GRH
25070152-01	VLB4	Valley	1	1	I75198392
Job Reference (optional)					

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Sun Jul 27 23:59:27
ID:CKtcSNrINSSyGdaBHoyY5SzRQro-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:43.4

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.31	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.16	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.14	Horiz(TL)	0.00	5	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH							
BCDL	10.0									Weight: 62 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
OTHERS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS

(size)	1=14-5-0, 5=14-5-0, 6=14-5-0, 7=14-5-0, 8=14-5-0
Max Horiz	1=-136 (LC 10)
Max Uplift	1=-29 (LC 10), 6=-154 (LC 15), 8=-156 (LC 14)
Max Grav	1=109 (LC 25), 5=100 (LC 24), 6=454 (LC 21), 7=401 (LC 24), 8=452 (LC 20)

FORCES


(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=-141/139, 2-3=-178/119, 3-4=-177/112, 4-5=-122/104
BOT CHORD	1-8=-59/119, 7-8=-59/99, 6-7=-59/99, 5-6=-59/99
WEBS	3-7=-223/0, 2-8=-374/196, 4-6=-375/195

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-4-13 to 3-2-13, Interior (1) 3-2-13 to 4-2-13, Exterior(2R) 4-2-13 to 10-2-13, Interior (1) 10-2-13 to 11-2-13, Exterior(2E) 11-2-13 to 14-5-5 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60

- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 29 lb uplift at joint 1, 156 lb uplift at joint 8 and 154 lb uplift at joint 6.

LOAD CASE(S) Standard



July 28, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1007 Serenity-Roof-B326 A CP TMB BDRM4 GRH
25070152-01	VLB5	Valley	1	1	I75198393
Job Reference (optional)					

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Sun Jul 27 23:59:27
ID:vFTOYozalWjXT9L6tv8uVZzRQre-RfC?PsB70Hq3NSgPqnL8w3uITxBGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:39.1

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.31	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.12	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.08	Horiz(TL)	0.00	5	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 50 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
OTHERS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(size)	1=12-0-3, 5=12-0-3, 6=12-0-3, 7=12-0-3, 8=12-0-3
Max Horiz	1=-113 (LC 10)
Max Uplift	1=-38 (LC 10), 5=-6 (LC 11), 6=-136 (LC 15), 8=-138 (LC 14)
Max Grav	1=77 (LC 30), 5=71 (LC 24), 6=434 (LC 21), 7=259 (LC 21), 8=432 (LC 20)

FORCES


(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=-114/100, 2-3=-219/116, 3-4=-218/115, 4-5=-89/63
BOT CHORD	1-8=-32/73, 7-8=-30/73, 6-7=-30/73, 5-6=-30/73
WEBS	3-7=-171/0, 2-8=-400/215, 4-6=-401/220

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-4-13 to 3-4-13, Exterior(2R) 3-4-13 to 9-0-8, Exterior(2E) 9-0-8 to 12-0-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60

- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 38 lb uplift at joint 1, 6 lb uplift at joint 5, 138 lb uplift at joint 8 and 136 lb uplift at joint 6.

LOAD CASE(S) Standard



July 28,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1007 Serenity-Roof-B326 A CP TMB BDRM4 GRH
25070152-01	VLB6	Valley	1	1	I75198394
Job Reference (optional)					

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Sun Jul 27 23:59:27
ID:vFTOYoa1WjXT9L6tv8uVZzRQre-RfC?PsB70Hq3NSgPqnL8w3uITxbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:33.2

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.44	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.42	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.18	Horiz(TL)	0.00	4	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 37 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
OTHERS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 9-7-6 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS

(size)	1=9-7-6, 3=9-7-6, 4=9-7-6
Max Horiz	1=-89 (LC 10)
Max Uplift	1=-58 (LC 21), 3=-47 (LC 20), 4=-106 (LC 14)
Max Grav	1=75 (LC 20), 3=94 (LC 21), 4=767 (LC 20)

FORCES


(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=-110/369, 2-3=-112/366
BOT CHORD	1-4=-241/170, 3-4=-241/170
WEBS	2-4=-632/265

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-4-13 to 3-4-13, Exterior(2R) 3-4-13 to 6-7-11, Exterior(2E) 6-7-11 to 9-7-11 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.

- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 58 lb uplift at joint 1, 47 lb uplift at joint 3 and 106 lb uplift at joint 4.

LOAD CASE(S) Standard



July 28, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1007 Serenity-Roof-B326 A CP TMB BDRM4 GRH
25070152-01	VLB7	Valley	1	1	I75198395
Job Reference (optional)					

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Sun Jul 27 23:59:28
ID:vFTOY0za1WjXT9L6tv8uVZzRQre-RfC?PsB70Hq3NSgPqnL8w3uITxbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:29.1

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.25	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.26	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.09	Horiz(TL)	0.00	4	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	10.0											
											Weight: 27 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
OTHERS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 7-2-10 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS

(size)	1=7-2-10, 3=7-2-10, 4=7-2-10
Max Horiz	1=-66 (LC 10)
Max Uplift	1=-26 (LC 21), 3=-14 (LC 20), 4=-70 (LC 14)
Max Grav	1=71 (LC 20), 3=103 (LC 21), 4=523 (LC 20)

FORCES


(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=-83/223, 2-3=-87/223
BOT CHORD	1-4=-176/150, 3-4=-176/150
WEBS	2-4=-415/192

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-4-13 to 3-7-10, Exterior(2R) 3-7-10 to 4-2-14, Exterior(2E) 4-2-14 to 7-2-14 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.

- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 26 lb uplift at joint 1, 14 lb uplift at joint 3 and 70 lb uplift at joint 4.

LOAD CASE(S) Standard



July 28, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1007 Serenity-Roof-B326 A CP TMB BDRM4 GRH
25070152-01	VLB8	Valley	1	1	I75198396
Job Reference (optional)					

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Sun Jul 27 23:59:28
ID:vFTOY0za1WjXT9L6tv8uVzZRQre-RfC?PsB70Hq3NSgPqnL8w3uITxbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:26

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.08	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.11	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.04	Horiz(TL)	0.00	3	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP							
BCDL	10.0									Weight: 17 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING

TOP CHORD Structural wood sheathing directly applied or 4-9-13 oc purlins.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS

(size) 1=4-9-13, 3=4-9-13, 4=4-9-13
Max Horiz 1=-43 (LC 10)
Max Uplift 3=-7 (LC 15), 4=-30 (LC 14)
Max Grav 1=58 (LC 20), 3=86 (LC 21), 4=285 (LC 20)

FORCES


(lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=-61/98, 2-3=-79/99
BOT CHORD 1-4=-80/85, 3-4=-80/85
WEBS 2-4=-203/92

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust)
Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10

- Unbalanced snow loads have been considered for this design.
 - Gable requires continuous bottom chord bearing.
 - Gable studs spaced at 4-0-0 oc.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 7 lb uplift at joint 3 and 30 lb uplift at joint 4.
- LOAD CASE(S)** Standard



July 28, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1007 Serenity-Roof-B326 A CP TMB BDRM4 GRH I75198397
25070152-01	VLD1	Valley	1	1	Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Sun Jul 27 23:59:28
ID:?VRASUfm0qfd3oFPBHC5FHzRQud-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1




Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.35	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.18	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.27	Horiz(TL)	0.00	5	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 76 lb	FT = 20%

LUMBER		
TOP CHORD	2x4 SP No.2	
BOT CHORD	2x4 SP No.2	
OTHERS	2x4 SP No.3	
BRACING		
TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins.	
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.	
REACTIONS	(size)	1=16-11-6, 5=16-11-6, 6=16-11-6, 8=16-11-6, 9=16-11-6
	Max Horiz	1=161 (LC 11)
	Max Uplift	1=-21 (LC 10), 6=-183 (LC 15), 9=-187 (LC 14)
	Max Grav	1=123 (LC 25), 5=86 (LC 21), 6=520 (LC 25), 8=496 (LC 24), 9=526 (LC 24)
FORCES	(lb) - Maximum Compression/Maximum Tension	
TOP CHORD		1-2=-145/253, 2-3=-108/190, 3-4=-109/170, 4-5=-111/218
BOT CHORD		1-9=-130/131, 8-9=-130/131, 6-8=-130/131, 5-6=-130/131
WEBS		3-8=-312/0, 2-9=-397/221, 4-6=-396/219

- NOTES**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-0-5 to 3-0-5, Interior (1) 3-0-5 to 5-6-0, Exterior(2R) 5-6-0 to 11-6-0, Interior (1) 11-6-0 to 13-7-3, Exterior(2E) 13-7-3 to 16-7-3 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60

- 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 4) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- 5) Unbalanced snow loads have been considered for this design.
- 6) Gable requires continuous bottom chord bearing.
- 7) Gable studs spaced at 4-0-0 oc.
- 8) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 9) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 21 lb uplift at joint 1, 187 lb uplift at joint 9 and 183 lb uplift at joint 6.

LOAD CASE(S) Standard



July 28,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1007 Serenity-Roof-B326 A CP TMB BDRM4 GRH I75198398
25070152-01	VLD2	Valley	1	1	Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Sun Jul 27 23:59:28
ID:Th_ZgqfOm8nUgyqbk?jKoVzRQuc-RfC?PsB70Hq3NSgPqnL8w3uITxbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:43.7

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.31	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.16	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.15	Horiz(TL)	0.00	5	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH							
BCDL	10.0									Weight: 63 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
OTHERS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS	(size)	1=14-6-10, 5=14-6-10, 6=14-6-10, 7=14-6-10, 8=14-6-10
	Max Horiz	1=138 (LC 11)
	Max Uplift	1=-24 (LC 10), 6=-156 (LC 15), 8=-159 (LC 14)
	Max Grav	1=124 (LC 25), 5=99 (LC 24), 6=456 (LC 21), 7=407 (LC 24), 8=456 (LC 20)

FORCES

	(lb) - Maximum Compression/Maximum Tension
TOP CHORD	1-2=-153/145, 2-3=-173/121, 3-4=-173/111, 4-5=-121/110
BOT CHORD	1-8=-61/127, 7-8=-61/101, 6-7=-61/101, 5-6=-61/101
WEBS	3-7=-227/0, 2-8=-375/197, 4-6=-375/196

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-0-5 to 3-3-10, Interior (1) 3-3-10 to 4-3-10, Exterior(2R) 4-3-10 to 10-3-10, Interior (1) 10-3-10 to 11-3-10, Exterior(2E) 11-3-10 to 14-6-14 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60

- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 24 lb uplift at joint 1, 159 lb uplift at joint 8 and 156 lb uplift at joint 6.

LOAD CASE(S) Standard



July 28, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1007 Serenity-Roof-B326 A CP TMB BDRM4 GRH
25070152-01	VLD3	Valley	1	1	I75198399
Job Reference (optional)					

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Sun Jul 27 23:59:28
ID:kUxM45s?bF21LX?KCRTFVazRQqU-RfC?PsB70Hq3NSgPqnL8w3uTXbGKWrCDoi7J4zJC?i

Page: 1



Scale = 1:39.3

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.31	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.12	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.08	Horiz(TL)	0.00	5	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0											
Weight: 50 lb											FT = 20%	

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
OTHERS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(size)	1=12-1-13, 5=12-1-13, 6=12-1-13, 7=12-1-13, 8=12-1-13
Max Horiz	1=-115 (LC 12)
Max Uplift	1=-33 (LC 10), 5=-5 (LC 11), 6=-136 (LC 15), 8=-140 (LC 14)
Max Grav	1=94 (LC 25), 5=73 (LC 24), 6=434 (LC 21), 7=261 (LC 21), 8=434 (LC 20)

FORCES


(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=-117/101, 2-3=-216/116, 3-4=-216/116, 4-5=-91/63
BOT CHORD	1-8=-32/79, 7-8=-32/74, 6-7=-32/74, 5-6=-32/74
WEBS	3-7=-174/0, 2-8=-397/217, 4-6=-397/217

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-0-5 to 3-0-5, Exterior(2R) 3-0-5 to 9-2-2, Exterior(2E) 9-2-2 to 12-2-2 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60

- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 33 lb uplift at joint 1, 5 lb uplift at joint 5, 140 lb uplift at joint 8 and 136 lb uplift at joint 6.

LOAD CASE(S) Standard



July 28, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1007 Serenity-Roof-B326 A CP TMB BDRM4 GRH
25070152-01	VLD4	Valley	1	1	I75198400
Job Reference (optional)					

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Sun Jul 27 23:59:28
ID:kUxM45s?bF21LX?KCRTFVazRQqU-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?i

Page: 1



Scale = 1:33.4

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.46	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.44	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.19	Horiz(TL)	0.01	4	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 37 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
OTHERS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 9-9-0 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS

(size)	1=9-9-0, 3=9-9-0, 4=9-9-0
Max Horiz	1=-91 (LC 10)
Max Uplift	1=-52 (LC 21), 3=-52 (LC 20), 4=-111 (LC 14)
Max Grav	1=94 (LC 20), 3=94 (LC 21), 4=788 (LC 20)

FORCES


(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=-117/382, 2-3=-117/382
BOT CHORD	1-4=-249/175, 3-4=-249/175
WEBS	2-4=-650/275

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-0-5 to 3-0-5, Exterior(2R) 3-0-5 to 6-9-5, Exterior(2E) 6-9-5 to 9-9-5 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.

- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 52 lb uplift at joint 1, 52 lb uplift at joint 3 and 111 lb uplift at joint 4.

LOAD CASE(S) Standard



July 28, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	1007 Serenity-Roof-B326 A CP TMB BDRM4 GRH
25070152-01	VLD5	Valley	1	1	I75198401
Job Reference (optional)					

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Feb 19 2025 Print: 8.730 S Feb 19 2025 MiTek Industries, Inc. Sun Jul 27 23:59:28
ID:CgVkhRtdMZAuzhaXm9_U1OzRQqT-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?i

Page: 1



Scale = 1:29.3

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.27	Vert(LL)	n/a	-	n/a	999	MT20
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.27	Vert(TL)	n/a	-	n/a	999	244/190
TCDL	10.0	Rep Stress Incr	YES	WB	0.09	Horiz(TL)	0.00	4	n/a	n/a	
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP							
BCDL	10.0										
Weight: 27 lb FT = 20%											

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
OTHERS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 7-4-3 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS

(size)	1=7-4-3, 3=7-4-3, 4=7-4-3
Max Horiz	1=68 (LC 11)
Max Uplift	1=-19 (LC 21), 3=-19 (LC 20), 4=-76 (LC 14)
Max Grav	1=105 (LC 20), 3=105 (LC 21), 4=545 (LC 20)

FORCES


(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=-92/236, 2-3=-92/236
BOT CHORD	1-4=-184/155, 3-4=-184/155
WEBS	2-4=-432/204

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-0-5 to 3-0-5, Exterior(2R) 3-0-5 to 4-4-8, Exterior(2E) 4-4-8 to 7-4-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.

- TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 19 lb uplift at joint 1, 19 lb uplift at joint 3 and 76 lb uplift at joint 4.

LOAD CASE(S) Standard




July 28, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate



818 Soundside Road
Edenton, NC 27932

Page: 1

- 5) Unbalanced snow loads have been considered for this design.
- 6) Gable requires continuous bottom chord bearing.
- 7) Gable studs spaced at 4-0-0 oc.
- 8) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 9) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- 10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 7 lb uplift at joint 3 and 35 lb uplift at joint 4.

LOAD CASE(S) Standard

- July 28, 2025



Symbols

PLATE LOCATION AND ORIENTATION



* Plate location details available in MITek software or upon request.

PLATE SIZE

4 X 4

The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T or I bracing if indicated.

BEARING




Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number/letter where bearings occur. Min size shown is for crushing only.

Industry Standards:

ANSI/TP1: National Design Specification for Metal Plate Connected Wood Truss Construction.
DSB-22: Building Component Safety Information, Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses.

Numbering System



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

Product Code Approvals

ICC-ES Reports:

ESR-1988, ESR-2362, ESR-2685, ESR-3282
ESR-4722, ESL-1388

Design General Notes

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.

Lumber design values are in accordance with ANSI/TP1 1 section 6.3. These truss designs rely on lumber values established by others.

© 2023 MITek® All Rights Reserved

General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor I bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TP1 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TP1 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TP1 1 Quality Criteria.
21. The design does not take into account any dynamic or other loads other than those expressly stated.

MITek

ENGINEERING BY
TRENCO
A MITek Affiliate

MITek Engineering Reference Sheet: MII-7473 rev. 1/2/2023