



NC DEPARTMENT OF  
**HEALTH AND  
HUMAN SERVICES**

ROY COOPER • Governor

KODY H. KINSLEY • Secretary

MARK BENTON • Chief Deputy Secretary for Health

SUSAN KANSAGRA • Assistant Secretary for Public Health

Division of Public Health

Submittal Includes: ☒ (a2) Improvement Permit ☒ (a2) Construction Authorization ☐ Fee \$ \_\_\_\_\_

**IMPROVEMENT PERMIT FOR G.S. 130A-335(a2)**

County: Harnett

PIN/Lot Identifier: 0642-85-3054 (Birchwood Trails, Lot 74)

Issued To: KB Homes

Property Location: 119 Thunderbird Lane, Fuquay Varina, NC 27526

Subdivision (if applicable) Birchwood Trails Lot #: 74 Block: \_\_\_\_\_ Section: \_\_\_\_\_

LSS Report Provided: Yes ☒ No ☐

If yes, name and license number of LSS: Heath Clapp #1354

New ☒

Expansion ☐

System Relocation ☐

Change of Use ☐

Facility Type: SFR (4-bedroom)

Number of bedrooms: 4 Number of Occupants: 8 Other: \_\_\_\_\_

Design Wastewater Strength: ☒ Domestic

☐ High Strength

☐ Industrial Process Wastewater

Proposed Design Daily Flow: 480 GPD Proposed LTAR (Initial): 0.3 Proposed LTAR (Repair): 0.15 - 0.3

Proposed Wastewater System Type\*: Pressure Manifold PPBPS T&J Panel (Initial) Pump Required: ☒ Yes ☐ No ☐ May be required

Proposed Wastewater System Type\*: Anaerobic Drip Irrigation (Repair) Pump Required: ☒ Yes ☐ No ☐ May be required

*\*Please include system classification for proposed wastewater system types in accordance with Rule .1301 Table XXXII*

Effluent Standard: ☒ DSE ☐ HSE ☐ NSF/ANSI 40 ☐ TS-I ☐ TS-II ☐ RCW

Saprolite System (Initial): ☐ Yes ☒ No

Saprolite System (Repair): ☐ Yes ☒ No

Fill System (Initial): ☐ Yes ☒ No If yes, specify: ☐ New ☐ Existing (when adding more than 6 inches of fill to system area provide a fill plan)

Fill System (Repair): ☐ Yes ☒ No If yes, specify: ☐ New ☐ Existing (when adding more than 6 inches of fill to system area provide a fill plan)

Usable Depth to LC (Initial)\*: 32" Usable Depth to LC (Repair)\*: 18" *\* Limiting Condition*

Max. Trench Depth (Initial)\*: 20" Max. Trench Depth (Repair)\*: 6" *\* Measured on the downhill side of the trench*

Artificial Drainage Required: ☐ Yes ☒ No If yes, please specify details: \_\_\_\_\_

Type of Water Supply: ☐ Private well ☐ Public well ☐ Shared well ☒ Municipal Supply ☐ Spring ☐ Other: \_\_\_\_\_

Drainfield location meets requirements of Rule .0508: Yes ☒ No ☐ Drainfield location meets requirements of Rule .0601: Yes ☒ No ☐

Permit valid for: ☒ Five years [site plan submitted pursuant to GS 130A-334(13a)] ☐ No expiration [plat submitted pursuant to GS 130A-334(7a)]

Permit conditions:

Licensed Soil Scientist Print Name: Heath Clapp

Licensed Soil Scientist Signature: Heath Clapp

Date: 11/11/2025

The LSS evaluation is being submitted pursuant to and meets the requirements of G.S. 130A-335(a2).

**\*See attached site sketch\***

## ***This Section for Local Health Department Use Only***

Initial submittal received: \_\_\_\_\_ by \_\_\_\_\_  
Date Initials

G.S. 130A-335(a3) states the following:

*When an applicant for an Improvement Permit submits to a local health department an Improvement Permit application, the permit fee charged by the local health department, the common form developed by the Department, and a soil evaluation pursuant to subsection (a2) of this section, the local health department shall, within five business days of receiving the application, conduct a completeness review of the submittal. A determination of completeness means that the Improvement Permit includes all of the required components. If the local health department determines that the Improvement Permit is incomplete, the local health department shall notify the applicant of the components needed to complete the Improvement Permit. The applicant may submit additional information to the local health department to cure the deficiencies in the Improvement Permit. The local health department shall make a final determination as to whether the Improvement Permit is complete within five business days after the local health department receives the additional information from the applicant. If the local health department fails to act within any period set out in this subsection, the applicant may treat the failure to act as a determination of completeness. The Department shall develop a common form for use as the Improvement Permit.*

The review for completeness of this Improvement Permit was conducted in accordance with G.S. 130A-335(a3). This Improvement Permit is determined to be:

☐ Incomplete (If box is checked, information in this section is required.)

The following items are missing:

\_\_\_\_\_  
\_\_\_\_\_

Copies of this were sent to the LSS and the Applicant on \_\_\_\_\_  
Date

State Authorized Agent: \_\_\_\_\_ Date: \_\_\_\_\_

☐ Complete

State Authorized Agent: \_\_\_\_\_ Date: \_\_\_\_\_

**This Improvement Permit is issued pursuant to G.S. 130A-335 (a2) and (a3) using the signed and sealed LSS/LG evaluation(s) attached here. The issuance of this permit in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. *This permit is subject to revocation if the site plan, plat, or the intended use changes.* The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of 15A NCAC 18E and to the conditions of this permit.**

**The Department, the Department's authorized agents, and the local health departments shall be discharged and released from any liabilities, duties, and responsibilities imposed by statute or in common law from any claim arising out of or attributed to evaluations, submittals, or actions from a licensed soil scientist or licensed geologist pursuant to GS 130A-335(a2).**

Improvement Permit Expiration Date: \_\_\_\_\_

**\*See attached site sketch\***

## Re-submittal of Improvement Permit

LHD USE ONLY: This IP resubmittal received: \_\_\_\_\_ by \_\_\_\_\_  
Date Initials

The following items are being resubmitted pursuant to G.S. 130A-335(a3) for issuance of the Improvement Permit:

---

---

---

---

I, \_\_\_\_\_ hereby attest that the information required to be included with this re-submittal  
*Licensed Soil Scientist (Print Name)*  
is accurate and complete to the best of my knowledge and that the proposed Improvement Permit meets all applicable federal,  
State, and local laws, regulations, rules, and ordinances.

\_\_\_\_\_  
*Signature of Licensed Soil Scientist*

\_\_\_\_\_  
*Date*

*The section below is for Local Health Department use after submittal of items noted as missing above.*

### LHD Follow-up Completeness Review of Improvement Permit

The review for completeness of this Improvement Permit re-submittal was conducted in accordance with G.S. 130A-335(a3). This Improvement Permit is determined to be:

☐ Incomplete (If box is checked, information in this section is required.)

The following items are missing:

---

---

Copies of this were sent to the LSS and the Applicant on \_\_\_\_\_  
Date

State Authorized Agent: \_\_\_\_\_

Date: \_\_\_\_\_

☐ Complete

State Authorized Agent: \_\_\_\_\_

Date: \_\_\_\_\_



Permit/File #: \_\_\_\_\_

**CONSTRUCTION AUTHORIZATION FOR G.S. 130A-335(a2)**County: HarnettPre-Construction Conference Required: Yes ☐ No ☒PIN/Lot Identifier: 0642-85-3054 (Birchwood Trails, Lot 74)Issued To: KB HomesProperty Location: 119 Thunderbird Lane, Fuquay Varina, NC 27526AOWE/PE Plans/Evaluations Provided: Yes ☒ No ☐ If yes, name and license number of AOWE/PE: Heath Clapp, 10057EFacility Type: SFR (4-bedroom)Number of bedrooms: 4 Number of Occupants: 8 Other: \_\_\_\_\_☒ New ☐ Expansion ☐ Repair ☐ System Relocation ☐ Change of UseBasement? ☐ Yes ☒ No Basement Fixtures? ☐ Yes ☒ NoCrawl Space? ☐ Yes ☒ No Slab Foundation? ☒ Yes ☐ NoType of Wastewater System\* PPBPS T&J Panel Pressure Manifold (Initial) Anaerobic Drip Irrigation (Repair)

\*Please include system classification for proposed wastewater system types in accordance with Rule .1301 Table XXXII

Design Daily Flow: 480 GPD Wastewater Strength: ☒ Domestic ☐ High Strength ☐ Industrial Process WWSession Law 2014-120 Section 53, Engineering Design Utilizing Low-flow Fixtures and Low-flow Technologies? ☐ Yes ☐ No  
(if yes, please provide engineering documentation)Effluent Standard: ☒ DSE ☐ HSE ☐ NSF/ANSI 40 ☐ TS-I ☐ TS-II ☐ RCWType of Water Supply: ☐ Private well ☐ Public well ☐ Shared well ☒ Municipal Supply ☐ Spring ☐ Other: \_\_\_\_\_**Installation Requirements/Conditions**Septic Tank Size: 1,250 gallons Total Trench/Bed Length: 300 feet Trench/Bed Spacing: 9 feet on centerTrench/Bed Width: 36 inches LTAR: 0.3 gpd/ft<sup>2</sup> Usable Depth to LC (Initial)\*: 32" <sup>\*Limiting condition</sup>Soil Cover: 0 inches Slope Corrected Maximum Trench/Bed Depth\*: 20" inches <sup>\*Measured on the downhill side of the trench</sup>Pump Tank Size (if applicable): 1,275 gallons Requires more than 1 pump? ☐ Yes ☐ NoPump Requirements: 16.27 ft. TDH vs. 25.22 GPM Grease Trap Size (if applicable): N/A gallonsDistribution Method: ☐ Serial ☐ D-Box or Parallel ☒ Pressure Manifold(s) ☐ LPP ☐ Other: \_\_\_\_\_Artificial Drainage Required: Yes ☐ No ☒ If yes, please specify details: \_\_\_\_\_**Legal Agreements** (If the answer is "Yes" to any type of legal agreements, please attach a copy of the agreement.)Multi-party Agreement Required [.0204(g)]: ☐ Yes ☒ No Declaration of Restrictive Covenants: ☐ Yes ☒ NoEasement, Right-of-Way, or Encroachment Agreement Required [.0301(b)]: ☐ Yes ☒ NoManagement Entity Required: ☐ Yes ☒ No Minimum O&M Requirements: \_\_\_\_\_

Permit conditions:

The requirements of 15A NCAC 18E are incorporated by reference into this permit and shall be met. Systems shall be installed in accordance with the attached site sketch. ***This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes.*** The Construction Authorization shall not be affected by a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of 15A NCAC 18E, or 15A NCAC 18A .1900, as applicable, and to the conditions of this permit.

AOWE/PE Print Name: Heath ClappAOWE/PE Signature: Heath ClappDate: 11/11/2025

This AOWE/PE submittal is pursuant to and meets the requirements of G.S. 130A-335(a2) and (a5).

**\*See attached site sketch\***

### ***This Section for Local Health Department Use Only***

Initial submittal received: \_\_\_\_\_ by \_\_\_\_\_  
Date Initials

G.S. 130A-335(a5) states the following:

*When an applicant for a Construction Authorization, or an Improvement Permit and Construction Authorization together, submits a Construction Authorization, or an Improvement Permit and Construction Authorization application together, the permit fee charged by the local health department, the common form developed by the Department, and any necessary signed and sealed plans or evaluations conducted by a person licensed pursuant to Chapter 89C of the General Statutes as a licensed engineer or a person certified pursuant to Article 5 of Chapter 90A of the General Statutes as an Authorized On-Site Wastewater Evaluator, the local health department shall, within five business days of receiving the application, conduct a completeness review of the submittal. A determination of completeness means that the Construction Authorization or Improvement Permit and Construction Authorization includes all of the required components. If the local health department determines that the Construction Authorization or Improvement Permit and Construction Authorization is incomplete, the local health department shall notify the applicant of the components needed to complete the Construction Authorization or Improvement Permit and Construction Authorization. The applicant may submit additional information to the local health department to cure the deficiencies in the Construction Authorization or Improvement Permit and Construction Authorization. The local health department shall make a final determination as to whether the Construction Authorization or Improvement Permit and Construction Authorization is complete within five business days after the local health department receives the additional information from the applicant. If the local health department fails to act within any period set out in this subsection, the applicant may treat the failure to act as a determination of completeness. The applicant may apply for the building permit for the project upon the decision of completeness of the Construction Authorization or Improvement Permit and Construction Authorization by the local health department or if the local health department fails to act within five business days. The Authorized On-Site Wastewater Evaluator or licensed engineer submitting the evaluation pursuant to this subsection may request that the local health department revoke or suspend the Construction Authorization or Improvement Permit and Construction Authorization for cause. Upon written request of the Authorized On-Site Wastewater Evaluator or licensed engineer, the local health department shall suspend or revoke the Construction Authorization or Improvement Permit and Construction Authorization pursuant to G.S. 130A-23. The Department shall develop a common form for use as the Construction Authorization.*

The review for completeness of this Construction Authorization was conducted in accordance with G.S. 130A-335(a5). This

Construction Authorization is determined to be:

☐ Incomplete (If box is checked, information in this section is required.)

The following items are missing: \_\_\_\_\_  
\_\_\_\_\_

Copies of this were sent to the AOWE/PE and the Applicant on \_\_\_\_\_  
Date

State Authorized Agent: \_\_\_\_\_ Date: \_\_\_\_\_

☐ Complete

State Authorized Agent: \_\_\_\_\_ Date of Issuance: \_\_\_\_\_

**This Construction Authorization is issued pursuant to G.S. 130A-335(a2) and (a5) using the signed and sealed plans or evaluations attached here. This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be affected by a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.**

**The Department, the Department's authorized agents, and the local health departments shall be discharged and released from any liabilities, duties, and responsibilities imposed by statute or in common law from any claim arising out of or attributed to plans, evaluations, preconstruction conference findings, submittals, or actions from a person licensed pursuant to Chapter 89C of the General Statutes as a licensed engineer or a person certified pursuant to Article 5 of Chapter 90A of the General Statutes as an Authorized On-Site Wastewater Evaluator in GS 130A-335(a2), (a5), and (a7). The Department, the Department's authorized agents, and the local health departments shall be responsible and bear liability for their actions and evaluations and other obligations under State law or rule, including the issuance of the operations permit pursuant to GS 130A-337.**

**Construction Authorization Expiration Date:** \_\_\_\_\_

**\*See attached site sketch\***

## Re-submittal of Construction Authorization

LHD USE ONLY: This CA resubmittal received: \_\_\_\_\_ by \_\_\_\_\_  
Date Initials

The following items are being resubmitted pursuant to G.S. 130A-335(a5) for issuance of the Construction Authorization:

---

---

---

---

I, \_\_\_\_\_ hereby attest that the information required to be included with this re-submittal  
*Authorized Onsite Wastewater Evaluator (Print Name)*  
is accurate and complete to the best of my knowledge and that the proposed Construction Authorization meets all applicable federal, State, and local laws, regulations, rules, and ordinances.

\_\_\_\_\_  
*Signature of Authorized On-Site Wastewater Evaluator*

\_\_\_\_\_  
*Date*

*The section below is for Local Health Department use after submittal of items noted as missing above.*

### LHD Follow-up Completeness Review of Construction Authorization

The review for completeness of this Construction Authorization re-submittal was conducted in accordance with G.S. 130A-335(a5). This Construction Authorization is determined to be:

☐ Incomplete (If box is checked, information in this section is required.)

The following items are missing:

---

---

Copies of this were sent to the AOWE/PE and the Applicant on \_\_\_\_\_  
Date

State Authorized Agent: \_\_\_\_\_

Date: \_\_\_\_\_

☐ Complete

State Authorized Agent: \_\_\_\_\_

Date: \_\_\_\_\_





County: \_\_\_\_\_

PIN/Lot Identifier: \_\_\_\_\_

Issued To: \_\_\_\_\_

Blank lined paper with a faint watermark of the Great Seal of the State of North Carolina in the background.

[illegible]



Agri-Waste Technology, Inc.  
1225 Crescent Green, Suite 250, Cary NC 27518  
agriwaste.com | 919.859.0669



**Soil Suitability for Domestic Sewage Treatment and Disposal Systems  
Birchwood Trails – Lot 74  
119 Thunderbird Lane, Fuquay Varina, NC 27526  
(Harnett County)  
October 7, 2025**

Soil suitability for domestic sewage treatment and disposal systems was evaluated on October 1, 2025, for the property located at 119 Thunderbird Lane in Fuquay Varina, NC (Harnett County). Heath Clapp of Agri-Waste Technology, Inc. (AWT) conducted the soil evaluation. This evaluation was done to facilitate permitting for a septic system for a 4-bedroom home. This report and attached documents were prepared *to this application is to be used to issue an Improvement Permit in accordance with G.S. 130A-335(a2) and (a3). The LSS evaluation is being submitted pursuant to and meets the requirements of G.S. 130A-335(a2).*

A drawing of the site plan, septic layout, septic system design, and soil pit locations is included in Attachment 1. Profile descriptions for each soil boring are included in Attachment 2.

The total property area is approximately 0.58 acres. The house and septic area are an open field. The proposed septic system for the property is a pressure manifold fed, PPBPS T&J Panel (50% reduction) system for the initial and an anaerobic drip irrigation septic system for the repair.

**Soil Suitability for Domestic Sewage Treatment and Disposal Systems**

The drawing in Attachment 1 details the property boundaries, soil boring locations, and layout of drain field trenches. Multiple soil borings were advanced within the proposed septic system area on the property. Soil borings were examined to determine soil suitability for on-site sewage disposal systems in accordance with 15A 18A .1900 Rules for Sewage Treatment and Disposal Systems. Soil borings 1-5 surround the initial drainfield area and are suitable for a conventional style trench. Soil borings 3-10 surround the repair drainfield area and are suitable for an anaerobic drip irrigation septic system.

The layout shown in Attachment 1 indicates there is available space for a four-bedroom septic system. The initial system can be installed with the use of a PPBPS T&J Panel (50% Reduction) drainfield product based on the layout in the field. The repair system will be an anaerobic drip irrigation septic system.



The proposed LTAR (Long Term Acceptance Rate) by AWT for the initial system is 0.3GPD/ft<sup>2</sup>. The soils on this property are group III soils within the distribution and treatment zone as used to define the LTAR. With an LTAR of 0.3GPD/ft<sup>2</sup>, 267 linear feet of PPBPS T&J Panel (50% reduction) trench is necessary to support a 4-bedroom home for the initial system. The attached drawing proves that 275 linear feet of PPBPS T&J Panel (50% reduction) trench can be installed within the suitable soils area on the property. **The maximum slope corrected trench depth for the initial system is 20”.**

The proposed LTAR (Long Term Acceptance Rate) by AWT for the repair system is 0.15 – 0.3 GPD/ft<sup>2</sup>. The soils on this property are group III soils within the distribution and treatment zone as used to define the LTAR. With an LTAR of 0.15 – 0.3 GPD/ft<sup>2</sup>, 1,600 - 3,200 ft<sup>2</sup> of anaerobic drip irrigation area is necessary to support a 4-bedroom home for the repair system. The attached drawing proves that there is approximately 4,100 ft<sup>2</sup> of suitable soils area on the property to locate the repair system. The maximum trench bottom should not exceed 6” for the repair system.

Any logging, disturbances, or grading done in the usable area or within the proposed setbacks will change the potential of using the area designated for a drainfield. Prior to moving forward with the development on the property, the Harnett County Health Department should be contacted to complete the necessary Construction Oversight and to issue an OP (Operations Permit) for the property once the septic system has been installed.

#### Conclusions

An IP (Improvement Permit) and CA (Construction Authorization) for this property can be issued with the site plan that is in Attachment 1. A CA permit will be required to secure a building permit for the property. The county issues an Operation Permit after the system has been installed to meet the specifications of the Authorization to Construct. Additional septic layouts have been or will be performed as needed. It will be critical to not disturb any of the proposed septic area or there is a risk that the IP and CA will be revoked. The LSS/AOWE Evaluation and attached documents were prepared *to this application is to be used to issue an Improvement Permit in accordance with G.S. 130A-335(a2) and (a3). The LSS/AOWE evaluation is being submitted pursuant to and meets the requirements of G.S. 130A-335(a2) and (a5).*

We appreciate the opportunity to assist you in this matter. Please contact us with any questions, concerns, or comments.

Sincerely,

Heath Clapp, NC LSS



Agri-Waste Technology, Inc.  
1225 Crescent Green, Suite 250, Cary NC 27518  
agriwaste.com | 919.859.0669

## SOIL & SITE EVALUATION for ON-SITE WASTEWATER SYSTEMS

Evaluation Date	10/1/2025	Site Location	119 Thunderbird Lane, Fuquay Varina, NC 27526	County	Harnett
PIN/Parcel	0642-85-3054	Property Size	0.58 acres	Property Recorded	Yes
Proposed Facility	SFR	Bedrooms	4	Wastewater Strength	Domestic
Water Supply	Municipal	Design Flow (.0400)	480	Evaluation Method	Auger

Profile #	.0502 Landscape Position Slope %	Horizon Depth (in)	Soil Morphology		Other Factors						.0509 Profile Class LTAR	.0502(d) Slope Correction
			.0503 Structure Texture	.0503 Consistence Mineralogy	.0504 Soil Wetness Color	.0505 Soil Depth (in)	.0506 Saprolite	.0507 Restrictive Horizon				
1, 2, 5	4%	Ap 0-10"	LS	NS, NP, VFr	10YR 3/3	44	S	S	0.4	1.6		
		E 10-18"	LS	NS; NP; VFr	10YR 7/6							
		Bt1 18-44"	SCL	S; SP; Fi-Fr	2.5YR 5/8							
		Bt2 44"+	SCL	S; P; Fi	2.5YR 5/8 10YR 6/2	System Type			Conventional			
3, 4	4%	Ap 0-10"	LS	NS, NP, VFr	10YR 3/3	34	S	S	0.4	1.6		
		E 10-18"	LS	NS; NP; VFr	10YR 7/6							
		Bt1 18-34"	SCL	S; SP; Fi-Fr	2.5YR 5/8							
		Bt2 34"+	SCL	S; P; Fi	2.5YR 5/8 10YR 6/2	System Type			Conventional			
6	4%	Ap 0-10"	LS	NS, NP, VFr	10YR 3/3	36	S	S	0.4	1.6		
		E 10-18"	LS	NS; NP; VFr	10YR 7/6							
		Bt1 18-36"+	SCL	S; SP; Fi-Fr	2.5YR 5/8							
						System Type			Conventional			
7, 8, 9, 10	1%	Ap 0-2"	LS	NS, NP, VFr	10YR 3/3	19	S	S	0.4	0.4		
		E 2-12"	LS	NS; NP; VFr	10YR 7/6							
		Bt1 12-19"	SCL	S; SP; Fi-Fr	2.5YR 5/8							
		Bt2 19"+	SCL	S; P; Fi	2.5YR 5/8 10YR 6/2	System Type			Anaerobic Drip			

Evaluated By:
Heath Clapp, LSS

Site Classification	Suitable	Site Classification	Suitable
Primary LTAR	0.4	Repair LTAR	0.4
Primary Trench Depth	20"	Repair Trench Depth	6"



Agri-Waste Technology, Inc.  
1225 Crescent Green, Suite 250, Cary NC 27518  
agriwaste.com | 919.859.0669

## SOIL & SITE EVALUATION for ON-SITE WASTEWATER SYSTEMS

### LEGEND

Soil Group	Soil Texture	Conventional LTAR	Anaerobic Dip LTAR	Aerobic Drip LTAR (TS-II)	Mineralogy &		Structure
					Moist	Wet	
I	S (Sand)	0.8-1.2	0.4-0.6	0.8-1.5			SG (Single grain)
	LS (Loamy Sand)				Lo (Loose)	NS (Non Sticky)	M (Massive)
II	SL (Sandy Loam)	0.6-0.8	0.3-0.4	0.6-0.8	VFR (Very Friable)	SS (Slightly Sticky)	GR (Granular)
	L (Loam)				FR (Friable)	S (Sticky)	SBK (Subangular Blocky)
	SiL (Silt Loam)				FI (Firm)	VS (Very Sticky)	ABK (Angular Blocky)
	SCL (Sandy Clay Loam)				VFI (Very Firm)	NP (Non Plastic)	
	CL (Clay Loam)				EFI (Extremely Firm)	SP (Slightly Plastic)	PR (Prismatic)
III	SiCL (Silty Clay Loam)	0.3-0.6	0.15-0.3	0.2-0.6		P (Plastic)	PL (Platy)
	SC (Sandy Clay)					VP (Very Plastic)	
	SiC (Silty Clay)						
	C (Clay)						
IV		0.1-0.4	0.05-1.5	0.05-0.2			
					SEXP (Slighty Expansive)		
					EXP (Expansive)		



# CERTIFICATE OF LIABILITY INSURANCE

DATE (MM/DD/YYYY)

1/20/2025

THIS CERTIFICATE IS ISSUED AS A MATTER OF INFORMATION ONLY AND CONFERS NO RIGHTS UPON THE CERTIFICATE HOLDER. THIS CERTIFICATE DOES NOT AFFIRMATIVELY OR NEGATIVELY AMEND, EXTEND OR ALTER THE COVERAGE AFFORDED BY THE POLICIES BELOW. THIS CERTIFICATE OF INSURANCE DOES NOT CONSTITUTE A CONTRACT BETWEEN THE ISSUING INSURER(S), AUTHORIZED REPRESENTATIVE OR PRODUCER, AND THE CERTIFICATE HOLDER.

**IMPORTANT:** If the certificate holder is an ADDITIONAL INSURED, the policy(ies) must have ADDITIONAL INSURED provisions or be endorsed. If SUBROGATION IS WAIVED, subject to the terms and conditions of the policy, certain policies may require an endorsement. A statement on this certificate does not confer rights to the certificate holder in lieu of such endorsement(s).

<b>PRODUCER</b> Hartsfield & Nash Agency, Inc. 10405 Ligon Mill Rd., Ste H Wake Forest NC 27587		<b>CONTACT</b> NAME: Connie Garkalns PHONE (A/C, No. Ext): 984-235-4273 E-MAIL ADDRESS: connie@hartsfield-nash.com		<b>FAX</b> (A/C, No): 919-556-8758
License#: 1000009111 AGRITEC-01		<b>INSURER(S) AFFORDING COVERAGE</b>		<b>NAIC #</b>
<b>INSURED</b> Agri-Waste Technology Inc 501 N. Salem St Ste 203 Apex NC 27502		INSURER A : Selective Insurance Company of		39926
		INSURER B : Accident Fund		10166
		INSURER C : Evanston Insurance Company		35378
		INSURER D :		
		INSURER E :		
		INSURER F :		

**COVERAGES****CERTIFICATE NUMBER:** 1304989694**REVISION NUMBER:**

THIS IS TO CERTIFY THAT THE POLICIES OF INSURANCE LISTED BELOW HAVE BEEN ISSUED TO THE INSURED NAMED ABOVE FOR THE POLICY PERIOD INDICATED. NOTWITHSTANDING ANY REQUIREMENT, TERM OR CONDITION OF ANY CONTRACT OR OTHER DOCUMENT WITH RESPECT TO WHICH THIS CERTIFICATE MAY BE ISSUED OR MAY PERTAIN, THE INSURANCE AFFORDED BY THE POLICIES DESCRIBED HEREIN IS SUBJECT TO ALL THE TERMS, EXCLUSIONS AND CONDITIONS OF SUCH POLICIES. LIMITS SHOWN MAY HAVE BEEN REDUCED BY PAID CLAIMS.

INSR LTR	TYPE OF INSURANCE	ADDL SUBR INSD WVD	POLICY NUMBER	POLICY EFF (MM/DD/YYYY)	POLICY EXP (MM/DD/YYYY)	LIMITS
A	<input checked="" type="checkbox"/> <b>COMMERCIAL GENERAL LIABILITY</b> <input type="checkbox"/> CLAIMS-MADE <input checked="" type="checkbox"/> OCCUR GEN'L AGGREGATE LIMIT APPLIES PER: <input type="checkbox"/> POLICY <input checked="" type="checkbox"/> PRO-JECT <input type="checkbox"/> LOC OTHER:		S 2253659	1/18/2025	1/18/2026	EACH OCCURRENCE \$ 2,000,000 DAMAGE TO RENTED PREMISES (Ea occurrence) \$ 300,000 MED EXP (Any one person) \$ 10,000 PERSONAL & ADV INJURY \$ 2,000,000 GENERAL AGGREGATE \$ 4,000,000 PRODUCTS - COMP/OP AGG \$ 4,000,000 \$
A	<input checked="" type="checkbox"/> <b>AUTOMOBILE LIABILITY</b> <input checked="" type="checkbox"/> ANY AUTO <input type="checkbox"/> OWNED AUTOS ONLY <input type="checkbox"/> SCHEDULED AUTOS <input checked="" type="checkbox"/> HIRED AUTOS ONLY <input checked="" type="checkbox"/> NON-OWNED AUTOS ONLY		S 2253659	1/18/2025	1/18/2026	COMBINED SINGLE LIMIT (Ea accident) \$ 1,000,000 BODILY INJURY (Per person) \$ BODILY INJURY (Per accident) \$ PROPERTY DAMAGE (Per accident) \$ \$
A	<input checked="" type="checkbox"/> <b>UMBRELLA LIAB</b> <input checked="" type="checkbox"/> OCCUR <input type="checkbox"/> EXCESS LIAB <input type="checkbox"/> CLAIMS-MADE DED RETENTION \$		S 2253659	1/18/2025	1/18/2026	EACH OCCURRENCE \$ 2,000,000 AGGREGATE \$ 2,000,000 \$
B	<b>WORKERS COMPENSATION AND EMPLOYERS' LIABILITY</b> ANY PROPRIETOR/PARTNER/EXECUTIVE OFFICER/MEMBER EXCLUDED? (Mandatory in NH) If yes, describe under DESCRIPTION OF OPERATIONS below Y / N <input checked="" type="checkbox"/> N / A		100003072	1/18/2025	1/18/2026	<input checked="" type="checkbox"/> PER STATUTE <input type="checkbox"/> OTH-ER E.L. EACH ACCIDENT \$ 1,000,000 E.L. DISEASE - EA EMPLOYEE \$ 1,000,000 E.L. DISEASE - POLICY LIMIT \$ 1,000,000
C	Prof & Pollution Liability Leased & Rented		MKLV3ENV104794 S 2253659	8/22/2024 1/18/2025	8/22/2025 1/18/2026	Each Claim 5,000,000 Equipment 25,000

DESCRIPTION OF OPERATIONS / LOCATIONS / VEHICLES (ACORD 101, Additional Remarks Schedule, may be attached if more space is required)

**CERTIFICATE HOLDER****CANCELLATION**Artisan Custom Homes  
21016 Catawba Avenue  
Cornelius NC 28031  
USA

SHOULD ANY OF THE ABOVE DESCRIBED POLICIES BE CANCELLED BEFORE THE EXPIRATION DATE THEREOF, NOTICE WILL BE DELIVERED IN ACCORDANCE WITH THE POLICY PROVISIONS.

AUTHORIZED REPRESENTATIVE

© 1988-2015 ACORD CORPORATION. All rights reserved.


# BIRCHWOOD TRAILS - LOT 74

Project Location  
119 Thunderbird Lane,  
Fuquay Varina, NC 27526  
Harnett County  
PIN: 0642-85-3054

Project Owner  
KB Home  
1800 Perimeter Park Drive, STE 140,  
Morrisville, NC 27560  
919-768-7960  
enpollock@kbhome.com

Project Consultant  
Heath Clapp, LSS, AOWE  
(919) 629-6404  
Jeff Vaughan, LSS, AOWE  
(919) 367-6313  
Agri-Waste Technology, Inc.  
1225 Crescent Green, Suite 250  
Cary, NC 27518  
(919) 859-0669  
(919) 233-1970 Fax

System Overview  
Single Family Residence  
Four (4) Bedroom, 480 gpd  
Conventional Pressure Manifold  
PPBPS T&J Panel (50% Reduction)  
Trench Product



VICINITY MAP

## Sheet Index


Sheet 1	Cover Sheet
Sheet 2	Property Layout
Sheet 3	Primary Drainfield
Sheet 4	Repair Drainfield
Sheet 5	Detail Sheet 1
Sheet 6	Detail Sheet 2



KB Home  
Birchwood Trails - Lot 74  
Project Location:  
119 Thunderbird Lane,  
Fuquay Varina, NC 27526  
Harnett County  
PIN: 0642-85-3054

Project Owner:  
KB Home  
1800 Perimeter Park Drive, STE 140  
Morrisville, NC 27560  
919-768-7960  
enpollock@kbhome.com

NC ONSITE WASTEWATER  
EVALUATOR 304



REV.	ISSUED DATE	DESCRIPTION

SHEET TITLE  
Cover Sheet

DRAWN BY: H. Clapp	CREATED ON: 11/6/2025
REVISED BY: ###	REVISED ON: ###
RELEASED BY: ###	RELEASED ON: ###
DRAWING NUMBER	

WW-1






**KB Home**  
**Birchwood Trails - Lot 74**

Project Location:  
119 Thunderbird Lane,  
Fuquay Varina, NC 27526  
Harnett County  
PIN: 0642-85-3054

**Project Owner:**  
KB Home  
1800 Perimeter Park Drive, STE 14  
Morrisville, NC 27560  
919-768-7960  
enpollack@kbhome.com

NC ONSITE WASTEWATER  
EVALUATOR SEAL

REV.	ISSUED DATE	DESCRIPTION
------	-------------	-------------

100

1000

--

|

--

--	--


SHEET TITLE	
-------------	--

## Property Layout

DRAWN BY: H. Clapp	CREATED ON: 11/6/2025
REVISED BY: #####	REVISED ON: ####
RELEASED BY: #####	RELEASED ON: ####

DRAWING NUMBER

**WW-2**




## PROPERTY LAYOUT

SOURCE: AWT, Inc.



1. Clear all trees less than 8" in diameter (measured at a height 3' from soil surface) from the drainfield.
2. Vegetation that will re-grow from a cut stump shall be stumped or pulled from the ground. Stumps shall not be pushed over.
3. Drainfield area shall be cleared of all leaves, pine straw, debris, etc. The accumulated material shall be removed from the drainfield.
4. In clayey soils, sides of trenches shall be raked and limed per manufacturer's instructions.
5. Supply lines shall be installed with a minimum of 18" cover.
6. The trenches shall be backfilled appropriately so that no low areas are present.
7. Apply lime over the drainfield area as needed. Seed fine fescue over the drainfield at the rate recommended by the seed manufacturer. Hand rake the seed into the soil surface. Straw the seeded area at the rate of 1.5-2 bales per 1000 sq. ft.

Primary distribution is pressure manifold utilizing PPBPS T&J Panel (50% Reduction) trench product.

[illegible]


**SOURCE:** Agr-Waste Technology, Inc.

1. Clear all trees less than 8" in diameter (measured at a height 3' from soil surface) from the drainfield.
2. Vegetation that will re-grow from a cut stump shall be stumped or pulled from the ground. Stumps shall not be pushed over.
3. Drainfield area shall be cleared of all leaves, pine straw, debris, etc. The accumulated material shall be removed from the drainfield.
4. In clayey soils, sides of trenches shall be raked and limed per manufacturer's instructions.
5. Supply lines shall be installed with a minimum of 18" cover.
6. The trenches shall be backfilled appropriately so that no low areas are present.
7. Apply lime over the drainfield area as needed. Seed fine fescue over the drainfield at the rate recommended by the seed manufacturer. Hand rake the seed into the soil surface. Straw the seeded area at the rate of 1.5-2 bales per 1000 sq. ft.


Site plan of the Anaerobic Drip Repair Area (System Type Vd). The plan shows the building footprint, property line setback, and various survey points (SB 1 through SB 10). The building is labeled with 74, 25,319 SF, and 0.581 AC. The area is approximately 4,100 sq. ft. The plan includes a scale bar (0 to 40 feet) and a north arrow.

Key features and labels:

- Anaerobic Drip Repair Area (System Type Vd):** Approximately 4,100 sq. ft.
- Building Footprint:** Labeled with 74, 25,319 SF, and 0.581 AC.
- Property Line Setback:** 10' Property Line Setback.
- Survey Points:** SB 1, SB 2, SB 3, SB 4, SB 5, SB 6, SB 7, SB 8, SB 9, SB 10.
- Scale:** 0 to 40 feet.
- North Arrow:** Indicated by an arrow pointing towards the top of the plan.



**SOURCE:** Agri-Waste Technology, Inc.




## Septic Tank

**SOURCE:** Shoaf Precast Septic, Inc.

## NOTES

1. Installation to follow all NC DHHS and Harnett County applicable rules and regulations.
2. Harnett County Health Department to perform construction inspections and final system certification.
3. Septic Tank to have approved effluent filter.
4. Contractor to abide by all safety regulations during system installation.
5. Contractor shall backfill around all access areas such that storm water is shed away from potential entry points.
6. Invert elevations of all components to be verified in field by contractor to insure proper operation.
7. All system piping to be SCH40 PVC (except where noted).
8. All gravity elbows to be long radius or long sweeping type elbows.
9. Actual installation and placement of treatment system to be overseen by Contractor.
10. Tanks to be set on 6" minimum gravel base. Use #5 or #57 stone for base.


Access Riser to Extend 6 Inches Above Finished Grade.



FOR RISER WALL PENETRATIONS		
Grommet Size, Inches (Nominal IPS Pipe Size)	Hole Saw Size, Inches	
1/2	1	
3/4	1 1/4	
1	1 9/16	
1 1/4	1 3/4	
1 1/2	2 1/8	
2	2 3/4	
3	3 7/8	
4	4 1/2	

## Riser Installation

9-11



**Pump Tank (or equiv. tank with 1-day storage)**

**SOURCE:** Shoaf Precast Septic, Inc.

1. Contractor to seed and/or mulch disturbed areas to coincide with existing landscape. Area shall not be left with uncovered soil.
2. Mount Control Panel a minimum of 24" above grade.
3. Power to panel to be installed by licensed electrician per code. One 15-amp circuit and one 20-amp circuit with individual neutrals to be run from house to control panel.
4. All risers to have cast-in-place tank adapters and be single-piece riser. Risers to extend 6" above soil surface and be designed to prevent surface water inflow.
5. Backfill around tank(s) shall be gravel or tank hole shall be over-excavated a minimum of 2' in all directions to allow for mechanical tamping of backfill.
6. All penetrations to be sealed.
7. All pressure lines to maintain 18" min. cover.
8. Contractor to adjust tank placement to meet site constraints.


All penetrations to be sealed.

All pressure lines to maintain 18" min. cover.


Contractor to adjust tank placement to meet site constraints.

REV.	ISSUED DATE	DESCRIPTION


SHEET TITLE	
Detail Sheet 2	
DRAWN BY: H. Clapp	CREATED ON: 11/6/2025
REVISED BY: ###	REVISED ON: ###
RELEASED BY: ###	RELEASED ON: ###
DRAWING NUMBER	




1 SYSTEM PROFILE VIEW  
 N.T.S.



2 PRESSURE MANIFOLD INSTALLATION (Manitec) - For Illustration Only  
 N.T.S. SOURCE: AWT



6 CONTROL PANEL SUPPORT  
 N.T.S. SOURCE: AWT



7 TRENCH X-SECTION (Typical)  
 N.T.S. SOURCE: AWT

## Septic System Design - Summary Page



Agri-Waste Technology, Inc.  
501 N Salem Street, Suite 203, Apex, NC 27502  
agriwaste.com | 919.859.0669

### Project Manager:

Heath Clapp, LSS  
hclapp@agriwaste.com  
919-629-6404

### Designer:

Heath Clapp, LSS  
hclapp@agriwaste.com

**Project:** Birchwood Trails - Lot 74

**Date:** 10/6/2025

**Property:** 119 Thunderbird Lane,  
Fuquay Varina, NC 27526

**County:** Harnett

**Subdiv.:** Birchwood Trails

**Lot #:** 74

**Permit #:**

**Owner:** KB Home

**Address:** 1800 Perimeter Park Drive, STE 140  
Morrisville, NC, 27560

**Type of System:** III b

**Phone:** 919-768-7960

**Email:** enpollock@kbhome.com

**PIN:** 0642-85-3054

**EHS:**

## Soil Parameters

### Soil Evaluation By:

Heath Clapp, LSS

### Special Conditions/Notes:

**LTAR:** 0.30 gpd/ft<sup>2</sup>

## Design Parameters

**Type of Establishment:** Dwelling Units, no more than 2 persons per bedroom

**Unit:** Bedroom

**# of Units:** 4

## Septic Tank Specifications

**Min. Tank Capacity:** 960 gal

**Actual Tank Volume:** 1,250 gal

**Tank Manufacturer:** Shoaf

**Tank Model:** TS 1250 STB

	Exterior	Interior
<b>Length:</b>	125.5	119.5 in.
<b>Width:</b>	65.5	59.5 in.
<b>Depth:</b>	61.5	54.5 in.

## Primary Drainfield Specifications

**Type of Distribution:** Parallel Pressure Manifold

**Trench Media:** PPBPS, Horizontal

**Trench Width:** 3 ft

**Trench Depth:** 20 in.

(or as specified on permit)

**Trench Bottom Area:** 1600 ft<sup>2</sup>

**Minimum Drain Line:** 267 ft

**Actual Drain Line:** 275 ft

**Number of Lines:** 7

**Minimum Line Spacing:** 8 ft O.C.

## Wastewater Treatment System Design Calculations

**Project:** Birchwood Trails - Lot 74

**Location:** 119 Thunderbird Lane,  
Fuquay Varina, NC 27526

**County:** Harnett

### Septic Tank Sizing

---

Daily Flow Estimate:

Unit	# of Units	Flow/Unit	Flow/Day
Bedroom	4	120	480
Q=			480 gpd

Septic Tank Minimum Capacity:

Per NCAC T15A:18A .1952(b)(2)(A):

For large residences, multiple dwelling units, or places of business or public assembly with  $Q \leq 600$ ,

Minimum Liquid Capacity (V)= 960 gal

Septic Tank Specs:

Manufacturer: Shoaf

Model: TS 1250 STB

Volume: 1,250 gal

Weight: 11,000 lbs

	Exterior	Interior	
Length:	125.5	119.5	in.
Width:	65.5	59.5	in.
Depth:	61.5	54.5	in.

Shape of Risers: Circular

Diameter: 2.00 ft



## Pump Tank Storage & Float Settings

**Project:** Birchwood Trails - Lot 74

**Location:** 119 Thunderbird Lane,  
Fuquay Varina, NC 27526

**County:** Harnett

Tank Manufacturer

Shoaf

Tank Model

TS 1275 PT

<b>Interior Height (in.)</b>	<b>60.5 in.</b>
<b>Avg. Storage</b>	<b>21.07 gal/in.</b>

### **Primary System**

#### **Elevations, measured from bottom towards top (0 = Interior Bottom of Tank):**

Top of pump (including 4" block)	16.1 in.	(Pump height = 12 1/16")
Pump Off	18.0 in.	
Pump On	29.0 in.	(set for dose volume)
Alarm On	35.0 in.	(6 in. above On Float)

Emergency Storage Available

Pump Tank 537 gal

Days of Storage 1.12 days

(determined from "interior top of tank" - "High Water Alarm")

## ELEVATIONS

**Project:** Birchwood Trails - Lot 74

**Location:** 119 Thunderbird Lane,  
Fuquay Varina, NC 27526

**County:** Harnett

**Benchmark** 0  
**BM Elev** 0 ft

**Septic Tank** 1,250 gal

Ground Surface		294.00 ft
Depth of Soil Cover	12 in.	1.00 ft
Overall Ht of Tank	61.5 in.	5.13 ft
Elev, Base of Tank		287.88 ft
Ht to 4" Inlet Invert	50 in.	4.17 ft
Elev, 4" Inlet Invert		292.04 ft
Ht to 4" Outlet Invert	48 in.	4.00 ft
Elev, 4" Outlet Invert		291.88 ft
Gravel Base	6 in.	0.50 ft
Elev, Bot of Excavation		287.38 ft

**Pump Tank** 1287 gal

Ground Surface		293.50 ft
Depth of Soil Cover	16 in.	1.33 ft
Overall Ht of Tank	67.5 in.	5.63 ft
Elev, Base of Tank		286.54 ft
Ht to 4" Inlet Invert	57 in.	4.75 ft
Elev, 4" Inlet Invert		291.29 ft
Ht to 2" Outlet Invert	54.5 in.	4.54 ft
Elev, 2" Outlet Invert		291.08 ft
Gravel Base	6 in.	0.50 ft
Elev, Bot of Excavation		286.04 ft

**ST Inlet Pipe**

Grade @ Stub-out		296 ft
Depth of Stub-out, top		1.5 ft
Elev, Stub-out Invert		294.15 ft
Elev @ ST Inlet Invert		292.04 ft
Length		21 ft
Slope		10.0 %

**Pipe, ST to PT**

ID	4 in.	0.33 ft
OD	4.5 in.	0.38 ft
Elev, ST Outlet Invert		291.88 ft
Elev, PT Inlet Invert		291.29 ft
Length		2 ft
Slope		29.2 %
Cover over inlet pipe		1.60 ft

**Pump Reqmt.**

Floor Thickness	4 in.	0.33 ft
Elev, Pump Tank Floor		286.88 ft
Pump Block Ht.	4 in.	0.33 ft
Elev, Pump Intake		287.21 ft

Grade @ Primary Manifold		296.30 ft
Min. Cover	18 in.	1.50 ft
Max Elev, Primary		294.80 ft
Max Elev, Repair		294.50 ft
Elev Diff, Primary		7.59 ft
Elev Diff, Repair		7.29 ft

Drainfield Design

Project Birchwood Trails - Lot 74  
Location 119 Thunderbird Lane,  
Fuquay Varina, NC 27526  
County Harnett

Drainfield Sizing

Primary			
LTAR	0.3 gpd/ft <sup>2</sup>		
Daily Design Flow	480 gpd	Type of Drainfield Media	PPBPS, Horizontal
Req. Drainfield Area	1,600 ft <sup>2</sup>	Required Drainline	
Trench Width, Eff.	3 ft	After 50% Reduction	267 ft
Required Drainline	533 ft	Minimum Line Spacing	8 ft (O.C.)
Repair			
LTAR	0.15 gpd/ft <sup>2</sup>		
Daily Design Flow	480 gpd	Type of Drainfield Media	Drip
Req. Drainfield Area	3,200 ft <sup>2</sup>	Required Drainline	
Trench Width, Eff.	2 ft	After 0% Reduction	1600 ft
Required Drainline	1600 ft	Minimum Line Spacing	2 ft (O.C.)

Drainfield Layout

Line	Use	Flag Color	Elevation (ft)	Line Length (ft)	Used as Primary (ft)	Used as Repair (ft)
1	Layout Line	interp		31	31.0	
2	Layout Line	interp		31	31.0	
3	Layout Line	interp		31	31.0	
4	Layout Line	interp		31	31.0	
5	Layout Line	interp		45	45.0	
6	Layout Line	interp		45	45.0	
7	Layout Line	interp		61	61.0	
Total				275	275	0
Count				7	7	0

Note: Line length totals are shown to the nearest foot.

## PRESSURE MANIFOLD DESIGN (Primary)

### Site Information

**Project:** Birchwood Trails - Lot 74  
**Location:** 119 Thunderbird Lane,  
 Fuquay Varina, NC 27526  
**County:** Harnett

### Design Information

Estimated Daily Flow	480 gal/day
L.T.A.R. (from Harnett Co.)	0.3 gal/day/ft <sup>2</sup>
L.T.A.R. + 5%	0.315 gal/day/ft <sup>2</sup>
Trench Width	3 ft.
Line Length Required	533 ft.
Length after 50% Reduction	267 ft
L.T.A.R. Reduced	0.600 gal/day/ft <sup>2</sup>
L.T.A.R. Reduced + 5%	0.630 gal/day/ft <sup>2</sup>

<b>DRAINFIELD INFO. - Primary</b>						
Proposed Type of System/Distribution: <b>Pump to Pressure Manifold</b> using PPBPS, Horizontal						
Line No.	Flag Color	Line Length (ft)	Tap	Flow (gpm)	Flow/Foot (gpm/ft)	Line L.T.A.R.
1	interp	31	1/2in SCH 80, Split	2.74	0.088	0.601
2	interp	31	1/2in SCH 80, Split	2.74	0.088	0.601
3	interp	31	1/2in SCH 80, Split	2.74	0.088	0.601
4	interp	31	1/2in SCH 80, Split	2.74	0.088	0.601
5	interp	45	1/2in SCH 40, Split	3.56	0.079	0.537
6	interp	45	1/2in SCH 40, Split	3.56	0.079	0.537
7	interp	61	1/2in SCH 80	5.48	0.090	0.610
<b>Total</b>		<b>275</b>	<b>Total</b>	<b>23.55</b>	<b>Avg.</b>	<b>0.58</b>
#N/A						

Total Run Time	20.38 min.
Drainfield Capacity	446.4 gal
% of Drainfield Cap	51.9% (Max. 98.4% to not exceed 7.2 gal/panel)
Dose Volume	231.7 gal/dose
<b>Run Time/Dose</b>	<b>9.8 minutes</b>
Volume/depth	21.07 gal/in. (Time to deliver max. 3.6 gal/panel)
Estimated Drawdown	11.00 in. (Per tank manufacturer's specifications)

<b>Manifold Box</b>			
Number of Taps	4	with	3 Split(s)
Manifold Length	3.5	ft.	(approximate)

## PUMP DESIGN

System (initial/repair): **Primary**

**Project:** Birchwood Trails - Lot 74  
**Location:** 119 Thunderbird Lane,  
Fuquay Varina, NC 27526  
**County:** Harnett

### Friction Losses

Suction Head	0 ft	(submersible 0)
Elev. Difference (highest point from pump)	7.59 ft	
Design Pressure At Outlet	2 ft	
<b>Supply Line - 2" Schedule 40 PVC</b>		
Pipe Diameter, Nominal	2 in.	
Pipe Diameter (ID)	2.047 in.	Flow 23.55 gpm
Pipe Length	277 ft	Velocity 2.30 ft/sec
Pipe Length for Fittings	27.7 ft	Meets requirement that 2 ft/s < v < 5 ft/s.
Equivalent Length	304.7 ft	
Estimated Friction Loss in Supply Line	3.18 ft	
Friction Loss - Taps/Special Fittings	3.5 ft	
<b>TOTAL</b>		<b>16.27 ft.</b>

Flow for Anti-Siphon Hole


Hole Diameter 3/16 in.  
Hole Flowrate 1.67 gpm

Pump Efficiency 0.7 (assumed, typical)  
Motor Efficiency 0.9 (assumed for electric pumps)  
**Flow 25.22 gpm**

**Required Horsepower 0.16 hp**  
**TDH 16.27 ft**

### Pump Selection

Manufacturer:	Zoeller
Model:	N98
Horsepower:	0.5



## Septic Tank Buoyancy Calculation

**Project:** Birchwood Trails - Lot 74  
**Location:** 119 Thunderbird Lane,  
 Fuquay Varina, NC 27526  
**County:** Harnett

Tank Size (nominal) 1250 gal

### Properties/Assumptions:

Min. liquid level to be maintained in tank at all times after initial installation.

Min. depth to water table	12.0 in.	from ground surface
Effluent Density	62.4 lb/ft <sup>3</sup>	(Specific Weight of Water)
Concrete Density	142.6 lb/ft <sup>3</sup>	
Soil App. Sp. Grav.	1.3	(typical value)
Soil Cover Over Tank	12 in.	(minimum)
Additional Cover	0 in.	for pipe grade
Unsubmerged wt of soil	81.1 lb/ft <sup>3</sup>	
Submerged wt of soil	49.9 lb/ft <sup>3</sup>	50% Porosity Assumed

### Tank Dimensions (from supplier):

		<u>Exterior</u>		<u>Interior</u>	
		Top	Bottom	Top	Bottom
Tank	Length	125.5	122.0	119.5	116.0 in.
	Width	65.5	62.0	59.5	56.0 in.
	Height	58.5	(w/o lid)	54.5	in.
Lid	Length	125.5 in.			
	Width	65.5 in.			
	Height	3.0 in.			
Area of Riser Openings		6.28 ft <sup>2</sup>			
Permanent Liquid Depth in Tank		0.0 in.		0.00 ft	
Tank Weight		11,000 lb		(per manufacturer)	

### Buoyancy Force Calculation:

Buoyancy Force Specific Weight of Water x Displaced Volume

Displaced Volume	281.4 ft <sup>3</sup> *
<b>Buoyancy Force</b>	<b>17,558 lb.</b>

### Weight Calculation:

Tank Weight	11000 lb		
Water Weight in Tank	0 lb	Volume	0.0 ft <sup>3</sup> *
Soil Weight Over Tank	4121 lb		
Soil Friction Force	4037 lb		
<b>Total Weight</b>	<b>19,158 lb</b>		

**Factor of Safety = 1.09**

Note: Total weight must be greater than buoyancy force so that tank will not float during high water table conditions.

\* Volume calculated by the prismoidal formula.



## Pump Tank Buoyancy Calculation

**Project:** Birchwood Trails - Lot 74  
**Location:** 119 Thunderbird Lane,  
 Fuquay Varina, NC 27526  
**County:** Harnett

Tank Size (nominal) 1287 gal

### Properties/Assumptions:

Min. liquid level to be maintained in tank at all times after initial installation.

Min. depth to water table	12 in.	from ground surface
Effluent Density	62.4 lb/ft <sup>3</sup>	(Specific Weight of Water)
Concrete Density	142.6 lb/ft <sup>3</sup>	
Soil App. Sp. Grav.	1.3	(typical value)
Soil Cover Over Tank	12 in.	(minimum)
Additional Cover	4 in.	for pipe grade
Unsubmerged wt of soil	81.1 lb/ft <sup>3</sup>	
Submerged wt of soil	49.9 lb/ft <sup>3</sup>	50% porosity assumed

### Tank Dimensions (from supplier):

		<u>Exterior</u>		<u>Interior</u>	
		Top	Bottom	Top	Bottom
Tank	Length	108.0	104.0	102.0	98.0 in.
	Width	58.0	54.0	52.0	48.0 in.
	Height	64.5	(w/o lid)	60.5	in.
Lid	Length	108.0 in.			
	Width	58.0 in.			
	Height	3.0 in.			
Area of Riser Openings		3.14 ft <sup>2</sup>			
Permanent Liquid Depth in Tank		0.0 in.		0.00 ft	
Tank Weight		10500 lb		(per manufacturer)	

### Buoyancy Force Calculation:

Buoyancy Force Specific Weight of Water x Displaced Volume

Displaced Volume	233.5 ft <sup>3</sup> *
<b>Buoyancy Force</b>	<b>14,573 lb</b>

### Weight Calculation:

Tank Weight	10500 lb		
Water Weight in Tank	0 lb	Volume	0.0 ft <sup>3</sup> *
Soil Weight Over Tank	3945 lb		
Soil Friction Force	4227 lb		
<b>Total Weight</b>	<b>18,672 lb</b>		

**Factor of Safety = 1.28**

Note: Total weight must be greater than buoyancy force  
 so that tank will not float during high water table conditions.

\* Volume calculated by the prismoidal formula.