| Permit/File #: | |
|----------------|--|
| | |



ROY COOPER • Governor

KODY H. KINSLEY • Secretary

MARK BENTON • Chief Deputy Secretary for Health

SUSAN KANSAGRA • Assistant Secretary for Public Health

Division of Public Health

| Submittal Includes: | (a2) Improvement Permit | (a2) Construction Authorization | tion | |
|-----------------------------|-----------------------------------|--------------------------------------|----------------------------------|-----------------------------|
| | IMPROVEN | MENT PERMIT FOR G.S. 130 | A-335(a2) | |
| County: | | | | |
| | | | | |
| | | | | |
| | | | | |
| Subdivision (if applicable | .) | Lot #: | Block: | Section: |
| LSS Report Provided: Ye | s No 🗌 | | | |
| If yes, name and license | number of LSS: | | | |
| New 🗌 | Expansion | System Relocation | Change of Use | : <u> </u> |
| Facility Type: | | | | |
| Number of bedrooms: | Number of Occupants: | Other: | | |
| Design Wastewater Stre | ngth: Domestic | High Strength | ndustrial Process Wastewater | - |
| Proposed Design Daily Fl | ow: GPD | Proposed LTAR (Initial): | Proposed LTAR (Repair): | |
| Proposed Wastewater Sy | /stem Type*: | (Initial) Pun | np Required: 🗌 Yes 📗 No | ☐ May be required |
| Proposed Wastewater Sy | ystem Type*: | (Repair) Pun | np Required: 🗌 Yes 🔲 No | May be required |
| *Please include system c | lassification for proposed waster | water system types in accordance wit | h Rule .1301 Table XXXII | |
| Effluent Standard: | DSE HSE NSF/ANSI 4 | 0 TS-I TS-II RCW | | |
| Saprolite System (Initial) | : Yes No Saprolit | te System (Repair): 🗌 Yes 📗 No | | |
| Fill System (Initial): 🔲 Y | es 🔲 No If yes, specify: 🗌 Ne | ew Existing (when adding more | than 6 inches of fill to system | n area provide a fill plan) |
| Fill System (Repair): 🔲 ነ | res No If yes, specify: N | lew Existing (when adding more | than 6 inches of fill to syster | n area provide a fill plan |
| Usable Depth to LC (Initi | al) ^x : | Usable Depth to LC (Repair)x: | × Limiting Co | ondition |
| Max. Trench Depth (Initi | al)‡: Max. Tr | rench Depth (Repair)‡: | [‡] Measured on the dow | nhill side of the trench |
| Artificial Drainage Requi | red: 🗌 Yes 🔲 No If yes, plea | se specify details: | | |
| Type of Water Supply: | Private well Public well | Shared well Municipal Sup | oply Spring Othe | er: |
| Drainfield location meet | s requirements of Rule .0508: Ye | es 🔲 No 🔲 Drainfield location r | neets requirements of Rule .0 | 0601: Yes |
| Permit valid for: Five | years [site plan submitted pursu | uant to GS 130A-334(13a)] 🔲 No ex | piration [plat submitted purs | uant to GS 130A-334(7a |
| Permit conditions: | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| Licensed Soil Scientist Pr | int Name: | | | |
| Licensed Soil Scientist Sig | gnature: Ha | eath Clapp | Date: | |

The LSS evaluation is being submitted pursuant to and meets the requirements of G.S. 130A-335(a2).



| Permit/File #: | |
|----------------|--|
|----------------|--|

This Section for Local Health Department Use Only

| initiai submittai received: | | Dy | |
|---|--|---|--|
| | Date | Initials | |
| G.S. 130A-335(a3) states the following: | | | |
| When an applicant for an Improvement Permit submits to a local health depart department, the common form developed by the Department, and a soil evaluation, the common form developed by the Department, and a soil evaluation, it is to complete the service of the end of the required components. If the local health department shall notify the applicant of the components needed to complete the Improved department to cure the deficiencies in the Improvement Permit. The local health sis complete within five business days after the local health department received act within any period set out in this subsection, the applicant may treat the factorism form for use as the Improvement Permit. | uation pursuant to sul review of the submit determines that the ment Permit. The app Ith department shall i es the additional infor | ssection (a2) of this section, the local health depart cal. A determination of completeness means that the improvement Permit is incomplete, the local health licant may submit additional information to the local make a final determination as to whether the Impro mation from the applicant. If the local health depa | ment shall, ne Improvement department al health ovement Permit rtment fails to |
| The review for completeness of this Improvement Permit was Permit is determined to be: | conducted in acc | ordance with G.S. 130A-335(a3). This In | iprovement |
| ☐ Incomplete (If box is checked, information in this section i | is required.) | | |
| The following items are missing: | | | |
| | 5 | | |
| Copies of this were sent to the LSS and the Applicant on | Date | | |
| State Authorized Agent: | | Date: | |
| ☐ Complete | | | |
| State Authorized Agent: | -1/-09 | Date: | |
| This Improvement Permit is issued pursuant to G.S. 130A-335 attached here. The issuance of this permit in no way guarant for checking with appropriate governing bodies in meeting the plat, or the intended use changes. The Improvement Permit permit is subject to compliance with the provisions of 15A No. The Department, the Department's authorized agents, and the liabilities, duties, and responsibilities imposed by statute evaluations, submittals, or actions from a licensed soil scient | tees the issuance heir requirement shall not be affe CAC 18E and to the local health decor in common le | of other permits. The permit holder is s. This permit is subject to revocation if cted by a change in ownership of the sit ne conditions of this permit. Expartments shall be discharged and release from any claim arising out of or attri | responsible the site plan, e. This ased from |
| Improvement Permit Expiration Date: | | | |
| | | | |
| | | | |

See attached site sketch



| Permit/File #: | e #: |
|----------------|------|
|----------------|------|

Re-submittal of Improvement Permit

| | LHD USE ONLY: This IP resubmittal receiv | ved: | by | _ |
|------------------|--|------------------------|-------------------------------|--------------------|
| The following it | tems are being resubmitted pursuant to G.S. 13 | 30A-335(a3) for issuar | nce of the Improvement Perr | mit: |
| | | | | |
| | J. LE | SIATE | All Control | |
| s accurate and | hereby att Scientist (Print Name) complete to the best of my knowledge and th laws, regulations, rules, and ordinances. | | on required to be included v | |
| Signatur | e of Licensed Soil Scientist | | Date | |
| HD Follow I | The section below is for Local Health Departn up Completeness Review of Improven | | of items noted as missing abo | ve. |
| The review for o | completeness of this Improvement Permit re-sermit is determined to be: | | ted in accordance with G.S. | 130A-335(a3). This |
| | (If box is checked, information in this section ems are missing: | is required.) | | |
| | | | | |
| Copies of this w | vere sent to the LSS and the Applicant on | Date | | |
| State Authorize | d Agent: | | Date: | |
| ☐ Complete | | | | |
| State Authorize | d Agent: | | Date: | |



| Permit/File #: |
|----------------|
|----------------|

CONSTRUCTION AUTHORIZATION FOR G.S. 130A-335(a2)

| County: | | | Pre-Construct | tion Conference | ce Required: Yes 🔲 No 🗌 | |
|-------------------------------------|---|--|--|--|---|--------|
| PIN/Lot Identifie | er: | | | | | |
| Issued To: | | | | | | |
| Property Locatio | on: | | | | | |
| AOWE/PE Plans/ | Evaluations Provide | d: Yes 🔲 No 🗌 | If yes, name and license n | umber of AOV | NE/PE: | |
| Facility Type: | | | | | | |
| Number of bedro | ooms: Num | nber of Occupants: _ | Other: | | | |
| New | Expansion | Repair | System Relocation | Ch | ange of Use | |
| Basement? | Yes | ☐ No | Basement Fixtures? | Yes | □ No | |
| Crawl Space? | Yes | ☐ No | Slab Foundation? | Yes | □ No | |
| Type of Wastewa | ater System* | | (Initia | l) | (Re | epair) |
| *Please include s | system classification | for proposed waste | water system types in acc | ordance with | Rule .1301 Table XXXII | |
| | w: 4-120 Section 53, Er | | stewater Strength: Dortilizing Low-flow Fixtures a | | / I / - / / / | 1 |
| | ovide engineering de | | | _ | | |
| | <u> </u> | <i>∞z/ k</i> | IO TS-I TS-II | | 7.04// | |
| Type of Water Su | upply: Private we | ell Public well | Shared well | 1unicipal Supp | oly Spring Other: | |
| Installation Requ | uirements/Conditio | <u>ns</u> | | | | |
| | | | | | Spacing: feet on center | |
| Trench/Bed Wid | th: inches | LTAR: | gpd/ft ² Usable | Depth to LC (| Initial) ^x : ^x Limiting condition | n |
| Soil Cover: | _ inches Slope C | Corrected Maximum | Trench/Bed Depth [‡] : | inches | * Measured on the downhill side of the trenc | h |
| Pump Tank Size | (if applicable): | gallons | Requires more than 1 | pump? 🗌 Ye | s 🗌 No | |
| Pump Requirem | ents: ft. TDH | l vs GPM | Grease Trap Size (if ap | plicable): | gallons | |
| Distribution Met | thod: Serial | D-Box or Parallel | Pressure Manifold(s | ;) | Other: | |
| Artificial Drainag | ge Required: Yes 🗌 | No If yes, ple | ase specify details: | | | |
| <u>Legal Agreemen</u> | i <mark>ts</mark> (If the answer is " | Yes" to any type of I | legal agreements, please d | attach a copy o | of the agreement.) | |
| Multi-party Agre | eement Required [.02 | 204(g)]: Yes | ☐ No De | eclaration of R | estrictive Covenants: Yes No | |
| Easement, Right- | of-Way, or Encroac | hment Agreement R | equired [.0301(b)]: 🗌 Ye | s No | | |
| Management En | itity Required: 🔲 Y | es 🗌 No Minimu | ım O&M Requirements: _ | MDE | | |
| Permit conditi | ions: | | | | | |
| | | | | | | _ |
| | | | | | | _ |
| | | | | | | _ |
| | | | | | | |
| with the attache Construction Au | ed site sketch. <i>This</i> thorization shall no | Construction Author t be affected by a cl | rization is subject to revo | <i>cation if the si</i> e site. This Co | e met. Systems shall be installed in accordanc ite plan, plat, or the intended use changes. The Instruction Authorization is subject to complia ions of this permit. | e |
| AOWF/PF Print N | Name: | - | | | | |
| | ture: | UIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIII | Clarps | ——— Dat | e: | |
| | | 1 0000 | | | ·· | |

This AOWE/PE submittal is pursuant to and meets the requirements of G.S. 130A-335(a2) and (a5).

See attached site sketch



| Permit/File #: |
|----------------|
| |

This Section for Local Health Department Use Only


| | Initial submittal received: | | by |
|--|---|---|---|
| | | Date | Initials |
| G.S. 130A-335(a5) states the follo | wing: | | |
| mprovement Permit and Construction Aut Department, and any necessary signed and engineer or a person certified pursuant to a department shall, within five business days the Construction Authorization or Improve determines that the Construction Authoriza applicant of the components needed to con additional information to the local health of Authorization. The local health departmen department fails to act within any period s apply for the building permit for the project Authorization by the local health departmen ficensed engineer submitting the evaluatio | horization application together, the pend sealed plans or evaluations conducted Article 5 of Chapter 90A of the General is of receiving the application, conduct a ment Permit and Construction Authorization or Improvement Permit and Construction Fundament to cure the deficiencies in the shall make a final determination as to ess days after the local health department to ut in this subsection, the applicant at upon the decision of completeness of ent or if the local health department fair newsuant to this subsection may requive Construction Authorization for cause. Ususpend or revoke the Construction All | rmit fee charged by the of by a person licensed pure Statutes as an Authoriza a completeness review of ation includes all of the truction Authorization is or Improvement Permit and the Construction Authorization to whether the Construction and treat the failure to the Construction Authorials to act within five business that the local health Upon written request of uthorization or Improver | ration together, submits a Construction Authorization, or an allocal health department, the common form developed by the arsuant to Chapter 89C of the General Statutes as a licensed and On-Site Wastewater Evaluator, the local health of the submittal. A determination of completeness means that required components. If the local health department incomplete, the local health department shall notify the and Construction Authorization. The applicant may submit reation or Improvement Permit and Construction on Authorization or Improvement Permit and Construction and information from the applicant. If the local health act as a determination of completeness. The applicant may rization or Improvement Permit and Construction and Says. The Authorized On-Site Wastewater Evaluator or department revoke or suspend the Construction the Authorized On-Site Wastewater Evaluator or licensed ment Permit and Construction Authorization pursuant to G.S. |
| The review for completeness of th | is Construction Authorization v | was conducted in a | ccordance with G.S. 130A-335(a5). This |
| Construction Authorization is dete | ermined to be: | | |
| ☐ Incomplete (If box is checked, | , information in this section is r | equired.) | |
| The following items are missing: _ | | 1 | |
| 1/1 CZ | | | |
| Copies of this were sent to the AC | WF/PF and the Applicant on | 11 | |
| 30p.00 0. u | | Date | |
| State Authorized Agent: | | 1.484/10 | Date: |
| 7// | My Children | | |
| Complete | | | |
| State Authorized Agent: | M XV | . 12.17 | Date of Issuance: |
| attached here. This Construction Construction Authorization shall to compliance with the provision The Department any liabilities, duties, and responolans, evaluations, preconstructions. | Authorization is subject to rev not be affected by a change in s of the Laws and Rules for Sev t's authorized agents, and the sibilities imposed by statute of on conference findings, submit | ocation if the site p ownership of the s wage Treatment an local health depart r in common law fr stals, or actions fro | sing the signed and sealed plans or evaluations plan, plat, or the intended use changes. The lite. This Construction Authorization is subject d Disposal and to the conditions of this permit. ments shall be discharged and released from om any claim arising out of or attributed to ma person licensed pursuant to Chapter 89C of e 5 of Chapter 90A of the General Statutes as an |
| Authorized On-Site Wastewater E | Evaluator in GS 130A-335(a2), (rtments shall be responsible a | (a5), and (a7). The l nd bear liability for | Department, the Department's authorized their actions and evaluations and other |
| Construction Authorization Expira | ation Date: | | |
| | | | |



| Permit/File #: |
|----------------|
|----------------|

Re-submittal of Construction Authorization

| | LHD USE ONLY: Th | nis CA resubmittal received: | Date | by Initials | - |
|------------------|---|--|-------------------------|-----------------------------|---------------------|
| The following i | tems are being resubm | itted pursuant to G.S. 130A-3 | 335(a5) for issuance of | of the Construction Author | ization: |
| | | | | | |
| | | | AT | <i>3</i> - | |
| 1 | | herehy attest ti | hat the information r | equired to be included wit | h this re-suhmittal |
| is accurate and | | (Print Name) of my knowledge and that thoons, rules, and ordinances. | | | |
| Signatui | re of Authorized On-Site Was | tewater Evaluator | 4 | Date | |
| | | ร for Local Health Department เ | | ems noted as missing above. | |
| LHD Follow- | up Completeness R | Review of Construction | Authorization | | |
| | completeness of this C on Authorization is det | onstruction Authorization re ermined to be: | -submittal was condu | ucted in accordance with G | i.S. 130A-335(a5). |
| ☐ Incomplete | (If box is checked, info | rmation in this section is req | uired.) | | |
| The following it | ems are missing: | | | | |
| | | JUNE ON | M AIDER | J. | |
| Copies of this w | vere sent to the AOWE | /PE and the Applicant on | Date | - | |
| State Authorize | ed Agent: | | | Date: | |
| ☐ Complete | | | | | |
| State Authorize | ed Agent: | | | Date: | |





ADDENDUM TO G.S. 130A-335(a2) SUBMITTAL

| County: | |
|---|--|
| PIN/Lot Identifier: | |
| Issued To: | |
| Additional Improvement Permit Conditions: | |
| | |
| E STATE | |
| | |
| 6 N N 1 30 1 - 5 N N | |
| | |
| | |
| | |
| Net - Y S/M Elizable 2 / Vene O M | |
| | |
| | |
| | |
| Additional Construction Authorization Conditions: | |
| 10RH 12 1776 | |
| White Tell I | |
| QUAM VI | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

7



Agri-Waste Technology, Inc.
1225 Crescent Green, Suite 250, Cary NC 27518
agriwaste.com | 919.859.0669



Soil Suitability for Domestic Sewage Treatment and Disposal Systems Birchwood Trails – Lot 75 106 Thunderbird Lane, Fuquay Varina, NC 27526 (Harnett County)

October 8, 2025

Soil suitability for domestic sewage treatment and disposal systems was evaluated on October 1, 2025, for the property located at 106 Thunderbird Lane in Fuquay Varina, NC (Harnett County). Heath Clapp of Agri-Waste Technology, Inc. (AWT) conducted the soil evaluation. This evaluation was done to facilitate permitting for a septic system for a 4-bedroom home. This report and attached documents were prepared to this application is to be used to issue an Improvement Permit in accordance with G.S. 130A-335(a2) and (a3). The LSS evaluation is being submitted pursuant to and meets the requirements of G.S. 130A-335(a2).

A drawing of the site plan, septic layout, septic system design, and soil pit locations is included in Attachment 1. Profile descriptions for each soil boring are included in Attachment 2.

The total property area is approximately 0.56 acres. The house and septic area are an open field. The proposed septic system for the property is a conventional pump, accepted status system for initial and conventional pump, PPBPS T&J Panel system for repair.

Soil Suitability for Domestic Sewage Treatment and Disposal Systems

The drawing in Attachment 1 details the property boundaries, soil pit/boring locations, and layout of drain field trenches. Multiple soil pits and borings were advanced within the proposed septic system area on the property. Soil pits/borings were examined to determine soil suitability for on-site sewage disposal systems in accordance with 15A 18A .1900 Rules for Sewage Treatment and Disposal Systems. All soil pits/borings are suitable for a conventional style trench. Soil pits/borings are within the proposed drainfield area.

The layout shown in Attachment 1 indicates there is available space for a four-bedroom accepted system. The initial system can be installed with the use of an accepted status drainfield based on the layout in the field.

The proposed LTAR (Long Term Acceptance Rate) by AWT is 0.4GPD/ft². The soils on this property are group III soils within the distribution and treatment zone as used to define the LTAR. With an LTAR of 0.4GPD/ft², 300 linear feet of trench is necessary to support a 4-bedroom home for the initial system and 200 linear feet of trench is necessary to support a 4-bedroom home for the repair system with the use of an PPBPS T&J Panel (50% Reduction) trench product. The maximum slope corrected trench depth is 22 inches. The attached drawings substantiate that the necessary linear footage of trench can be installed on the property for the initial and repair system.

Any logging, disturbances, or grading done in the usable area or within the proposed setbacks will change the potential of using the area designated for a drainfield. Prior to moving forward with the development on the property, the Harnett County Health Department should be contacted to complete the necessary Construction Oversight and to issue an OP (Operations Permit) for the property once the septic system has been installed.

Conclusions

An IP (Improvement Permit) and CA (Construction Authorization) for this property can be issued with the site plan that is in Attachment 1. A CA permit will be required to secure a building permit for the property. The county issues an Operation Permit after the system has been installed to meet the specifications of the Authorization to Construct. Additional septic layouts have been or will be performed as needed. It will be critical to not disturb any of the proposed septic area or there is a risk that the IP and CA will be revoked. The LSS/AOWE Evaluation and attached documents were prepared to this application is to be used to issue an Improvement Permit in accordance with G.S. 130A-335(a2) and (a3). The LSS/AOWE evaluation is being submitted pursuant to and meets the requirements of G.S. 130A-335(a2) and (a5).

We appreciate the opportunity to assist you in this matter. Please contact us with any questions, concerns, or comments.

Sincerely,

Heath Clapp, NC LSS



Agri-Waste Technology, Inc. 1225 Crescent Green, Suite 250, Cary NC 27518 agriwaste.com I 919.859.0669

SOIL & SITE EVALUATION for ON-SITE WASTEWATER SYSTEMS

Evaluation Date PIN/Parcel Proposed Facility Water Supply

| 10/1/2025 | |
|--------------|--|
| 0642-84-5992 | |
| SFR | |
| Municipal | |
| | |

Site Location Property Size Bedrooms Design Flow (.0400)

| 106 Thunderbird Lane, Fuquay Varina, NC 27526 |
|---|
| 0.56 acres |
| 4 |
| 480 |

County
Property Recorded
Wastewater Strength
Evaluation Method

| Harnett | |
|----------|--|
| Yes | |
| Domestic | |
| Διισρι | |

| | | | 0 1114 | | I | 0.11 | | | ı | |
|-----------|---|-----------------------|-------------------------------|------------------------------------|-----------------------------------|-----------------------------|--------------------|---------------------------------|-----------------------------------|---------------------------------|
| | | | Soil Mo | rphology | | Other Factors | | | | |
| Profile # | .0502 Landscape Position Slope % | Horizon Depth (in) | .0503 Structure Texture | .0503 Consistence Mineralogy | .0504 Soil Wetness Color | .0505 Soil Depth (in) | .0506 Saprolite | .0507 Restrictive Horizon | .0509 Profile Class LTAR | .0502(d) Slope Correction |
| | | Ap 0-6" | LS | NS, NP, VFr | 10YR 3/3 | | | | | |
| | | E 6-20" | LS | NS; NP; VFr | 10YR 7/6 | 36 | S | S | 0.4 | 1.6 |
| 1 | 4% | Bt1 20-36" | SCL | S; SP; Fi-Fr | 2.5YR 5/8 | | | | | |
| | | | | | | | System Type | • | Con | ventional |
| | | | • | • | ' | | | | | |
| | | • | | | | | | | | |
| | | Ap 0-6" | LS | NS, NP, VFr | 10YR 3/3 | | | | | |
| | | E 6-20" | LS | NS; NP; VFr | 10YR 7/6 | 36 | S | S | 0.4 | 0.8 |
| 2 | 2% | Bt1 20-36"+ | SCL | S; SP; Fi-Fr | 2.5YR 5/8 | | | | | |
| | | | | | | | System Type | | Con | ventional |
| | | | | | • | | | | | |
| | | | | | | | | | | |
| | | Ap 0-6" | LS | NS, NP, VFr | 10YR 3/3 | | | | | |
| | | E 6-20" | LS | NS; NP; VFr | 10YR 7/6 | 36 | S | S | 0.4 | 0.8 |
| 3 | 2% | Bt1 20-36"+ | SCL | S; SP; Fi-Fr | 2.5YR 5/8 | | | | | |
| | | | | | | | System Type | | Con | ventional |
| | | | | | | | | | | |
| | | | | _ | _ | | | | | |
| | | Ap 0-6" | LS | NS, NP, VFr | 10YR 3/3 | | | | | |
| | | E 6-18" | LS | NS; NP; VFr | 10YR 7/6 | 36 | S | S | 0.4 | 0.8 |
| 4 | 2% | Bt1 20-36"+ | SCL | S; SP; Fi-Fr | 2.5YR 5/8 | | | | | |
| | | | | | | | System Type | | Con | ventional |
| | | | | | | | System Type | | Con | ventional |

| Evaluated By: | |
|------------------|--|
| Heath Clapp, LSS | |

| Site Classification | Suitable | Site Classification | Suitable |
|----------------------|----------|---------------------|----------|
| Primary LTAR | 0.4 | Repair LTAR | 0.4 |
| Primary Trench Depth | 22" | Repair Trench Depth | 22" |



Agri-Waste Technology, Inc. 1225 Crescent Green, Suite 250, Cary NC 27518 agriwaste.com I 919.859.0669

SOIL & SITE EVALUATION for ON-SITE WASTEWATER SYSTEMS

LEGEND

| Soil Group | Soil Texture S (Sand) LS | Conventional LTAR 0.8-1.2 | Anaerobic Dip LTAR 0.4-0.6 | Aerobic Drip LTAR (TS-II) 0.8-1.5 | Minera Moist Lo | alogy & Wet NS | Structure SG (Single grain) M |
|------------|---------------------------------|----------------------------|-----------------------------|------------------------------------|----------------------------|-----------------------------|-------------------------------------|
| · | (Loamy Sand) | 0.0 2.2 | 51.1 51.5 | 0.0 2.0 | (Loose) | (Non Sticky) | (Massive) |
| | SL (Sandy Loam) | | | | VFR (Very Friable) | SS (Slightly Sticky) | GR (Granular) |
| II | L (Loam) | 0.6-0.8 | 0.3-0.4 | 0.6-0.8 | FR (Friable) | S (Sticky) | SBK (Subangular Blocky) |
| | SiL (Silt Loam) | | | | FI (Firm) | VS (Very Sticky) | ABK (Angular Blocky) |
| | SCL (Sandy Clay Loam) | | | | VFI (Very Firm) | NP (Non Plastic) | PR |
| III | CL (Clay Loam) | 0.3-0.6 | 0.15-0.3 | 0.2-0.6 | EFI (Extremely Firm) | SP (Slightly Plastic) | (Prismatic) |
| | SiCL (Silty Clay Loam) | | | | | P (Plastic) | PL (District) |
| | SC (Sandy Clay) | 0.4.0.4 | 0.05.4.5 | 0.05-0.2 | | VP (Very Plastic) | (Platy) |
| IV | SiC (Silty Clay) C (Clay) | 0.1-0.4 | 0.05-1.5 | | | ty Expansive) pansive) | |



CERTIFICATE OF LIABILITY INSURANCE

DATE (MM/DD/YYYY) 1/20/2025

THIS CERTIFICATE IS ISSUED AS A MATTER OF INFORMATION ONLY AND CONFERS NO RIGHTS UPON THE CERTIFICATE HOLDER. THIS CERTIFICATE DOES NOT AFFIRMATIVELY OR NEGATIVELY AMEND, EXTEND OR ALTER THE COVERAGE AFFORDED BY THE POLICIES BELOW. THIS CERTIFICATE OF INSURANCE DOES NOT CONSTITUTE A CONTRACT BETWEEN THE ISSUING INSURER(S), AUTHORIZED REPRESENTATIVE OR PRODUCER, AND THE CERTIFICATE HOLDER.

IMPORTANT: If the certificate holder is an ADDITIONAL INSURED, the policy(ies) must have ADDITIONAL INSURED provisions or be endorsed. If SUBROGATION IS WAIVED, subject to the terms and conditions of the policy, certain policies may require an endorsement. A statement on this certificate does not confer rights to the certificate holder in lieu of such endorsement(s).

| | 9 | men en aer een aer (e). | | |
|--|---------------------------------|--|--------|--|
| PRODUCER Hartsfield & Nash Agency, Inc. | | CONTACT NAME: Connie Garkalns | | |
| 10405 Ligon Mill Rd., Ste H Wake Forest NC 27587 | | PHONE (A/C, No, Ext): 984-235-4273 FAX (A/C, No): 919-55 | 6-8758 | |
| | | E-MAIL ADDRESS: connie@hartsfield-nash.com | | |
| | | INSURER(S) AFFORDING COVERAGE | NAIC# | |
| | License#: 1000009111 | INSURER A: Selective Insurance Company of | 39926 | |
| INSURED | AGRITEC-01 | INSURER B: Accident Fund | 10166 | |
| Agri-Waste Technology Inc 501 N. Salem St Ste 203 | | INSURER C : Evanston Insurance Company | 35378 | |
| Apex NC 27502 | | INSURER D: | | |
| | | INSURER E: | | |
| | | INSURER F: | | |
| COVERAGES | CERTIFICATE NUMBER: 130/498969/ | REVISION NUMBER: | | |


THIS IS TO CERTIFY THAT THE POLICIES OF INSURANCE LISTED BELOW HAVE BEEN ISSUED TO THE INSURED NAMED ABOVE FOR THE POLICY PERIOD INDICATED. NOTWITHSTANDING ANY REQUIREMENT, TERM OR CONDITION OF ANY CONTRACT OR OTHER DOCUMENT WITH RESPECT TO WHICH THIS CERTIFICATE MAY BE ISSUED OR MAY PERTAIN, THE INSURANCE AFFORDED BY THE POLICIES DESCRIBED HEREIN IS SUBJECT TO ALL THE TERMS, EXCLUSIONS AND CONDITIONS OF SUCH POLICIES. LIMITS SHOWN MAY HAVE BEEN REDUCED BY PAID CLAIMS.

| NSR LTR | TYPE OF INSURANCE | ADDL INSD | SUBR WVD | POLICY NUMBER | POLICY EFF (MM/DD/YYYY) | POLICY EXP (MM/DD/YYYY) | LIMIT | s |
|------------|--|--------------|-------------|-----------------------------|----------------------------|----------------------------|--|-------------------------|
| Α | X COMMERCIAL GENERAL LIABILITY | | | S 2253659 | 1/18/2025 | 1/18/2026 | EACH OCCURRENCE DAMAGE TO RENTED | \$2,000,000 |
| | CLAIMS-MADE X OCCUR | | | | | | PREMISES (Ea occurrence) MED EXP (Any one person) | \$ 300,000 \$ 10,000 |
| | | | | | | | PERSONAL & ADV INJURY | \$2,000,000 |
| | GEN'L AGGREGATE LIMIT APPLIES PER: | | | | | | GENERAL AGGREGATE | \$4,000,000 |
| | POLICY X PRO- JECT LOC | | | | | | PRODUCTS - COMP/OP AGG | \$4,000,000 |
| | OTHER: | | | | | | | \$ |
| A | AUTOMOBILE LIABILITY | | | S 2253659 | 1/18/2025 | 1/18/2026 | COMBINED SINGLE LIMIT (Ea accident) | \$1,000,000 |
| | X ANY AUTO | | | | | | BODILY INJURY (Per person) | \$ |
| | OWNED SCHEDULED AUTOS AUTOS | | | | | | BODILY INJURY (Per accident) | \$ |
| | X HIRED X NON-OWNED AUTOS ONLY | | | | | | PROPERTY DAMAGE (Per accident) | \$ |
| | | | | | | | | \$ |
| A | X UMBRELLA LIAB X OCCUR | | | S 2253659 | 1/18/2025 | 1/18/2026 | EACH OCCURRENCE | \$2,000,000 |
| | EXCESS LIAB CLAIMS-MADE | | | | | | AGGREGATE | \$2,000,000 |
| | DED RETENTION\$ | | | | | | | \$ |
| | WORKERS COMPENSATION AND EMPLOYERS' LIABILITY | | | 100003072 | 1/18/2025 | 1/18/2026 | X PER OTH- STATUTE ER | |
| | ANYPROPRIETOR/PARTNER/EXECUTIVE T/N | N/A | | | | | E.L. EACH ACCIDENT | \$1,000,000 |
| | (Mandatory in NH) | , | | | | | E.L. DISEASE - EA EMPLOYEE | \$1,000,000 |
| | If yes, describe under DESCRIPTION OF OPERATIONS below | | | | | | E.L. DISEASE - POLICY LIMIT | \$1,000,000 |
| C A | Prof & Pollution Liability Leased & Rented | | | MKLV3ENV104794 S 2253659 | 8/22/2024 1/18/2025 | 8/22/2025 1/18/2026 | Each Claim Equipment | 5,000,000 25,000 |

DESCRIPTION OF OPERATIONS / LOCATIONS / VEHICLES (ACORD 101, Additional Remarks Schedule, may be attached if more space is required)

| CERTIFICATE HOLDER | CANCELLATION |
|--|--|
| Artisan Custom Homes 21016 Catawba Avenue | SHOULD ANY OF THE ABOVE DESCRIBED POLICIES BE CANCELLED BEFORE THE EXPIRATION DATE THEREOF, NOTICE WILL BE DELIVERED IN ACCORDANCE WITH THE POLICY PROVISIONS. |
| Cornelius NC 28031 USA | COMMI GALLAN |
| 1 | 0 |

| BIRCHWOOD TRAILS - LOT 75 | | | | | | |
|---------------------------|-------------------------------------|--|--|--|--|--|
| Project Location | 106 Thunderbird Lane, | | | | | |
| | Fuquay Varina, NC 27526 | | | | | |
| | Harnett County | | | | | |
| | PIN: 0642-84-5992 | | | | | |
| | | | | | | |
| | | | | | | |
| Project Owner | KB Home | | | | | |
| | 1800 Perimeter Park Drive, STE 140, | | | | | |
| | Morrisville, NC 27560 | | | | | |
| | 919-768-7960 | | | | | |
| | enpollock@kbhome.com | | | | | |
| | | | | | | |
| Project Consultant | Heath Clapp, LSS, AOWE | | | | | |
| | (919) 629-6404 | | | | | |
| | Jeff Vaughan, LSS, AOWE | | | | | |
| | (919) 367-6313 | | | | | |
| | Agri-Waste Technology, Inc. | | | | | |
| | 1225 Crescent Green, Suite 250 | | | | | |
| | Cary, NC 27518 | | | | | |
| | (919) 859-0669 | | | | | |
| | (919) 233-1970 Fax | | | | | |
| | | | | | | |
| System Overview | Single Family Residence | | | | | |
| | Four (4) Bedroom, 480 gpd | | | | | |
| | Conventional Pressure Manifold | | | | | |
| | Accepted/Innovative Trench Product | | | | | |



VICINITY MAP

Sheet Index

| Sheet 1 | Cover Sheet | |
|---------|--------------------|--|
| Sheet 2 | Property Layout | |
| Sheet 3 | Primary Drainfield | |
| Sheet 4 | Repair Drainfield | |
| Sheet 5 | Detail Sheet 1 | |
| Sheet 6 | Detail Sheet 2 | |



Engineers and Soil Scientists Agri-Waste Technology, Inc.

Agri-Waste Technology, Inc. 1225 Crescent Green, Suite 250 Cary, North Carolina 27518 919-859-0669 www.agriwaste.com

KB Home Birchwood Trails - Lot 75

Project Location: 106 Thunderbird Lane, Fuquay Varina, NC 27526 Harnett County PIN: 0642-84-5992

Project Owner: KB Home 1800 Perimeter Park Drive, STE 14 Morrisville, NC 27560 919-768-7960 enpollock@kbhome.com

NC ONSITE WASTEWATER EVALUATOR SEAL


Certification
Number
Nu

rey. Issued date description

SHEET TITLE

Cover Sheet

DRAWING NUMBER



General Drainfield Notes:

- Clear all trees less than 8" in diameter (measured at a height 3' from soil surface) from the drainfield.
- 2. Vegetation that will re-grow from a cut stump shall be stumped or pulled from the ground. Stumps shall not be pushed over.
- Jrainfield area shall be cleared of all leaves, pine straw, debris, etc. The accumulated material shall be removed from the drainfield.
- 4. In clayey soils, sides of trenches shall be raked and limed per manufacturer's instructions.
- Supply lines shall be installed with a minimum of 18" cover.
- 6. The trenches shall be backfilled appropriately so that no low areas are present.
- 7. Apply lime over the drainfield area as needed. Seed fine fescue over the drainfield at the rate recommended by the seed manufacturer. Hand rake the seed into the soil surface. Straw the seeded area at the rate of 1.5-2 bales per 1000 sq. ft.

| DRAINFIELD INFO | Primary | | | | | |
|---------------------------------------|---------|---------------------------|---------------------|------|-----------|----------|
| Proposed Type of System/Distribution: | | Pump to Pressure Manifold | | | | |
| | | using EZflow | | | | |
| | Flag | Line | | Flow | Flow/Foot | Line |
| Line No. | Color | Length (ft) | Length (ft) Tap | | (gpm/ft) | L.T.A.R. |
| 1 | blue | 55 | 3/4in SCH 80, Split | 5.05 | 0.092 | 0.523 |
| 2 | purple | 55 | 3/4in SCH 80, Split | 5.05 | 0.092 | 0.523 |
| 3 | orange | 60 | 1/2in SCH 80 | 5.48 | 0.091 | 0.520 |
| 4 | white | 65 | 3/4in SCH 40, Split | 6.25 | 0.096 | 0.548 |
| 5 | orange | 65 | 3/4in SCH 40, Split | 6.25 | 0.096 | 0.548 |

SOURCE: Agri-Waste Technology, Inc.

Note:

Primary distribution is pressure manifold utilizing accepted trench product.



Agri-Waste Technology, Inc. 1225 Crescent Green, Suite 2t Cary, North Carolina 27518 919-859-0669 www.agriwaste.com

KB Home Birchwood Trails - Lot 75

Project Location: 106 Thunderbird Lane, Fuquay Varina, NC 27526 Harnett County PIN: 0642-84-5992

Project Owner: KB Home 1800 Perimeter Park Drive, STE 140 Morrisville, NC 27560 919-768-7960 envollock/@khbrone.com

NC ONSITE WASTEWATER EVALUATOR SEAL

Certification Number 10057E

rey, issued date description

SHEET TITLE


Primary Drainfield

DRAWN BY: CREATED ON: 10/6/2025

REVISED BY: REVISED ON: ####

RELEASED BY: RELEASED ON:

DRAWING NUMBER



General Drainfield Notes:

- Clear all trees less than 8" in diameter (measured at a height 3' from soil surface) from the drainfield.
- 2. Vegetation that will re-grow from a cut stump shall be stumped or pulled from the ground. Stumps shall not be pushed over.
- 3. Drainfield area shall be cleared of all leaves, pine straw, debris, etc. The accumulated material shall be removed from the drainfield.
- 4. In clayey soils, sides of trenches shall be raked and limed per manufacturer's instructions.
- 5. Supply lines shall be installed with a minimum of 18" cover.
- 6. The trenches shall be backfilled appropriately so that no low areas are present.
- 7. Apply lime over the drainfield area as needed. Seed fine fescue over the drainfield at the rate recommended by the seed manufacturer. Hand rake the seed into the soil surface. Straw the seeded area at the rate of 1.5-2 bales per 1000 sq. ft.


| DRAINFIELD INFO | Repair | | | | | |
|---------------------------------------|--------|--------------|-------------------------|-------|-----------|----------|
| Proposed Type of System/Distribution: | | Pump to Pres | sure Manifold | | | |
| | | using PPBPS, | using PPBPS, Horizontal | | | |
| Line Ma | Flag | Line | | Flow | Flow/Foot | Line |
| Line No. | Color | Length (ft.) | | (gpm) | (gpm/ft) | L.T.A.R. |
| 6 | interp | 50 | 1/2in SCH 80 | 5.48 | 0.110 | 0.800 |
| 7 | interp | 50 | 1/2in SCH 80 | 5.48 | 0.110 | 0.800 |
| 8 | interp | 50 | 1/2in SCH 80 | 5.48 | 0.110 | 0.800 |
| 9 | interp | 50 | 1/2in SCH 80 | 5.48 | 0.110 | 0.800 |
| | Total | 200 | Total | 24 02 | Ava | 0.00 |


SOURCE: Agri-Waste Technology, Inc.


Note: Repair distribution is pressure manifold utilizing accepted trench product.



DRAWING NUMBER







SOURCE: Shoaf Precast Septic, Inc.

RISER INSTALLATION INSTRUCTIONS: use o clean cloth and acetone or olcohol to clean the bonding surfaces of the adapter and riser. The bonding surfaces must be clean and dry for a good fit and waterlight joint. Let the acetone or olcohol dry completely. ply Adhesive Apply a bead of methocrylate adhesive to the outside of the adapter. One 7-oz packet of MA320 adhesive is typical for one 24" riser. Access Riser to Extend 6 Inches Above Finished Grade.

bodapter. One 7-02 packet of MA320 odhesive is typical for one 24" riser.

3. Install Riser

3.1. If the riser has penetrations, align the riser correctly.

3.2. Firmly press the riser onto the odopter until the bottom of the riser is resting on the concrete (cast-in-adapters) or the adapter flange (bolted-down adapters). Twist the riser back and forth slightly to fully seal it on to create a good band,

3.3. Apply a bead of methocrylate adhesive to the inside of the access riser-adapter joint.

3.4. Use a tangue depressor, putty knife, or clean cloth to make a continuous fillet on the inside of the access riser-adapter joint.

3.5. Apply hydraulic cement to band outer riser wall and top of tank.

Ensure inner lid is in place and secured.

| FOR RISER WALL PENETRATIONS | | | |
|---|--------|--|--|
| Grommet Size, Inches (Nominal IPS Pipe Size) Hole Saw Size, Inches | | | |
| 1/2 | 1 | | |
| 3/4 | 1 1/4 | | |
| 1 | 1 9/16 | | |
| 1 1/4 | 1 3/4 | | |
| 1 1/2 | 2 1/8 | | |
| 2 | 2 3/4 | | |
| 3 | 3 7/8 | | |
| 4 | 5 | | |

NOTES


- 1. Installation to follow all NC DHHS and Harnett County applicable rules and regulations.
- 2. Harnett County Health Department to perform construction inspections and final system certification.
- 3. Septic Tank to have approved effluent filter.
- 4. Contractor to abide by all safety regulations during system installation.
- 5. Contractor shall backfill around all access areas such that storm water is shed away from potential entry points.
- 6. Invert elevations of all components to be verified in field by contractor to insure proper operation.
- 7. All system piping to be SCH40 PVC (except where noted).
- 8. All gravity elbows to be long radius or long sweeping type elbows.
- 9. Actual installation and placement of treatment system to be overseen by Contractor.
- 10. Tanks to be set on 6" minimum gravel base. Use #5 or #57 stone for base.


- 11. Contractor to seed and/or mulch disturbed areas to coincide with existing landscape. Area shall not be left with uncovered soil.
- 12. Mount Control Panel a minimum of 24" above grade.
- 13. Power to panel to be installed by licensed electrician per code. One 15-amp circuit and one 20-amp circuit with individual neutrals to be run from house to control panel.
- 14. All risers to have cast-in-place tank adapters and be single-piece riser. Risers to extend 6" above soil surface and be designed to prevent surface water inflow.
- 15. Backfill around tank(s) shall be gravel or tank hole shall be over-excavated a minimum of 2' in all directions to allow for mechanical tamping of backfill.
- 16. All penetrations to be sealed.
- 17. All pressure lines to maintain 18" min. cover.
- 18. Contractor to adjust tank placement to meet site constraints.

1225 Crescent Green, Suite 250 919-859-0669 www.agriwaste.com **KB Home** Birchwood Trails - Lot 75 Project Location: 106 Thunderbird Lane Fuquay Varina, NC 27526 Harnett County PIN: 0642-84-5992 Project Owner KB Home 1800 Perimeter Park Drive, STE 140 Morrisville, NC 27560 919-768-7960 enpollock@kbhome.com NC ONSITE WASTEWATER EVALUATOR SEAL WAS WAS TE WAS Certification Number ALUATOR TILINALUAT CHILINA REV. ISSUED DATE DESCRIPTION SHEET TITLE Detail Sheet 1 DRÁWN BY: CREATED ON: H. Clapp REVISED BY: REVISED ON: RELEASED BY: RELEASED ON:

DRAWING NUMBER


| 3 | Riser | Installatio | r |
|----------|-------|-------------|---|
| MARALE . | | | |






CONTROL PANEL SUPPORT

WW-6 N.T.S. SOURCE: AW



PRESSURE MANIFOLD INSTALLATION (Manitee) - For Illustration Only

N.T.S. SOURCE: AWT



Engineers and Soil Scientists

Agri-Waste Technology, Inc.
1225 Crescent Green, Suite 250

Cary, North Carolina 27518 919-859-0669 www.agriwaste.com

KB Home Birchwood Trails - Lot 75

Project Location: 106 Thunderbird Lane, Fuquay Varina, NC 27526 Harnett County PIN: 0642-84-5992

Project Owner: KB Home 1800 Perimeter Park Drive, STE 140 Morrisville, NC 27560 919-768-7960 enpollock@kbhome.com

NC ONSITE WASTEWATER EVALUATOR SEAL



REY. ISSUED DATE DESCRIPTION

SHEET TITLE

Detail Sheet 2

DRAWING NUMBER

Septic System Design - Summary Page

Engineers and Soil Scientists

Agri-Waste Technology, Inc. 501 N Salem Street, Suite 203, Apex, NC 27502

agriwaste.com | 919.859.0669

Project Manager:

Heath Clapp, LSS

hclapp@agriwaste.com

919-629-6404

Designer:

Heath Clapp, LSS

hclapp@agriwaste.com

Project: Birchwood Trails - Lot 75

Property: 106 Thunderbird Lane

Fuquay Varina, NC 27526

Subdiv.: Birchwood Trails

Lot #: 75 Permit #:

Owner: KB Home

Address: 1800 Perimeter Park Drive, STET1/4/e of System: III b

Morrisville, NC, 27560

Phone: 919-768-7960

Email: enpollock@kbhome.com PIN: 0642-84-5992

Special Conditions/Notes:

Date:

County:

10/6/2025

Harnett

EHS:

Soil Parameters

Soil Evaluation By:

Heath Clapp, LSS

gpd/ft² LTAR: 0.40

Design Parameters

Type of Establishment: Dwelling Units, no more than 2 persons per bedroom

Unit: Bedroom # of Units:

Septic Tank Specifications

Min. Tank Capacity: 960 gal **Actual Tank Volume:** 1,250 gal **Tank Manufacturer:** Shoaf

Tank Model: TS 1250 STB

Exterior Interior

Length: 125.5 119.5 in. Width: 65.5 59.5 in. Depth: 61.5 54.5 in.

Primary Drainfield Specifications

Type of Distribution: Parallel Pressure Manifold

Trench Media: EZflow **Trench Width:** 3 ft

Trench Depth: 24 in. (or as specified on permit) **Trench Bottom Area:** 1200

Minimum Drain Line: 300 **Actual Drain Line:** 300

 ft^2

ft

ft

Number of Lines: 5

Minimum Line Spacing: 9 ft O.C.

Wastewater Treatment System Design Calculations

Project: Birchwood Trails - Lot 75 **Location:** 106 Thunderbird Lane

Fuquay Varina, NC 27526

County: Harnett

Septic Tank Sizing

Daily Flow Estimate:

| Unit | # of Units | Flow/Unit | Flow/Day | |
|---------|------------|-----------|----------|-----|
| Bedroom | 4 | 120 | 480 | ļ |
| | | Q= | 480 | gpd |

Septic Tank Minimum Capacity:

Per NCAC T15A:18A .1952(b)(2)(A):

For large residences, multiple dwelling units, or places of business or public assembly with $Q \le 600$,

Minimum Liquid Capacity (V)= 960 gal

Septic Tank Specs: Manufacturer:

facturer: Shoaf

Model: TS 1250 STB

Volume: 1,250 gal Weight: 11,000 lbs

Exterior Interior
Length: 125.5 119.5 in.
Width: 65.5 59.5 in.
Depth: 61.5 54.5 in.

Shape of Risers: Circular

Diameter: 2.00 ft

Pump Tank Storage & Float Settings

Project: Birchwood Trails - Lot 75
Location: 106 Thunderbird Lane
Eugusy Varios NC 27526

Fuquay Varina, NC 27526

County: Harnett

Tank Manufacturer Shoaf

Tank Model TS 1275 PT

Interior Height (in.) 60.5 in. Avg. Storage 21.07 gal/in.

Primary System

<u>Elevations</u>, measured from bottom towards top (0 = Interior Bottom of Tank):

Top of pump (including 4" block) 16.1 in. (Pump height = 12 1/16")

Pump Off 18.0 in.

Pump On 24.5 in. (set for dose volume)
Alarm On 30.5 in. (6 in. above On Float)

Emergency Storage Available

Pump Tank 632 gal
Days of Storage 1.32 days
(determined from "interior top of tank" - "High Water Alarm")

Repair System

Elevations, measured from bottom towards top (0 = Interior Bottom of Tank):

Top of pump (including 4" block)

16.1 in. (Pump height = 12 1/16")

Pump Off 18.0 in.

Pump On 26.0 in. (set for dose volume)
Alarm On 32.0 in. (6 in. above On Float)

Emergency Storage Available

Pump Tank 600 gal
Days of Storage 1.25 days
(determined from "interior top of tank" - "High Water Alarm")

ELEVATIONS

Project: Birchwood Trails - Lot 75 Location: 106 Thunderbird Lane Fuquay Varina, NC 27526

County: Harnett

| Benchmark | 0 |
|-----------|-----|
| RM Flev | 0 f |

| Benchmark | 0 | |
|----------------------------------|-----------|----------------------|
| BM Elev | 0 ft | |
| Septic Tank | 1,250 gal | |
| Ground Surface | | 302.80 ft |
| Depth of Soil Cover | 27 in. | 2.25 ft |
| Overall Ht of Tank | 61.5 in. | 5.13 ft |
| Elev, Base of Tank | | 295.43 ft |
| Ht to 4" Inlet Invert | 50 in. | 4.17 ft |
| Elev, 4" Inlet Invert | | 299.59 ft |
| Ht to 4" Outlet Invert | 48 in. | 4.00 ft |
| Elev, 4" Outlet Invert | | 299.43 ft |
| Gravel Base | 6 in. | 0.50 ft |
| Elev, Bot of Excavation | | 294.93 ft |
| Pump Tank | 1287 gal | |
| Ground Surface | | 303.20 ft |
| Depth of Soil Cover | 36 in. | 3.00 ft |
| Overall Ht of Tank | 67.5 in. | 5.63 ft |
| Elev, Base of Tank | | 294.58 ft |
| Ht to 4" Inlet Invert | 57 in. | 4.75 ft |
| Elev, 4" Inlet Invert | | 299.33 ft |
| Ht to 2" Outlet Invert | 54.5 in. | 4.54 ft |
| Elev, 2" Outlet Invert | | 299.12 ft |
| Gravel Base | 6 in. | 0.50 ft |
| Elev, Bot of Excavation | | 294.08 ft |
| ST Inlet Pipe | | |
| Grade @ Stub-out | | 302.1 ft |
| Depth of Stub-out, top | | 1.5 ft |
| Elev, Stub-out Invert | | 300.25 ft |
| Elev @ ST Inlet Invert | | 299.59 ft |
| Length | | 32 ft |
| Slope | | 2.0 % |
| Pipe, ST to PT | | |
| ID | 4 in. | 0.33 ft |
| OD | 4.5 in. | 0.38 ft |
| Elev, ST Outlet Invert | | 299.43 ft |
| Elev, PT Inlet Invert | | 299.33 ft |
| Length | | 2 ft |
| Slope | | 5.0 % 2.85 ft |
| Cover over inlet pipe | | 2.85 11 |
| Pump Reqmt. Floor Thickness | 4 : | 0.22 ft |
| | 4 in. | 0.33 ft |
| Elev, Pump Tank Floor | 4 in. | 294.91 ft 0.33 ft |
| Pump Block Ht. Elev, Pump Intake | 4 III. | 295.24 ft |
| Elev, Pump intake | | 295.24 11 |
| Grade @ Primary Manifold | | 304.10 ft |
| Grade @ Repair Manifold | | 302.60 ft |
| Min. Cover | 18 in. | 1.50 ft |
| Max Elev, Primary | _ | 302.60 ft |
| Max Elev, Repair | | 301.10 ft |
| Elev Diff, Primary | | 7.36 ft |
| , D, 1 milary | | 7.55 10 |

Elev Diff, Repair

5.86 ft

Drainfield Design

Project Birchwood Trails - Lot 75
Location 106 Thunderbird Lane

Fuquay Varina, NC 27526

County Harnett

Drainfield Sizing

| Primary | | | |
|----------------------|-------------------------|--------------------------|-------------------|
| LTAR | 0.4 gpd/ft ² | | |
| Daily Design Flow | 480 gpd | Type of Drainfield Media | EZflow |
| Req. Drainfield Area | 1,200 ft ² | Required Drainline | |
| Trench Width, Eff. | 3 ft | After 25% Reduction | 300 ft |
| Required Drainline | 400 ft | Minimum Line Spacing | 9 ft (O.C.) |
| Repair | | | |
| LTAR | 0.4 gpd/ft ² | | |
| Daily Design Flow | 480 gpd | Type of Drainfield Media | PPBPS, Horizontal |
| Req. Drainfield Area | 1,200 ft ² | Required Drainline | |
| Trench Width, Eff. | 3 ft | After 50% Reduction | 200 ft |
| Required Drainline | 400 ft | Minimum Line Spacing | 8 ft (O.C.) |

Drainfield Layout

| | | | Elevation | Line Length | Used as | Used as |
|------|-------------|------------|-----------|-------------|--------------|-------------|
| Line | Use | Flag Color | (ft) | (ft) | Primary (ft) | Repair (ft) |
| 1 | Layout Line | blue | | 55 | 55.0 | |
| 2 | Layout Line | purple | | 55 | 55.0 | |
| 3 | Layout Line | orange | | 60 | 60.0 | |
| 4 | Layout Line | white | | 65 | 65.0 | |
| 5 | Layout Line | orange | | 65 | 65.0 | |
| 6 | Layout Line | interp | | 50 | | 50.0 |
| 7 | Layout Line | interp | | 50 | | 50.0 |
| 8 | Layout Line | interp | | 50 | | 50.0 |
| 9 | Layout Line | interp | | 50 | | 50.0 |
| | | | Total | 500 | 300 | 200 |
| | | | Count | 9 | 5 | 4 |

Note: Line length totals are shown to the nearest foot.

PRESSURE MANIFOLD DESIGN (Primary)

Site Information

Project: Birchwood Trails - Lot 75 Location: 106 Thunderbird Lane

Fuquay Varina, NC 27526

County: Harnett

Design Information

Estimated Daily Flow 480 gal/day 0.4 gal/day/ft² L.T.A.R. (from Harnett Co.) 0.420 gal/day/ft² L.T.A.R. + 5% Trench Width 3 ft. 400 ft. Line Length Required Length after 25% Reduction 300 ft 0.533 gal/day/ft² L.T.A.R. Reduced

0.560 gal/day/ft² L.T.A.R. Reduced + 5%

DRAINFIELD INFO. - Primary

Proposed Type of System/Distribution: Pump to Pressure Manifold

using EZflow

| | Flag | Line | | Flow | Flow/Foot | Line |
|----------|--------|-------------|---------------------|-------|-----------|----------|
| Line No. | Color | Length (ft) | Тар | (gpm) | (gpm/ft) | L.T.A.R. |
| 1 | blue | 55 | 3/4in SCH 80, Split | 5.05 | 0.092 | 0.523 |
| 2 | purple | 55 | 3/4in SCH 80, Split | 5.05 | 0.092 | 0.523 |
| 3 | orange | 60 | 1/2in SCH 80 | 5.48 | 0.091 | 0.520 |
| 4 | white | 65 | 3/4in SCH 40, Split | 6.25 | 0.096 | 0.548 |
| 5 | orange | 65 | 3/4in SCH 40, Split | 6.25 | 0.096 | 0.548 |
| | Total | 300 | Total | 28.08 | Ava. | 0.53 |

Note: Line lengths are calculated in 4'4" increments to reflect use of PPBPS product.

| Total Run Time | 17.09 | min. | |
|---------------------|-------|----------|-------------------------------|
| Drainfield Capacity | 195.9 | gal | |
| % of Drainfield Cap | 69.9% | | (Req. Range 66-75%) |
| Dose Volume | 136.9 | gal/dose | |
| Run Time/Dose | 4.9 | minutes | Range 5-7 minutes unless up |
| Volume/denth | 21.07 | aal/in | (Por tank manufacturar's spec |

hill, checked (Per tank manufacturer's specifications) Volume/depth 21.07 gal/in. Estimated Drawdown 6.50 in.

Manifold Box

| Number of Taps | 3 | with | 2 | Split(s) |
|-----------------|-----|------|---------------|----------|
| Manifold Length | 3.0 | ft. | (approximate) | |

PRESSURE MANIFOLD SYSTEM DESIGN (Repair)

Site Information

Project: Birchwood Trails - Lot 75
Location: 106 Thunderbird Lane

Fuquay Varina, NC 27526

County: Harnett

Design Information

Estimated Daily Flow
L.T.A.R. (from Harnett Co.)

L.T.A.R. + 5%
Trench Width
Line Length Required
L.T.A.R. + 50% Reduction
L.T.A.R. Reduced

480 gal/day/ft²
0.420 gal/day/ft²
3 ft.
400 ft.
200 ft

L.T.A.R. Reduced 0.800 gal/day/ft² L.T.A.R. Reduced + 5% 0.840 gal/day/ft²

DRAINFIELD INFO. - Repair

Proposed Type of System/Distribution: Pump to Pressure Manifold

using PPBPS, Horizontal

| Line No. | Flag Color | Line Length (ft.) | | Flow (gpm) | Flow/Foot (gpm/ft) | Line L.T.A.R. |
|----------|---------------|----------------------|--------------|---------------|-----------------------|------------------|
| 6 | interp | 50 | 1/2in SCH 80 | 5.48 | 0.110 | 0.800 |
| 7 | interp | 50 | 1/2in SCH 80 | 5.48 | 0.110 | 0.800 |
| 8 | interp | 50 | 1/2in SCH 80 | 5.48 | 0.110 | 0.800 |
| 9 | interp | 50 | 1/2in SCH 80 | 5.48 | 0.110 | 0.800 |
| | Total | 200 | Total | 21.92 | Ava. | 0.80 |

Note: Line lengths are calculated in 4'4" increments to reflect use of PPBPS product.

Total Run Time 21.90 min.
Drainfield Capacity 316.8 gal
% of Drainfield Cap 53.2%
Dose Volume 168.5 gal/dose

(Max. 100.0% to not exceed 7.2 gal/panel)

Run Time/Dose
Volume/depth
Volume/depth
Estimated Drawdown

7.7 minutes
7.7 minutes
7.7 minutes
7.7 minutes
7.7 minutes
7.7 minutes
7.8 Time to deliver max. 3.6 gal/panel
7.9 (Per tank manufacturer's specifications)
8.00 in.

Manifold Box

Number of Taps 4 with 0 Split(s) Manifold Length 3.5 ft. (approximate)

PUMP DESIGN

System (initial/repair): Primary

Project: Birchwood Trails - Lot 75 106 Thunderbird Lane Location: Fuquay Varina, NC 27526

County: Harnett

Friction Losses

| Suction Head | 0 ft | (submersible 0) |
|---|------------------|---|
| Elev. Difference (highest point from pump) | 7.36 ft | |
| Design Pressure At Outlet | 2 ft | |
| Supply Line - 2" Schedule 40 PVC Pipe Diameter, Nominal 2 in. Pipe Diameter (ID) 2.047 in. Pipe Length 53 ft | Flow Velocity | 28.08 gpm 2.74 ft/sec |
| Pipe Length for Fittings 5.3 ft | , | ets requirement that 2 ft/s < v < 5 ft/s. |
| Equivalent Length 58.3 ft | | |
| Estimated Friction Loss in Supply Line | 0.84 ft | |
| Friction Loss - Taps/Special Fittings | 3.5 ft | |
| TOTAL | 13.70 ft. | |

Flow for Anti-Siphon Hole

Hole Diameter 3/16 in. Hole Flowrate 1.53 gpm


Pump Efficiency 0.7 (assumed, typical) 0.9 (assumed for electric pumps) Motor Efficiency 29.61 gpm Flow

Required Horsepower 0.16 hp

TDH 13.70 ft

Pump Selection

| Manufacturer | Zoeller |
|--------------|---------|
| Model | N98 |
| Horsepower | 0.5 |



PUMP DESIGN

System (initial/repair): Repair

Project: Birchwood Trails - Lot 75
Location: 106 Thunderbird Lane
Fuquay Varina, NC 27526

County: Harnett

Friction Losses

| Suction Head | 0 ft | (submersible 0) |
|--|-----------|--|
| | | (Submersible 0) |
| Elev. Difference (highest point from pump) | 5.86 ft | |
| Design Pressure At Outlet | 2 ft | |
| | | |
| Supply Line - 2" Schedule 40 PVC | | |
| Pipe Diameter, Nominal 2 in. | | |
| Pipe Diameter (ID) 2.047 in. | Flow | 21.92 gpm |
| Pipe Length 53 ft | Velocity | 2.14 ft/s |
| Pipe Length for Fittings 5.3 ft | M | eets requirement that 2 ft/s < v < 5 ft/s. |
| Equivalent Length 58.3 ft | | |
| Estimated Friction Loss in Supply Line | 0.53 ft | |
| | | |
| _ | | |
| Friction Loss - Taps/Special Fittings | 3.5 ft | |
| | • | |
| TOTAL | 11.89 ft. | |

Flow for Anti-Siphon Hole

Hole Diameter 3/16 in.
Hole Flowrate 1.43 gpm

Pump Efficiency 0.7 (assumed, typical)


Motor Efficiency 0.9 (assumed for electric pumps)

Flow 23.35 gpm

Required Horsepower 0.11 hp TDH 11.89 ft.

Pump Selection

| Manufacture | Zoeller |
|-------------|---------|
| Mode | N98 |
| Horsepowe | 0.5 |



Septic Tank Buoyancy Calculation

Project: Birchwood Trails - Lot 75
Location: 106 Thunderbird Lane

Fuquay Varina, NC 27526

County: Harnett

Tank Size (nominal) 1250 gal

Properties/Assumptions:

| Min. liquid level to be maintained in tank at all times after initial installation. | | | | | | |
|---|-------------------------------------|---|--|--|--|--|
| Min. depth to water table Effluent Density | 12.0 in. 62.4 lb/ft ³ | from ground surface (Specific Weight of Water) | | | | |
| Concrete Density Soil App. Sp. Grav. | 142.6 lb/ft ³ 1.3 | (typical value) | | | | |
| Soil Cover Over Tank | 12 in. | (minimum) | | | | |
| Additional Cover | 15 in. | for pipe grade | | | | |
| Unsubmerged wt of soil | 81.1 lb/ft ³ | | | | | |
| Submerged wt of soil | 49.9 lb/ft ³ | 50% Porosity Assumed | | | | |

Tank Dimensions (from supplier):

| ank Dimensions | (IIOIII Suppi | i c i). | | | | |
|--------------------|---------------|--------------------|-----------------|-----------------|------------------|-----|
| | | <u>Exte</u> | <u>Exterior</u> | | <u>rior</u> | |
| | | Тор | Bottom | Тор | Bottom | |
| Tank | Length | 125.5 | 122.0 | 119.5 | 116.0 in. | |
| | Width | 65.5 | 62.0 | 59.5 | 56.0 in. | |
| | Height | 58.5 | (w/o lid) | 54.5 | in. | |
| | | | | | | |
| Lid | Length | 125.5 | in. | | | |
| | Width | 65.5 | in. | | | |
| | Height | 3.0 | in. | | | |
| | | | | | | |
| A | rea of Riser | Openings | 6.28 1 | ft ² | | |
| | | | | | | |
| Permanen | t Liquid Dept | th in Tank | 0.0 | in. | 0.00 ft | |
| | • | - | | | | |
| | Tar | nk Weight | 11,000 l | lb | (per manufacture | er) |

Buoyancy Force Calculation:

| Buoyancy Force Specific Weight of Water x Displaced Volume | | | | | | |
|--|-------------------------|--|--|--|--|--|
| Displaced Volume | 289.2 ft ³ * | | | | | |
| Buoyancy Force | 18,048 lb. | | | | | |

Weight Calculation:

| Tank Weight | 11000 lb | | |
|-----------------------|-----------|--------|-----------------------|
| Water Weight in Tank | 0 lb | Volume | 0.0 ft ³ * |
| Soil Weight Over Tank | 7291 lb | | |
| Soil Friction Force | 4037 lb | | |
| Total Weight | 22,328 lb | | |

Factor of Safety = 1.24

Note: Total weight must be greater than buoyancy force so that tank will not float during high water table conditions.

^{*} Volume calculated by the prismoidal formula.

Pump Tank Buoyancy Calculation

Project: Birchwood Trails - Lot 75 Location: 106 Thunderbird Lane

Fuquay Varina, NC 27526

County: Harnett

Tank Size (nominal) 1287 gal

Properties/Assumptions:

| Min. liquid level to be maintained in tank at all times after initial installation. | | | | | | |
|---|---|--|--|--|--|--|
| Min. depth to water table Effluent Density Concrete Density Soil App. Sp. Grav. | 12 in. 62.4 lb/ft ³ 142.6 lb/ft ³ | from ground surface (Specific Weight of Water) (typical value) | | | | |
| - 30ii Αρρ. 3p. Giav. | 1.5 | (typical value) | | | | |
| Soil Cover Over Tank | 12 in. | (minimum) | | | | |
| Additional Cover | 24 in. | for pipe grade | | | | |
| | 04.4 II-/#3 | | | | | |
| Unsubmerged wt of soil | 81.1 lb/ft ³ | | | | | |
| Submerged wt of soil | 49.9 lb/ft ³ | 50% porosity assumed | | | | |

Tank Dimensions (from supplier):

| | one (nom capp | | | | |
|--------|----------------|------------|--------------|-----------------|--------------------|
| | | Exte | <u>erior</u> | <u>Inte</u> | <u>rior</u> |
| | | Тор | Bottom | Тор | Bottom |
| Tan | ık Length | 108.0 | 104.0 | 102.0 | 98.0 in. |
| | Width | 58.0 | 54.0 | 52.0 | 48.0 in. |
| | Height | 64.5 | (w/o lid) | 60.5 | in. |
| | | | | | |
| Li | d Length | 108.0 | in. | | |
| | Width | 58.0 | in. | | |
| | Height | 3.0 | in. | | |
| | | | | | |
| | Area of Riser | Openings | 3.14 | ft ² | |
| | | | | | |
| Perman | ent Liquid Dep | th in Tank | 0.0 | in. | 0.00 ft |
| | | | | | |
| | Tai | nk Weight | 10500 | lb | (per manufacturer) |

Buoyancy Force Calculation:

| Buoyancy Force Specific Weight of Water x Displaced Volume | | | |
|--|---|--|--|
| Displaced Volume Buoyancy Force | 238.8 ft ³ * 14,900 lb | | |

Weight Calculation:

| Total Weight | 22,030 lb | | |
|-----------------------|-----------|--------|-----------------------|
| Soil Friction Force | 4227 lb | | |
| Soil Weight Over Tank | 7303 lb | | |
| Water Weight in Tank | 0 lb | Volume | 0.0 ft ³ * |
| Tank Weight | 10500 lb | | |

Factor of Safety = 1.48

Note: Total weight must be greater than buoyancy force so that tank will not float during high water table conditions.

^{*} Volume calculated by the prismoidal formula.