



HARNETT COUNTY ENVIRONMENTAL HEALTH

File/Permit #: SFD2508-0057

CDP #:

IMPROVEMENT PERMIT (IP)

☒ New ☐ Expansion ☐ Repair ☐ System Relocation ☐ Change of Use

Owner: DRB GROUP NORTH CAROLINA LLC Applicant: DRB GROUP NORTH CAROLINA LLC

Property Location: 108 CELTIC LN LILLINGTON, NC 27546 PIN/Lot Identifier: 0680-37-0605.000

Subdivision: BLAKE POND Lot #: 12 Block: Section:

Facility Type: SFD 54.2' x 48' Number of bedrooms: 3 Number of Occupants: 6 Other:

Design Daily Flow: 360 GPD LTAR (Initial): .325 gpd/ft² LTAR (Repair): .3 gpd/ft²

Wastewater System Type: 25% Reduction System (Initial)

Pump Required: ☐ Yes ☒ No ☐ May be required Usable Depth to Limiting Condition (Initial): 48"

Wastewater System Type: 50% Reduction System (Repair)

Pump Required: ☐ Yes ☒ No ☐ May be required Usable Depth to Limiting Condition (Repair): 27"

Effluent Standard: ☒ DSE ☐ HSE ☐ Other: Type of Water Supply: ☐ Private well ☒ Municipal Supply ☐ Other:

Permit conditions:

No Cutting or Grading Soil in Septic or Septic Repair Area.
No Gutter or Foundation Drain to be Directed Towards Septic System.

The issuance of this permit in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This permit is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of 15A NCAC 18E and to the conditions of this permit.

Authorized Agent's Printed Name: Ren Levocz Date: 09/12/2025

Authorized Agent's Signature: *Ren Levocz* Expiration Date: 09/12/2030

CONSTRUCTION AUTHORIZATION (CA)

☒ New ☐ Expansion ☐ Repair ☐ System Relocation ☐ Change of Use

Owner: DRB GROUP NORTH CAROLINA LLC Applicant: DRB GROUP NORTH CAROLINA LLC

Property Location: 108 CELTIC LN LILLINGTON, NC 27546 PIN/Lot Identifier: 0680-37-0605.000

Subdivision: BLAKE POND Lot #: 12 Block: Section:

Facility Type: SFD 54.2' x 48' Number of bedrooms: 3 Number of Occupants: 6 Other:

Design Daily Flow: 360 GPD LTAR: .325 gpd/ft²

Effluent Standard: ☒ DSE ☐ HSE ☐ Other: Type of Water Supply: ☐ Private well ☒ Municipal Supply ☐ Other:

Installation Requirements/Conditions

Wastewater System Type: 25% Reduction System Pump Required: ☐ Yes ☒ No ☐ May be required

Septic Tank Size: 1,000 gallons Total Trench Length: 300' feet Trench Spacing: 9' feet on center

Pump Tank Size: gallons Maximum Trench Depth: 18"-28" inches Soil Cover: 6" inches

Trench Width: 36" inches Distribution Method: ☐ Serial ☒ D-Box or Parallel ☐ Pressure Manifold ☐ Other: 3 - 130' Lines

Artificial Drainage Required: Yes ☐ No ☒ If yes, please specify details:

Management Entity Required: ☐ Yes ☒ No Minimum O&M Requirements:

Permit conditions:

No Cutting or Grading Soil in Septic or Septic Repair Area.
No Gutter or Foundation Drain to be Directed Towards Septic System.

The requirements of 15A NCAC 18E are incorporated by reference into this permit and shall be met. Systems shall be installed in accordance with the attached site sketch. This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be affected by a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of 15A NCAC 18E, or 15A NCAC 18A .1900, as applicable, and to the conditions of this permit.

Authorized Agent's Printed Name: Ren Levocz Date: 09/12/25

Authorized Agent's Signature: *Ren Levocz* Expiration Date: 09/12/2030

Owner/Legal Representative Signature: Date:

***See attached site sketch**

PIN 0680-37-0605.000 SITE SKETCH Permit Number SFD2508-0057

Revised January 2024
Form IP-24.1