

**HARNETT COUNTY ENVIROMENTAL HEALTH**

File/Permit #: SFD2508-0092

CDP #:

IMPROVEMENT PERMIT (IP)☒ New☐ Expansion☐ Repair☐ System Relocation☐ Change of Use

Owner: PHAM MYTUYET THANH

Applicant: PHAM MYTUYET THANH

Property Location: 8619 NC 27 E

PIN/Lot Identifier: 1610-90-5340.000

Subdivision:

Lot #: TRACT 5-B

Block:

Section:

Facility Type: SFD 54' x 56'

Number of bedrooms: 4

Number of Occupants: 8

Other:

Design Daily Flow: 480

GPD

LTAR (Initial): .35

gpd/ft²

LTAR (Repair): .35

gpd/ft²

Wastewater System Type: 25% Reduction System

(Initial)

Pump Required: ☐ Yes ☒ No ☐ May be required

Usable Depth to Limiting Condition (Initial): 48"

Wastewater System Type: 25% Reduction System

(Repair)

Pump Required: ☐ Yes ☒ No ☐ May be required

Usable Depth to Limiting Condition (Repair): 48"

Effluent Standard: ☒ DSE ☐ HSE ☐ Other:Type of Water Supply: ☐ Private well ☒ Municipal Supply ☐ Other:**Permit conditions:**

No Foundation or Gutter Drains to be Directed Towards Septic System.
No Grading or Cutting or Soil in Septic or Septic Repair Area.

The issuance of this permit in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This permit is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of 15A NCAC 18E and to the conditions of this permit.

Authorized Agent's Printed Name: Ren Levocz

Date: 09/23/2025

Authorized Agent's Signature:

Expiration Date: 09/23/2030

CONSTRUCTION AUTHORIZATION (CA)☒ New☐ Expansion☐ Repair☐ System Relocation☐ Change of Use

Owner: PHAM MYTUYET THANH

Applicant: PHAM MYTUYET THANH

Property Location: 8619 NC 27 E

PIN/Lot Identifier: 1610-90-5340.000

Subdivision:

Lot #: TRACT 5-B

Block:

Section:

Facility Type: SFD 54' x 56'

Number of bedrooms: 4

Number of Occupants: 8

Other:

Design Daily Flow: 480

GPD

LTAR: .35

gpd/ft²Effluent Standard: ☒ DSE ☐ HSE ☐ Other:Type of Water Supply: ☐ Private well ☒ Municipal Supply ☐ Other:**Installation Requirements/Conditions**

Wastewater System Type: 25% Reduction System

Pump Required: ☐ Yes ☒ No ☐ May be required

Septic Tank Size: 1,000

gallons

Total Trench Length: 360'

feet

Trench Spacing: 9'

feet on center

Pump Tank Size:

gallons

Maximum Trench Depth: 18"-28"

inches

Soil Cover: 6"

inches

Trench Width: 36"

inches

Distribution Method: ☒ Serial☒ D-Box or Parallel☐ Pressure Manifold☐ Other: 3 - 120' LinesArtificial Drainage Required: Yes ☐ No ☒ If yes, please specify details:Management Entity Required: ☐ Yes ☒ No Minimum O&M Requirements:**Permit conditions:**

No Foundation or Gutter Drains to be Directed Towards Septic System.
No Grading or Cutting or Soil in Septic or Septic Repair Area.

The requirements of 15A NCAC 18E are incorporated by reference into this permit and shall be met. Systems shall be installed in accordance with the attached site sketch. This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be affected by a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of 15A NCAC 18E, or 15A NCAC 18A .1900, as applicable, and to the conditions of this permit.

Authorized Agent's Printed Name: Ren Levocz

Date: 09/23/25

Authorized Agent's Signature:

Expiration Date: 09/23/2030

Owner/Legal Representative Signature:

Date:

***See attached site sketch**

PIN 1610-90-5340.000 SITE SKETCH Permit Number SFD2508-0092

Date _____

System components represent approximate contours only. The contractor must flag the system prior to beginning the installation to ensure that the proper grade is maintained.

Scale = NTS

***More Line is Flagged Than Needed. Only Need 360' Total.
(3 - 120' Lines)**

