

Trenco
818 Soundside Rd
Edenton, NC 27932

Re: 25080114-A
55 Magnolia Acres-Crawl-Taylor FA TMB FL GLH

The truss drawing(s) referenced below have been prepared by Truss Engineering Co. under my direct supervision based on the parameters provided by Carter Components (Sanford, NC)).

Pages or sheets covered by this seal: I75888699 thru I75888706

My license renewal date for the state of North Carolina is December 31, 2025.

North Carolina COA: C-0844



August 25, 2025

Gilbert, Eric


IMPORTANT NOTE: The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to MiTek or TRENCO. Any project specific information included is for MiTek's or TRENCO's customers file reference purpose only, and was not taken into account in the preparation of these designs. MiTek or TRENCO has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.

Job	Truss	Truss Type	Qty	Ply	55 Magnolia Acres-Crawl-Taylor FA TMB FL GLH
25080114-A	F101	Floor Supported Gable	2	1	I75888699
Job Reference (optional)					

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Aug 13 2025 Print: 8.730 S Aug 13 2025 MiTek Industries, Inc. Mon Aug 25 13:05:06
ID:AQeszeD3tDntKw?2oFdVj5zKxvO-RfC?PsB70Hq3NSgPqnL8w3uITxbGKWrcDoi7J4zJC?f

Page: 1



Scale = 1:36.1

Plate Offsets (X, Y): [36:Edge,0-1-8]

Loading	(psf)	Spacing	1-4-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.05	Vert(LL)	0.00	36	>999	360	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.01	Vert(CT)	0.00	34	>999	240	
BCLL	0.0	Rep Stress Incr	YES	WB	0.02	Horz(CT)	0.00	19	n/a	n/a	
BCDL	5.0	Code	IRC2018/TPI2014	Matrix-R							
Weight: 80 lb											FT = 11%F, 11%E

LUMBER	
TOP CHORD	2x4 SP No.2(flat)
BOT CHORD	2x4 SP No.2(flat)
WEBS	2x4 SP No.3(flat)
OTHERS	2x4 SP No.3(flat)

WEBS	
2-35=-28/0, 3-34=-72/0, 4-33=-92/0,	
5-32=-88/0, 6-31=-89/0, 7-29=-89/0,	
8-28=-89/0, 9-27=-89/0, 11-26=-89/0,	
12-25=-89/0, 13-24=-89/0, 14-23=-89/0,	
15-22=-88/0, 16-21=-92/0, 17-20=-77/0	


BRACING	
TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size)	
19=19-0-0, 20=19-0-0, 21=19-0-0,	
22=19-0-0, 23=19-0-0, 24=19-0-0,	
25=19-0-0, 26=19-0-0, 27=19-0-0,	
28=19-0-0, 29=19-0-0, 31=19-0-0,	
32=19-0-0, 33=19-0-0, 34=19-0-0,	
35=19-0-0, 36=0-3-0	
Max Grav	19=23 (LC 1), 20=85 (LC 1),
	21=101 (LC 1), 22=97 (LC 1),
	23=98 (LC 1), 24=98 (LC 1), 25=98
	(LC 1), 26=98 (LC 1), 27=98 (LC
	1), 28=98 (LC 1), 29=98 (LC 1),
	31=98 (LC 1), 32=97 (LC 1),
	33=101 (LC 1), 34=79 (LC 1),
	35=31 (LC 1), 36=20 (LC 1)

FORCES (lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-36=-19/0, 18-19=-21/0, 1-2=-2/0, 2-3=-2/0,
	3-4=-2/0, 4-5=-2/0, 5-6=-2/0, 6-7=-2/0,
	7-8=-2/0, 8-9=-2/0, 9-11=-2/0, 11-12=-2/0,
	12-13=-2/0, 13-14=-2/0, 14-15=-2/0,
	15-16=-2/0, 16-17=-2/0, 17-18=-2/0
BOT CHORD	35-36=0/2, 34-35=0/2, 33-34=0/2, 32-33=0/2,
	31-32=0/2, 29-31=0/2, 28-29=0/2, 27-28=0/2,
	26-27=0/2, 25-26=0/2, 24-25=0/2, 23-24=0/2,
	22-23=0/2, 21-22=0/2, 20-21=0/2, 19-20=0/2

- NOTES**
- 1) All plates are 2x4 MT20 unless otherwise indicated.
 - 2) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - 3) Gable studs spaced at 1-4-0 oc.
 - 4) All bearings are assumed to be SP No.2 .
 - 5) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 36.
 - 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - 7) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 8) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard



August 25, 2025


WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932


Carter Components (Sanford, NC), Sanford, NC - 27332, Run: 8.73 S Aug 13 2025 Print: 8.730 S Aug 13 2025 MiTek Industries, Inc. Mon Aug 25 13:05:07 Page: 1
ID:AQeszeD3tDntKw?2oFdVf5zKxvO-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWRcDoi7J4cJZ?f



LUMBER		5) Required 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
TOP CHORD	2x4 SP No.2(flat)	
BOT CHORD	2x4 SP No.2(flat) *Except* 20-14:2x4 SP No.1(flat)	
WEBS	2x4 SP No.3(flat)	
OTHERS	2x4 SP No.3(flat)	6) CAUTION, Do not erect truss backwards.
BRACING		LOAD CASE(S) Standard
TOP CHORD	Structural wood sheathing directly applied or 5-9-9 oc purlins, except end verticals.	1) Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.	Uniform Loads (lb/ft) Vert: 14-22=-7, 1-13=-67 Concentrated Loads (lb) Vert: 24=-379
REACTIONS	(size) 14=0-4-8 22=0-3-0	

NOTES

- 1) Unbalanced floor live loads have been considered for this design.
- 2) All plates are MT20 plates unless otherwise indicated.
- 3) Bearings are assumed to be: Joint 22 SP No.2 , Joint 14 SP No.1 .
- 4) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MITEK® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI 1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbccomponents.com)




818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	55 Magnolia Acres-Crawl-Taylor FA TMB FL GLH I75888701
25080114-A	F103	Floor Supported Gable	1	1	Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Aug 13 2025 Print: 8.730 S Aug 13 2025 MiTek Industries, Inc. Mon Aug 25 13:05:07
ID:LGHbia9JHN1jb?YuS?W5UqzKxvU-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrcDoi7J4zJC?f

Page: 1



Scale = 1:30.6

Plate Offsets (X, Y): [26:Edge,0-1-8]

Loading	(psf)	Spacing	1-4-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.05	Vert(LL)	n/a	-	n/a	999	MT20
TCDL	10.0	Lumber DOL	1.00	BC	0.01	Vert(TL)	n/a	-	n/a	999	244/190
BCLL	0.0	Rep Stress Incr	YES	WB	0.02	Horiz(TL)	0.00	14	n/a	n/a	
BCDL	5.0	Code	IRC2018/TPI2014	Matrix-R							
Weight: 64 lb											FT = 11%F, 11%E

LUMBER

TOP CHORD 2x4 SP No.2(flat)
BOT CHORD 2x4 SP No.2(flat)
WEBS 2x4 SP No.3(flat)
OTHERS 2x4 SP No.3(flat)

BRACING

TOP CHORD Structural wood sheathing directly applied or 6'-0" oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10'-0" oc bracing.

REACTIONS (size) 14=16'-0"-0, 15=16'-0"-0, 16=16'-0"-0, 17=16'-0"-0, 18=16'-0"-0, 19=16'-0"-0, 20=16'-0"-0, 21=16'-0"-0, 22=16'-0"-0, 23=16'-0"-0, 24=16'-0"-0, 25=16'-0"-0, 26=16'-0"-0
Max Grav 14=42 (LC 1), 15=95 (LC 1), 16=98 (LC 1), 17=98 (LC 1), 18=98 (LC 1), 19=98 (LC 1), 20=98 (LC 1), 21=98 (LC 1), 22=98 (LC 1), 23=98 (LC 1), 24=98 (LC 1), 25=95 (LC 1), 26=42 (LC 1)

FORCES


(lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-26=-38/0, 13-14=-38/0, 1-2=-8/0, 2-3=-8/0, 3-4=-8/0, 4-5=-8/0, 5-6=-8/0, 6-7=-8/0, 7-8=-8/0, 8-9=-8/0, 9-10=-8/0, 10-11=-8/0, 11-12=-8/0, 12-13=-8/0
BOT CHORD 25-26=0/8, 24-25=0/8, 23-24=0/8, 22-23=0/8, 21-22=0/8, 20-21=0/8, 19-20=0/8, 18-19=0/8, 17-18=0/8, 16-17=0/8, 15-16=0/8, 14-15=0/8
WEBS 2-25=-87/0, 3-24=-89/0, 4-23=-89/0, 5-22=-89/0, 6-21=-89/0, 7-20=-89/0, 8-19=-89/0, 9-18=-89/0, 10-17=-89/0, 11-16=-89/0, 12-15=-87/0

NOTES

- All plates are 1.5x3 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.

- Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
- Gable studs spaced at 1'-4" oc.
- All bearings are assumed to be SP No.2 .
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Recommend 2x6 strongbacks, on edge, spaced at 10'-0"-0" oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard



August 25, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	55 Magnolia Acres-Crawl-Taylor FA TMB FL GLH
25080114-A	F104	Floor	10	1	I75888702
					Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Aug 13 2025 Print: 8.730 S Aug 13 2025 MiTek Industries, Inc. Mon Aug 25 13:05:07
ID:LGHbia9JHN1jb?YuS?W5UqzKxvU-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:32.2

Plate Offsets (X, Y): [5:0-1-8,Edge], [6:0-1-8,Edge], [12:Edge,0-1-8], [14:0-1-8,Edge], [15:0-1-8,Edge]

Loading	(psf)	Spacing	1-4-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL	40.0	Plate Grip DOL	1.00	TC	0.50	Vert(LL)	-0.23	15	>852	360	MT20HS	187/143
TCDL	10.0	Lumber DOL	1.00	BC	0.88	Vert(CT)	-0.31	15	>619	240	MT20	244/190
BCLL	0.0	Rep Stress Incr	NO	WB	0.42	Horz(CT)	0.05	12	n/a	n/a		
BCDL	5.0	Code	IRC2018/TPI2014	Matrix-SH							Weight: 80 lb	FT = 11%F, 11%E

LUMBER

TOP CHORD 2x4 SP No.2(flat)
BOT CHORD 2x4 SP No.2(flat)
WEBS 2x4 SP No.3(flat)

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 12=0-4-8, 18=0-4-8
Max Grav 12=596 (LC 1), 18=593 (LC 1)

FORCES (lb) - Maximum Compression/Maximum Tension


TOP CHORD 1-18=-58/0, 11-12=-51/0, 1-2=0/0,
2-3=-1972/0, 3-4=-1972/0, 4-5=-2700/0,
5-6=-2700/0, 6-8=-2700/0, 8-9=-1881/0,
9-10=-1881/0, 10-11=0/0
BOT CHORD 17-18=0/1223, 15-17=0/2457, 14-15=0/2700,
13-14=0/2399, 12-13=0/1092
WEBS 5-15=-168/0, 6-14=-196/0, 4-15=0/494,
4-17=-542/0, 3-17=-105/0, 2-17=0/840,
2-18=-1330/0, 10-12=-1215/0, 10-13=0/885,
9-13=-115/0, 8-13=-580/0, 8-14=0/539

NOTES

- 1) Unbalanced floor live loads have been considered for this design.
- 2) All plates are MT20 plates unless otherwise indicated.
- 3) All bearings are assumed to be SP No.2 .
- 4) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 5) Load case(s) 1 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.
- 6) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard

- 1) Dead + Floor Live (balanced): Lumber Increase=1.00,
Plate Increase=1.00
Uniform Loads (lb/ft)
Vert: 12-18=-7, 1-19=-67, 11-19=-68



August 25, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	55 Magnolia Acres-Crawl-Taylor FA TMB FL GLH
25080114-A	F105	Floor	19	1	I75888703
Job Reference (optional)					

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Aug 13 2025 Print: 8.730 S Aug 13 2025 MiTek Industries, Inc. Mon Aug 25 13:05:07
ID:LGHbia9JHN1jb?YuS?W5UqzKxvU-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:31.9

Plate Offsets (X, Y): [3:0-1-8,Edge], [4:0-1-8,Edge], [8:0-1-8,Edge], [9:0-1-8,Edge], [10:0-1-8,Edge], [11:Edge,0-1-8], [12:0-1-8,Edge], [13:0-1-8,Edge], [16:0-1-8,Edge], [17:0-1-8,Edge]

Loading	(psf)	Spacing	1-7-3	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL	40.0	Plate Grip DOL	1.00	TC	0.66	Vert(LL)	-0.09	17-18	>999	360	MT20	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.57	Vert(CT)	-0.13	17-18	>735	240		
BCLL	0.0	Rep Stress Incr	NO	WB	0.27	Horz(CT)	0.02	11	n/a	n/a		
BCDL	5.0	Code	IRC2018/TPI2014	Matrix-SH							Weight: 77 lb	FT = 11%F, 11%E

LUMBER

TOP CHORD 2x4 SP No.2(flat)
BOT CHORD 2x4 SP No.2(flat)
WEBS 2x4 SP No.3(flat)
OTHERS 2x4 SP No.3(flat)

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 11=0-3-8, 15=0-4-8, 18=0-4-8
Max Grav 11=417 (LC 7), 15=929 (LC 1), 18=395 (LC 10)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-18=-65/0, 10-11=-117/0, 1-2=0/0, 2-3=-947/0, 3-4=-947/0, 4-6=-39/276, 6-7=-41/273, 7-8=-840/0, 8-9=-840/0, 9-10=-8/0

BOT CHORD 17-18=0/724, 16-17=0/947, 15-16=0/947, 13-15=0/595, 12-13=0/840, 11-12=0/840

WEBS 3-17=-116/0, 4-16=0/76, 6-15=-224/0, 8-13=-140/0, 9-12=-1/37, 7-15=-759/0, 7-13=0/373, 2-17=0/251, 2-18=-787/0, 4-15=-1097/0, 9-11=-885/0


NOTES

- Unbalanced floor live loads have been considered for this design.
- All bearings are assumed to be SP No.2.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Load case(s) 1 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.

- Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
- CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard

- Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (lb/ft)
Vert: 11-18=-8, 1-3=-80, 3-7=-115, 7-9=-80, 9-10=-115



August 25, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	55 Magnolia Acres-Crawl-Taylor FA TMB FL GLH I75888704
25080114-A	F106	Floor Supported Gable	1	1	Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Aug 13 2025 Print: 8.730 S Aug 13 2025 MiTek Industries, Inc. Mon Aug 25 13:05:07
ID:iE5UIIDR6wf0imQrEY6GBuzKxvP-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:30.5

Plate Offsets (X, Y): [28:Edge,0-1-8]

Loading	(psf)	Spacing	1-4-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.05	Vert(LL)	0.00	28	>999	360	MT20	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.01	Vert(CT)	0.00	27-28	>999	240		
BCLL	0.0	Rep Stress Incr	YES	WB	0.02	Horz(CT)	0.00	15	n/a	n/a		
BCDL	5.0	Code	IRC2018/TPI2014	Matrix-R							Weight: 66 lb	FT = 11%F, 11%E

LUMBER

TOP CHORD 2x4 SP No.2(flat)
BOT CHORD 2x4 SP No.2(flat)
WEBS 2x4 SP No.3(flat)
OTHERS 2x4 SP No.3(flat)

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 15=0-3-8, 16=15-3-8, 17=15-3-8, 18=15-3-8, 19=15-3-8, 20=15-3-8, 21=15-3-8, 22=15-3-8, 23=15-3-8, 24=15-3-8, 25=15-3-8, 26=15-3-8, 27=15-3-8, 28=15-3-8
Max Uplift 16=2 (LC 3)
Max Grav 15=28 (LC 1), 16=27 (LC 4), 17=83 (LC 3), 18=101 (LC 1), 19=97 (LC 3), 20=98 (LC 1), 21=98 (LC 3), 22=98 (LC 1), 23=98 (LC 3), 24=98 (LC 1), 25=98 (LC 3), 26=98 (LC 1), 27=99 (LC 3), 28=40 (LC 1)


FORCES

(lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-28=-37/0, 14-15=-23/0, 1-2=-6/0, 2-3=-6/0, 3-4=-6/0, 4-5=-6/0, 5-6=-6/0, 6-7=-6/0, 7-8=-6/0, 8-9=-6/0, 9-10=-6/0, 10-11=-6/0, 11-12=-6/0, 12-13=-6/0, 13-14=-6/0
BOT CHORD 27-28=0/6, 26-27=0/6, 25-26=0/6, 24-25=0/6, 23-24=0/6, 22-23=0/6, 21-22=0/6, 20-21=0/6, 19-20=0/6, 18-19=0/6, 17-18=0/6, 16-17=0/6, 15-16=0/6
WEBS 13-16=-24/0, 2-27=-88/0, 3-26=-89/0, 4-25=-89/0, 5-24=-89/0, 6-23=-89/0, 7-22=-89/0, 8-21=-89/0, 9-20=-89/0, 10-19=-88/0, 11-18=-92/0, 12-17=-74/0

NOTES

- 1) Unbalanced floor live loads have been considered for this design.
- 2) All plates are 1.5x3 MT20 unless otherwise indicated.
- 3) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
- 4) Gable studs spaced at 1-4-0 oc.
- 5) All bearings are assumed to be SP No.2 .
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 2 lb uplift at joint 16.
- 7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 8) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
- 9) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard



August 25, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932


Job	Truss	Truss Type	Qty	Ply	55 Magnolia Acres-Crawl-Taylor FA TMB FL GLH I75888705
25080114-A	F107	Floor Supported Gable	3	1	Job Reference (optional)

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Aug 13 2025 Print: 8.730 S Aug 13 2025 MiTek Industries, Inc. Mon Aug 25 13:05:07

Page: 1

ID:iE5UIIDR6wf0imQrEY6GBuzKxvP-RfC?PsB70Hq3NSgPqnL8w3uITXbGKwRCDoi7J4zJC?f



Scale = 1:25.8

Plate Offsets (X, Y): [22:Edge,0-1-8]

Loading	(psf)	Spacing	1-7-3	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.07	Vert(LL)	0.00	21-22	>999	360	MT20	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.02	Vert(CT)	0.00	21-22	>999	240		
BCLL	0.0	Rep Stress Incr	YES	WB	0.03	Horz(CT)	0.00	12	n/a	n/a		
BCDL	5.0	Code	IRC2018/TPI2014	Matrix-R							Weight: 53 lb	FT = 11%F, 11%E

LUMBER

TOP CHORD 2x4 SP No.2(flat)
BOT CHORD 2x4 SP No.2(flat)
WEBS 2x4 SP No.3(flat)
OTHERS 2x4 SP No.3(flat)

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 12=0-3-0, 13=12-3-0, 14=12-3-0, 15=12-3-0, 16=12-3-0, 17=12-3-0, 18=12-3-0, 19=12-3-0, 20=12-3-0, 21=12-3-0, 22=12-3-0

Max Uplift 12=-4 (LC 3)

Max Grav 12=20 (LC 4), 13=99 (LC 1), 14=129 (LC 3), 15=114 (LC 1), 16=118 (LC 3), 17=117 (LC 1), 18=117 (LC 1), 19=117 (LC 3), 20=117 (LC 1), 21=120 (LC 3), 22=46 (LC 1)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-22=-43/0, 11-12=-19/11, 1-2=-5/0, 2-3=-5/0, 3-4=-5/0, 4-5=-5/0, 5-6=-5/0, 6-7=-5/0, 7-8=-5/0, 8-9=-5/0, 9-10=-5/0, 10-11=-5/0

BOT CHORD 21-22=0/5, 20-21=0/5, 19-20=0/5, 18-19=0/5, 17-18=0/5, 16-17=0/5, 15-16=0/5, 14-15=0/5, 13-14=0/5, 12-13=0/5


WEBS 10-13=-95/0, 2-21=-107/0, 3-20=-107/0, 4-19=-107/0, 5-18=-107/0, 6-17=-106/0, 7-16=-107/0, 8-15=-104/0, 9-14=-117/0

NOTES

- Unbalanced floor live loads have been considered for this design.
- All plates are 1.5x3 MT20 unless otherwise indicated.
- Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).

- Gable studs spaced at 1-4-0 oc.
- All bearings are assumed to be SP No.2.
- Provide mechanical connection (by others) of truss to bearing plate at joint(s) 12.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 4 lb uplift at joint 12.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
- CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard



August 25, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate


818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	55 Magnolia Acres-Crawl-Taylor FA TMB FL GLH
25080114-A	F108	Floor	10	1	I75888706
Job Reference (optional)					

Carter Components (Sanford, NC), Sanford, NC - 27332,

Run: 8.73 S Aug 13 2025 Print: 8.730 S Aug 13 2025 MiTek Industries, Inc. Mon Aug 25 13:05:08
ID:iE5UIIDR6wf0imQrEY6GBuzKxvP-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:29.8

Plate Offsets (X, Y): [2:0-1-8,Edge], [3:0-1-8,Edge], [6:0-1-8,Edge], [7:0-1-8,Edge], [13:0-1-8,Edge]

Loading	(psf)	Spacing	1-7-3	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL	40.0	Plate Grip DOL	1.00	TC	1.00	Vert(LL)	-0.03	12-13	>999	360	MT20	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.77	Vert(CT)	-0.26	12-13	>332	240		
BCLL	0.0	Rep Stress Incr	YES	WB	0.67	Horz(CT)	0.01	12	n/a	n/a		
BCDL	5.0	Code	IRC2018/TPI2014	Matrix-SH							Weight: 64 lb	FT = 11%F, 11%E

LUMBER

TOP CHORD 2x4 SP No.1(flat)
BOT CHORD 2x4 SP 2400F 2.0E(flat)
WEBS 2x4 SP No.3(flat)
OTHERS 2x4 SP No.3(flat)

BRACING

TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS (size) 9=0-3-0, 12=0-4-8, 15=0-4-8
Max Uplift 9=-170 (LC 3)
Max Grav 9=30 (LC 4), 12=1557 (LC 9), 15=655 (LC 10)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-15=0/94, 8-9=-121/0, 1-2=0/0, 2-3=-1692/0, 3-4=-1692/0, 4-5=0/1588, 5-6=0/1588, 6-7=0/670, 7-8=-9/0

BOT CHORD 14-15=0/1692, 13-14=0/1692, 12-13=0/503, 11-12=-670/0, 10-11=-670/0, 9-10=-670/0
WEBS 5-12=-28/52, 6-12=-1263/0, 7-9=0/746, 4-12=-2196/0, 2-15=-1871/0, 4-13=0/1398, 2-14=0/331, 3-13=-862/0, 6-11=0/193, 7-10=-195/0


NOTES

- Unbalanced floor live loads have been considered for this design.
- All bearings are assumed to be SP 2400F 2.0E .
- Provide mechanical connection (by others) of truss to bearing plate at joint(s) 9.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 170 lb uplift at joint 9.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

- Load case(s) 1 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.
- Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
- CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard

- Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (lb/ft)
Vert: 9-15=-8, 1-8=-80
Concentrated Loads (lb)
Vert: 3=-1066



August 25, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacompnents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932

Symbols

PLATE LOCATION AND ORIENTATION



* Plate location details available in MITek software or upon request.

PLATE SIZE

4 X 4

The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T or I bracing if indicated.


BEARING



Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number/letter where bearings occur. Min size shown is for crushing only.

Industry Standards:
ANSI/TP1: National Design Specification for Metal Plate Connected Wood Truss Construction.
DSB-22: Building Component Safety Information, Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses.

Numbering System



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

Product Code Approvals

ICC-ES Reports:
ESR-1988, ESR-2362, ESR-2685, ESR-3282
ESR-4722, ESL-1388

Design General Notes

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.

Lumber design values are in accordance with ANSI/TP1 section 6.3. These truss designs rely on lumber values established by others.

© 2023 MITek® All Rights Reserved

General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor I bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TP1 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TP1 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TP1 1 Quality Criteria.
21. The design does not take into account any dynamic or other loads other than those expressly stated.

MITek®

ENGINEERING BY
TRENCO
A MITek Affiliate

MITek Engineering Reference Sheet: MII-7473 rev. 1/2/2023