

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: ELYSE MEADOWS

LOT 66

INITIAL SYSTEM: ^{pump to} Approved 25% Reduction

REPAIR: ^{pump to} Approved 25% Reduction

DISTRIBUTION: SERIAL

DISTRIBUTION SERIAL

BENCHMARK: 100.0

LOCATION TOP STAKE 535

NO. BEDROOMS: 4

LTAR 0.4 GPD/FTL

SEPTIC TANK SIZE 1000

PUMP TANK SIZE 1000

LINE	FLAG COLOR	ELEVATION	LENGTH
------	------------	-----------	--------

Initial
sys tank

1	Y	96.20	80'
2	O	95.80	85'
3	Y	95.40	75'
4	O	95.00	75'

315' AVAILABLE

5	Y	94.40	75'
6	O	94.20	75'
7	Y	93.90	75'
8	O	93.60	40'
9	Y	93.20	40'
			305'

BY M. EAKER

DATE 03/2024

TYPICAL PROFILE

0-10" LF (VF, ugr)
10-36" SL (F. JAK)
cr 2" ± 32"

THERE SHALL BE NO GRADING,
CUTTING, LOGGING OR OTHER SOIL
DISTURBANCE IN SEPTIC AREA

HEALTH DEPARTMENT USE ONLY.

DESIGNS DO NOT GUARANTEE FUNCTIONALITY

Southeastern Soil & Environmental Associates LLC
PO Box 9321 Fayetteville, NC 28311
Mike@southeasternsoil.com
(910) 822-4540

Elyse Meadow Preliminary Septic Evaluation

