

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: ELISE MEADOWS

LOT 98

INITIAL SYSTEM: Approved 25% Reduction

REPAIR: Approved 25% Reduction

DISTRIBUTION: SERIAL

DISTRIBUTION P-BOX

BENCHMARK: 100.0

LOCATION TOP STAKE 432

NO. BEDROOMS: 3

LTAR 0.4 GPD/FTL

SEPTIC TANK SIZE 1000

PUMP TANK SIZE 1000

LINE	FLAG COLOR	ELEVATION	LENGTH
1	Y	97.30	60'
2	O	97.20	85'
3	Y	97.00	85'
			<u>230'</u>
4	O	96.50	80'
5	Y	96.60	30'
6	O	95.50	80'
7	Y	94.90	60' AVAL
			<u>300'</u>

Initial
54' for

BY M. EATON

DATE 03/2024

TYPICAL PROFILE

0-10 LB / V.F. w/pt
10-36+ SCL / F.V. 100'
CR 2 ≥ 34"

THERE SHALL BE NO GRADING,

CUTTING, LOGGING OR OTHER SOIL

DISTURBANCE IN SEPTIC AREA

HEALTH DEPARTMENT USE ONLY.

DESIGNS DO NOT GUARANTEE FUNCTIONALITY

Southeastern Soil & Environmental Associates LLC
PO Box 9321 Fayetteville, NC 28311
Mike@southeasternsoil.com
(910) 822-4540

Elyse Meadow
Preliminary Septic Evaluation

