

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

* Fix setback on map

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: Elyse Meadow

LOT 67

INITIAL SYSTEM: ^{GRAV} APPROVED 25% REDUCTION

REPAIR ^{GRAV} Approved 25% Reduction

DISTRIBUTION: D-Box

DISTRIBUTION D-Box

BENCHMARK: 100.0

LOCATION Tos B c 90/91

NO. BEDROOMS: 4

LTAR 0.35

LINE	FLAG COLOR	ELEVATION	LENGTH
1	O	97.50	90
2	B	97.08	90
3	O	96.91	90
4	B	96.75	90
			360

5	O	96.50	90
6	B	96.00	90
7	O	95.58	90
8	B	95.08	90
			360

BY B.C. RAYNOR

DATE 03/15/2024

TYPICAL PROFILE

THERE SHALL BE NO GRADING,

0-20 LS VFR GR

CUTTING, LOGGING OR OTHER SOIL

20-36 SCL Fi SBK

DISTURBANCE IN SEPTIC AREA

CR2 ≥ 36"

HEALTH DEPARTMENT USE ONLY.

DESIGNS DO NOT GUARANTEE FUNCTIONALITY

Southeastern Soil & Environmental Associates LLC
PO Box 9321 Fayetteville, NC 28311
Mike@southeasternsoil.com
(910) 822-4540

Elyse Meadow Preliminary Septic Evaluation

