


Second Floor:



Products				
PlotID	Net Qty	Product	Length	Plies
FJ1	14	14" FWI 205 or LPI 20Plus	37' 0"	1
FJ2	3	14" FWI 205 or LPI 20Plus	23' 0"	1
FJ3	6	14" FWI 205 or LPI 20Plus	22' 0"	1
FJ4	2	14" FWI 205 or LPI 20Plus	22' 0"	2
FJ5	9	14" FWI 205 or LPI 20Plus	21' 0"	1
FJ6	7	14" FWI 205 or LPI 20Plus	18' 0"	1
FJ7	8	14" FWI 205 or LPI 20Plus	16' 0"	1
FJ8	2	14" FWI 205 or LPI 20Plus	8' 0"	1
FJ9	1	14" FWI 205 or LPI 20Plus	5' 0"	1
FJ10	1	14" FWI 205 or LPI 20Plus	3' 0"	1
FJ11	1	14" FWI 205 or LPI 20Plus	2' 0"	1
BM1	4	1-3/4x 14 2.0E 2900Fb PWT LVL	20' 0"	4
BM2	2	1-3/4x 14 2.0E 2900Fb PWT LVL	16' 0"	2
BM3	4	1-3/4x 14 2.0E 2900Fb PWT LVL	8' 0"	2
BM4	2	1-3/4x 16 2.0E 2900Fb PWT LVL	22' 0"	2
BM5	2	1-3/4x 24 2.0E 2900Fb PWT LVL	22' 0"	2
BM6	2	1-3/4x 24 2.0E 2900Fb PWT LVL	16' 0"	2
BB04	2	1 1/2" x 7 1/4" Generic Material	10' 0"	2
RB1	14	1" x 14" BC RIM BOARD OSB	12' 0"	1
Bk1	1	14" FWI 205 or LPI 20Plus	17' 0"	1

Connector Summary			
PlotID	Qty	Manuf	Product
H1	3		ITS2.56/14
H1	3	Simpson	ITS2.56/14
H2	1	Simpson	ITS2.56/14
H3	1	Simpson	IUS2.56/14
H4	4	Simpson	IUS2.56/14
H5	18	Simpson	IUS2.56/14

Preliminary
Not for
Construction

General Notes:

- See Boise Cascade Installation Guide for Installation/Finishing details.
- All Measurements to be verified in the field.
- All I-Joist, LVL beams, and Rim Board must be field cut to length.
- Contractor to verify and approve the provided material list on this layout.
- The material provided is sold as a complete package, custom cut for this job; therefore, any cut lengths or pieces of cut lengths MAY NOT be returned for credit.
- Any material discrepancies must be reported before installation. Contact Talbert Building Supply at 336-599-1135.
- See original blueprints for additional structural notes.
- Ceramic tiles floors should be supported per APA standards. Additional joists may be required.
- Plumbing, HVAC, and Electrical trade to reference Boise Cascade Specifier or Installation Guide for hole cutting information.
- Boise Cascade/Talbert Building Supply is NOT the Engineer of Record. These plans are for the EoR to review and verify all bracing/load points are picked up properly. These plans are for gravity loads only and NOT lateral. Design and pricing hinges on EoR review/approval.
- Framing Note: Install all LVL with stamps/printing facing out for visibility.
- This layout was designed based on the Construction Documents and instruction provided to Talbert Building Supply by the contractor/home owner.

Builder:

Drees Homes

Job Name:

Brenner Residence

Address:

Sneed Lane

Raleigh, NC

Date: 7/25/25

By: WH

