

Trenco 818 Soundside Rd Edenton, NC 27932

Re: 251447-A

Lot 65 Magnolia Hills

The truss drawing(s) referenced below have been prepared by Truss Engineering Co. under my direct supervision based on the parameters provided by Comtech, Inc - Fayetteville.

Pages or sheets covered by this seal: I76645091 thru I76645126

My license renewal date for the state of North Carolina is December 31, 2025.

North Carolina COA: C-0844



September 26,2025

Galinski, John

**IMPORTANT NOTE:** The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to MiTek or TRENCO. Any project specific information included is for MiTek's or TRENCO's customers file reference purpose only, and was not taken into account in the preparation of these designs. MiTek or TRENCO has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.


	1.000	1,1000 1,740		' '			176645091
251447-A	A1	HIP GIRDER	1	2			
					Job Reference (optional)		
Comtech, Inc,	Fayetteville, NC - 283	14,	25	5.3.0 s Sep	17 2025 MiTek Industries, II	nc. Thu Sep 25 23:33:10	0 2025 Page 1
			ID:3YJEg_u8zX16F	RsP?VvW_\	V6zd0wB-wmA5hm6Nwz6sr	nvz8G799FqasYE1Koj?	KusnJSYyZxNt
<sub>-</sub> 1-2-8	6-0-0	14-2-15	22-4-1		30-7-0	36-7-0	37-9-8
1-2-8	6-0-0	8-2-15	8-1-3		8-2-15	6-0-0	1-2-8

Qtv

Plv

Lot 65 Magnolia Hills

Scale = 1:65.6



	<b>—</b>	6-0-0	14-2-15			22-4-1		30-		36-7-0	
		6-0-0	8-2-15			8-1-3	<u>'</u>	8-2	-15	6-0-0	<u> </u>
Plate Offsets	s (X,Y)	[3:0-5-8,0-2-12]									
TCDL 1	psf) 20.0 0.0 0.0 *	SPACING- Plate Grip Lumber DO Rep Stress	DOL 1.15 DL 1.15	BC 0	0.36 0.50 0.90	DEFL. Vert(LL) Vert(CT) Horz(CT)	in (loc) -0.15 11-14 -0.31 11-14 0.08 8	l/defl >999 >999 n/a	L/d 360 240 n/a	PLATES MT20	<b>GRIP</b> 244/190
	0.0		2021/TPI2014	Matrix-S		Wind(LL)	0.17 11-14	>999	240	Weight: 489 lb	FT = 20%

**BRACING-**

TOP CHORD

**BOT CHORD** 

LUMBER-

Job

Truss

Truss Type

TOP CHORD 2x6 SP No 1 2x6 SP No.1

BOT CHORD **WEBS** 2x4 SP No.2

REACTIONS. 2=0-3-8, 8=0-3-8 (size) Max Horz 2=-114(LC 27)

Max Uplift 2=-653(LC 8), 8=-653(LC 9) Max Grav 2=2833(LC 1), 8=2833(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

2-3=-4582/1149, 3-4=-6354/1682, 4-6=-6351/1682, 6-7=-3751/991, 7-8=-4580/1148 TOP CHORD

**BOT CHORD** 2-15=-975/3683, 14-15=-974/3704, 11-14=-1677/6353, 10-11=-1651/6351,


8-10=-875/3683

**WEBS** 3-15=0/728, 3-14=-868/3008, 4-14=-1007/593, 6-11=0/675, 6-10=-2968/858,

7-10=-358/1913

## NOTES-

- 1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows: Top chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc. Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc. Webs connected as follows: 2x4 - 1 row at 0-9-0 oc.
- 2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to
- ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated. 3) Unbalanced roof live loads have been considered for this design.
- 4) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope); Lumber DOL=1.60 plate grip DOL=1.60
- 5) Provide adequate drainage to prevent water ponding.
- 6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 7) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 653 lb uplift at joint 2 and 653 lb uplift at joint 8.
- 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



Structural wood sheathing directly applied or 6-0-0 oc purlins, except

September 26,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall

building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TP11 Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacomponents.com)



Job	Truss	Truss Type	Qty	Ply	Lot 65 Magnolia Hills
054.447.4		LUD OUDDED			176645091
251447-A	A1	HIP GIRDER	1	2	Job Reference (optional)

Comtech, Inc,

Fayetteville, NC - 28314,

25.3.0 s Sep 17 2025 MiTek Industries, Inc. Thu Sep 25 23:33:10 2025 Page 2 ID:3YJEg\_u8zX16RsP?VvW\_V6zd0wB-wmA5hm6Nwz6snvz8G799FqasYE1Koj?XusnJSYyZxNt

## NOTES-

10) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 137 lb down and 121 lb up at 6-0-0, 142 lb down and 118 lb up at 8-0-12, 142 lb down and 118 lb up at 10-0-12, 142 lb down and 118 lb up at 12-0-12, 142 lb down and 118 lb up at 14-0-12, 142 lb down and 118 lb up at 16-0-12, 142 lb down and 118 lb up at 16-0-12, 142 lb down and 118 lb up at 16-0-12, 142 lb down and 118 lb up at 16-0-12, 142 lb down and 118 lb up at 16-0-12, 142 lb down and 118 lb up at 16-0-12, 142 lb down and 118 lb up at 16-0-12, 142 lb down and 118 lb up at 16-0-12, 142 lb down and 118 lb up at 16-0-12, 142 lb down and 118 lb up at 16-0-12, 142 lb down and 118 lb up at 16-0-12, 142 lb down and 118 lb up at 16-0-12, 142 lb down and 118 lb up at 16-0-12, 142 lb down and 118 lb up at 16-0-12, 142 lb down and 118 lb up at 16-0-12, 142 lb down and 118 lb up at 16-0-12, 142 lb down and 118 lb up at 16-0-12, 142 lb down and 118 lb up at 16-0-12, 142 lb down and 118 lb up at 16-0-12, 142 lb down and 118 lb up at 16-0-12, 142 lb down and 118 lb up at 16-0-12, 142 lb down and 118 lb up at 16-0-12, 142 lb down and 118 lb up at 16-0-12, 142 lb down and 118 lb up at 16-0-12, 142 lb down and 118 lb up at 16-0-12, 142 lb down and 118 lb up at 16-0-12, 142 lb down and 118 lb up at 16-0-12, 142 lb down and 18 lb up at 16-0-12, 142 lb down and 18 lb up at 16-0-12, 142 lb down and 18 lb up at 16-0-12, 142 lb down and 18 lb up at 16-0-12, 142 lb down and 18 lb up at 16-0-12, 142 lb down and 18 lb up at 16-0-12, 142 lb down and 18 lb up at 16-0-12, 142 lb down and 18 lb up at 16-0-12, 142 lb down and 18 lb up at 16-0-12, 142 lb down and 18 lb up at 16-0-12, 142 lb down and 18 lb up at 16-0-12, 142 lb down and 18 lb up at 16-0-12, 142 lb down and 18 lb up at 16-0-12, 142 lb down and 18 lb up at 16-0-12, 142 lb down and 18 lb up at 16-0-12, 142 lb down and 18 lb up at 16-0-12, 142 lb down and 18 lb up at 16-0-12, 142 lb down and 18 lb up at 16-0-12, 142 lb down and 18 lb up at 16-0-12, 142 lb down and 18 lb up at 16-0-12, 142 lb down and 18 lb up at 16-0-12, 142 lb down and 18 lb up at 16-0-12, 142 lb down and 18 lb up at 16-0-12, 142 lb down and 18 lb up at 16-0-12, 142 lb dow lb down and 118 lb up at 18-0-12, 142 lb down and 118 lb up at 18-6-4, 142 lb down and 118 lb up at 20-6-4, 142 lb down and 118 lb up at 20-6-4, 142 lb down and 118 lb up at 20-6-4, 142 lb down and 118 lb up at 20-6-4, 142 lb down and 118 lb up at 20-6-4, 142 lb down and 118 lb up at 20-6-4, 142 lb down and 118 lb up at 20-6-4, 142 lb down and 118 lb up at 20-6-4, 142 lb down and 118 lb up at 20-6-4, 142 lb down and 118 lb up at 20-6-4, 142 lb down and 118 lb up at 20-6-4, 142 lb down and 118 lb up at 20-6-4, 142 lb down and 118 lb up at 20-6-4, 142 lb down and 118 lb up at 20-6-4, 142 lb down and 118 lb up at 20-6-4, 142 lb down and 118 lb up at 20-6-4, 142 lb down and 118 lb up at 20-6-4, 142 lb down and 118 lb up at 20-6-4, 142 lb down and 118 lb up at 20-6-4, 142 lb down and 118 lb up at 20-6-4, 142 lb down and 118 lb up at 20-6-4, 142 lb down and 118 lb up at 20-6-4, 142 lb down and 118 lb up at 20-6-4, 142 lb down and 118 lb up at 20-6-4, 142 lb down and 118 lb up at 20-6-4, 142 lb down and 118 lb up at 20-6-4, 142 lb down and 118 lb up at 20-6-4, 142 lb down and 118 lb up at 20-6-4, 142 lb down and 118 lb up at 20-6-4, 142 lb down and 118 lb up at 20-6-4, 142 lb down and 118 lb up at 20-6-4, 142 lb down and 118 lb up at 20-6-4, 142 lb down and 118 lb up at 20-6-4, 142 lb down and 118 lb up at 20-6-4, 142 lb down and 118 lb up at 20-6-4, 142 lb down and 118 lb up at 20-6-4, 142 lb down and 118 lb up at 20-6-4, 142 lb down and 118 lb up at 20-6-4, 142 lb down and 118 lb up at 20-6-4, 142 lb down and 118 lb up at 20-6-4, 142 lb down and 118 lb up at 20-6-4, 142 lb down and 118 lb up at 20-6-4, 142 lb down and 118 lb up at 20-6-4, 142 lb down and 118 lb up at 20-6-4, 142 lb down and 118 lb up at 20-6-4, 142 lb down and 20-6-4 lb up at 24-6-4, 142 lb down and 118 lb up at 26-6-4, and 142 lb down and 118 lb up at 28-6-4, and 137 lb down and 121 lb up at 30-7-0 on top chord, and 354 lb down and 123 lb up at 6-0-0, 76 lb down at 8-0-12, 76 lb down at 10-0-12, 76 lb down at 12-0-12, 76 lb down at 14-0-12, 76 lb down at 18-6-4, 76 lb down at 22-6-4, 76 lb down at 22-6-4, 76 lb down at 22-6-4, 76 lb down at 23-6-4, and 354 lb down at 25-6-4, and 354 lb d 30-6-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

## LOAD CASE(S) Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15 Uniform Loads (plf)

Vert: 1-3=-60, 3-7=-60, 7-9=-60, 2-8=-20

Concentrated Loads (lb)

Vert: 3=-104(B) 7=-104(B) 13=-38(B) 15=-351(B) 14=-38(B) 4=-104(B) 11=-38(B) 6=-104(B) 10=-351(B) 12=-38(B) 16=-104(B) 17=-104(B) 18=-104(B) 19=-104(B) 20=-104(B) 21=-104(B) 22=-104(B) 23=-104(B) 24=-104(B) 25=-104(B) 25=-104(B) 25=-38(B) 27=-38(B) 28=-38(B) 29=-38(B) 30=-38(B) 31=-38(B) 32=-38(B) 32=-38(B) 32=-38(B) 31=-38(B) 31=-38(B)



Job Truss Truss Type Qty Ply Lot 65 Magnolia Hills 176645092 HIP 251447-A A2 Job Reference (optional) Fayetteville, NC - 28314, 25.3.0 s Sep 17 2025 MiTek Industries, Inc. Thu Sep 25 23:33:11 2025 Page 1 Comtech, Inc. ID:3YJEg\_u8zX16RsP?VvW\_V6zd0wB-PykTv67?hHEjP2YLqrhOo26?4dNGXGlg6WXt\_?yZxNs

28-7-0

10-3-8

18-3-8

10-3-8

Scale = 1:68.0


36-7-0

8-0-0

Structural wood sheathing directly applied or 4-8-2 oc purlins, except

2-0-0 oc purlins (4-1-0 max.): 3-6.

Rigid ceiling directly applied or 10-0-0 oc bracing.



<u> </u>	8-0-0	18-3-8	28-7-0	36-7-0
	8-0-0	10-3-8	10-3-8	8-0-0
LOADING (psf) TCLL 20.0 TCDL 10.0 BCLL 0.0 * BCDL 10.0	SPACING-         2-0-0           Plate Grip DOL         1.15           Lumber DOL         1.15           Rep Stress Incr         YES           Code IRC2021/TPI2014	CSI. TC 0.50 BC 0.45 WB 0.48 Matrix-S	DEFL.         in (loc)         l/defl         L/d           Vert(LL)         -0.14         9-11         >999         360           Vert(CT)         -0.27         9-11         >999         240           Horz(CT)         0.07         7         n/a         n/a           Wind(LL)         0.08         11         >999         240	PLATES GRIP MT20 244/190  Weight: 241 lb FT = 20%

**BRACING-**

TOP CHORD

**BOT CHORD** 

LUMBER-

TOP CHORD 2x6 SP No.1 BOT CHORD 2x6 SP No.1

2x4 SP No.2 WFBS

REACTIONS. (size) 2=0-3-8, 7=0-3-8 Max Horz 2=-144(LC 10)

Max Uplift 2=-55(LC 9), 7=-55(LC 8) Max Grav 2=1682(LC 2), 7=1682(LC 2)

8-0-0

8-0-0

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown. 2-3=-2506/285, 3-4=-2923/369, 4-6=-2922/368, 6-7=-2508/285 TOP CHORD **BOT CHORD** 2-13=-134/1985, 11-13=-137/1973, 9-11=-88/1975, 7-9=-86/1987 **WEBS** 3-13=0/500, 3-11=-202/1140, 4-11=-729/251, 6-11=-202/1137, 6-9=0/500

## NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2E) -1-0-15 to 3-3-14, Interior(1) 3-3-14 to 8-0-0, Exterior(2R) 8-0-0 to 14-2-11, Interior(1) 14-2-11 to 28-7-0, Exterior(2R) 28-7-0 to 34-9-11, Interior(1) 34-9-11 to 37-7-15 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 55 lb uplift at joint 2 and 55 lb uplift at
- 7) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



September 26,2025



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall

building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TP11 Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacomponents.com)



Job Truss Truss Type Qty Ply Lot 65 Magnolia Hills 176645093 HIP 251447-A A3 Job Reference (optional) Fayetteville, NC - 28314, 25.3.0 s Sep 17 2025 MiTek Industries, Inc. Thu Sep 25 23:33:11 2025 Page 1 Comtech, Inc. ID:3YJEg\_u8zX16RsP?VvW\_V6zd0wB-PykTv67?hHEjP2YLqrhOo26z5dMPXHkg6WXt\_?yZxNs

26-7-0

18-3-8

8-3-8

Scale = 1:68.0


36-7-0

10-0-0

Structural wood sheathing directly applied or 3-9-14 oc purlins,

2-0-0 oc purlins (4-9-0 max.): 3-6.

Rigid ceiling directly applied or 10-0-0 oc bracing.



	10-0-0	8-3-8	26-7-0 8-3-8	36-7-0 10-0-0	
LOADING (psf) TCLL 20.0 TCDL 10.0 BCLL 0.0 * BCDL 10.0	SPACING- 2-0-0 Plate Grip DOL 1.15 Lumber DOL 1.15 Rep Stress Incr YES Code IRC2021/TPI2014	TC 0.63 V BC 0.57 V WB 0.42 F	EFL. in (loc) I/defl ert(LL) -0.13 2-13 >999 ert(CT) -0.23 2-13 >999 orz(CT) 0.07 7 n/a //ind(LL) 0.06 2-13 >999	L/d PLATES GRIP 360 MT20 244/190 240 n/a 240 Weight: 246 lb FT = 20	0%

**BRACING-**

TOP CHORD

**BOT CHORD** 

LUMBER-

TOP CHORD 2x6 SP No.1 2x6 SP No.1 BOT CHORD

2x4 SP No.2 **WEBS** 

REACTIONS. (size) 2=0-3-8, 7=0-3-8

Max Horz 2=-176(LC 10)

Max Uplift 2=-50(LC 12), 7=-50(LC 13) Max Grav 2=1826(LC 2), 7=1826(LC 2)

10-0-0

10-0-0

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown. 2-3=-2609/296, 3-4=-2484/360, 4-6=-2482/359, 6-7=-2610/296 TOP CHORD **BOT CHORD** 2-13=-102/2050, 11-13=-104/2037, 9-11=-75/2038, 7-9=-74/2051 **WEBS** 3-13=0/683, 3-11=-176/666, 4-11=-564/202, 6-11=-176/664, 6-9=0/683

## NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2E) -1-0-15 to 3-3-14, Interior(1) 3-3-14 to 10-0-0, Exterior(2R) 10-0-0 to 16-2-11, Interior(1) 16-2-11 to 26-7-0, Exterior(2R) 26-7-0 to 32-9-11, Interior(1) 32-9-11 to 37-7-15 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 50 lb uplift at joint 2 and 50 lb uplift at
- 7) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



September 26,2025



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall

building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TP11 Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacomponents.com)




Job Truss Truss Type Qty Ply Lot 65 Magnolia Hills 176645094 251447-A ROOF SPECIAL A4 Job Reference (optional)

Fayetteville, NC - 28314, Comtech, Inc.

25.3.0 s Sep 17 2025 MiTek Industries, Inc. Thu Sep 25 23:33:12 2025 Page 1

ID:3YJEg\_u8zX16RsP?VvW\_V6zd0wB-t9Ir6S8dSbMa1C7XOYCdKFf5?1heGl8qLAGQXRyZxNr 12-0-0 17-3-8 22-7-0 24-4-8 26-4-8 36-7-0 37-9-8 1-2-8 5-3-8 5-8-2 5-3-8 1-9-8 2-0-0 10-2-8

Scale = 1:69.1



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	\ /	/defl L/d	PLATES	GRIP	
Plate Offsets (X,Y)	[8:0-3-0,0-3-13]								
	12-0	)-0	ı	10-7-0	3-9	9-8 0-2-0	10-0-8		
	12-0	)-0		22-1-0	20-	4-0 201φ-0	30-7-0		

22-7-0

LC 1.15 0.81 Vert(LL) -0.23 14-17 244/190 20.0 Plate Grip DOL >999 360 MT20 вс Vert(CT) **TCDL** 10.0 Lumber DOL 1.15 0.64 -0.34 14-17 >999 240 WB **BCLL** 0.0 Rep Stress Incr YES 0.34 Horz(CT) 0.06 11 n/a n/a BCDL Code IRC2021/TPI2014 Matrix-S Wind(LL) 0.06 11-13 FT = 20% 10.0 >999 240 Weight: 274 lb

LUMBER-

Р

TOP CHORD 2x6 SP No 1 2x6 SP No.1

BOT CHORD WFBS 2x4 SP No 2 **BRACING-**TOP CHORD

Structural wood sheathing directly applied or 3-11-0 oc purlins,

36-7-0

2-0-0 oc purlins (3-10-5 max.): 5-7, 9-10.

26-4-8

26-6-8

**BOT CHORD** Rigid ceiling directly applied or 10-0-0 oc bracing. WEBS 2x4 SPF No.2 - 6-17, 6-14

Fasten (2X) T and I braces to narrow edge of web with 10d (0.131"x3") nails, 6in o.c., with 3in minimum end distance.

Brace must cover 90% of web length.

REACTIONS. (size) 2=0-3-8, 11=0-3-8

Max Horz 2=210(LC 11)

Max Uplift 2=-64(LC 12), 11=-79(LC 13) Max Grav 2=1717(LC 19), 11=1777(LC 2)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

12-0-0

TOP CHORD 2-3=-2455/483, 3-5=-2221/440, 5-6=-1766/427, 6-7=-1911/452, 7-8=-2218/495,

8-10=-1901/405, 10-11=-2474/430

**BOT CHORD** 2-17=-291/2064, 14-17=-160/1928, 13-14=-165/1959, 11-13=-164/1967 **WEBS** 3-17=-341/240, 5-17=-87/918, 6-17=-389/173, 9-14=-78/428, 7-9=-152/832,

10-13=0/430

## NOTES-

1) Unbalanced roof live loads have been considered for this design.

- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2E) -1-0-15 to 3-3-14, Interior(1) 3-3-14 to 12-0-0, Exterior(2R) 12-0-0 to 16-4-13, Interior(1) 16-4-13 to 22-7-0, Exterior(2E) 22-7-0 to 24-4-8, Interior(1) 24-4-8 to 26-4-8, Exterior(2R) 26-4-8 to 30-9-5, Interior(1) 30-9-5 to 37-7-15 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 64 lb uplift at joint 2 and 79 lb uplift at ioint 11.
- 7) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- 8) Warning: Additional permanent and stability bracing for truss system (not part of this component design) is always required.



September 26,2025



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall

building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TP11 Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacomponents.com)



Job Truss Truss Type Qty Ply Lot 65 Magnolia Hills 176645095 **ROOF SPECIAL** 251447-A A5 Job Reference (optional)

Fayetteville, NC - 28314, Comtech, Inc.

25.3.0 s Sep 17 2025 MiTek Industries, Inc. Thu Sep 25 23:33:12 2025 Page 1 ID:3YJEg\_u8zX16RsP?VvW\_V6zd0wB-t9Ir6S8dSbMa1C7XOYCdKFf7e1kQGfOqLAGQXRyZxNr

Scale = 1:69.3




Plate Offsets (X,Y)	[7:0-3-0,0-3-13], [9:0-4-0,0-3-15], [13:0-	2-12,0-4-8]	1-10-0	
LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) I/defl L/d	PLATES GRIP
TCLL 20.0	Plate Grip DOL 1.15	TC 0.64	Vert(LL) -0.15 13-15 >999 360	MT20 244/190
TCDL 10.0	Lumber DOL 1.15	BC 0.39	Vert(CT) -0.26 13-15 >999 240	
BCLL 0.0 *	Rep Stress Incr YES	WB 0.71	Horz(CT) 0.06 10 n/a n/a	
BCDL 10.0	Code IRC2021/TPI2014	Matrix-S	Wind(LL) 0.08 13 >999 240	Weight: 287 lb FT = 20%

LUMBER-TOP CHORD

2x6 SP No.1 \*Except\*

**BOT CHORD** 2x6 SP No.1

8-9: 2x6 SP 2400F 2.0E

**WEBS** 2x4 SP No.2 **BRACING-**TOP CHORD

**JOINTS** 

Structural wood sheathing directly applied or 4-9-0 oc purlins, except

2-0-0 oc purlins (6-0-0 max.): 5-6, 8-9.

**BOT CHORD** Rigid ceiling directly applied or 10-0-0 oc bracing. WEBS T-Brace: 2x4 SPF No.2 - 9-13, 5-13

Fasten (2X) T and I braces to narrow edge of web with 10d (0.131"x3") nails, 6in o.c., with 3in minimum end distance.

Brace must cover 90% of web length. 1 Brace at Jt(s): 8

REACTIONS. (size) 2=0-3-8, 10=0-3-8

Max Horz 2=241(LC 11)

Max Uplift 2=-76(LC 12), 10=-90(LC 13) Max Grav 2=1719(LC 19), 10=1728(LC 20)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-2475/445, 3-5=-1972/472, 5-6=-1619/472, 6-7=-1972/469, 7-9=-1592/306,

9-10=-2511/456

**BOT CHORD** 2-16=-243/2116, 15-16=-243/2116, 13-15=-70/1603, 12-13=-235/2018, 10-12=-233/2028

**WEBS** 3-16=0/296, 3-15=-629/217, 5-15=-59/711, 8-13=0/505, 6-8=-51/702, 9-13=-582/206,

## NOTES-

1) Unbalanced roof live loads have been considered for this design.

- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2E) -1-0-15 to 3-3-14, Interior(1) 3-3-14 to 14-0-0, Exterior(2R) 14-0-0 to 18-4-13, Interior(1) 18-4-13 to 20-7-0, Exterior(2R) 20-7-0 to 24-11-13, Interior(1) 24-11-13 to 28-4-8, Exterior(2R) 28-4-8 to 32-9-5, Interior(1) 32-9-5 to 37-7-15 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 76 lb uplift at joint 2 and 90 lb uplift at joint 10.
- 7) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- 8) Warning: Additional permanent and stability bracing for truss system (not part of this component design) is always required.



September 26,2025



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall

building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TP11 Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacomponents.com)




Job Truss Truss Type Qty Ply Lot 65 Magnolia Hills 176645096 **ROOF SPECIAL** 251447-A A6 Job Reference (optional)

Fayetteville, NC - 28314, Comtech, Inc.

25.3.0 s Sep 17 2025 MiTek Industries, Inc. Thu Sep 25 23:33:13 2025 Page 1 ID:3YJEg\_u8zX16RsP?VvW\_V6zd0wB-LLsDKo8FDuUReMijxGjstTBMGR\_V?6Lzaq0\_3tyZxNq

13-3-8 6-7-12 16-0-8 18-6-8 21-3-8 28-5-0 30-5-0 <u>36-7-</u>0 2-0-0 2-9-0 2-6-0 2-9-0 6-2-0

Scale = 1:83.4



	1	6-7-12	13-3-8	21-3-8	30-5-0	30 <sub>1</sub> 7-0	36-7-0	
	Г	6-7-12	6-7-12	8-0-0	9-1-8	0-2-0	6-0-0	1
Plate Offsets (X,Y)	[6:0-3-0.0-	3-61. [7:0-3-0.0-3-6]. [9	9:0-3-0.0-3-8], [14:0-2-	12.0-2-8]. [15:0-2-12.0-2-0]. [	17:0-1-8.0-2-01			

	, . ,	[	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	[ = .=,- = -], [ : -,- = -]	
LOADING	G (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) I/defl L/d	PLATES GRIP
TCLL	20.0	Plate Grip DOL 1.15	TC 0.40	Vert(LL) -0.27 13-14 >999 360	MT20 244/190
TCDL	10.0	Lumber DOL 1.15	BC 0.79	Vert(CT) -0.42 13-14 >999 240	
BCLL	0.0 *	Rep Stress Incr YES	WB 0.73	Horz(CT) 0.07 11 n/a n/a	
BCDL	10.0	Code IRC2021/TPI2014	Matrix-S	Wind(LL) 0.18 13-14 >999 240	Weight: 309 lb FT = 20%

LUMBER-

TOP CHORD 2x6 SP No 1 2x6 SP No.1

BOT CHORD WFBS 2x4 SP No.2 \*Except\*

5-8: 2x6 SP No.1

BRACING-TOP CHORD

**JOINTS** 

Structural wood sheathing directly applied or 4-7-8 oc purlins, except

2-0-0 oc purlins (5-4-15 max.): 6-7, 9-10. BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

WEBS T-Brace: 2x4 SPF No.2 - 9-14

Fasten (2X) T and I braces to narrow edge of web with 10d (0.131"x3") nails, 6in o.c., with 3in minimum end distance.

Brace must cover 90% of web length. 1 Brace at Jt(s): 21

REACTIONS. (size) 2=0-3-8, 11=0-3-8

Max Horz 2=272(LC 11)

Max Uplift 2=-85(LC 12), 11=-98(LC 13) Max Grav 2=1801(LC 19), 11=1766(LC 20)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-2625/415, 3-5=-2189/443, 5-6=-824/182, 6-7=-752/190, 7-8=-822/181,

8-9=-2230/448, 9-10=-2109/411, 10-11=-2668/417


**BOT CHORD** 2-18=-225/2261, 17-18=-225/2261, 14-17=-113/1863, 13-14=-308/2528, 11-13=-221/2106 **WEBS** 

3-17=-492/195, 17-19=-16/688, 14-20=-6/838, 9-13=-1008/221, 10-13=-108/1225,

9-14=-998/273, 5-19=-1241/362, 19-21=-1241/362, 20-21=-1171/352, 8-20=-1171/352, 6-21=-56/448, 7-21=-79/337

# NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2E) -1-0-15 to 3-3-14, Interior(1) 3-3-14 to 16-0-8, Exterior(2E) 16-0-8 to 18-6-8, Exterior(2R) 18-6-8 to 22-9-14, Interior(1) 22-9-14 to 30-5-0, Exterior(2R) 30-5-0 to 34-9-13, Interior(1) 34-9-13 to 37-7-15 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 85 lb uplift at joint 2 and 98 lb uplift at joint 11.
- 7) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- 8) Warning: Additional permanent and stability bracing for truss system (not part of this component design) is always required.



September 26,2025



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall


building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TP11 Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacomponents.com)



Job Truss Truss Type Qty Ply Lot 65 Magnolia Hills 176645097 251447-A A7 ROOF SPECIAL Job Reference (optional)

Fayetteville, NC - 28314, Comtech, Inc.

25.3.0 s Sep 17 2025 MiTek Industries, Inc. Thu Sep 25 23:33:14 2025 Page 1 ID:3YJEg\_u8zX16RsP?VvW\_V6zd0wB-pXPcX79tzCclGWHwVzE5PgkXBrJlkZg7oUlXbKyZxNp



Scale = 1:88.1




Plate Offsets (X,Y)-- [9:0-2-12,0-3-8], [10:0-3-0,0-3-6], [14:0-2-8,0-2-8], [15:0-2-8,0-2-0], [17:0-1-8,0-2-12]

LOADIN	G (psf)	SPACING- 2-0-0	CSI.	<b>DEFL</b> . ir	n (loc)	l/defl	L/d	PLATES	GRIP
TCLL	20.0	Plate Grip DOL 1.15	TC 0.38	Vert(LL) -0.32	13-14	>999	360	MT20	244/190
TCDL	10.0	Lumber DOL 1.15	BC 0.88	Vert(CT) -0.49	13-14	>891	240		
BCLL	0.0 *	Rep Stress Incr YES	WB 0.72	Horz(CT) 0.07	' 11	n/a	n/a		
BCDL	10.0	Code IRC2021/TPI2014	Matrix-S	Wind(LL) 0.22	13-14	>999	240	Weight: 306 lb	FT = 20%

LUMBER-TOP CHORD 2x6 SP No 1

BOT CHORD 2x6 SP No.1

**WEBS** 2x4 SP No.2 \*Except\*

5-7: 2x6 SP No.1

**BRACING-**TOP CHORD

**JOINTS** 

Structural wood sheathing directly applied or 4-7-6 oc purlins, except

2-0-0 oc purlins (4-4-4 max.): 9-10.

**BOT CHORD** Rigid ceiling directly applied or 10-0-0 oc bracing. WEBS T-Brace: 2x4 SPF No.2 - 9-14

Fasten (2X) T and I braces to narrow edge of web with 10d (0.131"x3") nails, 6in o.c., with 3in minimum end distance.

Brace must cover 90% of web length. 1 Brace at Jt(s): 21

REACTIONS. (size) 2=0-3-8, 11=0-3-8

Max Horz 2=-294(LC 10)

Max Uplift 2=-90(LC 12), 11=-102(LC 13) Max Grav 2=1818(LC 19), 11=1778(LC 20)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-2650/392, 3-5=-2260/447, 5-6=-794/134, 6-7=-815/135, 7-9=-2323/424,

9-10=-3250/535, 10-11=-2698/425

**BOT CHORD** 2-18=-203/2297, 17-18=-203/2297, 14-17=-113/1915, 13-14=-377/3160, 11-13=-250/2148 **WEBS** 3-17=-495/220, 9-13=-1071/290, 10-13=-247/1756, 9-14=-1515/315, 5-19=-1304/412,

19-21=-1304/412, 20-21=-1304/412, 7-20=-1304/412, 17-19=-15/685, 14-20=0/814,

6-21=0/549

## NOTES-

- Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2E) -1-0-15 to 3-3-14, Interior(1) 3-3-14 to 17-3-8, Exterior(2R) 17-3-8 to 21-8-5, Interior(1) 21-8-5 to 32-5-0, Exterior(2R) 32-5-0 to 36-9-13, Interior(1) 36-9-13 to 37-7-15 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 90 lb uplift at joint 2 and 102 lb uplift at
- 7) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- 8) Warning: Additional permanent and stability bracing for truss system (not part of this component design) is always required.



September 26,2025



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall

building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TP11 Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacomponents.com)




Job Truss Truss Type Qty Ply Lot 65 Magnolia Hills 176645098 ROOF SPECIAL GIRDER 251447-A **A8** Job Reference (optional)

Fayetteville, NC - 28314, Comtech, Inc.

25.3.0 s Sep 17 2025 MiTek Industries, Inc. Thu Sep 25 23:33:14 2025 Page 1 ID:3YJEg\_u8zX16RsP?VvW\_V6zd0wB-pXPcX79tzCcIGWHwVzE5PgkX3rM3kZY7oUIXbKyZxNp

18-6-8 21-3-8 2-6-0 2-9-0 6-7-12 1-2-8

Scale = 1:84.4



	1	6-7-12	13-3-8	1 16-0-8 I	18-6-8	21-3-8 21-7-0	27-11-4	<sub>1</sub> 34-5-0	34 <sub>1</sub> 7-0	1
		6-7-12	6-7-12	2-9-0	2-6-0	2-9-0 0-3-8	6-4-4	6-5-12	0-2-0	1
									2-0-0	
									200	_
Plate Offsets (X Y)	[6:0-3-0 0-3-6]	[7:0-3-0 0-3-6] [13	2.0-4-0 0-2-131 [17:0-	-2-12 0-2-81	[18:0-2-	12 0-2-01 [20:0	1-1-8 0-2-01			

I late Oil	13013 (A, I )	[0.0-3-0,0-3-0], [1.0-3-0,0-3-	-0], [12.0-4-0	0,0-2-10], [1	1.0-2-12,0-2-	0], [10.0-2-12,0-2-	0], [20.0-1-0,0-2	<u>0j</u>			
LOADIN	G (psf)	SPACING- 2	2-0-0	CSI.		DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL	20.0	Plate Grip DOL	1.15	TC	0.39	Vert(LL)	-0.25 16-17	>999	360	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.70	Vert(CT)	-0.39 16-17	>999	240		
BCLL	0.0 *	Rep Stress Incr	NO	WB	0.73	Horz(CT)	0.08 13	n/a	n/a		
BCDL	10.0	Code IRC2021/TPI2	2014	Matri	x-S	Wind(LL)	0.17 16-17	>999	240	Weight: 315 lb	FT = 20%

LUMBER-

TOP CHORD 2x6 SP No 1 BOT CHORD 2x6 SP No.1 WFBS

2x4 SP No.2 \*Except\* 5-8: 2x6 SP No.1

**BRACING-**TOP CHORD

**JOINTS** 

Structural wood sheathing directly applied or 4-4-6 oc purlins, except

2-0-0 oc purlins (5-7-7 max.): 6-7, 11-12.

BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing. WEBS T-Brace: 2x4 SPF No.2 - 10-17

Fasten (2X) T and I braces to narrow edge of web with 10d (0.131"x3") nails, 6in o.c., with 3in minimum end distance.

Brace must cover 90% of web length. 1 Brace at Jt(s): 24

REACTIONS. (size) 2=0-3-8, 13=0-3-8

Max Horz 2=273(LC 7)

Max Uplift 2=-86(LC 8), 13=-101(LC 9) Max Grav 2=1802(LC 35), 13=1777(LC 36)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-2629/123, 3-5=-2186/151, 5-6=-842/54, 6-7=-770/60, 7-8=-835/57, 8-10=-2215/142, 10-11=-3095/161, 11-12=-1941/79, 12-13=-2591/74

**BOT CHORD** 2-21=-135/2266, 20-21=-135/2266, 17-20=0/1858, 16-17=-21/2533, 15-16=-133/3771,

13-15=-12/2047

3-20=-498/192, 20-22=0/694, 17-23=0/858, 11-15=-2272/152, 12-15=0/1357,

10-17=-1070/208, 10-16=0/727, 11-16=-1308/118, 5-22=-1201/173, 22-24=-1201/173,

23-24=-1159/168, 8-23=-1159/168, 7-24=-71/341, 6-24=-60/450

## NOTES-

**WEBS** 

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope); Lumber DOL=1.60 plate grip DOL=1.60
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 86 lb uplift at joint 2 and 101 lb uplift at ioint 13.
- 7) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- 8) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 66 lb down and 36 lb up at 34-5-0 on top chord, and 10 lb down at 34-5-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 9) Warning: Additional permanent and stability bracing for truss system (not part of this component design) is always required.
- 10) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

## LOAD CASE(S) Standard

## WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REPERENCE PAGE MILITATORY. INCLUDED MITEKER PAGE M building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TP11 Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacomponents.com)



September 26,2025



Job	Truss	Truss Type	Qty	Ply	Lot 65 Magnolia Hills
					176645098
251447-A	A8	ROOF SPECIAL GIRDER	1	1	
					Job Reference (optional)

Comtech, Inc, Fayetteville, NC - 28314,

25.3.0 s Sep 17 2025 MiTek Industries, Inc. Thu Sep 25 23:33:15 2025 Page 2 ID:3YJEg\_u8zX16RsP?VvW\_V6zd0wB-Hjz\_ITAVkWk9ugs63hlKyuHipFhlT0oG18V48myZxNo

## LOAD CASE(S) Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15 Uniform Loads (plf)


Vert: 1-6=-60, 6-7=-60, 7-11=-60, 11-12=-60, 12-14=-60, 2-13=-20



818 Soundside Road Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Lot 65 Magnolia Hills	
						176645099
251447-A	B1	HIP GIRDER	1	2		
					Job Reference (optiona	al)
Comtech, Inc, Fayette	/ille, NC - 28314,		25	.3.0 s Sep	17 2025 MiTek Industrie	es, Inc. Thu Sep 25 23:33:15 2025 Page 1
		ID:3Y	/JEg_u8zX16F	RsP?VvW_	V6zd0wB-Hjz_ITAVkWk	49ugs63hlKyuHk0Fn_T8wG18V48myZxNo
<sub>L</sub> -1-2-8 <sub>L</sub>	5-10-0	14-3-12		22-9-	8	28-7-8
1-2-8	5-10-0	8-5-12		8-5-1	2	5-10-0

Scale = 1:50.8



1	5-10-0	İ	14-3-12	1	i	22-9	9-8		28-7-8	1
	5-10-0		8-5-12			8-5-	-12		5-10-0	<u> </u>
Plate Offsets (X,Y)	[3:0-5-4,0-2-12], [6:0-5-4,	,0-2-12]								
	•	-								
LOADING (psf)	SPACING-	2-0-0	CSI.	D	EFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.15	TC 0.32	V	ert(LL)	-0.07 10	>999	360	MT20	244/190
TCDL 10.0	Lumber DOL	1.15	BC 0.28	V	ert(CT)	-0.13 10-11	>999	240		
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.21	н	lorz(CT)	0.04 7	n/a	n/a		
BCDL 10.0	Code IRC2021/TF	PI2014	Matrix-S	l w	/ind(LL)	0.07 10	>999	240	Weight: 372 lb	FT = 20%
									=	

**BRACING-**

TOP CHORD

BOT CHORD

LUMBER-

TOP CHORD 2x6 SP No 1 BOT CHORD 2x6 SP No.1

**WEBS** 2x4 SP No.2

REACTIONS. (size) 7=0-3-8, 2=0-3-8

Max Horz 2=106(LC 28) Max Uplift 7=-483(LC 9), 2=-501(LC 8)

Max Grav 7=2100(LC 1), 2=2177(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-3447/843, 3-4=-4284/1127, 4-6=-4285/1127, 6-7=-3431/844 **BOT CHORD** 2-11=-732/2755, 10-11=-731/2776, 8-10=-646/2782, 7-8=-647/2761

WFBS 3-11=0/714, 3-10=-536/1723, 4-10=-1085/640, 6-10=-536/1720, 6-8=0/716

## NOTES-

- 1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows: Top chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc. Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc. Webs connected as follows: 2x4 - 1 row at 0-9-0 oc.
- 2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- 3) Unbalanced roof live loads have been considered for this design.
- 4) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope); Lumber DOL=1.60 plate grip DOL=1.60
- 5) Provide adequate drainage to prevent water ponding.
- 6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 7) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 483 lb uplift at joint 7 and 501 lb uplift at
- 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord
- 10) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 134 lb down and 118 lb up at 5-10-0, 139 lb down and 115 lb up at 7-10-12, 139 lb down and 115 lb up at 9-10-12, 139 lb down and 115 lb up at 11-10-12, 139 lb down and 115 lb up at 13-10-12, 139 lb down and 115 lb up at 14-8-12, 139 lb down and 115 lb up at 16-8-12, 139 lb down and 115 lb up at 18-8-12, and 139 lb down and 115 lb up at 20-8-12, and 134 lb down and 118 lb up at 22-9-8 on top chord, and 336 lb down and 119 lb up at 5-10-0, 73 lb down at 7-10-12, 73 lb down at 9-10-12, 73 lb down at 11-10-12, 73 lb down at 13-10-12, 73 lb down at 14-8-12, 73 lb down at 16-8-12, 73 lb down at 18-8-12, and 73 lb down at 20-8-12, and 336 lb down and 119 lb up at 22-8-12 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.



Structural wood sheathing directly applied or 6-0-0 oc purlins, except

2-0-0 oc purlins (6-0-0 max.): 3-6.

Rigid ceiling directly applied or 10-0-0 oc bracing.

September 26,2025

# LOAD CASE(S) Standard

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TP11 Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacomponents.com)



Job	Truss	Truss Type	Qty	Ply	Lot 65 Magnolia Hills
					176645099
251447-A	B1	HIP GIRDER	1	2	
					Job Reference (optional)

Comtech, Inc, Fayetteville, NC - 28314,

25.3.0 s Sep 17 2025 MiTek Industries, Inc. Thu Sep 25 23:33:15 2025 Page 2 ID:3YJEg\_u8zX16RsP?VvW\_V6zd0wB-Hjz\_ITAVkWk9ugs63hlKyuHk0Fn\_T8wG18V48myZxNo

## LOAD CASE(S) Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (plf)

Vert: 1-3=-60, 3-6=-60, 6-7=-60, 2-7=-20

Concentrated Loads (lb)

233-36(F) 24=-36(F) 25=-36(F) 25=-36(F) 26=-36(F) 27=-36(F) 27=-36(F) 27=-36(F) 26=-36(F) 26=-36



818 Soundside Road Edenton, NC 27932

Job Truss Truss Type Qty Ply Lot 65 Magnolia Hills 176645100 B2 ROOF SPECIAL GIRDER 251447-A Job Reference (optional) Fayetteville, NC - 28314, 25.3.0 s Sep 17 2025 MiTek Industries, Inc. Thu Sep 25 23:33:16 2025 Page 1 Comtech, Inc. ID:3YJEg\_u8zX16RsP?VvW\_V6zd0wB-lwXMypB8Vps0VqQldOGZU5psje3gCRSQGoEegCyZxNn

6-5-12


14-3-12

6-5-12

Scale: 3/16"=1"

34-7-0 35-9-8 2-0-8 1-2-8

32-6-8



	7-10-0	14-3-12 <sub>1</sub>	20-9-8	26-7-0	32-6-8   34-7-0
	7-10-0	6-5-12	6-5-12	5-9-8	5-11-8 2-0-8
Plate Offsets (X,Y)	- [6:0-5-4,0-2-12], [7:0-3-4,0-2-	12]			
LOADING (psf)	SPACING- 2-	)-0 <b>CSI.</b>	DEFL. i	n (loc) l/defl L/d	PLATES GRIP
TCLL 20.0		15 TC 0.51		6 11-12 >999 360	MT20 244/190
TCDL 10.0	·	15 BC 0.57	- ', '	3 11-12 >776 240	W1120 244/100
BCLL 0.0 *	Rep Stress Incr	NO WB 0.83	Horz(CT) 0.0	7 8 n/a n/a	
BCDL 10.0	Code IRC2021/TPI201	4 Matrix-S	Wind(LL) 0.18	8 11-12 >999 240	Weight: 242 lb FT = 20%

LUMBER-

TOP CHORD 2x6 SP No 1

2x6 SP No.1 \*Except\* **BOT CHORD** 

8-13: 2x6 SP 2400F 2.0E

**WEBS** 2x4 SP No.2

BRACING-TOP CHORD

Structural wood sheathing directly applied or 4-5-1 oc purlins, except

2-0-0 oc purlins (3-1-1 max.): 3-5, 6-7.

BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing. WEBS T-Brace: 2x4 SPF No.2 - 5-15, 6-12

Fasten (2X) T and I braces to narrow edge of web with 10d

(0.131"x3") nails, 6in o.c., with 3in minimum end distance.

Brace must cover 90% of web length.

REACTIONS. (size) 2=0-3-8, 8=0-3-8

Max Horz 2=142(LC 28)

Max Uplift 2=-39(LC 8), 8=-93(LC 9) Max Grav 2=1445(LC 1), 8=1445(LC 1)

7-10-0

7-10-0

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-2078/53, 3-4=-2225/85, 4-5=-2225/85, 5-6=-2717/82, 6-7=-5290/211,

7-8=-2543/104

**BOT CHORD** 2-16=-78/1610, 15-16=-80/1605, 12-15=0/2203, 11-12=-136/5193, 10-11=-48/1988, 8-10=-42/2029

> 3-16=0/325, 3-15=-138/880, 4-15=-451/161, 5-12=0/1051, 6-12=-3058/216, 6-11=-971/107, 7-11=-102/3398, 7-10=0/463

## NOTES-

**WEBS** 

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope); Lumber DOL=1.60 plate grip DOL=1.60
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 39 lb uplift at joint 2 and 93 lb uplift at
- 7) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- 8) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 64 lb down and 27 lb up at 30-5-12, and 132 lb down and 62 lb up at 32-6-8 on top chord, and 6 lb down at 30-5-12, and 15 lb down at 32-5-12 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 9) Warning: Additional permanent and stability bracing for truss system (not part of this component design) is always required.

10) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard



September 26,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TP11 Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacomponents.com)



Job	Truss	Truss Type	Qty	Ply	Lot 65 Magnolia Hills
					I76645100
251447-A	B2	ROOF SPECIAL GIRDER	1	1	
					Job Reference (optional)

Fayetteville, NC - 28314, Comtech, Inc,

25.3.0 s Sep 17 2025 MiTek Industries, Inc. Thu Sep 25 23:33:16 2025 Page 2 ID:3YJEg\_u8zX16RsP?VvW\_V6zd0wB-lwXMypB8Vps0VqQldOGZU5psje3gCRSQGoEegCyZxNn

## LOAD CASE(S) Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15 Uniform Loads (plf)

Vert: 1-3=-60, 3-5=-60, 5-6=-60, 6-7=-60, 7-9=-60, 2-8=-20




818 Soundside Road Edenton, NC 27932

Job Truss Truss Type Qty Ply Lot 65 Magnolia Hills 176645101 ВЗ **ROOF SPECIAL** 251447-A Job Reference (optional) 25.3.0 s Sep 17 2025 MiTek Industries, Inc. Thu Sep 25 23:33:17 2025 Page 1 Comtech, Inc.

Fayetteville, NC - 28314, ID:3YJEg\_u8zX16RsP?VvW\_V6zd0wB-D65kA9BmG7\_s7z?UA6oo1JM0k2MdxzDZVS\_BCfyZxNm 9-10-0 18-9-8 24-7-0 30-6-8 34-7-0 9-10-0 8-11-8 5-9-8 5-11-8 4-0-8

Scale: 3/16"=1"



<b>⊢</b>	9-10-0	18-9-8	30-6-8	34-7-0
<u> </u>	9-10-0	8-11-8	11-9-0	4-0-8
Plate Offsets (X,Y)	[2:0-6-12,0-0-13], [5:0-3-0,0-3-8]			
LOADING (psf) TCLL 20.0 TCDL 10.0 BCLL 0.0 * BCDL 10.0	SPACING- 2-0-0 Plate Grip DOL 1.15 Lumber DOL 1.15 Rep Stress Incr YES Code IRC2021/TPI2014	CSI.         DEFL.           TC 0.56         Vert(LL)           BC 0.71         Vert(CT)           WB 0.54         Horz(CT)           Matrix-S         Wind(LL	) 0.08 7 n/a n/a	<b>PLATES GRIP</b> MT20 244/190  Weight: 235 lb FT = 20%

LUMBER-TOP CHORD 2x6 SP No 1

BOT CHORD 2x6 SP No.1

2x4 SP No 2 WFBS

**BRACING-**TOP CHORD

Structural wood sheathing directly applied or 4-0-15 oc purlins,

except

2-0-0 oc purlins (4-10-14 max.): 3-4, 5-6.

**BOT CHORD** Rigid ceiling directly applied or 9-7-10 oc bracing. WEBS 2x4 SPF No.2 - 5-11, 5-9

Fasten (2X) T and I braces to narrow edge of web with 10d

(0.131"x3") nails, 6in o.c., with 3in minimum end distance.

Brace must cover 90% of web length.

REACTIONS. (size) 2=0-3-8, 7=0-3-8

Max Horz 2=-173(LC 10)

Max Uplift 2=-51(LC 12), 7=-96(LC 13) Max Grav 2=1681(LC 2), 7=1581(LC 2)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-2364/403, 3-4=-2100/475, 4-5=-2598/500, 5-6=-2007/356, 6-7=-2575/388

**BOT CHORD**  $2-13=-163/1850,\ 11-13=-165/1837,\ 9-11=-655/3858,\ 7-9=-221/2070$ **WEBS** 3-13=0/672, 3-11=-100/504, 4-11=-64/1029, 5-11=-1927/512, 5-9=-2027/479,

6-9=-67/1175

## NOTES-

1) Unbalanced roof live loads have been considered for this design.

- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2E) -1-0-15 to 3-3-14, Interior(1) 3-3-14 to 9-10-0, Exterior(2R) 9-10-0 to 14-2-13, Interior(1) 14-2-13 to 18-9-8, Exterior(2R) 18-9-8 to 23-2-5, Interior(1) 23-2-5 to 30-6-8, Exterior(2R) 30-6-8 to 34-11-5, Interior(1) 34-11-5 to 35-7-15 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 51 lb uplift at joint 2 and 96 lb uplift at joint 7.
- 7) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- 8) Warning: Additional permanent and stability bracing for truss system (not part of this component design) is always required.



September 26,2025



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall

building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TP11 Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacomponents.com)



Job Truss Truss Type Qty Ply Lot 65 Magnolia Hills 176645102 251447-A ROOF SPECIAL **B4** Job Reference (optional) Fayetteville, NC - 28314, 25.3.0 s Sep 17 2025 MiTek Industries, Inc. Thu Sep 25 23:33:17 2025 Page 1 Comtech, Inc. ID:3YJEg\_u8zX16RsP?VvW\_V6zd0wB-D65kA9BmG7\_s7z?UA6oo1JM472MRx\_fZVS\_BCfyZxNm

22-7-0

5-9-8

16-9-8

4-11-8


11-10-0

5-7-3

Scale: 3/16"=1

34-7-0

6-0-8



LOADING (psf) SPACING-CSI. DEFL. in (loc) I/defl L/d **PLATES** GRIP **TCLL** 20.0 Plate Grip DOL 1.15 TC 0.28 Vert(LL) -0.25 11-13 >999 360 MT20 244/190 TCDL 10.0 Lumber DOL 1.15 BC 0.72 Vert(CT) -0.41 11-13 >998 240 WB **BCLL** 0.0 Rep Stress Incr YES 0.45 Horz(CT) 0.07 8 n/a n/a BCDL 10.0 Code IRC2021/TPI2014 Matrix-S Wind(LL) 0.17 11-13 >999 240 FT = 20% Weight: 244 lb

LUMBER-

Plate Offsets (X,Y)--

TOP CHORD 2x6 SP No 1 BOT CHORD 2x6 SP No.1

WFBS 2x4 SP No 2 **BRACING-**

TOP CHORD Structural wood sheathing directly applied or 4-11-11 oc purlins,

28-6-8

2-0-0 oc purlins (5-7-5 max.): 4-5, 6-7.

**BOT CHORD** Rigid ceiling directly applied or 10-0-0 oc bracing. WEBS 2x4 SPF No.2 - 6-13, 6-10

Fasten (2X) T and I braces to narrow edge of web with 10d (0.131"x3") nails, 6in o.c., with 3in minimum end distance.

Brace must cover 90% of web length.

REACTIONS. (size) 2=0-3-8, 8=0-3-8

Max Horz 2=205(LC 11)

6-2-14

6-2-14

Max Uplift 2=-64(LC 12), 8=-105(LC 13) Max Grav 2=1637(LC 19), 8=1584(LC 2)

[6:0-2-12,0-3-8], [14:0-4-0,Edge]

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-2288/485, 3-4=-2071/453, 4-5=-1663/441, 5-6=-2116/469, 6-7=-1861/413,

**BOT CHORD** 2-15=-289/1950, 13-15=-112/1682, 11-13=-426/3019, 10-11=-428/3009, 8-10=-225/1897

**WEBS** 3-15=-315/218, 4-15=-51/744, 5-13=-130/956, 6-13=-1648/411, 6-11=0/322,

6-10=-1378/251, 7-10=-68/993

## NOTES-

1) Unbalanced roof live loads have been considered for this design.

- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2E) -1-0-15 to 3-3-14, Interior(1) 3-3-14 to 11-10-0, Exterior(2R) 11-10-0 to 16-2-13, Interior(1) 16-2-13 to 16-9-8, Exterior(2R) 16-9-8 to 21-2-5, Interior(1) 21-2-5 to 28-6-8, Exterior(2R) 28-6-8 to 32-11-5, Interior(1) 32-11-5 to 35-7-15 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 64 lb uplift at joint 2 and 105 lb uplift at ioint 8.
- 7) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- 8) Warning: Additional permanent and stability bracing for truss system (not part of this component design) is always required.



September 26,2025



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall

building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacomponents.com)



Job Truss Truss Type Qty Ply Lot 65 Magnolia Hills 176645103 **ROOF SPECIAL** 251447-A B5 Job Reference (optional) Fayetteville, NC - 28314, 25.3.0 s Sep 17 2025 MiTek Industries, Inc. Thu Sep 25 23:33:18 2025 Page 1 Comtech, Inc. ID:3YJEg\_u8zX16RsP?VvW\_V6zd0wB-hlf6NVCO1R6jl7ahkpJ1aWvEGSlSgJXij6jkk5yZxNI

20-7-0

5-9-8

26-6-8

n/a

>999

0.09 12-14

n/a

240

2-0-0 oc purlins (4-11-1 max.): 5-6, 7-8.

Rigid ceiling directly applied or 10-0-0 oc bracing.

Structural wood sheathing directly applied or 4-0-10 oc purlins,

Scale = 1:68.4

34-7-0

8-0-8


Weight: 248 lb

FT = 20%



13-10-0

6-7-3



Wind(LL)

**BRACING-**

TOP CHORD

**BOT CHORD** 

LUMBER-

BCDL

TOP CHORD 2x6 SP No 1 2x6 SP No.1

BOT CHORD WFBS 2x4 SP No.2

10.0

REACTIONS. (size) 2=0-3-8, 9=0-3-8

Max Horz 2=237(LC 11)

Max Uplift 2=-75(LC 12), 9=-112(LC 13) Max Grav 2=1672(LC 19), 9=1602(LC 20)

7-2-14

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

Code IRC2021/TPI2014

TOP CHORD 2-3=-2302/427, 3-5=-2115/462, 5-6=-1760/464, 6-7=-3079/713, 7-8=-2469/505,

8-9=-2292/412

**BOT CHORD** 2-14=-232/1981, 12-14=-50/1474, 11-12=-179/1799, 9-11=-178/1806

**WEBS**  $3-14=-311/251,\ 6-14=-82/822,\ 6-12=-427/2031,\ 7-12=-1979/535,\ 8-12=-121/947,$ 

8-11=0/301

## NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2E) -1-0-15 to 3-3-14, Interior(1) 3-3-14 to 13-10-0, Exterior(2E) 13-10-0 to 14-9-8, Exterior(2R) 14-9-8 to 19-2-5, Interior(1) 19-2-5 to 26-6-8, Exterior(2R) 26-6-8 to 30-11-5, Interior(1) 30-11-5 to 35-7-15 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60

Matrix-S

- 3) Provide adequate drainage to prevent water ponding.
- 4) All plates are MT20 plates unless otherwise indicated.
- 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 6) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 75 lb uplift at joint 2 and 112 lb uplift at joint 9.
- 8) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord



September 26,2025



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall

building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TP11 Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacomponents.com)




Job Truss Truss Type Qty Ply Lot 65 Magnolia Hills 176645104 **ROOF SPECIAL** 251447-A В6 Job Reference (optional) Fayetteville, NC - 28314, 25.3.0 s Sep 17 2025 MiTek Industries, Inc. Thu Sep 25 23:33:18 2025 Page 1 Comtech, Inc. ID:3YJEg\_u8zX16RsP?VvW\_V6zd0wB-hlf6NVCO1R6jl7ahkpJ1aWvAhSlAgPcij6jkk5yZxNl <u>24-6-8</u>

18-7-0

14-3-12

6-10-1

Scale = 1:74.4



	9-1-11	18-7-0	24-6-8	34-7-0
	9-1-11	9-5-5	5-11-8	10-0-8
DI-1- O#1- (V/ V/	[0.0.0.0.0.0] [0.0.0.0.0]			

	, . ,	[			
LOADIN	G (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) I/defl L/d	PLATES GRIP
TCLL	20.0	Plate Grip DOL 1.15	TC 0.61	Vert(LL) -0.19 12-14 >999 360	MT20 244/190
TCDL	10.0	Lumber DOL 1.15	BC 0.56	Vert(CT) -0.29 12-14 >999 240	
BCLL	0.0 *	Rep Stress Incr YES	WB 0.60	Horz(CT) 0.06 8 n/a n/a	
BCDL	10.0	Code IRC2021/TPI2014	Matrix-S	Wind(LL) 0.06 8-10 >999 240	Weight: 253 lb FT = 20%

LUMBER-TOP CHORD 2x6 SP No 1

BOT CHORD 2x6 SP No.1

WFBS 2x4 SP No 2 **BRACING-**TOP CHORD

Structural wood sheathing directly applied or 3-10-7 oc purlins,

34-7-0

10-0-8

except

2-0-0 oc purlins (5-2-9 max.): 6-7.

**BOT CHORD** Rigid ceiling directly applied or 10-0-0 oc bracing. WEBS 2x4 SPF No.2 - 6-12

Fasten (2X) T and I braces to narrow edge of web with 10d

(0.131"x3") nails, 6in o.c., with 3in minimum end distance. Brace must cover 90% of web length.

REACTIONS. (size) 2=0-3-8, 8=0-3-8

Max Horz 2=246(LC 11)

Max Uplift 2=-78(LC 12), 8=-113(LC 13) Max Grav 2=1734(LC 19), 8=1752(LC 20)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-2492/411, 3-5=-2392/532, 5-6=-2609/610, 6-7=-2185/458, 7-8=-2418/397 **BOT CHORD** 2-14=-217/2134, 12-14=-37/1543, 10-12=-138/1902, 8-10=-136/1913

**WEBS** 3-14=-408/289, 5-14=-181/966, 5-12=-322/1766, 6-12=-1616/433, 7-12=-56/502,

7-10=0/581

## NOTES-

1) Unbalanced roof live loads have been considered for this design.

- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2E) -1-0-15 to 3-3-14, Interior(1) 3-3-14 to 14-3-12, Exterior(2E) 14-3-12 to 18-7-0, Interior(1) 18-7-0 to 24-6-8, Exterior(2R) 24-6-8 to 28-11-5, Interior(1) 28-11-5 to 35-7-15 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 78 lb uplift at joint 2 and 113 lb uplift at joint 8.
- 7) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- 8) Warning: Additional permanent and stability bracing for truss system (not part of this component design) is always required.



September 26,2025



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall

building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TP11 Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacomponents.com)



Job Truss Truss Type Qty Ply Lot 65 Magnolia Hills 176645105 В7 **ROOF SPECIAL** 251447-A Job Reference (optional)


4x6 =

Fayetteville, NC - 28314, Comtech, Inc.

1-2-8

25.3.0 s Sep 17 2025 MiTek Industries, Inc. Thu Sep 25 23:33:19 2025 Page 1 ID:3YJEg\_u8zX16RsP?VvW\_V6zd0wB-AVDVarD0okEaMH9tlWqG6kRJys1mPvNsymTlHXyZxNk

Scale = 1:77.2



1	6-7-12	13-3-8	16-7-0	21-3-8 21 <sub>T</sub> 7-0	34-7-0	1
ı	6-7-12	6-7-12	3-3-8	4-8-8 0-3 <sup>1</sup> -8	13-0-0	

Plate Offsets (X,	[7:0-3-0,Edge], [16:0-2-4,0-2-0	[7:0-3-0,Edge], [16:0-2-4,0-2-0], [19:0-1-8,0-3-0]					
LOADING (psf)	SPACING- 2-0	·0 CSI.	<b>DEFL.</b> in (loc)	I/defl L/d	PLATES GRIP		
TCLL 20.0	Plate Grip DOL 1.	5 TC 0.77	Vert(LL) -0.30 15-16	>999 360	MT20 244/190		
TCDL 10.0	Lumber DOL 1.	5 BC 0.80	Vert(CT) -0.43 15-16	>965 240			
BCLL 0.0	Rep Stress Incr YE	S WB 0.44	Horz(CT) 0.07 13	n/a n/a			
BCDL 10.0	Code IRC2021/TPI201	Matrix-S	Wind(LL) 0.14 15-16	>999 240	Weight: 283 lb FT = 20%		

LUMBER-TOP CHORD

2x6 SP No 1 2x6 SP No.1

BOT CHORD WFBS 2x4 SP No.2 **BRACING-**TOP CHORD

BOT CHORD

Structural wood sheathing directly applied or 3-9-3 oc purlins, except

2-0-0 oc purlins (5-1-3 max.): 5-10. Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 2=0-3-8, 13=0-3-8

Max Horz 2=-246(LC 10)

Max Uplift 2=-78(LC 12), 13=-113(LC 13) Max Grav 2=1742(LC 19), 13=1743(LC 20)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-2484/394, 3-5=-2097/422, 5-6=-1723/418, 6-8=-1723/418, 8-9=-1809/430,

9-10=-1813/433, 10-12=-2615/579, 12-13=-2614/404

 $2 - 20 = -207/2109, \ 19 - 20 = -207/2109, \ 16 - 19 = -101/1873, \ 15 - 16 = -84/1766, \ 13 - 15 = -212/2070$ BOT CHORD **WEBS** 

6-19=0/592, 9-16=-313/274, 3-19=-414/186, 12-15=-301/267, 10-15=-249/774,

10-16=-235/738

## NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2E) -1-0-15 to 3-3-14, Interior(1) 3-3-14 to 14-3-12, Exterior(2E) 14-3-12 to 16-7-0, Interior(1) 16-7-0 to 22-6-8, Exterior(2R) 22-6-8 to 26-11-5, Interior(1) 26-11-5 to 35-7-15 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 78 lb uplift at joint 2 and 113 lb uplift at
- 7) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



September 26,2025




WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall

building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacomponents.com)





Tidle Offices (A, I)	[10.0 2 0,0 2 4], [14.0 2 0,0 2 0], [10.0 2 0,0	1 0]

LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) I/defl	L/d	PLATES GRIP
TCLL 20.0	Plate Grip DOL 1.15	TC 0.23	Vert(LL) -0.21 16-17 >999	360	MT20 244/190
TCDL 10.0	Lumber DOL 1.15	BC 0.62	Vert(CT) -0.26 16-17 >999	240	
BCLL 0.0 *	Rep Stress Incr YES	WB 0.73	Horz(CT) 0.06 11 n/a	n/a	
BCDL 10.0	Code IRC2021/TPI2014	Matrix-S	Wind(LL) 0.12 12-13 >999	240	Weight: 284 lb FT = 20%

LUMBER-

TOP CHORD 2x6 SP No 1 BOT CHORD 2x6 SP No.1

**WEBS** 2x4 SP No.2 \*Except\*

5-8: 2x6 SP No.1

TOP CHORD

BOT CHORD

BRACING-

2-0-0 oc purlins (6-0-0 max.): 6-7. Rigid ceiling directly applied or 10-0-0 oc bracing.

Structural wood sheathing directly applied or 4-7-8 oc purlins, except

JOINTS 1 Brace at Jt(s): 20, 21

REACTIONS. (size) 2=0-3-8, 11=0-3-8

Max Horz 2=234(LC 9)

Max Uplift 2=-78(LC 12), 11=-59(LC 13) Max Grav 2=1807(LC 19), 11=1665(LC 20)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-2691/410, 3-5=-2106/429, 5-6=-1271/263, 6-7=-1033/242, 7-8=-1332/267,

8-10=-2084/432. 10-11=-2512/411

**BOT CHORD** 2-17=-261/2293, 16-17=-261/2293, 13-16=-118/1717, 12-13=-245/1992, 11-12=-245/1992

**WEBS** 3-17=0/381, 16-18=-9/814, 13-19=-15/696, 3-16=-702/190, 10-12=0/261,

 $10 - 13 = -547/195, \ 5 - 18 = -653/217, \ 18 - 20 = -653/217, \ 20 - 21 = -690/218, \ 19 - 21 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \ 10 - 13 = -642/219, \$ 

8-19=-642/219, 6-20=-14/493, 7-21=-17/560

## NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2E) -1-0-15 to 3-3-14, Interior(1) 3-3-14 to 14-3-12, Exterior(2R) 14-3-12 to 18-8-9, Interior(1) 18-8-9 to 20-6-8, Exterior(2R) 20-6-8 to 24-11-5, Interior(1) 24-11-5 to 34-5-4 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 78 lb uplift at joint 2 and 59 lb uplift at
- 7) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



September 26,2025



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall

building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TP11 Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacomponents.com)



Job	Truss	Truss Type	Qty	Ply	Lot 65 Magnolia Hills	
						176645107
251447-A	C1SG	GABLE	1	1		
					Job Reference (optional)	
Comtech, Inc, Fay	etteville, NC - 28314,		2	5.3.0 s Sep	17 2025 MiTek Industries, Inc. Thu Sep 25 23:33:2	20 2025 Page 1
-			ID:3YJEg_u8zX16	RsP?VvW_	_V6zd0wB-ehntoBEeZ2MR_Rk3sELVfx_cAGUG8Rl	?BQCrpzyZxNj
-1-2-8		7-6-0	1		15-0-0	16-2-8
1-2-8		7-6-0			7-6-0	1-2-8

Scale = 1:27.9




Plate Offsets (X,Y) [2	7-6-0 2:0-2-4,0-1-1], [8:0-2-4,0-1-1]		'	7-6-0		'
LOADING (psf) TCLL 20.0 TCDL 10.0 BCLL 0.0 * BCDL 10.0	SPACING-         2-0-0           Plate Grip DOL         1.15           Lumber DOL         1.15           Rep Stress Incr         YES           Code IRC2021/TPI2014	CSI. TC 0.22 BC 0.33 WB 0.11 Matrix-S	DEFL. in (I Vert(LL) -0.05 Vert(CT) -0.09 13 Horz(CT) 0.01 Wind(LL) 0.08 13	8 n/a n/a	PLATES MT20 Weight: 74 lb	<b>GRIP</b> 244/190 FT = 20%

**BRACING-**

TOP CHORD

**BOT CHORD** 

LUMBER-

TOP CHORD 2x4 SP No 1 BOT CHORD 2x6 SP No.1

2x4 SP No.2 WFBS **OTHERS** 2x4 SP No.2

REACTIONS. (size) 2=0-3-0, 8=0-3-0

Max Horz 2=59(LC 16)

Max Uplift 2=-371(LC 8), 8=-371(LC 9) Max Grav 2=670(LC 1), 8=670(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-1063/1063, 3-4=-1016/1107, 4-5=-1007/1149, 5-6=-1007/1149, 6-7=-1016/1107,

7-6-0

7-8=-1063/1063

**BOT CHORD** 2-14=-907/951, 13-14=-907/951, 12-13=-907/951, 11-12=-907/951, 10-11=-907/951,

8-10=-907/951

**WEBS** 5-12=-523/448

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; Gable Roof; Common Truss; MWFRS (envelope) gable end zone and C-C Corner(3E) -1-2-8 to 3-2-5, Exterior(2N) 3-2-5 to 7-6-0, Corner(3R) 7-6-0 to 11-10-13, Exterior(2N) 11-10-13 to 16-2-8 zone; porch left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60  $\,$
- 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 4) All plates are 2x4 MT20 unless otherwise indicated.
- 5) Gable studs spaced at 2-0-0 oc.
- 6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 7) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 371 lb uplift at joint 2 and 371 lb uplift at joint 8.



15-0-0

Structural wood sheathing directly applied or 5-11-0 oc purlins.

Rigid ceiling directly applied or 7-8-15 oc bracing.

September 26,2025



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.


Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall

building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacomponents.com)



Job	Truss	Truss Type	Qty	Ply	Lot 65 Magnolia Hills	
						I76645108
251447-A	C2	COMMON	4	1		
					Job Reference (optional)	
Comtech, Inc, F	ayetteville, NC - 28314,		25	.3.0 s Sep	17 2025 MiTek Industries, Inc. Thu Sep 25 23:3	33:20 2025 Page 1
			ID:3YJEg_u8zX16I	RsP?VvW_	V6zd0wB-ehntoBEeZ2MR_Rk3sELVfx_Y0GV6	8R9?BQCrpzyZxNj
-1-2-8		7-6-0	1		15-0-0	16-2-8
1-2-8		7-6-0			7-6-0	1-2-8

Scale = 1:27.9



7-6-0 7-6-0			15-0-0 7-6-0				<del></del>
LOADING (psf) TCLL 20.0 TCDL 10.0 BCLL 0.0 * BCDL 10.0	SPACING- 2-0-0 Plate Grip DOL 1.15 Lumber DOL 1.15 Rep Stress Incr YES Code IRC2021/TPI2014	TC 0.49 BC 0.28	DEFL.         in           Vert(LL)         0.06           Vert(CT)         -0.07           Horz(CT)         0.01	(loc) I/defl 4-6 >999 2-6 >999 4 n/a	L/d 240 240 n/a	PLATES MT20 Weight: 66 lb	<b>GRIP</b> 244/190 FT = 20%

**BRACING-**

TOP CHORD

**BOT CHORD** 

LUMBER-

TOP CHORD 2x4 SP No.1 2x6 SP No.1 BOT CHORD 2x4 SP No.2 **WEBS** 

REACTIONS. (size) 2=0-3-0, 4=0-3-0

Max Horz 2=35(LC 12)

Max Uplift 2=-261(LC 8), 4=-261(LC 9) Max Grav 2=670(LC 1), 4=670(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

2-3=-1068/858, 3-4=-1068/855 TOP CHORD 2-6=-698/932, 4-6=-698/932 BOT CHORD

**WEBS** 3-6=-233/372

## NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2E) -1-2-8 to 3-2-5, Interior(1) 3-2-5 to 7-6-0, Exterior(2R) 7-6-0 to 11-10-13, Interior(1) 11-10-13 to 16-2-8 zone; porch left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 261 lb uplift at joint 2 and 261 lb uplift at joint 4.




Structural wood sheathing directly applied or 5-1-12 oc purlins.

Rigid ceiling directly applied or 8-10-14 oc bracing.

September 26,2025







LOADING	(psf)	SPACING- 2-0-0	CSI.	<b>DEFL.</b> in	(loc)	l/defl	L/d	PLATES GRIP
TCLL	20.0	Plate Grip DOL 1.15	TC 0.68	Vert(LL) -0.02	2-4	>999	360	MT20 244/190
TCDL	10.0	Lumber DOL 1.15	BC 0.16	Vert(CT) -0.04	2-4	>999	240	
BCLL	0.0 *	Rep Stress Incr NO	WB 0.00	Horz(CT) 0.00		n/a	n/a	
BCDL	10.0	Code IRC2021/TPI2014	Matrix-P	Wind(LL) 0.02	2-4	>999	240	Weight: 32 lb FT = 20%

**BRACING-**

TOP CHORD

**BOT CHORD** 

LUMBER-

REACTIONS.

TOP CHORD 2x4 SP No.1 BOT CHORD 2x6 SP No.1

WEBS 2x6 SP No.1

Max Horz 2=85(LC 8) Max Uplift 4=-294(LC 8), 2=-134(LC 8) Max Grav 4=734(LC 1), 2=331(LC 1)

(size) 4=0-3-8, 2=0-3-0

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 3-4=-173/274

## NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2E) -1-2-8 to 3-2-5, Interior(1) 3-2-5 to 6-2-4 zone; porch left exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 294 lb uplift at joint 4 and 134 lb uplift at joint 2.
- 6) Load case(s) 18, 23, 24 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.
- 7) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 500 lb down and 1091 lb up at 6-2-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 8) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

## LOAD CASE(S) Standard


 Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15 Uniform Loads (plf)

Vert: 1-3=-60, 2-4=-20 Concentrated Loads (lb) Vert: 4=-500(F)

18) Dead: Lumber Increase=0.90, Plate Increase=0.90 Plt. metal=0.90

Uniform Loads (plf) Vert: 1-3=-20, 2-4=-20

Concentrated Loads (lb) Vert: 4=-250(F)



Structural wood sheathing directly applied or 6-0-0 oc purlins,

except end verticals.

September 26,2025

## Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall

a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacomponents.com)



Job	Truss	Truss Type	Qty	Ply	Lot 65 Magnolia Hills
					I76645109
251447-A	P1	ROOF SPECIAL	7	1	
					Job Reference (optional)

Comtech, Inc, Fayetteville, NC - 28314,

25.3.0 s Sep 17 2025 MiTek Industries, Inc. Thu Sep 25 23:33:21 2025 Page 2 ID:F7e3nXrh6oAXz?Vjil5mfhz3PFB-6tLF?XEGKMUlcbJGPxskB9XgrfsCtvi9P4yPLQyZxNi

## LOAD CASE(S) Standard

23) Dead + 0.6 C-C Wind Min. Down: Lumber Increase=1.60, Plate Increase=1.60

Uniform Loads (plf) Vert: 1-2=4, 2-3=-28, 2-4=4 Horz: 1-2=-16, 2-3=16


Concentrated Loads (lb)

Vert: 4=-150(F) 24) Dead + 0.6 C-C Wind Min. Upward: Lumber Increase=1.60, Plate Increase=1.60

Uniform Loads (plf)

Vert: 1-3=4, 2-4=4 Horz: 1-3=-16 Concentrated Loads (lb) Vert: 4=-150(F)





LUMBER-

TOP CHORD 2x4 SP No.1 BOT CHORD 2x4 SP No.1 2x6 SP No.1 **WEBS** 

BRACING-

TOP CHORD Structural wood sheathing directly applied or 4-5-0 oc purlins,

except end verticals.

**BOT CHORD** Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 2=0-3-0, 4=0-1-8

Max Horz 2=62(LC 8)

Max Uplift 2=-63(LC 8), 4=-25(LC 12) Max Grav 2=256(LC 1), 4=149(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

## NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2E) -1-2-8 to 3-2-5, Interior(1) 3-2-5 to 4-2-4 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Bearing at joint(s) 4 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 6) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 4.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 63 lb uplift at joint 2 and 25 lb uplift at joint 4.



September 26,2025






WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacomponents.com)





TOP CHORD

**BOT CHORD** 

LUMBER-

REACTIONS.

TOP CHORD 2x4 SP No.1 BOT CHORD 2x6 SP No.1

2x6 SP No.1 **WEBS** 

> (size) 4=0-3-8, 2=0-3-0 Max Horz 2=78(LC 8)

Max Uplift 4=-90(LC 8), 2=-127(LC 8) Max Grav 4=208(LC 1), 2=307(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

## NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2E) -1-2-8 to 3-2-5, Interior(1) 3-2-5 to 5-6-12 zone; porch left exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 90 lb uplift at joint 4 and 127 lb uplift at ioint 2.



Structural wood sheathing directly applied or 5-9-8 oc purlins,

Rigid ceiling directly applied or 10-0-0 oc bracing.

except end verticals.

September 26,2025



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall

building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacomponents.com)



Job Truss Truss Type Qty Ply Lot 65 Magnolia Hills 176645112 JACK-OPEN 14 251447-A XA1 Job Reference (optional) Fayetteville, NC - 28314, 25.3.0 s Sep 17 2025 MiTek Industries, Inc. Thu Sep 25 23:33:22 2025 Page 1 Comtech, Inc. ID:3YJEg\_u8zX16RsP?VvW\_V6zd0wB-a4udDtFu5fc9EluSzfNzkM3ul3CtcMylekhytsyZxNh Scale = 1:26.1 8.00 12

> 6-0-0 6-0-0

LOADING	G (psf)	SPACING- 2-0-0	CSI.	DEFL.	in (loc)	I/defI	L/d	PLATES	GRIP
TCLL	20.0	Plate Grip DOL 1.15	TC 0.50	Vert(LL)	-0.02 2-4	>999	360	MT20	244/190
TCDL	10.0	Lumber DOL 1.15	BC 0.13	Vert(CT)	-0.03 2-4	>999	240		
BCLL	0.0 *	Rep Stress Incr YES	WB 0.00	Horz(CT)	-0.00 3	n/a	n/a		
BCDL	10.0	Code IRC2021/TPI2014	Matrix-P	Wind(LL)	0.00 2	****	240	Weight: 27 lb	FT = 20%

LUMBER-

2x4 SP No.1 TOP CHORD BOT CHORD 2x6 SP No.1 **BRACING-**

TOP CHORD **BOT CHORD**  Structural wood sheathing directly applied or 6-0-0 oc purlins. Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 3=Mechanical, 2=0-3-8, 4=Mechanical

0-2-0

Max Horz 2=151(LC 12) Max Uplift 3=-105(LC 12)

Max Grav 3=184(LC 19), 2=322(LC 1), 4=116(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2E) -1-2-8 to 3-2-5, Interior(1) 3-2-5 to 5-11-4 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60

3x4 =

- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 105 lb uplift at joint 3.



September 26,2025






Job Truss Truss Type Qty Ply Lot 65 Magnolia Hills 176645113 XB1 JACK-OPEN 10 251447-A Job Reference (optional)

Fayetteville, NC - 28314, Comtech, Inc.

25.3.0 s Sep 17 2025 MiTek Industries, Inc. Thu Sep 25 23:33:22 2025 Page 1 ID:3YJEg\_u8zX16RsP?VvW\_V6zd0wB-a4udDtFu5fc9EluSzfNzkM3uo3D0cMylekhytsyZxNh

5-10-0 5-10-0

Scale = 1:25.5



5-10-0

LOADIN	G (psf)	SPACING- 2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	20.0	Plate Grip DOL 1.15	TC 0.47	Vert(LL)	-0.01	2-4	>999	360	MT20	244/190
TCDL	10.0	Lumber DOL 1.15	BC 0.12	Vert(CT)	-0.03	2-4	>999	240		
BCLL	0.0 *	Rep Stress Incr YES	WB 0.00	Horz(CT)	-0.00	3	n/a	n/a		
BCDL	10.0	Code IRC2021/TPI2014	Matrix-P	Wind(LL)	0.00	2	****	240	Weight: 27 lb	FT = 20%

LUMBER-

2x4 SP No.1 TOP CHORD BOT CHORD 2x6 SP No.1 **BRACING-**

TOP CHORD **BOT CHORD**  Structural wood sheathing directly applied or 5-10-0 oc purlins.

Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 3=Mechanical, 2=0-3-8, 4=Mechanical

Max Horz 2=147(LC 12) Max Uplift 3=-102(LC 12)

Max Grav 3=178(LC 19), 2=316(LC 1), 4=113(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- $1) \ Wind: ASCE\ 7-16; \ Vult=130 mph\ (3-second\ gust)\ Vasd=103 mph; \ TCDL=6.0 psf; \ BCDL=6.0 psf; \ h=15 ft; \ Cat.\ II; \ Exp\ C; \ Enclosed; \ ASCE\ True for the property of the pro$ MWFRS (envelope) and C-C Exterior(2E) -1-2-8 to 3-2-5, Interior(1) 3-2-5 to 5-9-4 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 102 lb uplift at joint 3.



September 26,2025





Job	Truss	Truss Type	Qty	Ply	Lot 65 Magnolia Hills
			_		176645114
251447-A	XB2	JACK-OPEN	2	1	
					Llob Reference (optional)

-1-2-8

1-2-8


Comtech, Inc, Fayetteville, NC - 28314,

25.3.0 s Sep 17 2025 MiTek Industries, Inc. Thu Sep 25 23:33:22 2025 Page 1 ID:3YJEg\_u8zX16RsP?VvW\_V6zd0wB-a4udDtFu5fc9EluSzfNzkM3\_R3ElcMylekhytsyZxNh 2-0-8

Structural wood sheathing directly applied or 2-0-8 oc purlins.

Rigid ceiling directly applied or 10-0-0 oc bracing.

Scale = 1:13.1



2-0-8 2-0-8

LOADIN	G (psf)	SPACING- 2-0-0	CSI.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL	20.0	Plate Grip DOL 1.15	TC 0.11	Vert(LL)	-0.00	2	>999	360	MT20	244/190
TCDL	10.0	Lumber DOL 1.15	BC 0.01	Vert(CT)	-0.00	2	>999	240		
BCLL	0.0 *	Rep Stress Incr YES	WB 0.00	Horz(CT)	-0.00	3	n/a	n/a		
BCDL	10.0	Code IRC2021/TPI2014	Matrix-P	Wind(LL)	0.00	2	****	240	Weight: 11 lb	FT = 20%

**BRACING-**

TOP CHORD

BOT CHORD

LUMBER-

REACTIONS.

2x4 SP No.1 TOP CHORD BOT CHORD 2x6 SP No.1

(size) 3=Mechanical, 2=0-3-8, 4=Mechanical

Max Horz 2=65(LC 12)

Max Uplift 3=-29(LC 12), 2=-16(LC 12)

Max Grav 3=34(LC 19), 2=185(LC 1), 4=37(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2E) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 29 lb uplift at joint 3 and 16 lb uplift at joint 2.



September 26,2025






Job	Truss	Truss Type	Qty	Ply	Lot 65 Magnolia Hills
					I76645115
251447-A	YA1	JACK-OPEN	4	1	
					Joh Reference (ontional)

Comtech, Inc, Fayetteville, NC - 28314, 25.3.0 s Sep 17 2025 MiTek Industries, Inc. Thu Sep 25 23:33:23 2025 Page 1

ID:3YJEg\_u8zX16RsP?VvW\_V6zd0wB-2GS?QCGXszl0ruTeXMuCHac8QTa\_LpCStORVQlyZxNg 1-10-15 1-10-15

Scale = 1:12.6



1-10-15 1-10-15

LOADIN	G (psf)	SPACING- 2-0-0	CSI.	DEFL.	in	(loc)	I/defI	L/d	PLATES	GRIP
TCLL	20.0	Plate Grip DOL 1.15	TC 0.10	Vert(LL)	-0.00	2	>999	360	MT20	244/190
TCDL	10.0	Lumber DOL 1.15	BC 0.01	Vert(CT)	-0.00	2	>999	240		
BCLL	0.0 *	Rep Stress Incr YES	WB 0.00	Horz(CT)	-0.00	3	n/a	n/a		
BCDL	10.0	Code IRC2021/TPI2014	Matrix-P	Wind(LL)	0.00	2	****	240	Weight: 10 lb	FT = 20%

LUMBER-

2x4 SP No.1 TOP CHORD 2x6 SP No.1 BOT CHORD

**BRACING-**

TOP CHORD **BOT CHORD**  Structural wood sheathing directly applied or 1-10-15 oc purlins. Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 3=Mechanical, 2=0-3-8, 4=Mechanical

Max Horz 2=63(LC 12)

Max Uplift 3=-29(LC 12), 2=-15(LC 12)

Max Grav 3=40(LC 19), 2=174(LC 1), 4=37(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2E) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 29 lb uplift at joint 3 and 15 lb uplift at joint 2.



September 26,2025



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPII Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacomponents.com)




Job Truss Truss Type Qty Ply Lot 65 Magnolia Hills 176645116 JACK-OPEN 251447-A YA2 Job Reference (optional)

Fayetteville, NC - 28314, Comtech, Inc.

25.3.0 s Sep 17 2025 MiTek Industries, Inc. Thu Sep 25 23:33:23 2025 Page 1 ID:3YJEg\_u8zX16RsP?VvW\_V6zd0wB-2GS?QCGXszl0ruTeXMuCHac75TaOLpCStORVQlyZxNg

3-10-15 3-10-15

Scale = 1:19.3



3-10-15 3-10-15

LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. i	n (loc)	I/defI	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.15	TC 0.18	Vert(LL) -0.0	2-4	>999	360	MT20	244/190
TCDL 10.0	Lumber DOL 1.15	BC 0.05	Vert(CT) -0.0	2-4	>999	240		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.00	Horz(CT) -0.0	) 3	n/a	n/a		
BCDL 10.0	Code IRC2021/TPI2014	Matrix-P	Wind(LL) 0.0	) 2	****	240	Weight: 19 lb	FT = 20%

LUMBER-

2x4 SP No.1 TOP CHORD BOT CHORD 2x6 SP No.1 **BRACING-**

TOP CHORD **BOT CHORD**  Structural wood sheathing directly applied or 3-10-15 oc purlins. Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 3=Mechanical, 2=0-3-8, 4=Mechanical

Max Horz 2=106(LC 12)

Max Uplift 3=-66(LC 12), 2=-6(LC 12)

Max Grav 3=110(LC 19), 2=244(LC 1), 4=74(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2E) -1-2-8 to 3-2-5, Interior(1) 3-2-5 to 3-10-3 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 66 lb uplift at joint 3 and 6 lb uplift at joint 2.



September 26,2025



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacomponents.com)




Job Truss Truss Type Qty Ply Lot 65 Magnolia Hills 176645117 HALF HIP GIRDER 251447-A YA3 Job Reference (optional) Fayetteville, NC - 28314, Comtech, Inc.

25.3.0 s Sep 17 2025 MiTek Industries, Inc. Thu Sep 25 23:33:23 2025 Page 1 ID:3YJEg\_u8zX16RsP?VvW\_V6zd0wB-2GS?QCGXszl0ruTeXMuCHac6vTanLpCStORVQlyZxNg

-1-8-8 2-11-4 2-11-4 1-8-8

Scale = 1:13.0



2-11-4 LOADING (psf) SPACING-2-0-0 CSI. DEFL. in (loc) I/defI L/d **PLATES** GRIP **TCLL** 20.0 Plate Grip DOL 1.15 TC 0.19 Vert(LL) -0.00 2 >999 360 MT20 244/190 TCDL Lumber DOL 1.15 вс 0.02 Vert(CT) -0.00 >999 240 WB 0.00 Horz(CT) **BCLL** 0.0 Rep Stress Incr YES -0.00 3 n/a n/a Wind(LL) 2 BCDL 10.0 Code IRC2021/TPI2014 Matrix-P 0.00 240 Weight: 15 lb FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.1 BOT CHORD 2x6 SP No.1 BRACING-

TOP CHORD BOT CHORD Structural wood sheathing directly applied or 2-11-4 oc purlins.

Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 3=Mechanical, 2=0-4-9, 4=Mechanical

Max Horz 2=66(LC 12)

Max Uplift 3=-31(LC 12), 2=-34(LC 12)

Max Grav 3=40(LC 1), 2=262(LC 1), 4=54(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2E) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 31 lb uplift at joint 3 and 34 lb uplift at ioint 2.



September 26,2025



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall

building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacomponents.com)




Job Truss Truss Type Qty Ply Lot 65 Magnolia Hills 176645118 YB1 JACK-OPEN 251447-A Job Reference (optional)

Fayetteville, NC - 28314, Comtech, Inc.

25.3.0 s Sep 17 2025 MiTek Industries, Inc. Thu Sep 25 23:33:24 2025 Page 1 ID:3YJEg\_u8zX16RsP?VvW\_V6zd0wB-WS0OeYH9dHttT22r54QRpn9J9twF4GRb62A3ylyZxNf

-1-2-8 1-8-15 1-2-8 1-8-15

Scale: 1"=1'



1-8-15 1-8-15

LOADIN	G (psf)	SPACING- 2-0-0	CSI.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL	20.0	Plate Grip DOL 1.15	TC 0.10	Vert(LL)	-0.00	2	>999	360	MT20	244/190
TCDL	10.0	Lumber DOL 1.15	BC 0.01	Vert(CT)	-0.00	2	>999	240		
BCLL	0.0 *	Rep Stress Incr YES	WB 0.00	Horz(CT)	-0.00	3	n/a	n/a		
BCDL	10.0	Code IRC2021/TPI2014	Matrix-P	Wind(LL)	0.00	2	****	240	Weight: 10 lb	FT = 20%

LUMBER-

2x4 SP No.1 TOP CHORD BOT CHORD 2x6 SP No.1 **BRACING-**

TOP CHORD **BOT CHORD**  Structural wood sheathing directly applied or 1-8-15 oc purlins. Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 3=Mechanical, 2=0-3-8, 4=Mechanical

Max Horz 2=60(LC 12)

Max Uplift 3=-25(LC 12), 2=-17(LC 12)

Max Grav 3=32(LC 19), 2=169(LC 1), 4=34(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2E) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 25 lb uplift at joint 3 and 17 lb uplift at joint 2.



September 26,2025



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPII Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacomponents.com)




Job Truss Truss Type Qty Ply Lot 65 Magnolia Hills 176645119 YB2 JACK-OPEN 251447-A Job Reference (optional)

Fayetteville, NC - 28314, Comtech, Inc.

25.3.0 s Sep 17 2025 MiTek Industries, Inc. Thu Sep 25 23:33:24 2025 Page 1 ID:3YJEg\_u8zX16RsP?VvW\_V6zd0wB-WS0OeYH9dHttT22r54QRpn9I7twi4GRb62A3ylyZxNf

3-8-15 3-8-15

Scale = 1:18.7



3-8-15

LOADING (psf)	SPACING- 2-0-0	CSI.	<b>DEFL.</b> ir	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.15	TC 0.16	Vert(LL) -0.00	2-4	>999	360	MT20 2	244/190
TCDL 10.0	Lumber DOL 1.15	BC 0.04	Vert(CT) -0.00	2-4	>999	240		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.00	Horz(CT) -0.00	3	n/a	n/a		
BCDL 10.0	Code IRC2021/TPI2014	Matrix-P	Wind(LL) 0.00	2	****	240	Weight: 18 lb	FT = 20%

LUMBER-

2x4 SP No.1 TOP CHORD BOT CHORD 2x6 SP No.1 **BRACING-**

TOP CHORD **BOT CHORD**  Structural wood sheathing directly applied or 3-8-15 oc purlins.

Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 3=Mechanical, 2=0-3-8, 4=Mechanical

Max Horz 2=102(LC 12)

Max Uplift 3=-63(LC 12), 2=-7(LC 12)

Max Grav 3=104(LC 19), 2=238(LC 1), 4=71(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2E) -1-2-8 to 3-2-5, Interior(1) 3-2-5 to 3-8-3 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 63 lb uplift at joint 3 and 7 lb uplift at joint 2.



September 26,2025




WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall

building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacomponents.com)





TOP CHORD

BOT CHORD

LUMBER-

REACTIONS.

TOP CHORD 2x4 SP No.1 BOT CHORD 2x4 SP No 1

> (size) 3=Mechanical, 2=0-3-8, 4=Mechanical Max Horz 2=41(LC 8)

Max Uplift 3=-23(LC 12), 2=-90(LC 8), 4=-11(LC 8) Max Grav 3=38(LC 1), 2=192(LC 1), 4=42(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2E) zone; porch left exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 23 lb uplift at joint 3, 90 lb uplift at joint 2 and 11 lb uplift at joint 4.



Structural wood sheathing directly applied or 2-3-15 oc purlins.

Rigid ceiling directly applied or 10-0-0 oc bracing.

September 26,2025




WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall

building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacomponents.com)





TOP CHORD

**BOT CHORD** 

LUMBER-

REACTIONS.

TOP CHORD 2x4 SP No.1 BOT CHORD 2x4 SP No.1

(size) 3=Mechanical, 2=0-3-0, 4=Mechanical

Max Horz 2=62(LC 8) Max Uplift 3=-50(LC 12), 2=-110(LC 8), 4=-21(LC 8)

Max Grav 3=111(LC 1), 2=259(LC 1), 4=83(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- $1) \ Wind: ASCE\ 7-16; \ Vult=130mph\ (3-second\ gust)\ Vasd=103mph; \ TCDL=6.0psf;\ BCDL=6.0psf;\ h=15ft;\ Cat.\ II;\ Exp\ C;\ Enclosed;\ ASCE\ TCDL=6.0psf;\ h=15ft;\ h=$ MWFRS (envelope) and C-C Exterior(2E) -1-2-8 to 3-2-5, Interior(1) 3-2-5 to 4-3-3 zone; porch left exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 50 lb uplift at joint 3, 110 lb uplift at joint 2 and 21 lb uplift at joint 4.



Structural wood sheathing directly applied or 4-3-15 oc purlins.

Rigid ceiling directly applied or 10-0-0 oc bracing.

September 26,2025



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacomponents.com)



Job Truss Truss Type Qty Ply Lot 65 Magnolia Hills 176645122 DIAGONAL HIP GIRDER 2 251447-A ZA1 Job Reference (optional)

Fayetteville, NC - 28314, Comtech, Inc.

25.3.0 s Sep 17 2025 MiTek Industries, Inc. Thu Sep 25 23:33:25 2025 Page 1 ID:3YJEg\_u8zX16RsP?VvW\_V6zd0wB-\_famruInOa?k5Cd1enxgM\_hShHFCphQkKiwcUByZxNe

4-3-8


except end verticals.

Structural wood sheathing directly applied or 6-0-0 oc purlins,

Rigid ceiling directly applied or 10-0-0 oc bracing.

4-0-13 1-8-8 4-0-13

Scale = 1:25.8



LOADING	G (psf)	SPACING- 2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	20.0	Plate Grip DOL 1.15	TC 0.24	Vert(LL)	-0.00	7-8	>999	360	MT20	244/190
TCDL	10.0	Lumber DOL 1.15	BC 0.09	Vert(CT)	-0.01	7-8	>999	240		
BCLL	0.0 *	Rep Stress Incr NO	WB 0.15	Horz(CT)	0.00	7	n/a	n/a		
BCDL	10.0	Code IRC2021/TPI2014	Matrix-P	Wind(LL)	0.00	8	>999	240	Weight: 51 lb	FT = 20%

**BRACING-**

TOP CHORD

**BOT CHORD** 

4-0-13

LUMBER-

REACTIONS.

TOP CHORD 2x4 SP No.1 BOT CHORD 2x6 SP No.1

WFBS 2x4 SP No.2

(size) 7=Mechanical, 2=0-4-9

Max Horz 2=150(LC 8)

Max Uplift 7=-110(LC 8), 2=-50(LC 8) Max Grav 7=353(LC 35), 2=456(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-523/31

**BOT CHORD** 2-8=-118/381 7-8=-118/381

**WEBS** 3-7=-430/133

### NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope); Lumber DOL=1.60 plate grip DOL=1.60
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 110 lb uplift at joint 7 and 50 lb uplift at joint 2.
- 7) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 75 lb down and 33 lb up at 2-9-8, 75 lb down and 33 lb up at 2-9-8, and 107 lb down and 84 lb up at 5-7-7, and 107 lb down and 84 lb up at 5-7-7 on top chord , and 2 lb down at 2-9-8, 2 lb down at 2-9-8, and 20 lb down at 5-7-7, and 20 lb down at 5-7-7 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 8) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

### LOAD CASE(S) Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15 Uniform Loads (plf)

Vert: 1-4=-60, 4-5=-20, 2-6=-20

Concentrated Loads (lb)

Vert: 10=-23(F=-11, B=-11) 12=-17(F=-9, B=-9)



September 26,2025



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall

building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacomponents.com)



Job Truss Truss Type Qty Ply Lot 65 Magnolia Hills 176645123 ZB1 DIAGONAL HIP GIRDER 2 251447-A Job Reference (optional)

Fayetteville, NC - 28314, Comtech, Inc.

25.3.0 s Sep 17 2025 MiTek Industries, Inc. Thu Sep 25 23:33:26 2025 Page 1 ID:3YJEg\_u8zX16RsP?VvW\_V6zd0wB-Sr882EIP9u7biMBDCVSvuCEdvgbZY8vuZMfA0dyZxNd

4-2-2


except end verticals.

Structural wood sheathing directly applied or 6-0-0 oc purlins,

Rigid ceiling directly applied or 10-0-0 oc bracing.

-1-<u>8-8</u> 8-1-8 1-8-8 3-11-6

Scale = 1:25.2



LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL.	in (loc)		L/d		RIP
TCLL 20.0	Plate Grip DOL 1.15	TC 0.21	1 ' '	0.00 . 0	- 000	360	MT20 24	44/190
TCDL 10.0	Lumber DOL 1.15	BC 0.08	/	-0.01 7-8	>999	240		
BCLL 0.0 *	Rep Stress Incr NO	WB 0.13	Horz(CT)	0.00 7	n/a	n/a		
BCDL 10.0	Code IRC2021/TPI2014	Matrix-P	Wind(LL)	0.00	>999	240	Weight: 49 lb	FT = 20%

**BRACING-**

TOP CHORD

**BOT CHORD** 

3-11-6

LUMBER-

REACTIONS.

TOP CHORD 2x4 SP No.1 BOT CHORD 2x6 SP No.1

WFBS 2x4 SP No.2

(size) 7=Mechanical, 2=0-4-9

Max Horz 2=146(LC 8)

Max Uplift 7=-104(LC 8), 2=-48(LC 8) Max Grav 7=336(LC 35), 2=443(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-502/26

**BOT CHORD** 2-8=-112/361 7-8=-112/361

**WEBS** 3-7=-408/127

### NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope); Lumber DOL=1.60 plate grip DOL=1.60
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 104 lb uplift at joint 7 and 48 lb uplift at ioint 2.
- 7) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 74 lb down and 28 lb up at 2-6-11, 74 lb down and 28 lb up at 2-6-11, and 104 lb down and 79 lb up at 5-4-10, and 104 lb down and 79 lb up at 5-4-10 on top chord, and 0 lb down at 2-6-11, 0 lb down at 2-6-11, and 18 lb down at 5-4-10, and 18 lb down at 5-4-10 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 8) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

### LOAD CASE(S) Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15 Uniform Loads (plf)

Vert: 1-4=-60, 4-5=-20, 2-6=-20

Concentrated Loads (lb)

Vert: 10=-11(F=-6, B=-6) 12=-14(F=-7, B=-7)



September 26,2025



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall

building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacomponents.com)



Job Truss Truss Type Qty Ply Lot 65 Magnolia Hills 176645124 ZB2 JACK-OPEN 251447-A Job Reference (optional)

Fayetteville, NC - 28314, Comtech, Inc.


25.3.0 s Sep 17 2025 MiTek Industries, Inc. Thu Sep 25 23:33:26 2025 Page 1 ID:3YJEg\_u8zX16RsP?VvW\_V6zd0wB-Sr882EIP9u7biMBDCVSvuCEdlgcXYAxuZMfA0dyZxNd

Structural wood sheathing directly applied or 2-9-4 oc purlins.

Rigid ceiling directly applied or 10-0-0 oc bracing.

-1-8-8 1-8-8

Scale = 1:12.6



2-9-4

LOADING	G (psf)	SPACING- 2-0-0	CSI.	<b>DEFL.</b> in	(loc)	I/defI	L/d	PLATES GRIP
TCLL	20.0	Plate Grip DOL 1.15	TC 0.25	Vert(LL) -0.00	2	>999	360	MT20 244/190
TCDL	10.0	Lumber DOL 1.15	BC 0.02	Vert(CT) -0.00	2-4	>999	240	
BCLL	0.0 *	Rep Stress Incr YES	WB 0.00	Horz(CT) -0.00	3	n/a	n/a	
BCDL	10.0	Code IRC2021/TPI2014	Matrix-P	Wind(LL) 0.00	2	****	240	Weight: 14 lb FT = 20%

**BRACING-**

TOP CHORD

BOT CHORD

LUMBER-

REACTIONS.

2x4 SP No.1 TOP CHORD BOT CHORD 2x6 SP No.1

(size) 3=Mechanical, 2=0-4-10, 4=Mechanical

Max Horz 2=64(LC 12)

Max Uplift 3=-28(LC 12), 2=-35(LC 12)

Max Grav 3=32(LC 1), 2=258(LC 1), 4=50(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Corner(3) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 28 lb uplift at joint 3 and 35 lb uplift at joint 2.



September 26,2025



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPII Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacomponents.com)




Job Truss Truss Type Qty Ply Lot 65 Magnolia Hills 176645125 ZP1 DIAGONAL HIP GIRDER 251447-A Job Reference (optional) Fayetteville, NC - 28314, 25.3.0 s Sep 17 2025 MiTek Industries, Inc. Thu Sep 25 23:33:27 2025 Page 1 Comtech, Inc.

ID:F7e3nXrh6oAXz?VjiI5mfhz3PFB-x1iWGaJ1wCFSKWmQmCz8RPnob4umHdK1o?PjZ3yZxNc 3-0-15 6-1-7

3-0-15 3-0-8

Scale = 1:14.7



	<u> </u>	3-0-15 3-0-15		6-1- 3-0-	
LOADING (psf) TCLL 20.0 TCDL 10.0 BCLL 0.0 * BCDL 10.0	SPACING- 2-0-0 Plate Grip DOL 1.15 Lumber DOL 1.15 Rep Stress Incr NO Code IRC2021/TPI2014	CSI. TC 0.21 BC 0.21 WB 0.06 Matrix-P	DEFL.         in           Vert(LL)         -0.00           Vert(CT)         -0.01           Horz(CT)         0.00           Wind(LL)         0.01	8 >999 360 8 >999 240	<b>GRIP</b> 244/190 FT = 20%

**BRACING-**

TOP CHORD

**BOT CHORD** 

LUMBER-

REACTIONS.

TOP CHORD 2x4 SP No.1 BOT CHORD 2x4 SP No.1

WFBS 2x4 SP No.2

(size) 7=Mechanical, 2=0-4-4

-1-8-8

1-8-8

Max Horz 2=63(LC 4)

Max Uplift 7=-55(LC 8), 2=-117(LC 4) Max Grav 7=219(LC 1), 2=359(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-360/75

**BOT CHORD** 2-8=-103/308 7-8=-103/308

**WEBS** 3-7=-325/109

### NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope); Lumber DOL=1.60 plate grip DOL=1.60
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 55 lb uplift at joint 7 and 117 lb uplift at joint 2.
- 7) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 25 lb down and 24 lb up at 3-4-9, and 25 lb down and 24 lb up at 3-4-9 on top chord, and 4 lb down and 24 lb up at 3-4-9, and 4 lb down and 24 lb up at 3-4-9 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 8) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

### LOAD CASE(S) Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15 Uniform Loads (plf)

Vert: 1-4=-60, 4-5=-20, 2-6=-20



Structural wood sheathing directly applied or 6-0-0 oc purlins,

Rigid ceiling directly applied or 10-0-0 oc bracing.

except end verticals.

September 26,2025



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall

building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacomponents.com)




Job Truss Truss Type Qty Ply Lot 65 Magnolia Hills 176645126 251447-A ZP2 DIAGONAL HIP GIRDER Job Reference (optional) Fayetteville, NC - 28314, 25.3.0 s Sep 17 2025 MiTek Industries, Inc. Thu Sep 25 23:33:27 2025 Page 1 Comtech, Inc. ID:F7e3nXrh6oAXz?Vjil5mfhz3PFB-x1iWGaJ1wCFSKWmQmCz8RPnmp4tfHaL1o?PjZ3yZxNc

4-5-14

4-5-14

Scale = 1:19.6

8-11-6



	-	4-5-14 4-5-14	8-11-6 4-5-8
LOADING (psf)	SPACING- 2-0-0	CSI. DEFL.	in (loc) I/defl L/d PLATES GRIP
TCLL 20.0	Plate Grip DOL 1.15	TC 0.33 Vert(LL)	0.03 7-8 >999 240 MT20 244/190
TCDL 10.0	Lumber DOL 1.15	BC 0.28 Vert(CT)	-0.04 7-8 >999 240
BCLL 0.0 *	Rep Stress Incr NO	WB 0.25 Horz(CT)	0.01 7 n/a n/a
BCDL 10.0	Code IRC2021/TPI2014	Matrix-P	Weight: 40 lb FT = 20%

**BRACING-**

TOP CHORD

**BOT CHORD** 

LUMBER-

TOP CHORD 2x4 SP No.1 BOT CHORD 2x4 SP No.1

2x4 SP No.2 **WEBS** 

REACTIONS. (size) 7=Mechanical, 2=0-3-14

-1-8-8

1-8-8

Max Horz 2=84(LC 4)

Max Uplift 7=-174(LC 4), 2=-212(LC 4) Max Grav 7=396(LC 1), 2=488(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-777/280

**BOT CHORD** 2-8=-315/710 7-8=-315/710

**WEBS** 3-7=-742/329

### NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope); porch left exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) \* This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 174 lb uplift at joint 7 and 212 lb uplift at joint 2.
- 7) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 25 lb down and 24 lb up at 3-4-9, 25 lb down and 24 lb up at 3-4-9, and 83 lb down and 62 lb up at 6-2-8, and 83 lb down and 62 lb up at 6-2-8 on top chord, and 4 lb down and 24 lb up at 3-4-9, 4 lb down and 24 lb up at 3-4-9, and 26 lb down and 46 lb up at 6-2-8, and 26 lb down and 46 Ib up at 6-2-8 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 8) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).


### LOAD CASE(S) Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15 Uniform Loads (plf)

Vert: 1-4=-60, 4-5=-20, 2-6=-20

Concentrated Loads (lb)

Vert: 10=-53(F=-26, B=-26) 12=-26(F=-13, B=-13)



Structural wood sheathing directly applied or 6-0-0 oc purlins,

except end verticals.

September 26,2025





building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TP11 Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacomponents.com)



### Symbols

## PLATE LOCATION AND ORIENTATION



offsets are indicated and fully embed teeth Center plate on joint unless x, y Apply plates to both sides of truss Dimensions are in ft-in-sixteenths



edge of truss. plates 0- 1/16" from outside For 4 x 2 orientation, locate

connector plates. required direction of slots in This symbol indicates the

\* Plate location details available in MiTek software or upon request

### PLATE SIZE

to slots. Second dimension is the length parallel to slots. width measured perpendicular The first dimension is the plate

## LATERAL BRACING LOCATION



by text in the bracing section of the output. Use T or I bracing if indicated. ndicated by symbol shown and/or

### **BEARING**



Min size shown is for crushing only number/letter where bearings occur reaction section indicates joint (supports) occur. Icons vary but Indicates location where bearings

### Industry Standards:

National Design Specification for Metal Plate Connected Wood Trusses Installing, Restraining & Bracing of Metal Guide to Good Practice for Handling, Building Component Safety Information, Design Standard for Bracing. Plate Connected Wood Truss Construction.

DSB-22: ANSI/TPI1:

## Numbering System



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

# Product Code Approvals

ICC-ES Reports:

ESR-1988, ESR-2362, ESR-2685, ESR-3282 ESR-4722, ESL-1388

# Design General Notes

truss unless otherwise shown Trusses are designed for wind loads in the plane of the

established by others section 6.3 These truss designs rely on lumber values Lumber design values are in accordance with ANSI/TPI 1

© 2023 MiTek® All Rights Reserved

## MiTek



MiTek Engineering Reference Sheet: MII-7473 rev. 1/2/2023

# General Safety Notes

## Damage or Personal Injury Failure to Follow Could Cause Property

- Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI
- Ņ Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor I bracing should be considered.
- Never exceed the design loading shown and never stack materials on inadequately braced trusses.
- Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
- Cut members to bear tightly against each other

'n

- joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TPI 1. Place plates on each face of truss at each
- Design assumes trusses will be suitably protected from the environment in accord with ANSI/TPI 1.
- œ Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
- Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.

9

- Camber is a non-structural consideration and is the camber for dead load deflection responsibility of truss fabricator. General practice is to
- 11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
- Lumber used shall be of the species and size, and in all respects, equal to or better than that
- Top chords must be sheathed or purlins provided at spacing indicated on design.
- Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
- 15. Connections not shown are the responsibility of others
- Do not cut or alter truss member or plate without prior approval of an engineer.
- Install and load vertically unless indicated otherwise.
- Use of green or treated lumber may pose unacceptable project engineer before use. environmental, health or performance risks. Consult with
- 19. Review all portions of this design (front, back, words is not sufficient. and pictures) before use. Reviewing pictures alone
- Design assumes manufacture in accordance with ANSI/TPI 1 Quality Criteria.
- 21. The design does not take into account any dynamic or other loads other than those expressly stated.



RE: 251447-B

Lot 65 Magnolia Hills

Trenco 818 Soundside Rd Edenton, NC 27932

Site Information:

Customer: Precision Custom Homes and Renovations Project Name: 251447-B

Lot/Block: Model:

Address: 314 Persimmon Tree Dr. Subdivision: State: NC

### General Truss Engineering Criteria & Design Loads (Individual Truss Design Drawings Show Special Loading Conditions):

Design Code: IRC2021/TPI2014 Design Program: MiTek 20/20 25.2

Wind Code: N/A Wind Speed: N/A mph Roof Load: N/A psf Floor Load: 55.0 psf

This package includes 9 individual, dated Truss Design Drawings and 0 Additional Drawings.

No.	Seal#	Truss Name	Date
1	175971131	ET1	8/28/2025
2	175971132	ET2	8/28/2025
3	175971133	F01	8/28/2025
4	175971134	F02	8/28/2025
5	175971135	F03	8/28/2025
6	175971136	F04	8/28/2025
7	175971137	F05	8/28/2025
8	175971138	F07	8/28/2025
9	175971139	F08	8/28/2025

The truss drawing(s) referenced above have been prepared by

Truss Engineering Co. under my direct supervision

based on the parameters provided by Comtech, Inc - Fayetteville.

Truss Design Engineer's Name: Gilbert, Eric

My license renewal date for the state of North Carolina is December 31, 2025

North Carolina COA: C-0844

IMPORTANT NOTE: The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to TRENCO. Any project specific information included is for TRENCO customers file reference purpose only, and was not taken into account in the preparation of these designs. TRENCO has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.



August 28, 2025


Job	Truss	Truss Type	Qty	Ply	Lot 65 Magnolia Hills
					175971131
251447-B	ET1	GABLE	1	1	
			l		Lob Reference (optional)

25.3.0 s Aug 20 2025 MiTek Industries, Inc. Thu Aug 28 07:05:29 2025 Page 1

0-<u>1</u>-8

ID:3YJEg\_u8zX16RsP?VvW\_V6zd0wB-6ZF8wLf0zi0XYUxTjAWJPVja3YyUibimfkwYGQyjOTq

Scale: 1/4"=1'



	1-4-0	2-8-0 1-4-0	<del>4-0-0</del> <del>1-4-0</del>	5-4-0 1-4-0	6-8-0 1-4-0	8-0-0 1-4-0	9-4-0 1-4-0	10-8-0	12-0-0 1-4-0	13-4-0	14-8-0 1-4-0	16-0-0	17-4-0	18-8-0 1-4-0	20-0-0 1-4-0	21-4-0 1-4-0	22-8-0 1-4-0	<del>  24-0-0</del>   <del>1-4-0</del>	25-4-0 1-4-0	26-8-0 1-4-0	28-0-0 28-6-8 1-4-0 0-6-8	
LOAD TCLL TCDL BCLL BCDL	NG (ps 40. 10. 0. 5.	.0 .0 .0	F L	SPACINO Plate Gri Lumber I Rep Stre Code IR	p DOL DOL ss Incr	2-0-0 1.00 1.00 YES PI2014	) ) S	C: TC BC W M:	0.0	01	,	DEFL. /ert(LL) /ert(CT) Horz(CT)	in n/a n/a 0.00	- -	l/defl n/a n/a n/a	L/d 999 999 n/a		M	_ATES T20 eight: 12		<b>GRIP</b> 244/190 FT = 20%F, 1	I1%E

LUMBER-**BRACING-**

TOP CHORD 2x4 SP No.1(flat) TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, 2x4 SP No.1(flat) BOT CHORD except end verticals. WFBS

2x4 SP No.3(flat) **OTHERS** 2x4 SP No.3(flat) **BOT CHORD** Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. All bearings 28-6-8.

(lb) - Max Grav All reactions 250 lb or less at joint(s) 48, 25, 47, 46, 45, 44, 43, 42, 41, 40, 39, 37, 36, 35, 34, 33, 32, 31, 30, 29, 28, 27, 26

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

### NOTES-

- 1) All plates are 1.5x3 MT20 unless otherwise indicated.
- 2) Plates checked for a plus or minus 1 degree rotation about its center.
- 3) Gable requires continuous bottom chord bearing.
- 4) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
- 5) Gable studs spaced at 1-4-0 oc.
- 6) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.



August 28,2025




Job	Truss	Truss Type	Qty	Ply	Lot 65 Magnolia Hills
251447-B	ET2	GABLE	1	1	I75971132

0-<u>11</u>-8

25.3.0 s Aug 20 2025 MiTek Industries, Inc. Thu Aug 28 07:05:30 2025 Page 1 ID:3YJEg\_u8zX16RsP?VvW\_V6zd0wB-alpW8hgek?8OAeWgGu1YyjGlpxllR2yvtOg6osyjOTp

0-<u>11</u>-8

Scale: 3/8"=1'



<u></u>	1-4-0	2-8-0 1-4-0		5-4-0 6-8-0 -4-0 1-4-0			10-8-0	12-0-0 1-4-0	13-4-		14-8-0 1-4-0	16-0-0 1-4-0	17-4-0	18-8-0 1-4-0 1-9-8
LOADING TCLL TCDL BCLL BCDL			SPACING- Plate Grip DOL Lumber DOL Rep Stress Incr Code IRC2021/	2-0-0 1.00 1.00 YES	CSI. TC BC WB Matri	0.06 0.01 0.03	DEFL. Vert(LL) Vert(CT) Horz(CT)	in n/a n/a 0.00		I/defl n/a n/a n/a n/a	L/d 999 999 n/a	. 40	PLATES MT20 Weight: 86 lb	<b>GRIP</b> 244/190 FT = 20%F, 11%E

LUMBER-**BRACING-**

TOP CHORD 2x4 SP No.1(flat) 2x4 SP No.1(flat) BOT CHORD

2x4 SP No.3(flat) WFBS **OTHERS** 2x4 SP No.3(flat) TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins,

except end verticals.

**BOT CHORD** Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. All bearings 19-5-8.

(lb) - Max Grav All reactions 250 lb or less at joint(s) 34, 18, 33, 32, 30, 29, 28, 27, 26, 25, 24, 23, 22, 21, 20,

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

### NOTES-

- 1) All plates are 1.5x3 MT20 unless otherwise indicated.
- 2) Plates checked for a plus or minus 1 degree rotation about its center.
- 3) Gable requires continuous bottom chord bearing.
- 4) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
- 5) Gable studs spaced at 1-4-0 oc.
- 6) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.





Job	Truss	Truss Type	Qty	Ply	Lot 65 Magnolia Hills
251447-B	F01	Floor	5	1	175971133
231447-B	FUI	Floor	5	'	Job Reference (optional)

Comtech, Inc,

Fayetteville, NC - 28314,

1-9-4


25.3.0 s Aug 20 2025 MiTek Industries, Inc. Thu Aug 28 07:05:30 2025 Page 1 ID:3YJEg\_u8zX16RsP?VvW\_V6zd0wB-alpW8hgek?8OAeWgGu1YyjGYlx5jRwWvtOg6osyjOTp

0-1-8

HI 1-3-0

2-5-12

0-1-8 Scale = 1:58.0



		17	7-4-12						17-1-4		
Plate Off	sets (X,Y)	[15:0-1-8,Edge], [20:0-1-8,	,Edge], [21:0-	-1-8,Edge], [2	4:0-1-8,Edge]	, [33:0-1-8,Edge]	], [34:0-1-8	,Edge], [39:	0-1-8,0-1-0]		
LOADIN	G (psf)	SPACING-	2-0-0	CSI.		DEFL.	in (lo	oc) I/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.90	Vert(LL)	-0.27 23-	,	480	MT20	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.85	Vert(CT)	-0.37 23-	24 >554	360		
BCLL	0.0	Rep Stress Incr	YES	WB	0.57	Horz(CT)	0.06	21 n/a	n/a		
BCDL	5.0	Code IRC2021/TPI	2014	Matrix	:-S					Weight: 178 lb	FT = 20%F, 11%E

LUMBER-TOP CHORD 2x4 SP No 1(flat)

2x4 SP No.1(flat) \*Except\* **BOT CHORD** 

21-28: 2x4 SP 2400F 2.0E(flat)

WFBS 2x4 SP No.3(flat) **BRACING-**TOP CHORD

Structural wood sheathing directly applied or 2-2-0 oc purlins,

34-6-0

except end verticals.

BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except:

6-0-0 oc bracing: 30-32,29-30,27-29,26-27.

REACTIONS. (size) 37=0-3-0, 29=0-3-8, 21=0-3-0

Max Grav 37=843(LC 3), 29=2186(LC 1), 21=830(LC 4)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-1503/0, 3-4=-2386/0, 4-5=-2643/0, 5-6=-2643/0, 6-7=-2643/0, 7-8=-1780/88, 8-10=-506/546, 10-11=0/2201, 11-12=0/2201, 12-14=-681/785, 14-15=-1899/278,

17-4-12

15-16=-2534/0, 16-17=-2534/0, 17-18=-2402/0, 18-19=-1542/0

 $36-37=0/903,\ 35-36=0/2079,\ 34-35=0/2643,\ 33-34=0/2643,\ 32-33=0/2272,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35=0/2643,\ 34-35$ 

 $30 - 32 = -286/1285, \ 29 - 30 = -976/0, \ 27 - 29 = -1165/0, \ 26 - 27 = -526/1397, \ 25 - 26 = 0/2534,$ 

24-25=0/2534, 23-24=0/2610, 22-23=0/2105, 21-22=0/965  $2\text{-}37\text{=-}1200/0,\ 2\text{-}36\text{=-}0/834,\ 3\text{-}36\text{=-}802/0,\ 3\text{-}35\text{=-}0/427,\ 4\text{-}35\text{=-}357/9,\ 4\text{-}34\text{=-}350/210,}$ 

10-29=-1600/0, 10-30=0/1200, 8-30=-1156/0, 8-32=0/754, 7-32=-768/0, 7-33=0/811 6-33=-384/0, 19-21=-1233/0, 19-22=0/803, 18-22=-783/0, 18-23=0/413, 17-23=-290/84,

12-29=-1578/0, 12-27=0/1136, 14-27=-1077/0, 14-26=0/810, 15-26=-1102/0,

17-24=-451/56, 15-25=0/378

### NOTES-

**WEBS** 

BOT CHORD

- 1) Unbalanced floor live loads have been considered for this design.
- 2) All plates are 3x4 MT20 unless otherwise indicated.
- 3) Plates checked for a plus or minus 1 degree rotation about its center.
- 4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
- 5) CAUTION, Do not erect truss backwards.



August 28,2025



Job	Truss	Truss Type	Qty	Ply	Lot 65 Magnolia Hills
			_		175971134
251447-B	F02	Floor	3	1	
					Job Reference (optional)

25.3.0 s Aug 20 2025 MiTek Industries, Inc. Thu Aug 28 07:05:31 2025 Page 1 ID:3YJEg\_u8zX16RsP?VvW\_V6zd0wB-2xNvL1hGVJGFno5sqbYnUwomXLTOANB262PfLlyjOTo


Structural wood sheathing directly applied or 6-0-0 oc purlins,


Rigid ceiling directly applied or 6-0-0 oc bracing.

except end verticals.

0-1-8







TOP CHORD

BOT CHORD

LUMBER-2x4 SP No.1(flat) TOP CHORD

BOT CHORD 2x4 SP No.1(flat) WFBS 2x4 SP No.3(flat)

REACTIONS. (size) 31=0-3-0, 18=0-3-0, 23=0-3-8

Max Grav 31=854(LC 10), 18=536(LC 4), 23=1831(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

2-3=-1528/0, 3-4=-2433/0, 4-5=-2723/0, 5-6=-2723/0, 6-7=-2723/0, 7-8=-1895/0, TOP CHORD

8-10=-640/19, 10-11=0/1619, 11-12=0/1619, 12-13=-534/758, 13-14=-1022/387,

14-15=-1022/387 15-16=-850/32

**BOT CHORD**  $30 - 31 = 0/916,\ 29 - 30 = 0/2115,\ 28 - 29 = 0/2703,\ 27 - 28 = 0/2723,\ 26 - 27 = 0/2373,\ 25 - 26 = 0/1410,$ 

 $23-25=-494/0,\ 22-23=-1043/109,\ 21-22=-387/1022,\ 20-21=-387/1022,\ 19-20=-137/1078,$ 

18-19=0/563

WEBS 2-31=-1217/0, 2-30=0/850, 3-30=-818/0, 3-29=0/442, 4-29=-375/0, 4-28=-244/309,  $10 - 23 = -1497/0,\ 10 - 25 = 0/1144,\ 8 - 25 = -1106/0,\ 8 - 26 = 0/708,\ 7 - 26 = -708/0,\ 7 - 27 = 0/705,$ 

6-27=-338/0, 16-18=-747/0, 16-19=-46/399, 15-19=-318/146, 12-23=-1013/0,

12-22=0/766, 13-22=-925/0, 15-20=-411/0, 13-21=0/267

- 1) Unbalanced floor live loads have been considered for this design.
- 2) All plates are 3x4 MT20 unless otherwise indicated.
- 3) Plates checked for a plus or minus 1 degree rotation about its center.
- 4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
- 5) CAUTION, Do not erect truss backwards.





-	lob	Truss	Truss Type	Qty	Ply	Lot 65 Magnolia Hills
١.		Γ02	51.005		.	175971135
2	251447-B	F03	FLOOR	9	1	Job Reference (optional)

25.3.0 s Aug 20 2025 MiTek Industries, Inc. Thu Aug 28 07:05:32 2025 Page 1 ID:3YJEg\_u8zX16RsP?VvW\_V6zd0wB-W8xHZNhuGdO6Pyf2OJ3018L1tlrfvp8CLi9CtkyjOTn

Structural wood sheathing directly applied or 6-0-0 oc purlins,

Rigid ceiling directly applied or 10-0-0 oc bracing.

except end verticals.

0-1-8 H | 1-3-0

2-6-0

0-1-8 Scale = 1:38.3




Plate Offsets (X,Y)	Plate Offsets (X,Y) [8:0-3-0,0-0-0], [15:0-3-0,Edge], [21:0-3-0,Edge], [22:0-3-0,Edge], [28:0-1-8,0-0-8], [29:0-1-8,0-0-8]				
LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) I/defl L/d	PLATES GRIP	
TCLL 40.0	Plate Grip DOL 1.00	TC 0.28	Vert(LL) -0.32 21 >816 480	MT20 244/190	
TCDL 10.0	Lumber DOL 1.00	BC 0.62	Vert(CT) -0.44 21 >594 360	M18AHS 186/179	
BCLL 0.0	Rep Stress Incr YES	WB 0.63	Horz(CT) 0.05 16 n/a n/a		
BCDL 5.0	Code IRC2021/TPI2014	Matrix-S		Weight: 175 lb FT = 20%F, 11%E	

**BRACING-**TOP CHORD

BOT CHORD

LUMBER-TOP CHORD

2x4 SP No 1(flat) BOT CHORD 2x4 SP No.1(flat)

WFBS 2x4 SP No.3(flat)

REACTIONS. (size) 27=0-3-0, 16=0-3-0

Max Grav 27=1203(LC 1), 16=1203(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

2-3=-2459/0, 3-4=-4251/0, 4-5=-5445/0, 5-7=-5445/0, 7-8=-5947/0, 8-9=-5947/0, TOP CHORD

9-10=-5471/0, 10-11=-5471/0, 11-13=-4246/0, 13-14=-2460/0 26-27=0/1467, 25-26=0/3507, 23-25=0/4963, 22-23=0/5947, 21-22=0/5947, 20-21=0/5809,

18-20=0/4966, 17-18=0/3506, 16-17=0/1467 WFBS

2-27=-1813/0, 2-26=0/1316, 3-26=-1387/0, 3-25=0/984, 4-25=-942/0, 4-23=0/625, 14-16=-1814/0, 14-17=0/1317, 13-17=-1385/0, 13-18=0/979, 11-18=-953/0, 11-20=0/654,

9-20=-512/0, 7-23=-1064/20, 9-21=-267/688, 8-21=-322/41

### NOTES-

BOT CHORD

- 1) Unbalanced floor live loads have been considered for this design.
- 2) All plates are MT20 plates unless otherwise indicated.
- 3) All plates are 6x6 MT20 unless otherwise indicated.
- 4) Plates checked for a plus or minus 1 degree rotation about its center.
- 5) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.





Job	Truss	Truss Type	Qty	Ply	Lot 65 Magnolia Hills
					175971136
251447-B	F04	Floor	6	1	
					Job Reference (optional)

25.3.0 s Aug 20 2025 MiTek Industries, Inc. Thu Aug 28 07:05:32 2025 Page 1 ID:3YJEg\_u8zX16RsP?VvW\_V6zd0wB-W8xHZNhuGdO6Pyf2OJ3018Lt8lpBvqUCLi9CtkyjOTn

Structural wood sheathing directly applied, except end verticals.

Rigid ceiling directly applied or 10-0-0 oc bracing.

0-1-8 Scale = 1:32.9

0-1-8 H | 1-3-0 2-4-0




Plate Offsets (X,Y)				
LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) I/defl L/d	PLATES GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.90	Vert(LL) -0.31 17 >753 480	MT20 244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.72	Vert(CT) -0.42 17 >549 360	M18AHS 186/179
BCLL 0.0	Rep Stress Incr YES	WB 0.54	Horz(CT) 0.06 13 n/a n/a	
BCDL 5.0	Code IRC2021/TPI2014	Matrix-S		Weight: 100 lb FT = 20%F, 11%E

**BRACING-**

TOP CHORD

**BOT CHORD** 

19-5-8 19-5-8

LUMBER-TOP CHORD

2x4 SP No 1(flat) BOT CHORD 2x4 SP 2400F 2.0E(flat)

WFBS 2x4 SP No.3(flat)

REACTIONS. (size) 22=0-3-0, 13=0-3-8

Max Grav 22=1050(LC 1), 13=1050(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown. 2-3=-1958/0, 3-4=-3238/0, 4-5=-4126/0, 5-6=-4126/0, 6-7=-4036/0, 7-8=-4036/0, TOP CHORD

8-9=-3250/0. 9-11=-1955/0

21-22=0/1139, 19-21=0/2740, 18-19=0/3741, 17-18=0/4126, 16-17=0/4126, 15-16=0/3740. BOT CHORD 14-15=0/2740, 13-14=0/1139

 $2\text{-}22\text{-}1514/0,\ 2\text{-}21\text{=}0/1138,\ 3\text{-}21\text{=}-1088/0,\ 3\text{-}19\text{=}0/693,\ 4\text{-}19\text{=}-699/0,\ 4\text{-}18\text{=}0/811,\ 3\text{-}21\text{=}-1088/0,\ 3\text{-}19\text{=}0/693,\ 4\text{-}19\text{=}-699/0,\ 4\text{-}18\text{=}0/811,\ 3\text{-}21\text{=}-1088/0,\ 3\text{-}19\text{=}0/693,\ 4\text{-}19\text{=}-699/0,\ 4\text{-}18\text{=}0/811,\ 3\text{-}21\text{=}-1088/0,\ 3\text{-}19\text{=}0/693,\ 4\text{-}19\text{=}-699/0,\ 4\text{-}18\text{=}0/811,\ 3\text{-}21\text{=}-1088/0,\ 3\text{-}21\text$ WFBS

5-18=-364/0, 11-13=-1514/0, 11-14=0/1134, 9-14=-1092/0, 9-15=0/710, 8-15=-682/0,

8-16=0/402, 6-16=-593/276

### NOTES-

- 1) Unbalanced floor live loads have been considered for this design.
- 2) All plates are MT20 plates unless otherwise indicated.
- 3) All plates are 3x4 MT20 unless otherwise indicated.
- 4) Plates checked for a plus or minus 1 degree rotation about its center.
- 5) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.





Job	Truss	Truss Type	Qty	Ply	Lot 65 Magnolia Hills
					175971137
251447-B	F05	FLOOR	2	1	
					Job Reference (optional)

25.3.0 s Aug 20 2025 MiTek Industries, Inc. Thu Aug 28 07:05:32 2025 Page 1 ID:3YJEg\_u8zX16RsP?VvW\_V6zd0wB-W8xHZNhuGdO6Pyf2OJ3018L\_vllGvsyCLi9CtkyjOTn


Structural wood sheathing directly applied or 6-0-0 oc purlins,


Rigid ceiling directly applied or 10-0-0 oc bracing, Except:

except end verticals.

2-2-0 oc bracing: 14-15.

0-1-8





'				
Plate Offsets (X,Y)	Plate Offsets (X,Y) [4:0-1-8,Edge], [10:0-1-8,Edge], [11:0-1-8,Edge], [14:0-1-8,Edge], [19:0-1-8,Edge], [20:0-1-8,0-1-0], [21:0-1-8,0-1-0]			
LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) I/defl L/d	PLATES GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.47	Vert(LL) -0.25 13-14 >813 480	MT20 244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.97	Vert(CT) -0.33 13-14 >619 360	
BCLL 0.0	Rep Stress Incr YES	WB 0.45	Horz(CT) 0.06 11 n/a n/a	
BCDL 5.0	Code IRC2021/TPI2014	Matrix-S		Weight: 90 lb FT = 20%F, 11%E

**BRACING-**

TOP CHORD

BOT CHORD

17-3-0

LUMBER-TOP CHORD

2x4 SP 2400F 2.0E(flat) 2x4 SP No.1(flat)

BOT CHORD

2x4 SP No.3(flat) WFBS

REACTIONS.

(size) 11=0-3-0, 19=0-3-8

Max Grav 11=923(LC 1), 19=923(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

2-3=-1755/0, 3-4=-2785/0, 4-5=-3224/0, 5-6=-3224/0, 6-7=-2783/0, 7-9=-1755/0 TOP CHORD

**BOT CHORD** 18-19=0/1085, 16-18=0/2389, 15-16=0/3224, 14-15=0/3224, 13-14=0/3116, 12-13=0/2406,

11-12=0/1080

WFBS 9-11=-1381/0, 9-12=0/940, 7-12=-905/0, 7-13=0/525, 6-13=-462/0, 2-19=-1388/0,

2-18=0/931, 3-18=-882/0, 3-16=0/609, 4-16=-760/0, 6-14=-154/521, 5-14=-267/9

### NOTES-

- 1) Unbalanced floor live loads have been considered for this design.
- 2) All plates are 3x4 MT20 unless otherwise indicated.
- 3) Plates checked for a plus or minus 1 degree rotation about its center.
- 4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.





Job	Truss	Truss Type	Qty	Ply	Lot 65 Magnolia Hills
051117 D	F07	_			175971138
251447-B	F07	Floor	ь	1	
					Job Reference (optional)

25.3.0 s Aug 20 2025 MiTek Industries, Inc. Thu Aug 28 07:05:33 2025 Page 1 ID:3YJEg\_u8zX16RsP?VvW\_V6zd0wB-?KVfmjiW1wWz16EEy0aFaLtAb9ACeK5LaMumPByjOTm


Structural wood sheathing directly applied or 6-0-0 oc purlins,

Rigid ceiling directly applied or 10-0-0 oc bracing.

except end verticals.



 $0_1 1_1 8$ Scale = 1:23.0



	1		13-8-0	1	
			13-8-0		
ite O	Offsets (X,Y)	[5:0-1-8,Edge], [13:0-1-8,Edge]			
					=

LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) I/defl L/d	PLATES GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.41	Vert(LL) -0.11 11-12 >999 480	MT20 244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.67	Vert(CT) -0.14 11-12 >999 360	
BCLL 0.0	Rep Stress Incr YES	WB 0.33	Horz(CT) 0.03 9 n/a n/a	
BCDL 5.0	Code IRC2021/TPI2014	Matrix-S		Weight: 72 lb $FT = 20\%F$ , 11%E

**BRACING-**TOP CHORD

BOT CHORD

LUMBER-

Plate

TOP CHORD 2x4 SP No.1(flat) 2x4 SP No.1(flat)

**BOT CHORD** 

WFBS 2x4 SP No.3(flat)

REACTIONS. (size) 15=0-3-0, 9=0-3-8

Max Grav 15=732(LC 1), 9=732(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

2-3=-1252/0, 3-4=-2011/0, 4-5=-2011/0, 5-6=-1901/0, 6-7=-1266/0 TOP CHORD

14-15=0/781, 13-14=0/1713, 12-13=0/2011, 11-12=0/2011, 10-11=0/1733, 9-10=0/775 **BOT CHORD WEBS** 2-15=-1038/0, 2-14=0/654, 3-14=-641/0, 3-13=0/561, 7-9=-1029/0, 7-10=0/684,

6-10=-649/0, 6-11=0/309, 5-11=-328/45

### NOTES-

- 1) Unbalanced floor live loads have been considered for this design.
- 2) All plates are 3x4 MT20 unless otherwise indicated.
- 3) Plates checked for a plus or minus 1 degree rotation about its center.
- 4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.





Job	Truss	Truss Type	Qty	Ply	Lot 65 Magnolia Hills
					175971139
251447-B	F08	Floor	1	1	
					Job Reference (optional)

Fayetteville, NC - 28314, Comtech, Inc.


25.3.0 s Aug 20 2025 MiTek Industries, Inc. Thu Aug 28 07:05:33 2025 Page 1 ID:3YJEg\_u8zX16RsP?VvW\_V6zd0wB-?KVfmjiW1wWz16EEy0aFaLtDJ9FxeNNLaMumPByjOTm


Structural wood sheathing directly applied or 6-0-0 oc purlins,

Rigid ceiling directly applied or 10-0-0 oc bracing.

except end verticals.

0-1-8





10-1-0 Plate Offsets (X,Y)-- [3:0-1-8,Edge], [4:0-1-8,Edge]

	[			
LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) I/defl L/d	PLATES GRIP
TCLL 40.0	Plate Grip DOL 1.00	TC 0.24	Vert(LL) -0.05 10-11 >999 480	MT20 244/190
TCDL 10.0	Lumber DOL 1.00	BC 0.37	Vert(CT) -0.05 10 >999 360	
BCLL 0.0	Rep Stress Incr YES	WB 0.18	Horz(CT) 0.01 7 n/a n/a	
BCDL 5.0	Code IRC2021/TPI2014	Matrix-S		Weight: 54 lb FT = 20%F, 11%E

**BRACING-**TOP CHORD

BOT CHORD

LUMBER-

TOP CHORD 2x4 SP No.1(flat) BOT CHORD 2x4 SP No.1(flat)

WFBS 2x4 SP No.3(flat)

REACTIONS. (size) 12=0-3-0, 7=0-3-8 Max Grav 12=535(LC 1), 7=535(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-832/0, 3-4=-1090/0, 4-5=-832/0

**BOT CHORD** 11-12=0/561, 10-11=0/1090, 9-10=0/1090, 8-9=0/1090, 7-8=0/561 **WEBS** 2-12=-744/0, 2-11=0/377, 3-11=-384/0, 5-7=-744/0, 5-8=0/377, 4-8=-384/0

### NOTES-

- 1) Unbalanced floor live loads have been considered for this design.
- 2) Plates checked for a plus or minus 1 degree rotation about its center.
- 3) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.





### Symbols

## PLATE LOCATION AND ORIENTATION



offsets are indicated and fully embed teeth Center plate on joint unless x, y Apply plates to both sides of truss Dimensions are in ft-in-sixteenths



edge of truss. plates 0- 1/16" from outside For 4 x 2 orientation, locate

connector plates. required direction of slots in This symbol indicates the

\* Plate location details available in MiTek software or upon request

### PLATE SIZE

to slots. Second dimension is the length parallel to slots. width measured perpendicular The first dimension is the plate

## LATERAL BRACING LOCATION



by text in the bracing section of the output. Use T or I bracing if indicated. ndicated by symbol shown and/or

### **BEARING**



Min size shown is for crushing only number/letter where bearings occur reaction section indicates joint (supports) occur. Icons vary but Indicates location where bearings

### Industry Standards:

National Design Specification for Metal Plate Connected Wood Trusses Installing, Restraining & Bracing of Metal Guide to Good Practice for Handling, Building Component Safety Information, Design Standard for Bracing. Plate Connected Wood Truss Construction.

DSB-22: ANSI/TPI1:

## Numbering System



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

# Product Code Approvals

ICC-ES Reports:

ESR-1988, ESR-2362, ESR-2685, ESR-3282 ESR-4722, ESL-1388

# Design General Notes

truss unless otherwise shown Trusses are designed for wind loads in the plane of the

established by others section 6.3 These truss designs rely on lumber values Lumber design values are in accordance with ANSI/TPI 1

© 2023 MiTek® All Rights Reserved

## MiTek



MiTek Engineering Reference Sheet: MII-7473 rev. 1/2/2023

# General Safety Notes

## Damage or Personal Injury Failure to Follow Could Cause Property

- Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI
- Ņ Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor I bracing should be considered.
- Never exceed the design loading shown and never stack materials on inadequately braced trusses.
- Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
- Cut members to bear tightly against each other

'n

- joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TPI 1. Place plates on each face of truss at each
- Design assumes trusses will be suitably protected from the environment in accord with ANSI/TPI 1.
- œ Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
- Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.

9

- Camber is a non-structural consideration and is the camber for dead load deflection responsibility of truss fabricator. General practice is to
- 11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
- Lumber used shall be of the species and size, and in all respects, equal to or better than that
- Top chords must be sheathed or purlins provided at spacing indicated on design.
- Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
- 15. Connections not shown are the responsibility of others
- Do not cut or alter truss member or plate without prior approval of an engineer.
- Install and load vertically unless indicated otherwise.
- Use of green or treated lumber may pose unacceptable project engineer before use. environmental, health or performance risks. Consult with
- 19. Review all portions of this design (front, back, words is not sufficient. and pictures) before use. Reviewing pictures alone
- Design assumes manufacture in accordance with ANSI/TPI 1 Quality Criteria.
- 21. The design does not take into account any dynamic or other loads other than those expressly stated.




9/26/2025 Input by: Neal Baggett

Job Name: 65 MAGNOLIA HILLS Project #

1.750" X 24.000" **Kerto-S LVL** 3-Ply - PASSED FB1

evel: Level





Const

0

Wind

Page 1 of 17

Member Information

Type: Plies: 3 Moisture Condition: Dry Deflection LL: 480 Deflection TL: 360 Importance: Normal - II

Application: Design Method: ASD **Building Code: IBC/IRC 2015** Load Sharing: Yes Deck: Not Checked

Reactions UNPATTERNED Ib (Uplift) Brg Direction Live Dead Snow 112 7018 5324 Vertical 1

0 2 Vertical 112 5588 3893 0 0

### Analysis Results

Temperature:

Analysis	Actual	Location	Allowed	Capacity	Comb.	Case
Moment	65847 ft-lb	11' 1/4"	131295 ft-lb	50%	D+S	L
Unbraced	65847 ft-lb	11' 1/4"	66073 ft-lb	100%	D+S	L
Shear	9830 lb	2'3"	30912 lb	32%	D+S	L
LL Defl inch	0.228 (L/1158)	11'1"	0.549 (L/480)	41%	S	L
TL Defl inch	0.530 (L/498)	11'1 1/4"	0.733 (L/360)	72%	D+S	L

### **Bearings**

Bearing Length Dir. Cap. React D/L lb Total Ld. Case Ld. Comb. 7018 / 5324 D+S 1-SPF 3.000" Vert 12342 L End Grain 5588 / 3893 9480 L D+S 2 - SPF 3.000" Vert End Grain

### **Design Notes**

- 1 Provide support to prevent lateral movement and rotation at the end bearings.
- 2 Fasten all plies using 3 rows of 10d Box nails (.128x3") at 12" o.c. Maximum end distance not to exceed 6". Nail from both sides.
- 3 Refer to last page of calculations for fasteners required for specified loads.
- 4 Girders are designed to be supported on bottom edge only and across their full width.
- 5 Top loads must be supported equally by all plies.

Temp <= 100°F

- 6 Top must be laterally braced at a maximum of 3'11 15/16" o.c.
- 7 Bottom must be laterally braced at end bearings.
- 8 Lateral slenderness ratio based on single ply width.

ID	Load Type	Location	Trib Width	Side	Dead 0.9	Live 1	Snow 1.15	Wind 1.6	Const. 1.25	Comments
1	Uniform			Тор	120 PLF	0 PLF	0 PLF	0 PLF	0 PLF	WALL
2	Tie-In Far	0-0-0 to 22-4-0	0-3-0	Far Face	15 PSF	40 PSF	0 PSF	0 PSF	0 PSF	FLOOR LOADING
2	Tie-In Near	0-0-0 to 22-4-0	0-0-0	Тор	15 PSF	40 PSF	0 PSF	0 PSF	0 PSF	FLOOR LOADING
3	Part. Uniform	0-0-0 to 14-11-0		Тор	392 PLF	0 PLF	392 PLF	0 PLF	0 PLF	ATRUSSES
4	Part. Uniform	0-0-0 to 17-9-0		Near Face	92 PLF	0 PLF	92 PLF	0 PLF	0 PLF	P TRUSSES

Continued on page 2...

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

- Dry service conditions, unless noted otherwise
   LVL not to be treated with fire retardant or corrosive
- Handling & Installation
- LVL beams must not be cut or drilled Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code
- approvals

  Damaged Beams must not be used
- Design assumes top edge is laterally restrained
  Provide lateral support at bearing points to avoid
  lateral displacement and rotation
- - This design is valid until 2/28/2028

**Manufacturer Info** 6. For flat roofs provide proper drainage to prevent ponding

Metsä Wood 301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851 (800) 622-5850 www.metsawood.com/us








9/26/2025 Input by: Neal Baggett

Project #:

1.750" X 24.000" 3-Ply - PASSED **Kerto-S LVL** FB<sub>1</sub>

\_evel: Level

Job Name: 65 MAGNOLIA HILLS





5 1/4"

Page 2 of 17

.Continued from page 1

ID	Load Type	Location	Trib Width	Side	Dead 0.9	Live 1	Snow 1.15	Wind 1.6	Const. 1.25	Comments
5	Point	16-1-0		Тор	1416 lb	0 lb	1416 lb	0 lb	0 lb	A1
	Bearing Length	0-3-8								
6	Part. Uniform	17-1-0 to 22-4-0		Тор	61 PLF	0 PLF	61 PLF	0 PLF	0 PLF	Y TRUSSES
	Self Weight				28 PLF					

NOtes
Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

- Dry service conditions, unless noted otherwise
   LVL not to be treated with fire retardant or corrosive

### Handling & Installation

- Handling & Installation

  1. IVI beams must not be cut or drilled

  2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals

  3. Damaged Beams must not be used

  4. Design assumes top edge is laterally restrained

  5. Provide lateral support at bearing points to avoid lateral displacement and rotation
- 6. For flat roofs provide proper drainage to prevent ponding

Metsä Wood 301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851 (800) 622-5850 www.metsawood.com/us

Manufacturer Info

Comtech, Inc. 1001 S. Reilly Road, Suite #639 Fayetteville, NC USA 28314 910-864-TRUS



This design is valid until 2/28/2028



9/26/2025 Input by: Neal Baggett

Job Name: 65 MAGNOLIA HILLS


Project #:

**Kerto-S LVL** FB1

1.750" X 24.000"

3-Ply - PASSED

Level: Level





Page 3 of 17

### Multi-Ply Analysis

Fasten all plies using 3 rows of 10d Box nails (.128x3") at 12" o.c.. Nail from both sides. Maximum end distance not to exceed

Capacity	43.4 %	
Load	122.7 PLF	
Yield Limit per Foot	282.4 PLF	
Yield Limit per Fastener	94.1 lb.	
См	1	
Yield Mode	IV	
Edge Distance	1 1/2"	
Min. End Distance	3"	
Load Combination	D+S	
Duration Factor	1.15	

### Notes

NOtes
Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

- Dry service conditions, unless noted otherwise
   LVL not to be treated with fire retardant or corrosive

### Handling & Installation

- L. UVL beams must not be cut or drilled
   Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals
   Damaged Beams must not be used
- Danaged Beams must not be used
  Design assumes top edge is laterally restrained
  Provide lateral support at bearing points to avoid
  lateral displacement and rotation

For flat roofs provide proper drainage to prevent ponding

This design is valid until 2/28/2028

Metsä Wood 301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851 (800) 622-5850

www.metsawood.com/us

Manufacturer Info





9/26/2025 Input by: Neal Baggett

Job Name: 65 MAGNOLIA HILLS

Project #:

1.750" X 9.250" 2-Ply - PASSED Kerto-S LVL DB<sub>2</sub>

Application:

Design Method:

**Building Code:** 

Load Sharing:

Deck:


ASD

No

**IBC/IRC 2015** 

Not Checked

Level: Level





Page 4 of 17

Member Information

Type: Plies: 2 Moisture Condition: Dry Deflection LL: 480 Deflection TL: 360 Importance: Normal - II

Temperature: Temp <= 100°F Reactions UNPATTERNED Ib (Uplift)

Brg	Direction	Live	Dead	Snow	Wind	Const
1	Vertical	2696	922	0	0	0
2	Vertical	2696	922	0	0	0

### Analysis Results

Analysis	Actual	Location	Allowed	Capacity	Comb.	Case
Moment	5296 ft-lb	3'3 1/2"	12542 ft-lb	42%	D+L	L
Unbraced	5296 ft-lb	3'3 1/2"	9872 ft-lb	54%	D+L	L
Shear	2496 lb	1' 1/4"	6907 lb	36%	D+L	L
LL Defl inch	0.073 (L/1016)	3'3 1/2"	0.155 (L/480)	47%	L	L
TL Defl inch	0.098 (L/757)	3'3 1/2"	0.207 (L/360)	48%	D+L	L

### **Bearings**

Bearing	Length	Dir.	Cap. F	React D/L lb	Total	Ld. Case	Ld. Comb.
1 - SPF End Grain	3.000"	Vert	41%	922 / 2696	3618	L	D+L
2 - SPF End Grain	3.000"	Vert	41%	922 / 2696	3618	L	D+L

### **Design Notes**

- 1 Provide support to prevent lateral movement and rotation at the end bearings.
- 2 Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c. Maximum end distance not
- 3 Refer to last page of calculations for fasteners required for specified loads.
- 4 Girders are designed to be supported on bottom edge only and across their full width.
- 5 Top loads must be supported equally by all plies.
- 6 Top must be laterally braced at end bearings.
- 7 Bottom must be laterally braced at end bearings.
- 8 Lateral slenderness ratio based on single ply width

0 241011	ai ololiaolillood lallo badda oli o									
ID	Load Type	Location	Trib Width	Side	Dead 0.9	Live 1	Snow 1.15	Wind 1.6	Const. 1.25	Comments
1	Uniform			Top	273 PLF	819 PI F	0 PI F	0 PI F	0 PI F	F01

Self Weight 7 PI F

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

- Dry service conditions, unless noted otherwise
   LVL not to be treated with fire retardant or corrosive
- Handling & Installation
- LVL beams must not be cut or drilled Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code
- approvals

  Damaged Beams must not be used
- Design assumes top edge is laterally restrained
  Provide lateral support at bearing points to avoid
  lateral displacement and rotation
- 6. For flat roofs provide proper drainage to prevent ponding

301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851 (800) 622-5850 www.metsawood.com/us

**Manufacturer Info** 

Comtech, Inc. 1001 S. Reilly Road, Suite #639 Fayetteville, NC USA 28314 910-864-TRUS



This design is valid until 2/28/2028

isDesign

Client: Project: Address:

9/26/2025 Input by: Neal Baggett

Job Name: 65 MAGNOLIA HILLS


Project #:

**Kerto-S LVL** DB<sub>2</sub>

1.750" X 9.250"

2-Ply - PASSED

Level: Level





Page 5 of 17

### Multi-Ply Analysis

Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c.. Maximum end distance not to exceed 6".

	•	
Capacity	0.0 %	
Load	0.0 PLF	
Yield Limit per Foot	163.7 PLF	
Yield Limit per Fastener	81.9 lb.	
См	1	
Yield Mode	IV	
Edge Distance	1 1/2"	
Min. End Distance	3"	
Load Combination		
Duration Factor	1.00	

### Notes

NOtes
Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

- Dry service conditions, unless noted otherwise
   LVL not to be treated with fire retardant or corrosive

### Handling & Installation

- Handling & Installation

  1. UVI beams must not be cut or drilled

  2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals

  3. Damaged Beams must not be used

  4. Design assumes top edge is laterally restrained

  5. Provide lateral support at bearing points to avoid lateral displacement and rotation

For flat roofs provide proper drainage to prevent ponding

This design is valid until 2/28/2028

Metsä Wood 301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851 (800) 622-5850 www.metsawood.com/us

Manufacturer Info








9/26/2025 Input by: Neal Baggett

Job Name: 65 MAGNOLIA HILLS Project #:

1.750" X 9.250" 2-Ply - PASSED **Kerto-S LVL** HDR1

Level: Level





Page 6 of 17

### Member Information

Type:	Giraer
Plies:	2
Moisture Condition:	Dry
Deflection LL:	480
Deflection TL:	360
Importance:	Normal - II
Temperature:	Temp <= 100°F

Application: Design Method: ASD **Building Code: IBC/IRC 2015** Load Sharing: No Deck: Not Checked

### Reactions UNPATTERNED Ib (Uplift)

Brg	Direction	Live	Dead	Snow	Wind	Const
1	Vertical	932	1926	1240	0	0
2	Vertical	932	1926	1240	0	0

### Analysis Results

Analysis	Actual	Location	Allowed	Capacity	Comb.	Case
Moment	4613 ft-lb	2'11 1/2"	14423 ft-lb	32%	D+0.75(L+S)	L
Unbraced	4613 ft-lb	2'11 1/2"	11027 ft-lb	42%	D+0.75(L+S)	L.
Shear	2328 lb	4'10 3/4"	7943 lb	29%	D+0.75(L+S)	L
LL Defl inch	0.033 (L/2026)	2'11 1/2"	0.139 (L/480)	24%	0.75(L+S)	L
TL Defl inch	0.072 (L/928)	2'11 1/2"	0.185 (L/360)	39%	D+0.75(L+S)	L

### **Bearings**

Bearing L	ength	Dir.	Cap. F	React D/L lb	Total	Ld. Case	Ld. Comb.
1 - SPF 3. End Grain	.000"	Vert	40%	1926 / 1629	3555	L	D+0.75(L+S)
2 - SPF 3. End Grain	.000"	Vert	40%	1926 / 1629	3555	L	D+0.75(L+S)

### **Design Notes**

- 1 Provide support to prevent lateral movement and rotation at the end bearings.
- 2 Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c. Maximum end distance not
- 3 Refer to last page of calculations for fasteners required for specified loads.
- 4 Girders are designed to be supported on bottom edge only and across their full width.
- 5 Top loads must be supported equally by all plies.
- 6 Top must be laterally braced at end bearings.
- 7 Bottom must be laterally braced at end bearings.
- 8 Lateral slenderness ratio based on single ply width.

ID	Load Type	Location	Trib Width	Side	Dead 0.9	Live 1	Snow 1.15	Wind 1.6	Const. 1.25	Comments
1	Uniform			Тор	120 PLF	0 PLF	0 PLF	0 PLF	0 PLF	WALL
2	Uniform			Тор	105 PLF	315 PLF	0 PLF	0 PLF	0 PLF	FLOOR TRUSSES
3	Uniform			Тор	419 PLF	0 PLF	419 PLF	0 PLF	0 PLF	ROOF TRUSSES
	Self Weight				7 PLF					

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

Dry service conditions, unless noted otherwise
 LVL not to be treated with fire retardant or corrosive

### Handling & Installation

- LVL beams must not be cut or drilled
  Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals

  2 Damaged Beams must not be used
- Design assumes top edge is laterally restrained
  Provide lateral support at bearing points to avoid
  lateral displacement and rotation
- 6. For flat roofs provide proper drainage to prevent ponding

This design is valid until 2/28/2028

301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851 (800) 622-5850

www.metsawood.com/us

Manufacturer Info





isDesign

Client: Project: Address:

9/26/2025 Input by:

Neal Baggett Job Name: 65 MAGNOLIA HILLS


Project #:

**Kerto-S LVL** HDR1

1.750" X 9.250"

2-Ply - PASSED

Level: Level





Page 7 of 17

### Multi-Ply Analysis

Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c.. Maximum end distance not to exceed 6".

	•	
Capacity	0.0 %	
Load	0.0 PLF	
Yield Limit per Foot	163.7 PLF	
Yield Limit per Fastener	81.9 lb.	
См	1	
Yield Mode	IV	
Edge Distance	1 1/2"	
Min. End Distance	3"	
Load Combination		
Duration Factor	1.00	

### Notes

NOtes
Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

- Dry service conditions, unless noted otherwise
   LVL not to be treated with fire retardant or corrosive

### Handling & Installation

- Handling & Installation

  1. UVI beams must not be cut or drilled

  2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals

  3. Damaged Beams must not be used

  4. Design assumes top edge is laterally restrained

  5. Provide lateral support at bearing points to avoid lateral displacement and rotation


For flat roofs provide proper drainage to prevent ponding

This design is valid until 2/28/2028

Metsä Wood 301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851 (800) 622-5850 www.metsawood.com/us


Manufacturer Info





This design is valid until 2/28/2028

соттесн






Date: 9/26/2025 Input by: Neal Baggett

Job Name: 65 MAGNOLIA HILLS Project #:

1.750" X 9.250" 2-Ply - PASSED **Kerto-S LVL** HDR2

Level: Level





Page 10 of 17

Member Information

Type: Plies: 2 Moisture Condition: Dry Deflection LL: 480 Deflection TL: 360 Importance:

Normal - II Temperature: Temp <= 100°F

Application: Design Method: ASD **Building Code: IBC/IRC 2015** 

Load Sharing: No

Deck: Not Checked Reactions UNPATTERNED Ib (Uplift)

Brg	Direction	Live	Dead	Snow	Wind	Const
1	Vertical	902	2097	1379	0	0
2	Vertical	902	2097	1379	0	0

### Analysis Results

Analysis	Actual	Location	Allowed	Capacity	Comb. Cas	se
Moment	5574 ft-lb	3'3 1/2"	14423 ft-lb	39%	D+0.75(L+S) L	
Unbraced	5574 ft-lb	3'3 1/2"	10370 ft-lb	54%	D+0.75(L+S) L	
Shear	2627 lb	1' 1/4"	7943 lb	33%	D+0.75(L+S) L	
LL Defl inch	0.047 (L/1601)	3'3 1/2"	0.155 (L/480)	30%	0.75(L+S) L	
TL Defl inch	0.104 (L/719)	3'3 1/2"	0.207 (L/360)	50%	D+0.75(L+S) L	

### **Bearings**

Bearing Length Dir. Cap. React D/L lb Total Ld. Case Ld. Comb. D+0.75(L+S) 1 - SPF 3.000" Vert 2097 / 1711 3808 L End

Grain

2097 / 1711 3808 L D+0.75(L+S) 2 - SPF 3.000" Vert End Grain

### **Design Notes**

- 1 Provide support to prevent lateral movement and rotation at the end bearings.
- 2 Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c. Maximum end distance not
- 3 Refer to last page of calculations for fasteners required for specified loads.
- 4 Girders are designed to be supported on bottom edge only and across their full width.
- 5 Top loads must be supported equally by all plies.
- 6 Top must be laterally braced at end bearings.
- 7 Bottom must be laterally braced at end bearings.

	8 Lateral slenderness ratio based on single ply width.									
I	ID	Load Type	Location	Trib Width	Side	Dead 0.9	Live 1	Snow 1.15	Wind 1.6	Const. 1.25
I	1	Uniform			Тор	120 PLF	0 PLF	0 PLF	0 PLF	0 PLF

2 Uniform Top 91 PI F 274 PI F 0 PI F 0 PI F 0 PI F FLOOR TRUSSES 0 PLF 3 Uniform 419 PLF 0 PLF 419 PLF 0 PLF ROOF TRUSSES Top

> Self Weight 7 PI F

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

Dry service conditions, unless noted otherwise
 LVL not to be treated with fire retardant or corrosive

### Handling & Installation

- LVL beams must not be cut or drilled Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code
- Damaged Beams must not be used
- Design assumes top edge is laterally restrained
  Provide lateral support at bearing points to avoid
  lateral displacement and rotation
- 6. For flat roofs provide proper drainage to prevent ponding

301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851 (800) 622-5850 www.metsawood.com/us

**Manufacturer Info** 

Comtech, Inc. 1001 S. Reilly Road, Suite #639 Fayetteville, NC USA 28314 910-864-TRUS

Comments

WALL



This design is valid until 2/28/2028

isDesign

Client: Project: Address:

9/26/2025 Input by:

Neal Baggett Job Name: 65 MAGNOLIA HILLS


Project #:

**Kerto-S LVL** HDR2

1.750" X 9.250"

2-Ply - PASSED

Level: Level





Page 11 of 17

### Multi-Ply Analysis

Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c.. Maximum end distance not to exceed 6".

	•	
Capacity	0.0 %	
Load	0.0 PLF	
Yield Limit per Foot	163.7 PLF	
Yield Limit per Fastener	81.9 lb.	
См	1	
Yield Mode	IV	
Edge Distance	1 1/2"	
Min. End Distance	3"	
Load Combination		
Duration Factor	1.00	

### Notes

NOtes
Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

- Dry service conditions, unless noted otherwise
   LVL not to be treated with fire retardant or corrosive

### Handling & Installation

- Handling & Installation

  1. UVI beams must not be cut or drilled

  2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals

  3. Damaged Beams must not be used

  4. Design assumes top edge is laterally restrained

  5. Provide lateral support at bearing points to avoid lateral displacement and rotation

For flat roofs provide proper drainage to prevent ponding

This design is valid until 2/28/2028

Metsä Wood 301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851 (800) 622-5850 www.metsawood.com/us

Manufacturer Info








9/26/2025 Input by:

Neal Baggett Job Name: 65 MAGNOLIA HILLS

Project #:

2-Ply - PASSED **Kerto-S LVL** 1.750" X 9.250" HDR3

Level: Level





Page 12 of 17

### Member Information

Type:	Girder
Plies:	2
Moisture Condition:	Dry
Deflection LL:	480
Deflection TL:	360
Importance:	Normal - II
Temperature:	Temp <= 100°F

Application: Design Method: ASD **Building Code: IBC/IRC 2015** Load Sharing: No Deck: Not Checked

Reactions UNPATTERNED Ib (Uplift) Brg Live Snow Wind Direction Const 0 1472 1451 0 Vertical 0 2 Vertical 0 871 850 0 0

### Analysis Results

Analysis	Actual	Location	Allowed	Capacity	Comb.	Case
Moment	4533 ft-lb	2'9 1/2"	14423 ft-lb	31%	D+S	L
Unbraced	4533 ft-lb	2'9 1/2"	11027 ft-lb	41%	D+S	L
Shear	2462 lb	1' 1/4"	7943 lb	31%	D+S	L
LL Defl inch	0.031 (L/2162)	2'9 1/2"	0.139 (L/480)	22%	S	L
TL Defl inch	0.062 (L/1074)	2'9 1/2"	0.185 (L/360)	34%	D+S	L

### **Bearings**

Bearing	Length	Dir.	Сар.	React D/L lb	Total	Ld. Case	Ld. Comb.
1 - SPF End Grain	3.000"	Vert	33%	1472 / 1451	2923	L	D+S
2 - SPF End Grain	3.000"	Vert	20%	871 / 850	1721	L	D+S

### **Design Notes**

- 1 Provide support to prevent lateral movement and rotation at the end bearings.
- 2 Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c. Maximum end distance not
- 3 Refer to last page of calculations for fasteners required for specified loads.
- 4 Girders are designed to be supported on bottom edge only and across their full width.
- 5 Top loads must be supported equally by all plies.
- 6 Top must be laterally braced at end bearings.
- 7 Bottom must be laterally braced at end bearings.
- 8 Lateral slenderness ratio based on single ply width.

	ID	Load Type	Location	Trib Width	Side	Dead 0.9	Live 1	Snow 1.15	Wind 1.6	Const. 1.25	Comments
	1	Point	0-9-8		Тор	763 lb	0 lb	763 lb	0 lb	0 lb	A2
		Bearing Length	0-3-8								
	2	Point	2-9-8		Тор	1416 lb	0 lb	1416 lb	0 lb	0 lb	A1
		Bearing Length	0-3-8								
	3	Point	4-9-8		Тор	122 lb	0 lb	122 lb	0 lb	0 lb	YA2
		Bearing Length	0-3-8								
ı		Self Weight				7 PLF					

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

- Dry service conditions, unless noted otherwise
   LVL not to be treated with fire retardant or corrosive
- Handling & Installation
  - LVL beams must not be cut or drilled Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code
  - approvals

    Damaged Beams must not be used
  - Design assumes top edge is laterally restrained
    Provide lateral support at bearing points to avoid
    lateral displacement and rotation
- - This design is valid until 2/28/2028

Manufacturer Info 6. For flat roofs provide proper drainage to prevent ponding

301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851 (800) 622-5850 www.metsawood.com/us





isDesign

Client: Project: Address:

9/26/2025 Input by:

Neal Baggett Job Name: 65 MAGNOLIA HILLS

Level: Level

Project #:


**Kerto-S LVL** HDR3

1.750" X 9.250"

2-Ply - PASSED



Page 13 of 17



### Multi-Ply Analysis

Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c.. Maximum end distance not to exceed 6".

, ,	•	
Capacity	0.0 %	
Load	0.0 PLF	
Yield Limit per Foot	163.7 PLF	
Yield Limit per Fastener	81.9 lb.	
См	1	
Yield Mode	IV	
Edge Distance	1 1/2"	
Min. End Distance	3"	
Load Combination		
Duration Factor	1.00	

### Notes

NOtes
Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

- Dry service conditions, unless noted otherwise
   LVL not to be treated with fire retardant or corrosive

### Handling & Installation

- Handling & Installation

  1. UVI beams must not be cut or drilled

  2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals

  3. Damaged Beams must not be used

  4. Design assumes top edge is laterally restrained

  5. Provide lateral support at bearing points to avoid lateral displacement and rotation

- For flat roofs provide proper drainage to prevent ponding

This design is valid until 2/28/2028

Metsä Wood 301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851 (800) 622-5850 www.metsawood.com/us

Manufacturer Info





9/26/2025

Input by: Neal Baggett Job Name: 65 MAGNOLIA HILLS

Project #:

1.750" X 11.875" 2-Ply - PASSED **Kerto-S LVL GDH** 

Application:


Design Method:

**Building Code:** 

Load Sharing:

Deck:

Level: Level



Floor

ASD

No

**IBC/IRC 2015** 

Not Checked



3 1/2'

Page 14 of 17

### Member Information

Type:	Girder
Plies:	2
Moisture Condition:	Dry
Deflection LL:	480
Deflection TL:	360
Importance:	Normal -
	_

- II

Temperature: Temp <= 100°F

### Reactions UNPATTERNED Ib (Uplift)

Brg	Direction	Live	Dead	Snow	Wind	Const
1	Vertical	0	995	539	0	0
2	Vertical	0	995	539	0	0

### **Bearings**

				eact D/L lb	Total	Ld. Case	Ld. Comb
	3.500"	Vert	15%	995 / 539	1534	L	D+S
End Grain							
2 - SPF End Grain	3.500"	Vert	15%	995 / 539	1534	L	D+S

### Analysis Results

Analysis	Actual	Location	Allowed	Capacity	Comb.	Case
Moment	6108 ft-lb	8'5"	22897 ft-lb	27%	D+S	L
Unbraced	6108 ft-lb	8'5"	6109 ft-lb	100%	D+S	L
Shear	1300 lb	1'3 3/8"	10197 lb	13%	D+S	L
LL Defl inch	0.112 (L/1755)	8'5 1/16"	0.409 (L/480)	27%	S	L
TL Defl inch	0.319 (L/617)	8'5 1/16"	0.546 (L/360)	58%	D+S	L

### **Design Notes**

- 1 Provide support to prevent lateral movement and rotation at the end bearings.
- 2 Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c. Maximum end distance not
- 3 Refer to last page of calculations for fasteners required for specified loads.
- 4 Girders are designed to be supported on bottom edge only and across their full width.
- 5 Top loads must be supported equally by all plies.
- 6 Top must be laterally braced at a maximum of 16'3 3/4" o.c.
- 7 Bottom must be laterally braced at end bearings.
- 8 Lateral slenderness ratio based on single ply width.

o Laterar ordinat	o zatorar cionacinicos ratio sacoa circingio pi) matri									
ID	Load Type	Location	Trib Width	Side	Dead 0.9	Live 1	Snow 1.15	Wind 1.6	Const. 1.25	Comments
1	Uniform			Тор	45 PLF	0 PLF	0 PLF	0 PLF	0 PLF	WALL
2	Uniform			Тор	64 PLF	0 PLF	64 PLF	0 PLF	0 PLF	P2
	Self Weight				9 PLF					

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

- Dry service conditions, unless noted otherwise
   LVL not to be treated with fire retardant or corrosive

### Handling & Installation

LVL beams must not be cut or drilled
Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals

2 Damaged Beams must not be used

- Design assumes top edge is laterally restrained
  Provide lateral support at bearing points to avoid
  lateral displacement and rotation

6. For flat roofs provide proper drainage to prevent ponding

This design is valid until 2/28/2028

Metsä Wood 301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851 (800) 622-5850 www.metsawood.com/us

**Manufacturer Info** 





isDesign

Client: Project: Address:

9/26/2025 Input by: Neal Baggett


Job Name: 65 MAGNOLIA HILLS

Page 15 of 17

Project #:

2-Ply - PASSED **Kerto-S LVL** 1.750" X 11.875" **GDH** 

Level: Level



### Multi-Ply Analysis

Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c.. Maximum end distance not to exceed 6".

Capacity	0.0 %	
Load	0.0 PLF	
Yield Limit per Foot	163.7 PLF	
Yield Limit per Fastener	81.9 lb.	
CM	1	
Yield Mode	IV	
Edge Distance	1 1/2"	
Min. End Distance	3"	
Load Combination		
Duration Factor	1.00	

### Notes

NOtes
Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

- Dry service conditions, unless noted otherwise
   LVL not to be treated with fire retardant or corrosive

### Handling & Installation

Handling & Installation

1. UVI beams must not be cut or drilled

2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals

3. Damaged Beams must not be used

4. Design assumes top edge is laterally restrained

5. Provide lateral support at bearing points to avoid lateral displacement and rotation

For flat roofs provide proper drainage to prevent ponding

This design is valid until 2/28/2028

Manufacturer Info

Metsä Wood 301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851 (800) 622-5850 www.metsawood.com/us







Date: 9/26/2025 Input by:

Neal Baggett Job Name: 65 MAGNOLIA HILLS

Project #:

1.750" X 9.250" 2-Ply - PASSED Kerto-S LVL DB<sub>1</sub>

Application:

Design Method:

**Building Code:** 

Load Sharing:

Deck:


ASD

No

**IBC/IRC 2015** 

Not Checked

Level: Level





Page 16 of 17

### Member Information Type:

Plies: 2 Moisture Condition: Dry Deflection LL: 480 Deflection TL: 360

Importance: Normal - II Temperature: Temp <= 100°F

### Reactions UNPATTERNED Ib (Uplift)

Brg	Direction	Live	Dead	Snow	Wind	Const
1	Vertical	0	902	865	0	0
2	Vertical	0	902	865	0	0

### Analysis Results

Analysis	Actual	Location	Allowed	Capacity	Comb.	Case
Moment	4148 ft-lb	5'1 3/4"	14423 ft-lb	29%	D+S	L
Unbraced	4148 ft-lb	5'1 3/4"	7519 ft-lb	55%	D+S	L
Shear	1401 lb	1' 3/4"	7943 lb	18%	D+S	L
LL Defl inch	0.084 (L/1409)	5'1 3/4"	0.246 (L/480)	34%	S	L
TL Defl inch	0.171 (L/689)	5'1 3/4"	0.328 (L/360)	52%	D+S	L

### Bearings

Bearing	Length	Dir.	Cap. Re	act D/L lb	Total	Ld. Case	Ld. Comb.
1 - SPF End Grain	3.500"	Vert	17%	902 / 865	1766	L	D+S
2 - SPF End Grain	3.500"	Vert	17%	902 / 865	1766	L	D+S

### **Design Notes**

- 1 Provide support to prevent lateral movement and rotation at the end bearings.
- 2 Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c. Maximum end distance not
- 3 Refer to last page of calculations for fasteners required for specified loads.
- 4 Girders are designed to be supported on bottom edge only and across their full width.
- 5 Top loads must be supported equally by all plies.
- 6 Top must be laterally braced at end bearings.
- 7 Bottom must be laterally braced at end bearings.
- 8 Lateral slenderness ratio based on single ply width.

ID	Load Type	Location	Trib Width	Side	Dead 0.9	Live 1	Snow 1.15	Wind 1.6	Const. 1.25	Comments
1	Uniform			Ton	168 DI E	0 PLF	168 DI E	∩ DI E	∩ DI E	C2

Self Weight 7 PI F

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

- Dry service conditions, unless noted otherwise
   LVL not to be treated with fire retardant or corrosive

- Handling & Installation
- LVL beams must not be cut or drilled
  Refer to manufacturer's product information
  regarding installation requirements, multi-ply
  fastening details, beam strength values, and code approvals

  Damaged Beams must not be used
- Design assumes top edge is laterally restrained
  Provide lateral support at bearing points to avoid
  lateral displacement and rotation
- 6. For flat roofs provide proper drainage to prevent ponding

Metsä Wood 301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851 (800) 622-5850 www.metsawood.com/us

**Manufacturer Info** 

Comtech, Inc. 1001 S. Reilly Road, Suite #639 Fayetteville, NC USA 28314 910-864-TRUS



This design is valid until 2/28/2028

isDesign

Client: Project: Address:

9/26/2025 Input by: Neal Baggett


Job Name: 65 MAGNOLIA HILLS

Page 17 of 17

Project #:

1.750" X 9.250" 2-Ply - PASSED **Kerto-S LVL** DB<sub>1</sub>

Level: Level



### Multi-Ply Analysis

Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c.. Maximum end distance not to exceed 6".

Capacity	0.0 %	
Load	0.0 PLF	
Yield Limit per Foot	163.7 PLF	
Yield Limit per Fastener	81.9 lb.	
CM	1	
Yield Mode	IV	
Edge Distance	1 1/2"	
Min. End Distance	3"	
Load Combination		
Duration Factor	1.00	

### Notes

NOtes
Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

- Dry service conditions, unless noted otherwise
   LVL not to be treated with fire retardant or corrosive

### Handling & Installation

Handling & Installation

1. UVI beams must not be cut or drilled

2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals

3. Damaged Beams must not be used

4. Design assumes top edge is laterally restrained

5. Provide lateral support at bearing points to avoid lateral displacement and rotation

For flat roofs provide proper drainage to prevent ponding

This design is valid until 2/28/2028

(800) 622-5850 www.metsawood.com/us

Manufacturer Info Metsä Wood

301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851



