

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: EVYSE MEADOWS

INITIAL SYSTEM: ^{pump to} Approved 25% Reduction

DISTRIBUTION: P-Box

BENCHMARK: 100.0

NO. BEDROOMS: 4

SEPTIC TANK SIZE 1000

LOT 69

REPAIR: ^{pump to} Approved 25% Reduction

DISTRIBUTION P-Box

LOCATION TOP STAKE

LTAR 0.4 GPD/FT²

PUMP TANK SIZE 1000

LINE	FLAG COLOR	ELEVATION	LENGTH
------	------------	-----------	--------

Initial
545' per

1	R	97.40	90.1'
2	Y	97.20	90.1'
3	R	97.00	90.1'
4A	Y	96.80	90.1'
			40
			310.1'
4B	Y	96.80	90.1'
5	R	96.60	90.1'
6	Y	96.40	90.1'
7			90.1'
			40
			310.1'

BY M. EAKER

TYPICAL PROFILE

0-10 LS (VF, w/gt)
10-36+ silt / F₁ / M₁ /
C₁ > 34"

DATE 03/2024

THERE SHALL BE NO GRADING,
 CUTTING, LOGGING OR OTHER SOIL

DISTURBANCE IN SEPTIC AREA

HEALTH DEPARTMENT USE ONLY.

DESIGNS DO NOT GUARANTEE FUNCTIONALITY

Southeastern Soil & Environmental Associates LLC
PO Box 9321 Fayetteville, NC 28311
Mike@southeasternsoil.com
(910) 822-4540

Elyse Meadow
Preliminary Septic Evaluation

