GRAYSON



BRIARWOOD BLUFF LOT 25

PLAN ID 010123

110 VILLAGE TRAIL SUITE 215 WOODSTOCK, GA. 30188

	DRAWING INDEX
A0.0 A1.1 A2.1 A3.1 A5.1 A5.2 A6.1 A7.2-A7.3	COVER SHEET FRONT ELEVATIONS SIDE & REAR ELEVATIONS SLAB FOUNDATION FIRST FLOOR PLANS & DETAILS SECOND FLOOR PLANS & DETAILS ROOF PLANS ELECTRICAL PLANS TRIM LOCATION LAYOUTS

AREA TABULATION		
FIRST FLOOR	716	
SECOND FLOOR	780	
TOTAL	1496	
GARAGE	418	
FRONT PORCH (COVERED)	62	
REAR PATIO	120	

DATE	BY	REVISION	PAGE #
5/30/2023	AW	Prototype walk revisions - see revision sheet	A3.1, A5.1, A5.2, A7.2, A7.3, A8.1
1/24/2024	AW	Added optional side entry	ALL

PLAN REVISIONS

GOVERNMENTAL CODES & STANDARDS

HOME TO BE BUILT TO CONFORM TO ALL APPLICABLE LOCAL CODES, PRACTICES AND STANDARDS


BUILDING CODE ANALYSIS / DESIGN CRITERIA


HOME TO BE BUILT TO MEET OR EXCEED ALL LOCAL CODES AND DESIGN CRITERIA

ALL NON-MASONRY RETURNS TO BE HORIZONTAL SIDING

SEE SHEET D3 OF SDH TYPICAL DETAILS FOR SOFFIT DETAILS PER SOFFIT MATERIAL

BRIARWOOD BLUFF LOT 25







SMITH DOUGLAS HOMES QUALITY I INTEGRITY I VALUE


ELEVATIONS FRONT ELEVATION GRAYSON


SMITH DOUGLAS HOMES 110 VILLAGE TRAIL SUITE 115 WOODSTOCK, GA 30188 www.smithdouglas.com

SMITH DOUGLAS HOMES expressly reserves it's property rights in these plans and drawings. These plans and related drawings are not to be reproduced without written consent from SMITH DOUGLAS HOMES.














SMITH DOUGLAS HOMES 110 VILLAGE TRAIL SUITE 115 WOODSTOCK, GA 30188 www.smithdouglas.com

SMITH DOUGLAS HOMES expressly reserves it's property rights in these plans and drawings. These plans are drawings are not to be reproduced without writte consent from SMITH DOUGLAS HOMES.



34'-0" 12'-0" DROP 4" BELOW HOUSE SLAB RADON VENT LOC. 1'-11" DROP 4" BELOW HOUSE SLAB START AT THIS CORNER TO LAY OUT PLATES 5'-3% DROP 4" BELOW HOUSE SLAB 14'-4" 16' X 7' OHGD (R.O. 16'=3" X 7'=1 1/2") WEATHER LIP

1'-10½"

14'-0"

1'-10½"

SLAB PLAN


16'-3"

20'-0"

BRIARWOOD BLUFF LOT 25

*RADON VENT PROVIDED PER LOCAL CODE

REFER TO DETAIL 3/D1 FOR BRICK LEDGE DETAIL WHEN BRICK VENEER IS CHOSEN





SMITH DOUGLAS HOMES

FOUNDATION PLAN SLAB PLAN GRAYSON

SMITH DOUGLAS HOMES 110 VILLAGE TRAIL SUITE 115 WOODSTOCK, GA 30188 www.smithdouglas.com

SMITH DOUGLAS HOMES expressly reserves it's property rights in these plans and drawings. These plans and related drawings are not to be reproduced without writte consent from SMITH DOUGLAS HOMES.





COUNTERTOP

SECTION @ KITCHEN ISLAND KNEE WALL

4'-10½" 3'-3½"

SECTION AT STAIRS

BEDROOM 3 CLOSET




SMITH DOUGLAS HOMES 110 VILLAGE TRAIL SUITE 115 WOODSTOCK, GA 30188 www.smithdouglas.com

SMITH DOUGLAS HOMES expressly reserves it's property rights in these plans and drawings. These plans and relatedrawings are not to be reproduced without writte consent from SMITH

*RADON VENT PROVIDED PER LOCAL CODE





*RADON VENT PROVIDED PER LOCAL CODE

REFER TO MANUFACTURER'S SPECS. FOR DRAIN LOCATIONS ON DETAIL SHEETS D12, D12.1, & D12.2

SMITH DOUGLAS HOMES OUALITY I INTEGRITY I VALUE

SMITH DOUGLAS HOMES

110 VILLAGE TRAIL
SUITE 115

WOODSTOCK, GA 30188
www.mithdouglas.com

SMITH DOUGLAS HOMES expressly reserves it's property rights in these plans and drawings. These plans and related drawings are not to be eproduced without writter

PLAN ID:

PAGE NO:

AMP

AW

DATE: 10/14/25

FACADE OPT:


PLAN ID:

PLAN ID:

B


PAGE NO:

A5.2



ROOF LAYOUT "B"

SCALE: 1/8" = 1'-0"





SMITH DOUGLAS HOMES GUALITY I INTEGRITY I VALUE

ROOF PLAN
ROOF PLAN
GRAYSON

SMITH DOUGLAS HOMES 110 VILLAGE TRAIL SUITE 115 WOODSTOCK, GA 30188 www.smithdouglas.com

SMITH DOUGLAS HOMES expressly reserves it's property rights in these plans and drawings. These plans and related drawings are not to be reproduced without writte consent from SMITH DOUGLAS HOMES






FIRST FLOOR ELECTRICAL PLAN

SCALE : 1/8" = 1'-0"

ELECTRICAL LEGEND			
\$	SWITCH	φ	120V RECEPTACLE
\$3	3 WAY SWITCH	•	220V RECEPTACLE
\$4	4 WAY SWITCH	P _{GFCI}	GFCI OUTLET
-ф _к	KEYLESS	₩P GFCI	WEATHER PROOF GFCI OUTLET
Ä	WALL MOUNT FIXTURE	Pusb	USB OUTLET
Ø	CEILING FIXTURE	† _{GL}	GAS LINE
0	CEILING FIXTURE	\$	FLOOD LIGHT
	TV	X	CEILING FAN
C5	CAT 5		
₽H	TELEPHONE	≡	EXHAUST FAN
SD/C∘ ₩	SMOKE DETECTOR & CARBON MONOXIDE		ELECTRICAL WIRING
ELECTRICAL PLANS TO FOLLOW ALL LOCAL CODES			
APPRO	X. FIXTURE HGTS (MEASUR	ED FROM B	OTTOM OF FIXTURE)
BREAKFAST/DINING ROOM		63" ABOVE FINISHED FLOOR	
KITCHEN PENDANT LIGHTS		33" ABOVE COUNTER TOP	
TWO STORY FOYER FIXTURE		11'-6" FROM 1ST FLR TO BOTTOM OF LIGHT FIXTURE	
CEILING FAN		96" ABOVE FINISHED FLOOR	
FLOOI	D LIGHTS	10' MAX.	. ABOVE FIN. FLOOR

NOTE: FINAL PLACEMENT OF PHONE/CABLE T.B.D. ON SITE BY THE BUILDER




 $igotimes_{oldsymbol{\mathcal{O}}}$ smith douglas ELECTRICAL PLAN FIRST FLOOR FLOOR

SMITH DOUGLAS HOMES 110 VILLAGE TRAIL SUITE 115 WOODSTOCK, GA 30188 www.smithdouglas.com

GRAYSON






SECOND FLOOR ELECTRICAL PLAN

SCALE : 1/8" = 1'-0"

ELECTRICAL LEGEND			
\$	SWITCH	φ	120V RECEPTACLE
\$3	3 WAY SWITCH	Φ	220V RECEPTACLE
\$4	4 WAY SWITCH	P _{GFCI}	GFCI OUTLET
-ф _к	KEYLESS	₩P GFCI	WEATHER PROOF GFCI OUTLET
ΨØ	WALL MOUNT FIXTURE	Pusb	USB OUTLET
Ø	CEILING FIXTURE	† _{GL}	GAS LINE
0	CEILING FIXTURE	8	FLOOD LIGHT
TV	TV		CEILING FAN
C5 ₩	CAT 5		
₽H	TELEPHONE	▤	EXHAUST FAN
SD/C∘ ₩	SMOKE DETECTOR & CARBON MONOXIDE		ELECTRICAL WIRING
ELECTRICAL PLANS TO FOLLOW ALL LOCAL CODES			
APPROX. FIXTURE HGTS (MEASURED FROM BOTTOM OF FIXTURE)			
BREAKFAST/DINING ROOM		63" ABOVE FINISHED FLOOR	
KITCHEN PENDANT LIGHTS		33" ABOVE COUNTER TOP	
TWO STORY FOYER FIXTURE		11'-6" FROM 1ST FLR TO BOTTOM OF LIGHT FIXTURE	
CEILING FAN		96" ABOVE FINISHED FLOOR	
FLOOI	D LIGHTS	10' MAX	. ABOVE FIN. FLOOR

NOTE: FINAL PLACEMENT OF PHONE/CABLE T.B.D. ON SITE BY THE BUILDER






SMITH DOUGLAS HOMES 110 VILLAGE TRAIL SUITE 115 WOODSTOCK, GA 30188 www.smithdouglas.com

SMITH DOUGLAS HOMES expressly reserves it's oroperty rights in these plans and drawings. These plans and related drawings are not to be produced without writte consent from SMITH





TWO PIECE CROWN —

FIRST FLOOR PLAN

TRIM LAYOUT FIRST FLOOR PLAN

SCALE : 1/8" = 1'-0"

SMITH DOUGLAS HOMES

FLOOR PLAN

FLOOR PLAN

FLOOR PLAN

SMITH DOUGLAS HOMES
110 VILLAGE TRAIL
SMITE 1110

MODDSTOCK, 104


MODDSTOCK, 104

GRAYSON

GRAYSON

SMITH DOUGLAS HOMES expressly reserves it's property rights in these plans and drawings. These plans and related drawings are not to be reproduced without writte consent from SMITH DOUGLAS HOMES.





CONNECTION SPECIFICATIONS (TYP. U.N.O.)

DESCRIPTION OF BLDG. ELEMENT	3"x0.l3l" NAIL5	3"x0.120" NAILS
JOIST TO SOLE PLATE	(3) TOENAILS	(3) TOENAILS*
SOLE PL. TO JOIST/RIM OR BLK'G	NAILS @ 4" o.c.	NAILS @ 4" O.C.
STUD TO PLATE	(4) TOENAILS/ (3)END NAILS	(4) TOENAILS/ (4)END NAILS*
RIM TO TOP PLATE	TOENAILS @ 6" o.c.	TOENAILS @ 4" o.c.*
BLK'G. BTWN. JOISTS TO TOP PL.	(3) TOENAILS EA. END	(3) TOENAILS EA. END*
DOUBLE STUD	NAILS @ 16" O.C.	NAILS @ 16" O.C.
DOUBLE TOP PLATE	NAILS @ 12" o.c.	NAILS @ 8" o.c.
DOUBLE TOP PLATE LAP SPLICE	(12) NAILS IN LAPPED AREA (24" MIN.)	(15) NAILS IN LAPPED AREA (24" MIN.)
TOP PLATE LAP @ CORNERS & INTERSECTING WALLS	(3) NAILS	(3) NAILS
RAFTER/TRUSS TO TOP PLATE	(4) TOENAILS +	(4) TOENAILS +
	(I) SIMPSON H2.5T	(I) SIMPSON H2.5T
GAB, END TRUSS TO DBL, TOP PL.	TOENAILS @ 8" o.c.	TOENAILS @ 6" o.c.
R.T. w/ HEEL HT. 9 ¼" TO 12"	2xIO BLK EVERY 3RD BAY FASTENED TO DBL. TOP PLATE W/ TOENAILS @ 6" O.C.	2xIO BLK EVERY 3RD BAY FASTENED TO DBL. TOP PLATE W/ TOENAILS @ 4" O.C.
R.T. w/ HEEL HT. 12" TO 16"	2xI2 BLK EVERY 3RD BAY FASTENED TO DBL. TOP PLATE w/ TOENAILS @ 6" O.C.	2xI2 BLK EVERY 3RD BAY FASTENED TO DBL. TOP PLATE w/ TOENAILS @ 4" O.C.
R.T. w/ HEEL HT. UP TO 24"	LAP WALL SHTG. W/ DBL. TOP PL. & INSTALL ON TRUSS VERT FASTEN W/ NAILS @ 6" O.C.	LAP WALL SHTG. W/ DBL. TOP PL. & INGTALL ON TRUSS VERT FASTEN W/ NAILS @ 6" O.C.*
R.T. w/ HEEL HT. 24" TO 48"	LAP WALL SHTG. W/ DBL. TOP PL. & INSTALL ON TRUSS VERT FASTEN W/ NAILS @ 6" O.C. PROVIDE 2x BLK @ EA. BAY AT TOP OF HEEL	LAP WALL SHTG, W/ DBL. TOP PL. & INSTALL ON TRUSS VERT FASTEN W/ NAILS @ 6" O.C. PROVIDE 2x BLK @ EA. BAY AT TOP OF HEEL*
WALL TO FOUNDATION	WALL SHTG. LAP W/ SILL PL. & FASTENED PER SHEAR WALL FASTENING SPEC.	

· 2½",XO.113 IS AN ACCEPTABLE ALTERNATIVE TO A 3"XO.120", SAME SPACING OR NUMBER OF NAILS. ONLY ACCEPTABLE WHERE * ARE SHOWN)

ADDITIONAL NOTES FOR TRUSS & I-JOIST MANUFACTURER

ROOF TRUSS AND ENGINEERED JOISTS SHALL BE DESIGNED TO MEET THE DEFLECTION CRITERIA BELOW, UNLESS NOTED OTHERWISE ON PLAN.
MULHERN & KULP CANNOT BE HELD RESPONSIBLE FOR ANY STRUCTURAL ISSUES RELATED TO ANY BUILDING COMPONENT IF COMPONENT SHOP DRAWINGS ARE NOT SUBMITTED TO M&K FOR REVIEW PRIOR TO FABRICATION, DELIVERY, OR INSTALL ATION.

TRUSSES/LIGISTS SHALL BE DESIGNED SO THAT DIFFERENTIAL DEFLECTION BETWEEN ADJACENT PARALLEL TRUSSES/JOISTS OR GIRDER TRUSSES/FLUS BEAMS DO NOT EXCEED THE FOLLOWING: A. ROOF TRUSSES:

- I/4" DEAD LOAD ATTIC TRUSSES, & I-JOISTS:
- 1/8" DEAD LOAD

ABSOLUTE DEAD LOAD DEFECTION OF ATTIC TRUSSES WHEN AD JACENT TO ELOOR FRAMING BY OTHERS SHALL BE LIMITED TO 3/16". (NOT DIFFERENTIAL DEFLECTION)

VENEER LINTEL SCHEDULE

SPAN (MAX)	HEIGHT OF VENEER ABOVE LINTEL	STEEL ANGLE SIZE	
3'-0"	20 FT. MAX	L3"x3"x¼"	
	3 FT. MAX	L3"x3"x¼"	
6'-0"	I2 FT. MAX	L4"x3"x¼"	
	20 FT. MAX	L5"x3½"x5%"	
8'-0"	3 FT, MAX	L4"x4"x½" *	
0-0	I2 FT. MAX	L5"x3½"x5%"	
	I6 FT. MAX	L6"x3½"x3%"	
9'-6"	I2 FT. MAX	L6"x3½"x5%"	

- L LINIELS: SHALL SUPPORT 2 3%" 3 ½" VENEER W 40 psf MAXIMUM WEIGHT IG SHALL HAVE 4" MIN. BEARING IG SHALL HAVE 8" MIN. BEARING IG SHALL NOT BE FASTENED BACK TO HEADER.

- < 46 SHALL NOT BE FASTIBLED BACK TO HEADER. IN MALL 046°02. W ½" DIA. x 3 ½" LONG LAS SCREDE DIA XT DOOD HEADER IN MALL 046°02. W ½" DIA. x 3 ½" LONG LAS SCREDE IN 2E. LONG VERTICALLY SLOTTED HOLES. MAX. YEBER TH. APPLIES TO AN PORCITO OF BROCK OVER THE OPENING. ALL LINES SHALL BE LONG LES VERTICAL. ALL LINES SHALL BE LONG LES VERTICAL. WHEN SUPPORTING VEDERS ("3" MUED OVER THE BEARING LENGTH ONLY, THIS IS TO ALLON FOR NORTHER JOHN THIS HIGH SIGN OVER THE BEARING LENGTH ONLY, THIS IS TO ALLON FOR NORTHER JOHN THIS HIGH IS.</p>
- PRICTURAL PLANS FOR ANY LINTEL CONDITION NOT ENCOMPASSED BY THE
- 'Arameters. En veneer use l4x3x/4".

GENERAL STRUCTURAL NOTES

FOUNDATION

- DESIGN IS BASED ON 2018 NCSBC-RESIDENTIAL CODE & 2018 IRC WITH SOUTH CAROLINA AMENDMENTS
- FOOTING DESIGN 2,000 PSF NET ALLOWABLE SOIL BEARING PRESSURE IS ASSUMED. BUILDER/CONTRACTOR MUST VERIFY.
- FASTEN 2x4/6 SILL PLATES TO CONC FND WITH A MINIMUM OF 2 ANCHORS PER PLATE, 12" MAX. FROM PLATE ENDS - UTILIZING I/2" DIA, ANCHOR BOLTS @ 6'-0" O.C,7" MIN, EMBEDMENT
- FA4 ANCHOR STRAPS @ 6'-0" O.C
- FASTEN 2xi0 SILL PLATES TO PRECAST BSMT WALLS WITH A MINIMUM OF 2 ANCHORS PER PLATE, I2" MAX. FROM PLATE ENDS UTILIZING: • I/2" DIA. BOLTS @ 2'-0" O.C
- ALL LUMBER EXPOSED TO WEATHER OR IN CONTACT W PERIMETER
- FOUNDATION SHALL BE PRESERVATIVE TREATED SOUTHERN PINE #2. BUILDER TO VERIFY CORROSION-RESISTANCE COMPATIBILITY OF HARDWARE & FASTENERS IN CONTACT W PRESERVATIVE-TREATED
- WOOD, CONTACT LUMBER & HARDWARE SUPPLIERS TO COORD. FOUNDATION WALLS & FOOTINGS SHALL BE PLAIN CONCRETE, U.N.O.
- CONCRETE DESIGN BASED ON ACI 318. CONCRETE SHALL ATTAIN THE FOLLOWING MIN. COMPRESSIVE STRENGTHS IN 28 DAYS, U.N.O.:
 - f'c = 4,000 psi: FOUNDATION WALLS 3,000 psi: FOOTINGS & INTERIOR SLABS ON GRADE 3,500 psi: GARAGE & EXTERIOR SLABS ON GRADE = 60,000 psi
- BASEMENT FOUNDATION WALL DESIGN BASED ON:
 - . 8' OR 9' HEIGHT (AS NOTED ON PLANS) TALLER WALLS MUST BE ENGINEERED.
- BASEMENT WALL DESIGN IS BASED ON 30 OR 45 PCF BACKFILL SOIL TYPE CLASSIFICATIONS:
 - 30 PCF TYPE (GW, GP, SW, SP) 45 PCF TYPE (GM, GC, SM, SM-SC, ML)
 - IMPORTANT IF 60 PCF SOIL TYPE (SC, ML-CL, OR CL) IS UTILIZED FOR BACKELL, CONTACT MULHERN & KULP FOR FURTHER EVALUATION OF FOUNDATION DESIGN.
- BASEMENT WALLS SHALL BE BRACED, PRIOR TO BACKFILLING, BY ADEQUATE TEMPORARY BRACING OR INSTALL 1st FLOOR DECK.
- ALL CONCRETE EXPOSED TO THE WEATHER SHALL NOT HAVE LESS THAN 5% OR MORE THAN 7% AIR ENTRAINMENT.
- ALL FOOTINGS SHALL BEAR BELOW FROST LINE (TYP.) OR 12" MIN IN REGIONS WHERE CODE FROST DEPTH IS NOT APPLICABLE. CONSULT SOILS REPORT OR BUILDING DEPT. FOR MINIMUM DEPTH BELOW
- FOOTINGS AND SLABS ON GRADE SHALL BEAR ON VIRGIN SOIL OR 95% COMPACTED FILL.
- PROVIDE CONTROL JOINTS AT ALL INSIDE CORNERS OF SLAB EDGES, AND OTHER LOCATIONS WHERE SLAB CRACKS ARE LIKELY TO DEVELOP.
- JOINTS SHALL BE LOCATED @ 10'-0" O.C. (RECOMMENDED) OR 15'-0" O.C. (MAXIMUM)
- JOINT GRID PATTERN SHALL BE AS CLOSE TO SQUARES AS POSSIBLE (I:I RATIO), WITH A MAXIMUM OF I:I.5 RATIO · CONTROL JOINTS SHALL NOT BE INSTALLED IN STRUCTURAL
- PICAL REINFORCEMENT DETAILS: PROVIDE 3" MIN. CLEAR COVER WHERE CAST AGAINST FARTH LI/2" MIN CLEAR COVER AGAINST FORMS. LAP ALL REBAR 40 BAR DIAMETERS MIN. (24 FOR #4 BARS) & BEND BARS AND LAP AT CORNERS. PROVIDE 6"

HOOK INTO SUPPORTING FOOTINGS WHEN FOOTINGS INTERSECT.

DIMENSIONS BY OTHERS, BUILDER TO VERIEY.

LEGEND

R.T. NDICATES ROOF TRUSSES @ 24" O.C. PER ROOF. MANUF. (TYP. U.N.O.)

OF. INDICATES TRUSS OVERFRAMING • 24" O.C. (TYP. U.N.O.)

INDICATES 14" DEEP FLOOR I-JOISTS @ 24" O.C. MAX, JOIST SERIES AND SPACING SHALL BE THE RESPONSIBILITY OF THE MANUFACTURER NOTE: 14" FLOOR TRUSSES @ 24" O.C. MAX. IS AN ACCEPTABLE ALTERNATE FLOOR SYSTEM

- INDICATES LOCATIONS OF POTENTIAL TILE FLOOR - JOIST MANUFACTURER SHALL DESIGN FLOOR SYSTEM FOR ADD'L 10 PSF DEAD LOAD AT THESE LOCATIONS.
- INTERIOR BEARING WALL
- □===□ BEARING WALL ABOVE (B.W.A.)

- INDICATES POST ABOVE (P.A.) PROVIDE SOLID BLOCKING UNDER POST OR JAMB ABOVE.

LATERAL/WALL BRACING & WALL SHEATHING SPECIFICATIONS

THIS MODEL HAS BEEN DESIGNED TO RESIST LATERAL FORCES RESULTING FROM: MPH WIND IN 2018 NCSBC:RO

20MPH WIND IN 2018 IRC (120 MPH WIND SPEED IN ASCE 7 WIND MAP PER IRC R301211) EXP. B. RISK CAT. 2 & SEISMIC CAT. A/B.

THE DESIGN WAS COMPLETED PER 2015 \$ 2018 IBC SECTION 1609) & ASCE 7 AS PERMITTED BY R30113 DE THE 2018 NOSBO:RC & 2018 IRC. ACCORDINGLY THIS MODEL, AS DOCUMENTED AND DETAILED HEREWITHIN, IS ADEQUATE TO RESIST THE CODE REQUIRED LATERAL FORCES.

DESIGN WIND UPLIFT LOADS HAVE BEEN CALCULATED UTILIZING ASCE 7 (ACCEPTED ENGINEERING PRACTICE) AS ALLOWED PER 2018 NCSBC:RC & 2018 IRC SECTION R802.II.I.I. THIS MODEL HAS BEEN DETAILED WHERE REQUIRED & FNGINFFRFD TO RESIST THE WIND UPLIFT LOAD PATH PER SECTIONS R602.3.5¢ R802.II.

EXT. WALL SHEATHING SPECIFICATION

- •7/16" OSB OR 15/32" PLYWOOD: FASTEN SHEATHING W/ 2 8"XO.II3 NAILS @ 6" O.C. AT EDGES & @ 12" O.C. IN THE PANEL FIELD. (TYP, U.N.O.)
- ALL SHEATHING PANELS SHALL BE ORIENTED

 VERTICALLY (LONG DIRECTION PARALLEL TO STUDS) AND INSTALLED FULL HEIGHT OF SHEAR WALL - OR -2x HORIZONTAL BLOCKING SHALL BE PROVIDED TO SUPPORT ALL UNSUPPORTED PANEL EDGES & EDGE
- ALL EXT. WALLS SHALL BE CONTINUOUSLY SHEATHED AND ARE CONSIDERED SHEAR WALLS.
- ALT, STAPLE CONNECTION SPEC: 1 3/4" 16 GA STAPLES (1/6" CROWN) @ 3" O.C. AT EDGES & @ 6" O.C IN FIELD.

3" O.C. EDGE NAILING

AT DESIGNATED AREAS - FASTEN PANEL EDGES OF WOOD STRUCTURAL WALL SHEATHING TO FRAMING W 2 3" x 0.113" NAILS @ 3" O.C. AND 12" O.C. IN THE PANEL FIELD NO STAPLE ALTERNATIVE AVAILABLE AT THIS SPEC. ALL SHEATHING PANELS SHALL BE ORIENTED VERTICALLY (LONG DIRECTION PARALLEL TO STUD) AND INSTALLED FULL HEIGHT OF SHEAR MALL - OR - 2X HORIZONTAL BLOCKING SHALL BE PROVIDED TO SUPPORT UNSUPPORTED PANEL EDGES AND 3" O.C. EDGE FASTENING.

- SEE CONNECTION SPECIFICATIONS CHART FOR STANDARD SHEAR TRANSFER DETAILING. IF ADDITIONAL CAPACITY IS REQUIRED BY DESIGN, IT WILL BE SPECIFICALLY NOTED ON PLAN.
- DESIGN ASSUMES 16" O.C MAX. STUD SPACING, U.N.O
- ALL STRUCTURAL PANELS ARE TO BE DIRECTLY APPLIED TO STUD FRAMING.
- PRE-MANUFACTURED PANELIZED WALLS: FASTEN TOGETHER END STUDS OF WALL PANELS SHEATHED w/ OSB OR PLYWOOD w/ 3" x 0.120 NAILS @ 4" O.C. (THRU ONE SIDE ONLY)

INDICATES EXTENT OF INT. OSB SHEARWALL, AND/OR 3" O.C. EDGE NAILING

NDICATES HOLDOWN

NON-BEARING HEADER SCHEDULE

SPAN	2x4 NON-BEARING PARTITION WALL	2x6 NON-BEARING PARTITION WALL
UP TO 3'-0"	(I)2x4 FLAT	(I)2x6 FLAT
UP TO 6'-0"	(2)2x4	(3)2×4
UP TO 8'-0"	(2)2×6	(3)2x6

ALL NON-BEARING INTERIOR STUD WALLS SHALL BE CONSTRUCTED WITH 2x 'STUD' GRADE MEMBERS SPACED @ 24" O.C. (MAX.)

FLOOR FRAMING

- I-JOISTS SHALL BE DESIGNED BY MANUF. TO MEET OR EXCEED L/480 LIVE LOAD DEFLECTION CRITERIA. (EXCLUDES STONE/MARBLE OR WET BED CONSTRUCTED FLOORS - CONTACT M&K FOR EXCLUDED FLOOR DESIGNS)
- PER THE GUIDELINES OF THE TILE COUNCIL OF NORTH AMERICA (TCNA HANDBOOK), IT SHALL BE THE FLOOR FINISH INSTALLER'S RESPONSIBILITY TO VERIFY THAT THE FINISHES TO BE INSTALLED MATCH THE DESIGN CRITERIA NOTED ABOVE (UNDER "DESIGN
- FLOOR SYSTEMS & SHEATHING HAVE BEEN DESIGNED TO SUPPORT ADDITIONAL DEAD LOAD FROM CERAMIC TILE (EXCLUDING MARBLE OR STONE). HOWEVER, IT SHALL BE THE FLOOR FINISH INSTALLER'S RESPONSIBILITY TO PROVIDE PROPER UNDERLAYMENT, UNCOUPLING MEMBRANE AND MORTAR/GROUT PER THE ASSEMBLY DESIGNATIONS IN THE TONA HANDBOOK (TILE COUNCIL OF NORTH AMERICA).
- AT I-JOIST FLOORS, PROVIDE I" MIN. OSB RIM BOARD.
- METAL HANGERS SHALL BE SPECIFIED BY MANUFACTURER, U.N.O. • I-JOIST SHOP DWGS. SHALL BE SUBMITTED TO ARCH. & ENG. FOR REVIEW AND APPROVAL PRIOR TO FABRICATION OR DELIVERY.
- FLOOR SHEATHING SHALL BE 23/32" A.P.A. RATED 'STURD-I-FLOOR 24" O.C., EXPOSURE I (OR APPROVED EQUAL) WITH TONGUE AND GROOVE EDGES. FASTEN TO FRAMING MEMBERS W GLUE AND
- 2 ½" x 0.131" NAILS @ 6"o.c. @ PANEL EDGES € @ 12"o.c. FIELD.
- 2 3" x 0.120" NAILS @ 4" O.C. @ PANEL EDGES & @ 8" O.C. FIELD. - 2 🖁 × 0.113" NAILS @ 3" O.C. @ PANEL EDGES & @ 6" O.C. IN FIELD.

ROOF FRAMING

- ROOF SHEATHING SHALL BE 1/16" A.P.A. RATED SHEATHING 24/16 EXPOSURE I (OR APPROVED EQUAL). FASTEN TO FRAMING MEMBERS
- w/ 2 $\frac{1}{2}$ " × 0.131" NAILS @ 6"o.c. @ PANEL EDGES & @ 12" O.C. FIELD. - w/ 2 🖁 × 0.120" NAILS @ 4"o.c. @ PANEL EDGES & @ 8" O.C. FIELD. - W/2 累"×0.113" NAILS @ 3"o.c. @ PANEL EDGES & @ 6" O.C. FIELD.
- WITHIN 48" OF ALL ROOF EDGES, RIDGES, & HIPS FASTEN ROOF SHEATHING FIELDS PER EDGE NAILING SPEC.
- FASTEN EACH ROOF TRUSS TO TOP PLATE W USP RTTA CLIP (OR APPROVED EQUAL) @ ALL BEARING POINTS. PROVIDE (2) RTTA CLIPS AT 2-PLY GIRDER TRUSSES, (3) RTTA CLIPS AT 3-PLY GIRDER TRUSSES & ROOF BEAMS - AT ALL BEARING POINTS
- METAL HANGERS SHALL BE SPECIFIED BY THE MANUFACTURER, U.N.O.
- ROOF TRUSS SHOP DWGS. SHALL BE SUBMITTED TO ARCH & ENG. FOR REVIEW AND APPROVAL PRIOR TO FABRICATION OR DELIVERY ERECT AND INSTALL ROOF TRUSSES PER WTCA & TPI'S BCSI I "GUIDE TO GOOD PRACTICE FOR HANDLING, INSTALLING & BRACING OF METAL PLATE CONNECTED WOOD TRUSSES."
- SUPPORT SHORT SPAN ROOF TRUSSES w/2x4 LEDGER FASTENED TO FRAMING w/(2) 3" x 0.120" NAILS @ 16" O.C. (UP TO 7' SPAN).

MEANS & METHODS NOTES

THE STRUCTURE IS DESIGNED TO BE SELF SUPPORTING AND STABLE AFTER THE BUILDING IS FINISHED AND ALL PLAN, DETAIL, AND NOTE SPECIFICATIONS HAVE BEEN COMPLETED. IT IS THE CONTRACTOR'S SOLE RESPONSIBILITY TO DETERMINE THE ERECTION PROCEDURES AND SEQUENCE TO INSURE THE SAFETY OF THE BUILDING AND ITS COMPONENTS DURING CONSTRUCTION. THIS INCLUDES, BUT IS NOT LIMITED TO, THE ADDITION OF NECESSARY SHORING, SHEETING, TEMPORARY BRACING, GUYS, AND TIE-DOWNS. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL SHORING AND BRACING REQUIRED TO STABILIZE AND PROTECT EXISTING AND ADJACENT STRUCTURES AND SYSTEMS DURING COURSE OF DEMOLITION AND CONSTRUCTION OF

STRUCTURAL DESIGN AND SPECIFICATIONS ASSUME THAT ALL SUPPORTING AND NON-SUPPORTING ELEMENTS IN CONTACT WITH FLOOR FRAMING ARE LEVEL, INCLUDING, BUT NOT LIMITED TO; FOUNDATIONS SLABS ON GRADE BEAMS WALLS AND NON-BEARING LEMENTS. IT IS THE CONTRACTOR'S RESPONSIBILITY LEVELNESS AND MAKE ADJUSTMENTS AS NECESSARY, INCLUDING CONSIDERATION OF THOSE AREAS THAT MAY CONTRACTUAL, INDUSTRY, OR WARRANTY TOLERANCES.

GENERAL STRUCTURAL NOTES

- DESIGN IS BASED ON 2018 NOSBC-RESIDENTIAL CODE & 2018 IRC WITH SOUTH CAROLINA AMENDMENTS
- WOOD FRAME ENGINEERING IS BASED ON NDS, "NATIONAL DESIGN SPECIFICATION FOR WOOD CONSTRUCTION" - LATEST EDITION.

LIVE = 20 PSF DEAD = 1 PSF T.C., 10 PSF B.C ROOF

LOAD DURATION FACTOR = 1.25 FLOOR LIVE = 40 PSF (30 PSF @ SLEEPING AREAS) DEAD = 10 PSF (I-JOISTS)

ADD'L IO PSF @ CERAMIC TILE IN BATHS & LAUND.

2,000 PSF ASSUMED ALLOWABLE BEARING PRESSURE (TO BE VERIFIED BY BUILDER)

GENERAL FRAMING

- CONNECTIONS TABLE (IRC. TABLE R6023(I)) OR ON PLANS ALL NAILS SPECIFIED ARE MIN DIAMETER AND LENGTH REQUIRED FOR CONNECTION, ALL HANGER NAILS SHALL BE INSTALLED PER MANUFACTURER'S REQUIREMENTS FOR MAX CHARTED CAPACITY. NOTE: HANGERS USE COMMON NAIL DIAMETERS NOT TYPICAL FRAMING GUN NAILS.
- EXT. & INT. BEARING WALLS SHALL BE 2x4 OR 2x6 (AS SHOWN ON PLANS) @ 16" O.C. SPF/SP "STUD" GRADE LUMBER, OR BETTER, U.N.O. WALLS OVER 12' TALL SHALL BE PER PLAN.
- ALL INTERIOR BEARING WALLS ARE ASSUMED TO BE SHEATHED W/ GYP WALL BOARD (ONE SIDE MIN.) OR PROVIDE MID HT. BLOCKING.
- ALL HEADERS, BEAMS & OTHER STRUCTURAL MEMBERS SHALL BE SPRUCE-PINE-FIR #2 (SPF) OR SOUTHERN PINE #2 (SP) LUMBER, OR BETTER. SUPPORT ALL HEADERS/ BEAMS W (1)2x JACK STUD & (1)2x
- THE NUMBER OF STUDS SPECIFIED AT A SUPPORT INDICATES THE NUMBER OF JACK STUDS REQUIRED, U.N.O.. ALL NON-BEARING INTERIOR STUD WALLS SHALL BE CONSTRUCTED
- WITH 2x 'STUD' GRADE MEMBERS SPACED @ 24" O.C. (MAX., U.N.O.) HEADERS IN NON-LOAD BEARING WALLS SHALL BE: (I)2x4/6 FLAT @ OPENINGS UP TO 4', (2)2x4/6 FLAT UP TO 8'.
- ALL FRAMING LUMBER SHALL BE DRIED TO 15% MC (KD-15). PENGINEERED LUMBER BEAMS TO MEET OR EXCEED THE FOLLOWING
- 'LVL' Fb=2600 psi; Fv=285 psi; E=2.0xl0^6 psi
- ENGINEERED LUMBER POSTS TO MEET OR EXCEED THE FOLLOWING: • 'LVL' - Fb=2400 psi; FcII=2500 psi; E=I.8xI0^6 psi
- FOR 2 & 3 PLY BEAMS OF EQUAL $1\frac{3}{4}$ " MAX, WIDTH, FASTEN PLIES TOGETHER WITH 3 ROWS OF 3"X0.120" NAILS @ 8" O/C OR 2 ROWS USP WS35 SCREWS (OR 3K" TRUSSLOK SCREWS) @ 16" O/C, USE A MINIMUM OF 4 ROWS FOR BEAM DEPTHS OF 14" OR GREATER.

 APPLY FASTENING AT BOTH FACES FOR 3-PLY CONDITION. LOCATE TOP & BOTTOM NAILS/SCREWS 2" FROM EDGE. SOLID 3½" OR 5½" BEAMS ARE ACCEPTABLE, USE 2 ROWS OF NAILS FOR 2x6 & 2x8
- FOR 4 PLY BEAMS OF EQUAL 13/4" MAX, WIDTH, FASTEN PLIES TOGETHER WITH 3 ROWS OF USP WS6 SCREWS (OR 6 $^3\!\!\!/_{\!\!4}$ " TRUSSLOK SCREWS) @ 16" O/C. USE A MINIMUM OF 4 ROWS FOR BEAM DEPTHS OF 14" OR GREATER, APPLY FASTENING AT BOTH FACES (ONE SIDE ONLY FOR TRUSSLOK SCREWS). LOCATE TOP AND BOTTOM SCREWS 2" FROM EDGE. A SOLID 7" BEAM IS ACCEPTABLE.
- PROVIDE SOLID BLOCKING IN FLOOR SYSTEM UNDER ALL POSTS CONTINUOUS TO FND/BEARING. BLOCKING TO MATCH POST ABOVE.
- ALL EXTERIOR 4x4 WOOD POSTS SHALL HAVE USP BCS22-4 CAP \$ PA44E BASE, U.N.O.
- BUILDER RESPONSIBLE TO DETERMINE CORROSION-RESISTANCE REQUIREMENTS AND COMPATIBILITY OF HARDWARE EASTENERS AND CONNECTORS FOR ENVIRONMENTAL EXPOSURE AND IN CONTACT W/ PRESERVATIVE-TREATED WOOD OF ACTUAL FINAL CONDITIONS AND SOURCED MATERIALS. CONTACT LUMBER \$ HARDWARE SUPPLIERS TO COORD.
- ALL FASTENERS AND CONNECTORS EXPOSED TO SALT WATER (WITHIN 300' OF SALT WATER SHORELINE, INCLUDING VENTED SPACES) SHALL BE STAINLESS STEEL.

MUCHERN+KULP
RESIDENTIAL STRUCTURAL ENGINEERINS C-3825



Mulhern+Kulp project numbe 256-22018

SMK RAF issue date: 01.05.2023

REVISIONS

initial:


SMITH DOUGI HOMES

NOTES MODE STRUCTURAL


ZONI SON WIND 120 N

GENERAL

BRIARWOOD LOT 25





PARTIAL MONO-SLAB FOUNDATION PLAN SCALE: 1/4"=1'-0" ON 22x34 OPT. COVERED PATIO ALL ELEVS, SIM. SEE BASE ELEV, FOR ADD'L INFO 1/8"=1'-0" ON 11x17



SCALE: |/4"=|'-0" ON 22x34 |/8"=|'-0" ON ||x|7

ALL ELEVS. SIM.







REFER TO SO.O FOR TYPICAL STRUCTURAL NOTES & SCHEDULES

LEGEND

R.T. INDICATES ROOF TRUSSES @ 24" O.C. PER ROOF. MANUF, (TYP, UN.O.)

OF, INDICATES TRUSS OVERFRAMING
24" O.C. (TYP, UN.O.)

F.J. NIDICATES 14" DEEP FLOOR I-JOISTS © 24" O.C.
MAX. JOIST SERIES AND SPACING SHALL BE THE
RESPONSIBILITY OF THE MANUFACTURER
NOTE: 14" FLOOR TRUSSES © 24" O.C. MAX. IS AN ACCEPTABLE ALTERNATE FLOOR SYSTEM

INDICATES LOCATIONS OF POTENTIAL TILE FLOOR. - JOIST MANUFACTURER SHALL DESIGN FLOOR SYSTEM FOR ADD'L 10 PSF DEAD LOAD AT THESE LOCATIONS.

• IIIIIII INTERIOR BEARING WALL

• □=== BEARING WALL ABOVE (B.W.A.)

• --- BEAM/HEADER

• JL METAL HANGER

• * INDICATES POST ABOVE (P.A.) PROVIDE SOLID BLOCKING UNDER POST OR JAMB ABOVE.

2/6/24

MULHERN+KULP
RESIDENTIAL STRUCTURAL ENSINEERINS rive(way, State 1956 • April 1 • marken (appoint nse # C-3825



Mulhern+Kulp project number: 256-22018

SMK RAP issue date: 01.05.2023

REVISIONS:

initial:


SMITH DOUGLAS HOMES


FOUNDATION

SON MODEI GRA

120 MPH WIND ZONE NORTH CAROLINA

MONO-SLAB





2/6/24

MULHERN + KULP

RESIDENTIAL STRUCTURAL ENGINEERING

RESIDENTIAL STRUCTURAL ENGINEERING

PARTICULAR STRUCTURAL SAME

PARTICULAR STRUCTURAL SAME

PARTICULAR SAME

Mulhern+Kulp project number:

256-22018

SMK RAP issue date: 01.05.2023

initial:

SMITH DOUGLAS HOMES

GRAYSON MODEL

FRAMING |

ROOF

120 MPH WIND ZONE NORTH CAROLINA

REFER TO SO.O FOR TYPICAL STRUCTURAL NOTES & SCHEDULES PLAN

RT. INDICATES ROOF TRUSSES @ 24" O.C. PER ROOF.

BRIARWOOD

THIS LEVEL HAS BEEN DESIGNED FOR 9'-I" PLATE HEIGHT

LOT 25



INDICATES LOCATIONS OF POTENTIAL TILE FLOOR.

• JL METAL HANGER

BLOCKING UNDER POST OR JAMB ABOVE.

LEGEND

MANUF. (TYP. U.N.O.)

O.F. INDICATES TRUSS OVERFRAMING • 24" O.C. (TYP. U.N.O.)



F.J. INDICATES I4" DEEP FLOOR I-JOISTS @ 24" O.C.
MAX. JOIST SERIES AND SPACING SHALL BE THE
RESPONSIBILITY OF THE MANUFACTURER
NOTE: I4" FLOOR TRUSSES @ 24" O.C. MAX. IS AN
ACCEPTABLE ALTERNATE FLOOR SYSTEM


JOIST MANUFACTURER SHALL DESIGN FLOOR
SYSTEM FOR ADD'L 10 PSF DEAD LOAD AT THESE LOCATIONS.


INTERIOR BEARING WALL


● □===□ BEARING WALL ABOVE (B.W.A.)


• --- BEAM/HEADER

S3.0M INDICATES POST ABOVE (P.A.) PROVIDE SOLID










TYPICAL SLAB ON GRADE 2 PERIMETER FOOTING w/ BRICK VENEER

TYPICAL SLAB ON GRADE GARAGE 3 PERIMETER FOOTING


TYPICAL SLAB ON GRADE GARAGE 4 PERIMETER FOOTING w/ BRICK VENEER




TYPICAL SLAB ON GRADE

PERIMETER FOOTING







TYPICAL SLAB ON GRADE GARAGE 6 ENTRY @ PERIMETER FOOTING




TYPICAL MONOLITHIC INTERIOR GARAGE FOOTING




TYPICAL SLAB ON GRADE PERIMETER



TYPICAL THICKENED SLAB @ 9 INTERIOR BEARING WALL





OPT. BRICK (SEE ARCH FOR LOCATIONS)

FOOTING @ PORCH/PATIO

BRIARWOOD LOT 25

2/6/24

MULHERN+KULP
RESIDENTIAL STRUCTURAL ENGINEERINS SECTION OF THE SECTION OF STATE OF SECTION OF THE S

Mulhern+Kulp project number: 256-22018

SMK RAP issue date: 01.05.2023


initial:

SMITH DOUGLAS HOMES


MODE FOUNDATION DETAILS SON

120 MPH WIND ZONE NORTH CAROLINA GRA

SD1.0



BOTH SIDES OF GARAGE DOOR 120 MPH WIND SPEED (ULT) SCALE: N.T.S.



2/6/24

MULHERN+KULP RESIDENTIAL STRUCTURAL ENSINEERINS 2005 Brookside Perkvey, Suite 205 - Algebra 2778-777-2004 - methemicalment NC License # C-3825

Mulhern+Kulp project number: 256-22018

SMK RAP issue date: 01.05.2023

initial:

REVISIONS:

SMITH DOUGLAS HOMES

MODE


FRAMING DETAILS GRAYSON


120 MPH WIND ZONE NORTH CAROLINA


BRIARWOOD

LOT 25

SD2.0







2x4 HORIZ. - FASTEN W 3 I/4'x0.I20" (MIN.) 6 8" O.C. TO 2x6 VERTICAL 2x4 BLOCKING W (4) 3"x0.120" (MIN.) TOE-NAILS EACH END @ EACH DIAGONAL BRACE -2 3/8"x0.113" NAILS @ 2x6 DIAG, BRACE (w/ 2x4

T-BRACE IF LENGTH EXCEEDS 6),

SPACED • 4-0" O.C., MAX, FASTEN
2x4 TO 2x6 N 9" NO.120" (MIN)

NAILS • 8" O.C.,

YOUR PROPERTY OF THE STRONG-BACK @ MID-HEIGHT DIRECT-APPLIED GMB CEILING 7 — PROVIDE 2x4 BLOCKING @ 48" O.C. IN FIRST BAY OF ROOF TRUSSES-CUT TO FIT TIGHT BETWN TRUSS BOT. CHORDS. FASTEN W (4) 3"x0.120" (MIN.) TOE-NAILS @ EACH END 2x EXTERIOR WALL -SEE PLANS FOR SPECIFICATIONS

BRACE GABLE END TRUSSES PER ABOVE DETAIL WHEN GABLE HEIGHT IS LESS THAN 9-0'. 'L' BRACES REQUIRED WHERE NOTED BY TRUSS MANUFACTURER.

TYPICAL GABLE END BRACING DETAIL SCALE: NONE REQUIRED TRUSS

TYPICAL GABLE END BRACING DETAIL SCALE: NONE RECORD & SABLE END TRUSS REQ'D & GABLE END TRUSS HEIGHT BETW'N 9'-0" TO 14'-0"

BRACE GABLE END TRUSSES PER ABOVE DETAIL WHEN GABLE HEIGHT EXCEEDS 9'-0'. 'L' BRACES NOT REQUIRED.

LETTERED DETAILS ARE TYPICAL FOR THIS HOME & SHALL BE IMPLEMENTED IN ALL APPLICABLE AREAS. THESE DETAILS ARE NOT "CUT" ON THE PLANS.

NUMBERED DETAILS ARE PLAN SPECIFIC AND ARE ONLY REQUIRED WHERE SPECIFICALLY INDICATED ("CUT") ON THE PLANS.

> BRIARWOOD LOT 25

MULHERNHAL STRUCTURAL ENGINEERING
SESSEMENT STRUCTURAL ENGINEERING
PROFIT STRUCTURAL STRUCTURAL ENGINEERING
PROFIT STRUCTURAL STRUCTURAL ENGINEERING
PROFIT STRUCTURAL STRUCTURA STR Mulhern+Kulp project number: 256-22018 issue date: 01.05.2023 REVISIONS: SMITH DOUGLAS HOMES

2/6/24

SMK

RAP

initial:

GRAYSON MODEI FRAMING DETAILS

120 MPH WIND ZONE NORTH CAROLINA

SD2.1

72527843 25 BRIARWOOD 34' 0" 1/2 2' 0", 2' 0", 2' 0", 」2' 0", 2' 0", 2' 0", 2' 0", 2' 0", 2' 0", 2' 0", 2' 0", 2' 0", 2' 3", 1' 9", 2' 0", 2' 0", 2' 0", 10 - A2H A2H 44 12' 1 1/2" STORAGE **INSTALL A 2 X 6 ON TOP RIBBON** NOTCH OF C SERIES TRUSSES FOR **REAR TRUSSES TO BEAR ON** V2 **INSTALL A 2 X 6 ON FLOOR TRUSSES** 31' 0" AFTER SHEATHED FOR C SERIES TRUSSES TO BEAR ON V1 0 (BLOCK SOLID UNDER C03 GIRDERS 35' **DOWN TO WALL)** 0 B3 -0 B2 2.0" N B2 0 2'0" (H) **FACE MOUNT HANGER** JUS26 N. B2 0 0 $\bar{\sim}$ D1 B2 2.0" B2 0 N B2 2'0" B1 C5 22 \aleph E2 $^{\circ}$ ဗ 2 2 2 \aleph C_2 E2 E2 \mathcal{D} E2 E2 교 2 X 4 LEDGER 20' 0" 14' 0"

PLACEMENT PLAN

 \triangle Indicates left end of truss Scale: N.T.S

SITE BUILT UFP



DOUGLAS -SMITH


포 BEH


ROOF -GRAYSON

DSN

DESIGNER JNN LAYOUT DATE 9/6/24 ARCH DATE -STRUC DATE

JOB #: -MASTER





Connector Summary			
PlotID	Qty	Manuf	Product
H1	14	MiTek	IHFL1714
H2	2	MiTek	TFL1714
Н3	2	MiTek	HD412IF
	PlotID H1 H2	PlotID Qty H1 14 H2 2	PlotID Qty Manuf H1 14 MiTek H2 2 MiTek

GENERAL NOTES:

1.) TOP CHORD OF JOISTS ARE PAINTED RED AT NUMBERED END. PLACE PAINTED END AS NOTED ON PLAN.
2.) FOLLOW SPECIAL SPACING AND LOCATION DIMENSIONS FOR EXTRAS OR SHIFTED JOISTS AS SHOWN ON PLAN.

AS SHOWN ON PLAN.
3) ALL INTERIOR WALL PLATES MUST BE LEVEL WITH OUTSIDE WALL TOP PLATES.
4.) DO NOT STACK CONSTRUCTION LOADS ON UN-BRACED JOISTS.
5.) PROVIDE SOLID SUPPORT BELOW ALL BEAM AND HEADER BEARING POINTS IN WALL AND JOIST SPACES CONTINUOUS DOWN TO THE FOUNDATION.
6.) LOCATE CRIPPLE STUDS IN JOIST SPACE DIRECTLY BELOW HEADER JACKS AT ALL FIRST

DIRECTLY BELOW HEADER JACKS AT ALL FIRST FLOOR EXTERIOR DOOR LOCATIONS.
7.) INSTALL NAILS IN ALL HOLES PROVIDED IN (7.) INSTALL NAILS IN ALL HOLES PROVIDED IN JOIST HANGERS EXCEPT AT BOTTOM CHORD SEAT. PLACE A DAB OF GLUE IN THE HANGER SEAT BEFORE SETTING JOISTS.

8.) IMPORTANT NOTE! NO STRUCTURAL ANALYSIS OF CONVENTIONAL HEADERS HAS BEFOLO SUBJECTED. EN DAY DATED. THEY APPEARS THE SEAT OF THE PROPERTY AND THE PROPERTY AND

BEEN CONDUCTED IF NOT NOTED. THEY ARE CONSIDERED TO BE ADEQUATE TO SUPPORT THE APPLIED LOADS.

FRAMER NOTE

DENOTES DUCT HOLE RUNS

ALL DIMENSIONS TO CENTERLINE UNLESS OTHERWISE NOTED

Avoid Plumbing Drops

. GLUE AND NAIL PLYWOOD SUBFLOOR TO BEAMS AND GIRDERS AT 6" O/C WHERE NO WALL IS ABOVE. 2. FILL HANGER SEAT WITH GLUE BEFORE SETTING JOIST IN HANGER. FILL ROUND HOLES WITH

CRITICAL !!

INSTALL 2X4 SQUASH BLOCKS IN FLOOR TRUSS SPACE BELOW ALL EXTERIOR DOOR HEADER JACKS. CUT 1/16" TALLER THAN TRUSS.

PLAN LEGEND

*INDICATES BEAM ABOVE TOP PLATE (FLUSH WITH FLOOR SYSTEM)

H-, 1H-, GDH- INDICATES BEAM BELOW TOP PLATE (DROPPED BELOW FLOOR SYSTEM)

*BEAMS MAY PROTRUDE ABOVE OR BELOW DECKING OR TOP PLATE RESPECTIVELY, REFER TO DETAIL IF BEAM IS A DIFFERENT DEPTH THAN FLOOR SYSTEM

(ADD LINE FOR EACH ADDITIONAL PLY)

SHIFT JOIST TO MISS PLUMBING, ALIGN WWALL OR SUPPORT FURNITURE

FRAMER NOTE

FIELD TRIM NON RED END TO KEEP HOLES ALIGNED CONTAR EL LADO DE SIN MARCA ROJA PARA HOYOS ALINEADOS

FIELD LOCATE PLUMBING DROPS/CAN **LIGHTS, ETC... PRIOR TO JOIST SECUREMENT TO**

LAYOUT FOR 19.2" O/C

AVOID INTERFERENCE

1= 19-3/16" 9= 172-13/16" 2= 38-3/8" 10= 192" 3=57-5/8" 11= 211-3/16" 4= 76-13/16" 12= 230-3/8" 13= 249-13/16" 5= 96" 6= 115-3/16" 14= 268-13/16" 7= 134-3/8" 15= 288" 8= 153-5/8"

FIELD VERIFY DIMENSIONS TO **JOISTS LOCATED UNDER WALLS!!**

2ND FLOOR LAYOUT

2ND FLOOR PLACEMENT PLAN

SCALE: 1/8" = 1'

BUILT الله الله

UFP



Lot 25 Briarwood Bluff

Smith Douglas Homes

Grayson B 2nd Floor

NC 27332

DESIGNER PB2 LAYOUT DATE 10/3/2025 ARCH DATE 12/14/2022 **STRUC DATE** 2/15/2023

JOB #: 25100257IJ2