




Agri-Waste Technology, Inc.
501 N Salem Street, Suite 203, Apex, NC 27502
agriwaste.com | 919.859.0669



Soil Suitability for Domestic Sewage Treatment and Disposal Systems
Birchwood Trails – Lot 45
Olive Branch Rd. Fuquay Varina, NC 27526
(Harnett County)
January 31, 2024

Soil suitability for domestic sewage treatment and disposal systems was evaluated on April 24, 2023, for the property located at Olive Branch Rd. in Fuquay Varina, NC (Harnett County). Jeff Vaughan, Heath Clapp, and Trent Bostic of Agri-Waste Technology, Inc. (AWT) conducted the soil evaluation. This evaluation was done to facilitate permitting for a septic system for a 4-bedroom home. This report and attached documents were prepared *to this application is to be used to issue an Improvement Permit in accordance with G.S. 130A-335(a2) and (a3). The LSS evaluation is being submitted pursuant to and meets the requirements of G.S. 130A-335(a2).*

A drawing of the site plan, septic layout, septic system design, and soil pit locations is included in Attachment 1. Profile descriptions for each soil boring are included in Attachment 2.

Site Conditions

The total property area is approximately .48 acres. The house and septic area are wooded. The proposed septic system for the property is a pressure manifold fed, accepted status system for initial and repair. The home is proposed near the front of the lot and the septic system is proposed to the rear of the house.

Soil Suitability for Domestic Sewage Treatment and Disposal Systems

The drawing in Attachment 1 details the property boundaries, soil pit locations, and layout of drain field trenches. Multiple soil pits and borings were advanced within the proposed septic system area on the property. The site has been evaluated and meets the soil and site evaluations criteria set forth in 15A NCAC Subchapter 18E – Wastewater Treatment and Dispersal Systems.. All soil pits/borings were provisionally suitable for a conventional style trench. Soil pits/borings are within the proposed drainfield area.

The layout shown in Attachment 1 indicates there is available space for a four-bedroom accepted system. The initial system can be installed with the use of an accepted status drainfield based on the layout in the field.

The proposed LTAR (Long Term Acceptance Rate) by AWT is 0.4GPD/ft². The soils on this property are group III soils within the distribution and treatment zone as used to define the LTAR. With an LTAR of 0.4GPD/ft², 600 linear feet of trench is necessary to support a 4-bedroom home for the initial and repair system with the use of an accepted trench product. The maximum slope corrected trench depth is 22 inches. The attached drawings substantiate that the necessary linear footage of trench can be installed on the property for the initial and repair system.

Any logging, disturbances, or grading done in the usable area or within the proposed setbacks will change the potential of using the area designated for a drainfield. Prior to moving forward with the development on the property, the Harnett County Health Department should be contacted to complete the necessary Construction Oversight and to issue an OP (Operations Permit) for the property once the septic system has been installed.

Conclusions

An IP (Improvement Permit) and CA (Construction Authorization) for this property can be issued with the site plan that is in Attachment 1. A CA permit will be required to secure a building permit for the property. The county issues an Operation Permit after the system has been installed to meet the specifications of the Authorization to Construct. Additional septic layouts have been or will be performed as needed. It will be critical to not disturb any of the proposed septic area or there is a risk that the IP and CA will be revoked. The LSS/AOWE Evaluation and attached documents were prepared *to this application is to be used to issue an Improvement Permit in accordance with G.S. 130A-335(a2) and (a3). The LSS/AOWE evaluation is being submitted pursuant to and meets the requirements of G.S. 130A-335(a2) and (a5).*


We appreciate the opportunity to assist you in this matter. Please contact us with any questions, concerns, or comments.

Sincerely,

A handwritten signature in black ink, appearing to read "Jeff V", is positioned above the printed name.

Jeff Vaughan, NC LSS

Permit #: _____



NC DEPARTMENT OF
**HEALTH AND
HUMAN SERVICES**

ROY COOPER • Governor

KODY H. KINSLEY • Secretary

MARK BENTON • Deputy Secretary for Health

SUSAN KANSAGRA • Assistant Secretary for Public Health

Division of Public Health

Submittal Includes: ☐ (a2) Improvement Permit ☐ (a2) Construction Authorization ☐ Fee \$ _____

IMPROVEMENT PERMIT FOR G.S. 130A-335(a2)

County: _____

PIN/Lot Identifier: _____

Issued To: _____

Property Location: _____

Subdivision (if applicable) _____ Lot #: _____ Block: _____ Section: _____

LSS Report Provided: Yes ☐ No ☐

If yes, name and license number of LSS: _____

New ☐

Expansion ☐

System Relocation ☐

Change of Use ☐

Proposed Structure: _____

Number of bedrooms: _____ Number of Occupants: _____ Other: _____

Design Wastewater Strength: ☐ domestic ☐ high strength ☐ industrial process

Proposed Design Daily Flow: _____ GPD Proposed LTAR (Initial): _____ Proposed LTAR (Repair): _____

Proposed Wastewater System Type*: _____ (Initial) Pump Required: ☐ Yes ☐ No ☐ May be required

Proposed Wastewater System Type*: _____ (Repair) Pump Required: ☐ Yes ☐ No ☐ May be required

**Please include system classification for proposed wastewater system types in accordance with 15A NCAC 18A .1961 Table V(a)*

Saprolite System (initial): ☐ Yes ☐ No Saprolite System (repair): ☐ Yes ☐ No

Fill System (Initial): ☐ Yes ☐ No If yes, specify: ☐ New ☐ Existing (when adding more than 6 inches of fill to system area provide a fill plan)

Fill System (repair): ☐ Yes ☐ No If yes, specify: ☐ New ☐ Existing (when adding more than 6 inches of fill to system area provide a fill plan)

Usable Soil Depth (Initial): _____ Usable Soil Depth (Repair): _____

Max. Trench Depth (Initial)*: _____ Max. Trench Depth (Repair)*: _____ ** Measured on the downhill side of the trench*

Artificial Drainage Required: ☐ Yes ☐ No If yes, please specify details: _____

Type of Water Supply: ☐ Private well ☐ Public well ☐ Shared well ☐ Municipal Supply ☐ Spring ☐ Other: _____

Drainfield location meets requirements of Rule .1945: Yes ☐ No ☐ Drainfield location meets requirements of Rule .1950: Yes ☐ No ☐

Permit valid for: ☐ Five years [site plan submitted pursuant to GS 130A-334(13a)] ☐ No expiration [plat submitted pursuant to GS 130A-334(7a)]

Permit conditions:

Licensed Soil Scientist Print Name: _____

Licensed Soil Scientist Signature: _____ Date: _____

The LSS evaluation is being submitted pursuant to and meets the requirements of G.S. 130A-335(a2).

See attached site sketch

NC DEPARTMENT OF HEALTH AND HUMAN SERVICES • DIVISION OF PUBLIC HEALTH

LOCATION: 5605 Six Forks Road, Building 3, Raleigh, NC 27609

MAILING ADDRESS: 1632 Mail Service Center, Raleigh, NC 27699-1632

www.ncdhhs.gov • TEL: 919-707-5854 • FAX: 919-845-3972

AN EQUAL OPPORTUNITY / AFFIRMATIVE ACTION EMPLOYER

This Section for Local Health Department Use OnlyInitial submittal received: _____ by _____
Date Initials

G.S. 130A-335(a3) states the following:

When an applicant for an Improvement Permit submits to a local health department an Improvement Permit application, the permit fee charged by the local health department, the common form developed by the Department, and a soil evaluation pursuant to subsection (a2) of this section, the local health department shall, within five business days of receiving the application, conduct a completeness review of the submittal. A determination of completeness means that the Improvement Permit includes all of the required components. If the local health department determines that the Improvement Permit is incomplete, the local health department shall notify the applicant of the components needed to complete the Improvement Permit. The applicant may submit additional information to the local health department to cure the deficiencies in the Improvement Permit. The local health department shall make a final determination as to whether the Improvement Permit is complete within five business days after the local health department receives the additional information from the applicant. If the local health department fails to act within any period set out in this subsection, the applicant may treat the failure to act as a determination of completeness. The Department shall develop a common form for use as the Improvement Permit.

The review for completeness of this Improvement Permit was conducted in accordance with G.S. 130A-335(a3). This Improvement Permit is determined to be:

☐ Incomplete (If box is checked, information in this section is required.)

The following items are missing:

_____Copies of this were sent to the LSS and the Applicant on _____
Date

State Authorized Agent: _____ Date: _____

☐ Complete

State Authorized Agent: _____ Date: _____

This Improvement Permit is issued pursuant to G.S. 130A-335 (a2) and (a3) using the signed and sealed LSS/LG evaluation(s) attached here. The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This permit is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

The Department, the Department's authorized agents, and the local health departments shall be discharged and released from any liabilities, duties, and responsibilities imposed by statute or in common law from any claim arising out of or attributed to evaluations, submittals, or actions from a licensed soil scientist or licensed geologist pursuant to GS 130A-335(a2).

Improvement Permit Expiration Date: _____

See attached site sketch

Re-submittal of Improvement Permit

LHD USE ONLY: This IP resubmittal received: _____ by _____
Date *Initials*

The following items are being resubmitted pursuant to G.S. 130A-335(a3) for issuance of the Improvement Permit:

I, _____ hereby attest that the information required to be included with this re-submittal
Licensed Soil Scientist (Print Name)
is accurate and complete to the best of my knowledge and that the proposed Improvement Permit meets all applicable federal, State, and local laws, regulations, rules, and ordinances.

Signature of Licensed Soil Scientist

Date

The section below is for Local Health Department use after submittal of items noted as missing above.

LHD Follow-up Completeness Review of Improvement Permit

The review for completeness of this Improvement Permit re-submittal was conducted in accordance with G.S. 130A-335(a3). This Improvement Permit is determined to be:

☐ Incomplete (If box is checked, information in this section is required.)

The following items are missing:

Copies of this were sent to the LSS and the Applicant on _____
Date

State Authorized Agent: _____

Date: _____

☐ Complete

State Authorized Agent: _____

Date: _____

CONSTRUCTION AUTHORIZATION FOR G.S. 130A-335(a2)

County: _____

PIN/Lot Identifier: _____

Issued To: _____

Property Location: _____

AOWE/PE Plans/Evaluations Provided: Yes ☐ No ☐ If yes, name and license number of AOWE/PE: _____

Facility Type: _____

☐ New ☐ Expansion ☐ Repair ☐ System Relocation ☐ Change of Use

Basement? ☐ Yes ☐ No Basement Fixtures? ☐ Yes ☐ No

Type of Wastewater System* _____ (Initial) _____ (Repair)

**Please include system classification for proposed wastewater system types in accordance with 15A NCAC 18A .1961 Table V(a)*

Design Daily Flow: _____ GPD Wastewater Strength: ☐ domestic ☐ high strength ☐ industrial process

Session Law 2014-120 Section 53, Engineering Design Utilizing Low-flow Fixtures and Low-flow Technologies? ☐ Yes ☐ No
(if yes, please provide engineering documentation)

Installation Requirements/Conditions

Septic Tank Size: _____ gallons Total Trench/Bed Length: _____ feet Trench/Bed Spacing: _____ feet on center

Trench/Bed Width: _____ inches LTAR: _____ gpd/ft²

Soil Cover: _____ inches Slope Corrected Maximum Trench/Bed Depth[†]: _____ inches ** Measured on the downhill side of the trench*

Aggregate Depth: _____ inches above pipe _____ inches below pipe _____ inches total

Pump Tank Size (if applicable): _____ gallons Requires more than 1 pump? ☐ Yes ☐ No

Pump Requirements: _____ ft. TDH vs. _____ GPM Grease Trap Size (if applicable): _____ gallons

Distribution Method: ☐ Serial ☐ D-Box or Parallel ☐ Pressure Manifold(s) ☐ LPP ☐ Other: _____

Artificial Drainage Required: Yes ☐ No ☐ If yes, please specify details: _____

Legal Agreements (If the answer is "Yes" to any type of legal agreements, please attach a copy of the agreement.)

Multi-party Agreement Required [.1937(h)]: ☐ Yes ☐ No

Easement, Right-of-Way, or Encroachment Agreement Required [.1938(j)]: ☐ Yes ☐ No

Declaration of Restrictive Covenants: ☐ Yes ☐ No

Pre-Construction Conference Required: Yes ☐ No ☐

Conditions: _____

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by reference into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

AOWE/PE Print Name: _____

Expiration Date: _____

AOWE/PE Signature: _____

Date: _____

This AOWE/PE submittal is pursuant to and meets the requirements of G.S. 130A-335(a2) and (a5).



See attached site sketch

This Section for Local Health Department Use OnlyInitial submittal received: _____ by _____
Date Initials

G.S. 130A-335(a5) states the following:

When an applicant for a Construction Authorization, or an Improvement Permit and Construction Authorization together, submits a Construction Authorization, or an Improvement Permit and Construction Authorization application together, the permit fee charged by the local health department, the common form developed by the Department, and any necessary signed and sealed plans or evaluations conducted by a person licensed pursuant to Chapter 89C of the General Statutes as a licensed engineer or a person certified pursuant to Article 5 of Chapter 90A of the General Statutes as an Authorized On-Site Wastewater Evaluator, the local health department shall, within five business days of receiving the application, conduct a completeness review of the submittal. A determination of completeness means that the Construction Authorization or Improvement Permit and Construction Authorization includes all of the required components. If the local health department determines that the Construction Authorization or Improvement Permit and Construction Authorization is incomplete, the local health department shall notify the applicant of the components needed to complete the Construction Authorization or Improvement Permit and Construction Authorization. The applicant may submit additional information to the local health department to cure the deficiencies in the Construction Authorization or Improvement Permit and Construction Authorization. The local health department shall make a final determination as to whether the Construction Authorization or Improvement Permit and Construction Authorization is complete within five business days after the local health department receives the additional information from the applicant. If the local health department fails to act within any period set out in this subsection, the applicant may treat the failure to act as a determination of completeness. The applicant may apply for the building permit for the project upon the decision of completeness of the Construction Authorization or Improvement Permit and Construction Authorization by the local health department or if the local health department fails to act within five business days. The Authorized On-Site Wastewater Evaluator or licensed engineer submitting the evaluation pursuant to this subsection may request that the local health department revoke or suspend the Construction Authorization or Improvement Permit and Construction Authorization for cause. Upon written request of the Authorized On-Site Wastewater Evaluator or licensed engineer, the local health department shall suspend or revoke the Construction Authorization or Improvement Permit and Construction Authorization pursuant to G.S. 130A-23. The Department shall develop a common form for use as the Construction Authorization.

The review for completeness of this Construction Authorization was conducted in accordance with G.S. 130A-335(a5). This

Construction Authorization is determined to be:

☐ Incomplete (If box is checked, information in this section is required.)The following items are missing: _____
_____Copies of this were sent to the AOWE/PE and the Applicant on _____
Date

State Authorized Agent: _____ Date: _____

☐ Complete

State Authorized Agent: _____ Date of Issuance: _____

This Construction Authorization is issued pursuant to G.S. 130A-335(a2) and (a5) using the signed and sealed plans or evaluations attached here. This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be affected by a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

The Department, the Department's authorized agents, and the local health departments shall be discharged and released from any liabilities, duties, and responsibilities imposed by statute or in common law from any claim arising out of or attributed to plans, evaluations, preconstruction conference findings, submittals, or actions from a person licensed pursuant to Chapter 89C of the General Statutes as a licensed engineer or a person certified pursuant to Article 5 of Chapter 90A of the General Statutes as an Authorized On-Site Wastewater Evaluator in GS 130A-335(a2), (a5), and (a7). The Department, the Department's authorized agents, and the local health departments shall be responsible and bear liability for their actions and evaluations and other obligations under State law or rule, including the issuance of the operations permit pursuant to GS 130A-337.

Construction Authorization Expiration Date: _____

See attached site sketch

Re-submittal of Construction Authorization

LHD USE ONLY: This CA resubmittal received: _____ by _____
Date Initials

The following items are being resubmitted pursuant to G.S. 130A-335(a5) for issuance of the Construction Authorization:

I, _____ hereby attest that the information required to be included with this re-submittal
Authorized Onsite Wastewater Evaluator (Print Name)
is accurate and complete to the best of my knowledge and that the proposed Construction Authorization meets all applicable federal, State, and local laws, regulations, rules, and ordinances.

Signature of Authorized On-Site Wastewater Evaluator

Date

The section below is for Local Health Department use after submittal of items noted as missing above.

LHD Follow-up Completeness Review of Construction Authorization

The review for completeness of this Construction Authorization re-submittal was conducted in accordance with G.S. 130A-335(a5). This Construction Authorization is determined to be:

☐ Incomplete (If box is checked, information in this section is required.)

The following items are missing:

Copies of this were sent to the AOWE/PE and the Applicant on _____
Date

State Authorized Agent: _____

Date: _____

☐ Complete

State Authorized Agent: _____

Date: _____

Comments: _____

LEGEND

LANDSCAPE POSITION	SOIL GROUP	SOIL TEXTURE	CONVENTIONAL LTAR (gpd/ft²)	SAPROLITE LTAR (gpd/ft²)	LPP LTAR (gpd/ft²)	MINERALOGY/ CONSISTENCE		STRUCTURE
CC (Concave slope)	I	S (Sand)	0.8 - 1.2	0.6 - 0.8	0.4 -0.6	MOIST	WET	SG (Single grain)
CV (Convex Slope)		LS (Loamy sand)		0.5 -0.7		Lo (Loose)	NS (Non-sticky)	M (Massive)
D (Drainage way)	II	SL (Sandy loam)	0.6 - 0.8	0.4 -0.6	0.3 - 0.4	VFR (Very friable)	SS (Slightly sticky)	GR (Granular)
FP (Flood plain)		L (Loam)		0.2 - 0.4		FR (Friable)	S (Sticky)	SBK (Subangular blocky)
FS (Foot slope)	III	SiL (Silt loam)	0.3 - 0.6	0.1 - 0.3	0.15 - 0.3	FI (Firm)	VS (Very sticky)	ABK (Angular blocky)
H (Head slope)		SCL (Sandy clay loam)		0.05 - 0.15**		VFI (Very firm)	NP (Non-plastic)	PR (Prismatic)
L (Linear Slope)		CL (Clay loam)		None		EFI (Extremely firm)	SP (Slightly plastic)	PL (Platy)
N (Nose slope)		SiCL (Silty clay loam)					P (Plastic)	
R (Ridge/summit)		Si (Silt)						
S (Shoulder slope)		IV				SC (Sandy clay)	0.1 - 0.4	
T (Terrace)	SiC (Silty clay)		EXP (Expansive)					
TS (Toe Slope)	C (Clay)							
		O (Organic)	None					

* Adjust LTAR due to depth, consistence, structure, soil wetness, landscape, position, wastewater flow and quality.

**Sandy clay loam saprolite can only be used with advanced pretreatment in accordance with 15A NCAC 18E .1200.

HORIZON DEPTH

In inches below natural soil surface

DEPTH OF FILL

In inches from land surface

RESTRICTIVE HORIZON

Thickness and depth from land surface

SAPROLITE

S(suitable) or U(unsuitable); Evaluation of saprolite shall be by pits.

SOIL WETNESS

Inches from land surface to free water or inches from land surface to soil colors with chroma 2 or less - record Munsell color chip designation


CLASSIFICATION

S (Suitable) or U (Unsuitable)

Show profile locations and other site features (dimensions, reference or benchmark, and North).

BIRCHWOOD TRAILS - LOT 45

Project Location	Olive Branch Rd
	Fuquay Varina, NC 27526
	Harnett County
	PIN: ----
Project Owner	Ballentine Associates, PA
	221 Providence Rd
	Chapel Hill, NC 27514
	919-929-0481
	dillons@ballentineassociates
Project Consultant	Jeff Vaughan, L.S.S
	(919) 367-6313
	Trent Bostic
	(919) 367-6322
	Agri-Waste Technology, Inc.
	501 N. Salem Street, Suite 203
	Apex, NC 27502
	(919) 859-0669
	(919) 233-1970 Fax
System Overview	Single Family Residence
	Four (4) Bedroom, 480 gpd
	Pressure Manifold Distribution
	Accepted/Innovative Trench Product



VICINITY MAP

Sheet Index

Sheet 1	Cover Sheet
Sheet 2	Property Layout
Sheet 3	Primary Drain Field
Sheet 4	Repair Drain Field
Sheet 5	Detail Sheet 1
Sheet 6	Detail Sheet 2
Sheet 7	Excavation Safety



AWT
Engineers and Soil Scientists
Agri-Waste Technology, Inc.
501 N. Salem Street, Suite 203 Apex,
North Carolina 27502
919-859-0669 www.agriwaste.com

Ballentine Associates, PA
Birchwood Trails - Lot 45



Project Location:
Olive Branch Rd
Fuquay Varina, NC 27526
Harnett County
PIN: ----

Project Owner:
Ballentine Associates, PA
221 Providence Rd
Chapel Hill, NC 27514
919-929-0481
dillons@ballentineassociates

NC ONSITE WASTEWATER
EVALUATOR SEAL



REV.	ISSUED DATE	DESCRIPTION
SHEET TITLE		
Cover Sheet		
DRAWN BY: H. Clapp	CREATED ON: 1/31/2024	
REVISED BY: ####	REVISED ON: ####	
RELEASED BY: ####	RELEASED ON: ####	
DRAWING NUMBER		
WW-1		



REV.	ISSUED DATE	DESCRIPTION

SHEET TITLE


Property Layout

DRAWN BY: H. Clapp	CREATED ON: 1/31/2024
REVISED BY: ####	REVISED ON: ####
RELEASED BY: ####	RELEASED ON: ####

DRAWING NUMBER
WW-2

1. Clear all trees less than 8" in diameter (measured at a height 3' from soil surface) from the drainfield.
2. Vegetation that will re-grow from a cut stump shall be stumped or pulled from the ground. Stumps shall not be pushed over.
3. Drainfield area shall be cleared of all leaves, pine straw, debris, etc. The accumulated material shall be removed from the drainfield.
4. In clayey soils, sides of trenches shall be raked and limed per manufacturer's instructions.
5. Supply lines shall be installed with a minimum of 18" cover.
6. The trenches shall be backfilled appropriately so that no low areas are present.
7. Apply lime over the drainfield area as needed. Seed fine fescue over the drainfield at the rate recommended by the seed manufacturer. Hand rake the seed into the soil surface. Straw the seeded area at the rate of 1.5-2 bales per 1000 sq. ft.

DRAINFIELD INFO. - Primary						
Proposed Type of System/Distribution:		<i>Pump to Pressure Manifold using Chambers</i>				
Line No.	Flag Color	Line Length (ft)	Tap	Flow (gpm)	Flow/Foot (gpm/ft)	Line L.T.A.R.
1	blue	52	1/2in SCH 40, Split	3.56	0.068	0.513
2	White	56	1/2in SCH 40, Split	3.56	0.063	0.476
3	purple	96	1/2in SCH 40	7.11	0.074	0.556
4	red	96	1/2in SCH 40	7.11	0.074	0.556
	Total	300	Total	21.33	Avg.	0.525



1 Primary Drainfield
WW-3 SOURCE: Agri-Waste Technology, Inc.

Ballentine Associates, PA
Birchwood Trails - Lot 45

Project Location:
 Olive Branch Rd
 Fuquay Varina, NC 27526
 Harnett County
 PIN: ----

Project Owner:
 Ballentine Associates, PA
 221 Providence Rd
 Chapel Hill, NC 27514
 919-929-0481
 dillons@ballentineassociates




REV.	ISSUED DATE	DESCRIPTION
SHEET TITLE		
Primary Drainfield		
DRAWN BY: H. Clapp		CREATED ON: 1/31/2024
REVISED BY: ####		REVISED ON: ####
RELEASED BY: ####		RELEASED ON: ####

DRAWING NUMBER
WW-3


General Drainfield Notes:

1. Clear all trees less than 8" in diameter (measured at a height 3' from soil surface) from the drainfield.
2. Vegetation that will re-grow from a cut stump shall be stumped or pulled from the ground. Stumps shall not be pushed over.
3. Drainfield area shall be cleared of all leaves, pine straw, debris, etc. The accumulated material shall be removed from the drainfield.
4. In clayey soils, sides of trenches shall be raked and limed per manufacturer's instructions.
5. Supply lines shall be installed with a minimum of 18" cover.
6. The trenches shall be backfilled appropriately so that no low areas are present.
7. Apply lime over the drainfield area as needed. Seed fine fescue over the drainfield at the rate recommended by the seed manufacturer. Hand rake the seed into the soil surface. Straw the seeded area at the rate of 1.5-2 bales per 1000 sq. ft.

DRAINFIELD INFO. - Repair						
Proposed Type of System/Distribution:			Pump to Pressure Manifold using EZflow			
Line No.	Flag Color	Line Length (ft.)		Flow (gpm)	Flow/Foot (gpm/ft)	Line L.T.A.R.
5	yellow	100	3/4in SCH 80	10.10	0.101	0.542
6	blue	80	1/2in SCH 40	7.11	0.089	0.477
7	white	70	1/2in SCH 40	7.11	0.102	0.545
8	purple	30	1/2in SCH 80, Split	2.74	0.091	0.490
9	red	30	1/2in SCH 80, Split	2.74	0.091	0.490
Total		310	Total	29.8	Avg.	0.509




REV.	ISSUED DATE	DESCRIPTION
SHEET TITLE		
Repair Drainfield		
DRAWN BY:	CREATED ON:	
H. Clapp	1/31/2024	
REVISED BY:	REVISED ON:	
####	####	
RELEASED BY:	RELEASED ON:	
####	####	
DRAWING NUMBER		
WW-4		



Septic Tank

SOURCE: Shoaf Precast Septic, Inc.




Pump Tank (or equiv. tank with 1-day storage)

SOURCE: Shoaf Precast Septic, Inc.

NOTES

- Installation to follow all NC DHHS and Harnett County applicable rules and regulations.
- Harnett County to perform construction inspections and final system certification.
- Septic Tank to have approved effluent filter.
- Contractor to abide by all safety regulations during system installation.
- Contractor shall backfill around all access areas such that storm water is shed away from potential entry points.
- Invert elevations of all components to be verified in field by contractor to insure proper operation.
- All system piping to be SCH40 PVC (except where noted).
- All gravity elbows to be long radius or long sweeping type elbows.
- Actual installation and placement of treatment system to be overseen by Contractor.
- Tanks to be set on 6" minimum gravel base. Use #5 or #57 stone for base.

- Contractor to seed and/or mulch disturbed areas to coincide with existing landscape. Area shall not be left with uncovered soil.
- Mount Control Panel a minimum of 24" above grade.
- Power to panel to be installed by licensed electrician per code. One 15-amp circuit and one 20-amp circuit with individual neutrals to be run from house to control panel.
- All risers to have cast-in-place tank adapters and be single-piece riser. Risers to extend 6" above soil surface and be designed to prevent surface water inflow.
- Backfill around tank(s) shall be gravel or tank hole shall be over-excavated a minimum of 2' in all directions to allow for mechanical tamping of backfill.
- All penetrations to be sealed.
- Spigot to be located on outside of building within 50' of tanks.
- All pressure lines to maintain 18" min. cover.
- Contractor to adjust tank placement to meet site constraints.



Riser Safety Nets

SOURCE: SIM-TECH, Inc.



Engineers and Soil Scientists

Agri-Waste Technology, Inc.
501 N. Salem Street, Suite 203
Apex, North Carolina 27502
919-859-0669
www.agriwaste.com

Ballentine Associates, PA
Birchwood Trails - Lot 45

Project Location:
Olive Branch Rd
Fuquay Varina, NC 27526
Harnett County
PIN: ---

Project Owner:
Ballentine Associates, PA
221 Providence Rd
Chapel Hill, NC 27514
919-929-0481
dillons@ballentineassociates.com



REV. ISSUED DATE DESCRIPTION

SHEET TITLE

Detail Sheet 1







DRAWN BY: H. Clapp
CREATED ON: 1/31/2024

REVISED BY: #####
REVISED ON: #####

RELEASED BY: #####
RELEASED ON: #####

DRAWING NUMBER

WW-5



REV.	ISSUED	DATE	DESCRIPTION
------	--------	------	-------------

DRAWN BY: H. Clapp	CREATED ON: 1/31/2024
REVISED BY: ####	REVISED ON: ####
RELEASED BY: ####	RELEASED ON: ####

The employer must comply with the trenching and excavation requirements of 29 CFR 1926.651 and 1926.652 or comparable OSHA-approved state plan requirements.

OSHA standards require that a competent person inspect trenches daily and as conditions change before worker entry to ensure elimination of excavation hazards. A competent person is an individual who is capable of identifying existing and predictable hazards or working conditions that are hazardous, unsanitary, or dangerous to workers, soil types and protective systems required, and who is authorized to take prompt corrective measures to eliminate these hazards and conditions.

OSHA standards require safe access and egress to all excavations, including ladders, steps, ramps, or other safe means of exit for employees working in trench excavations 4 feet (1.22 meters) or deeper. These devices must be located within 25 feet (7.6 meters) of all workers.

Heavy equipment and trucks should stay as far as possible from the edge of any trench. Always use pads under stabilizers to minimize ground pressures that could lead to failures.

"Saturated soil" means a soil in which the voids are filled with water. Saturation does not require flow. Saturation, or near saturation, is necessary for the proper use of instruments such as a pocket penetrometer or shear vane.

"Submerged soil" means soil which is underwater or is free seeping.





- (i) The soil is fissured; or
- (ii) The soil is subject to vibration from heavy traffic, pile driving, or similar effects; or
- (iii) The soil has been previously disturbed; or
- (iv) The soil is part of a sloped, layered system where the layers dip into the excavation on a slope of four horizontal to one vertical (4H:1V) or greater; or
- (v) The material is subject to other factors that would require it to be classified as a less stable material.

- (i) Cohesive soil with an unconfined compressive strength of 0.5 tsf (48 kPa) or less; or
- (ii) Granular soils including gravel, sand, and loamy sand; or
- (iii) Submerged soil or soil from which water is freely seeping; or
- (iv) Submerged rock that is not stable, or
- (v) Material in a sloped, layered system where the layers dip into the excavation or a slope of four horizontal to one vertical (4H:1V) or steeper.

"Wet soil" means soil that contains significantly more moisture than moist soil, but in such a range of values that cohesive material will slump or begin to flow when vibrated. Granular material that would exhibit cohesive properties when moist will lose those cohesive properties when wet.

- (1) Classification of soil and rock deposits. Each soil and rock deposit shall be classified by a competent person as Stable Rock, Type A, Type B, or Type C in accordance with the definitions set forth in paragraph (b) of this appendix.
- (2) Basis of classification. The classification of the deposits shall be made based on the results of at least one visual and at least one manual analysis. Such analyses shall be conducted by a competent person using the tests described in paragraph (d) below, or in other recognized methods of soil classification and testing such as those adopted by the American Society for Testing Materials, or the U.S. Department of Agriculture textural classification system.
- (3) Visual and manual analyses. The visual and manual analyses, such as those noted as being acceptable in paragraph (d) of this appendix, shall be designed and conducted to provide sufficient quantitative and qualitative information as may be necessary to identify properly the properties, factors, and conditions affecting the classification of the deposits.
- (4) Layered systems. In a layered system, the system shall be classified in accordance with its weakest layer. However, each layer may be classified individually where a more stable layer lies under a less stable layer.
- (5) Reclassification. If, after classifying a deposit, the properties, factors, or conditions affecting its classification change in any way, the changes shall be evaluated by a competent person. The deposit shall be reclassified as necessary to reflect the changed circumstances.

- (i) Observe samples of soil that are excavated and soil in the sides of the excavation. Estimate the range of particle sizes and the relative amounts of the particle sizes. Soil that is primarily composed of fine-grained material is cohesive material. Soil composed primarily of coarse-grained sand or gravel is granular material.
- (ii) Observe soil as it is excavated. Soil that remains in clumps when excavated is cohesive. Soil that breaks up easily and does not stay in clumps is granular.
- (iii) Observe the side of the opened excavation and the surface area adjacent to the excavation. Crack-like openings such as tension cracks could indicate fissured material. If chunks of soil spall off a vertical side, the soil could be fissured. Small spalls are evidence of moving ground and are indications of potentially hazardous situations.
- (iv) Observe the area adjacent to the excavation and the excavation itself for evidence of existing utility and other underground structures, and to identify previously disturbed soil.
- (v) Observe the opened side of the excavation to identify layered systems. Examine layered systems to identify if the layers slope toward the excavation. Estimate the degree of slope of the layers.
- (vi) Observe the area adjacent to the excavation and the sides of the opened excavation for evidence of surface water, water seeping from the sides of the excavation, or the location of the level of the water table.
- (vii) Observe the area adjacent to the excavation and the area within the excavation for sources of vibration that may affect the stability of the excavation face.



REV.	ISSUED DATE	DESCRIPTION
SHEET TITLE		
Excavation Safety		
DRAWN BY: H. Clapp		CREATED ON: 1/31/2024
REVISED BY: ####		REVISED ON: ####
RELEASED BY: ####		RELEASED ON: ####
DRAWING NUMBER		
WW-7		

Septic System Design - Summary Page



Agri-Waste Technology, Inc.
501 N Salem Street, Suite 203, Apex, NC 27502
agriwaste.com | 919.859.0669

Project Manager:

Jeff Vaughan, PhD, LSS
jvaughan@agriwaste.com
919-859-0669

Engineer:

Heath Clapp
hclapp@agriwaste.com

Project: Birchwood Trails, Lot 45
Property: Olive Branch Road,
Fuquay Varina, NC 27526

Date: 1/31/2024

County: Harnett

Subdiv.:

Lot #: 45

Permit #:

Owner: Ballentine Associates, PA
Address: 221 Providence Road,
Chapel Hill, NC 27514

Type of System: III b

Phone: 919-929-0481

Email: dillons@ballentineassociates.com

PIN: 0

EHS:

Soil Parameters

Soil Evaluation By:

Special Conditions/Notes:

LTAR: 0.400 gpd/ft²

Design Parameters

Type of Establishment: Residence, 5 or fewer bedrooms

Unit: Bedroom

of Units: 4

Septic Tank Specifications

Min. Tank Capacity: 1,000 gal

Actual Tank Volume: 1,250 gal

Tank Manufacturer: Shoaf

Tank Model: TS 1250 STB

	Exterior	Interior
Length:	125.5	119.5 in.
Width:	65.5	59.5 in.
Depth:	62.0	54.5 in.

Primary Drainfield Specifications

Type of Distribution: Parallel Pressure Manifold

Trench Media: Chambers

Trench Width: 3 ft

Trench Depth: 22 in.

(or as specified on permit)

Trench Bottom Area: 1200 ft²

Minimum Drain Line: 300 ft

Actual Drain Line: 305 ft

Number of Lines: 5

Minimum Line Spacing: 9 ft O.C.

Wastewater Treatment System Design Calculations

Project: Birchwood Trails, Lot 45
Location: Olive Branch Road,
Fuquay Varina, NC 27526
County: Harnett

Septic Tank Sizing

Daily Flow Estimate:

Unit	# of Units	Flow/Unit	Flow/Day
Bedroom	4	120	480
Q=			480

gpd

Septic Tank Minimum Capacity:

Per NCAC T15A:18A .1952(b)(1):

For individual residences with 4 bedrooms,

Minimum Liquid Capacity (V)= 1,000 gal

Septic Tank Specs:

Manufacturer: Shoaf
Model: TS 1250 STB
Volume: 1,250 gal
Weight: 11,000 lbs

	Exterior	Interior	
Length:	125.5	119.5	in.
Width:	65.5	59.5	in.
Depth:	62.0	54.5	in.

Shape of Risers: Circular

Diameter: 2.00 ft

Pump Tank Storage & Float Settings

Project: Birchwood Trails, Lot 45
Location: Olive Branch Road,
Fuquay Varina, NC 27526
County: Harnett

Tank Manufacturer Shoaf
Tank Model TS 1275 PT

Interior Height (in.) 60.5 in.
Avg. Storage 21.07 gal/in.

Primary System

Elevations, measured from bottom towards top (0 = Interior Bottom of Tank):

Top of pump (including 4" block)	14.1 in.	(Pump height = 10 1/16")
Pump Off	16.0 in.	
Pump On	22.5 in.	(set for dose volume)
Alarm On	28.5 in.	(6 in. above On Float)

Emergency Storage Available

Pump Tank 674 gal

Days of Storage 1.40 days

(determined from "interior top of tank" - "High Water Alarm")

Repair System

Elevations, measured from bottom towards top (0 = Interior Bottom of Tank):

Top of pump (including 4" block)	16.1 in.	(Pump height = 12 1/16")
Pump Off	18.0 in.	
Pump On	25.0 in.	(set for dose volume)
Alarm On	31.0 in.	(6 in. above On Float)

Emergency Storage Available

Pump Tank 622 gal

Days of Storage 1.29 days

(determined from "interior top of tank" - "High Water Alarm")

ELEVATIONS

Project: Birchwood Trails, Lot 45

Location: Olive Branch Road,
Fuquay Varina, NC 27526

County: Harnett

Benchmark 0
BM Elev 0 ft

Septic Tank 1,250 gal

Ground Surface	291.50	ft
Depth of Soil Cover	16 in.	1.33 ft
Overall Ht of Tank	61.5 in.	5.13 ft
Elev, Base of Tank		285.04 ft
Ht to 4" Inlet Invert	50 in.	4.17 ft
Elev, 4" Inlet Invert		289.21 ft
Ht to 4" Outlet Invert	48 in.	4.00 ft
Elev, 4" Outlet Invert		289.04 ft
Gravel Base	6 in.	0.50 ft
Elev, Bot of Excavation		284.54 ft

Pump Tank 1275 gal

Ground Surface	291.50	ft
Depth of Soil Cover	18 in.	1.50 ft
Overall Ht of Tank	67.5 in.	5.63 ft
Elev, Base of Tank		284.38 ft
Ht to 4" Inlet Invert	54.5 in.	4.54 ft
Elev, 4" Inlet Invert		288.92 ft
Ht to 2" Outlet Invert	58 in.	4.83 ft
Elev, 2" Outlet Invert		289.21 ft
Gravel Base	6 in.	0.50 ft
Elev, Bot of Excavation		283.88 ft

ST Inlet Pipe

Grade @ Stub-out	291.5	ft
Depth of Stub-out, top	1.5	ft
Elev, Stub-out Invert		289.65 ft
Elev @ ST Inlet Invert		289.21 ft
Length	10	ft
Slope		4.4 %

Pipe, ST to PT

ID	4 in.	0.33 ft
OD	4.5 in.	0.38 ft
Elev, ST Outlet Invert		289.04 ft
Elev, PT Inlet Invert		288.92 ft
Length	4	ft
Slope		3.1 %
Cover over inlet pipe		1.94 ft

Pump Reqmt.

Floor Thickness	4 in.	0.33 ft
Elev, Pump Tank Floor		284.71 ft
Pump Block Ht.	4 in.	0.33 ft
Elev, Pump Intake		285.04 ft

Grade @ Primary Manifold	292.50	ft
Grade @ Repair Manifold	293.75	ft
Min. Cover	18 in.	1.50 ft
Max Elev, Repair		292.25 ft
Elev Diff, Repair		7.21 ft

Drainfield Design

Project	Birchwood Trails, Lot 45
Location	Olive Branch Road, Fuquay Varina, NC 27526
County	Harnett

Drainfield Sizing

Primary			
LTAR	0.4 gpd/ft ²	Type of Drainfield Media	
Daily Design Flow	480 gpd	Chambers	
Req. Drainfield Area	1,200 ft ²	Required Drainline	
Trench Width, Eff.	3 ft	After 25% Reduction	300 ft
Required Drainline	400 ft	Minimum Line Spacing	9 ft (O.C.)

Repair			
LTAR	0.4 gpd/ft ²	Type of Drainfield Media	
Daily Design Flow	480 gpd	EZflow	
Req. Drainfield Area	1,200 ft ²	Required Drainline	
Trench Width, Eff.	3 ft	After 25% Reduction	300 ft
Required Drainline	400 ft	Minimum Line Spacing	9 ft (O.C.)

Drainfield Layout

Line	Use	Flag Color	Elevation (ft)	Line Length (ft)	Used as Primary (ft)	Used as Repair (ft)
1	Layout Line	blue		52	52.0	
2	Layout Line	White		56	56.0	
3	Layout Line	purple		96	96.0	
4	Layout Line	red		96	96.0	
5	Layout Line	yellow		100		100.0
6	Layout Line	blue		80		80.0
7	Layout Line	white		70		70.0
8	Layout Line	purple		30		30.0
9	Layout Line	red		30		30.0
Total				610	300	310
Count				9	4	5

Note: Line length totals are shown to the nearest foot.
For Chambers or Low-profile Chambers:
Effective trench lengths are shown. Add 1' for total installation length.

PRESSURE MANIFOLD DESIGN (Primary)

Site Information

Project: Birchwood Trails, Lot 45
Location: Oliva Branch Road,
Fuquay Varina, NC 27526
County: Harnett

Design Information

Estimated Daily Flow	480 gal/day
L.T.A.R.	0.4 gal/day/ft ²
L.T.A.R. + 5%	0.420 gal/day/ft ²
Trench Width	3 ft.
Line Length Required	400 ft.
Length after 25% Reduction	300 ft
L.T.A.R. Reduced	0.533 gal/day/ft ²
L.T.A.R. Reduced + 5%	0.560 gal/day/ft ²

DRAINFIELD INFO. - Primary						
Proposed Type of System/Distribution: Pump to Pressure Manifold using Chambers						
Line No.	Flag Color	Line Length (ft)	Tap	Flow (gpm)	Flow/Foot (gpm/ft)	Line L.T.A.R.
1	blue	52	1/2in SCH 40, Split	3.56	0.068	0.513
2	White	56	1/2in SCH 40, Split	3.56	0.063	0.476
3	purple	96	1/2in SCH 40	7.11	0.074	0.556
4	red	96	1/2in SCH 40	7.11	0.074	0.556
Total		300	Total	21.33	Avg.	0.525
<i>Note: Line lengths are calculated in 5' increments to reflect use of EZflow product.</i>						
Total Run Time	22.50 min.					
Drainfield Capacity	195.9 gal					
% of Drainfield Cap	69.9% (Req. Range 66-75%)					
Dose Volume	136.9 gal/dose					
Run Time/Dose	6.4 minutes Range 5-7 minutes unless uphill, checked					
Volume/depth	21.07 gal/in. (Per tank manufacturer's specifications)					
Estimated Drawdown	6.50 in.					
Manifold Box						
Number of Taps	3 with 1 Split(s)					
Manifold Length	3.0 ft. (approximate)					

PRESSURE MANIFOLD SYSTEM DESIGN (Repair)

Site Information

Project: Birchwood Trails, Lot 45
Location: Olive Branch Road,
 Fuquay Varina, NC 27526
County: Harnett

Design Information

Estimated Daily Flow	480 gal/day
L.T.A.R.	0.4 gal/day/ft ²
L.T.A.R. + 5%	0.420 gal/day/ft ²
Trench Width	3 ft.
Line Length Required	400 ft.
Length after 25% Reduction	300 ft
L.T.A.R. Reduced	0.533 gal/day/ft ²
L.T.A.R. Reduced + 5%	0.560 gal/day/ft ²

DRAINFIELD INFO. - Repair						
Proposed Type of System/Distribution: Pump to Pressure Manifold using EZflow						
Line No.	Flag Color	Line Length (ft.)		Flow (gpm)	Flow/Foot (gpm/ft)	Line L.T.A.R.
5	yellow	100	3/4in SCH 80	10.10	0.101	0.542
6	blue	80	1/2in SCH 40	7.11	0.089	0.477
7	white	70	1/2in SCH 40	7.11	0.102	0.545
8	purple	30	1/2in SCH 80, Split	2.74	0.091	0.490
9	red	30	1/2in SCH 80, Split	2.74	0.091	0.490
Total		310	Total	29.8	Avg.	0.509
<i>Note: Line lengths are calculated in 5' increments to reflect use of EZflow product.</i>						

Total Run Time	16.11 min.
Drainfield Capacity	202.4 gal
% of Drainfield Cap	72.9% (Req. Range 66-75%)
Dose Volume	147.6 gal/dose
Run Time/Dose	5.0 minutes Range 5-7 minutes unless uphill, checked
Volume/depth	21.07 gal/in. (Per tank manufacturer's specifications)
Estimated Drawdown	7.00 in.

Manifold Box	
Number of Taps	4 with 1 Split(s)
Manifold Length	3.5 ft. (approximate)

PUMP DESIGN

System (initial/repair): **Primary**

Project: Birchwood Trails, Lot 45
Location: Olive Branch Road,
Fuquay Varina, NC 27526
County: Harnett

Friction Losses

Suction Head	0 ft	(submersible 0)
Elev. Difference (highest point from pump)	5.96 ft	
Design Pressure At Outlet	2 ft	
Supply Line - 2" Schedule 40 PVC		
Pipe Diameter, Nominal	2 in.	
Pipe Diameter (ID)	2.047 in.	
Pipe Length	47 ft	
Pipe Length for Fittings	4.7 ft	
Equivalent Length	51.7 ft	
Estimated Friction Loss in Supply Line	0.45 ft	
Flow	21.33 gpm	
Velocity	2.08 ft/sec	
Meets requirement that $2 \text{ ft/s} < v < 5 \text{ ft/s}$.		
Friction Loss - Taps/Special Fittings	3.5 ft	
TOTAL		11.91 ft.

Flow for Anti-Siphon Hole


Hole Diameter 3/16 in.
Hole Flowrate 1.43 gpm

Pump Efficiency 0.7 (assumed, typical)
Motor Efficiency 0.9 (assumed for electric pumps)
Flow 22.76 gpm

Required Horsepower 0.11 hp
TDH 11.91 ft

Pump Selection

Manufacturer:	Zoeller
Model:	N53
Horsepower:	0.3



PUMP DESIGN

System (initial/repair): **Repair**

Project: Birchwood Trails, Lot 45
Location: Olive Branch Road,
Fuquay Varina, NC 27526
County: Harnett

Friction Losses

Suction Head	0	ft	(submersible 0)
Elev. Difference (highest point from pump)	7.21	ft	
Design Pressure At Outlet	2	ft	
Supply Line - 2" Schedule 40 PVC			
Pipe Diameter, Nominal	2	in.	
Pipe Diameter (ID)	2.047	in.	
Pipe Length	114	ft	
Pipe Length for Fittings	11.4	ft	
Equivalent Length	125.4	ft	
Estimated Friction Loss in Supply Line	2.02	ft	
Flow	29.8	gpm	
Velocity	2.91	ft/s	Meets requirement that 2 ft/s < v < 5 ft/s.
Friction Loss - Taps/Special Fittings	3.5	ft	
TOTAL		14.73	ft.

Flow for Anti-Siphon Hole


Hole Diameter 3/16 in.
Hole Flowrate 1.59 gpm

Pump Efficiency 0.7 (assumed, typical)
Motor Efficiency 0.9 (assumed for electric pumps)
Flow 31.39 gpm

Required Horsepower 0.19 hp
TDH 14.73 ft.

Pump Selection

Manufacturer:	Zoeller
Model:	N98
Horsepower:	0.5



Septic Tank Buoyancy Calculation

Project: Birchwood Trails, Lot 45
Location: Olive Branch Road,
 Fuquay Varina, NC 27526
County: Harnett

Tank Size (nominal) 1250 gal

Properties/Assumptions:

Min. liquid level to be maintained in tank at all times after initial installation.

Min. depth to water table	12.0 in.	from ground surface
Effluent Density	62.4 lb/ft ³	(Specific Weight of Water)
Concrete Density	142.6 lb/ft ³	
Soil App. Sp. Grav.	1.3	(typical value)
Soil Cover Over Tank	12 in.	(minimum)
Additional Cover	4 in.	for pipe grade
Unsubmerged wt of soil	81.1 lb/ft ³	
Submerged wt of soil	49.9 lb/ft ³	50% Porosity Assumed

Tank Dimensions (from supplier):

		<u>Exterior</u>		<u>Interior</u>	
		Top	Bottom	Top	Bottom
Tank	Length	125.5	122.0	119.5	116.0 in.
	Width	65.5	62.0	59.5	56.0 in.
	Height	58.5	(w/o lid)	54.5	in.
Lid	Length	125.5 in.			
	Width	65.5 in.			
	Height	3.0 in.			
Area of Riser Openings		6.28 ft ²			
Permanent Liquid Depth in Tank		0.0 in.			0.00 ft
Tank Weight		11,000 lb		(per manufacturer)	

Buoyancy Force Calculation:

Buoyancy Force Specific Weight of Water x Displaced Volume

Displaced Volume	283.5 ft ³ *
Buoyancy Force	17,689 lb.

Weight Calculation:

Tank Weight	11000 lb		
Water Weight in Tank	0 lb	Volume	0.0 ft ³ *
Soil Weight Over Tank	4966 lb		
Soil Friction Force	4037 lb		
Total Weight	20,004 lb		

Factor of Safety = 1.13

Note: Total weight must be greater than buoyancy force so that tank will not float during high water table conditions.

** Volume calculated by the prismoidal formula.*

Pump Tank Buoyancy Calculation

Project: Birchwood Trails, Lot 45
Location: Olive Branch Road,
 Fuquay Varina, NC 27526
County: Harnett

Tank Size (nominal) 1275 gal

Properties/Assumptions:

Min. liquid level to be maintained in tank at all times after initial installation.

Min. depth to water table	12 in.	from ground surface
Effluent Density	62.4 lb/ft ³	(Specific Weight of Water)
Concrete Density	142.6 lb/ft ³	
Soil App. Sp. Grav.	1.3	(typical value)
Soil Cover Over Tank	12 in.	(minimum)
Additional Cover	6 in.	for pipe grade
Unsubmerged wt of soil	81.1 lb/ft ³	
Submerged wt of soil	49.9 lb/ft ³	50% porosity assumed

Tank Dimensions (from supplier):

		<u>Exterior</u>		<u>Interior</u>	
		Top	Bottom	Top	Bottom
Tank	Length	108.0	104.0	102.0	98.0 in.
	Width	58.0	54.0	52.0	48.0 in.
	Height	64.5	(w/o lid)	60.5	
Lid	Length	108.0 in.			
	Width	58.0 in.			
	Height	3.0 in.			
Area of Riser Openings		3.14 ft ²			
Permanent Liquid Depth in Tank		0.0 in.		0.00 ft	
Tank Weight		10500 lb		(per manufacturer)	

Buoyancy Force Calculation:

Buoyancy Force Specific Weight of Water x Displaced Volume

Displaced Volume	234.1 ft ³ *
Buoyancy Force	14,606 lb

Weight Calculation:

Tank Weight	10500 lb		
Water Weight in Tank	0 lb	Volume	0.0 ft ³ *
Soil Weight Over Tank	4281 lb		
Soil Friction Force	4227 lb		
Total Weight	19,008 lb		

Factor of Safety = 1.30

Note: Total weight must be greater than buoyancy force
 so that tank will not float during high water table conditions.

* Volume calculated by the prismatic formula.



AGRITEC-01

CGARKALNS

CERTIFICATE OF LIABILITY INSURANCE

DATE (MM/DD/YYYY)

1/12/2024

THIS CERTIFICATE IS ISSUED AS A MATTER OF INFORMATION ONLY AND CONFERS NO RIGHTS UPON THE CERTIFICATE HOLDER. THIS CERTIFICATE DOES NOT AFFIRMATIVELY OR NEGATIVELY AMEND, EXTEND OR ALTER THE COVERAGE AFFORDED BY THE POLICIES BELOW. THIS CERTIFICATE OF INSURANCE DOES NOT CONSTITUTE A CONTRACT BETWEEN THE ISSUING INSURER(S), AUTHORIZED REPRESENTATIVE OR PRODUCER, AND THE CERTIFICATE HOLDER.

IMPORTANT: If the certificate holder is an ADDITIONAL INSURED, the policy(ies) must have ADDITIONAL INSURED provisions or be endorsed. If SUBROGATION IS WAIVED, subject to the terms and conditions of the policy, certain policies may require an endorsement. A statement on this certificate does not confer rights to the certificate holder in lieu of such endorsement(s).

PRODUCER Hartsfield & Nash Agency, Inc. 10405 Ligon Mill Rd., Ste H Wake Forest, NC 27587	CONTACT NAME: Connie Garkalns	
	PHONE (A/C, No, Ext): (919) 556-3698 FAX (A/C, No): (919) 556-8758	
	E-MAIL ADDRESS: Connie@hartsfield-nash.com	
	INSURER(S) AFFORDING COVERAGE	NAIC #
	INSURER A : Selective Insurance Company of the Southeast	39926
INSURED Agri-Waste Technology Inc 501 N. Salem St Ste 203 Apex, NC 27502	INSURER B : ACCIDENT FUND INSURANCE COMPANY OF AMERICA	10166
	INSURER C : Evanston Insurance Company	35378
	INSURER D :	
	INSURER E :	
	INSURER F :	

COVERAGES

CERTIFICATE NUMBER:

REVISION NUMBER:

THIS IS TO CERTIFY THAT THE POLICIES OF INSURANCE LISTED BELOW HAVE BEEN ISSUED TO THE INSURED NAMED ABOVE FOR THE POLICY PERIOD INDICATED. NOTWITHSTANDING ANY REQUIREMENT, TERM OR CONDITION OF ANY CONTRACT OR OTHER DOCUMENT WITH RESPECT TO WHICH THIS CERTIFICATE MAY BE ISSUED OR MAY PERTAIN, THE INSURANCE AFFORDED BY THE POLICIES DESCRIBED HEREIN IS SUBJECT TO ALL THE TERMS, EXCLUSIONS AND CONDITIONS OF SUCH POLICIES. LIMITS SHOWN MAY HAVE BEEN REDUCED BY PAID CLAIMS.

INSR LTR	TYPE OF INSURANCE	ADDL INSD	SUBR WVD	POLICY NUMBER	POLICY EFF (MM/DD/YYYY)	POLICY EXP (MM/DD/YYYY)	LIMITS
A	<input checked="" type="checkbox"/> COMMERCIAL GENERAL LIABILITY <input type="checkbox"/> CLAIMS-MADE <input checked="" type="checkbox"/> OCCUR GEN'L AGGREGATE LIMIT APPLIES PER: <input type="checkbox"/> POLICY <input checked="" type="checkbox"/> PROJECT <input type="checkbox"/> LOC OTHER:			S 2253659	1/18/2024	1/18/2025	EACH OCCURRENCE \$ 2,000,000
							DAMAGE TO RENTED PREMISES (Ea occurrence) \$ 300,000
							MED EXP (Any one person) \$ 10,000
							PERSONAL & ADV INJURY \$ 2,000,000
							GENERAL AGGREGATE \$ 4,000,000
							PRODUCTS - COMP/OP AGG \$ 4,000,000
							\$
A	<input checked="" type="checkbox"/> AUTOMOBILE LIABILITY <input checked="" type="checkbox"/> ANY AUTO <input type="checkbox"/> OWNED AUTOS ONLY <input type="checkbox"/> SCHEDULED AUTOS <input type="checkbox"/> HIRED AUTOS ONLY <input type="checkbox"/> NON-OWNED AUTOS ONLY			S 2253659	1/18/2024	1/18/2025	COMBINED SINGLE LIMIT (Ea accident) \$ 1,000,000
							BODILY INJURY (Per person) \$
							BODILY INJURY (Per accident) \$
							PROPERTY DAMAGE (Per accident) \$
							\$
							\$
A	<input type="checkbox"/> UMBRELLA LIAB <input checked="" type="checkbox"/> OCCUR <input type="checkbox"/> EXCESS LIAB <input type="checkbox"/> CLAIMS-MADE DED <input type="checkbox"/> RETENTION \$			S 2253659	1/18/2024	1/18/2025	EACH OCCURRENCE \$ 2,000,000
							AGGREGATE \$ 2,000,000
							\$
B	WORKERS COMPENSATION AND EMPLOYERS' LIABILITY ANY PROPRIETOR/PARTNER/EXECUTIVE OFFICER/MEMBER EXCLUDED? (Mandatory in NH) If yes, describe under DESCRIPTION OF OPERATIONS below	Y / N <input checked="" type="checkbox"/> N	N / A	100003072	1/18/2024	1/18/2025	<input checked="" type="checkbox"/> PER STATUTE <input type="checkbox"/> OTH-ER
							E.L. EACH ACCIDENT \$ 1,000,000
							E.L. DISEASE - EA EMPLOYEE \$ 1,000,000
							E.L. DISEASE - POLICY LIMIT \$ 1,000,000
C	Prof & Pollution			MKLV3ENV104078	8/22/2023	8/22/2024	Each Claim 5,000,000
A	Leased / Rented			S 2253659	1/18/2024	1/18/2025	Equipment 25,000

DESCRIPTION OF OPERATIONS / LOCATIONS / VEHICLES (ACORD 101, Additional Remarks Schedule, may be attached if more space is required)

CERTIFICATE HOLDER

CANCELLATION

***This is ONLY For Informational Purposes
Contact Agency for Specific Holder info to be added

SHOULD ANY OF THE ABOVE DESCRIBED POLICIES BE CANCELLED BEFORE THE EXPIRATION DATE THEREOF, NOTICE WILL BE DELIVERED IN ACCORDANCE WITH THE POLICY PROVISIONS.

AUTHORIZED REPRESENTATIVE