



Planning Services Sign Permit Review Form

PO Box 65
108 E. Front Street
Lillington, NC 27546
Ph: (910) 893- 7525 opt. 4
Fax: (910) 814-6459

Date of Submittal	Application Number	Applicant	Landowner
5/21/2021	SIGN2105-0008	Advance Signs & Service	Womble Rental Management Association

Contact Person	Contact Number	Sign Location	PIN Number
Debbie Landell	(919) 639-4666	67 Marshbanks St.	0670-82-4894.000

Proposed Sign			
Type	Dimensions	Location / Setbacks	Illumination
<input checked="" type="checkbox"/> Wall <input type="checkbox"/> Ground <input type="checkbox"/> Monument <input type="checkbox"/> Directory <input type="checkbox"/> Outdoor Advertising	Sign Length: 11' 3" Width: 2'	West Elevation (Front)	<input type="checkbox"/> None <input type="checkbox"/> External <input checked="" type="checkbox"/> Internal <input type="checkbox"/> Electronic Message
Total Length of Wall	25'	Total Size of Project / Parcel	<input checked="" type="checkbox"/> Less Than 1 Acre <input type="checkbox"/> Greater Than 1 Acre
Total Sq. Ft. Electronic Message Display	0	Pole Style Ground Sign Encasement	

Current Signage			
Current Wall Signs	Current Ground Signs	Distance Between Signs On Property	Distance Between Outdoor Advertising Signs
0	0	N/A	N/A

Reviewed By:	Date of Review	Review Results	
Sarah Arbour	5/28/2021	<input checked="" type="checkbox"/> Approved	<input type="checkbox"/> Disapproved

Comments	See sign plans below.
----------	-----------------------

Planning Services Sign Permit Review Form

11 ft3 in

2 ft

1 ft9 in

22.5 SQ FT PROPOSED

LED Internally Illuminated Channel Letters
Flush Mounted to Existing Fascia with
CNC Routed Cloud Background

- (A) White 2447 acrylic face
- (B) 1" White Jewelite face trim cap
- (C) 0.063 Aluminum Return painted White
- (D) 0.090 Aluminum letter back plate
- (E) Internal GE White LEDs
- (F) Low Voltage LED wire
- (G) 1/4" Bolt attachments (min. 6 per letter)
- (H) Return Weep Hole
- (I) Flat .090 Aluminum Cloud Background Flush Mounted to Raceway (Raceway Mounted)

LISTED

25'-0" Frontage

2447 White
Acrylic Faces

Aluminum
Cloud Painted
Black

3M 3630-141
Gold Nugget