

LOCATION MAP NOT TO SCALE

SITE SUMMARY

SITE AR	· _ - ·	
-	SITE AREA:	0.93 ACRES (40,572 S.F.)
I	MPERVIOUS AREA:	26,115 S.F. (64.4%)
F	PERVIOUS AREA:	14,457 S.F. (35.6%)
ZONING	CLASSIFICATION	
	JURISDICTION:	HARNETT COUNTY
2	ZONING:	COMMERCIAL
,	ADJACENT ZONING:	COMMERCIAL
BUILDIN	G SETBACKS	
F	FRONT:	50
	SIDE:	20'/20' (CORNER)
F	REAR:	25
BUILDIN	G SUMMARY	
E	BUILDING AREA:	2,500 S.F. (54 SEATS)
- E	BUILDING COVERAGE:	6.16%
PARKIN	G SUMMARY	
F	PARKING REQ.:	1 SPACES / 4 SEATS + 2 / EMPLOYEE
-		18 SPACES
- F	PARKING PROV.:	9.6 SPACES / 1,000 S.F
-		24 SPACES
-	STANDARD STALL DIM	ENSIONS: 9' x 18
-	MIN. DRIVE WIDTH:	24

ORDINANC	E REQUIREMENTS	
PARKING LOT RE	QUIREMENTS:	24 S PACES
	PERIMETER PLANTINGS	
EVERGREE	N SCREEN MAINTAINED @ 3' HT. WITH	HIN 3 YEARS
	MIN. 18" HEIGHT AT PLANTING	
	1 TREE / 10 SPACES =	3 TREES
	2 SHRUBS / 10 SPACES =	6 SHRUBS
EAC	H SPACE MUST BE WITHIN 60' OF A T	REE

HARNETT COUNTY UTILITY EASEMENT NOTE:

NO TREES ARE TO BE PLANTED WITHIN ANY UTILITY EASEMENTS. ANY SHRUBS PLANTED WITHIN THE EASEMENTS ARE DONE SO AT THE OWNER'S RISK AND SHALL BE THE OWNER'S RESPONSIBILITY TO REPLACE IF REMOVED DUE TO MAINTENANCE OF UTILITY LINES.
SHRUBS PLANTED WITHIN THE EASEMENTS SHALL NOT BE PLANTED DIRECTLY OVER A UTILITY LINE. PLANT LOCATIONS SHOWN ON THE PLAN MAY NEED SHIFT IN THE FIELD BASED ON THE BUILT CONDITION OF THE UTILITIES TO ENSURE THE AFORE MENTIONED REQUIREMENTS ARE MET.

RECEIVED By Mike Erickson at 8:02 am, Jan 20, 2022

NOTE: ALL QUANTITIES ARE FOR A GENERAL GUIDE ONLY. CONTRACTOR SHALL CONFIRM ALL QUANTITIES PRIOR TO BIDDING AND INSTALLATION. LECRAW ENGINEERING, INC. SHALL TAKE NO RESPONSIBILITY FOR THE ACCURACY OF THE QUANTITIES PROVIDED.

PLAN	T LIST						
TREES:							
	BOTANICAL NAME	COMMON NAME	QUANTITY	MIN. SIZE	MIN.SPACING	TREE TYPE	COMMENTS
(CD)	Cedrus atlantica 'Glauca Fastigiata'	Columnar Blue Atlas Cedar	3	8-10' HT'	12' O.C.	EVERGREEN CANOPY	UPRIGHT HABIT
(UA)	Ulmus parvifolia 'Athena'	Athena Elm	4	3" CAL.	N/A	DECIDUOUS CANOPY	6' CLEAR BELOW CANOPY
		TOTAL NUMBER OF TREES:	7				
SHRUBS	S/HERBACEOUS ORNAMENTALS:						
(IP)	Illicium parviflorum	Anise	158	18" HT.	5' O.C.		
(LP)	Loropetalum chinensis rubrum 'Ruby'	Ruby Loropetalum	27	5 GAL.	5' O.C.		
(MC)	Muhlenbergia capillaris	Pink Muhly Grass	102	3 GAL.	3' O.C.		
		TOTAL NUMBER OF SHRUBS:	287				
GROUNI	DCOVERS/VINES/PERENNIALS:						
(MUL)	Mulch	Pinestraw	6,000 S.F.				
(SOD)	Cynodon dactylon	Bermuda Grass	10,500 S.F.				
(SEED)	Hydroseed	Hydroseed	3,500 S.F.	BERMUDAGRASS MIX			


4	NATURAL GAS TANK	01/19/22	MAT	ISM
3	HRW COMMENTS	10/19/21	MAT	ISW
2	DRB & HRW COMMENTS	09/30/21	MAT	ISM
1	DRB & HRW COMMENTS	08/18/21	MAT	ISW
REV.#		DATE	DRAWN CHECK BY: BY:	CHECK BY:

SEAL:

DESIGN TEAM: DESIGNED BY:



Know what's **below. Call** before you dig.



SCALE: 1"=20'

JULY 2, 2021 LANDSCAPE PLAN