



Planning Services Sign Permit Review Form

PO Box 65
108 E. Front Street
Lillington, NC 27546
Ph: (910) 893- 7525 opt. 4
Fax: (910) 814-6459

Date of Submittal	Application Number	Applicant	Landowner
6/10/2025	SIGN2506-0004	Mr. Sign Guy	First Health Family Dent.

Contact Person	Blanca Sanchez	Contact Number	252-561-7446
Sign Location	6720 Overhills Road	PIN Number	0514-08-5495.000

Proposed Sign			
Type	Dimensions	Location / Setbacks	Illumination
<input type="checkbox"/> Wall <input type="checkbox"/> Ground <input checked="" type="checkbox"/> Monument <input type="checkbox"/> Directory <input type="checkbox"/> Outdoor Advertising	Length N/A Width 11' Height 9' 4" Total Sq. Ft. 102.67	Overhills Road ?	<input type="checkbox"/> None <input type="checkbox"/> External <input checked="" type="checkbox"/> Internal <input checked="" type="checkbox"/> Electronic Message
Total Length of Wall	N/A	Total Size of Project / Parcel	<input type="checkbox"/> Less Than 1 Acre <input checked="" type="checkbox"/> Greater Than 1 Acre
Total Sq. Ft. Electronic Message Display	21 sq. ft. = 20.5%	Pole Style Ground Sign Encasement	Material N/A Width N/A

Current Signage			
Current Wall Signs	Current Ground Signs	Distance Between Signs On Property	Distance Between Outdoor Advertising Signs
N/A	N/A	N/A	N/A

Reviewed By:	Date of Review	Review Results
Randy Baker	6/13/2025	<input type="checkbox"/> Approved <input checked="" type="checkbox"/> Denied

Comments	Need site plan to reference exact distance from the public right of way. Signs shall be set back at least 10 feet from any public right(s) of way and/or property line.
----------	---

Planning Services

Sign Permit Review Form

DISREGARD ANY DIMENSIONS AND ART ON THIS PAGE; ONLY USE DIMENSIONS ON LINE DRAWING PAGE AND ART FROM SIGNED ART PAGE.

Synthetic stucco columns approx. 48" X 24" X 24" - Includes a one color Masterwall fine spray finish

2'-0" 7'-0" 2'-0"

3'-0" 2" 3'-0" 2" 3'-0"

Duracore synthetic stucco sign base with Masterwall faux brick finish

6' tall Man

SIGN SPECIFICATIONS

Color: Full Color / RGB text, pictures & video
Pitch: 10mm
Matrix: 95210
Dimensions: 9'-0" x 7'-0" (Tall x Wide)
Max # of Lines: 13
Max Letter Per Line: 35
Cabinet Size: 3'-0" x 7'-0" (Tall x Wide)
Monument Size: 9'-10" x 11'-0" (Tall x Wide)

Cabinet PMS Color:
PANTONE 350 C
Powdercoat Color RAL 6005

Letters PMS Color:
PANTONE 7506 C
Powdercoat Color RAL 1018

Topper PMS Color:
PANTONE 125 C
Powdercoat Color RAL

Grout PMS Color:
PANTONE 7582 C
Powdercoat Color RAL

See available powdercoat colors:
<https://goldenrule.com/signs/powdercoat-colors>

The Golden Rule Matching System is the sign industry standard for color selection. Customer provide artwork and proper calibration can find the accuracy between the color you see and the final PMS color when painted. For exterior colors, call your Project Director for a sample.

* Overall sign depth may vary due to support size required by engineering.

First Choice Community Health - Anderson Creek Family Dentistry


6720 Overhills Rd.
Spring Lake, NC 28390

GR
Golden Rule
SIGNS

Pg. 1

Planning Services

Sign Permit Review Form

 <p>Golden Rule SIGNS</p>	Key: <ul style="list-style-type: none">8GA. COPPER AND 1/2" ROD X8"ID CABINET POWER WHIPPRIMARY EMC WHIPSECONDARY EMC WHIPCLIENT PROVIDED PRIMARY	<p>GRS REQUIRES THAT THE SIGN OPERATE ON AT LEAST 1 DEDICATED CIRCUIT AND RECOMMENDS 1 CIRCUIT PER L.E.D. DISPLAY. WARRANTY REQUIRES EACH L.E.D. DISPLAY TO HAVE A MINIMUM 1/2" COPPER, IN-EARTH GROUND ROD WITH CONTINUOUS 8 GAUGE COPPER WIRE, 6' LONG LOCATED 8 FEET FROM THE BASE OF THE SIGN.</p>	 <p>Cellular Modem</p>	<p>Visit resource. impactledsigns.com for more details</p>	Pg. 6
	 <p>Anderson Creek Family Dentistry</p> <p>Overhills Rd</p> <p>Overhills Rd</p>				
Sign Location:					