

Complaint # ceen2411-001

SANITATION COMPLAINT

Date 11-1-24

Phone# (910) (919) 909 4387

Name of Complainant Ricky Holland [] ANONYMOUS

[☒] Sewer [] Solid Waste [] Other _____

Nature of Complaint Damage Chambers when pump
was turned on sewage arise from ground

Directions to site of Complaint _____

Owner of property site Prices Real Estate Company

Address and/or phone # 8909 US 401 N

Inspection Information

DATE _____ TIME _____ PERFORMED BY _____

PROBLEM(S) FOUND _____

Correction of Problem

DATE _____

COMMENTS _____

Name _____ Date Secured _____

Harnett County Department of Public Health

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Pars Development Group PROPERTY LOCATION: 8909 US 401 N LOT # _____
 SUBDIVISION _____
 NEW ☒ REPAIR ☐ EXPANSION ☐ Site Improvements required prior to Construction Authorization Issuance
 Type of Structure: Dollar General (70'x100')
 Proposed Wastewater System Type: Pump to 25% Reduction Sys
 Projected Daily Flow: 200 GPD
 Number of bedrooms: NA Number of Occupants: NA max
 Basement ☐ Yes ☒ No
 Pump Required: ☒ Yes ☐ No ☐ May be required based on final location and elevations of facilities
 Type of Water Supply: ☐ Community ☒ Public ☐ Well Distance from well NA feet Permit valid for: ☒ Five years
 Permit conditions: ☐ No expiration

Authorized State Agent: [Signature] Date: 05/06/2019 SEE ATTACHED SITE SKETCH
 The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules 1950, 1952, 1954, 1955, 1956, 1957, 1958, and 1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Pars Development Group PROPERTY LOCATION: 8909 US 401 N LOT # _____
 SUBDIVISION _____
 Facility Type: Dollar General (70'x100') ☒ New ☐ Expansion ☐ Repair
 Basement? ☐ Yes ☒ No Basement fixtures? ☐ Yes ☐ No
 Type of Wastewater System** At-Grade 25% Reduction System (Initial) Wastewater Flow: 200 GPD
 (See note below, if applicable ☐)
At-Grade 25% Reduction System (Repair)
 Installation Requirements/Conditions
 Septic Tank Size 1000 gallons Exact length of each trench 42 feet Trench Spacing: 9 Feet on Center
 Pump Tank Size 1000 gallons Trenches shall be installed on contour at a Soil Cover: 6 (Imported) inches
 Maximum Trench Depth of: 12 inches (Maximum soil cover shall not exceed
 (Trench bottoms shall be level to $\pm 1/4"$ 36" above the trench bottom)
 in all directions)
 Pump Requirements: _____ ft. TDH vs. _____ GPM _____ inches below pipe
 Aggregate Depth: NA inches above pipe
 Conditions: 6In Approved filled cover required Septic Area shall be protected by barricade; No grading _____ inches total

**WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA.
 NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.**

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: [Signature] Date: 05/06/2019
ANDREW CURRIN Construction Authorization Expiration Date: 05/06/2024

HTE# BCEM1811-00057

Permit # NA

Harnett County Department of Public Health Site Sketch

ISSUED TO: Pars Development Grp. PROPERTY LOCATION: 8909 US 401 N.
SUBDIVISION _____ LOT # _____

Authorized State Agent: *Andrew Corbin* Date: 05/06/2019
ANDREW CORBIN

* SEPTIC AREA SHALL BE CLEARED AS TO NOT DISTURB
THE NATURAL GRADE [NO GRADING]

* SEPTIC AREA SHALL BE PROTECTED BY BARRICADE

* 6IN APPROVED FILL COVER REQUIRED [AT GRADE]



* SOIL REPORT AND PROPOSAL BY
SOUTHERN SOIL & ENVIRONMENTAL ASSOC., INC.

HTE# B.COM1811-0009

Harnett County Department of Public Health

25501

PERMIT # NA

Operation Permit

☒ New Installation ☒ Septic Tank ☒ Nitrification Line ☐ Repair ☐ ExpansionPROPERTY LOCATION: 8909 US 401 N.Name: (owner) Pass Development Group SUBDIVISION _____ LOT # _____System Installer: Regional Codes Registration # _____Basement with plumbing: ☐ Garage ☐ Number of Bedrooms NA 200 GPD MAXType of Water Supply: ☐ Community ☒ Public ☐ Well Distance from well NA feetSystem Type: 25% reduction by IIIb Types V and VI Systems expire in 5 years.

(In accordance with Table V a)

Owner must contact Health Department 6 months prior to expiration for permit renewal.

This system has been installed in compliance with applicable North Carolina General Statutes, Rules for Sewage Treatment and Disposal, and all conditions of the Improvement Permit and Construction Authorization.



PERMIT CONDITIONS

I. Performance: System shall perform in accordance with Rule .1961. US 401 N.

II. Monitoring: As required by Rule .1961.

III. Maintenance: As required by Rule .1961. Other _____

Subsurface system operator required? Yes ☐ No ☐

If yes, see attached sheet for additional operation conditions, maintenance and reporting.

IV. Operation: _____

V. Other: _____

☐ D-Box ☐ Pump ☐ Alarm ☐ H2O Line ☐ PWR Line

Following are the specifications for the sewage disposal system on the above captioned property.

Type of system: ☐ Conventional ☒ Other 42 Chambers IIIb Septic Tank: 1000 gallons Pump Tank: 1000 gallonsSubsurface Drainage Field No. of ditches 3 exact length of each ditch 42 feet width of ditches 3 feet depth of ditches 18 inches

French Drain Required: _____ Linear feet

Authorized State Agent [Signature]Date 12/18/2019